

An aerial photograph of a vast, fragmented ice field, likely in the Arctic. The ice consists of numerous irregular, light blue and white floes of varying sizes, separated by dark, open water. The overall scene conveys a sense of a melting and breaking apart of the ice cover.

Snow, Water, Ice and Permafrost in the Arctic (SWIPA):

Climate Change and
the Cryosphere

Arctic Monitoring and Assessment Programme (AMAP)

Educational use: This report (in part or in its entirety) and other SWIPA products available from www.amap.no/swipa can be used freely as teaching materials and for other educational purposes.

The only condition of such use is acknowledgement of AMAP/SWIPA as the source of the material according to the recommended citation. In case of questions regarding educational use, please contact the AMAP Secretariat (amap@amap.no).

Note: This report may contain images (e.g. photographs) for which permission for use will need to be obtained from original copyright holders.

Snow, Water, Ice and Permafrost in the Arctic (SWIPA): Climate Change and the Cryosphere

Arctic Monitoring and Assessment Programme
(AMAP), Oslo, 2011

Snow, Water, Ice and Permafrost in the Arctic (SWIPA): Climate Change and the Cryosphere

ISBN – 978-82-7971-071-4

© Arctic Monitoring and Assessment Programme, 2011

Published by

Arctic Monitoring and Assessment Programme (AMAP), Gaustadalléen 21, N-0349 Oslo, Norway (www.amap.no)

Citation

AMAP, 2011. Snow, Water, Ice and Permafrost in the Arctic (SWIPA): Climate Change and the Cryosphere. Arctic Monitoring and Assessment Programme (AMAP), Oslo, Norway. xii + 538 pp.

Ordering

AMAP Secretariat, Gaustadalléen 21, N-0349 Oslo, Norway

This report is also published as an electronic document, available from the AMAP website at www.amap.no

Production

Production management

Simon Wilson (AMAP Secretariat)

Scientific, technical and linguistic editing

Carolyn Symon (carolyn.symon@btinternet.com), with assistance from Henning Thing (University of Copenhagen), Janet Pawlak (AMAP Secretariat), Tania Larson (US Geological Survey)

Lay-out and technical production

Burnthebook Design, Derby DE24 8HR, United Kingdom (burnthebook.co.uk)

Design and production of computer graphics

Simon Wilson (AMAP Secretariat), Frits Steenhuisen (Arctic Centre, University of Groningen), John Bellamy (johnbellamy@swipnet.se), Hugo Ahlenius (hugo.ahlenius@nordpil.com), Kerry Haywood (kerry@burnthebook.co.uk), Simon Duckworth (simon@burnthebook.co.uk)

Cover photograph

Multi-layer ice in the Chukchi Sea. Photo: © Steven Kazlowski/Science Faction/Corbis

Printing

Narayana Press, Gylling, DK-8300 Odder, Denmark (www.narayanapress.dk); a Swan-labelled printing company, 541 562.

AMAP Working Group:

Russel Shearer (Chair, Canada), Fred Wrona (Canada), Mikala Klint (Denmark), Henrik Larsen (Denmark), Morten Skovgaard Olsen (Vice-chair, Denmark), Outi Mähönen (Vice-chair, Finland), Helgi Jensson (Iceland), Per Døvre (Norway), Yuri Tsaturov (Russia), Tove Lundeborg (Sweden), Tom Armstrong (USA), Jan-Idar Solbakken (Permanent Participants of the indigenous peoples organisations).

AMAP Secretariat:

Lars-Otto Reiersen, Simon Wilson, Yuri Sychev, Janet Pawlak, Christine Daae Olseng, Jan René Larsen, Inger Utne.

Arctic Council Member States and Permanent Participants of the Council:

Canada, Denmark/Greenland/Faroe Islands, Finland, Iceland, Norway, Russia, Sweden, United States, Aleut International Association (AIA), Arctic Athabaskan Council (AAC), Gwich'in Council International (GCI), Inuit Circumpolar Council (ICC), Russian Association of Indigenous Peoples of the North (RAIPON), Saami Council.

SWIPA Integration Team:

Maria Ananicheva, Terry V. Callaghan, Dorte Dahl-Jensen, Sebastian Gerland, Barry Goodison, Mats A. Granskog, Grete K. Hovelsrud, Margareta Johansson, Jeffrey R. Key, Alexander Klepikov, Joan Nymand Larsen, Walter N. Meier, Morten Skovgaard Olsen (Chair), Bob E.H. van Oort, James E. Overland, Janet Pawlak, Birger Poppel, Terry Prowse, Volker Rachold, Lars-Otto Reiersen, James D. Reist, Martin Sharp, Igor A. Shiklomanov[†], Henning Thing, Valery Vuglinsky, John E. Walsh, Simon Wilson, Daqing Yang

Contents

Chapter 1. Introduction

Lead authors: Morten Skovgaard Olsen, Lars-Otto Reiersen

Chapter 2. Arctic Climate: Recent Variations

Lead authors: John E. Walsh, James E. Overland, Pavel Y. Groisman, Bruno Rudolf

Chapter 3. Climate Model Projections for the Arctic

Lead authors: James E. Overland, Muyin Wang, John E. Walsh, Jens H. Christensen, Vladimir M. Kattsov, William L. Chapman

Chapter 4. Changing Snow Cover and its Impacts

Lead authors: Terry V. Callaghan, Margareta Johansson, Ross D. Brown, Pavel Y. Groisman, Niklas Labba, Vladimir Radionov

Chapter 5. Changing Permafrost and its Impacts

Lead authors: Terry V. Callaghan, Margareta Johansson, Oleg Anisimov, Hanne H. Christiansen, Arne Instanes, Vladimir Romanovsky, Sharon Smith

Chapter 6. Changing Lake and River Ice Regimes: Trends, Effects and Implications

Lead authors: Terry Prowse, Knut Alfredsen, Spyros Beltaos, Barrie Bonsal, Claude Duguay, Atte Korhola, James McNamara, Warwick F. Vincent, Valery Vuglinsky, Gesa Weyhenmeyer

Chapter 7. Mountain Glaciers and Ice Caps

Lead authors: Martin Sharp, Maria Ananicheva, Anthony Arendt, Jon-Ove Hagen, Regine Hock, Edward Josberger, R. Dan Moore, William Tad Pfeffer, Gabriel J. Wolken

Chapter 8. The Greenland Ice Sheet in a Changing Climate

Lead authors: Dorthe Dahl-Jensen, Jonathan Bamber, Carl E. Boggild, Erik Buch, Jens H. Christensen, Klaus Dethloff, Mark Fahnestock, Shawn Marshall, Minik Rosing, Konrad Steffen, Robert Thomas, Martin Truffer, Michael van den Broeke, Cornelis van der Veen

Chapter 9. Sea Ice

Lead authors: Walter N. Meier, Sebastian Gerland, Mats A. Granskog, Jeffrey R. Key, Christian Haas, Grete K. Hovelsrud, Kit M. Kovacs, Alexander Makshtas, Christine Michel, Donald Perovich, James D. Reist, Bob E.H. van Oort

Chapter 10. Arctic Societies, Cultures, and Peoples in a Changing Cryosphere

Lead authors: Grete K. Hovelsrud, Birger Poppel, Bob E.H. van Oort, James D. Reist

Chapter 11. Cross-cutting Scientific Issues

Lead authors: Terry V. Callaghan, Dorthe Dahl-Jensen, Margareta Johansson, Roland Kallenborn, Jeffrey R. Key, Robie Macdonald, Terry Prowse, Martin Sharp, Konrad Steffen, Warwick F. Vincent

Chapter 12. SWIPA Synthesis: Implications of Findings

Lead author: James D. Reist

Acronyms and abbreviations

Acknowledgments

Genrikh Alekseev, **Knut Alfredsen**, Michel Allard, **Maria Ananicheva***, **Oleg Anisimov**, Katey Walter Anthony, **Anthony Arendt**, Derek Armitage, Michael Baffrey, **Jonathan Bamber**, David Barber, Roger G. Barry, **Spyros Beltaos**, Jacob Bendtsen, Terry Bidleman, Cecilia Bitz, Helgi Björnsson, Sylvie Blangy, Bodil Bluhm, **Carl E. Bøggild**, Tobias Bolch, **Barrie Bonsal**, Breck Bowden, Raymond S. Bradley, **Michael van den Broeke**, **Ross D. Brown**, **Erik Buch**, Olga N. Bulygina, Igor Buzin, Vladimir Buzin, **Terry V. Callaghan***, F. Stuart Chapin III, **William L. Chapman**, **Jens H. Christensen**, Torben R. Christensen, **Hanne H. Christiansen**, John J. Clague, John Graham Cogley, Jonathan Colman, **Dorthe Dahl-Jensen***, Halvor Dannevig, **Klaus Dethloff**, Yonas Dibike, Julian A. Dowdeswell, **Claude Duguay**, Mark B. Dyurgerov, Hajo Eicken, Richard L.H. Essery, Bernd Etzelmüller, **Mark Fahnestock**, Bruce C. Forbes, Donald Forbes, Mads C. Forchhammer, James Ford, Povl Frich, Dmitry Frolov, Stefan Fronzek, Nikolaus Gantner, Tony Gaston, Shari Gearheard, **Sebastian Gerland***, David Gilichinsky, Andrey Glazovsky, Vladimir N. Golubev, Barry Goodison*, Rolf Gradinger, **Mats A. Granskog***, Andrea Grant-Friedman, Thomas C. Grenfell, **Grete K. Hovelsrud***, **Pavel Y. Groisman**, **Christian Haas**, **Jon-Ove Hagen**, Crispin Halsall, Larry Hinzman, **Regine Hock**, Marika Holland, Kim Holmén*, Richard E. Honrath†, Hans-Wolfgang Hubberten, Steven Hudson, Ole Humlum, George Hunt, Henry Huntington, Jun Inoue, **Arne Instanes**, Janet Intrieri, Hester Jiskoot, Tómas Jóhannesson, **Margareta Johansson***, M. Torre Jorgensen, **Edward Josberger**, Glenn P. Juday, **Roland Kallenborn**, **Vladimir M. Kattsov**, Frank Kauker, **Jeffrey R. Key***, Lene Kielsen-Holm, Takashi Kikuchi, Alexander Klepikov*, **Atte Korhola**, **Kit M. Kovacs**, Alexander Krenke, Peter Kuhry, James Kuptana, Ron Kwok, **Niklas Labba**, Joan Nyman Larsen*, Seymour Laxon, Antoni Lewkowicz,

Leif Lia, Ronald Lindsay, Amy L. Lovecraft, **Robie Macdonald**, Andy Mahoney, **Alexander Makshtas**, Sergei S. Marchenko, **Shawn Marshall**, James Maslanik, Lars Mathiasen, A. David McGuire, **James McNamara**, Mark F. Meier, **Walter N. Meier***, Rae Melloh, Brian Menounos, Anna V. Meshcherskaya, **Christine Michel**, Alexander Milner, **R. Dan Moore**, Sue E. Moore, Yaroslav Muravyev, Julian Murton, Son Nghiem, Marcel Nicolaus, Matt Nolan, Dirk Notz, Naum G. Oberman, **Morten Skovgaard Olsen*** (SWIPA IT Chair), **Bob E.H. van Oort***, Taha Ouarda, Paul Overduin, **James E. Overland***, Finnur Palsson, Mark Parsons, Janet Pawlak*, Christina Pedersen, Leif Toudal Pedersen, **Donald Perovich**, Marina N. Petrushina, **William Tad Pfeffer**, Gareth K. Phoenix, Reinhard Pienitz, Igor Polyakov, John Pomeroy, **Birger Poppel***, Simon Prinsenberg, **Terry Prowse***, Volker Rachold*, Valentina Radić, **Vladimir Radionov**, Arja Rautio, Vyacheslav N. Razuvaev, **Lars-Otto Reiersen***, **James D. Reist***, Paul Renaud, Svetlana A. Reneva, David A. Robinson, Odd Rogne, Peter Romanov, **Vladimir Romanovsky**, **Minik Rosing**, **Bruno Rudolf**, Stine Rybråten, Søren Rysgaard, Niels M. Schmidt, Edward A.G. Schuur, Igor Semiletov, Mark C. Serreze, Natalia Shakhova, **Martin Sharp***, Vladimir Shevchenko, Alexander I. Shiklomanov, Igor A. Shiklomanov†, Nikolay I. Shiklomanov, Koji Shimada, Drew Shindell, Andrey B. Shmakin, Matthew Shupe, Peter Sköld, **Sharon Smith**, Vasily Smolyanitsky, Sergey A. Sokratov, Steven Solomon†, **Konrad Steffen**, Morten Stickler, Matthew Sturm, Henning Thing*, **Robert Thomas**, **Martin Truffer**, **Cornelis van der Veen**, Andrei A. Velichko, Timo Vihma, **Warwick F. Vincent**, **Valery Vuglinsky***, **John E. Walsh***, **Muyin Wang**, Stephen G. Warren, Jan Weckström, Mark Wensnahan, **Gesa Weyhenmeyer**, Jeremy L. White, Simon Wilson*, **Gabriel J. Wolken**, Ming-ko Woo, Eric F. Wood, Mattias de Woul, Fred Wrona, Daqing Yang*, Jinlun Zhang, Yu Zhang

* SWIPA Integration Team meeting participant

† Deceased

Preface

This report presents the findings of the *Snow, Water, Ice and Permafrost in the Arctic (SWIPA): Climate Change and the Cryosphere* assessment performed by the Arctic Monitoring and Assessment Programme (AMAP) in close cooperation with the International Arctic Science Committee (IASC), the World Climate Research Programme/Climate and Cryosphere (WCRP/CliC) Project and the International Arctic Social Sciences Association (IASSA).

The SWIPA assessment is the third AMAP assessment addressing Arctic climate issues and is a direct follow-up to the Arctic Climate Impact Assessment (ACIA)¹ published in 2005. The ACIA reviewed the state of knowledge regarding ongoing change in the Arctic climate and documented the role that the Arctic plays in the global climate system; it represents the benchmark against which this updated assessment of change in the Arctic cryosphere has been developed.

The SWIPA assessment was conducted between 2008 and 2011 by an international group of over 200 scientists, experts and knowledgeable members of the Arctic indigenous communities. Lead authors were selected by an open nomination process coordinated by AMAP, IASC, WCRP/CliC and several national and international organizations. A similar process was used to select international experts who independently reviewed this report. A SWIPA Integration Team, including the lead authors for the twelve chapters, was responsible for scientific oversight and coordination of all work related to the preparation of the assessment report. Documentation available on the website www.amap.no includes listings of the comments received from the peer reviewers.

Information contained in this report is fully referenced and based first and foremost on research and monitoring efforts published since 2003 (i.e., information gathered since the ACIA report was undertaken). It includes peer-reviewed material accepted for publication up until October 2010, and in some cases later. Unpublished monitoring information, including both *in situ* and satellite observations, with well-established national and international standards and QA/QC (quality assurance / quality control) protocol are also part of the assessment. Acknowledging national differences in scientific quality assurance, the SWIPA assessment therefore draws mainly on peer-reviewed publications and work accepted for publication in respected scientific journals, including works reviewed by Russian scientific committees. Other sources of information, such as government reports, design standards, official records, statistics and other publicly available material, have however also been included in the work in order to provide as complete a picture of the effects of a changing Arctic cryosphere as possible; this is particularly the case for parts of the assessment dealing with the human dimension. All such references have been collected and are available upon request (at cost of reproduction) from the AMAP Secretariat. Care has been taken to ensure that no critical probability statements are based on these materials.

Access to reliable and up-to-date information is essential for the development of science-based decision-making regarding

ongoing changes in the Arctic and their global implications. SWIPA summary reports² and SWIPA films (available with different language subtitles) have therefore been specifically developed for policy-makers, summarizing the main findings of the SWIPA assessment. The SWIPA lead authors have confirmed that both this report and its summary report accurately and fully reflect their scientific assessment. This report constitutes the fully-referenced scientific basis for all statements made in the SWIPA summary report and its executive summary with recommendations for policy makers. The SWIPA reports and films are available from the AMAP Secretariat and on the AMAP website www.amap.no.

AMAP and its partner organizations would like to express their appreciation to all experts who have contributed their time and effort, and data; and especially to the lead authors and members of the SWIPA Integration Team who coordinated the production of this report. Thanks are also due to the many referees and reviewers who contributed to the SWIPA peer-review process and provided valuable comments that helped to ensure the quality of the report. A list of the main contributors is included at the start of each chapter. The list is not comprehensive. Specifically, it does not include the many national institutes, laboratories and organizations, and their staff, which have been involved in the various countries. Apologies, and no lesser thanks are given to any individuals unintentionally omitted from the list. Special thanks are due to the lead authors responsible for the preparation of the various chapters of this report.

The support of the Arctic countries and non-Arctic countries implementing research and monitoring in the Arctic is vital to the success of AMAP. The AMAP work is essentially based on ongoing activities within these countries, and the countries also provide the necessary support for most of the experts involved in the preparation of the AMAP assessments. In particular, AMAP would like to thank Canada, Denmark, Norway and the Nordic Council of Ministers for their financial support to the SWIPA work, and to sponsors of programmes and projects that have delivered data for use in this assessment. Special thanks are given to those experts involved in International Polar Year (IPY) projects who made their results available for the SWIPA assessment.

The AMAP Working Group is pleased to present its assessment to the Arctic Council and the international science community.

Morten Skovgaard Olsen (SWIPA Chair)
 Russel Shearer (AMAP Chair)
 Lars-Otto Reiersen (AMAP Executive Secretary)

Oslo, April 2011

Disclaimer: The views expressed in this peer-reviewed report are the responsibility of the authors of the report and do not necessarily reflect the views of the Arctic Council, its members or its observers.

¹ ACIA, 2005. Arctic Climate Impact Assessment. Cambridge University Press.

² AMAP, 2012. Arctic Climate 2011: Snow, Water, Ice and Permafrost in the Arctic (SWIPA). Arctic Monitoring and Assessment Programme, Oslo, Norway.

Executive Summary and Key Messages

SWIPA Summary for policymakers

AMAP's new assessment of the impacts of climate change on Snow, Water, Ice and Permafrost in the Arctic (SWIPA) brings together the latest scientific knowledge about the changing state of each component of the Arctic 'cryosphere'. It examines how these changes will impact both the Arctic as a whole and people living within the Arctic and elsewhere in the world.

'Cryosphere' is the scientific term for that part of the Earth's surface that is seasonally or perennially frozen. It includes snow, frozen ground, ice on rivers and lakes, glaciers, ice caps, ice sheets and sea ice. The cryosphere structures the physical environment of the Arctic. It provides services to humans such as freshwater supplies and transport routes. The cryosphere is an integral part of the climate system, and affects climate regionally and globally.

The SWIPA Assessment follows on from the Arctic Climate Impact Assessment (ACIA), published in 2005. It aims to update the findings from ACIA and to provide more in-depth coverage of issues related to the Arctic cryosphere.

The observed changes in sea ice on the Arctic Ocean and in the mass of

the Greenland Ice Sheet and Arctic ice caps and glaciers over the past ten years are dramatic and represent an obvious departure from the long-term patterns.

Some elements of the cryosphere, such as the extent of snow, ice over water, and the dynamics of glaciers and ice streams vary greatly over short timescales (seasonally, or from year to year) and from place to place. Other aspects of the cryosphere, such as the extent of permafrost and large ice sheets, vary and change over decadal time scales and large areas. Distinguishing long-term change from natural variability requires data to be collected at many locations over many years and carefully analyzed. Detecting these cryospheric responses to changing climate presents different challenges and requires long term records as well as high frequency observations.

Why the Arctic cryosphere is changing

The past six years (2005–2010) have been the warmest period ever recorded in the Arctic. Higher surface air temperatures are driving changes in the cryosphere.

Key finding 1

There is evidence that two components of the Arctic cryosphere – snow and sea ice – are interacting with the climate system to accelerate warming.

Key finding 2

The Arctic is warming. Surface air temperatures in the Arctic since 2005 have been higher than for any five-year period since measurements began around 1880. The increase in annual average temperature since 1980 has been twice as high over the Arctic as it has been over the rest of the world. Evidence from lake sediments, tree rings and ice cores indicates that Arctic summer temperatures have been higher in the past few decades than at any time in the past 2000 years. Previously unseen weather patterns and ocean currents have been observed, including higher inflows of warm water entering the Arctic Ocean from the Pacific. These changes are the main drivers of change in the Arctic cryosphere.

In attributing the cause of warming in the Arctic, SWIPA refers to the findings of the Fourth Assessment Report from the Intergovernmental Panel on Climate Change (IPCC). This states that "Most

of the observed increase in global average temperatures since the mid-20th century is very likely [$> 90\%$ probability] due to the observed increase in anthropogenic GHG [greenhouse gas] concentrations".

Climate-cryosphere interactions may now be accelerating warming

The greatest increase in surface air temperature has happened in autumn, in regions where sea ice has disappeared by the end of summer. This suggests that the sea is absorbing more of the sun's energy during the summer because of the loss of ice cover. The extra energy is being released as heat in autumn, further warming the Arctic lower atmosphere. Over land, the number of days with snow cover has changed mostly in spring. Early snow melt is accelerated by earlier and stronger warming of land surfaces that are no longer snow-covered.

These processes are termed 'feedbacks'. Snow feedbacks are

well known. The sea ice feedback has been anticipated by climate scientists, but clear evidence for it has only been observed in the Arctic in the past five years.

A number of other potential feedback mechanisms at play in the Arctic have been identified. These mechanisms can alter the rate or even direction of climate change and associated changes in the cryosphere. Of those feedbacks expected to have strong effects, seven lead to

further and/or accelerated warming, and just one leads to cooling. The intensity of feedbacks between the cryosphere and climate are not yet well quantified, either within the Arctic or globally. This lends considerable uncertainty to predictions of how much and how fast the cryosphere and the Arctic environment will change.

How the Arctic cryosphere is changing

The extent and duration of snow cover and sea ice have decreased across the Arctic. Temperatures in the permafrost have risen by up to 2°C. The southern limit of permafrost has moved northward in Russia and Canada.

Key finding 3

The largest and most permanent bodies of ice in the Arctic – multi-year sea ice, mountain glaciers, ice caps and the Greenland Ice Sheet – have all been declining faster since 2000 than they did in the previous decade.

Key finding 4

Model projections reported by the Intergovernmental Panel on Climate Change (IPCC) in 2007 underestimated the rates of change now observed in sea ice.

Key finding 5

The extent and duration of snow cover have decreased throughout the Arctic. The Arctic land area covered by snow in early summer has reduced by 18% since 1966. Coastal areas of Alaska and northern Fennoscandia have seen the strongest decreases in the number of days with snow cover. The change is largely caused by snow melting earlier in the spring. Snow depth has decreased in some areas such as the North American Arctic, but has increased in others such as northern Russia.

Permafrost – permanently frozen ground – underlies most of the Arctic land area and extends under parts of the Arctic Ocean. Temperatures in the permafrost have risen by up to 2°C over the past two to three decades, particularly in colder sites (typical permafrost temperatures range from -16°C to just below 0°C, depending on the location). The depth of soil above the permafrost that seasonally thaws each year has increased in Scandinavia, Arctic Russia west of the Urals, and inland Alaska. The southern limit of the permafrost retreated northward by 30 to 80 km in Russia between 1970 and 2005, and by 130 km during the past 50 years in Quebec.

Ice cover on lakes and rivers in the Northern Hemisphere is breaking-up earlier than previously observed. Studies of sediments in High Arctic lakes indicate that the duration of ice cover on some lakes has declined significantly over the past 100 years. The rates of change in lake and river ice conditions vary across the Arctic, although there are few long-term systematic observations.

Large bodies of ice are melting faster

Net loss of mass from the Greenland Ice Sheet has increased from an estimated 50 Gt per year (50 000 000 000 metric tonnes per year) in the period 1995–2000 to ~200 Gt per year in the period 2004–2008. The current loss (~200 Gt per year) represents enough water to supply more than one billion city-dwellers.

Nearly all glaciers and ice caps in the Arctic have shrunk over the past 100 years. The rate of ice loss increased over the past decade in most regions, but especially in Arctic Canada and southern Alaska. Total loss of ice from glaciers and smaller ice caps in the Arctic probably exceeded 150 Gt per year in the past decade, similar to the estimated amount being lost from the Greenland Ice Sheet.

Arctic sea-ice decline has been faster during the past ten years than in the previous 20 years. This decline in sea-ice extent is faster than projected by the models used in the IPCC's Fourth Assessment Report in 2007. The area of sea ice persisting in summer (polar pack ice) has been at or near record low levels every year since 2001. It is now about one third smaller than the average summer sea-ice cover from 1979 to 2000. New observations reveal that average sea-ice thickness is decreasing and the sea-ice cover is now dominated by younger, thinner ice.

More change is expected

Maximum snow depth is expected to increase over many areas by 2050, with greatest increases over Siberia. Despite this, average snow cover duration is projected to decline by up to 20% by 2050.

Key finding 6

The Arctic Ocean is projected to become nearly ice-free in summer within this century, likely within the next thirty to forty years.

Key finding 7

Average Arctic autumn-winter temperatures are projected to increase by between 3 and 6 °C by 2080, even using scenarios in which greenhouse gas emissions are projected to be lower than they have been for the past ten years.

The climate models used for SWIPA do not include possible feedback effects within the cryosphere system that may release additional stores of greenhouse gases from Arctic environments.

Arctic snowfall and rain are projected to increase in all seasons, but mostly in winter. Despite this, Arctic landscapes are generally expected to dry out more during summer. This is because higher air temperatures mean that more water evaporates, snow melt finishes earlier, and water flow regimes are altered.

With increasing snowfall, all projections show maximum snow depth during winter increasing over many areas. The greatest increases (15–30% by 2050) are expected in Siberia. Even so, snow will tend to lie on the ground for

10–20% less time each year over most of the Arctic, due to earlier melting in spring.

Models project continued thawing of permafrost.

Projections show that sea-ice thickness and summer sea-ice extent will continue to decline in the coming decades, although considerable variation from year to year will remain. A nearly ice-free summer is now considered likely for the Arctic Ocean by mid-century. This means there will no longer be any thick multi-year ice consistently present.

Climate model projections show a 10–30% reduction in the mass of mountain glaciers and ice caps by the end of the century.

The Greenland Ice Sheet is expected to melt faster than it is melting now, but no current models can predict exactly how this and other land-based ice masses in the Arctic will respond to projected changes in the climate. This is because ice dynamics and complex interactions between ocean, snow, ice and the atmosphere are not fully understood.

How these changes affect Arctic ecosystems and people

Changes in the cryosphere cause fundamental changes to the characteristics of Arctic ecosystems and in some cases loss of entire habitats. This has consequences for people who receive benefits from Arctic ecosystems.

Key finding 8

The observed and expected future changes to the Arctic cryosphere impact Arctic society on many levels. There are challenges, particularly for local communities and traditional ways of life. There are also new opportunities.

Key finding 9

Changes in the cryosphere cause fundamental changes in Arctic ecosystems

Changes in the amount of snow and the structure of the snowpack affect soils, plants and animals. Some species, such as pink-footed goose, benefit from less snow cover in spring. But animals grazing through snow, such as reindeer/caribou, suffer if winter rainfall creates an ice-crust over the snow. This is already happening more often in northern Canada and Scandinavia.

Less snow and faster melting are causing summer drought in forests, wetlands, and lakes supplied by snow melt. Thawing permafrost is also causing wetlands in some areas to drain and dry out, while creating new wetlands elsewhere.

The loss of ice cover over rivers, lakes and seas is changing animal and plant communities in the water.

The loss of large areas of sea ice represents devastating habitat loss for some ice-adapted species, including polar bear, seals, walrus, narwhal and

some microbial communities. Many animals, including bowhead whales, depend on tiny crustaceans that thrive near the sea ice. This food source is changing as the ice edge recedes.

These changes to ecosystems directly affect supplies of water, fish, timber, traditional/local foods and grazing land used by Arctic people. For example, it has been suggested that stocks of some sub-Arctic and Arctic-adapted fish species, including commercially important species, could change as sea ice recedes. Uncertainty about changing supplies of living natural resources makes it difficult to plan for the future.

Forestry may benefit from thawing permafrost in areas where there is enough water for trees to grow, but insect pests are increasingly causing problems. Some hunted animals, such as seals and walruses, are declining in numbers as ice conditions change. Others are moving to new locations, so hunters have to travel further to reach them.

Transport options and access to resources are radically changed by differences in the distribution and seasonal occurrence of snow, water, ice and permafrost in the Arctic. This affects both daily living and commercial activities.

Key finding 10

Arctic infrastructure faces increased risks of damage due to changes in the cryosphere, particularly the loss of permafrost and land-fast sea ice.

Key finding 11

Cryospheric change affects Arctic livelihoods and living conditions

Access to northern areas via the sea is increasing during the summer as sea ice disappears; allowing increased shipping and industrial activity. Offshore oil and gas activities will benefit from a longer open water season, although threats from icebergs may increase due to increased iceberg production. The International Maritime Organization is devising new mandatory guidelines for ships operating in ice-covered waters. Sea-ice decline creates challenges for local residents who use the ice as a platform for travel and hunting; these challenges may include travelling farther over uncertain ice conditions and increased hazards.

On land, access to many areas is becoming more difficult as ice roads melt earlier and freeze later and as permafrost degrades. Industrial operations reliant on ice roads will need to concentrate heavy load transport into the coldest part of the year. Shorter seasons where ice and snow roads can be used severely impact communities that rely on land transport of goods to maintain reasonable retail costs and ensure economic viability, particularly in northern Canada and Russia. Some land areas become more accessible for mining as glaciers and ice caps recede.

Thawing permafrost is causing increased deformation of buildings, roads, runways and other man-made structures in some areas, although poor design in the past is a contributing factor. New design methods are being developed that consider the likelihood of environmental change. Buildings and other infrastructure are at risk from heavier snow loads and floods caused by the release of ice jams in rivers or sudden emptying of glacial lakes.

Two-thirds of the Arctic coastline is held together and protected by ice. When land-fast sea ice melts earlier and permafrost thaws, rapid erosion can occur. Along the coasts bordering the Laptev and Beaufort

seas, coastal retreat rates of more than two metres per year have been recorded. A number of Inuit villages in Alaska are preparing to relocate in response to the encroaching sea.

In the short term, increased glacier melt creates new opportunities for hydroelectricity generation. This has potential benefits for industry. In the longer term, the volume of meltwater will decrease as glaciers shrink, potentially affecting electricity production.

Melting ice and snow release contaminants that have been stored for many years, allowing the contaminants to re-enter the environment. Exposure of people and top predators to contaminants that accumulate in food chains could further increase.

Increased access to the Arctic creates new economic opportunities. Cruise ship tourism is increasing. More people are coming to witness the effects of climate change on Arctic glaciers, for example at the Ilulissat Icefjord in Greenland. Increased tourism may challenge lifestyles and services in local communities as well as increase the demand for effective infrastructure (e.g., air services, marine navigation aids, and other safety measures). Loss of Arctic wildlife and change of scenery may adversely affect the tourist industry in the long term.

Cryospheric change combined with rapid development creates opportunities and challenges for Arctic residents. Traditional knowledge can help to detect change and adapt to it. While traditional knowledge continues to evolve, it is a challenge to ensure that this knowledge is being passed on to younger generations as lifestyles change. Some aspects of traditional knowledge become less applicable as the cryosphere and other components of the Arctic system change even more rapidly and become less predictable.

Why changes in the Arctic matter globally

Changes in the Arctic cryosphere have impacts on global climate and sea level

When highly reflective snow and ice surfaces melt away, they reveal darker land or ocean surfaces that absorb more of the sun's energy. The result is

enhanced warming of the Earth's surface and the air above it. There is evidence that this is happening over the Arctic Ocean as the sea ice retreats, as well as on land as snow melts earlier.

Overall emissions of methane and carbon dioxide from the Arctic could

Loss of ice and snow in the Arctic enhances climate warming by increasing absorption of the sun's energy at the surface of the planet. It could also dramatically increase emissions of carbon dioxide and methane and change large-scale ocean currents. The combined outcome of these effects is not yet known.

Key finding 12

Arctic glaciers, ice caps and the Greenland Ice Sheet contributed over 40% of the global sea level rise of around 3 mm per year observed between 2003 and 2008. In the future, global sea level is projected to rise by 0.9–1.6 m by 2100 and Arctic ice loss will make a substantial contribution to this.

Key finding 13

increase due to warming of soils and freshwater systems, and thawing of ancient frozen soil beneath the seabed.

The combined outcome of these effects on global climate is not yet known.

All the main sources of freshwater entering the Arctic Ocean are increasing – river discharge, rain/snow, and melting glaciers, ice caps, and the Greenland Ice Sheet. Recent calculations estimate that an extra 7700 km³ of freshwater – equivalent to one metre of water over the entire land surface of Australia – has been added to the Arctic Ocean in recent years. There is a risk that this could alter large-scale ocean currents that affect climate on a continental scale.

Melting glaciers and ice sheets worldwide have become the biggest contributor to global sea level rise. Arctic glaciers, ice caps, and the Greenland Ice Sheet contributed 1.3 mm – over 40% – of the total 3.1 mm global sea level rise observed every year between 2003 and 2008. These contributions from the Arctic to global sea level rise are much greater than previously measured.

High uncertainty surrounds estimates of future global sea level. Latest models predict a rise of 0.9 to 1.6 m above

the 1990 level by 2100, with Arctic ice making a significant contribution.

Changes in the Arctic cryosphere affect global society

Sea level rise is one of the most serious societal impacts of cryospheric change. Higher average sea level and more damaging storm surges will directly affect millions of people in low-lying coastal flood plains. Sea level rise increases the risk of inundation in coastal cities such as Shanghai and New York.

On the other hand, global economic activity may benefit from cryospheric changes in the Arctic. For example, opening transpolar sea routes across the Arctic Ocean will reduce the distance for ships travelling between Europe and the Pacific by 40% compared to current routes. This could reduce emissions and energy use.

Some unique Arctic species, such as the narwhal, face particular threats as the cryosphere changes. The decline of cryospheric habitats such as sea ice and wetlands over permafrost will impact on migratory species of mammals and birds from elsewhere in the world. These adverse effects on biodiversity are of global concern.

What should be done

Everyone who lives, works or does business in the Arctic will need to adapt to changes in the cryosphere. Adaptation also requires leadership from governments and international bodies, and increased investment in infrastructure.

Key finding 14

Adaptation is urgent and needed at all levels

Cryospheric change affects people at the local level first, and local communities will need to devise strategies to cope with emerging risks.

At national and regional levels, adaptation requires leadership from governments and international bodies to establish new laws and regulations. For example, new fishing regulations will be required as fish stocks change. New standards will need to be developed for construction, particularly in areas affected by thawing permafrost.

Governments will need to invest in transport networks to cope with the shorter ice road season. Search and rescue operations will need to be enhanced to respond to increasing traffic and risks at sea, and accurate forecasts of weather and sea conditions are required to ensure travel safety.

Arctic communities are resilient and will actively respond to cryospheric change. However, rapid rates of change may outpace adaptation capacity. Knowledge and research are needed to foresee how living conditions are likely to change, and to evaluate possible adaptation options. Concerns of indigenous peoples need particular attention in this regard.

Changes in the cryosphere are not the only driver of change in the Arctic. Cryospheric change and climate change occur in the context of societal change, which may be even more challenging. The combined effects of societal, climatic and cryospheric change must be taken into account in adaptation strategies.

Cutting greenhouse gas emissions globally is urgent

Climate change represents an urgent and potentially irreversible threat to human societies. Global climate modeling studies show that deep and immediate

There remains a great deal of uncertainty about how fast the Arctic cryosphere will change in the future and what the ultimate impacts of the changes will be. Interactions ('feedbacks') between elements of the cryosphere and climate system are particularly uncertain. Concerted monitoring and research is needed to reduce this uncertainty.

Key finding 15

cuts in global greenhouse gas emissions are required to hold the increase in global average temperatures below 2 °C above pre-industrial levels. Combating human-induced climate change is an urgent common challenge for the international community, requiring immediate global action and international commitment.

Following the ACIA report, published in 2005, Ministers of the Arctic Council acknowledged that “timely, measured and concerted action is needed to address global emissions.” They endorsed a number of policy recommendations for reducing greenhouse gas emissions, including to “Adopt ... strategies ... [to] address net greenhouse gas emissions and limit them in the long term to levels consistent with the ultimate objective of the UNFCCC [United Nations Framework Convention on Climate Change].”

The key findings of the SWIPA assessment, especially the rapid and accelerated rates of change in Arctic cryosphere conditions, emphasize the need for greater urgency in taking these actions.

Uncertainty can be reduced by further research

Current monitoring, research and model results provide high confidence that significant changes are occurring in the Arctic cryosphere and that these changes will continue in the future. Some of the observed changes align with expectations but one major component of the cryosphere (sea ice) has reacted faster than anticipated just five years ago. Even so, substantial uncertainty remains, particularly concerning the future timing of changes, and the effects of interactions (feedbacks) between components of the cryosphere and climate system.

To reduce the uncertainty in future assessments, more robust observational networks are needed. Satellites and airborne measurements have improved the ability to observe some elements of the Arctic cryosphere such as sea-ice extent and snow cover. Monitoring of other key elements of the cryosphere, notably sea-ice thickness, snow depth, permafrost and glaciers, requires surface-based observations.

Many surface-based snow, freshwater ice, and precipitation gauge networks have diminished or have been completely

lost, and sites for measuring sea ice, land ice, and physical properties of snow are sparse. Observational networks need to be expanded to provide a robust set of cryospheric data for monitoring, model improvement and satellite product validation.

The biggest unanswered questions identified by this report are:

- What will happen to the Arctic Ocean and its ecosystems as freshwater is added by melting ice and increased river flow?
- How quickly could the Greenland Ice Sheet melt?
- How will changes in the Arctic cryosphere affect the global climate?
- How will the changes affect Arctic societies and economies?

Answering some of these questions requires improved monitoring networks. A better understanding of the complex interactions between the physical, chemical and biological environments in the Arctic is needed. There is a lack of systematically collected information on the effects of cryospheric change on human society.

Communicating about cryospheric change and its effects

The SWIPA assessment documents the importance of climate-induced changes in Arctic snow, water and ice conditions and the profound implications for the local, regional, and global society.

Active communication of this new knowledge, to enhance global, national, and local awareness, will help to ensure that the SWIPA assessment generates benefits for people in the Arctic.

A co-ordinated response to cryospheric change

The combined effects of the changing cryosphere, climate change, and rapid development in the Arctic will create political challenges for Arctic societies, as well as the global community. Traditional livelihoods are most vulnerable to changes in the cryosphere. There is a need for co-operation and co-ordinated effort at all levels, to respond to change and increase the resilience of Arctic ecosystems and societies.

Recommendations

Based on the SWIPA key findings, the AMAP Working Group have agreed to the following recommendations:

Adaptation

Members of the Arctic Council and governments at all levels in the Arctic should work to:

- Develop regional-scale assessments of cryospheric change and the associated risks.
- Develop and implement Arctic adaptation strategies appropriate to the scale and character of anticipated changes. Such strategies must take account of other relevant drivers of change.
- Ensure that standards for environmental management are in place, or can be adapted, to take account of cryospheric change. Develop regulations where necessary.
- Upgrade the capacity for search and rescue operations and environmental hazard responses.
- Facilitate measures to increase the accuracy of forecasting for ice, weather, and sea conditions, and make forecasts accessible to all Arctic residents and organizations.

Mitigation

International negotiations to reduce global greenhouse gas emissions should be pursued as a matter of urgency.

Member States of the Arctic Council should increase their leadership role in this process.

Observation

Arctic countries and international organizations should:

- Improve and expand systematic, comprehensive surface-based monitoring of the cryosphere.
- Maintain and support development of remote sensing methods for observing the cryosphere.
- Develop and enhance systems to observe the cascading effects of cryospheric change on ecosystems and human society.
- Expand research into processes that are important for modeling the cryosphere, to reduce uncertainty in predicting cryospheric change. In particular, improvements are needed in modeling permafrost dynamics, snow-vegetation interactions, and mass loss from glaciers, ice caps, and the Greenland Ice Sheet.

Outreach

The Members and Observers of the Arctic Council should individually and collectively inform and educate Arctic societies and the global society about the changes in the Arctic linked to climate change, and how they affect people locally, regionally and globally.

Policy Needs

Governments and institutions at all levels should increase co-operation and co-ordinate efforts to respond to the challenges and opportunities associated with cryospheric change.

The Arctic Council should conduct an integrated assessment of the combined impacts of change in the Arctic, focused on how to minimize environmental damage and enhance human well-being.

1. Introduction

AUTHORS: MORTEN SKOVGAARD OLSEN, LARS-OTTO REIERSEN

CONTRIBUTING AUTHORS: POVL FRICH, JAMES OVERLAND, JAMES D. REIST, SIMON WILSON

Contents

1.1. Why assess the effect of climate change in the Arctic cryosphere?	2
1.2. An Arctic cryosphere assessment.....	2
1.2.1. What is the Arctic?	2
1.2.2. What is the cryosphere?	2
1.3. Aims of SWIPA.....	2
1.4. Roles and relevance of the cryosphere	4
1.5. What SWIPA does and does not cover	5
1.6. The SWIPA assessment process	7
1.7. Readers guide: What will the readers find within each chapter?	7
References.....	8

1.1. Why assess the effect of climate change in the Arctic cryosphere?

The *Arctic Climate Impact Assessment* (ACIA, 2005) was the second climate assessment conducted by the Arctic Monitoring and Assessment Programme (AMAP), one of the Arctic Council's expert Working Groups. It was produced in close cooperation with the International Arctic Science Committee (IASC) and the Arctic Council Working Group on Conservation of Arctic Flora and Fauna (CAFF). The ACIA report provided the first comprehensive documentation of the ongoing climate change within the Arctic and its potential impacts at local, regional and global levels, and formed an important background report for the Fourth Assessment Report of the Intergovernmental Panel on Climate Change (IPCC, 2007). The ACIA report was the first Arctic climate impact assessment to synthesize and evaluate information on physical changes, changes in biological systems, and impacts on human infrastructure and activities.

The ACIA summary report (ACIA, 2004) identified ten key findings:

1. Arctic climate is now warming rapidly and much larger changes are projected.
2. Arctic warming and its consequences have worldwide implications.
3. Arctic vegetation zones are very likely to shift, causing wide-ranging impacts.
4. Animal species' diversity, ranges, and distribution will change.
5. Many coastal communities and facilities face increasing exposure to storms.
6. Reduced sea ice is very likely to increase marine transport and access to resources.
7. Thawing ground will disrupt transportation, buildings, and other infrastructure.
8. Indigenous communities are facing major economic and cultural impacts.
9. Elevated ultraviolet radiation levels will affect people, plants, and animals.
10. Multiple influences interact to cause impacts to people and ecosystems.

In its policy response to the ACIA, the Arctic Council (Arctic Council, 2004):

Acknowledge[d] the need to further organize the work of the Arctic Council and its subsidiary bodies based on the findings of the ACIA and direct[ed] the SAOs to report on the progress made at the 2006 Ministerial Meeting.

and

Direct[ed] relevant technical working groups of the Arctic Council to review the scientific chapters of the ACIA in the context of their ongoing and future work programmes and to report on the progress made at the 2006 Ministerial Meeting.

New observations showed (and continue to show) that in

recent years some of the components of the Arctic cryosphere have undergone changes that exceed even those described and projected in the ACIA (2005) and IPCC (2007) assessments. Consequently, the Arctic Council initiated an assessment of 'Climate Change and the Cryosphere: Snow, Water, Ice and Permafrost in the Arctic (SWIPA)' in 2008 (SWIPA project description, 2008).

The Arctic Council requested AMAP to undertake the assessment in collaboration with relevant international organizations (IASC and the International Arctic Social Sciences Association, IASSA) and relevant international activities (the World Climate Research Programme's Climate and Cryosphere Project, CliC; and the International Polar Year, IPY).

1.2. An Arctic cryosphere assessment

1.2.1. What is the Arctic?

The geographical delineation of the Arctic used by the SWIPA assessment is based on the definition used by AMAP (see Figure 1.1). The 'AMAP area' essentially includes the terrestrial and marine areas north of the Arctic Circle (66°32' N), and north of 62° N in Asia and 60° N in North America, modified to include the marine areas north of the Aleutian chain, Hudson Bay, and parts of the North Atlantic Ocean including the Labrador Sea.

1.2.2. What is the cryosphere?

The cryosphere collectively describes elements of the Earth System containing water in its seasonally and perennially frozen state. In the Arctic, the various components of the cryosphere include the following: snow, including solid precipitation; permafrost areas (i.e., ground that remains at or below 0 °C for two or more consecutive years) present in terrestrial and marine environments; river and lake ice; mountain glaciers and ice caps; the Greenland Ice Sheet; and sea ice in all its forms (i.e., perennial pack ice, seasonal land-fast ice). These cryospheric components (see Figure 1.2) represent a globally unique system, parts of which are inextricably linked with each other, with the landscapes, seascapes, ecosystems and humans in the Arctic, and with the global climate and ecological systems themselves. Consequently, shifts in the Arctic cryosphere have great significance, not just regionally within the Arctic but also globally across the planet as a whole.

1.3. Aims of SWIPA

The objectives of the SWIPA Project are to provide the Arctic Council with timely, up-to-date, and synthesized scientific knowledge about the present status, processes, trends, and future consequences of changes in Arctic snow cover, permafrost, lake and river ice, mountain glaciers and ice caps, the Greenland Ice Sheet, and sea ice conditions, and related hydrological conditions in the Arctic. Future scenarios have been developed to determine, as far as possible, the consequences of these changes on physical processes on local, regional, and global scales, and to determine consequences for Arctic biological systems, and human societies and lifestyles.

The ACIA assessment constitutes the benchmark for the SWIPA assessment, which focuses on recent change in the Arctic cryosphere and the effects of observed and projected



Figure 1.1. The Arctic, as defined by AMAP and as used in the present assessment.




Figure 1.2. The various components of the Arctic cryosphere.

change. The SWIPA assessment is thus an update and extension of the ACIA findings on the consequences of change in the Arctic cryosphere component of the global climate system. Figure 1.3 presents a conceptual illustration of the various components of the SWIPA assessment and the links between them.

1.4. Roles and relevance of the cryosphere

The cryosphere is a defining aspect of polar and high altitude regions of the globe, with the relative importance of various components differing as to their location on the Earth. The cryosphere is a fundamental regulator or controller of local and regional climate as well as global climate systems. Moreover, the cryosphere itself provides direct services (or impediments) to other elements of the earth system, including humans, as well as indirectly affecting the nature of services provided by those other elements (i.e., ecosystem provisioning and regulatory services).

Both the Arctic generally, and the Arctic cryosphere in particular, combine to act as the thermostat for the Northern Hemisphere. Heat from the warmer lower latitudes is transported to the Arctic by ocean currents and the atmosphere. Air and water masses are cooled in the Arctic and then returned to southern latitudes as cold air outbreaks and cold ocean currents. The Arctic also cools the Earth by reflecting radiation back into space. These processes regulate many aspects of the global climate system. Moreover, general properties of the cold sink enable heat transfer northward

(thus cooling more southerly source regions), and with that, physical transport of atmospheric and water constituents (i.e., gases, freshwaters and marine waters). Contaminants, aerosols, dust and soot mostly generated in southerly areas are also transported northward in gases and water, as are nutrients and biota. Nutrients released locally or advected into the Arctic provide the basis for much Arctic productivity and may be concentrated at key frontal regions between southern and northern oceanic water masses. Properties of the cold sink also result in the deposition, precipitation or concentration of these transported constituents, which include anthropogenically produced contaminants. On the longer timescale, storage of greenhouse gases (GHGs), and accumulation of organic material or ground ice has taken place due to natural processes. Gaseous carbon that has been produced in geological deposits is currently capped by permafrost.

The cryospheric components represent the solid phases of water or regular cyclical changes between solid, liquid or gaseous phases. Solid phases provide fundamental physical structuring of the Arctic environment (e.g., ice as a platform for activities) and also act as significant storage reservoirs for many constituents (e.g., water itself as ice or semi-permanent snow, contaminants, impermeable permafrost storing GHGs). Thus, from the perspective of SWIPA, recent cryospheric change primarily represents an irregular shift in phase from solid to liquid, a shift toward greater durations of the liquid phase, or a shift in timing of such phases. Phase changes themselves are key (and essential) structural changes in the physical systems. Many ecosystem components and the resulting services that humans receive from those ecosystems rely upon fixed phases




Figure 1.3. The Arctic cryosphere and linkages to various levels of effects or consequences of changes. The SWIPA assessment focuses on the red components highlighted in the various elements of the overall system and the cascade of effects shown as thick arrows. Several points emerge from the diagram: (i) Arctic climate change induces change in systems other than just the cryosphere itself (blue arrows); (ii) other drivers of the overall system induce changes in various elements (green arrows) (and thus discerning those solely due to cryospheric change may be difficult especially as consequences for humans); (iii) feedbacks are important aspects of the overall system (dotted arrows, and not all are shown), and may induce synergistic as well as antagonistic effects in receiving elements (e.g., human behavioral responses to Arctic cryospheric changes will induce feedbacks in the biophysical system); (iv) climate-induced changes in the cryosphere have differing consequences within versus outside the Arctic; and (v) cumulative effects (i.e., additive or multiplicative cascades through components of the overall system) are implied but not explicitly shown on the figure.

of the cryosphere or upon regular relatively predictable spatio-temporal shifts in such (e.g., seasonally predictable patterns of ice formation in a particular location). Physical services include acting as a stable platform upon which activities (e.g., travel on ice) or infrastructure (e.g., basis for roads) can occur. Alternatively, the liquid phase of water is fundamental to life and affects freshwater supply which, in turn, profoundly affects Arctic ecosystems, their productivity and services, and ecological links to humans, as well as affecting humans directly. More subtle cryospheric services include sources of water to maintain stream flow (e.g., glacial melt), acting as drainage barriers in the landscape (e.g., permafrost) thereby maintaining local water balances, and as elements that re-structure (e.g., river ice jams) or protect (e.g., land-fast sea ice) landscapes.

Box 1.1. Discerning change and variability in complex systems

One generation ago, the concept of climate change was very strict: Most scientists agreed that a statistically significant change from one standard normal period (such as 1961–1990) to another similar period defined by the World Meteorological Organization (WMO) would constitute a change locally.

One decade ago, the criteria for change were relaxed by the Intergovernmental Panel on Climate Change (IPCC, 2001). Owing to new observational evidence, the IPCC stated in its Third Assessment report that *it is very likely that the 1990s was the warmest decade... in the instrumental record (1861–2000)*.

Less than five years ago, in its Fourth Assessment Report (IPCC, 2007) the IPCC stated: *The last time the polar regions were significantly warmer than present for an extended period (about 125,000 years ago), reductions in polar ice volume led to 4 to 6 m of sea level rise.*

In the period since the completion of the ACIA assessment in 2004, the Arctic has experienced its highest temperatures of the instrumental record.

Why has it come this far? First of all it has to do with climate change itself. Changes in the Arctic have taken scientists working in the field by surprise. Neither previous observations nor modeling experiments had indicated that cryospheric change could take place so fast. Second, a number of new observational techniques (such as satellites in the sky, drones in the sea, and automatic stations on glaciers) have led to recent amplification in the number of independent – yet verifiable – pieces of evidence, which all tell the same story: The Arctic cryosphere is changing rapidly. Scientists are now convinced that the emerging picture of a rapidly thawing Arctic environment is not a coincidence, but a real and significant change in the climate system of the Earth.

Details about significance may be discussed at length, as has been the case in the scientific literature and in the present report, but it is now becoming very clear that the cryosphere is changing rapidly and that neither observations nor models are able to tell the full story.

The need for concerted monitoring of the cryosphere has emerged with this report as one of the most pressing challenges of our time.

Conversely, depending upon the nature of the human activity, the solid phase of the cryosphere may act as an impediment to some activities or services preventing or altering how or when the environment might be used (e.g., sea ice as a barrier to shipping or resource exploitation). Thus, any observed physical changes in the Arctic cryospheric components represent significant departures from recent norms in the environment from which a cascade of consequences may result.

1.5. What SWIPA does and does not cover

Cryospheric change and variability is fundamentally linked to climate change (see Boxes 1.1 to 1.3) and climatic variability. The SWIPA assessment is not, however, an assessment of climate change *per se*, neither is it a comprehensive update of the ACIA results. Like ACIA, the SWIPA assessment considers the implications of change in the physical components of the Arctic cryosphere on Arctic human populations, and – where relevant – humans living outside the Arctic. The ACIA findings constitute the benchmark for the SWIPA assessment, and an assessment against which the new information presented in the SWIPA assessment can be compared.

The climate change history and future projections presented in the ACIA report (ACIA, 2005) and the IPCC Fourth Assessment report (IPCC, 2007) represent the ‘climate framework’ for the SWIPA assessment. This information is summarized in Chapter 2 (this volume). Development of new climate change projections or detailed analyses of recent trends in anthropogenic GHG emissions were outside the scope of this assessment. New information presented in this assessment concerning, for example, modeling activities is therefore restricted to evaluating models to select those most useful for refining projections for individual cryosphere components.

Box 1.2. Are Arctic climate and cryospheric changes attributable to anthropogenic causes?

Once change in a system of interest has been observed and confirmed, the second step is to understand the causes for that change. That is, with respect to climate and cryospheric change in the Arctic, is this the result of ‘natural’ (i.e., non-anthropogenic) drivers and thus part of either system cyclicity or long-term evolution, or is it the result of ‘non-natural’ (i.e., anthropogenic) drivers?

High association of climate changes with significantly increased levels of anthropogenically produced GHGs, and the understanding of causal linkages between GHGs (a primary driver) and the climate system (a responding system), both provide evidence that human-derived activities have altered, and are continuing to alter the global climate system over the recent past (e.g., see IPCC, 2007 and ACIA, 2005). Accordingly, although the SWIPA Science Report focuses primarily on Arctic cryospheric changes driven by underlying climate changes rather than on causation of those changes, the overwhelming basis for conducting such an assessment is that anthropogenic drivers are significant and fundamental contributors to Arctic climate change, which is the main driver of changes in the Arctic cryosphere.

Box 1.3. An example of rapid change in the cryosphere attributed to global warming

The Arctic is warming faster than other regions of the Earth. This is known as the Arctic amplification effect (Figure 1.4). The effect can be local such as through loss of sea ice (Miller et al., 2010) or as a result of the planetary atmospheric and oceanic circulation (Langen and Alexeev, 2007). Forcing of the 20th and 21st century warming is generally attributed to changes in solar heating, volcanism, GHGs, and aerosols. In discussing these impacts it is important to go beyond simply independently correlating the time series of the forcing function with the northern hemispheric temperature record, and put the contribution of each factor on a comparative quantitative basis. This was done by Crowley (2000) and the results are summarized in Figure 1.5 showing historical forcing over time, where the forcing influence is normalized in terms of W/m^2 . Volcanoes have a cooling influence of up

to -5 W/m^2 that can last for a year or two. Increased carbon dioxide (CO_2), a warming influence with a continuing increase in the second half of the 20th century, has a value of 2.4 W/m^2 by 2000. Sulfate (SO_4) is an aerosol with a cooling influence of 0.6 W/m^2 by 2000. Solar forcing has decadal and centennial variability, but its influence over the previous 200 years is below 0.4 W/m^2 . In 2000, the ratio of the CO_2 influence to the solar contribution is 8:1. Crowley's work was echoed in the IPCC AR4 Summary for policymakers (IPCC, 2007) which stated that most of the observed increase in global average temperature since the mid-20th century is very likely to be due to the observed increase in anthropogenic GHG concentrations and therefore it is unlikely that the increased warming and melt of ice in the Arctic is only due to the solar component (see Stott et al., 2000 and Overland, 2009 for further discussion).

Figure 1.4. Near-surface air temperature anomaly multiyear composites for 2002–2009. Anomalies are relative to the 1951–1980 mean and show a strong Arctic amplification of recent temperature trends. Data are from the NCEP–NCAR Reanalysis through the NOAA/Earth Systems Research Laboratory, generated online at www.cdc.noaa.gov.





Figure 1.5. Relative forcing of 20th century northern hemispheric temperature increases. Redrawn after Crowley (2000). Note scale differences in y-axes.



All parts of the Arctic cryosphere are a product of and subject to climatic conditions, but whereas seasonal phenomena (such as seasonal snow cover and seasonal ice on rivers and lakes) respond to specific weather conditions and rapidly changing climatic conditions, other parts of the cryosphere (such as permafrost) respond very slowly. The implication is that the timescales for which it is meaningful to model change in one part of the cryosphere may be very different from those that are meaningful for modeling change in another. Furthermore, the capability of different models to project change in a given component of the cryosphere may differ substantially. Therefore different model assemblies, scenarios, and timescales have been used in the projections of change in the different components of the Arctic cryosphere.

While reference is made to possible relationships between short-lived climate forcers such as black carbon ('soot') and some components of the Arctic cryosphere, this is not assessed in detail in the present assessment. A separate AMAP report on the state of scientific knowledge concerning short-lived climate forcers of climate change in the Arctic was presented to the Arctic Council at its meeting in May 2011 (AMAP, 2011a).

1.6. The SWIPA assessment process

The SWIPA assessment was produced by more than 200 scientists and experts from the Arctic and non-Arctic countries. They were initially nominated by countries and relevant international bodies and were selected on the basis of their scientific qualifications by appointed convening lead authors. These experts were charged with compiling and evaluating information from Arctic monitoring networks and recent national and international research activities, such as those carried out during the International Polar Year (2007–2008), focusing on new information gathered since the ACIA assessment. Each chapter of the present assessment was drafted by a group of experts including relevant expertise from different scientific disciplines and geographical areas. A SWIPA assessment 'Integration Team' including the convening lead authors for each chapter was responsible for the overall conduct and organization of the assessment.

This assessment report is fully-referenced. The majority of the assessment is based purely on information that is published and available in the peer-reviewed scientific literature or on new results obtained using well-documented models and observational methods. In the case of sections dealing with for instance societal implications of cryospheric change (in

the specific chapters and in Chapter 10 in particular) some information sources differ from this principle. In order to assess these aspects, the authors needed to use some 'grey literature' such as government reports, design standards, or anecdotal evidence. However, all materials used in the preparation of this assessment, that are not available in the mainstream published scientific literature, have been collected and are available through the AMAP Secretariat.

The assessments by chapter authors followed recommendations to promote the use of common terminology as far as possible. This included use of terminology associated with probability statements where discussion of future events and conditions need to take into account the likelihood that these conditions or events will occur. To ensure consistency of the summarized material, the procedures used by ACIA (as refined from those of the IPCC) were used throughout this report (see Figure 1.6).

Statements regarding the likelihood of particular events or conditions occurring reflect expert evaluation of peer-reviewed results, typically from multiple lines of evidence.

The assessment presented in this report has been subject to a comprehensive review process, which involved a review by national experts that contributed data and information to the assessment, to verify that the interpretation of their data was correct and acceptable to the primary sources. In addition, a strict and independent peer review process was established by the AMAP Working Group to secure and document the integrity of the process (see the Preface for further details of the review process).

Documentation of the results of the peer review process applied to the SWIPA assessment is available on the AMAP website: www.amap.no.

1.7. Readers guide: What will the readers find within each chapter?

This report presents the findings of the SWIPA assessment as developed by the report authors, produced under their responsibility. It represents the scientific findings of a large group of independent scientific experts.

A separate report, produced under the responsibility of the AMAP Working Group, summarizes the SWIPA Science Assessment (AMAP, 2012). A SWIPA Summary for Policymakers produced under the AMAP Working Group and presented to the Arctic Council Ministers at their meeting in




Figure 1.6. Five-tier lexicon describing the likelihood of expected change.

Nuuk, Greenland, 2011 includes policy-relevant scientific recommendations (AMAP, 2011b). The scientific SWIPA assessment report (the present report) provides the validated scientific basis for all statements made in the overview report and the SWIPA summary for policymakers, as confirmed by the lead authors of the SWIPA scientific assessment.

This report is developed in five main parts. The first part (Chapters 1 to 3) introduces and defines the scope of the assessment, and presents the background climate information that establishes the framework for the assessment of Arctic cryospheric change. The second part (Chapters 4 to 9) describes the physical and other aspects of each of the individual components of the Arctic cryosphere, including discussion of the impacts of change in the cryospheric components concerned. A third part (Chapter 10) focuses on the combined impacts of Arctic cryospheric change on Arctic human society. The fourth part (Chapter 11) focuses on cross-cutting issues of importance at local, regional and global levels. Finally, Chapter 12 presents an integrated synthesis of the findings of the assessment together with the conclusions and recommendations of the assessment as a whole.

A more detailed description of the content of each of the main chapters is as follows:

- Chapter 1 sets the stage for the assessment describing its scope and how it was accomplished.
- Chapter 2 presents an overview of past and present climate in the Arctic, establishing the ‘climate framework’ for the assessment.
- Chapter 3 provides a critical evaluation of the climate models employed by the IPCC in relation to their ability to produce projections for components of the Arctic cryosphere.
- Chapter 4 describes the snow component of the cryosphere, focusing on variation and change in snow extent and depth over time, seasons and geographical extent.
- Chapter 5 describes permafrost conditions and the consequences of the permafrost thawing that is ongoing in different regions of the Arctic.
- Chapter 6 describes changes in Arctic river and lake ice and how these affect biological systems and the human use of these components of the cryosphere.
- Chapter 7 describes changing Arctic mountain glaciers and ice caps, the changes that are being observed and the mechanisms behind these changes.
- Chapter 8 presents a review of the status of the mass balance of the Greenland Ice Sheet, updating a preliminary assessment of this subject that was prepared for the UN Climate Change Conference 2009 (UNFCCC COP15) in Copenhagen (AMAP, 2009).
- Chapter 9 presents a synthesis of observed changes in Arctic sea-ice extent and thickness that have been recorded over the past several decades. The chapter also assesses how the observed changes affect biological life associated with sea ice and effects on human activities, such as shipping and traditional hunting.
- Chapter 10 presents a synthesis of available information on the potential effects of the changes in the Arctic cryosphere on humans and human activities.
- Chapter 11 presents an integrated assessment of cross-cutting scientific issues that affect multiple components of the cryosphere. These include assessments of feedback mechanisms leading to global sea-level rise; ways in which cryospheric change affects transport and bioavailability of contaminants within the Arctic region; ways in which cryospheric change affects Arctic ecosystems; and systems available for observing changes in the Arctic cryosphere.
- Chapter 12 presents an overall summary of the major findings of the SWIPA assessment. It is based on the logical consequences of and conclusions stemming from the scientific findings presented in the preceding chapters.

References

- ACIA, 2004. Impacts of a Warming Arctic: Arctic Climate Impact Assessment. 140 pp. Cambridge University Press.
- ACIA, 2005. Arctic Climate Impact Assessment: Scientific Report. 1042 pp. Cambridge University Press.
- AMAP, 2009. The Greenland Ice Sheet in a Changing Climate: Snow, Water, Ice and Permafrost in the Arctic (SWIPA) 2009. By: D. Dahl-Jensen, C.E. Boggild, E. Buch, J.H. Christensen, K. Dethloff, M. Fahnestock, S. Marshall, M. Rosing, K. Steffen, R. Thomas, M. Truffer, M. van den Broeke and C.J. van der Veen. 115 pp. Arctic Monitoring and Assessment Programme (AMAP), Oslo, Norway.
- AMAP, 2011a. The Impact of Black Carbon on Arctic Climate. By: P.K. Quinn, A. Stohl, A. Arneth, T. Berntsen, J. F. Burkhart, J. Christensen, M. Flanner, K. Kupiainen, H. Lihavainen, M. Shepherd, V. Shevchenko, H. Skov and V. Vestreng. Arctic Monitoring and Assessment Programme (AMAP), Oslo, Norway.
- AMAP, 2011b. SWIPA 2011 Executive Summary: Snow, Water, Ice, and Permafrost in the Arctic. Arctic Monitoring and Assessment Programme (AMAP), Oslo, Norway.
- AMAP, 2012. Arctic Climate 2011: Snow, Water, Ice and Permafrost in the Arctic (SWIPA). Arctic Monitoring and Assessment Programme, Oslo, Norway.
- Arctic Council, 2004. Arctic Climate Impact Assessment. Policy Document. Issued by the Fourth Arctic Council Ministerial Meeting. Reykjavik, November 24, 2004.
- Crowley, T.J., 2000. Causes of climate change over the past 1000 years. *Science*, 289:270.
- IPCC, 2001. Climate Change 2001: Synthesis Report. A Contribution of Working Groups I, II, and III to the Third Assessment Report of the Intergovernmental Panel on Climate Change. Watson, R.T. and the Core Writing Team (Eds.), pp. 398. Cambridge University Press.
- IPCC, 2007. Summary for Policymakers. Climate Change 2007: The Physical Science Basis. Contribution of Working Group I to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change. Solomon, S., D. Qin, M. Manning, Z. Chen, M. Marquis, K.B. Averyt, M. Tignor and H.I. Miller (Eds.), pp. 1-21. Cambridge University Press.
- Langen, P.L. and V.A. Alexeev, 2007. Polar amplification as a preferred response in an idealized aquaplanet GCM. *Climate Dynamics*, 29:305-317.
- Miller, G.H., R.B. Alley, J. Brigham-Grette, J.J. Fitzpatrick, L. Polyak, M. Serreze and J.W.C. White, 2010. Arctic amplification: can the past constrain the future? *Quaternary Science Reviews*, 29:1779-1790.
- Overland, J.E., 2009. The case for global warming in the Arctic. In: Nihoul, J.C.J. and A.G. Kostianoy (Eds.). *Influence of Climate Change on the Changing Arctic and Sub-Arctic Conditions*, pp. 13-23, Springer.
- Stott, P.A., F.B. Tett, G.S. Jones, M.R. Allen, J.F.B. Mitchell and G.J. Jenkins, 2000. External control of 20th century temperature by natural and anthropogenic forcings. *Science*, 290:2133.
- SWIPA, 2008. Climate Change and the Cryosphere: Snow, Water, Ice, and Permafrost in the Arctic (SWIPA). Project description as approved by Senior Arctic Officials in Svolvær.

2. Arctic Climate: Recent Variations

AUTHORS: JOHN E. WALSH, JAMES E. OVERLAND, PAVEL Y. GROISMAN, BRUNO RUDOLF

Contents

Key Findings	2
Summary	2
2.1. Introduction	3
2.2. Air temperatures.....	3
2.3. Precipitation.....	7
2.4. Storminess	8
2.5. Cloudiness	9
2.6. Ocean variations.....	9
2.7. Conclusions	10
References.....	12

Key Findings

- In the period since the completion of the Arctic Climate Impact Assessment in 2004, the Arctic has experienced its highest surface air temperatures of the instrumental record, exceeding even the warmth of the 1930s and 1940s.
- Subject to the uncertainties inherent in proxy information, recent paleo-reconstructions show that Arctic summer temperatures have been higher in the past few decades than at any time in the past 2000 years.
- The spatial distribution of the recent warming points strongly to an influence of sea-ice reduction, as the greatest temperature increase has occurred in the lower atmosphere over the marginal sea ice zone during autumn.
- A secondary maximum of warming during springtime is consistent with an earlier loss of terrestrial snow cover in recent years.
- The spatial pattern of the near-surface warming shows the signature of the Pacific Decadal Oscillation in the Pacific sector as well as the influence of a dipole-like circulation pattern in the Atlantic sector, where wind-driven export of older sea ice appears to have preconditioned the Arctic Ocean for its recent rapid ice loss.
- Although the trends are not statistically significant because interannual variability is large, recent annual pan-Arctic precipitation generally exceeds the mean of the 1950s by about 5%.
- The years since 2000 have been quite wet in the Arctic according to both precipitation and river discharge data. The five wettest years since 1950 have all occurred in the past decade.
- Storm activity and the occurrence of temperature extremes have increased at some locations in the North American Arctic, but there are no indications of systematic increases in storminess in the Arctic over the past half century.
- While cloud data for the Arctic are difficult to interpret quantitatively, there are indications of increases in cloudiness over the Arctic, especially in low clouds during the warm season.
- The Arctic Ocean has experienced enhanced oceanic heat inflows from both the North Atlantic and the North Pacific. The Pacific inflows appear to have played a role in the retreat of sea ice in the Pacific sector of the Arctic Ocean.
- North Atlantic inflows to the Arctic Ocean appear to be characterized by increasingly warm pulses of water. One such pulse moved along the Siberian shelf break in the mid-2000s, while the next pulse is now poised to enter the Arctic Ocean through Fram Strait.

Summary

In the period since the completion of the Arctic Climate Impact Assessment in 2004 (ACIA, 2005), the Arctic has experienced its highest temperatures of the instrumental record, even exceeding the warmth of the 1930s and 1940s. Recent paleo-reconstructions, while subject to uncertainties in the methodology and spatial representativeness, also show that Arctic summer temperatures have been higher in the past few decades than at any time in the past 2000 years. The geographical distribution of the recent warming points strongly to an influence of sea-ice reduction on temperature, as the greatest temperature increase has occurred in the lower atmosphere over the marginal sea ice zone during autumn. The seasonality and location of the maximum warming indicates that the Arctic may have passed the threshold at which absorption of solar radiation during summer limits ice growth during the following autumn and winter, initiating a feedback that leads to a substantial increase in Arctic Ocean surface air temperatures. A secondary maximum of warming during springtime is consistent with an earlier loss of terrestrial snow cover in recent years. The spatial pattern of the near-surface warming shows the signature of the Pacific Decadal Oscillation (PDO) in the Pacific sector as well as the influence of a dipole-like circulation pattern in the Atlantic sector. Since the Arctic Oscillation (AO) has been generally neutral, it has not been a major determinant of Arctic warmth of the past several years. Spatially averaged Arctic precipitation over the land areas north of 55° N shows large year-to-year variability. This variability is superimposed on an increase of about 5% since 1950. While the statistical significance of the precipitation increase has not been demonstrated, the years since 2000, and especially since 2004, have been quite wet according to both precipitation and river discharge data. The five wettest years since 1950 have all occurred in the past decade. Estimates of precipitation over the Arctic Ocean remain a high priority need in assessments of recent Arctic change. There are indications of increases in cloudiness over the Arctic, especially in low clouds during the warm season, consistent with a longer summer season and a reduction of summer sea ice. However, conclusions about trends in Arctic cloudiness are limited by large uncertainties in Arctic cloud data.

While there are indications of local changes in the occurrence of storm events and extreme temperatures in Alaska, systematic changes in strong storms and other extreme events have not been documented on a pan-Arctic basis. In view of the potential impacts of extreme events on the cryosphere as well as on human activities, research on changes in climate-related extreme events in the Arctic must be considered a priority.

The Arctic Ocean has experienced enhanced oceanic heat inflows from both the North Atlantic and the North Pacific. The Pacific inflows appear to have played a role in the retreat of sea ice in the Pacific sector of the Arctic Ocean. The association between sea ice and enhanced North Atlantic layer heat content is complicated by the strong halocline above the Atlantic layer, so the role of the Atlantic water heat anomalies is still under investigation. Nevertheless, the Atlantic water heat influx to the Arctic Ocean appears to be characterized by increasingly warm pulses separated by brief respites of cooling, as occurred in 2008/2009.

2.1. Introduction

The cryospheric changes described in this assessment report are part of a broader suite of interrelated variations in the Arctic climate system. A thorough review of Arctic climate, its relation to external forcing, and its variations through 2004 was presented in the Arctic Climate Impact Assessment report (ACIA, 2005: chapter 2). As a result, this report includes a brief overview of more recent Arctic climate variations, by describing Arctic climate variations during the post-ACIA period and by summarizing key observational studies of Arctic climate that have appeared since 2004. This chapter emphasizes the primary climate drivers (temperature, precipitation, storminess, clouds, ocean) of cryospheric change. Recent changes in the primary cryospheric variables (snow, sea ice, glaciers, permafrost) are presented in subsequent chapters. This chapter does not project recent variations into the future, as the main sources of such projections are the climate models discussed in Chapter 3.

2.2. Air temperatures

- In the period since the completion of the Arctic Climate Impact Assessment in 2004, the Arctic has experienced its highest surface air temperatures of the instrumental record, exceeding even the warmth of the 1930s and 1940s.
- Subject to the uncertainties inherent in proxy information, recent paleo-reconstructions show that Arctic summer temperatures have been higher in the past few decades than at any time in the past 2000 years.
- The spatial distribution of the recent warming points strongly to sea-ice reduction influencing warming, as the greatest temperature increase has occurred in the lower atmosphere over the marginal sea ice zone during autumn.
- A secondary maximum of warming during springtime is consistent with an earlier loss of terrestrial snow cover in recent years.

- The spatial pattern of the near-surface warming shows the signature of the Pacific Decadal Oscillation in the Pacific sector as well as the influence of a dipole-like circulation pattern in the Atlantic sector.

The Arctic Climate Impact Assessment (ACIA) reviewed Arctic climatic history from the pre-Quaternary through the Holocene (ACIA, 2005: section 2.7). Since the publication of the ACIA report, Arctic paleo-climate studies have refined temporal and regional variations of Arctic paleo-climate. A recent integrative study provided a reconstruction of pan-Arctic summer temperatures over the past 2000 years based on various proxies, including lake sediments, pollen records, diatoms, and tree rings (Kaufman et al., 2009). This reconstruction adds to the previous knowledge base by showing that the Arctic had been undergoing a slow (summer) cooling for most of the 2000-year period prior to the 1800s (Figure 2.1). This cooling is consistent with the slow variations of the Earth-Sun orbital parameters, which affect the solar radiation reaching the Arctic in the sunlit portion of the year. However, warming since the 1800s, as shown by the instrumental data (Figure 2.1), has left the Arctic warmer by a considerable margin than at any time in the preceding 2000 years. The recent instrumental temperatures are outside the envelope of the natural variability depicted by the reconstruction. For example, the warming is far more than simply a recovery from the so-called Little Ice Age, which is apparent from the 1500s through the 1800s (Figure 2.1). While the figure conveys a visually striking picture of recent Arctic warming, it should be noted that the data used by Kaufman et al. (2009) were biased towards Greenland, with very few sites in Siberia and no data from the polar ocean. Moreover, when uncertainties from the methods and the sparseness of the data are included, the recent decades of proxy data (Figure 2.1) are not significantly warmer than 2000 years ago. Finally, the locations of the proxy sites generally do not correspond with the instrumental data locations, thus contributing to the differences between the proxy and instrumental values in the mid-20th century.




Figure 2.1. Estimated Arctic average summer air temperature anomalies for the past 2000 years (relative to the 1961 to 1990 mean), based on proxy records from lake sediments, ice cores, and tree rings. The shaded area represents variability among the 23 sites used for the reconstruction. Source: Kaufman et al. (2009), modified by UCAR (University for Atmospheric Research).

The recent warming is highlighted in greater temporal detail in Figure 2.2, which shows the annual temperatures averaged over a pan-Arctic domain (60° to 90° N) through 2009. Consistent with the long-term reconstruction (see Figure 2.1) and with the Arctic temperature depictions presented in the ACIA report (ACIA, 2005), Figure 2.2 clearly shows the early 20th century warming, followed by the mid-century cooling and the late century warming. It is notable, however, that the warmest five years in the entire record have all occurred since 2004, i.e. in the post-ACIA period. Monte Carlo tests (1000 trials in which the data points in Figure 2.2 are randomly reordered) show that the likelihood of such a sequence occurring by random chance is close to zero. Including the past five years of temperature data in the temperature record takes the recent Arctic warming from a state of temperatures comparable to those of the 1930s to a state that is warmer than the 1930s. This is one of the more notable occurrences in Arctic climate for the post-ACIA period and is consistent with the reductions in snow cover, glacier mass and sea ice discussed in Chapters 4, 7, 8 and 9. Moreover, because the time series is based on land station observations only, it does not explicitly use temperature measurements from the ocean areas where sea ice has been lost over the past several years. The recent anomalies (see Figure 2.2) may therefore be conservative estimates of the pan-Arctic values during the seasons (summer and autumn) of greatest sea ice loss.

The recent Arctic warming varies with season and is stronger than the warming at mid- and lower latitudes (Figure 2.3). It is also stronger than the warming over Antarctica in all calendar months except August and September, when the warming near both poles is comparable. Of particular note is the seasonality of the Arctic warming, which is greatest over the Arctic Ocean during autumn and early winter. This seasonality is consistent with the recent loss of Arctic sea ice, and serves as an indication that the ice-albedo feedback has emerged as a contributor to temperature anomalies in the Arctic. A secondary maximum of Arctic warming propagating poleward from 50° to 60° N during spring is consistent with an earlier seasonal loss of snow cover over northern land areas. The seasonal variation of the warming is consistent with greenhouse-driven changes projected by global climate models (see Chapter 3).




Figure 2.2. Annual Arctic surface air temperature anomalies for 1880 to 2009 (relative to the 1961 to 1990 mean), averaged over the area between 60° and 90° N. Source: P. Groisman, NOAA/National Climate Data Center.




Figure 2.3. Monthly surface air temperature anomalies averaged over the period 2001 to 2009 (relative to the mean for 1951 to 2000) shown as a function of latitude. Source: NASA Goddard Institute for Space Studies (<http://data.giss.nasa.gov/gistemp/>).

The role of the ice-albedo feedback in the Arctic temperature record of the past five years is further supported by the spatial patterns in the annual and seasonal (Figure 2.4) temperature anomalies of the past five years relative to the mean temperatures for 1951 to 2000. The annual pattern contains anomalies exceeding 2 °C over much of the Arctic Ocean, and shows a clear polar amplification (Figure 2.4). It should be noted that reduced sea-ice concentrations and thicknesses, in addition to reduced sea-ice extent, can contribute to the feedback between sea ice and surface air temperature over the central Arctic Ocean. Equatorward of the Arctic Ocean, the warming is generally stronger over the continents than over the oceans. These spatial features are consistent with greenhouse-driven projections of change simulated by climate models (Chapter 3).

The seasonal air temperature patterns (Figure 2.4) highlight the maximum warming in autumn and winter, expanding on the patterns of warming by latitude and season shown in Figure 2.3. The seasonal patterns, especially for winter, contain more spatial variability than the annual pattern, consistent with advective influences arising from anomalies of the atmospheric circulation. The seasonal patterns in Figure 2.4 show two differences from the corresponding patterns depicted in the ACIA report (ACIA, 2005): a maximum warming over the marginal ice zone during autumn and winter, and some warming over the Arctic Ocean during summer – despite the large thermal capacity of the ocean. The summertime warming of the Arctic Ocean is consistent with thinner sea ice and/or an earlier retreat of sea ice during summer (see Chapter 9).

To some extent, these recent spatial patterns in temperature change (Figure 2.4) are shaped by the phase of the low-frequency (decadal or multi-decadal) variations in atmospheric circulation. Two large-scale modes for which there are documented effects on regional Arctic air temperatures are the Arctic Oscillation (AO), which drives temperature anomalies from eastern Canada across the North Atlantic to northern Eurasia (Thompson and Wallace, 2000), and the Pacific Decadal Oscillation (PDO), which has a strong influence on sub-Arctic temperatures in the Pacific sector (Mantua and Hare, 2002). The Arctic warming of the late 1980s and early 1990s has been

attributed by various researchers (e.g., Comiso, 2003; Overland et al., 2008) to a predominantly positive phase of the AO (Figure 2.5). And in fact, the warming of the 1980s to 1990s was indeed stronger over northern Eurasia than over many other sectors of the Arctic. In contrast, the more recent Arctic warming cannot be attributed to the AO. First, the AO index has been in a generally neutral state (oscillating between positive and negative phases) since 1997 – despite the Arctic’s warmest years

in the instrumental record having occurred since 2004 (see Figure 2.2). Second, the AO index reached the most negative values ever recorded in December 2009 to January 2010. At the same time, the High Arctic was relatively warm while northern Europe and Asia experienced a period of extreme cold. These concurrent anomalies of opposite sign point to the perils of using spatially aggregated temperature data as proxies for temperatures in particular sub-regions. For example, in the




Figure 2.4. Annual and seasonal surface air temperature anomalies averaged over the period 2005 to 2009 (relative to the mean for 1951 to 2000). Source: NASA Goddard Institute for Space Studies (<http://data.giss.nasa.gov/gistemp>).

AO index (standardized 3-month running mean)




Figure 2.5. AO index, plotted as a standardized 30-month running mean for the period 1950 to 2009. Source: NOAA/Climate Prediction Center.

context of the snow, water, ice, and permafrost in the Arctic, a seasonal or annual temperature anomaly averaged over the Arctic may differ even in sign from a local or regional anomaly most relevant to a particular glacier, ice sheet, lake, river basin, or sub-Arctic sea.

The PDO has been shown to be a primary determinant of wintertime temperature anomalies in northwestern North America (Hartmann and Wendler, 2005) and it is clear from Figure 2.6 that the PDO index (evaluated from Pacific sea-surface temperatures) does indeed exhibit multi-decadal variability. The increase from the mid-1970s to the early 1980s corresponds with a substantial increase in air temperature over Alaska and northwestern Canada. Whereas, the negative values of 2008 to 2009 coincide with an episode of below-normal air temperature in 2008 to 2009, although the PDO index became positive when averaged over the final six months of 2009. The influence of the PDO extends westward to far eastern Siberia, where temperature anomalies are out of phase with those of Alaska and the Yukon, largely as a result of the intensification cycles of the Aleutian Low pressure system in conjunction with the PDO. Indeed, the couplet of temperature anomalies of opposite sign in the winter pattern (see Figure 2.4) and in the multi-decadal trends (ACIA, 2005: section 2.6.2.1) are driven, to a large extent, by the PDO and associated wind anomalies in the vicinity of the Aleutian Low. A major challenge in anticipating temperature changes in the Pacific sub-Arctic is related to the inability to predict phase transitions of the PDO. However, it is notable (see concluding discussion in Section 2.7) that neither the PDO nor the AO has been in a phase conducive to Arctic warming during the past several years – despite the anomalous pan-Arctic warmth of these years (Figure 2.2).

The relatively high Arctic air temperatures of recent years have also been associated with atmospheric circulation patterns conducive to the export of older, thicker sea ice from the Arctic Ocean to the North Atlantic. Several post-ACIA studies have

pointed to the prominent role of similar circulation patterns, which have been assigned names ranging from the ‘Dipole Anomaly’ (Wu et al., 2006) to the ‘Arctic Rapid-Change Pattern’ (Zhang et al., 2008). These patterns are best developed in the winter half of the year but can affect sea-ice export in all seasons. In addition, they are argued to have preconditioned the Arctic sea-ice cover for the rapid summer retreat of the late 2000s (Smedsrud et al., 2008). Overland and Wang (2005) and Overland et al. (2008) highlighted the meridional (across-pole) character of this atmospheric pattern, which in addition to affecting sea-ice export, advects heat into the Arctic Ocean in a pattern distinct from the PDO and AO. More recently, Overland and Wang (2010) have presented evidence that the loss of sea ice has become sufficient to influence the atmospheric heat budget and circulation pattern in the autumn and early winter months. Francis et al. (2009) arrived at a similar conclusion based on a data analysis encompassing a larger sample of years.

A major topic of attention in the past few years has been the vertical structure of the recent Arctic warming, since the vertical structure provides clues as to the nature (drivers) of the warming. Graversen et al. (2008) argued that an elevated maximum of the warming precludes a major role of surface heating, although several subsequent studies (Bitz and Fu, 2008; Grant et al., 2008) have provided evidence of a surface-based warming. The apparent discrepancy between the different analyses is due to the use of different datasets (re-analyses) and time periods. While the warming is clearly strongest at the surface during autumn in the NCEP/NCAR re-analysis (Kalnay et al., 1996) (Figure 2.7), this near-surface warming is not apparent in the European ERA-40 database used by Graversen et al. (2008). Moreover, the data on which Figure 2.7 is based include the years of extreme ice minima that were not in the Graversen and co-workers study, giving credence to the argument that the ice-albedo feedback to Arctic temperatures is just now emerging in the post-ACIA period (Serreze et al., 2008).




Figure 2.6. Pacific Decadal Oscillation index, expressed in terms of monthly values and a five-month running mean (black line). Source: Joint Institute for the Study of the Atmosphere and Ocean, NOAA/University of Washington (<http://jisao.washington.edu/pdo>).

Finally, the studies of variation and trends in Arctic temperature have focused almost exclusively on monthly, seasonal, or annual mean temperatures. There has been little work on systematic changes in variability or extremes. Among the few studies of this kind, Walsh et al. (2005) found little evidence of increased variance in daily temperatures in Alaska and western Canada over the 50-year period ending in 2000. However, there were indications of an increased frequency of daily extreme temperatures from the 1950s to the 1990s. Whether this trend has continued into the past five years of record Arctic warmth (Figure 2.2) is unknown, but model projections indicate that increasing frequencies of record-high daily temperatures are characteristic of climate change driven by increasing greenhouse gas concentrations (Timlin and Walsh, 2007). Given the impacts of extreme events on humans, ecosystems, and other parts of the cryosphere, a priority for research is to determine the relationship between changes in means and extremes of Arctic climate variables.




Figure 2.7. Latitude-height cross-section of pan-Arctic autumn (October / November / December) temperature anomalies for 2003-2008 (relative to the 1858-96 base period). Source: J. Overland, NOAA; based on the National Centers for Environmental Prediction / National Center for Atmospheric Research (NCAR/NCEP) re-analysis.

2.3. Precipitation

- Although the trends are not statistically significant because interannual variability is large, recent annual pan-Arctic precipitation generally exceeds the mean of the 1950s by about 5%.
- The years since 2000 have been quite wet in the Arctic according to both precipitation and river discharge data. The five wettest years since 1950 have all occurred in the past decade.

Evidence for trends in Arctic precipitation is complicated by inadequacies both in *in situ* measurements and remote sensing-derived estimates of precipitation in cold climates. While these deficiencies were highlighted in the ACIA report (ACIA, 2005) and are discussed in Chapter 11, Section 11.5, it is necessary to reiterate the challenges created by changing station distributions and gauge undercatch of snow. Moreover, high-latitude precipitation gauges are sited preferentially in low-elevation areas. These factors impede attempts to construct temporally homogeneous records of spatially averaged precipitation. Partly for this reason, variations in Arctic precipitation have been examined using atmospheric re-analysis output, either as directly simulated by models (Serreze et al., 2005) or as moisture flux convergences (e.g., Peterson et al., 2006).

The most comprehensive collection of *in situ* precipitation data belongs to the Global Precipitation Climatology Center, which has produced Arctic precipitation time series such as that shown in Figure 2.8 for monthly precipitation averaged over the land areas north of 55° N. The data show a strong seasonal cycle (with larger amounts in the warm season) and considerable interannual variability. A polynomial fit to the data indicates a small increase of about 5% (from 35 mm to 37 mm) over the period 1951 to 2009. This is a modest increase in relation to the variability and is not statistically significant, pointing to the difficulty of extracting significant signals from highly variable precipitation data.

In terms of annual variations in precipitation over the period 1951 to 2009, the five wettest years (exceeding 450 mm) have all occurred in the most recent decade: 2000, 2002, 2005, 2007, and 2008 (Figure 2.9). Anomalies in both hydrological winter and hydrological summer have contributed to these large precipitation amounts in recent years. As noted in Chapter 3, global climate models project an increase in Arctic precipitation under all scenarios of greenhouse forcing. However, in the models as in the observational data, interannual variability is large, resulting in a smaller signal-to-noise ratio for precipitation than for surface air temperature.

The seasonal evolution of the annual precipitation anomalies over the past two decades illustrates the general wetness of the Arctic during the post-ACIA period (Figure 2.10). The summer precipitation anomalies contributed most to the cumulative annual anomalies in 2005 and 2007, although winter and spring provided the larger contributions in 2008. As previously noted, these years were not distinguished by large amplitudes of the AO index or PDO index, although the Arctic Rapid-Change Pattern was prominent from 2006 onward (Zhang et al., 2008). While the predominance of positive anomalies in precipitation amount is apparent, there are occasional years with small overall deficits in the past decade (e.g., 1999, 2003).




Figure 2.8. Monthly precipitation averaged over land areas north of 55° N for the period 1951 to 2009. The solid black line shows a least-squares polynomial fit. Source: Global Precipitation Climatology Center / World Meteorological Organization / Deutscher Wetterdienst (Courtesy of B. Rudolf).




Figure 2.9. Annual precipitation for the period 1951 to 2009 averaged over land areas north of 55° N for hydrological winter (October to March) and hydrological summer (April to September). Source: Global Precipitation Climatology Center / World Meteorological Organization / Deutscher Wetterdienst (Courtesy B. Rudolf).




Figure 2.10. Monthly-accumulated anomalies of precipitation for the period 1991 to 2009 (relative to the corresponding monthly means for 1951 to 2000) averaged over land areas north of 55° N. Source: Global Precipitation Climatology Center / World Meteorological Organization / Deutscher Wetterdienst (Courtesy of B. Rudolf).

The cumulative anomalies for most years retain the same sign through the full year, and the years with the largest positive anomalies tend to accumulate the greatest anomaly amounts during summer and autumn.


Finally, the increasing frequency of wet years at high northern latitudes is supported by increases in river discharge amounts (Figure 2.11). For Eurasia, the discharge of the largest rivers has increased by about 10% since 1935, despite the large interannual variations apparent. The rate of increase for North America is similar, although the record length of river discharge is shorter. The discharge curves for the two continents show a positive correlation, and their extreme years also show some correspondence with the annual precipitation amounts (see Figures 2.8 and 2.9). Since Arctic river discharge has direct ties to many of the cryospheric variables, it will be discussed further in subsequent chapters of this report.

2.4. Storminess

- Storm activity and the occurrence of temperature extremes have increased at some locations in the North American Arctic, but there are no indications of systematic increases in storminess in the Arctic over the past half century.

In addition to their highly publicized impacts on coastal regions and coastal residents, storms affect the cryosphere through their associated precipitation (affecting glaciers, ice sheets, snow cover, and even permafrost), winds (affecting sea ice motion and the distribution of snow on land and sea ice), and waves (affecting coastal permafrost). While storms have received increased diagnostic analyses through case studies (e.g., Roberts et al., 2008), there have been few rigorous evaluations of variations and trends in storminess in the Arctic, particularly the central Arctic. Wang et al. (2006) reported a northward shift of cyclone activity, primarily during winter, over Canada during 1953 to 2002, while Mesquita et al. (2010) found that temporal trends of cyclones in the North Pacific have generally been weak over the 60-year period ending in 2008, although the U.S. Global Change Research Program (Karl et al., 2009) points to an increase in storminess on the northern Alaskan coast and to associated risks of flooding and coastal erosion. Since any increases in coastal flooding and erosion are also

Figure 2.11. Total annual river discharge to the Arctic Ocean from the six largest rivers in the Eurasian Arctic for the observational period 1936 to 2007 (updated from Peterson et al., 2002) and from the five large North American pan-Arctic rivers for the period 1973 to 2006. The least squares linear trend lines are shown as dashed lines. Provisional estimates of annual discharge for the six major Eurasian Arctic rivers are based on near real time data (<http://RIMS.unh.edu>) are shown as red dots. Source: Richter-Menge and Overland (2009). Courtesy of A. Shiklomanov.



related to retreating sea ice, the role of storminess in itself can be difficult to unravel. Nevertheless, it is apparent from the absence of a comprehensive (pan-Arctic) evaluation of recent variations in storminess that there is a need for systematic assessments of storminess in the Arctic. Such an assessment should include historical variations and their diagnosis, as well as more substantive attempts to project changes into the future. The simulation of future changes in storminess is one of the major challenges facing coarse-resolution global models that are used in assessments such as those of the Intergovernmental Panel on Climate Change (Solomon et al., 2007).

2.5. Cloudiness

- While cloud data for the Arctic are difficult to interpret quantitatively, there are indications of increases in cloudiness over the Arctic, especially in low clouds during the warm season.

Through their large contributions to the surface energy budget, Arctic clouds can have important impacts on the surface energy budget and the cryosphere. These impacts can be manifest in interannual variations as well as trends. For example, Kay et al. (2008) showed that the extreme retreat of sea ice in the summer of 2007 was accompanied by unusually clear skies over much of the Arctic Ocean. Trends and other longer-term variations have been addressed in several post-ACIA studies, although the observational challenges posed by Arctic clouds must be recognized, both for remote sensing and for *in situ* measurements.

Wang and Key (2005) used high-resolution infrared (Advanced Very High Resolution Radiometer, AVHRR) satellite imagery to compute trends of -6% for winter, +3% for spring, +2% for summer, and -2% for autumn per decade during 1982 to 1999. Eastman and Warren (2010), on the other hand, used surface-based observations from 1991 to 2007 and obtained small positive trends in all seasons. Low clouds were primarily responsible for these trends. Perhaps more importantly for cryospheric changes, clouds over sea ice showed a tendency

to increase with increasing air temperature and decreasing sea ice in all seasons except summer. Particularly in autumn, there was an increase in low clouds consistent with reduced sea ice, indicating that recent cloud changes may be enhancing the warming of the Arctic and accelerating the decline of sea ice (Eastman and Warren, 2010). This suggestion is consistent with the recent model-based results of Vavrus et al. (2010), who found that, in ensembles of 21st century projections by the Community Climate System Model (CCSM3), clouds increased in autumn and decreased in summer during periods of rapid sea ice loss. This seasonality of the sea ice / cloud associations is not inconsistent with the loss of sea ice in recent years such as 2007, and could amplify the loss of sea ice in the future.

2.6. Ocean variations

- The Arctic Ocean has experienced enhanced oceanic heat inflows from both the North Atlantic and the North Pacific. The Pacific inflows appear to have played a role in the retreat of sea ice in the Pacific sector of the Arctic Ocean.
- North Atlantic inflows to the Arctic Ocean appear to be characterized by increasingly warm pulses of water. One such pulse moved along the Siberian shelf break in the mid-2000s, while the next pulse is now poised to enter the Arctic Ocean through Fram Strait.

A key driver of cryospheric change is the variability of the high-latitude oceans. For example, the heat content of the polar oceans directly affects sea ice, tidewater glaciers and ice shelves, snowfall over the high latitudes, and perhaps even the large-scale atmospheric circulation. Salinity variations affect the stratification and control the locations of deep mixing of the oceans, while high-latitude ocean currents contribute to the driving of sea-ice motion and the advection of heat and freshwater anomalies. Historically, the high-latitude oceans have been woefully undersampled by observations, especially below the surface. However, during the past decade, and especially in the post-ACIA period of the International Polar Year (IPY),




Figure 2.12. Major surface ocean currents and water transport in the Arctic. Cross-sections of temperature in the upper layers of the Arctic Ocean are also shown. Source of temperature cross sections: I. Polyakov, International Arctic Research Center.

2007/2008, there have been unprecedented opportunities to monitor the Arctic Ocean and its exchanges with the mid-latitudes – precisely during a period of unprecedented change in various components of the cryosphere.

Insights into high-latitude ocean variability, as gleaned from preliminary analyses of IPY-period observational data, have been summarized by Dickson and Farbach (2010). Following are brief summaries of those insights that have potential implications for cryospheric variations documented elsewhere in this report. First, the annual mean northward transport through the Bering Strait in 2007 was comparable (about 1 Sv) to the previous highest annual value; together with positive anomalies of heat content, it appears that the Bering Strait heat flux in 2007 was also at a record-length high (Dickson and Farbach, 2010: p. 5). In recent years, a more immediate driver of sea-ice melt appears to be associated with a near-surface temperature maximum (NSTM) at a depth of ~25 m in Canada Basin, where the NSTM may serve to maintain thinner ice during winter, an earlier melt during spring, and hence year-to-year persistence of ice anomalies (Jackson et al., 2010). The somewhat deeper (~60 m) layer of Pacific Summer Water may also have played a role in the summer ice retreat. Thinner ice in this region could also favor the wind-stress and ice-loss feedback mechanism proposed by Shimada et al. (2006). Second, North Atlantic inflows appear to be increasingly consequential for the Arctic Ocean. North Atlantic inflows to the Arctic through the Barents Sea appear to have reached their highest temperatures in 100 years (Holliday et al., 2007). In addition, mooring measurements from the Arctic

Ocean indicate the propagation of increasingly warm water in a cyclonic direction around the Arctic Ocean shelf break (Figure 2.12), consistent with the mean pattern of Arctic Ocean currents. While the Atlantic layer containing this anomalous heat is subducted several hundred metres below the surface as it circulates through the Arctic Ocean, the role of its anomalous heat in the sea-ice retreat and other cryospheric variations has not been firmly established. The Atlantic water heat influx to the Arctic Ocean appears to be characterized by increasingly warm pulses separated by brief respites (Polyakov et al., 2010). As shown in Figure 2.12, one such respite of cooling appears to have occurred in 2008/2009, although the Fram Strait cross-sections show that the next pulse of warming may now be poised to enter the Arctic Ocean. Finally, IPY measurements in various straits of northern Canada have confirmed the importance of the Canadian Archipelago for the freshwater flux from the Arctic Ocean to the North Atlantic, providing significant inputs to the Atlantic Meridional Overturning Circulation and thus to climate (Dickson and Farbach, 2010). The nature of the linkage between Arctic Ocean outflows and climate remains a holy grail of Arctic research.

2.7. Conclusions

This review of recent Arctic climate variations, with an emphasis on air temperature and precipitation, serves two purposes. First, it shows that variations in Arctic surface air temperature and precipitation are key drivers of recent Arctic cryospheric change. Taken together with the cryospheric changes presented

Box 2.1. Are changes in the Arctic affecting mid-latitude weather?

A recent Arctic influence on mid-latitude weather was the emergence of strong meridional atmospheric circulation in winter 2009/10 and the beginning of winter 2010/11, which allowed cold air to advect southward into eastern North America and Asia, and northern Europe (Cattiaux et al., 2010; L'Heureux et al., 2010; Seager et al., 2010). Cold air is normally trapped within the Arctic in winter by strong Polar Vortex winds, which circle the North Pole consistent with the low geopotential height field over the central Arctic (shown in purple in Figure 2.13a). This pattern broke down in December 2009 (Figure 2.13b); the Polar Vortex winds, normally blowing from west to east, weakened as shown by the increased geopotential height field (greens) over the central Arctic, and north-south winds increased allowing cold Arctic air to spill southward. This created the Warm Arctic-Cold Continent Climate Pattern, shown in Figure 2.14 for December 2009. December 2010 had a similar pattern. Higher than normal Arctic temperatures (red) were seen especially in

regions that were sea-ice-free in summer: north of Alaska and in the Barents Sea. The cold continents (purple) are seen where Arctic air penetrated southward. One indicator of a weak Polar Vortex is the North Atlantic Oscillation (NAO) index. Winter 2009/10 had the lowest NAO value in 145 years of historical record (www.cgd.ucar.edu/cas/jhurrell/indices.html).

Attribution for these cold mid-latitude winters is nearly impossible given the chaotic nature of atmospheric circulation. But given the extreme atmospheric circulation in back-to-back years and the recent changes in the Arctic, a possible weak Arctic-sub-Arctic linkage cannot be ruled out. Warmer Arctic air in autumn is less dense and increases the geopotential thickness between constant pressure surfaces, thus working against the stability of the Polar Vortex (Schweiger et al., 2008; Serreze et al., 2008; Overland and Wang, 2010). Models results also suggest Arctic-sub-Arctic teleconnections (Singarayer et al., 2006; Sokolova et al., 2007; Seierstad and Bader, 2008; Budikova, 2009; Deser et al., 2010; Kumar et al., 2010; Petoukhov and Semenov, 2010). Increased sub-Arctic weather variability seems a possibility as increasing amounts of sea ice are lost as the mid-century approaches.




Figure 2.13. Arctic atmospheric pressure fields: (a) average 850 mb geopotential height values for December from 1981 to 2010, (b) with unusual 850 mb geopotential height maximums observed over the Arctic in December 2009. Figures from NOAA/ESRL Physical Sciences Division.




Figure 2.14. The Warm Arctic-Cold Continents Climate Pattern for (a) December 2009 and (b) December 2010. Plots show anomalies or deviations from the normal 1000 mb air temperature values which were observed from 1981 to 2010. Data are from the NCEP-NCAR Reanalysis through the NOAA/ESRL Physical Sciences Division.

in later chapters of this report, a picture emerges of changes that are generally consistent across the Arctic system. Second, it shows that the Arctic is exhibiting markedly different behavior now than earlier in the instrumental period and, in the case of summer surface air temperatures, relative to 2000-year reconstructions of past variations. The available data do not permit determinations of whether other variables or seasons have experienced recent excursions outside their 2000-year range of variability. Nevertheless, the unprecedented warmth of the past five years reinforces the urgency of an assessment of cryospheric changes in the North. From a general climate perspective, the results point to the emergence of the ice-albedo-temperature feedback in the seasonal and spatial patterns of the recent surface air temperature anomalies in the Arctic. This is perhaps the most fundamentally important development in high-latitude climate since the Arctic Climate Impact Assessment in 2004 (ACIA, 2005). Given the absence of strong anomalies in large-scale circulation drivers such as the AO and the PDO in the past five years, the recent events support the changes that were anticipated in the ACIA report (ACIA, 2005) and echo the statement of Serreze and Francis (2006: p. 241) that “*Given the general consistency with model projections, we are likely near the threshold when absorption of solar radiation during summer limits ice growth the following autumn and winter, initiating a feedback leading to a substantial increase in Arctic Ocean surface air temperatures*”. The cryospheric and atmospheric changes of the past five years indicate that this threshold may well have been crossed.

The recent occurrence of an Arctic influence on mid-latitude weather is reported in Box 2.1.

The results presented in this chapter also point to various observational needs. These are discussed in more detail in Chapter 11, Section 11.5. Specifically, the precipitation estimates summarized in Section 2.3 are, by necessity, for Arctic land areas only. There are no systematically compiled sources of precipitation over the Arctic Ocean and its marginal seas, although it should be noted that Peterson et al. (2006) deduced recent increases in precipitation over the sub-Arctic North Atlantic based on computed moisture flux convergences in atmospheric re-analyses. Moreover, as described in Chapter 11, Section 11.5, the station-derived estimates of precipitation for land areas in the Arctic have uncertainties arising from measurement errors (e.g., gauge undercatch of snow, for which only approximate correction procedures exist) and from the preferential siting of precipitation gauges in low-elevation areas. Temperatures over the Arctic Ocean are also subject to uncertainties, as the estimates of surface air temperatures over ice-covered seas are generally based on extrapolation of temperature anomalies from nearby land areas. Satellite-derived estimates of Arctic surface (skin) temperatures are generally biased toward cloud-free conditions. As atmospheric re-analyses for high-latitude regions are improved (e.g., Bromwich et al., 2010), estimates of pan-Arctic temperature as well as precipitation will become more robust.

References

- ACIA (Ed.), 2005. Arctic Climate Impact Assessment. 1042 pp. Cambridge University Press.
- Bitz, C.M. and Q. Fu, 2008. Arctic warming aloft is data set dependent. *Nature*, 455:E3–E4.
- Bromwich, D.H., Y.-H. Kuo, M. Serreze, J.E. Walsh, L.-H. Bai, M. Barlage, K. Hines and A. Slater, 2010. Arctic system reanalysis: Call for community involvement. *EOS Transactions AGU*, 91:13–14.
- Budikova, D., 2009. Role of Arctic sea ice in global atmospheric circulation: A review. *Global and Planetary Change*, 68:149–163.
- Cattiaux, J., R. Vautard, C. Cassou, P. Yiou, V. Masson-Delmotte and F. Codron, 2010. Winter 2010 in Europe: A cold extreme in a warming climate. *Geophysical Research Letters*, 37:L20704.
- Comiso, J.C., 2003. Warming trends in the Arctic from clear sky satellite observations. *Journal of Climate*, 16:3498–3510.
- Deser, C., R. Tomas, M. Alexander and D. Lawrence, 2010. The seasonal atmospheric response to projected Arctic sea ice loss in the late 21st century. *Journal of Climate*, 23:333–351.
- Dickson, R.R. and E. Fahrbach, 2010. Observing our northern Seas during the IPY. Report of the Arctic Ocean Sciences Board and of the IPY Joint Committee. 34 pp.
- Eastman, R. and S.G. Warren, 2010. Interannual variations of Arctic cloud types in relation to sea ice. *Journal of Climate*, 23:4216–4232.
- Francis, J.A., W.H. Chan, D.J. Leathers, J.R. Miller and D.E. Veron, 2009. Winter Northern Hemisphere weather patterns remember summer Arctic sea-ice extent. *Geophysical Research Letters*, 36:L07503.
- Grant, A.N., S. Bronnimann and L. Haimberger, 2008. Recent Arctic warming vertical structure contested. *Nature*, 455:E2–E3.
- Graversen, R.G., T. Mauritsen, M. Tjernstrom, E. Kallen and G. Svensson, 2008. Vertical structure of recent Arctic warming. *Nature*, 451:53–54.
- Hartmann, B. and G. Wendler, 2005. The significance of the 1976 Pacific climate shift in the climatology of Alaska. *Journal of Climate*, 18:4824–4839.
- Holliday, N.P., S.L. Hughes, A. Lavin, K.A. Mork, G. Nolan, W. Walkowski and A. Bresczynska-Moller, 2007. The end of a trend? The progression of unusually warm and saline water from the eastern North Atlantic into the Arctic Ocean. *CLIVAR Exchanges*, 12:19–20.
- Jackson, J.M., E.C. Carmack, F.A. McLaughlin, S.E. Allen and R.G. Ingram, 2010. Identification, characterization, and change of the near-surface temperature maximum in the Canada Basin, 1993–2008. *Journal of Geophysical Research-Oceans*, 115:C05021.
- Kalnay, E., M. Kanamitsu, R. Kistler, W. Collins, D. Deaven, L. Gandin, M. Iredell, S. Saha, G. White, J. Woollen, Y. Zui, M. Chelliah, W. Ebisuzakip, W. Higgins, J. Janowiak, K.C. Mo, C. Ropelewski, J. Wang, A. Leetma, R. Reynolds, R. Jenne and D. Joseph, 1996. The NCEP/NCAR 40-Year Reanalysis Project. *Bulletin of the American Meteorological Society*, 77:437–471.
- Karl, T.R., J.M. Melillo and T.C. Peterson, 2009. Global Climate Change Impacts in the United States. Unified Synthesis Product. Report by the U.S. Climate Change Science Program and the Subcommittee on Global Change Research, pp. 288, Cambridge University Press.
- Kaufman, D.S., D.P. Schneider, N.P. McKay, C.M. Ammann, R.S. Bradley, K.R. Briffa, G.H. Miller, B.L. Otto-Bliesner, J.T. Overpeck, B.M. Vinther and M. Arctic Lakes 2k Project, 2009. Recent warming reverses long-term Arctic cooling. *Science*, 325:1236–1239.
- Kay, J.E., T. L'Ecuyer, A. Gettelman, G. Stephens and C. O'Dell, 2008. The contribution of cloud and radiation anomalies to the 2007 Arctic sea ice extent minimum. *Geophysical Research Letters*, 35:L08503.
- Kumar, A., J. Perlwitz, J. Eischeid, X. Quan, T. Xu, T. Zhang, M. Hoerling, B. Jha and W. Wang, 2010. Contribution of sea ice loss to Arctic amplification. *Geophysical Research Letters*, 37:L21701.
- L'Heureux, M., A. Butler, B. Jha, A. Kumar and W. Wang, 2010. Unusual extremes in the negative phase of the Arctic Oscillation during 2009. *Geophysical Research Letters*, 37:L10704.
- Mantua, N.J. and S.R. Hare, 2002. The Pacific decadal oscillation. *Journal of Oceanography*, 58:35–44.
- Mesquita, M.D.S., D.E. Atkinson and K.I. Hodges, 2010. Characteristics and variability of storm tracks in the North Pacific, Bering Sea, and Alaska. *Journal of Climate*, 23:294–311.
- Overland, J.E. and M.Y. Wang, 2005. The third Arctic climate pattern: 1930s and early 2000s. *Geophysical Research Letters*, 32:L23808.

- Overland, J.E. and M.Y. Wang, 2010. Large-scale atmospheric circulation changes are associated with the recent loss of Arctic sea ice. *Tellus Series A*, 62:1-9.
- Overland, J.E., M. Wang and S. Salo, 2008. The recent Arctic warm period. *Tellus Series A*, 60:589-597.
- Peterson, B.J., R.M. Holmes, J.W. McClelland, C.J. Vorosmarty, R.B. Lammers, A.I. Shiklomanov, I.A. Shiklomanov and S. Rahmstorf, 2002. Increasing river discharge to the Arctic Ocean. *Science*, 298:2171-2173.
- Peterson, B.J., J. McClelland, R. Curry, R.M. Holmes, J.E. Walsh and K. Aagaard, 2006. Trajectory shifts in the Arctic and subarctic freshwater cycle. *Science*, 313:1061-1066.
- Petoukhov, V. and V.A. Semenov, 2010. A link between reduced Barents-Kara sea ice and cold winter extremes over northern continents. *Journal of Geophysical Research*, 115:D21111.
- Polyakov, I.V., V.A. Alexeev, U.S. Bhatt, E.I. Polyakova and X.D. Zhang, 2010. North Atlantic warming: patterns of long-term trend and multidecadal variability. *Climate Dynamics*, 34:439-457.
- Richter-Menge, J. and J.E. Overland (Eds.), 2009. *Arctic Report Card 2009*. 103 pp. NOAA.
- Roberts, E., N. Nawri and R.E. Stewart, 2008. On the storms passing over southern Baffin Island during autumn 2005. *Arctic*, 61:309-321.
- Schweiger, A.J., R.W. Lindsay, S. Vavrus and J.A. Francis, 2008. Relationships between Arctic sea ice and clouds during autumn. *Journal of Climate*, 21:4799-4810.
- Seager, R., Y. Kushnir, J. Nakamura, M. Ting and N. Naik, 2010. Northern Hemisphere winter snow anomalies: ENSO, NAO and the winter of 2009/10. *Geophysical Research Letters*, 37:L14703.
- Seierstad, I.A. and J. Bader, 2008. Impact of a projected future Arctic sea ice reduction on extratropical storminess and the NAO. *Climate Dynamics*, 33:937-943.
- Serreze, M.C. and J.A. Francis, 2006. The Arctic amplification debate. *Climatic Change*, 76:241-264.
- Serreze, M.C., A.P. Barrett and F. Lo, 2005. Northern high-latitude precipitation as depicted by atmospheric reanalyses and satellite retrievals. *Monthly Weather Review*, 133:3407-3430.
- Serreze, M.C., A.P. Barrett, J.C. Stroeve, D.N. Kindig and M.M. Holland, 2008. The emergence of surface-based Arctic amplification. *The Cryosphere Discussions*, 2:601-622.
- Shimada, K., T. Kamoshida, M. Itoh, S. Nishino, E. Carmack, F. McLaughlin, S. Zimmermann and A. Proshutinsky, 2006. Pacific Ocean inflow: Influence on catastrophic reduction of sea ice cover in the Arctic Ocean. *Geophysical Research Letters*, 33:L08605.
- Singarayer, J.S., J.L. Bamber and P.J. Valdes, 2006. Twenty-first-century climate impacts from a declining Arctic sea ice cover. *Journal of Climate Dynamics*, 19:1109-1125.
- Smedsrud, L.H., A. Sorteberg and K. Kloster, 2008. Recent and future changes of the Arctic sea-ice cover. *Geophysical Research Letters*, 35:L20503.
- Sokolova, E., K. Dethloff, A. Rinke and A. Benkel, 2007. Planetary and synoptic scale adjustment of the Arctic atmosphere to sea ice cover changes. *Geophysical Research Letters*, 34:L17816.
- Solomon, S., D. Qin, M. Manning, Z. Chen, M. Marquis, K.B. Averyt, M. Tignor and H.L. Miller (Eds.), 2007. *Climate Change 2007: The Physical Science Basis. Contribution of Working Group I to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change*. 996 pp. Cambridge University Press.
- Thompson, D.W.J. and J.M. Wallace, 2000. Annular modes in the extratropical circulation. Part I: Month-to-month variability. *Journal of Climate*, 13:1000-1016.
- Timlin, M.S. and J.E. Walsh, 2007. Historical and projected distributions of daily temperature and pressure in the Arctic. *Arctic*, 60:389-400.
- Vavrus, S., M.M. Holland and D.A. Bailey, 2010. Changes in Arctic clouds during intervals of rapid sea ice loss. *Climate Dynamics*, 36:1475-1489.
- Walsh, J.E., I. Shapiro and T.L. Shy, 2005. On the variability and predictability of daily temperatures in the Arctic. *Atmosphere-Ocean*, 43:213-230.
- Wang, X.J. and J.R. Key, 2005. Arctic surface, cloud, and radiation properties based on the AVHRR Polar Pathfinder dataset. Part II: Recent trends. *Journal of Climate*, 18:2575-2593.
- Wang, X.L., H. Wan and V.R. Swail, 2006. Observed changes in cyclone activity in Canada and their relationships to major circulation regimes. *Journal of Climate*, 19:896-915.
- Wu, B.Y., J. Wang and J.E. Walsh, 2006. Dipole anomaly in the winter Arctic atmosphere and its association with sea ice motion. *Journal of Climate*, 19:210-225.
- Zhang, X.D., A. Sorteberg, J. Zhang, R. Gerdes and J.C. Comiso, 2008. Recent radical shifts of atmospheric circulations and rapid changes in Arctic climate system. *Geophysical Research Letters*, 35:L22701.

3. Climate Model Projections for the Arctic

AUTHORS: JAMES E. OVERLAND, MUYIN WANG, JOHN E. WALSH, JENS H. CHRISTENSEN, VLADIMIR M. KATTSOV, WILLIAM L. CHAPMAN

Contents

Key Findings	2
Summary	2
3.1. Introduction	2
3.2. Projections of Arctic climate and key drivers of Arctic cryospheric change	3
3.3. Climate projection uncertainties	8
3.4. Treatment of sea ice, snow, permafrost, glaciers, and ice sheets in climate models	9
3.5. Key considerations in model selection	10
3.5.1. Choices for evaluating hindcast skill	10
3.6. Meta-analysis	13
3.7. Two regional examples	13
3.7.1. Alaska	13
3.7.2. Sea ice simulation for the Barents and Bering Seas	13
3.8. Downscaling techniques	15
3.9. Conclusions	15
Acknowledgments	16
References	16

Key Findings

- Most of the information on future changes in the Arctic is based on atmosphere-ice-ocean general circulation models from 18 climate modeling centers that formed part of the Intergovernmental Panel on Climate Change Fourth Assessment in 2007.
- No single model can be considered ‘best’ because results differ depending on the variable of interest (temperature, sea ice, sea-level pressure), location, and verification method, in apparently unsystematic ways.
- While details depend on location, time of year, model, and assumed future increases in greenhouse gas emissions, the consensus suggests a general increase in Arctic-wide autumn and winter surface air temperatures of 3 to 6 °C by 2080, a nearly sea-ice free September by 2050, and a general increase in precipitation over future decades.
- Owing to the random influence of natural variability, the single future trajectory that we will live through will differ somewhat from the smooth average of all possible future trajectories from the general circulation models. For example, the observed sea-ice loss in summer 2007 was greater than most trajectories projected by the general circulation models.

Summary

Projections of future changes in the cryosphere are dependent on interpretation of results from multiple climate model forecasts at regional scales. In setting the stage for discussing the various physical and biological components of the SWIPA project, this chapter surveys the major causes of the range of results provided by multiple atmosphere-ice-ocean general circulation models and recommends a methodology for summarizing the available projections in practical applications such as this assessment. Strategies are assessed for reducing the uncertainties from multiple model projections while acknowledging that multiple model simulation results (termed ‘ensemble members’) must be retained because forecasts should include a range of results caused by natural variability present in the real world and represented in the climate models. Results from international modeling centers form an ‘ensemble of opportunity’ from which composite projections can be made. However, experience suggests that these models need to be subjected to a selection methodology and independent interpretation.

Interpretation of results from 18 international modeling centers developed for the Fourth Assessment of the Intergovernmental Panel on Climate Change, suggests an increase in Arctic-wide autumn and winter surface air temperatures of 3 to 6 °C by 2080, a nearly sea-ice free September by 2050, and a general increase in precipitation. Loss of sea ice and increased temperatures are a coupled process with the greatest temperature increases seen in the autumn. The Arctic shows the largest future temperature changes on the planet.

Considerations that guide in the initial screening of a set of models are model resolution, comprehensiveness of processes included in the model, and sophistication of the parameterizations. A main procedure for selecting a subset of the models is based on comparison to observations during the model hindcast period. The quality of individual model performance varies for different regions, variables, and evaluation metrics. For this reason, the use of a single model forecast is not recommended. The coarse resolution of most current climate models dictates caution in their application on smaller scales in heterogeneous regions such as along coastlines or in locations with rugged orography.

3.1. Introduction

Much of the information on future change in the Arctic contained in this assessment report is based on comprehensive atmosphere-ice-ocean general circulation models (GCMs) from 18 international climate modeling centers that were developed for the Intergovernmental Panel on Climate Change (IPCC) Fourth Assessment Report (AR4) in 2007. As results from these models can vary, it is important to assess the robustness of the information provided by these models. The strategy for using these projections of change is an emerging research focus that has a direct bearing on the credibility of the future trajectories of cryospheric components. Accordingly, this chapter provides a review of climate model treatments of the Arctic, an assessment of their performance in the Arctic, and an overview of the key considerations that guide the use

of these models in assessments of the likely impacts of future climate change.

The IPCC used projections from about two dozen GCMs developed by 18 international modeling centers in AR4 (Solomon et al., 2007). Table 3.1 lists the models and their resolution. A major feature of AR4 was that the detailed numerical information from these projections was made available to the wider scientific community for independent review; the projections and corresponding 20th century hindcasts are now archived as part of the Climate Model Intercomparison Project (CMIP3) by the Program for Climate Model Diagnosis and Intercomparison (PCMDI; www.pcmdi.llnl.gov). The model results have been evaluated independently by the authors of this chapter in addition to many other groups. While much of the earlier work emphasized global- and hemispheric-scale changes, governments, management agencies, and other stakeholders need regional predictions of possible future climate states in order to assess and plan for possible ecological and societal impacts and necessary adaptation actions. This chapter focuses on two central questions: how dependable are these model projections at regional scales and what is the limit of their utility?

There are several arguments for suggesting that these models can provide reliable projections. Models are built on well-known physical principles, and many large-scale aspects of present-day climate are simulated quite well by these models (Randall et al., 2007; Knutti, 2008). Furthermore, biases in simulated climate by different models tend to be unsystematic (Raisanen, 2007), although there is some covariability of errors (Jun et al., 2008) and this statement is not valid for sea ice (Wang and Overland, 2009). While it might be thought that there would be considerable convergence between different models in their simulation results for the 20th century and projections for the 21st century, given that they are trying to simulate responses to similar forcing, there is in fact considerable variability in the ability of models to hindcast climate patterns based on location, variable of interest, and evaluation metrics (e.g., means, variance, trends), with some models performing well according to some criteria but not to others. Thus, the question of model reliability has no simple quantitative answer; there is no one best model (Gleckler et al., 2008). Contributing to these differences are model structure, physical parameterizations, and all the reasonable choices made during model development. The impact of natural variability, producing a range of results for similar model runs, is another challenge in comparing models with each other and with observational data. While practitioners are aware of many of these deficiencies, there is nonetheless a need to understand and make the best possible use of the output of existing models while improved models are being developed.


3.2. Projections of Arctic climate and key drivers of Arctic cryospheric change

Global climate models project that the Arctic will warm at a greater rate over the coming decades and century compared with other regions of the globe (Serreze and Francis, 2006; Overland, 2009). Subsequent chapters of this assessment report make use of 21st century projections of specific cryospheric variables (snow, sea ice, permafrost). While many factors contribute to changes over this time frame, atmospheric temperature and precipitation are among the key drivers that

affect all cryospheric variables. Therefore, for these fields this chapter updates the Arctic Climate Impact Assessment (ACIA) projections of change on a seasonal basis. The update is based on the CMIP3 model simulations discussed in the existing literature.

While all models have biases, many of the biases tend to offset when the models' simulations are aggregated or composited. An important question is: how well do composites of the model simulations capture recent trends? This question can be answered by compositing the CMIP3 model simulations of the past half century and comparing the simulated trends with the observed trends, omitting the FGOALS and GISS-ER models (see Table 3.1) on the basis described in the following sections. Figure 3.1 shows the simulated change of annual mean Arctic temperature for 1957 to 2006, together with the temperature change from the National Centers for Environmental Prediction and National Center for Atmospheric Research (NCEP/NCAR)

a. Observed



b. IPCC models





Figure 3.1. Changes in annual mean temperature over the 50-year period, 1957 to 2006, as (a) observed (NCEP/NCAR re-analysis) and (b) simulated; 'b' is a composite of fourteen IPCC model simulations in AR4 (Solomon et al., 2007). See Walsh et al. (2008) for model selection.

Table 3.1. Selected model features. Salient features of the participating AR4 coupled models are listed by IPCC ID along with the calendar year of origin ('vintage'). Also listed are the respective sponsoring institutions, the horizontal and vertical resolution of the model atmosphere and ocean, the pressure of the atmospheric top, as well as the oceanic vertical coordinate (depth or density), and upper boundary condition (free surface or rigid lid). The three right-most columns list the characteristics of sea-ice dynamics and structure (e.g., rheology vs. 'free drift' assumption and inclusion of ice leads), and whether adjustments of surface momentum, heat, or freshwater fluxes are applied in coupling the atmosphere, ocean, and sea ice components. Land features such as the representation of soil moisture (single-layer 'bucket' vs. multi-layered scheme) and the presence of a vegetation canopy or a river routing scheme also are noted. Relevant references describing details of the sea-ice and land surface formulations also are cited. Source: Randall et al. (2007).

Model ID, Vintage	Sponsor(s), Country	Atmosphere	Ocean	Sea ice	Coupling	Land
		Top resolution	Resolution Z Coord., Top BC	Dynamics, Leads (Sources)	Flux adjustments	Soil, Plants, Routing (Sources)
1: BCC-CM1, 2005	Beijing Climate Center, China	top = 25 hPa T63 (1.9° × 1.9°) L16	1.9° × 1.9° L30 depth, free surface	no rheology or leads	heat, momentum	layers, canopy, routing
2: BCCR-BCM2.0, 2005	Bjerknes Centre for Climate Research, Norway	top = 10 hPa T63 (1.9° × 1.9°) L31	0.5 – 1.5° × 1.5° L35 density, free surface	rheology, leads (Hibler, 1979; Harder, 1996)	no adjustments	layers, canopy, routing (Mahfouf et al., 1995; Douville et al., 1995; Oki and Sud, 1998)
3: CCSM3, 2005	National Center for Atmospheric Research, USA	top = 2.2 hPa T85 (1.4° × 1.4°) L26	0.3 – 1° × 1° L40 depth, free surface	rheology, leads (Briegleb et al., 2004)	no adjustments	layers, canopy, routing (Oleson et al., 2004)
4: CGCM3.1(T47), 2005	Canadian Centre for Climate Modeling and Analysis, Canada	top = 1 hPa T47 (~2.8° × 2.8°) L31	1.9° × 1.9° L29 depth, rigid lid	rheology, leads (Hibler, 1979; Flato and Hibler, 1992)	heat, freshwater	layers, canopy, routing (Verseghe et al., 1993)
5: CGCM3.1(T63), 2005	Canadian Centre for Climate Modeling and Analysis, Canada	top = 1 hPa T63 (~1.9° × 1.9°) L31	0.9° × 1.4° L29 depth, rigid lid	rheology, leads (Hibler, 1979; Flato and Hibler, 1992)	heat, freshwater	layers, canopy, routing (Verseghe et al., 1993)
6: CNRM-CM3, 2004	Météo-France, Centre National de Recherches Météorologiques, France	top = 0.05 hPa T63 (~1.9° × 1.9°) L45	0.5 – 2° × 2° L31 depth, rigid lid	rheology, leads (Hunke and Dukowicz, 1997; Méliá, 2002)	no adjustments	layers, canopy, routing (Mahfouf et al., 1995; Douville et al., 1995; Oki and Sud, 1998)
7: CSIRO-MK3.0, 2001	CSIRO Atmospheric Research, Australia	top = 4.5 hPa T63 (~1.9° × 1.9°) L18	0.8° × 1.9° L31 depth, rigid lid	rheology, leads (O'Farrell, 1998)	no adjustments	layers, canopy (Gordon et al., 2002)
8: ECHAM5/MPI-OM, 2005	Max Planck Institute for Meteorology, Germany	top = 10 hPa T63 (~1.9° × 1.9°) L31	1.5° × 1.5° L40 depth, free surface	rheology, leads (Hibler, 1979; Semtner, 1976)	no adjustments	bucket, canopy, routing (Hagemann, 2002; Hagemann and Gates, 2001)
9: ECHO-G, 1999	Meteorological Institute of the University of Bonn, Meteorological Research Institute of KMA, and Model & Data Group, Germany/Korea	top = 10 hPa T30 (~3.9° × 3.9°) L19	0.5 – 2.8° × 2.8° L20 depth, free surface	rheology, leads (Wolff et al., 1997)	heat, freshwater	bucket, canopy, routing (Roeckner et al., 1996; Dümenil and Todini, 1992)
10: FGOALS-g1.0, 2004	LASG/Institute of Atmospheric Physics, China	top = 2.2 hPa T42 (~2.8° × 2.8°) L26	1.0° × 1.0° L16 eta, free surface	rheology, leads (Briegleb et al., 2004)	no adjustments	layers, canopy, routing
11: GFDL-CM2.0, 2005	U.S. Dept. of Commerce, NOAA, Geophysical Fluid Dynamics Laboratory, USA	top = 3 hPa 2.0° × 2.5° L24	0.3 – 1.0° × 1.0° depth, free surface	rheology, leads (Winton, 2000; Delworth et al., 2006)	no adjustments	bucket, canopy, routing (Milly and Shmakin, 2002; GFDL GAMDT, 2004)
12: GFDL-CM2.1, 2005	U.S. Dept. of Commerce, NOAA, Geophysical Fluid Dynamics Laboratory, USA	top = 3 hPa 2.0° × 2.5° L24	0.3 – 1.0° × 1.0° depth, free surface	rheology, leads (Winton, 2000; Delworth et al., 2006)	no adjustments	bucket, canopy, routing (Milly and Shmakin, 2002; GFDL GAMDT, 2004)

Model ID, Vintage	Sponsor(s), Country	Atmosphere	Ocean	Sea ice	Coupling	Land
		Top resolution	Resolution Z Coord., Top BC	Dynamics, Leads (Sources)	Flux adjustments	Soil, Plants, Routing (Sources)
13: GISS-AOM, 2004	NASA/Goddard Institute for Space Studies, USA	top = 10 hPa 3°×4° L12	3°×4° L16 mass/area, free sfc.	rheology, leads (Flato and Hibler, 1992)	no adjustments	layers, canopy, routing (Abramopoulos et al., 1988; Miller et al., 1994)
14: GISS-EH, 2004	NASA/Goddard Institute for Space Studies, USA	top = 0.1 hPa 4°×5° L20	2°×2° L16 density, free surface	rheology, leads (Liu et al., 2003; Schmidt et al., 2004)	no adjustments	layers, canopy, routing (Friend and Kiang, 2005)
15: GISS-ER, 2004	NASA/Goddard Institute for Space Studies, USA	top = 0.1 hPa 4°×5° L20	4°×5° L13 mass/area, free sfc.	rheology, leads (Liu et al., 2003; Schmidt et al., 2004)	no adjustments	layers, canopy, routing (Friend and Kiang, 2005)
16: INM-CM3.0, 2004	Institute for Numerical Mathematics, Russia	top = 10 hPa 4°×5° L21	2°×2.5° L33 sigma, rigid lid	no rheology or leads	regional freshwater	layers, canopy, no routing (Volodin and Lykosoff, 1998)
17: IPSL-CM4, 2005	Institut Pierre Simon Laplace, France	top = 4 hPa 2.5°×3.75° L19	12°×2° L31 depth, free surface	rheology, leads (Goosse and Fichefet, 1999)	no adjustments	layers, canopy, routing (Krinner et al., 2005)
18: MIROC3.2 (hires), 2004	Center for Climate System Research (University of Tokyo), National Institute for Environmental Studies, and Frontier Research Center for Global Change (JAMSTEC), Japan	top = 40 km T106 (~1.1°×1.1°) L56	0.2°×0.3° L47 sigma/depth, free surface	rheology, leads (K-1 Developers, 2004)	no adjustments	layers, canopy, routing (K-1 Developers, 2004; Oki and Sud, 1998)
19: MIROC3.2 (medres), 2004		top = 30 km T42 (~2.8°×2.8°) L20	0.5–1.4°×1.4° L43 sigma/depth, free surface	rheology, leads (K-1 Developers, 2004)	no adjustments	layers, canopy, routing (K-1 Developers, 2004; Oki and Sud, 1998)
20: MRI-CGCM 2.3.2, 2003	Meteorological Research Institute, Japan	top = 0.4 hPa T42 (~2.8°×2.8°) L30	0.5–2.0°×2.5° L23 depth, rigid lid	free drift, leads (Mellor and Kantha, 1989)	heat, freshwater, momentum (12S–12N)	layers, canopy, routing (Sellers et al., 1986; Sato et al., 1989)
21: PCM, 1998	National Center for Atmospheric Research, USA	top = 2.2 hPa T42 (~2.8°×2.8°) L26	0.5–0.7°×1.1° L40 depth, free surface	rheology, leads (Hunke and Dukowicz 1997, 2003; Zhang et al., 1999)	no adjustments	layers, canopy, no routing (Bonan, 1998)
22: UKMO-HadCM3, 1997	Hadley Centre for Climate Prediction and Research/Met Office, UK	top = 5 hPa 2.5°×3.8° L19	1.5°×1.5° L20 depth, rigid lid	free drift, leads (Cattle and Crossley, 1995)	no adjustments	layers, canopy, routing (Cox et al., 1999)
23: UKMO-HadGEM, 2004	Hadley Centre for Climate Prediction and Research/Met Office, UK	top = 39.2 km ~1.3°×1.9° L38	0.3–1.0°×1.0° L40 depth, free surface	rheology, leads (Hunke and Dukowicz, 1997; Semtner, 1976)	no adjustments	layers, canopy, routing (Essery et al., 2001; Oki and Sud, 1998)

re-analysis for the same period. The scaling (color bars) is identical for both the simulated and observed change maps. It is apparent that the CMIP3 composite captures the change in terms of (i) polar amplification, with maximum warming over the Arctic, and (ii) the magnitude of the warming, which averages between 0.5 and 1.0 °C over the domain in both cases, with local maxima of about 2 °C in each case. Not surprisingly, there are some differences in the regional details. For example, the re-analysis shows an area of cooling in the North Pacific, while the CMIP3 composite does not. Also, the location of the

maximum warming is over the Beaufort Sea in the re-analysis and over the Barents Sea in the CMIP3 composite, indicating that some of the models demonstrate a loss of sea ice in the Barents Sea during 1957 to 2006. However, the CMIP3 model runs for this period were not set up to simulate observed regional variations, which may be generated from internal variability particularly originating from the oceans. It is also important to note that the agreement between the simulated and observed trends is weaker seasonally, especially during winter when the actual climate system has circulation-driven

variations of temperature. Similarly, the individual models show much wider ranges of changes hemispherically and regionally because natural variability dominates a single realization over a 50-year period – as noted in Section 3.3 and as shown by Wang et al. (2007). Figure 3.2 shows that the 50-year temperature change for winter from three individual models displays large spatial and across-model variability. The spatial scale of this variability is consistent with circulation-driven anomalies of temperature. The winter CMIP3 composite temperature change map smooths much of the across-model variance (see Figure 3.2), but it does not – nor should it – match the spatial variations of the observed winter change, which have areas of cooling in eastern Siberia and near Greenland, probably due to the real atmosphere's natural variations during 1957 to 2006.

Fourteen of the global climate models used in the IPCC AR4 (Solomon et al., 2007) project warming for the Arctic beyond 2030 for each of three increasingly larger greenhouse gas emissions scenarios (labeled B1, A1B, and A2 according to IPCC terminology – see Box 3.1), although interannual variability of the surface air temperatures in the Arctic is large, especially over land (Chapman and Walsh, 2007). Projected changes vary widely among models and emissions scenarios. By the end of the 21st century, the projected annual mean temperature changes range from increases of +1.0 to +5.5 °C for the B1 scenario, increases from +2.5 to +7.0 °C for the A1B scenario, and increases from +4.0 to +9.0 °C for the A2 scenario. These ranges are larger than the corresponding values for the entire globe. Differences between the three emissions scenarios are projected to be small in the first half of the 21st century, but increase toward the end of the 21st century. Warming rates are smaller over land and largest over the Arctic Ocean. The greatest annual warming over land is near the Barents Sea (~6.5 °C for the A1B scenario). All models project the largest warming in autumn and winter, although the rates vary considerably

Box 3.1. IPCC emissions scenarios

Emissions scenarios imply that model simulations of future climate conditions are made specifying different rates of increase in the emission of greenhouse gases. In IPCC AR4, the A2 emissions scenario (for a very heterogeneous world with high population growth, modest economic development and slow technological change) implies a greater carbon dioxide (CO₂) increase than the B2 emissions scenario (for a world with intermediate population and economic growth, emphasizing local solutions to economic, social, and environmental sustainability) and the A1B emissions scenario (a world of very rapid economic growth, a global population that peaks in mid-century and rapid introduction of new and more efficient technologies, with a balance across fossil intensive and non-fossil energy resources) that is an in-between case.

among the models and across emissions scenarios. Walsh et al. (2008) evaluated the performance of fifteen models used in IPCC AR4 (Solomon et al., 2007) and found that models with smaller errors tended to simulate greater warming and greater increases in precipitation amount over the Arctic (60° to 90° N). Such findings have application for the selection of subsets of models to reduce the associated uncertainties, although there is no guarantee that the models that best capture recent climate will produce the best projections of future change.

It is apparent from the composite CMIP3 projections of seasonal temperature change for the late 21st century (Figure 3.3) that warming dominates in all seasons, and that the warming is amplified compared to previous climatology in all seasons except in summer when the melting 'ice bath' of the Arctic Ocean constrains the surface air temperature to remain close to 0 °C. The annual mean warming is polar-amplified,




Figure 3.2. Patterns of winter temperature change over the 50-year period, 1951 to 2000, simulated by three individual models (the three small plots), and the corresponding mean pattern of fourteen different models (the large plot). All models are from the suite used in the IPCC AR4 (Solomon et al., 2007). See Walsh et al. (2008) for model selection.




Figure 3.3. Projected changes of seasonal mean surface air temperature for the period 2070 to 2090. Changes are composited over the CMIP3 models forced by the A1B emissions scenario. Fourteen model projections form the composite. Modified from Walsh et al. (2008).

in much the same way as the observed and simulated patterns of annual mean warming for the 1957 to 2006 period (Figure 3.1). The warming is largest over the Arctic in autumn and winter (3 to 6 °C by 2080), consistent with a loss of summer sea ice, greater absorption of solar radiation during summer, and release of this additional heat to the atmosphere during the cold season. Especially during winter, the spatial pattern bears the signature of sea ice reduction, with local maxima of 6 to 7 °C in the areas that have lost sea ice. Over much of the northern land areas, the warming is between 2 and 3 °C. It should be noted that the projections in Figure 3.3 are based on the A1B scenario. The corresponding spatial patterns for the A2 and B1 scenarios are similar to the A1B patterns shown in Figure 3.3, but the magnitudes of the warming are 30% to 50% larger for the A2 scenario and 30% to 50% smaller for the B1 scenario.

It is difficult to establish cause and effect between loss of sea

ice and increased air temperature. Wang and Overland (2009) demonstrated that the more reliable models show a greater reduction rate in summer sea-ice loss (see Chapter 9). Further, given the major observed sea-ice reductions in 2007 to 2010, the faster sea-ice loss ensemble members should be favored (Holland et al., 2008), giving a nearly sea-ice free September by the mid-21st century.

Kattsov et al. (2007b) projected changes in precipitation amounts for 2041 to 2060 and 2080 to 2099 relative to measured precipitation data for 1980 to 1999 for a subset (13) of 21 of the IPCC AR4 GCMs forced by emissions scenarios B1, A1B, and A2. All of the models and scenarios showed increased precipitation across the Arctic through the 21st century, with much larger percentage increases than shown for the global mean precipitation and with distinct regional patterns. Percentage increases are generally largest at higher latitudes and most pronounced over northeast Greenland followed by coastal Siberia and the Canadian Arctic Archipelago. Percentage increases projected by 2080 to 2099 vary across the Arctic from a range of 5% to 40% (B1 scenario) to a range of 5% to 70% (A2 scenario), with the largest increases projected for northeast Greenland. The Arctic precipitation changes have a pronounced seasonality, with the largest relative increases in winter and autumn and the smallest in summer. The across-model scatter of the precipitation increase for each emissions scenario is large, but smaller than the scatter among different models in the baseline period (Kattsov et al., 2007b).

Figure 3.4 shows the CMIP3 composite projections of change in precipitation for summer and winter in the period 2070 to 2090. Although precipitation fields are inherently noisier than surface air temperature fields, compositing the simulations eliminates much of the spatial noise. The high latitudes are dominated by increases in precipitation in both seasons, with the largest increases found in coastal mountain ranges during winter. The only areas for which precipitation is projected to decrease are in the North Atlantic south of Greenland in winter and at the domain's periphery in summer when mid-latitude continental drying is projected by many models. The increase in precipitation is driven largely by changes in moisture flux convergence. Increases in Arctic precipitation are generally greatest in the models with the greatest warming. Only a proportion of the projected increases in precipitation will lead to increases in snow accumulation, since the fraction of precipitation falling as rain will increase under the projected increases in surface air temperature due to a general shortening of the period with sub-zero temperatures.




Figure 3.4. Projected changes for winter (left) and summer (right) precipitation for the period 2070 to 2090 in a composite of CMIP3 simulations forced by the IPCC A1B emissions scenario. Fourteen model projections form the composite. Modified from Walsh et al. (2008).

It should be emphasized that the projected increases in precipitation (typically 1 to 2 cm per season in the Arctic) do not preclude drying of the Arctic terrestrial regions. As illustrated in IPCC AR4 (Solomon et al., 2007: figure 10.3), increases in precipitation over Arctic land areas are accompanied by increases in evapotranspiration and runoff under the various greenhouse gas emissions scenarios, resulting in decreases in soil moisture. The net hydrological effect of a warming Arctic is an ongoing area of research, as precipitation and evapotranspiration are highly parameterized in models and hence subject to considerable uncertainties. Nevertheless, as reported in Chapter 2 there are suggestions of only small increases in Arctic precipitation over the past 50 to 60 years, while terrestrial drying has been sufficient to impact lake levels and fire frequencies in at least some Arctic terrestrial regions (GCCIOUS, 2009).

3.3. Climate projection uncertainties

There are three main sources of uncertainty in the use of GCMs for climate projections: large natural variations (both forced and unforced), the range in emissions scenarios, and structural or model uncertainties. First, it is known that if climate models are run several times with slightly different initial conditions, the trajectory of day-to-day and indeed year-to-year evolution will have a different timing of events, even though the underlying statistical-spectral character of the ‘model climate’ tends to be similar for each run. This variability is a true feature of the climate system, and users of climate projections must recognize its importance. This uncertainty can affect decadal or even longer-term means, so it is highly relevant to the use of model-derived climate projections. To reduce the influence of the range of natural variability, the projections may be averaged over decades or, preferably, ensemble averages may be formed from a set of at least several model runs. Such a procedure can help distinguish the anthropogenic contribution to climate change from the natural variability. There may also be interest in the possible changes in extreme states, which can result from a trend due to external (e.g., anthropogenic) effects combined with an episodic event due to intrinsic climate variability. Here, it is important to recognize the limitations in predicting the timing of events. Certainly, a drawback of considering only a single model run, rather than an ensemble of model runs, is that the intrinsic natural variability component cannot be clearly separated from the influence of anthropogenic external forcing.

A second source of uncertainty arises from the range in plausible emissions scenarios. Emissions scenarios are developed based on assumptions for the future development of humankind (Nakicenovic et al., 2000); they are converted into greenhouse gases and aerosol concentrations, which are then used to drive the GCMs in the form of external forcing specified in the CMIP3 models and summarized in IPCC AR4 (Solomon et al., 2007). Most of the CMIP3 models have made projections under the emissions scenarios A2, A1B, and B1 (see Box 3.1). Because the residence time of carbon in the atmospheric system is of the order of centuries, climate projections are relatively insensitive to the precise details of which future emissions scenarios are used over the next few decades, as the impacts of the scenarios are rather similar before the mid-21st century.

However, for the latter half of the 21st century, and especially by 2100, the choice of emissions scenario dominates over natural variability and model-to-model differences, becoming the major source of uncertainty of climate projections (Solomon et al., 2007). With 2030 to 2050 as a timescale of interest, a single mid-range anthropogenic emissions scenario is often used (the A1B or the A1B and A2 together to increase the number of potential ensemble members), as their CO₂ trajectories are similar before 2050. However, some differences do emerge in the Arctic even before the mid-21st century as a result of, for example, the different scenarios of aerosols with their pronounced spatial distributions.

The third source of uncertainty is termed ‘structural uncertainty’, and is used here to refer not only to a model’s configuration (resolution, vertical coordinate, grid-point vs. spectral) but also to its formulation features. Different numerical approximations of the model equations, including spatial resolution, introduce part of the structural uncertainty. Sub-grid scale processes must be parameterized in all models; by necessity, these parameterizations are simplifications of complex processes and require tuning. The selection of parameterization schemes, and the tuning of their coefficients, is at least somewhat subjective, and the various modeling centers have made different choices. Multi-model ensembles have the advantage of sampling this structural uncertainty. For example, there is a minimum error when the composite contains five to seven models (Figure 3.5) when sampling the dependence of the root mean square error of Arctic surface air temperature on the number of highest-ranking models included in a multi-model ensemble composite. Apparently, single models are subject to structural errors, while as the number of models included in the average exceeds five to seven, the inclusion of additional, poorer-performing models compared to observations degrades the multi-model ensemble composite. This finding appears to be robust across variables and regions within the extratropical Northern Hemisphere, although its dependence on the length of the validation period requires further investigation.

Average of the 12 monthly RMS errors for each model, °C




Figure 3.5. Dependence of the root mean square error (integrated over 60° to 90° N and the seasonal cycle for the period 1981 to 2000) of Arctic surface air temperature on the number of highest-ranking models included in a multi-model ensemble composite.

3.4. Treatment of sea ice, snow, permafrost, glaciers, and ice sheets in climate models

In the treatment of the cryosphere, one of the major developments over the past several years has been the implementation of sea-ice dynamics in all coupled models. Previously, many models used very simple descriptions of sea ice or even none at all (Houghton et al., 2001). Table 3.1 contains short descriptions of the sea-ice treatment in each of the 23 participating models. Moreover, Table 3.1 shows that very few models employ artificial flux adjustment (regressing the solution back toward a base state) between the ocean (including sea ice) and the atmospheric component. Although a questionable modeling methodology improvement, the implications for model performance are less promising insofar as systematic biases are pronounced in many models, as the purpose of flux adjustments was to tie the models closer to observations. This is particularly evident in the Arctic, due to the complicated interplay between ocean, sea ice, land, and atmosphere.

Sea-ice components of current GCMs usually predict ice thickness (or volume), fractional cover, snow depth, surface and internal temperatures (or energy), and horizontal velocity. Some models now include prognostic sea-ice salinity (Schmidt et al., 2004). Sea-ice albedo is typically prescribed, with only crude dependence on ice thickness, snow cover, and puddling effects. The complexity of sea-ice dynamics varies from the relatively simple ‘cavitating fluid’ model (Flato and Hibler, 1992) to the viscous-plastic model (Hibler, 1979), which is computationally expensive, particularly for global climate simulations. The elastic-viscous-plastic model (Hunke and Dukowicz, 1997) is being increasingly employed, particularly due to its efficiency for parallel computers. Treatment of sea-ice thermodynamics typically includes constant conductivity and heat capacities for ice and snow (if represented), a heat reservoir simulating the effect of brine pockets in the ice, and several layers, the upper one representing snow. Some models include snow-ice formation, which occurs when an ice floe is submerged by the weight of the overlying snow cover and the flooded snow layer refreezes. In a significant advance over many models of a decade ago, many sea-ice models (even with fine resolution) incorporate sub-grid scale ice thickness distributions with several thickness ‘categories’, rather than considering the ice as a uniform slab with inclusions of open water. Although parameterizations of ridging mechanics and their relationship with the ice thickness distribution have improved (e.g., Toyota et al., 2004), inclusion of advanced ridging parameterizations has lagged other aspects of sea ice dynamics (rheology, in particular).

Land surface processes are also treated interactively in the models, although the processes represented vary widely among the models. A common feature in all of the more recent models is the implementation of river routing schemes, which allows for the return of surface waters back to the ocean. Cold land processes have received considerable attention with multi-layer snowpack models (e.g., Oleson et al., 2004) in many GCMs, as has the inclusion of soil freezing and thawing (e.g., Boone et al., 2000). Sub-grid scale snow parameterizations

(Liston, 2004), snow-vegetation interactions, and the wind redistribution of snow (Essery and Pomeroy, 2004) are also more common in current models. A key feature of snow formulations is the parameterization of snow albedo, which depends on snow depth, age, and vegetative masking. Various model experiments in recent years have shown that the degree of vegetative masking of snow is important for climate locally and, in some experiments, remotely. The sophistication of the snow albedo parameterization, both on land and over sea ice, varies widely among models. A recent advance is the coupling of groundwater models into land surface schemes (e.g., Liang et al., 2003). These have only been evaluated locally but may be adaptable to global scales.

Below ground, a few layers typically are used to describe the diffusion of heat and moisture processes. In all cases, these layers are reaching no deeper than a few metres below the surface. Some models use a simple bucket description of soil moisture processes, while others use a more consistent interaction between moisture and energy fluxes, including freezing and thawing within the soils. Some details regarding these schemes are summarized as key words and listed in Table 3.1. A common feature of most GCMs is the treatment of the lower boundary condition as zero flux. This limits the ability of any long-term penetration of a climate change warming signal into the ground and instead causes a spurious reflection at the lower boundary, resulting in an exacerbated warming of the model soil layers. In cold climate regions, this poses a challenge as even the penetration of the annual signal of the temperature to depth is corrupted this way. Recent model developments are introducing more soil layers and a greater depth, resulting in substantial improvements in simulations of the subsurface annual cycle. Therefore, the permafrost simulations described in Chapter 5 are based on ‘offline’ simulations, i.e., a spatially distributed permafrost model with parameterizations, resolution, and depth that are enhanced relative to the terrestrial modules in GCMs.

A related model shortcoming has been a general ignorance of wetlands and organic soils, which are present in many Arctic regions, dominating the landscape in some areas. Shallow lakes, for example, cover as much as 30% of tundra areas such as the coastal plain of northern Alaska. High-latitude organic soils are included in some models (Wang et al., 2002). Regional climate model simulations also appear to improve when these special landscape types are taken into consideration.

When it comes to the treatment of glaciers and ice sheets, current GCMs are generally lacking in that the models do not include many processes important to glaciers, ice sheets, and their coupling to the atmosphere (and ocean). Glaciers are mostly of a size that is not resolved by GCMs and therefore are not treated interactively. Ice sheet models are used in calculations of long-term warming and sea-level scenarios, although they have not been incorporated into any of the 23 AR4 GCMs. The ice sheet models are run offline, and that is the approach followed in Chapter 8 for Greenland as well as for the smaller ice caps and glaciers. Ice sheet models are included in some Earth System Models of Intermediate Complexity (EMICs). However, the timescale of projected melting of the Greenland Ice Sheet may be different in coupled and offline simulations. One aspect of concern would seem to be the apparent discrepancy between the simplistic treatments of

an ice sheet in the climate model, from which the output fields are then subsequently used to force an ice sheet model. The consequences of such an inconsistency still have to be assessed in the context of an evolving climate. Similarly, the approach used for assessing changes in permafrost conditions is based on offline modeling of permafrost conditions. With the limitations of shallow soil layers and lack of organic soil treatment in GCMs, this inconsistency in the driving climate needs to be kept in mind when using an offline approach such as has been employed in the present assessment.

3.5. Key considerations in model selection

There is no universal methodology for using multiple GCMs for climate projections. The performance of CMIP3 models varies with location, variable of interest, and analysis method, with some models performing well for some criteria but not for others (Gleckler et al., 2008; Walsh et al., 2008). If the climate impact problem is defined by needing a projection of a specific variable in a specific location, it is unclear whether it is preferable to base model selection decisions on the accuracy of the models for this local variable in hindcast simulations or with respect to overall measures of performance over a range of variables and larger regions. For example, advective processes can strongly affect local climate, implying that credible simulation of climate over a wider area will be important for changes at a particular location. Moreover, the coarse resolution of most current climate models certainly dictates caution in their application on smaller scales in heterogeneous regions such as along coastlines or in locations with rugged orography. Experience of conducting model evaluations over the past few years indicates the value of multiple and complementary approaches, i.e., models should be compared using different metrics. Due to the need to account for structural uncertainty, a single 'best' model should not be relied upon. Rather, a reduced group of models (a minimum of about five) may generally be optimal, but this may also be variable and regionally dependent. This approach contrasts with that of IPCC AR4, where averages were often presented across all contributed models of opportunity, regardless of quality.

There are three general concepts pertaining to multiple model evaluation. The first consideration is the quality of the underlying physics. Does the model include reasonable parameterizations of the physics of interest? For example, sea ice is represented in separate models at considerably different levels of sophistication. The number of layers in the ice and the presence or absence of ice transport, deformation, and thickness categories vary among models, as noted in Section 3.4. Similarly, if projections of permafrost are to be obtained directly from a GCM, the model should include processes affecting soil temperature and water in a manner that allows for credible simulations of temporal evolution. While this initial 'pre-screening' contains some inevitable subjectivity, it will leave the user with a set of model simulations that represents a more justifiable 'ensemble of opportunity'.

The second consideration is consistency: do different models in the ensemble of opportunity produce similar simulations? The degree of similarity can reflect how well underlying mechanisms are represented in the models. The

third consideration is the skill of the models' hindcasts relative to various datasets or fields (e.g., for the 20th century). While past skill would seem to be a necessary condition for using a model, this provides no guarantee of accurate model projections under new external forcing or climate states (Reifen and Toumi, 2009). It is suggested that past performance should represent a primary criterion in rating the models, but that hindcasts should not be the only consideration in choosing models on which to base a projection.

3.5.1. Choices for evaluating hindcast skill

For evaluating hindcast skill, choices include the selection of observational datasets, variables, regions, metrics, and weighting approaches. The metrics can include comparisons to mean climate, climate variability as represented by the annual cycle or interannual variability, correlation, or trends due to externally forced change.

Validation of models generally includes comparison to means. However, this approach has two drawbacks in relation to projections. First, the quality of projections should also relate to potential changes (or sensitivities) in the force balance or heat budget in the system, in addition to mean states. Second, models are tuned to represent the mean state and are not independent of the observational fields. However, if model projections depend on the state of the system (e.g., the state of sea ice) at the end of the 20th century, then having the correct mean conditions is critical (Wang and Overland, 2009).

Several authors recommended using the seasonal cycle for comparison, which appears to be a good choice as the range of radiative forcing and other conditions over the year is comparable to or greater than the magnitude of potential future climate shifts (Hall and Qu, 2006; Knutti et al., 2008; Walsh et al., 2008). It is also important to consider interannual variability ('variance'). For example, Stoner et al. (2009) documented the ability of models to capture the timescales and spatial patterns of the major modes of observed natural variability. Namely, the Arctic Oscillation (AO), the North Atlantic Oscillation (NAO), the Atlantic Multi-decadal Oscillation (AMO), the El Niño / Southern Oscillation (ENSO), the Pacific Decadal Oscillation (PDO) and the Pacific North American (PNA), as shown in Table 3.2.

Using the correlation between model and observation time series is a poor choice for evaluating hindcast skill as the observations represent only a single realization of a system with strong natural variability. Comparisons must therefore utilize climate statistics rather than year-to-year values that manifest natural variability (i.e., chaotic uncertainty) (Kattsov et al., 2007a; Overland and Wang, 2007).

Using trends to evaluate hindcast skill would be another seemingly good choice, as the interest is in projecting future trends. However, over the past 20 to 50 years, internal variability is large and obscures the underlying trend due to external causes in the observation set, especially in the case of regional trends. In addition, a regional trend may not necessarily be attributable to an external driver. These problems compound the difficulty in using trends as a constraint.

Applying aggregate metrics (i.e., using multiple criteria) to model selection, while intellectually appealing, also has limitations. If an increasing number of variables or subregions are included as independent constraints, then an increasing

Table 3.2. Results of an evaluation by Stoner et al. (2009) of global climate model simulations of modes of natural variability. Green represents a good match, yellow a partial match, and red a lack of correspondence.

Model	Time series						Teleconnection pattern					
	AO	NAO	AMO	ENSO	PDO	PNA	AO	NAO	AMO	ENSO	PDO	PNA
BCCR												
CCSM3.0												
CGCM3.1 (T47)												
CNRM												
CSIRO-MK3												
ECHAM5												
GFDL-CM2.0												
GFDL-CM2.1												
GISS-ER												
INM-CM3												
IPSL												
MIROC-MED												
MRI												
PCM												
UKMO-HADCM3												
UKMO-HADGEM												

number of models will exhibit deficiencies that make them candidates for exclusion. Experience suggests that a practical limit to model selection is rapidly reached for CMIP3 archived models. Likewise, if a ‘model climate performance index’ is developed by averaging performance rankings over many variables, it can produce inconsistencies. For example, what is the meaning of an additive index where a given model performs well on one variable but poorly on another? Is it better that a model does a reasonable job on a single or a few variables, or is middle-of-the-road performance over multiple variables more appropriate? User priorities may dictate the weighting of a particular variable in model evaluation, but deficiencies in fields of other variables may point to structural shortcomings that adversely affect a model’s projections of change.

It is thus necessary to make choices regarding best practice selection methods. Inevitably, this leads to subjectivity in the approach for assessing the overall best models. In fact, the process should be viewed as reducing the impact of models with large hindcast errors rather than the selection of best models, while retaining several models as a measure of structural uncertainty. The ‘best’ multi-model ensemble will vary from application to application, depending on the particular priorities of the users. By necessity, credibility is increased by consensus between different approaches to selection and by the openness, simplicity, and transparency of the process. Careful documentation of the model selection procedure is essential. Although averaging is often a better procedure than simply using one model (Reichler and Kim, 2008), including all CMIP3 models as a grand average or a distribution is not a viable option, as some are obvious outliers with respect to observational correspondence. Thus, the following is noted:

1. An initial screening based on the underlying physics of various models, particularly as it pertains to the application at hand, will ensure that any quantitative evaluations are based on a set of models that is at least potentially credible.

2. In many applications, it will be advisable to eliminate the models that seriously fail to meet one or more observational constraints, based on actual or synthetic data (re-analyses). For example, do the selected variables have reasonable means and seasonal cycles (variance) close to the observations at a continental scale or above? This does not guarantee future performance, but it at least indicates that the projections are built upon reasonable background and users have more confidence in the models. It bears noting that even reproducing mean quantities approximately correct is different, as the CMIP3 models are initialized in the 19th century.
3. After eliminating poorly performing outlier models, the remaining subset of models can be evaluated for individual variables and regions of interest. The present analyses of GCM hindcast simulations show that different models perform differently in different regions and for different variables within a region, often without obvious reasons. Nevertheless, for specific applications, it is plausible that the models with better hindcast simulations of externally driven changes will also provide projections that are more reliable.
4. As a general rule, it is advisable to use multi-model ensembles to account for structural uncertainty. This is a sampling problem so a sample size of at least several models is desirable (Figure 3.5). A multi-model mean should tend to be more reliable than any individual model, even if the individual model is of high quality based on its performance in a 20th century hindcast. All current generation models include some non-systematic errors, and these errors can be reduced through averaging (Reichler and Kim, 2008). Models selected by multivariable metrics generally outperform any individual model. As noted earlier, natural variability over the evaluation period also argues for the use of multiple models in obtaining a projection.

Table 3.3. Summary of CMIP3 model evaluations over the Northern Hemisphere and Arctic for selected variables.

Region	Source	Global	NH 20° to 90° N			NH 20° to 90° N		NH 60° to 90° N			NH 40° to 90° N		Global			
		Reichler and Kim, 2008	Gleckler et al., 2008			Walsh et al., 2008		Walsh et al., 2008		Wang et al., 2007	Overland and Wang, 2007	Wang and Overland, 2009	Wu et al., 2008			
		14 variables	SAT	SLP	T850	SAT	SLP	SAT	SLP	SAT	Sea ice		Climate sensitivity			
Model ID	Country	Variance (annual mean)	Annual mean RMS error			RMS error (monthly mean)		RMS error (monthly mean)		Variance (winter)	Summer mean	Seasonal cycle				
1	BCCR-BCM2.0	Norway	16	14								×	×			
2	CCM3	USA	7	9				2/2	13/13	2/3	15/4	✓	✓	✓	2.7	
3	CGCM3.1(T47)	Canada	5	6	5			10/10	4/5	11/8	2/4	✓	✓	×	3.4	
4	CGCM3.1(T63)	Canada	8	8	4						✓	✓	×	3.4		
5	CNRM-CM3	France	14	13	7			5/6	11/3	5/6	12/3	✓	✓	✓		
6	CSIRO-Mk3.0	Australia	13	7	19			12/13	9/10	14/13	9/14	✓	×	×	3.1	
7	ECHAM5/MPI	Germany	3	2	1			1/1	1/1	1/1	1/1	✓	✓	×	3.4	
8	ECHO-G(MIUB)	Germany/ Korea	3								✓	✓	✓	3.2		
9	FGOALS-g1.0(IAP)	China	12	20	16			15/15	10/9	15/15	13/15	×				
10	GFDL-CM2.0	USA	10	11	9			14/4	4/4	9/5	8/10	✓	✓	×	2.9	
11	GFDL-CM2.1	USA	1	4	2			5/3	2/2	3/2	4/2	✓	×	×	3.4	
12	GISS-AOM	USA	19	17	13						×	✓	×	2.7		
13	GISS-EH	USA	22	15	18						×					
14	GISS-ER	USA	18	18	20			10/12	14/14	10/10	14/11	×	×	×		
15	Ingv	Italy	11											×	×	
16	INM-CM3.0	Russia	15	14	12			10/11	9/11	6/7	7/9	✓	×	×	2.1	
17	IPSL-CM4	France	17	19	21			12/8	15/15	7/9	11/13	×	✓	✓	4.4	
18	MIROC3.2(hires)	Japan	9	5	11						×	×	×	4.3		
19	MIROC3.2(lowres)	Japan	12	10	8			3/5	5/6	4/4	3/8	×	✓	✓	4.0	
20	MRI-CGCM2.3.2	Japan	4	12	15			7/7	6/7	13/12	11/12	×	×	×	3.2	
21	PCM	USA	21	16	17			14/14	12/11	13/14	5/7	✓				
22	UKMO-HadCM3	UK	6	3	10			6/10	7/8	8/11	6/6	✓	×	×	3.3	
23	UKMO-HadGem1	UK	2	1	6							✓	✓	4.4		
24	BCC-CM1	China														
25	CSIRO-MK3.5	Australia												×		

Cells with two numbers indicate the order of ranking for each model of selected variables for a given region by papers published in the past – the first number is based on the original output, the second is when the bias has been removed. A blue dot indicates cases where a model fares better than the typical model with respect to the reference data, and a red dot indicates the contrary. A tick and a cross indicate where models passed or did not pass the selection criterion.

3.6. Meta-analysis

A meta-analysis approach is illustrated here by synthesizing the results from several earlier papers (Table 3.3). Walsh et al. (2008) analyzed surface air temperature (SAT) and sea-level pressure (SLP) north of 60° N using the observational constraint of the root mean square (RMS) error and variance over the seasonal cycle. Similarly, Gleckler et al. (2008) compared modeled mean values of sea-level pressure and 850 hPa temperatures (T850) with re-analyses in a complex model climate performance index. Wang et al. (2007) used the criteria of interannual variance of winter Arctic land surface air temperatures. Summer Arctic sea ice was investigated by Wang and Overland (2009), who required that the models not only be able to simulate the mean minimum sea-ice extent but also the magnitude of seasonality (March minus September extent). All of these evaluations involved assessing how well the model hindcasts for the 20th century matched observations. For reference, two more studies are also included, those of Reichler and Kim (2008) and Wu et al. (2008); the first included criteria for the entire planet, and the second concerned model sensitivity.

With the high-latitude Northern Hemisphere and the SWIPA processes being the primary focus of this assessment, the meta-analysis ranks the models based on their performance on selected variables (surface air temperature, sea-ice extent, and sea-level pressure) over the Arctic and Northern Hemisphere when compared with observations. Of the CMIP3 models, some consistently perform better than others across the criteria. These are (in alphabetic order): CCSM3, CNRM-CM3, ECHO-G/MIUB, UKMO-HadGEM1 (shaded in blue in Table 3.3), which pass selection criteria for both Arctic surface air temperature and sea ice (Wang et al., 2007; Wang and Overland, 2009) and ranked relatively high by other studies (see also Table 3.3), as well as those shaded in yellow: CGCM3.1 (T47), CGCM3.1 (T63), ECHAM5/MPI, GFDL-CM2.1, MIROC3.2(medres), and UKMO-HadCM3. The second group of models ranked high generally, but fail at least one of the sea-ice extent or Arctic surface air temperature tests. The third group (shaded in green) includes only one model (IPSL-CM4), which performs well in the sea ice simulation but ranked generally low in all other studies.

Although there is consistency in results among the difference methods of ranking the models, there is also a caveat in the process. For example, the CCSM3 model performs relatively well for temperature and sea ice simulations but is biased for sea-level pressure in the Northern Hemisphere, as pointed out by Walsh et al. (2008). This is especially problematic over the Arctic region because when the sea-level pressure bias is removed, the model ranking is advanced from fifteenth place to fourth place (see Table 3.3). The issue is whether the models' bias should be removed before they are ranked?

It should be noted that this chapter does not endorse any particular model result; Table 3.3 is for illustrative purposes only. Unfortunately, the review in this chapter found no systematic conclusions for the differences in model projections. As noted again in the next sections, evaluation results differ based on location and variable of interest.

3.7. Two regional examples

3.7.1. Alaska

According to Walsh et al. (2008), the top-performing models for Alaska are the GFDL-CM2.1, ECHAM5/MPI-OM, CNRM-CM3, UKMO-HadCM3, and the Japanese MIROC3.2(medres), all of which belong to the first or second group of meta-rankings in Table 3.3. It should be noted that the ranking depends on whether the annual mean biases are included in the root mean square errors. The ECHAM5/MPI model ranks well below the median (thirteenth out of the fifteen models) in its simulation of Alaskan temperature primarily because the temperatures projected by the model are too cold throughout the year over Alaska (Figure 3.6). However, the amplitude of its seasonal cycle is very close to the observed, so removal of the annual mean bias improves the model's rank to the first of the same set of fifteen models. Hence, an important consideration in the use of GCM output is the nature of any bias adjustment that may be imposed. This example illustrates the important point that a climate model that simulates several variables well can be a relatively poor performer in the simulation of other variables, particularly on a regional basis. The converse is also true.

With regard to the reasons for the different levels of skill over Alaska and Greenland as well as the larger domains, no systematic relationship to model resolution has emerged. The models with the smallest RMS errors (ECHAM5/MPI and GFDL-CM 2.1) have resolutions that are neither the highest nor the lowest of the fifteen models. There is also no obvious relationship between model performance and the type of sea ice formulation in the models. Other candidates for explanations of the differences in model performance include the cloud formulations and radiative properties, the planetary boundary layer parameterization, and the land surface schemes of the various models (e.g., Kattsov et al., 2007b; Sorteberg et al., 2007). Biases in the large-scale atmospheric circulation, perhaps driven by processes outside the Arctic, are also candidates to explain the across-model differences in temperature, precipitation, and sea-level pressure.

An interesting result that emerged from this regional evaluation is that the top-performing models tended to be more sensitive to greenhouse forcing than the poorer-performing models. This similarity is apparent in the late 21st-century changes in Arctic surface air temperature, precipitation, and sea level pressure. Perhaps models that best capture the seasonal cycle of radiative forcing are more sensitive to external (greenhouse) forcing. The reasons for this correspondence require further investigation.

3.7.2. Sea ice simulation for the Barents and Bering Seas

The Bering Sea and Chukchi Sea between Alaska and northeastern Russia, and the Barents Sea north of Norway are known as seasonal sea-ice zones, where the sea ice advances in winter and spring and retreats in summer, leaving regions of open water. The climatology of sea-ice extents for the Barents Sea (65° to 82° N, 15° to 60° E) represents an exception to the statement in the introduction that biases in simulated climate by different models tend to be unsystematic. The simulated




Figure 3.6. Root mean square error of January air temperatures relative to the ERA-40 re-analysis for the period 1958 to 2000. Simulations are from a subset of the 20th-century simulations run for IPCC AR4 (Solomon et al., 2007). Source: Walsh et al. (2008).

seasonal cycle of sea-ice conditions averaged over the period 1980 to 1999 shows that most models have too much sea ice in this region compared to the observed climatology (Figure 3.7). Expansion of sea ice in the Barents Sea is generally countered by ocean advection of heat into the region from the North Atlantic. An ongoing assessment indicates that the current-generation models in CMIP3 still have difficulty in achieving satisfactory simulations of ocean currents in this region. This over-specification of sea ice at the end of the 20th century had unfortunate implications for the full IPCC AR4. Too much sea ice in too many models meant that the simulated winter temperatures for the region during 1980 to 1999 were also too low (Figure 3.6). When the temperature change was projected for 2090 to 2999 relative to 1980 to 1999 and averaged over all the models, the changes were some of the largest on the planet, greater than 5 °C (Solomon et al., 2007: figures SPM6). The reason for this was not that this region would be excessively warm in the decade of 2090, but that the reference temperatures were incorrectly too low. While the average sea-ice extents are

too high for the Barents Sea, several models (e.g., CCSM3, ECHAM5/MPI-OM, and MRI) do considerably well for the seasonal cycle of sea-ice extent, suggesting that the Barents Sea is a major candidate for a reduced set of projections based on model selection. However, since only one (CCSM3) of the three models mentioned above shows good agreement with the observations on Arctic-wide sea-ice extent (Wang and Overland, 2009), there is not enough confidence in a multi-model approach to the projection of future sea-ice conditions over the Barents Sea.

For the Bering Sea, the multi-step strategy has been used to evaluate model performance and select models suitable for regional projections (see procedure proposed in Section 3.5). For example, for the eastern Bering Sea (54° to 66° N, 175° to 155° W), the six models identified by Wang and Overland (2009) were initially selected, as these have simulated Arctic-wide sea-ice extents both in terms of the summer mean and the magnitude of seasonal cycle reasonably well. The models were then required be able to simulate the spring (April and


Barents Sea sea ice extent, 10^6 km^2 

Figure 3.7. Seasonal cycle of sea ice in the Barents Sea according to various CMIP3 models. Note that most models show too much sea ice coverage. Source: modified version of figure 3 from Overland and Wang (2007).

May) sea-ice extent over the eastern Bering Sea with a less than 20% error from the observed value. The process led to four best-performing models over the eastern Bering Sea: CCSM3, CNRM-CM3, ECHO-G, and MIROC(medres). When a similar strategy was applied to the Chukchi Sea and the Beaufort Sea, the result was that all six models (CCSM3, CNRM-CM3, ECHO-G, IPSL-CM4, MIROC(medres), and UKMO-HadGEM1) identified by Wang and Overland (2009) passed the selection criteria. However, for the western Bering Sea and the Bering Strait, only one model (CCSM3) passed the selection criteria. For the Sea of Okhotsk, none of the models passed the selection criteria (Wang and Overland, 2009). This raises the question as to why some models perform better in one region than another, even for the same variable. Unfortunately, there is no clear answer to this at present.

3.8. Downscaling techniques

Direct use of output from GCMs for many cryospheric projections is not currently feasible due to the biases in model data on regional scales and due to the inability of models to resolve features of sea ice (e.g., polynyas and leads), glaciers, and topographic features that have major influences on snow and permafrost. In fact, most cryospheric features vary over smaller scales than climate model grid boxes, and terrestrial snow and ice often occupy complex terrain that is only coarsely resolved in the models' underlying topography. The accumulation and ablation of ice are particularly sensitive to biases in air temperature, which controls the energy available for melt and the snow-rain ratio of precipitation. Hence, some method of downscaling is required that transfers global-scale climate information to local scales prior to making cryospheric projections. Downscaling considerations are discussed in the following paragraphs, with some examples from glaciology. Because the central issues are similar across cryospheric variables, the discussion is also relevant to other components of the cryosphere.

Statistical downscaling is often applied by establishing statistical relationships between meteorological quantities determined at the GCM and local scales, either using field

observations or other suitable meteorological data such as data from climate re-analyses. In an application to glaciers, Radić and Hock (2006) applied 'local scaling' to correct for the biases in climate model air temperature and precipitation for projecting the mass balance of the Storglaciären glacier up to 2100. Downscaled temperature series were produced from GCMs and regional climate models (RCMs) by shifting the series by the averaged monthly differences between climate-model and local-scale data (ERA-40 re-analysis data, in this case) over a baseline period for which both GCM and local-scale data were available. Hence, the average seasonal cycle from ERA-40 was used as a reference by which seasonal cycles from the climate model were 'corrected'. The results highlight the importance of including the seasonally varying biases instead of assuming a constant bias throughout the year. Precipitation was scaled by the ratio of precipitation in the reference dataset (ERA-40) summed over the baseline period and the corresponding climate model precipitation sum. A drawback of statistical downscaling is the inherent assumption that the statistical relationships established over a baseline period will continue to hold in future climates.

An alternative approach to statistical downscaling is to use changes in GCM variables between defined future time intervals and a baseline period. These changes are then used to perturb observed local climate data to drive a mass balance model and project future mass balance changes. The changes in climate variables are often simply linearly interpolated between time intervals to allow for transient simulations. Due to generally large interannual variability, projected climate variable changes can be sensitive to the choice of baseline period. This is especially true when large fluctuations occur around the reference period or when the climate variable shows a trend during this period (Aðalgeirsdóttir et al., 2006).

Zhang et al. (2007) used a second downscaling approach, dynamical downscaling, employing the high-resolution Arctic MM5 regional atmospheric model driven by a global atmospheric re-analysis to obtain temperature and precipitation data on a 10-km resolution grid to force a glacier mass balance model. The results of mass balance simulations using dynamical downscaled data and simulations based on observed temperature and precipitation data are in reasonably good agreement when calibration is used to minimize systematic biases in the MM5 downscaling. These results point to the potential utility of dynamically downscaled future projections derived from high-resolution regional models driven by GCM projections. However, a common drawback is that systematic biases in the GCM projections propagated into the results from regional models.

3.9. Conclusions

This chapter discusses approaches for using the output from current generation climate models for regional climate projection applications. The skill and reliability of individual models will generally vary with the parameter, region, and metric. The reasons for these inconsistencies are rarely clear, which bears on the credibility of the composite model results on regional scales. Nevertheless, there appears to be utility in regional projections, as gauged by the hundreds of studies noted by the Program for Climate Model Diagnosis and Intercomparison (PCMDI).

The strategy for dealing with climate model errors and uncertainties should be keyed in accordance with a user's particular application. First, models should be pre-screened on the basis of their inclusion and formulation of key physical and dynamical processes, especially those directly relevant to the application at hand. Second, the available models can be evaluated based on the ability of their 20th-century hindcasts to reproduce the large-scale climate variability for the region of interest. This variability can include the annual cycle of certain variables that are responsive to radiative forcing; it can also include the leading spatial and/or temporal modes of variability. Such an evaluation can serve as a basis for eliminating some models from further consideration. Third, hindcasts of specific parameters can be considered in the region of interest. Correspondence of these hindcasts with observations can be the basis of a user's further selection of models or assignments of weights to models. More credence should be given to the projections from the models that are found to replicate past large-scale and externally driven conditions, considering both means and variances and perhaps other criteria such as trends or spatial modes of variability. While it may be tempting to determine a single best model and use its projections, this practice has serious limitations. All climate models are subject to structural uncertainty; the spread in the projections from different models provides a measure of this source of uncertainty.

The Arctic examples presented here suggest that metric-based sub-selection of models is effective for constructing ensemble averages. It is counter-intuitive and counter-productive to include the simulations from models known or strongly suspected to have low skill for a particular regional parameter relative to an observational constraint. While this is a logical consideration, there is no proof that it necessarily provides better projections. Finally, consideration can be given to the sophistication of each model in relation to the parameters of interest. For example, models with superior schemes for handling sea ice are liable to be more appropriate for Arctic applications such as this assessment.

The coarse resolution of most current climate models certainly dictates caution in their application on smaller scales in heterogeneous regions such as along coastlines, sea ice margins, or in locations with rugged orography. The direct use of data from GCMs for many cryospheric applications is not currently feasible, due to the biases in model data on regional scales and due to the inability of models to resolve features of sea ice (e.g., polynyas and leads), glaciers, and topographic features that have major influences on snow and permafrost. In fact, many cryospheric features vary over much smaller scales than climate model grid boxes, and terrestrial snow and ice often occupy complex terrain that is only coarsely resolved in the models' underlying topography.

Even within the reduced set of selected models, the quest for reasons for conflicting model results has no apparent quantitative solution. Given this situation, the use of selection metrics and aggregation methods should remain simple. Moreover, as applications will differ using these practices, choices made for any analysis should be as transparent as possible, with careful documentation of the model selection procedure. Finally, studies that include a selection of models should openly acknowledge that the selection process is guided by the application.

While noting the difficulties in interpreting the reasons for the range of results from different model forecasts for the same variable, overall interpretation of GCM projections has been useful. They include known physics and are quantitative in their calculation of mass and energy budgets. With a careful consideration and selection of models based on past performance compared to observations, the range of results can be reduced, providing a useful prediction of future climate states for regional and larger domains. That Arctic temperatures will generally increase by 3 to 6 °C (the greatest projected increases on the planet), that September will be nearly sea-ice free by mid-century, and that precipitation, but not necessarily as snow, will increase are robust conclusions from considering the results from 23 IPCC GCM models. In this chapter, the high-latitude needs of SWIPA have led to the identification of preferred models for use in the SWIPA modules. The choices of models in the subsequent chapters reflect these findings.

Acknowledgments

The authors acknowledge the modeling groups, the Program for Climate Model Diagnosis and Intercomparison (PCMDI), and the World Climate Research Programme's (WCRP's) Working Group on Coupled Modelling (WGCM) for their roles in making available the WCRP CMIP3 multi-model dataset. Support of this dataset is provided by the Office of Science, U.S. Department of Energy. We appreciate the organizational support to host workshops to discuss the use of CMIP3 models from the Arctic Council AMAP Climate Expert Group and the SWIPA Integration Team, the Ecosystem Studies of Sub-Arctic Seas (ESSAS), and Working Group 20 (Evaluations of Climate Change Projections) of the North Pacific Marine Science Organization (PICES). James E. Overland, Muyin Wang, and Nicholas Bond appreciate the support of the NOAA Arctic Program Office, the NOAA FATE Project, and the Arctic Yukon Kuskokwim (AYK) Sustainable Salmon Initiative. This chapter is partially funded by the Joint Institute for the Study of the Atmosphere and Ocean (JISAO) under NOAA Cooperative Agreement No. NA17RJ1232, Contribution # 1760. John E. Walsh and William L. Chapman were supported by NSF Grants OPP-0652838 and OPP-0520112. Vladimir M. Kattsov was supported by NSF Grant OPP-0652838 and Russian Foundation for Basic Research Grant 08-05-00569. Pacific Marine Environmental Laboratory contribution #3428.

References

- Abramopoulos, F., C. Rosenzweig and B. Choudhury, 1988. Improved ground hydrology calculations for global climate models (GCMs): Soil water measurement and evapotranspiration. *Journal of Climate*, 1:921–941.
- Aðalgeirsdóttir, G., T. Johannesson, H. Björnsson, F. Pálsson and O. Sigurosson, 2006. Response of Hofsjökull and southern Vatnajökull, Iceland, to climate change. *Journal of Geophysical Research-Earth Surface*, 111:F03001.
- Bonan, G.B., 1998. The land surface climatology of the NCAR Land Surface Model coupled to the NCAR Community Climate Model. *Journal of Climate*, 11:1307–1326.
- Boone, A., V. Masson, T. Meyers and J. Noilhan, 2000. The influence of the inclusion of soil freezing on simulations by a soil-vegetation-atmosphere transfer scheme. *Journal of Applied Meteorology*, 39:1544–1569.
- Briegleb, B.P., C.M. Bitz, E.C. Hunke, W.H. Lipscomb, M.M. Holland, J.L. Schramm and R.E. Moritz, 2004. Scientific Description of the Sea Ice Component in the Community Climate System Model, Version 3.

- NCAR Technical Note TN-463STR, National Center for Atmospheric Research, Boulder, Colorado.
- Cattle, H. and J. Crossley, 1995. Modelling Arctic climate change. The Royal Society of London. Philosophical Transactions. Series A, 352:201–213.
- Chapman, W.L. and J.E. Walsh, 2007. Simulations of Arctic temperature and pressure by global coupled models. *Journal of Climate*, 20:609–632.
- Cox, P.M., R.A. Betts, C.B. Bunton, R.L.H. Essery, P.R. Rowntree and J. Smith, 1999. The impact of new land surface physics on the GCM simulation of climate and climate sensitivity. *Climate Dynamics*, 15:183–203.
- Delworth, T.L., A.J. Broccoli, A. Rosati and 39 others, 2006. GFDL's CM2 global coupled climate models. Part I: Formulation and simulation characteristics. *Journal of Climate*, 19:643–674.
- Douville, H., J.F. Royer and J.F. Mahfouf, 1995. A new snow parameterization for the Meteo-France climate model. 1. Validation in stand-alone experiments. *Climate Dynamics*, 12:21–35.
- Dümenil, L. and E. Todini, 1992. A rainfall-runoff scheme for use in the Hamburg climate model. In: O'Kane, J.P. (Ed.). *Advances in Theoretical Hydrology: A Tribute to James Dooge*, pp. 129–157, Elsevier Press.
- Essery, R. and J. Pomeroy, 2004. Vegetation and topographic control of wind-blown snow distributions in distributed and aggregated simulations for an Arctic tundra basin. *Journal of Hydrometeorology*, 5:735–744.
- Essery, R.H., M. Best and P. Cox, 2001. MOSES 2.2 Technical Documentation. Hadley Centre Technical Note, 30, 31 pp. Hadley Centre for Climate Analysis and Research, Exeter, UK.
- Flato, G.M. and W.D. Hibler, 1992. Modeling pack ice as a cavitating fluid. *Journal of Physical Oceanography*, 22:626–651.
- Friend, A.D. and N.Y. Kiang, 2005. Land surface model development for the GISS GCM: Effects of improved canopy physiology on simulated climate. *Journal of Climate*, 18:2883–2902.
- GCCIIUS and Federal Advisory Committee Author Team, 2009. Global Climate Change Impacts in the United States. 162 pp. National Oceanic and Atmospheric Administration.
- GFDL GAMDT, 2004. The new GFDL global atmosphere and land model AM2-LM2: Evaluation with prescribed SST simulations. *Journal of Climate*, 17:4641–4673.
- Gleckler, P.J., K.E. Taylor and C. Doutriaux, 2008. Performance metrics for climate models. *Journal of Geophysical Research-Atmospheres*, 113:D06104.
- Goosse, H. and T. Fichefet, 1999. Importance of ice-ocean interactions for the global ocean circulation: A model study. *Journal of Geophysical Research-Oceans*, 104:23337–23355.
- Gordon, H.B., I.D. Rotstain, J.L. McGregor, M.R. Dix, E.A. Kowalczyk, S.P. O'Farrell, L.J. Waterman, A.C. Hirst, S.G. Wilson, M.A. Collier, I.G. Watterson and T.I. Elliott, 2002. The CSIRO Mk3 Climate System Model. CSIRO Atmospheric Research Technical Paper, 40, 134 pp. Commonwealth Scientific and Industrial Research Organization Atmospheric Research, Appendale, Victoria, Australia.
- Hagemann, S., 2002. An Improved Land Surface Parameter Dataset for Global and Regional Climate Models. MPI Report 336, 28 pp. Max-Planck-Institut für Meteorologie, Hamburg, Germany.
- Hagemann, S. and L.D. Gates, 2001. Validation of the hydrological cycle of ECMWF and NCEP reanalyses using the MPI hydrological discharge model. *Journal of Geophysical Research-Atmospheres*, 106:1503–1510.
- Hall, A. and X. Qu, 2006. Using the current seasonal cycle to constrain snow albedo feedback in future climate change. *Geophysical Research Letters*, 33:L03502.
- Harder, M., 1996. Dynamik, Rauigkeit und Alter des Meereises in der Arktis. Numerische Untersuchungen mit einem grossskaligen Modell. Ph.D. Thesis. 126 pp. Alfred-Wegener Institut für Polar Meeresforschung, Bremerhaven, Germany.
- Hibler, W.D., 1979. Dynamic thermodynamic sea ice model. *Journal of Physical Oceanography*, 9:815–846.
- Holland, M.M., C.M. Bitz, B. Tremblay and D.A. Bailey, 2008. The role of natural versus forced change in future rapid summer Arctic ice loss. In: *Arctic Sea Ice Decline: Observations, Projections, Mechanisms, and Implication*. Geophysical Monograph Series, American Geophysical Union, Washington D.C.
- Houghton, J.T., Y. Ding, D.J. Griggs, M. Noguer, J. van der Linden, X. Dai, K. Maskell and C.A. Johnson (Eds.), 2001. *Climate Change 2001: The Scientific Basis*. Contribution of Working Group I to the Third Assessment Report of the Intergovernmental Panel on Climate Change. 881 pp. Cambridge University Press.
- Hunke, E.C. and J.K. Dukowicz, 1997. An elastic-viscous-plastic model for sea ice dynamics. *Journal of Physical Oceanography*, 27:1849–1867.
- Jun, M.Y., R. Knutti and D.W. Nychka, 2008. Local eigenvalue analysis of CMIP3 climate model errors. *Tellus Series A*, 60:992–1000.
- K-1 Developers, 2004. K-1 Coupled Model (MIROC) Description. K-1 Technical Report 1, K-1 Technical Report 1, 39 pp. Center for Climate System Research, University of Tokyo.
- Kattsov, V.M., G.A. Alekseev, T.V. Pavlova, P.V. Sporyshev, R.V. Bekryaev and V.A. Govorkova, 2007a. Modeling the evolution of the World Ocean ice cover in the 20th and 21st centuries. *Izvestia of Russian Academy of Sciences: Physics of Atmosphere and Ocean*, 43:165–181.
- Kattsov, V.M., J.E. Walsh, W.L. Chapman, V.A. Govorkova, T.V. Pavlova and X.D. Zhang, 2007b. Simulation and projection of arctic freshwater budget components by the IPCC AR4 global climate models. *Journal of Hydrometeorology*, 8:571–589.
- Knutti, R., 2008. Should we believe model predictions of future climate change? *Philosophical Transactions of the Royal Society - Mathematical Physical and Engineering Sciences*, 366:4647–4664.
- Knutti, R., M.R. Allen, P. Friedlingstein, J.M. Gregory, G.C. Hegerl, G.A. Meehl, M. Meinshausen, J.M. Murphy, G.K. Plattner, S.C.B. Raper, T.F. Stocker, P.A. Stott, H. Teng and T.M.L. Wigley, 2008. A review of uncertainties in global temperature projections over the twenty-first century. *Journal of Climate*, 21:2651–2663.
- Krinner, G., N. Viovy, N. de Noblet-Ducoudre, J. Ogee, J. Polcher, P. Friedlingstein, P. Ciais, S. Sitch and I.C. Prentice, 2005. A dynamic global vegetation model for studies of the coupled atmosphere-biosphere system. *Global Biogeochemical Cycles*, 19:GB1015.
- Liang, X., Z.H. Xie and M.Y. Huang, 2003. A new parameterization for surface and groundwater interactions and its impact on water budgets with the variable infiltration capacity (VIC) land surface model. *Journal of Geophysical Research-Atmospheres*, 108:8613.
- Liston, G.E., 2004. Representing subgrid snow cover heterogeneities in regional and global models. *Journal of Climate*, 17:1381–1397.
- Liu, J.P., G.A. Schmidt, D.G. Martinson, D. Rind, G. Russell and X.J. Yuan, 2003. Sensitivity of sea ice to physical parameterizations in the GISS global climate model. *Journal of Geophysical Research-Oceans*, 108:3053.
- Mahfouf, J.F., A.O. Manzi, J. Noilhan, H. Giordani and M. Deque, 1995. The land-surface scheme ISBA within the Meteo-France climate model ARPEGE. Part I: Implementation and preliminary results. *Journal of Climate*, 8:2039–2057.
- Mélia, D.S., 2002. A global coupled sea ice-ocean model. *Ocean Modelling*, 4:137–172.
- Mellor, G.L. and L. Kantha, 1989. An ice-ocean coupled model. *Journal of Geophysical Research-Oceans*, 94:10937–10954.
- Miller, J.R., G.L. Russell and G. Caliri, 1994. Continental-scale river flow in climate models. *Journal of Climate*, 7:914–928.
- Milly, P.C.D. and A.B. Shmakin, 2002. Global modeling of land water and energy balances. Part I: the land dynamics (LaD) model. *Journal of Hydrometeorology*, 3:283–299.
- Nakicenovic, N. and R. Swart (Eds.), 2000. *Emissions Scenarios: A Special Report of Working Group III of the Intergovernmental Panel on Climate Change*. 599 pp. Cambridge University Press.
- O'Farrell, S.P., 1998. Investigation of the dynamic sea ice component of a coupled atmosphere sea ice general circulation model. *Journal of Geophysical Research-Oceans*, 103:15751–15782.
- Oki, T. and Y.C. Sud, 1998. Design of total runoff integrating pathways (TRIP) - A global river channel network. *Earth Interactions*, 2:1–37.
- Oleson, K.W., Y. Dai, G. Bonan, M. Bosilovich, R. Dickinson, P. Dirnmayr, F. Hoffman, P. Houser, S. Levis, G.Y. Niu, P.M.V. Thornton, Z.L. Yang and X. Zeng, 2004. Technical Description of the Community Land Model (CLM). NCAR Technical Note NCAR Technical Note NCAR/TN-461+STR, 186 pp. National Center for Atmospheric Research, Boulder, Colorado.
- Overland, J.E., 2009. The case for global warming in the Arctic. In: Nihoul, J.C.J. and A.G. Kostianoy (Eds.). *Influence of Climate Change on the Changing Arctic and Sub-Arctic Conditions*, pp. 13–23, Springer.
- Overland, J.E. and M. Wang, 2007. Future regional Arctic Sea ice declines. *Geophysical Research Letters*, 34:L17705.
- Radić, V. and R. Hock, 2006. Modeling future glacier mass balance and

- volume changes using ERA-40 reanalysis and climate models: A sensitivity study at Storglaciaren, Sweden. *Journal of Geophysical Research-Earth Surface*, 111:F03003.
- Raisanen, J., 2007. How reliable are climate models? *Tellus Series A*, 59:2-29.
- Randall, D.A., R.A. Wood, S. Bony, R. Colman, T. Fichet, J. Fyfe, V. Kattsov, A. Pitman, J. Shukla, J. Srinivasan, R.J. Stouffer, A. Sumi and K. Taylor, 2007. Climate models and their evaluation. In: Solomon, S., D. Qin, M. Manning, Z. Chen, M. Marquis, K.B. Averyt, M. Tignor and H.L. Miller (Eds.). *Climate Change 2007: The Physical Science Basis. Working Contribution of Working Group I to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change* Cambridge University Press.
- Reichler, T. and J. Kim, 2008. How well do coupled models simulate today's climate? *Bulletin of the American Meteorological Society*, 89:303-311.
- Reifen, C. and R. Toumi, 2009. Climate projections: Past performance no guarantee of future skill? *Geophysical Research Letters*, 36:L13704.
- Roeckner, E., K. Arpe, L. Bengtsson, M. Christoph, M. Claussen, L. Dümenil, M. Esch, M. Giorgetta, U. Schlese and U. Schulzweida, 1996. *The Atmospheric General Circulation Model ECHAM4: Model Description and Simulation of Present-Day Climate*. MPI Report, 218, 94 pp. Max-Planck-Institut für Meteorologie, Hamburg, Germany.
- Sato, N., P.J. Sellers, D.A. Randall, E.K. Schneider, J. Shukla, J.L. Kinter, Y.T. Hou and E. Albertazzi, 1989. Effects of implementing the simple biosphere model in a general circulation model. *Journal of the Atmospheric Sciences*, 46:2757-2782.
- Schmidt, G.A., C.M. Bitz, U. Mikolajewicz and L.B. Tremblay, 2004. Ice-ocean boundary conditions for coupled models. *Ocean Modelling*, 7:59-74.
- Sellers, P.J., Y. Mintz, Y.C. Sud and A. Dalcher, 1986. A simple biosphere model (SiB) for use within general circulation models. *Journal of the Atmospheric Sciences*, 43:505-531.
- Semtner, A.J., 1976. A Model for the thermodynamic growth of sea ice in numerical investigations of climate. *Journal of Physical Oceanography*, 6:379-389.
- Serreze, M.C. and J.A. Francis, 2006. The Arctic amplification debate. *Climate Change*, 76:241-264.
- Solomon, S., D. Qin, M. Manning, Z. Chen, M. Marquis, K.B. Averyt, M. Tignor and H.L. Miller (Eds.), 2007. *Contribution of Working Group I to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change*, 2007. 996 pp. Cambridge University Press.
- Sorteberg, A., V. Kattsov, J.E. Walsh and T. Pavlova, 2007. The arctic surface energy budget as simulated with the IPCC AR4 AOGCMs. *Climate Dynamics*, 29:131-156.
- Stoner, A.M.K., K. Hayhoe and D.J. Wuebbles, 2009. Assessing general circulation model simulations of atmospheric teleconnection patterns. *Journal of Climate*, 22:4348-4372.
- Toyota, T., T. Kawamura, K.I. Ohshima, H. Shimoda and M. Wakatsuchi, 2004. Thickness distribution, texture and stratigraphy, and a simple probabilistic model for dynamical thickening of sea ice in the southern Sea of Okhotsk. *Journal of Geophysical Research-Oceans*, 109:C06001.
- Verseghy, D.L., N.A. McFarlane and M. Lazare, 1993. A Canadian land surface scheme for GCMs: II. Vegetation model and coupled runs. *International Journal of Climatology*, 13:347-370.
- Volodin, E.M. and V.N. Lykosov, 1998. Parametrization of heat and moisture transfer in the soil-vegetation system for use in atmospheric general circulation models: I. Formulation and simulations based on local observational data. *Izvestiya Akademii Nauk Fizika Atmosfery i Okeana*, 34:453-465.
- Walsh, J.E., W.L. Chapman, V. Romanovsky, J.H. Christensen and M. Stendel, 2008. Global Climate Model Performance over Alaska and Greenland. *Journal of Climate*, 21:6156-6174.
- Wang, M. and J.E. Overland, 2009. A sea ice free summer Arctic within 30 years? *Geophysical Research Letters*, 36:L07502.
- Wang, S.S., R.F. Grant, D.L. Verseghy and T.A. Black, 2002. Modelling carbon dynamics of boreal forest ecosystems using the Canadian Land Surface Scheme. *Climatic Change*, 55:451-477.
- Wang, M., J.E. Overland, V. Kattsov, J.E. Walsh, X.D. Zhang and T. Pavlova, 2007. Intrinsic versus forced variation in coupled climate model simulations over the Arctic during the twentieth century. *Journal of Climate*, 20:1093-1107.
- Winton, M., 2000. A reformulated three-layer sea ice model. *Journal of Atmospheric and Oceanic Technology*, 17:525-531.
- Wolff, J.-O., E. Maier-Reimer and S. Lebutke, 1997. *The Hamburg Ocean Primitive Equation Model (HOPE)*. DKRZ Technical Report, 13, 110 pp. Deutsches KlimaRechenZentrum, Hamburg, Germany.
- Wu, Q.G., D.J. Karoly and G.R. North, 2008. Role of water vapor feedback on the amplitude of season cycle in the global mean surface air temperature. *Geophysical Research Letters*, 35:L08711.
- Zhang, Y.X., W. Maslowski and A.J. Semtner, 1999. Impact of mesoscale ocean currents on sea ice in high-resolution Arctic ice and ocean simulations. *Journal of Geophysical Research-Oceans*, 104:18409-18429.
- Zhang, J., U.S. Bhatt, W.V. Tangborn and C.S. Lingle, 2007. Climate downscaling for estimating glacier mass balances in northwestern North America: Validation with a USGS benchmark glacier. *Geophysical Research Letters*, 34:L21505.

4. Changing Snow Cover and its Impacts

COORDINATING LEAD AUTHORS: TERRY V. CALLAGHAN, MARGARETA JOHANSSON

LEAD AUTHORS: ROSS D. BROWN, PAVEL YA. GROISMAN, NIKLAS LABBA, VLADIMIR RADIONOV

CONTRIBUTING AUTHORS: ROGER G. BARRY, SYLVIE BLANGY, RAYMOND S. BRADLEY, OLGA N. BULYGINA, TORBEN R. CHRISTENSEN, JONATHAN COLMAN, RICHARD L.H. ESSERY, BRUCE C. FORBES, MADS C. FORCHHAMMER, DIMITRY M. FROLOV, VLADIMIR N. GOLUBEV, THOMAS C. GRENFELL, RICHARD E. HONRATH[†], GLENN P. JUDAY, RAE MELLOH, ANNA V. MESHCHERSKAYA, MARINA N. PETRUSHINA, GARETH K. PHOENIX, JOHN POMEROY, ARJA RAUTIO, VYACHESLAV N. RAZUVAEV, DAVID A. ROBINSON, PETER ROMANOV, NIELS M. SCHMIDT, MARK C. SERREZE, VLADIMIR SHEVCHENKO, ALEXANDER I. SHIKLOMANOV, DREW SHINDELL, ANDREY B. SHMAKIN, PETER SKÖLD, SERGEY A. SOKRATOV, MATTHEW STURM, STEPHEN WARREN, MING-KO WOO, ERIC F. WOOD, DAQUING YANG

Contents

Key Findings	2	4.7. Conclusions: the human face of snow change	43
Summary	2	4.7.1. Opportunities and challenges	43
4.1. Introduction	4	4.7.2. 'Winners and losers'	43
4.2. Basic snow characteristics from an Arctic perspective	5	4.7.3. Need for policy development	43
4.2.1. Characteristics and definitions of Arctic snow	5	Acknowledgments	43
4.2.2. Role of snow cover in the Arctic climate system	7	Appendix 4.1. Existing sources for data and information on Arctic snow cover	44
4.3. Changes in snow regime and properties	8	References	47
4.3.1. Observed changes in Arctic snow cover and snowfall ..	8		
4.3.2. Projected changes in snow cover and its characteristics	16		
4.4. Evaluation of the impacts of a changing snow cover and its characteristics	19		
4.4.1. Changes in snow cover and impacts on climate processes	20		
4.4.2. Changes in the hydrological cycle at the local and regional scale	22		
4.4.3. Ecological processes and the role of snow cover	24		
4.4.4. Socio-economic processes and the role of snow cover	30		
4.5. Suggested strategies for local and regional adaptation	35		
4.5.1. Natural adaptations	36		
4.5.2. Adaptations in infrastructure maintenance and development	37		
4.5.3. Adaptations in land and resource use	37		
4.5.4. Provision of knowledge (scientific and traditional) for adaptation	38		
4.6. Uncertainties, gaps, and recommendations	39		
4.6.1. Major issues	40		
4.6.2. Detailed issues	40		

Key Findings

- Snow cover changes over the Arctic in response to warming and increasing winter precipitation occur at different rates and in different directions depending on the season, region, and snow cover variable.
- Changes in Arctic snow cover are contributing to changes in the Arctic thermal and hydrological regimes, with important implications for permafrost, Arctic ecology, and snow-vegetation-climate feedbacks.
- Climate model projections of changes in Arctic snow cover over the next 50 years from the models used in the IPCC Fourth Assessment are generally consistent with observed trends, but they have large uncertainties.
- The changing Arctic snow climate is already generating widespread human, ecological, and economic impacts, which will probably intensify in the future. Impacts can be beneficial or deleterious.
- Adapting to changing snow cover conditions is an ongoing process; however, the current rate of change, together with new constraints, will challenge adaptive capacity.

Summary

Snow is a dominant feature of the Arctic terrestrial landscape for eight to ten months of the year. Its extent, dynamics, and properties affect climate, human activities (including socio-economics and culture), infrastructure, hydrological processes, permafrost, hazards, biodiversity, and ecosystem processes. This chapter provides a baseline assessment of recent past and projected future changes in snow cover and their likely consequences.

Observed changes in snow

Major advances have been made in the ability to monitor Arctic snow cover from space over the past ten years from sensors such as MODIS, AMSR-E and QuikSCAT, but a number of significant challenges remain for documenting past variability and rates of change. These include major gaps in observing networks, unrepresentative observations, and inconsistencies in analysis products. The provision of reliable precipitation information over the Arctic is an ongoing key challenge as the observations are prone to significant random errors and biases and automation of observations has created new challenges for maintaining the integrity and quality of observations.

Analysis of *in situ* and satellite snow cover data shows evidence of different regional snow cover responses to the widespread warming and increasing winter precipitation that have characterized the Arctic climate for the past 40 to 50 years. The largest and most rapid decreases in snow water equivalent (SWE) and snow cover duration (SCD) are observed over maritime regions of the Arctic with the highest precipitation amounts (Alaska, northern Scandinavia, and the Pacific coast region of Russia). There is also evidence of marked differences in the response of snow cover between the North American and Eurasian sectors of the Arctic, with the North American sector exhibiting decreases in snow cover and snow depth over the entire period of available *in situ* observations from around 1950, while widespread decreases in snow cover are not apparent over Eurasia until after around 1980. However, snow depths are increasing in many regions of Eurasia. This discrepancy warrants further study as both continents have experienced significant increases in winter precipitation over the past 50 years.

Seasonal differences in observed changes in snow cover are also marked, with most of the decreases in SCD occurring in the spring period, consistent with stronger warming and positive snow- and ice-albedo feedbacks in the spring and the effect of black carbon in decreasing snow albedo (reflectivity of the snow). New analyses of *in situ* observations and satellite data show stronger decreases in snow cover in Arctic coastal regions than inland that are likely to be in response to earlier sea-ice disappearance.

Warming and more frequent winter thaws are contributing to changes in snowpack structure, which has important implications for land use and provision of ecosystem services. For example, increased numbers of winter thaws and rain-on-snow events are associated with an increase in potential for ice crust formation, but a shorter melt season has been found to reduce the frequency of basal ice formation over the Russian Arctic west of the Taymir Peninsula. Surface crusts and basal ice layers hinder the ability of reindeer/caribou and other animals to feed.

Projected changes in snow cover

Although climate model projections of changes in Arctic snow cover over the next 50 years from the models used in the Fourth Assessment of the Intergovernmental Panel on Climate Change (IPCC) are for the most part consistent with observed trends, there are large uncertainties in the projections related to inadequacies in the representation of Arctic climate, snow processes, and snow-albedo feedbacks. Further uncertainties arise because important Arctic snow processes such as blowing snow and vegetation interactions are not included, there are large model differences in snow-albedo feedbacks, and models tend to have cold-wet biases over higher latitudes.

The CMIP3 (Coupled Model Intercomparison Project phase 3) general circulation model (GCM) consensus of projected changes in snow cover over the Arctic in response to increasing greenhouse gas concentrations in the atmosphere shows three regions of SWE response: significant decreases in maximum SWE over temperate regions such as Scandinavia; a broad zone over the boreal forest region without statistically significant changes; and a northernmost zone of increased maximum SWE over northern Siberia and the Canadian Arctic Archipelago. In contrast, SCD is projected to decrease over the entire Arctic with the largest and earliest changes over more temperate regions and the smallest and slowest changes over high latitudes. The magnitude of the projected changes by 2050 is in the range 0–15% for maximum SWE over much of the Arctic, with the largest increases (15–30%) over the Siberian sector. Annual SCD is projected to decrease by about 10–20% over much of the Arctic, with the smallest decreases over Siberia (<10%) and the largest decreases over Alaska and northern Scandinavia (30–40%).

Impacts

Changes in precipitation and temperature are expected to dramatically change the hydrological regime of the Arctic by affecting snow accumulation and melt, evaporation, and runoff as well as short- and long-term water storage changes. However, the net hydrological balance for ecosystems and biogeochemical cycling is uncertain.

Arctic ecological processes interact with snow cover in many complex ways. Vegetation affects interception, sublimation, snow trapping, energy exchanges, hydrology, and accumulation and ablation of snow. Snow provides protection for vegetation from extreme environments and provides water in the spring. Interactions between snow and current and projected advances of shrubs and trees into the tundra are expected to amplify warming in the Arctic. Changing snow conditions also affect biogeochemical cycles. The date of the onset of snow melt is a good predictor of annual atmospheric carbon accumulation as the timing and duration of the snow-free season control the growing season for vegetation. Geochemical processes in the snowpack affect the concentrations of trace gases in the Arctic's lower atmosphere. Deposition of contaminants to snowpacks concentrates many compounds, some of which can be hazardous as they move through the food chain. A shorter snow period would reduce the period for accumulation.

Socio-economic consequences

Projected changes in the hydrological cycle will have impacts on several commercial sectors. A more even water discharge, resulting from changes in snow cover, will affect the capacity and operations of current and future hydroelectric developments and might solve some of the rising energy needs. Despite reduction in snow cover in the Arctic, the northward retreat of snow cover in mid-latitudes may provide new opportunities for snow-based tourist activities in the Arctic. However, changes in the consistency of the snowpack and the unpredictability of snow conditions could lead to negative experiences for tourists and even an increased frequency of hazards such as snow avalanches and slush torrents. Furthermore, reduced Arctic snow cover is already limiting the productivity of some forests. Although boreal forestry is expected to become more productive and move northward during climate warming, snow is an important source of water that might become limiting. As snow cover is reduced and rainfall increases, broadleaf trees will have more advantage than conifers, thereby decreasing carbon storage and negatively impacting the forest economy. Changing snow conditions have already damaged valuable timber species leading to the loss of millions of hectares of trees.

Traditional land use is tightly coupled to snow conditions. Snow depth, distribution within the landscape, timing of snow onset and thaw, extreme climate events in winter, and the physical properties of snow throughout the profile of the snowpack all have impacts on the general activities of Arctic residents such as transport, herding, hunting and fishing and other forms of land use.

Effects of climate change on human health include direct impacts (such as those caused by changes in temperature, snow cover, and ultraviolet light) and indirect impacts (such as those caused by climate-induced changes in wildlife and the diseases that they share with humans). The impact of changing snow on subsistence wildlife species is critical to the diet of indigenous residents, and its impact on recreation and mobility could affect psychosocial stress. Already, many Arctic indigenous people and other residents have high and increasing mortality rates from work-related accidents sustained while undertaking hazardous tasks in harsh environments.

Adaptation and mitigation

Arctic communities have limited ability to mitigate likely future changes in snow, and limited ability to migrate as in the past, so they must adapt to transitional snow regimes. However, they cannot migrate as freely as during historic climatic changes. Adaptation will be necessary in the areas of infrastructure maintenance and development, land use and resource management, reindeer herding, conservation, tourism, hunting and fishing, agriculture, and forestry. Flexibility, diversification, and investment will be required to ensure successful adaptation. However, despite their ability to adapt, Arctic peoples' subsistence livelihoods are likely to become more insecure, and there is likely to be a shift from a mixed economy to a market-based economy that will have significant cultural implications.

Improved monitoring and forecasting of snow conditions (including projections of future changes) are needed at the local scale to assist adaptation. The provision of relevant information from scientists requires the active involvement of community

members; local, regional, and national organizations; and decision- and policy-makers. Greater engagement is also needed between the scientific community and Arctic residents in order to incorporate traditional knowledge in the design and interpretation of monitoring and modeling studies.

The multitude of impacts responding to changing snow conditions provides challenges and opportunities. The ability to adapt to the challenges and respond to the opportunities will vary between urban and rural populations and the Arctic and global communities: there will be winners and losers. Policy development is required to enhance the adaptation potential and opportunities and to minimize the challenges for the potential losers.

4.1. Introduction

Frozen precipitation accumulating on a surface creates a snow cover. Snow is an important and dominant feature of Arctic terrestrial landscapes with cover present for eight to ten months of the year. Its extent, dynamics, and properties (e.g., depth, density, water equivalent, grain size, and changes in structure throughout its vertical profile) affect climate (e.g., ground thermal regime), human activities (e.g., transportation, resource extraction, water supply, use of land, and ecosystem services), as well as infrastructure, hydrological processes, permafrost, extreme events (including hazards such as avalanches and floods), biodiversity, and ecosystem processes. Snow is therefore a significant component in the socio-economics of Arctic societies. Snow also has a number of important linkages to other components of the cryosphere (see Chapter 11). Large-scale anomalies in snow cover extent, depth, and water equivalent tend to persist for longer (for months or even for most of the cold season) than the synoptic conditions through which they were initially caused. Therefore, snow cover at monthly to seasonal timescales becomes one of the few significant memory components of the Earth's climate system and is used in long-term weather forecasting, which has many profound implications for people. Over millennia, snow has provided an archive of past environments and climates that is currently being used to investigate the causes of climate change (see also Chapter 8 on the Greenland Ice Sheet).

Air temperature and precipitation are the main drivers of regional-scale snow cover variability over the Arctic region, with local-scale variability in snow cover related to interactions with vegetation cover and terrain through processes such as blowing snow, canopy interception, and sublimation (when water changes directly from solid to vapor form without thawing) (King et al., 2008). Impurities in the snowpack (e.g., leaf litter and organic and black carbon) contribute to local (landscape) and regional (circum-Arctic) variations in surface albedo, which influence the surface energy budget and spring season melt rates. Over Eurasia, the climate-forcing effect of surface deposition of organic and black carbon in reducing snow surface albedo is estimated to be of the same order of magnitude as that of anthropogenic carbon dioxide (Flanner et al., 2008; Grenfell et al., 2009).

Observational data show that the Arctic's land area has experienced a significant poleward amplification of global warming trends and increased precipitation over the past several decades (Déry and Brown, 2007; Trenberth et al., 2007; Min et

al., 2008). These changes are driving widespread reductions in snow cover duration, particularly in the spring period when the melt is earlier, as well as increased snow accumulation in some regions of northern Eurasia (Kitaev et al., 2005; Bulygina et al., 2009). The changes are also driving increased frequencies of rain-on-snow and mid-winter melt events in some regions of the Arctic (Groisman et al., 2003; Burn et al., 2004).

These trends in the main drivers of snow variability are likely to continue. According to the IPCC Fourth Assessment (IPCC AR4) (Christensen et al., 2007), the Arctic is very likely to warm during the 21st century, particularly during winter. Annual Arctic winter precipitation is also considered very likely to increase. This degree of certainty in projected precipitation changes is higher over the Arctic than other regions of the globe as there is a high level of consistency between climate model projections of precipitation changes in this region. The CMIP3 suite of coupled climate models (Meehl et al., 2007) projects reduced SCD over the Arctic with increased annual maximum snow accumulation over the northern extremities of both continents (Lemke et al., 2007; Räisänen, 2007; Brown and Mote, 2009). However, the rate and magnitude of the snow cover response to changing climatic conditions is expected to vary considerably due to regional differences in projected climate change and differing regional and elevational sensitivities of snow to climate change (Brown and Mote, 2009). The response of snowpack properties to a changing climate is also potentially complex to project, because in addition to affecting start and end dates of snow cover, changes in air temperature affect the fraction of precipitation falling as snow, rain-on-snow events, freeze-thaw events, the density of snowfall, and the density of snow on the ground. Increasing winter precipitation may result in increased accumulation in some areas, while enhanced growth of Arctic shrubs in response to warming (e.g., Sturm et al., 2001b; Forbes et al., 2010) may result in local increases in snow cover accumulation independent of increases in precipitation.

Changing snow cover in the Arctic has many complex implications for the natural world and for the economic development of society, including indigenous peoples and other Arctic residents, through changes in the physical environment and the associated impacts on climate feedbacks, water resources, infrastructure, and ecosystem services. For example, reductions in snow cover extent and duration as well as decreased reflectance from accumulation of black carbon and dynamic vegetation interactions provide positive feedbacks to the climate system in that they enhance the rate of warming over the Arctic (Hansen and Nazarenko, 2004). In addition, it is anticipated that future variations in snow depth may dramatically change the hydrological regime of the Arctic (Adam et al., 2009), which in turn will affect water resources, transportation, and ecosystem services. Changes in snow accumulation will also affect the ground thermal regime with impacts on permafrost temperature and distribution. Changes in snow regime and their effects on permafrost affect hydrology, infrastructure (buildings, runways, pipelines, transport routes), and ecosystems (see Chapter 5). Changes in snowfall regime (amount, timing, and phases of water or snow) over the Greenland Ice Sheet and other Arctic glaciers and ice sheets will affect the mass balance of the ice (see Chapters 7 and 8), while more frequent mixed-precipitation

events and rain-on-snow events will have adverse impacts on biodiversity, animal populations, vegetation, and ecosystem processes. Changes in snow accumulation also affect freshwater availability and sea-ice growth rates, light transmission through ice, and ice dynamics (see Chapter 9). Deposition of airborne contaminants on snowpacks concentrates many chemical compounds. Snowpack chemical reactions affect nitrogen oxides, halogens, ozone, organic compounds, and mercury, which affect people and terrestrial, freshwater, and marine Arctic ecosystems (AMAP, 1998, 2009).

The identification of snow-related vulnerabilities and sensitivities, together with some assessment of the uncertainties involved, is essential to determine the information required for developing adaptation responses and policies. Arctic societies have constantly adapted to changing climatic conditions, but their increasing reliance on urban environments and infrastructure now limits some of their options (Chapin et al., 2004). However, current ability to predict future changes in climate provides advanced warning of impacts and opportunities that will allow early development of adaptation strategies. In addition, development of climate downscaling techniques provides some of the tools required for adaptation planning.

Although changes in snow cover and its properties are already significant and future changes will have many socio-economic and other implications, snow has not been treated authoritatively in previous assessments. For example, the Arctic Climate Impact Assessment (ACIA, 2005), dedicated relatively little space to snow dynamics and the response of the Arctic snow cover to climate change simulated by the CMIP3 models did not receive much attention in the IPCC AR4 (Solomon et al., 2007). For these reasons, this chapter cannot use the ACIA report or the IPCC AR4 as benchmarks, and so draws on earlier, as well as more recent work, to provide a new benchmark.

This chapter aims to provide a synthesis of current knowledge of existing and projected changes in Arctic snow cover (including various properties of snow) and the likely impacts on society. The chapter presents basic information on snow characteristics and their relevance to the natural world and to society, charts recent changes in snow conditions, and synthesizes new projections of changes in snow and their implications. The information is used to highlight how adaptations to changing snow conditions might occur in the natural world and how society might develop socio-economic adaptation strategies. Data are drawn from many different sources, including monitoring programs, field experiments, model output, and traditional knowledge of indigenous peoples. There is a particular focus on knowledge from new sources such as International Polar Year (IPY) projects. The chapter ends by listing important gaps in understanding and recommends priority actions.

4.2. Basic snow characteristics from an Arctic perspective

- Snow is a dominant feature of the Arctic landscape persisting for eight to ten months of the year.
- Snow depth, extent, duration, timing, water equivalent, and stratigraphy have many consequences for the climate system, hydrology, permafrost, ecology, biogeochemical cycling, and socio-economics.

4.2.1. Characteristics and definitions of Arctic snow

Frozen precipitation accumulating on a surface creates a snow cover. In the Arctic, snow covers land and ice surfaces for eight to ten months of the year, with important regional gradients in duration and amount related to topography and regional variations in temperature and precipitation. A summary of the key features of the Arctic snow cover is provided in Box 4.1 (see Sturm et al., 1995 and Fierz et al., 2009 for scientific terminologies).

There is a wide range of regularly observed snow cover information in the Arctic from *in situ* and satellite observations (see Appendix 4.1 for a detailed discussion). The SCD on the ground is one of the best-observed variables in terms of resolution and longevity. Snow depth and SWE (the depth of liquid water that would result from melting the snow) are more difficult to monitor due to their high spatial variability, large gaps in the *in situ* observing networks, and difficulties in monitoring from satellites. Information on snow density and surface properties is important for transportation and reindeer herding in the Arctic; however, these properties are routinely measured at only a limited number of research stations outside the Russian Federation, where they form part of the snow course observation routine at the national meteorological network, in operation since 1966 (Bulygina et al., 2010a). In some remote areas, for example in Zackenberg (northeast Greenland), a digital camera placed in a weatherproof box with battery and solar cells has been used to record snow depth on stakes during winter and then collected during summer when the site was visited (Hinkler et al., 2002). Long-term records of snow characteristics in the Arctic are rare, with the exception of the record since 1913 from Abisko in the Swedish sub-Arctic (Kohler et al., 2006; Callaghan et al., 2010).

The indigenous peoples of the Arctic have a profound knowledge of changing snow conditions of practical importance for survival, which has been passed from generation to generation. Languages, such as the Sámi language and Inuktitut, have many terms to describe snow cover related to migrations and transportation, hunting, and reindeer herding (Ryd, 2001). The snow surface is often described from a mobility perspective, while the descriptions of snow layers detail animals' ability to find grazing. Such knowledge has created and preserved the way of life for indigenous peoples in the Arctic (e.g., Ryd, 2001; Roturier and Roue, 2009) and this depth of understanding cannot be fully captured in standard weather and hydro-meteorological monitoring programs.

Box 4.1. Arctic snow cover

The characteristics of Arctic snow cover are the result of a complex interplay of atmospheric and surface processes that determine not only the quantity of water stored as snow, but also snowpack condition (e.g., grain size, density, ice layers). The amount of snow accumulating on a surface is influenced by precipitation amount, type, and timing; blowing snow transport and sublimation; and vegetation interception. However, the character and evolution of high-latitude snowpack has the additional complexity of being particularly strongly dependent on blowing snow processes with the distribution and physical properties of snow on the ground closely linked to local-scale variability in terrain and vegetation (King et al., 2008).

The key large-scale physiographic and climatic factors influencing the regional distribution of Arctic snow cover (see Figure 4.1) are elevation, amount of vegetation cover, spatial distribution of freezing temperatures, and location of the main cyclone tracks bringing moisture into the Arctic. Air temperature and elevation exert the strongest influences on the distribution of SCD across the Arctic (Figure 4.1e) with both continents exhibiting marked east-west increases in snow cover in response to the modification of winter air

masses over the cold, dry continental interiors. Land areas in the zone of -20°C temperatures (see darker blue area in Figure 4.1c) experience snow cover for most of the year, and climate models suggest that these areas will see increased snow accumulation in the future (Räsänen, 2007). The spatial distribution of SWE is more complex than SCD but is basically driven by moisture availability over the snow season, reflected in the cyclone frequency map (Figure 4.1d). The highest snow accumulations in the Arctic are located in the coastal mountain regions and considerably more moisture penetrates into the western sector of the Eurasian Arctic than North America, where the coastal mountains block moisture entering from the Pacific Ocean. Regions with winter temperatures closer to freezing, such as Scandinavia and the Pacific coasts of Russia and Alaska, are also more likely to experience thaw and rain-on-snow events that create ice layers in the snowpack. Snow cover in these maritime regions of the Arctic has been shown to be more sensitive to temperature changes (Brown and Mote, 2009).

The high winds, low temperatures and low snowfall amounts over the exposed tundra regions of the Arctic produce a snow cover that is typically quite shallow, about 30 to 40 cm (except in drifts and gullies), with a wind-hardened




Figure 4.1. Basic characteristics of the Arctic related to snow cover: (a) elevation distribution over the Arctic from the GTOPO30 dataset, (b) tree fraction from 500-m resolution MODIS Vegetation Continuous Field product (Hansen et al., 2003), (c) 0°C and -20°C mean winter isotherms (November–May) for the period 1970 to 1999, from the NCEP Reanalysis, (d) October to March cyclone frequency from the NCEP Reanalysis for the period 1958 to 1997 from Key and Chan (1999), (e) mean annual snow-cover duration for the period 1998 to 2007 from the NOAA IMS 24 km product (Ramsay, 1998), (f) mean annual maximum snow-water equivalent for the period 1998 to 2007 from the Canadian Meteorological Centre snow depth analysis (Brasnett, 1999).

surface layer ('wind slab') overlying a less dense depth hoar ('sugar snow') layer (Derksen et al., 2010). The average snow density remains close to 300 kg/m³ over much of the snow season, but snow depth and properties can exhibit strong local variation with many exposed areas, drifts, dunes, and sastrugi (sharp irregular ridges on the snow surface formed by wind erosion and deposition). In forested regions of the Arctic (taiga/boreal forest), snow cover is more uniform and less dense (~200 kg/m³) as the trees act as windbreaks and shade the snow from incoming solar radiation in the spring (McKay and Gray, 1981). In contrast, north of the treeline, where wind action compacts the snow, snow density is higher.

The average seasonal evolution of snow depth and density at three Canadian Arctic sites in different climate regimes – Fort Reliance in the sub-humid high boreal zone, Baker Lake in the low Arctic zone, and Clyde in the High Arctic zone (zones as defined by Environment Canada, 1989) – show characteristic linear increases in SWE and snow density over the snow season typical of Arctic snow cover (Figure 4.2). Clyde has the largest accumulations of the three sites due to its location on the east coast of Baffin Island where winter cyclones are more frequent (Figure 4.1d).

Snow is critically important to the lifestyle and well-being of indigenous peoples. The Inuit have a rich snow vocabulary with many of the words related to uses of snow for drinking water, making shelters, and trafficability (see 'snow' in the online English-Inuktitut-French glossary maintained by Nunavut Arctic College at www.btb.gc.ca/btb.php?lang=eng&cont=202#s). Similarly, the Sámi have a rich vocabulary, but this also relates to snowpack conditions relevant to reindeer herding practices (Ryd, 2001).




Figure 4.2. Mean seasonal evolution of snow-water equivalent and snow density for the period 1965 to 1994 for three stations along an east-west transect over the Canadian Arctic representing a typical snow season in the Arctic. Source: data from Meteorological Service of Canada (2000).

4.2.2. Role of snow cover in the Arctic climate system

Snow cover has a number of important physical properties that exert an influence on climate or moderate its effects (see Cohen and Rind, 1991). It has high short-wave albedo, high thermal emissivity, low heat conductivity, large latent heat of fusion, and low surface roughness while it stores and rapidly releases water in the melt season. The combination of high albedo (as high as 0.8 to 0.9 for dry snow) and low thermal conductivity promotes low surface temperatures and low-level temperature inversions. The low thermal conductivity of snow allows it to insulate the surface from large energy losses in winter, and this has major implications for the energy and moisture fluxes in the near-surface layers. Consequently, the insulating effect has a strong impact on ice growth rates and ice thickness and on the development of seasonally frozen ground and permafrost. The surface energy exchanges are further modified by the low aerodynamic roughness of snow cover, which can reduce turbulence and, hence, vertical transfer of energy. On some occasions, sastrugi and wind scoops may negate the streamlined surface by interaction with turbulence of strong winds and may act as a feedback loop to enhance turbulence over snow cover. However, the major snow impact on surface roughness is its reduction.

Onset of snow cover is associated with an abrupt drop in surface air temperature (by up to 10 °C; Voeikov, 1952; Leathers and Robinson, 1993; Groisman et al., 1997). This is mostly caused by a dramatic decrease in the surface energy budget due to the high reflectivity of newly established snow cover that enhances and stabilizes the temperature decrease. However, about half of the temperature decrease is caused by the weather factors that have already decreased air temperature (i.e., the cold fronts that brought snowfall in the first place) (Voeikov, 1952; Lamb, 1955; Leathers et al., 1995). In the mid-latitudes, it is usually a few weeks between the first snowfall and the formation of a continuous snow cover, but in the Arctic one major snowstorm in autumn may be enough to generate a continuous snow cover, because there is insufficient energy at this time to reverse the state of the ground to snow-free conditions. For example, at 60° N in October over Eurasia the surface radiation budget is in the range of ± 10 W/m² (see Figure 17 in Groisman and Bartalev and NSPD Team, 2007), which is insufficient for appreciable snow melt. Thus, once established, snow cover feedbacks tend to support the continuing existence of the snow cover. A number of studies have shown that large-scale snow cover anomalies can play a significant role in global-scale atmospheric circulations that act over timescales of seasons to years (Groisman et al., 1994a; Gong et al., 2004; Fletcher et al., 2009a,b).

When snow cover is established, its insulating properties affect both the surface and the near-surface temperature regime. Soil surface temperature in mid-winter under 50 cm of snow may be around zero, while the air temperature above the snowpack is as low as -20 °C (Pomeroy and Brun, 2001). The insulating role of snow prevents deep freezing of near-surface ground, which has important implications for the active layer and for permafrost (see Chapter 5), as well as for the runoff response in spring and for ecological and biogeochemical processes. In the permafrost areas of the Arctic, variations in

snow cover depth (rather than surface air temperature) are a major factor controlling temperature variability in the upper 3 m of soil. Due to an increasing winter snow depth in these regions, soil warming trends are observed even at locations with cooling trends in surface air temperature (Bulygina et al., 2007, 2009). At these sites, the contribution of the mean annual air temperature to the total variance of soil temperature at 160 cm is less than 5%, while the contribution of the snow depth is 30% (Sherstyukov et al., 2008).

During spring, when there are large amounts of incoming solar radiation (greater than 100 W/m^2), the presence of snow on the ground effectively delays warming. This is because of the still relatively high reflectivity of melting snow (albedo ~ 0.5 to 0.7) compared to other surfaces, such as soil, vegetation, or ponds on the ground or on sea ice, and the energy required to melt it. The large amount of energy required to melt snow means that near-surface spring temperatures stay close to 0°C with frequent melt-and-refreeze cycles until the snow cover becomes discontinuous. These freeze-thaw cycles are readily observable with satellite data (Rawlins et al., 2005; Bartsch et al., 2007). Once the snow cover becomes discontinuous, the melting process becomes rapid owing to advection of energy from snow-free patches (Marsh et al., 1997). Nevertheless, even with high levels of insolation it may take more than a month for the snowpack to disappear completely in regions with a deep snow cover, in shaded areas, or where deep drifts have formed (Ramage et al., 2007).

Changes in snow cover over the Arctic region, particularly in spring, have a strong impact on regional energy budgets owing to the large amount of incoming solar energy reaching the snow surface (Groisman et al., 1994a,b; Déry and Brown, 2007). From a modeling study, Euskirchen et al. (2007) estimated that a pan-Arctic reduction in snow cover of 0.22 d/y over the 1970 to 2000 period of warming contributed an additional 0.8 W/m^2 per decade of energy. Their simulation also showed evidence of regional asymmetry in Arctic snow-albedo feedback with stronger heating contributions over the North American sector from loss of snow cover. Recent work by Fernandes et al. (2009) highlighted the importance of snow metamorphism (or aging) in the albedo feedback with their satellite-based analysis showing that snow metamorphism was as important as loss of snow cover in determining the total terrestrial snow-albedo feedback over Eurasia.

4.3. Changes in snow regime and properties

- Snow-cover duration has decreased. The largest and most consistent change in snow cover is earlier disappearance of snow in spring, averaging 3.4 days per decade over the pan-Arctic terrestrial region (excluding Greenland) during 1972 to 2009. The larger response in spring compared with autumn (0.5 days per decade) is consistent with greater positive snow-albedo and black carbon feedbacks in spring.
- Snow-cover extent has decreased. Data from visible satellite imagery show that Arctic snow cover extent in May and June decreased by an average of 18% over the 1966 to 2008 period of the National Oceanic and Atmospheric Administration (NOAA) record.

- Rates of change in SWE and SCD vary across the Arctic. The largest decreases in SWE and SCD occur in maritime regions of the Arctic (Alaska, northern Scandinavia, and the Pacific coast region of Russia), while new analyses show stronger decreases in Arctic coastal regions than inland.
- Snow depth changes have differed between North America and Eurasia over the past 50 years. Many regions of Eurasia exhibit increasing maximum *in situ* snow depth trends, while North American sites show decreasing trends, although both continents have experienced significant increases in winter precipitation over the past 50 years.
- There is new evidence of changes in snowpack structure, such as more frequent ice crust formation resulting from more frequent winter thaws and rain-on-snow events. These changes have important implications for land use and provision of ecosystem services.
- Annual SCD is projected to decrease. Decreases by 10–20% over most of the Arctic by 2050 are projected, with the smallest decreases over Siberia ($<10\%$) and the greatest losses over Alaska and northern Scandinavia (30% to 40%). The earliest and largest decreases in SCD and snow accumulation are projected to occur over coastal regions of the continents in agreement with observed trends.
- Slight increases in maximum snow accumulation are projected. Increases of 0–15% are projected over much of the Arctic with the largest increases (15–30%) over the Siberian sector.
- The frequency and areal extent of rain-on-snow events are projected to increase over all regions of the Arctic over the next 50 years.

4.3.1. Observed changes in Arctic snow cover and snowfall

4.3.1.1. Changes in solid precipitation

In the Atlantic, North European, and West Siberian sectors (see Appendix 4.1 for sector definitions), the climatic conditions are formed largely under the influence of heat and moisture advection from the North Atlantic area. Climate in the East Siberian and Chukchi sectors is significantly influenced by circumpolar conditions over the northern Pacific Ocean, as well as by the center of action above Siberia. The Alaskan sector is also influenced by circumpolar processes over the northern Pacific Ocean. In the Canadian sector, the climatic conditions in winter are governed both by anticyclonic circulation above northwestern Canada and the Arctic Basin and by a frequent passage of Atlantic lows.

The frequency, duration, and intensity of snowfall play a major role in the formation, characteristics, and variability of a snow cover. Analysis of trends in seasonal totals of precipitation from October to May (which correspond to the snowfall season with mean monthly temperatures below -2°C) at climate stations located north of 60°N revealed an increase in cold season precipitation between 1936 and 2009 in almost all sectors of the Arctic (Figures 4.3 and 4.4; Table 4.1).

The analysis is based on monthly total precipitation data collected at the stations from the start of their operation up




Figure 4.3. Long-term variability of total precipitation during the cold season (October to May when mean monthly temperature is below -2°C) for inland stations in different sectors of the Arctic (see Appendix 4.1 for sector definitions) together with their long-term (1936–2009) and short-term (1980–2009) linear trends; red line denotes positive trend and dark blue line negative trend. Precipitation amounts were calculated using a method of optimal averaging (Frolov, 2010). Results for Canada used the adjusted and homogenized precipitation dataset of Mekis and Hogg (1999) updated to 2008.




Figure 4.4. Long-term variability of total precipitation during the cold season (October to May when mean monthly temperature is below -2°C) in the marginal Arctic seas, central Arctic basin, and northern territories of the Canadian Archipelago together with their long-term (1936 to 2009) and short-term (1980 to 2009) linear trends; red line denotes positive trend and dark blue line negative trend. Precipitation amounts over each sea were calculated using a method of arithmetic averaging of total precipitation at all coastal meteorological stations near or in the area of each sea, and at North Pole drifting stations (Frolov, 2010). Results for Canada used the adjusted and homogenized precipitation dataset of Mekis and Hogg (1999) updated to 2008.

Table 4.1. Linear trend analysis (least-squares method) for cold season (October to May) total precipitation over the long term (1936 to 2009) and short term (1980 to 2009). See Appendix 4.1 for sector definitions. Values in **bold** are significant at the confidence level $p \leq 0.10$ (B_x = trend in mm per decade; Δ = linear change over the period as a percentage of the 1961 to 1990 mean; r^2 = percentage of variance explained by linear regression).

Areas	60 – 70 ° N						70 – 85 ° N						60 – 85 ° N					
	1936 – 2009			1980 – 2009			1936 – 2009			1980 – 2009			1936 – 2009			1980 – 2009		
	B_x	Δ , %	r^2 , %	B_x	Δ , %	r^2 , %	B_x	Δ , %	r^2 , %	B_x	Δ , %	r^2 , %	B_x	Δ , %	r^2 , %	B_x	Δ , %	r^2 , %
Atlantic (50° W to 30° E)	9.2	8.2	22.2	-13.7	-4.8	13.0	9.1	28.6	46.7	10.1	12.9	27.1	9.1	10.3	30.8	-5.5	-2.6	7.4
North European (30° E to 60° E)	16.2	40.0	70.8	7.9	7.8	19.0	6.2	20.3	50.9	9.9	13.1	29.8	12.1	33.0	73.8	9.0	9.9	30.9
West Siberian (60° E to 100° E)	10.3	28.5	65.4	1.2	1.3	4.5	-0.2	-1.1	1.9	17.1	38.6	65.2	5.9	20.6	59.0	7.9	11.2	37.3
East Siberian (100° E to 150° E)	3.1	15.0	41.3	4.5	8.8	26.4	-3.5	-21.2	38.8	1.0	2.5	5.2	0.6	2.7	9.7	3.1	6.7	22.3
Chukchi (150° E to 170° W)	-0.2	-0.7	1.3	-6.9	-9.5	24.8	-8.4	-42.3	56.4	-3.3	-6.7	17.3	-3.4	-12.8	24.3	-5.5	-8.7	29.3
Alaskan (170° W to 140° W)	2.5	10.9	15.1	0.0	0.0	0.0	-0.4	-6.6	3.6	10.1	67.8	44.1	2.0	9.4	14.7	1.7	3.4	5.4
Canadian ^a (140° W to 60° W)	6.3	23.1	26.9	8.1	11.7	8.1	8.5	54.2	28.7	2.9	7.6	0.8	7.8	30.7	40.3	10.0	16.5	17.0
Whole latitudinal zone ^b	5.7	14.5	27.2	0.1	0.1	0.0	1.8	10.5	7.4	5.8	13.7	12.1	3.6	10.9	20.6	3.7	4.7	5.2

^a For Canada the adjusted and homogenized precipitation dataset of Mekis and Hogg (1999, updated to 2008) was used. Data are available from 1936 to 2008 for 60° to 70° N, but there are no data prior to 1939 for 70° to 85° N (and 60° to 85° N); ^b for non-overlapping sectors weighted by land area for 1936 to 2008 for 60° to 70° N and 1939 to 2008 for 70° to 85° N and 60° to 85° N.

to 2009. Regionally averaged series were calculated over the latitudinal zones from 60° to 70° N, 70° to 85° N, and 60° to 85° N using a method of optimal averaging for the seven sectors shown in Table 4.1 (Frolov, 2010). Canadian results were computed from a 2008 update of the adjusted and homogenized precipitation dataset of Mekis and Hogg (1999), but there were insufficient station data in the Canadian Arctic sector north of 70° N to compute trends in the 70° to 85° N and 60° to 85° N sectors prior to 1939 (Appendix 4.1, Figure A2).

4.3.1.2. Snow depth, snow-water equivalent, snow-cover duration and extent

There have been long-term increases in winter snow depth over northern Scandinavia and Eurasia (Figures 4.5, 4.6 and 4.7) but significant decreases over the North American Arctic between 1950 and 2006 (Figure 4.8) (Kohler et al., 2006; Bulygina et al., 2009). Similarly, SWE increased over Eurasia and most of northern Russia for the 1966 to 2009 period (Bulygina et al., 2010b), but decreased over northern Canada over the 1966 to 1996 period (Atkinson et al., 2006). This contrast is surprising as both continents have experienced long-term increases in cold season precipitation (Table 4.1, Figures 4.3 and 4.4; Trenberth et al., 2007; Min et al., 2008).

Over most of Russia, the number of days with snow depth greater than 20 cm has increased (Figure 4.6). In the northern and southern regions of Western Siberia, in Yakutia, and on the coast of the Sea of Okhotsk, the trend is 8 to 10 days per decade. In contrast, the Chukchi Peninsula and Transbaikalia has experienced a decrease of days with snow depth greater than 20 cm by 6 to 10 days per decade (Bulygina et al., 2009).

Trends in SCD also contrast between the two Arctic regions (Figures 4.7 and 4.8) but began to decline over Eurasia after 1980. Maximum decreases in SCD of the order of four to six days per decade were found in the western and southern regions of European Russia from 1951 to 2006 (Kitaev et al., 2006; Razuvaev and Bulygina, 2006; Bulygina et al., 2009, 2010b; Shmakin, 2010). In contrast, there is an increase in SCD recorded in Yakutia (central Siberia) and in some regions of the Russian Far East, owing to their proximity to the Pacific.

Groisman et al. (2006) reported a general increase in SCD over Russia and the Russian polar region north of the Arctic Circle by five days (3%) and twelve days (5%), respectively, over the period 1936 to 2004. The authors concluded that paradoxically, the increase in SCD could not be associated with ‘Arctic warming’, which was not apparent over the period of their observation.




Figure 4.5. Spatial distribution of linear trend coefficients (cm per decade; 1% to 5% significance level) of maximum snow depth for permanent snow cover over the period 1966 to 2007. Source: Bulygina et al. (2009).




Figure 4.6. Spatial distribution of linear trend coefficients (days per decade; 1% to 5% significance level) showing the number of days with snow cover exceeding 20 cm for the period 1966 to 2007. Source: Bulygina et al. (2009).

In the coastal zone of the Eurasian Arctic, the interannual variability of dates of formation and decay of continuous snow cover is large, varying by 1.5 months. The duration of the period with continuous snow cover varies from 200 to 300 days at different stations in this zone (Radionov et al., 2004a). In the Fennoscandian and Alaskan-Canadian sector there has been a statistically significant decrease of about 3 days per decade in SCD (Table 4.2). In contrast, an increase by 1.5 days per decade was detected in the Kara Sea sector. During the past three decades (1978 – 2007), there has been a statistically significant decrease in SCD in coastal and island areas in all sectors of the Arctic (ranging from 4 to 9 days per decade) except for the Kara Sea and the Chukchi Sea sectors (Table 4.2).

The NOAA satellite record shows that variability in SCD in the North American and Eurasian Arctic has been more or less in phase since observations began in 1966, with contrasting seasonal patterns of little change in autumn SCD (i.e., the snow cover onset date) while spring SCD (i.e., the snow-off date) underwent a rapid decrease during the 1980s (Figure 4.9). Foster et al. (2008) attributed this step change to a regime change in the Arctic Oscillation (AO) to more positive values. However, a new multi-dataset study of spring snow cover changes over the Arctic (Brown et al., 2010) suggested that the reduction in spring snow cover is more linear over time and has a closer link to Arctic temperature trends than to the Arctic Oscillation. The asymmetric seasonal response of SCD




Figure 4.7. Long-term variability in northern Eurasia (1936 to 2000) of (a) mean February snow depth, (b) the number of days where 50% or more of the land surface is snow covered in winter (November to May), and (c) mean air temperature during winter (November to May). Solid lines indicate linear trends (Kitaev et al., 2005); the red line is an ad hoc indication of recent decreases in the number of days with snow cover in contrast to the long-term trend.




Figure 4.8. Variability and change in North American Arctic snow cover from the 1950/51 to 2006/07 snow season. (a) Annual snow cover duration. (b) Annual maximum snow depth. Values are regionally averaged anomalies from 23 stations (14 from Canada, 9 from Alaska) with anomalies calculated with respect to a 1971 to 2000 reference period. The least squares linear trend lines shown are both statistically significant (0.05 level) with slopes of -2.8 days/decade and -1.9 cm/decade. Source: updated from Atkinson et al. (2006).

Table 4.2. Results of linear trend analysis (using least-squares method) of continuous snow-cover duration^a from regionally averaged *in situ* observations in coastal and island areas of the Arctic from 1951 to 2007. Values in **bold** are significant at the 0.05 significance level. (B_x = coefficient of linear trend, number of days per decade; Δ = linear change over period as a percentage of the 1961 to 1990 mean; r^2 = percentage of variance explained by linear trend). Source: updated from Radionov et al. (2004a).

	1951 – 2007			1978 – 2007		
	B_x	Δ , %	r^2 , %	B_x	Δ , %	r^2 , %
Fennoscandia sector	-3.45	-10.3	48.0	-7.34	-11.5	54.1
Barents Sea sector	-0.59	-1.7	9.2	-6.28	-9.4	50.1
Kara Sea sector	1.46	3.2	29.5	0.98	1.1	11.3
Laptev Sea	-0.26	-0.6	6.5	-5.35	-6.0	68.3
East Siberian Sea sector	1.77	3.8	22.3	-8.74	-10.0	60.6
Chukchi Sea sector	0.27	0.6	4.9	-2.96	-3.7	30.2
Alaska and Canada sector ^b	-3.00	-6.7	33.2	-4.06	-4.8	29.0

^a Defined by Radionov et al. (1996) as the duration of the period with continuous snow-cover (50% or more of the visible area is reported as 'snow covered'); ^b computed from Canadian and Alaskan daily snow depth data with snow cover duration defined as the number of days in the snow season with daily snow depths ≥ 2 cm following Brown and Goodison (1996).


is consistent with observed warming trends that are likely being enhanced by positive snow-albedo feedbacks (Groisman et al., 1994a; Déry and Brown, 2007).

The trend (days per decade) in the dates of the onset and disappearance of continuous snow-cover over the coastal region of northern Russia for the 1973 to 2003 period shows great variability but a slight tendency for later formation of snow-cover in autumn and for an earlier reduction of snow-cover in spring (Figure 4.10). Negative values indicate a later date of formation or decay of snow-cover in comparison with the long-term average date (Radionov et al., 2004a).

Data from visible satellite imagery show that Arctic snow-cover extent in May to June decreased by an average of 18% over the 1966 to 2008 period of the NOAA record. Spatial analysis of snow-cover trends in the NOAA dataset (Figure 4.11) confirms a number of the previously mentioned characteristics. Specifically, that decreases are more marked in the snow-cover melt period than the snow-cover onset period, that the date of snow-cover onset has become earlier over northern Russia, and that spring decreases over Eurasia tend to be stronger in northern coastal regions. The average change in SCD over the pan-Arctic region (excluding Greenland) was -0.49 days per decade in the snow-cover onset period, and -3.43 days per decade in the spring snow-cover melt period (Figure 4.11).

Arctic indigenous peoples have also observed long-term changes in snow conditions as these have direct impacts on their livelihoods (Forbes and Stammer, 2009; Bartsch et al., 2010). However, their observations are at the local scale, and few are published. Also, most of their observations relate to changes in snow structure and their impacts on the mobility of reindeer and reindeer herders as well as access to vegetation. Observations on snow-cover by the Sámi from northern Sweden highlight recent increases in ice crusts and in some areas snow accumulation, with statements such as “*all valleys were snow free during (reindeer) calving in the 1930s*,” “*terrain*

Arctic autumn SCD anomaly (relative to 1988-2007)



Arctic spring SCD anomaly (relative to 1988-2007)




Figure 4.9. Time series of standardized snow-cover duration anomalies for the North American and Eurasian Arctic (relative to a 1988 to 2007 reference period) from the NOAA record for the (a) first half (autumn) and (b) second half (spring) of the snow season. Solid lines denote the five-year moving average. Source: Derksen et al. (2009).




Figure 4.10. Linear trend in the (a) formation and (b) decay dates of continuous snow cover at Arctic coastal stations for the period 1973 to 2010.




Figure 4.11. Trend in snow-cover duration for (a) autumn (snow-cover onset period) and (b) spring (snow-cover melt period) over the 1972/73 to 2008/09 snow seasons from the NOAA weekly dataset maintained at Rutgers University by Dr. D. Robinson. Trends were computed using the least squares method. Source: updated from UNEP (2007) by R. Brown, Climate Research Division, Environment Canada, 21 September 2009.

elements that determined animal movements in the summer are now snow covered: reindeer now find new passes and roam over a wider area”, “snow-covered areas and snow patches persist longer into the summer in high mountain areas”, and “rapid thaws created problems when moving to summer grazing areas in 1938 – 40” (Riseth et al., 2011). Many of these observations match or add to nearby climate station monitoring, particularly for the period up to the 1990s (Callaghan et al., 2010).

Arctic snow cover exhibits large interannual variability, linked to large-scale variation in atmospheric circulation, around the previously documented trends. For example, the increase in snow depth over most of northern Eurasia in recent decades can be explained in two ways. First, there was a dramatic retreat in Arctic sea ice at the end of the warm season (Serreze et al., 2007) that left large ice-free or thin-ice areas at the beginning of the cold season in the Eurasian sector of the Arctic Ocean. These allowed additional water vapor influx into the dry Arctic atmosphere that ended up as snowfall further south. Second, more intensive cyclonic circulation and more frequent cyclones (Popova, 2004) related to changes in atmospheric circulation also caused increased snow depth over most of northern Eurasia in recent decades. This circulation change is linked to significant increases in the North Atlantic Oscillation (NAO) index since the 1970s (Popova, 2007). Snow accumulation in Eurasia is also strongly modulated by the Scandinavian pattern (SCAND) that reflects the intensity of blocking anticyclones in Eastern Europe. Snow accumulation is negatively correlated with the SCAND index, and in the 1951 to 1975 period, was the most important circulation pattern influencing variation in snow depth across Eurasia (Popova, 2007). The Pacific North America (PNA) and Pacific Decadal Oscillation (PDO) have been shown to influence climate and snow cover over the western Canadian Arctic (Derksen et al., 2008b) with positive (negative) modes of the PNA and PDO associated with reduced (increased) snow accumulation and a shorter (longer) snow cover season.

4.3.1.3. Changes in snow properties

4.3.1.3.1. Snow structure and snow cover stratigraphy

Data on trends in snow cover stratigraphy are rare (but see Bulygina et al., 2010a, for data relating to Russia; Riseth et al., 2011 and Johansson et al., 2011, for data relating to Sweden; and Gerland et al., 1999, for data related to Svalbard). Nevertheless, they are important for example in determining animal access to food beneath snow, while the presence of weak layers (depth hoar) or slip planes (crusts or ice layers) in the snowpack increases the potential for avalanche release. Sámi traditional knowledge from the Abisko area of sub-Arctic Sweden reports several local changes in the physical properties of the snow cover, particularly the development since the 1980s of more snow and ice layers in the snowpack that are hard for the reindeer to penetrate (Riseth et al., 2011; Johansson et al., 2011). These relate to observations of more frequent winter thaws and rain-on-snow events (Shmakin, 2010) (Figure 4.12) that can have catastrophic consequences for animal populations (see Section 4.4.3.2). The observations also relate to heavy snowfall under relatively high temperatures and compression by later snowfall. In Canada, traditional knowledge records evidence of harder snow that impacts the construction of snow shelters (Walser, 2009). In contrast, observations of recent changes in snow stratigraphy for northern Eurasia showed that interannual variability outweighed any possible trends (Golubev et al., 2008).

An ice layer at the bottom of the snowpack (‘basal ice’) is an important problem for Arctic grazing animals such as reindeer, caribou, musk ox, and small rodents such as lemmings, particularly if the ice layer forms early in the season and restricts access to forage for an extended period (Forchhammer and Boertmann, 1993; Aanes et al., 2000; Solberg et al., 2001; Griffith et al., 2002). Basal ice layers can form at any time during the snow season from thaw events followed by subsequent




Figure 4.12. Sum of rain exceeding 4 mm per day falling on snow deeper than 3 cm, showing the change for 1989 to 2006 relative to 1951 to 1980. Source: Shmakin (2010).

refreezing. However, the data archive of Bulygina et al. (2010a) suggests that they tend to be more frequently encountered in spring. In Russia, the thickness of the basal ice layer has been routinely measured at 958 long-term stations since 1966 as part of the meteorological observing program (Bulygina et al., 2010a). Dangerous events for reindeer husbandry (DER) are reported by the Russian Meteorological Service when the basal ice layer is thicker than 5 mm over ten consecutive days. A recent analysis of DER events in Russia since 1966 (Bulygina et al., 2010a) found a downward trend of about 5% per decade in the number of sites reporting DER events, mainly in response to a shorter and more intense snow melt season. Further analysis of DER frequency in the early winter period is required to determine if there are changes with potential impacts for grazing animals. In contrast, a 50-year record of snow stratigraphy from northern Sweden shows a significant increase in hard snow/ice layers in the snow pack, particular at the ground surface (Johansson et al., 2011).

4.3.1.3.2. Observed changes in albedo and snowpack chemistry: black carbon effects

Snow is the most reflective natural surface on Earth, with albedo typically 70% to 80% for the freshly fallen snow. However, albedo gradually decreases with snow ageing and contamination by external materials that accumulate in the snowpack. Nevertheless, the decreased albedo of the older snow cover remains much higher than that of all underlying surfaces except ice. Because the albedo is so high, it can be reduced by even small amounts of dark impurities. Just a few parts-per-billion (ppb) of black carbon (soot) can reduce the albedo of snow by 1–4%, as the black carbon strongly absorbs solar radiation (Warren and Wiscombe, 1980, 1985; Flanner et al., 2007). The absorbed radiation is converted to internal energy that is re-emitted as heat to the surrounding snow or ice and air. Hence, deposition of black carbon and other aerosols, such as deposition from volcanoes, onto snow and ice surfaces can increase melt rates (although the study by Jones et al. (2005) on the climate effects of a ‘super volcanic eruption’ suggested increasing snow cover in response to the cooling). Snow with black carbon, therefore, melts sooner in the spring and uncovers the darker underlying surface, causing an amplifying feedback on climate (Hansen and Nazarenko, 2004; Grenfell et al., 2009).

Some black carbon emissions result from marine transportation and offshore fossil fuel extraction within the Arctic (Macdonald et al., 2005), activities which are likely to increase as sea ice retreats (see Chapters 9 and 10). However, sources of black carbon are primarily located outside the Arctic. The main source is biomass burning (Hegg et al., 2009); forest fires and agricultural fires as well as the burning of fossil fuels.

Nevertheless, black carbon particles can travel long distances and are able to reach the Arctic in substantial quantities. Observations show a large seasonal cycle in atmospheric levels, with maximum concentrations in surface air during late winter and early spring and minimum values in late summer and early autumn (Sharma et al., 2006). Black carbon particles are typically hydrophobic when emitted, but age fairly rapidly to a hydrophilic state by mixing with other particles in the atmosphere. They are then deposited at the surface primarily by wet deposition, although dry deposition also plays a small but important role. Atmospheric residence times are generally about three to eight days (Shindell et al., 2008). A typical mid-latitude snow crystal contains thousands of particles, including absorbing black carbon and mineral dust (Chylek et al., 1987).

Clarke and Noone (1985) measured black carbon in snow throughout the western Arctic. The cleanest snow is in Greenland, with about 2 ppb. Snow in Canada, Alaska, and on sea ice in the Arctic Ocean has 5 to 10 ppb (Hegg et al., 2009), which is less than was reported by Clarke and Noone (1985). This result is consistent with the decline in atmospheric black carbon levels measured continuously at Alert since 1989 (Quinn et al., 2007). Snow in the Russian Arctic sampled in the winters of 2007 and 2008 (Grenfell et al., 2009) showed higher values than elsewhere in the Arctic, typically in the range 20 to 30 ppb. The median background values were 15 to 25 ppb on or near the coasts of the Barents and Kara Seas and near a polynya located within the Laptev Sea. Values were 15 to 20 ppb on the Chukchi Peninsula, but only 5 ppb in a fresh snowfall event at the end of April. Farther south and west, background levels were higher at 20 to 80 ppb in the Sakha Republic and 40 ppb on the Taymir Peninsula (Grenfell et al., 2009).

The change in albedo due to the presence of black carbon can have substantial effects on snow melt and atmospheric temperatures when large amounts of sunlight reach the snow surface – the 20-year global warming potential of black carbon is 2000 carbon dioxide equivalents (Hansen et al., 2007). The effects of black carbon are greatest in large, open areas and in late spring, summer, and early autumn. The albedo reduction also varies with the age of the snow, with older, larger-grained snow showing roughly three times the reduction of new, smaller-grained snow (Warren and Wiscombe, 1985). More broadly, by reducing the reflection of solar radiation to space, deposition of black carbon onto snow and ice leads to warming of the planet as a whole, resulting in increased melt rates of snow and ice. Model studies suggest that black carbon plays a very large role in spring snow melt, with about 20% to 30% greater melting than in simulations that do not include the effects of black carbon deposits (Flanner et al., 2007). Experiments suggest that emissions of black carbon and organic matter from fossil

fuel combustion induce 95% as much loss of springtime snow cover over Eurasia as anthropogenic carbon dioxide (Flanner et al., 2008).

4.3.2. Projected changes in snow cover and its characteristics

4.3.2.1. Methodology to predict changes in snow cover and characteristics

The present (2009) ability of the scientific community to provide guidance on how Arctic snow cover will respond to climate change is limited by a number of issues. First, there is no systematic collection of pan-Arctic snow data for monitoring changing snow cover conditions and for developing and evaluating climate models. Second, for computational reasons, the CMIP3 suite of coupled climate models used relatively simple snow schemes that did not include many processes important for high-latitude snowpack evolution (Brun et al., 2008; Holko et al., 2008). In addition, Kattsov et al. (2007) showed that the CMIP3 models tended to overestimate precipitation over major river basins in the Arctic due to inadequate treatment of orography and biases in atmospheric and sea-ice circulation. Räisänen (2007) and Brown and Mote (2009) found that the CMIP3 model mean SWE climatology over the Northern Hemisphere agreed reasonably well with available observations. However, there is also recent evidence that the atmospheric circulation patterns and snow feedbacks in the CMIP3 models are unrealistic over high latitudes. For example, Hardiman et al. (2008) showed that none of the CMIP3 models were able to reproduce the observed strong correlations of Eurasian autumn snow extent to atmospheric wave activity and Northern Annular Mode (NAM) anomalies in the following winter. Also, Fernandes et al. (2009) noted that the CMIP3 models do not properly capture the spatial and temporal characteristics of northern hemisphere snow temperature sensitive regions documented by Groisman et al.


(1994a). Inadequate representation of snow-albedo feedbacks may be contributing to this, as previously noted by Qu and Hall (2006).

In light of these limitations, it is unrealistic to expect GCMs to provide high-quality projections of future changes in snow cover over the Arctic region. However, they can provide an indication of large-scale changes in precipitation- and temperature-dependent snow cover variables, such as snow cover start and end dates and maximum winter accumulation, which are important for many applications (see Section 4.3.2.2). Changes in snow properties such as snow density, ice layers, and changes in spatial accumulation patterns require the use of more-sophisticated models and downscaling approaches (discussed in Section 4.3.2.3).

4.3.2.2. Climate model projections of changes in snow cover and snow water equivalent

The response of northern hemisphere snow cover to climate change simulated by the CMIP3 models did not receive much attention in the IPCC Fourth Assessment (Solomon et al., 2007). Subsequently, Räisänen (2007) examined projected 21st century changes in the SWE for 20 of the CMIP3 general circulation models and found that, while the projected warming shortens the snow season in both autumn and spring in all of Eurasia and North America, SWE at the height of winter generally increased in the coldest areas and decreased elsewhere. Regions with increasing levels of SWE coincided with the position of the -20°C isotherm in late 20th century November to March mean temperature (Räisänen, 2007) that covers the northernmost portions of both continents (Figure 4.1). Already, there is evidence of increasing snow depth over northern Eurasia (e.g., Kitaev et al., 2005; Bulygina et al., 2009) (Figure 4.6) but less evidence of increased snow accumulation over the Canadian Arctic (Brown and Mote, 2009).

Analysis of the model consensus pattern for change in maximum SWE (Brown and Mote, 2009) (Figure 4.13) showed




that the response consisted of three broad zones: with significant decreases at lower latitudes; a broad zone over mid-to-high latitudes, where changes were not statistically significant; and the northern zone of increasing levels identified by Räisänen (2007). The temporal evolution of the climate change response of SCD (Figure 4.14) is different in that decreases dominate (no regions were identified where climate models show significant increases in SCD), with the earliest and largest decreases in SCD occurring in coastal regions of the continents. Taken together, these figures suggest different regional snow cover responses over the Arctic, with the largest and most rapid decreases both in SWE and SCD over Alaska, northern Scandinavia, and the Pacific coast region of Russia.

Projected changes in maximum monthly SWE (SWE_{max}) and annual SCD for the 2049–2060 period versus 1970–1999 are provided in Figure 4.15 from a composite of six of the highest resolution GCMs that met the Arctic performance criteria applied in Chapter 3. The choice of six models was based on the findings of Chapter 3 that composites formed from the best-performing five to seven models agreed more closely with observations than composites formed from fewer or more models. The six models used are CCSM3, CNRM, ECHAM5, GFDL, HADGem1, and MIROC32, and results are computed for the IPCC A2 emissions scenario. The projections suggest slight increases in SWE_{max} (0–15%) over much of the Arctic, with the largest increases (15–30%) over the Siberian sector. Annual SCD is projected to decrease by about 10–20% over much of the Arctic, with the smallest decreases over Siberia (< 10%) and the largest decreases over Alaska and northern

Scandinavia (30–40%). The climate models project similar decreases in snow cover at the start and end of the snow season (not shown). The climate model standard deviations (right-hand panels in Figure 4.15) show relatively high values of model consistency (standard deviations < 10%) over the Arctic region both for SWE_{max} and annual SCD with areas of lower model consistency over Alaska and western Europe. The process of interpolating climate model output with different resolutions to a standard grid contributes to higher model standard deviations in coastal mountain areas.

Some aspects of these climate model snow-cover change projections may not be realistic. Brown and Mote (2009) found no evidence in the climate models of the accelerating reduction in high-latitude spring snow cover documented by Déry and Brown (2007) consistent with polar amplification of warming and an enhanced albedo feedback in spring. The muted spring response in the models could be due to a number of reasons, including lack of black carbon darkening (Flanner et al., 2008), inadequate snow-albedo treatments (Qu and Hall, 2006), and wet-cold biases in models over high latitudes (Randall et al., 2007). The slower decrease in SCD over eastern Eurasia shown by the climate models is also inconsistent with observed trends and may be linked to difficulties in simulating the climate interactions of the Tibetan Plateau (Cui et al., 2007).

Snow cover changes are also likely to be much more complex in mountainous terrain than represented in the coarse-resolution GCM results. A sensitivity analysis of snow cover changes to increasing temperature and precipitation suggested a potentially complex elevation response of snow cover in






Figure 4.15. Projected changes in maximum monthly snow-water equivalent and annual snow-cover duration between 1970–1999 and 2049–2060 for six general circulation models using the IPCC A2 emissions scenario. (a) Projected percentage change in maximum monthly snow-water equivalent with the standard deviation of the six projections shown in (b). (c) Projected percentage change in mean annual snow-cover duration with the standard deviation of the six projections shown in (d). Seasonal snow-cover information over the Greenland Ice Sheet is not available from the climate models. Source: computed from climate model projections presented by Brown and Mote (2009).

mountain regions due to non-linear interactions between the duration of the snow season and snow accumulation rates (Brown and Mote, 2009). This non-linear response can be expected to contribute to regional-scale variability in the elevation response of snow cover to climate change, which will be modified by local factors such as lapse rate (rate of air temperature change with increasing altitude), aspect, topography, and vegetation.

4.3.2.3. **Snow cover information for adaptation and decision-making – downscaling approaches**

For many applications, the snow-cover change information from GCMs is too coarse for use by decision-makers. There is a wide range of options for downscaling information to the required level, with an extensive body of literature and guidelines (e.g., Wilby et al., 2004; Christensen et al., 2007; Benestad et al., 2008). The two main approaches are dynamical and statistical downscaling. Dynamical downscaling uses higher resolution regional climate models (RCMs) driven with lower resolution GCM data as the boundary forcing. This approach has been used in Norway (Vikhamar-Schuler et al., 2006), the western United States (Rauscher et al., 2008), and Switzerland (Bavay et al., 2009) to investigate the local and regional response of snow cover to different climate change scenarios. These high-resolution model-based approaches are computationally expensive to run but are attractive in that they provide a physically based approach to downscaling (although care must be taken to account for any biases in RCM fields that can be passed from the driving model or generated by the RCM, such as in the land surface scheme).

A number of high-latitude environment distributed process models have been developed in recent years (e.g., Liston et al., 2007; Pomeroy et al., 2007; Schramm et al., 2007; Andreadis et al., 2009; Shmakin et al., 2009) that can be driven with atmospheric re-analyses or RCMs to provide assessments of variability and change in snow cover and hydrology at basin to pan-Arctic scales (e.g., Su et al., 2005). Previous evaluations of snow models in the Arctic (Slater et al., 2001; Bowling et al., 2003) have shown that most models are able to provide reasonable snow cover simulations given good quality input data. The challenge is to provide realistic driving variables, particularly precipitation, to these process models. The potential for using snow information directly from existing re-analyses such as ERA-40, NCEP, and JRA-25 is limited by the relatively coarse resolution and because the snow fields must be carefully evaluated on a regional basis due to spatially and temporally varying biases and errors in the assimilation of snow observations (Khan et al., 2008). The Arctic System Reanalysis project (an IPY Project) is intended to address a number of these issues (<http://polarmet.mps.ohio-state.edu/PolarMet/ASR.html>).

There are few pan-Arctic RCMs under development, and their initial evaluation (Rinke et al., 2006) showed large scatter among models and reduced confidence in air temperatures over land, surface radiation fluxes, and cloud cover. More recently, Ma et al. (2008) carried out a five-month climate simulation with the modified mesoscale model, Polar MM5, coupled to the NCAR Land Surface Model (LSM) and found


that the coupled model improved forecast skill for surface variables at some sites. Ongoing work developing the Polar Weather Research and Forecasting (Polar WRF) model (e.g., Hines and Bromwich, 2008) is providing guidance on the most appropriate physical parameterizations for use in polar regions. Three climate model intercomparison projects (MIP) are in progress to improve Arctic climate models: the Arctic Regional Climate MIP (ARCMIP), the Arctic Ocean MIP (AOMIP), and the Coupled Arctic Regional Climate MIP (CARCMIP) for coupled atmosphere-ice-ocean-land models.

Statistical downscaling techniques are based on the development of statistical relationships between low-resolution GCM fields and the high-resolution observed records (usually surface variables such as precipitation or temperature) through a variety of methods, including regression analysis, weather typing, and analogues (see Kattsov et al., 2005; Benestad et al., 2008). While there are few examples of statistical downscaling applied directly to snow cover in the Arctic, there are many examples of downscaling temperature and precipitation information (e.g., Kattsov et al., 2005), which are two of the basic ingredients for simulating snow cover.

The development of scenarios for changes in snow cover properties relevant to ecological studies (e.g., snowpack structure, ice layers, rain-on-snow events) will require the use of detailed physical models that take account of snow layering. There are several such models available (e.g., CROCUS, Brun et al., 1989; SNTHERM, Jordan, 1991; and SNOWPACK, Bartelt and Lehning, 2002), and these can be readily run in 1-D column mode at individual sites with locally downscaled driving fields from climate models. However, running these models in a spatially distributed mode like Bavay et al. (2009) is computationally expensive, and ongoing work is needed to find ways to efficiently couple detailed snow process models into distributed Arctic process models that take account of heterogeneous terrain and vegetation (Brun et al., 2008). An example of snow depth projections using the HIRHAM RCM is shown in Figure 4.16.

4.4. **Evaluation of the impacts of a changing snow cover and its characteristics**

- Changing Arctic snow climate has had widespread impacts and future changes will probably intensify these. Impacts can be beneficial or deleterious depending on the snow cover sensitivities involved.
- Diminished spring floods and a longer snow-free season increase the potential for evaporation and threats to wetlands, but this may be offset by new sources of water from thawing permafrost and associated thermokarst. The critically important balance between the two processes is unknown and areas of drying tundra as well as of increased water logging are being reported across the Arctic.
- Snow-vegetation interactions are expected to play an important role in the future evolution of northern hydrology and thermal regimes. The enhanced growth of Arctic shrubs in response to warming increases the potential for local increases of snow cover accumulation independent



of increases in precipitation. Increased shrubiness will also change snowpack properties and melt dynamics that in turn will have implications for the soil thermal regime and hydrology.

- Reduced SCD shortens the winter snow transportation season, which is important for many Arctic communities and commercial enterprises.
- Snow-related hazards could increase in areas with projected increases in annual maximum snow accumulation.
- Increased winter precipitation and a more even seasonal distribution of runoff may prove beneficial to the hydropower industry.
- A shorter SCD is likely to increase plant productivity and carbon capture where soil moisture is adequate.
- Reductions in the amount of water stored in the winter snowpack in some areas are already increasing the moisture stress of northern coniferous forests in summer.
- Winter thaws and rain-on-snow events are already damaging vegetation and impacting Arctic grazing mammal population. Projected increase in frequency of these events will lead to additional challenges for commercial reindeer herding.

4.4.1. Changes in snow cover and impacts on climate processes

Snow cover plays a major role in climate, and the hydrological and ecological systems through its influence on the surface energy balance (e.g., reflectivity), water balance (e.g., water storage and release), thermal regimes (e.g., insulation), and vegetation and trace gas fluxes (see Figure 4.17).

The main snow-climate processes are briefly presented here in Section 4.4.1, while the impacts of snow on the hydrological cycle, vegetation, trace gases, and the accumulation of black carbon that affect the climate system are presented in Sections 4.4.2, 4.4.3.1, 4.4.3.3 and 4.3.13.2.

4.4.1.1. Changes in surface boundary layer processes, such as atmospheric inversions

Temperature inversions close to the ground surface are characteristic features of Arctic climate, particularly in winter when the ground is snow covered. Stable conditions can persist for weeks, decoupling the surface from atmospheric conditions a few kilometres aloft. They thus affect the surface energy exchange. Low-level inversions result from two basic conditions:




Figure 4.17. Schematic illustration outlining the importance of snow on climate, hydrology, and ecosystems. The solid black line represents an idealized ground-snow-atmosphere temperature profile to highlight the strong temperature gradients occurring near the snow surface. Source: R. Brown and T. V. Callaghan, March 2010. Superscript numbers refer to sections in the text that describe the processes as follows: ¹(4.2.2), ²(4.3.1.3.2), ³(4.4.2.2), ⁴(4.4.3.1), ⁵(4.4.3.3), ⁶(4.4.3.1), ⁷(4.2.2), ⁸(4.4.3.2).

1. A radiative imbalance, in which surface energy emission exceeds that received directly from solar radiation and the atmosphere (a condition that is common in the Arctic snow season, when net radiation is generally negative, and during the rest of the year, when the sun is lowest in the sky).
2. Warm air advection over a cooler surface (common in snow-covered regions and over sea ice), a condition which may occur at any time of year. During late spring and early summer, this may involve the formation of shallow surface inversions with only slightly cooler temperatures near the surface as melting snow and ice act as a heat sink. However, in winter, warm air aloft can create extremely stable conditions with temperature gradients in the lower troposphere of more than +6 °C/100 m (Overland and Guest, 1991; Bradley et al., 1992a).

Studies of inversion characteristics over time show a widespread decline in surface-based inversion depth from the 1950s to the 1980s across Arctic Canada and Alaska (Bradley et al., 1992b; Hartmann and Wendler, 2005; Bourne, 2008). However, over the past 20 years inversion depths have shown no further downward trends at most sites. It is possible that some of the declines seen in the early period were artifacts of improved instrumentation (faster response times and thus improved detection of atmospheric structure; see Walden et al., 1996), but the widespread and steady nature of the observed declines in Siberia, Alaska, and Canada make such an explanation unlikely to be applicable in all areas. Circulation changes (such as the mid-1970s shift in the Pacific Decadal Oscillation) appear to have had a strong influence on inversion structure in Alaska (Bourne, 2008). Circulation changes across the Arctic have contributed significantly to warming (Graversen et al., 2008), and it is likely that such changes have affected the near-surface inversion structure.

General circulation models perform poorly at simulating conditions in the near-surface boundary layer and there have

been few attempts to use regional models to dynamically downscale GCMs over the Arctic. However, initial results indicate that such simulations overestimate surface temperature and daily inversion variability, and underestimate inversion depths and strength (Bourne, 2008). Simulations of future winter climate in Alaska (for emissions scenario A1B) downscaled to the regional level for Alaska (MM5 driven by CCSM3) suggest that inversions will become shallower and less strong (Bourne, 2008), but given the relatively poor performance of these models in simulating modern conditions, these results can only be considered as suggestive rather than definitive. Much additional research using different regional models is needed before a clear picture of how anthropogenic global warming may be expressed in terms of the surface-based inversion structure in the Arctic.

4.4.1.2. Changes in the atmospheric moisture budget in relation to snow cover

The atmospheric moisture budget is changing and will continue to evolve throughout the 21st century in response to a warming climate, changes in sea ice and snow cover, and altered atmospheric circulation (Rawlins et al., 2010). Increased winter snowfall over land areas may act to keep soil moisture levels higher in spring, working with increased precipitation to promote more evaporation. On the other hand, under a warming climate earlier loss of the snow cover over Arctic and sub-Arctic lands, by exposing the dark underlying surface, will promote surface heating, and hence, an earlier transition to the summer-type convective precipitation regime over Arctic and sub-Arctic lands (Groisman et al., 1994b).

Simulations from most coupled GCMs point to intensification of the northern high-latitude freshwater cycle through the 21st century (e.g., Holland et al., 2006; Kattsov et al., 2007). A warmer atmosphere carries more water vapor and with efficient precipitation-generating mechanisms (convergence and uplift), precipitation increases. While evaporation also increases, the precipitation change dominates such that there

is an increase in net precipitation and hence river discharge. Although the balance of observational evidence points to intensification over the past several decades, intrinsic variability and lack of consistency in observed trends limit confidence in the robustness of the changes (Rawlins et al., 2010).

A warmer Arctic atmosphere also provides more energy for sublimation. A review of the blowing snow sublimation process was provided by King et al. (2008) with an estimate of ~20% of annual snowfall for Arctic blowing snow sublimation losses. Providing estimates of how this may change in the future is complicated by difficulties in scaling-up the local-scale processes that drive the blowing snow sublimation process (King et al., 2008).

Although the future is uncertain, there are likely to be changes in patterns of atmospheric circulation affecting pathways of moisture transport and in turn influencing precipitation and snow cover. Some simulations suggest that in the future there will be a more frequent positive phase of the Northern Annular Mode (NAM) and its Atlantic-side component, the NAO (Rogers and van Loon, 1979). How altered precipitation linked to future behavior of the NAM and NAO and other patterns of atmospheric variability translate into changes in snow cover will depend on attendant temperature rise. This translation is important given the potential for snow cover forcing on circulation. For example, there is evidence from models (e.g., Walland and Simmonds, 1997) and observations (Clark and Serreze, 2000) that variability in Eurasian snow cover extent modulates atmospheric circulation patterns over the North Pacific Ocean. In addition, the recent modeling study of Deser et al. (2010) suggests that a seasonal cycle of sea-ice extent projected for the late 21st century will promote increases in winter snow depth over Siberia and northern Canada because of increased winter precipitation.

4.4.2. Changes in the hydrological cycle at the local and regional scale

4.4.2.1. Regional and seasonal variability in sources of moisture for precipitation

Within the Arctic drainage basin, maximum monthly precipitation occurs in the summer to autumn period, but the maximum discharge is observed in June, when it primarily originates from snow accumulated over the long (five- to eight-month) cold period (Figure 4.18). Long-term averages of precipitable water calculated from the atmospheric moisture budgets of the large Arctic-draining Eurasian watersheds (Ob, Yenisey, Lena, Kolyma-Indigirka) have symmetric annual cycles, with July peaks and winter minima (Serreze and Etringer, 2003). This reflects the annual cycle in atmospheric temperature and the ability of the atmosphere to carry water vapor. Precipitation also has a symmetric annual cycle with a summer peak. While effective precipitation-generating mechanisms exist in all seasons, these watersheds are far removed from oceanic moisture sources ('continentality'). As such, precipitation tends to follow the seasonality in the available column water vapor. During winter, the primary precipitation mechanism is a modest convergence of water vapor; this precipitation is stored in the winter snowpack and released in spring and summer as river discharge.

Processes over the major Eurasian catchments contrast sharply with the Atlantic sector of the Arctic, which has a general cold season precipitation maximum. Here, the annual cycle of precipitation is not moisture limited but rather reflects the stronger precipitation-generating mechanisms in the cold season (i.e., vapor flux convergence and uplift associated with eddy activity along the North Atlantic storm track). In this region, the annual cycles of precipitation and column water are in opposition (Serreze and Etringer, 2003).

In the Arctic Ocean region, precipitable water has a July peak and winter minimum (AARI, 1985). Similar to the terrestrial watersheds, the vapor flux convergence tends to have a general cold season minimum and summer to early autumn peak (e.g., Walsh et al., 1994; Yang, 1999). Here, however, evaporation is always low, limited in winter by low temperatures and in summer by the presence of a melting snow and sea-ice surface. For all seasons, precipitation is primarily related to the horizontal vapor flux convergence.

4.4.2.2. The role of snow cover in the seasonal hydrological cycle

Snow cover has a direct impact on the hydrological cycle in its redistribution of water between cold and warm seasons, with limited water availability during the cold season and an abundance of water during snow melt. The snow-generated runoff in the Arctic drainage basin is up to 75% of total annual flow in some northern regions of Siberia and North America (Woo, 1980).

Whereas snow cover has a direct impact on the hydrological cycle in its redistribution of water between cold and warm seasons, the indirect snow cover impact has its effects on the surface energy budget. That is, on the latent heat flux to the atmosphere (suppressed by low surface temperatures associated with snow cover and the absence of transpiration) and to the soil (by intercepting precipitation and meltwater and sending a significant part downstream during the snow melt period instead of contributing to the baseflow; Dingman, 2002). Therefore, future variations in snow depth may dramatically change the hydrological regime of the Arctic (Adam et al., 2009).

Changes in precipitation and temperature are expected to affect all aspects of the cryospheric hydrological cycle, including snow accumulation and melt, evaporation, and runoff as well as




Figure 4.18. The seasonal cycle of discharge for the four largest rivers flowing into the Arctic Ocean. Source: Shiklomanov et al. (2007).

short- and long-term storage changes. Net snow accumulation at the end of winter will be modified by winter warming and precipitation enhancement in the circumpolar areas, but their effects would vary between regions (see Section 4.3.2). In other Arctic and sub-Arctic areas, projected increases in winter precipitation may be accompanied by increased occurrences of winter thaw. Mid-winter melt events and rainfall instead of snowfall can lead to a reduction in net snow accumulation, and such tendencies are suggested by the records of some stations in northwestern Canada (Burn et al., 2004). Changes in the physical and biological environment (see Section 4.3.1.3.1) further influence winter snow accumulation. The polar sea ice is retreating at a dramatic rate, and this shortens the ice-covered season while creating or enlarging polynyas (areas of open water surrounded by sea ice) in the Arctic Ocean. The Svalbard islands offer a present-day analogue for many Arctic islands under scenario climates. Humlum et al. (2003) noted that when airflow over open waters advects warm air to the islands in the winter, it is often accompanied by heavy snowfalls and periods of snow melt.

Shortening of the snow cover period leads to a corresponding extension of the evaporation season. Earlier snow melt under a future climate will be accompanied by an earlier break-up of lake and river ice (see Chapter 6)

Changes in streamflow will be expressed mostly through high and low flows. At present, spring floods usually represent the highest flow of the year, generated by rapid melting of a snowpack built up in the long winter. A shortened snow accumulation season interrupted by mid-winter melt events will diminish the water supply and moderate its rate of delivery. An increase in groundwater discharge in winter, however, can produce more icing (also known as 'aufeis' or 'naled') in stream channels to block the spring flow and intensify the snowmelt flood locally. Streamflow data from northern Canada show that there are detectable trends of decreasing freshet (a sudden overflow of a stream from a heavy rain or thaw) peaks and earlier arrival of spring floods (Woo and Thorne, 2003; Burn et al., 2004; Aziz and Burn, 2006).

After the spring flood, streamflow declines to its summer low. With an extended snow-free period and higher evaporation rates, groundwater drawdown will be accompanied by reduced baseflow. Small basins with polar desert conditions may find a total cessation of their summer flow except during heavy rains. Recent studies suggest that there may be a link between significant increases in winter baseflow of many northward-flowing rivers and permafrost thawing (St Jacques and Sauchyn, 2009). Plausible causes include a thicker active layer or forest fire or precipitation increase in the cold months (McClelland et al., 2004; Rawlins et al., 2009; Shiklomanov and Lammers, 2009). However, there is incompatibility between positive trends in the runoff of the Yenisey and Lena Rivers and the lack of positive trends in precipitation data (Figure 4.18), perhaps owing to data quality issues (Berezovskaya et al., 2004). Human activities such as reservoir operation also have overwhelming effects on streamflow regimes (Ye et al., 2003; McClelland et al., 2004; Yang et al., 2004; Woo et al., 2008).

Although snow is currently the principal promoter of river flow, in future the number and magnitude of rainfall events may increase, while the contribution of snow may decline, notably in the sub-Arctic. The seasonal flow pattern may then

be replaced by a pluvial or a nivo-pluvial regime. Under climate change scenarios of warmer winters and more rain events, simulations of streamflow in mountainous basins of northern Canada suggest that winter flow will increase and spring freshet dates will advance (Figure 4.19a), but peak flow will decline, as will summer flow due to intensified evaporation (Kerkhoven and Gan, 2005; Woo et al., 2008). Thus, the total annual flow is likely to remain the same (see superimposed present and




Figure 4.19. Exceedance probability (the probability that a certain value is going to be exceeded) of several streamflow characteristics of the Liard River (Yukon, Canada) for the present climate, under the IPCC B2 emissions scenario for 2050, and 2100. Showing the (a) date of arrival of spring freshet, (b) annual flow, and monthly flows for (c) April, (d) May, and (e) June. Source: Woo et al. (2008).

future probabilities in Figure 4.19b). An earlier melt season will spread the basin snow melt over a longer period (Figure 4.19c, d, e) (Woo et al., 2008).

Reduced snow accumulation, earlier snow melt, and increased evaporation (and sublimation) have consequences for seasonal and longer-term storage of water and ice. Many late-lying and semi-permanent snowbanks will shrink or disappear from the Arctic landscape. Snow storage on glaciers will change with negative consequences for their mass balance (see Chapter 7). The loss of snowbeds will lead to the demise of many patchy wetlands in the Arctic that depend on the late-lying snow to sustain wetland saturation (Woo and Young, 2003). For all northern wetlands, snowmelt flood is of great importance, as it replenishes wetland storage every spring through infilling of surface depressions and saturation of the peat and mineral soils (Woo and Guan, 2006). With diminished spring floods and a longer snow-free season for evaporation, the hydrological and ecological health of northern wetlands could deteriorate, but thawing permafrost and associated thermokarst could provide a new source of water. The critically important balance between the two processes is unknown, and areas of drying tundra as well as of increased waterlogging are both being reported (see Chapter 5).

4.4.3. Ecological processes and the role of snow cover

4.4.3.1. Interactions between snow and vegetation

The interaction between snow and vegetation is complex, and can involve interception, sublimation, snow trapping (Figure 4.20), energy exchanges, and hydrology. On the one hand, vegetation has strong and complex influences on the accumulation and ablation of snow (Pomeroy et al., 2006), which are expected to alter as vegetation distribution or structure change under a warming climate. On the other hand, snow provides protection for vegetation from extreme low temperatures, large temperature fluctuations, ice crystal blast, and desiccation.



Figure 4.20. Intercepted snow as shown in Kuusamo, northern Finland, can remain in a forest canopy for some time. Photo: Licensed under a Creative Commons CC BY SA License; Author: Muu-karhu.

4.4.3.1.1. Effects of vegetation on snow – vertical profile

Snow falling onto shrubs and trees is partitioned into interception by the canopy and throughfall to the ground (Hedstrom and Pomeroy, 1998). As the intercepted snow load increases, the interception efficiency increases due to snow bridging between canopy elements but decreases due to bending of branches under the load. Canopy capacities can be much greater for snow than for liquid water and intercepted snow can remain in a forest canopy for some time. Snow can be removed from canopies by direct unloading, drip of meltwater, and sublimation (Storck et al., 2002; Molotch et al., 2007).

According to Sámi reindeer herders, large trees in old forests trap part of the snowfall, thereby reducing the depth of the snow on the ground. In younger stands, with only small seedlings, most of the snow accumulates on the ground, resulting in a deeper snow cover (Kumpula et al., 2007). When all the snow that has accumulated in the canopy of a dense even-aged stand melts and falls, the snow cover is compacted over the whole stand. In such cases, reindeer herders can only use stands with low stem density or stands in which younger trees with smaller crowns have not trapped as much snow (Roturier and Roue, 2009).

4.4.3.1.2. Effects of vegetation on snow – horizontal aspects

Vegetation reduces the horizontal redistribution of snow and can therefore have greater snow depths than open areas, particularly downwind of vegetation patch edges where snow relocated from open areas can be trapped. Snow trapping depends on the height, density, and distribution of vegetation, all of which are projected to change under a warming climate. Snow in shrub patches contains a greater percentage of low-density depth hoar, increasing the insulation of underlying soil (Sturm et al., 2001a).

4.4.3.1.3. Effects of vegetation on the energy balance of snow

Vegetation can increase or decrease snow-melt rates relative to open areas depending on vegetation characteristics (Davis et al., 1997; Lee and Mahrt, 2004; Pomeroy et al., 2006). However, many processes are involved, and the net outcome in the context of vegetation changes is difficult to model.

Vegetation shades snow on the ground from solar radiation to an extent dependent on the density of canopy elements exposed above the snow and the fractions of the incoming radiation that are direct or diffuse. In areas of discontinuous vegetation cover, even snow in open areas can be shaded by cast shadows, particularly in the Arctic where the sun is low in the sky. Although sophisticated models of radiative transfer through vegetation canopies exist (e.g., Ni et al., 1997), practical applications almost invariably use simpler models that only consider vertical fluxes and thus cannot represent shading or canopy gaps (Bewley et al., 2007); the measurement of accurate spatial statistics is also challenging (Link et al., 2004).

Merely because the thermal emissivity of canopy materials is higher than that of air, the presence of a vegetation canopy can greatly increase the net thermal radiation absorbed by snow (Sicart et al., 2004). Moreover, because vegetation has a lower

albedo than snow and can be warmed to temperatures above 0 °C, sun-lit vegetation can have temperatures well in excess of the air and snow temperatures, further increasing the thermal radiation emitted to the snow (Pomeroy et al., 2009). These influences will be least under dense vegetation that limits the penetration of solar radiation and greatest close to the sun-lit edges of vegetation patches (Essery et al., 2008). Because snow generally has a high albedo and only absorbs a small fraction of the incoming solar radiation, the increase in thermal radiation due to the presence of vegetation can exceed the corresponding reduction in solar radiation in the radiative energy balance of a snowpack (Sicart et al., 2004). Sparse vegetation debris lying on a snow surface reduces its albedo (Hardy et al., 1998), thereby increasing melt rates while buried branches and litter absorb solar radiation that can penetrate to some depth in snow, possibly leading to subsurface melting. Turbulent transfers of heat to a snow surface are increased by the exposure of sparse vegetation but decreased by dense vegetation cover (Reba et al., 2009).

Ground vegetation also plays a key role in thawing and freezing events. According to Sámi reindeer herders, in forests with a thick layer of vegetation, the water flows down through the generally thick moss layer, leaving the lichen accessible for the reindeer to graze. In contrast, in thinner layers of lichen-dominated vegetation, the water soaks into the lichen mat and freezes, forming a crust of ice and limiting its availability as reindeer fodder (Roturier and Roue, 2009) (see Section 4.4.3.2 for impacts of these freezing and thawing events on animals).

4.4.3.1.4. Effects of snow on vegetation

There is a close relationship between snow distribution and vegetation type (Evans et al., 1989), and the heterogeneity of the snow regime helps drive the (large-scale) diversity of the Arctic flora. For example, the high wind speeds in the Arctic ensure considerable redistribution of snow, and some areas may be exposed and snow free for much of the winter, while others, such as snowbeds that often have relatively high diversity and harbor rare plant species, accumulate snow. Exposed areas typically have cushion plants, evergreen dwarf shrubs and tussock graminoids, whose forms provide protection from wind abrasion and summer drought stress (Walker et al., 2001). Plants covered by snow in winter often have the capacity to burst bud quickly after snow melt from buds pre-formed in the previous growing season and using carbohydrate reserves from the previous season's photosynthesis. Such rapid response maximizes their use of the short Arctic growing season (Chambers, 1991; Walker et al., 2001) determined by the period and timing of SCD. The ongoing and projected changes in snow conditions presented in earlier sections will profoundly affect the distribution of vegetation and biodiversity.

Arctic plants may be physiologically active under snow before completion of melt, especially in the later stages of melt when soils may be warmer and enough light may penetrate the snow to allow photosynthesis. Lichens and bryophytes are most capable of this, as they are physiologically active at low temperatures, have low-light compensation points, are able to acquire moisture and nutrients directly from meltwater, and have an opportunistic growth strategy that allows quick reactivation when suitable growth conditions occur (Kappen

et al., 1995; Walker et al., 2001; Kappen and Valladares, 2007). However, such activity is detrimental to lichens, because their freeze tolerance has a high carbohydrate cost, particularly in warm, low-light subnivean cavities (Kappen et al., 1995). An increase in SCD or warm subnivean conditions may result in declines in these species (Benedict, 1990).

In contrast, vascular plants (e.g., herbs, shrubs, grasses, sedges) in the Arctic show less ability for subnivean activity, although they are capable of rapidly increasing rates of photosynthesis following snow melt (Tieszen, 1974; Defoliart et al., 1988) and some vascular plants are capable of net photosynthesis below snow during melt (Semikhatova et al., 1992; Starr and Oberbauer, 2003). Such favorable conditions may last for two to four weeks and thus represent a significant extension of the growing season. Indeed, cold season photosynthesis (from vascular and non-vascular plants) was recently found to constitute a considerable amount (19%) of the gross annual CO₂ uptake in sub-Arctic heathland (Larsen et al., 2007a).

Snow can provide nutrients to some plants. Arctic vascular plants captured less than 0.1% of their annual nitrogen requirement from melting snow in the tundra (Bilbrough et al., 2000), while bryophytes and lichens gained ten-fold more. Similarly, in the High Arctic, bryophytes and lichens (as well as soil microbes) showed much better ability to acquire snowpack nitrogen than vascular plants (Tye et al., 2005).

Snow manipulation experiments suggest that responses of vegetation to changing snow-melt timing may not be simple. Some snow-depth manipulations suggest that where areas have rapid snow melt, even considerable increases in snow depth may have only modest impacts on growing season length (Walker et al., 1999). Nevertheless, delayed snow melt can delay plant phenology and ultimately productivity (Walker et al., 2001). However, delayed vegetative growth and flowering may also lead to delayed senescence and ultimately no increase in productivity (Walker et al., 1999). Similarly, species showing earlier physiological activity induced by snow removal and warming manipulations can show earlier senescence, again with no increase in productivity (Starr et al., 2008). Therefore, where Arctic plants have such determinate growth, an earlier growing season may not mean a more productive growing season, but in the longer term, when species with more southern distributions invade, the system is likely to become more productive (Sitch et al., 2008; Wolf et al., 2008).

4.4.3.1.5. Impacts of winter thaw on vegetation

Projected increases in Arctic winter precipitation may be accompanied by increased occurrences of winter thaw (see Section 4.3.1.3.1). Melting of snow cover in the Arctic begins at below-freezing air temperatures (it starts with temperatures as low as -5 °C) owing to the influence of solar radiation (Radionov et al., 1996). The first snow melt can occur in winter, and for several months thereafter the snowpack remains on the ground. However, even the first such melt initiates a process of snow metamorphosis on its surface that changes snow albedo by generating a snow crust on the surface and ice layers within the snowpack or at the ground surface. Such crusts and ice layers remain until complete snow melt and have important, often devastating, consequences for some animal populations

including domesticated reindeer (see Section 4.4.3.2).

Increases in mid-winter melt events and rainfall instead of snowfall are suggested by the records of some stations in northwestern Canada (Burn et al., 2004) and in the western part of northern Eurasia (Groisman et al., 2003). For example, in Fennoscandia, in the second half of the 20th century, the number of days with winter thaw increased by six over 50 years, or by 35% (Groisman and Soja, 2009; Groisman et al., 2010), while the number of days with rain-on-snow events increased by at least three (see also Figure 4.12; Shmakin, 2010). These events result in sudden loss of snow protection to vegetation. Temperatures rise rapidly to well above freezing, causing snow melt at landscape scales (Robinson et al., 1998; Phoenix and Lee, 2004; Bokhorst et al., 2008, 2009), warming plants and soils and then (following a few days of warming) exposing the ecosystem to rapidly returning extreme cold. Simulation of such events in the sub-Arctic together with observations of a natural event in winter 2007/08 has shown that shrub species may suffer with increased mortality of buds and shoots, delayed bud burst in spring, and reduced flowering and berry production (Bokhorst et al., 2008, 2009). The large scale of the natural event that reduced the Normalized Difference Vegetation Index (NDVI) (related to productivity) over more than 1400 km², suggests that extreme warming events may reduce productivity of Arctic vegetation and counterbalance (Bokhorst et al., 2009; Figure 4.21) the long-term trend of shrub expansion into the tundra (Sturm et al., 2001b; Tape et al., 2006).

In the northernmost coastal rainforest region of British Columbia and southeast Alaska, winter thaw events are an important factor in the decline of one of the most valuable timber species in North America: Alaska yellow-cedar (*Chamaecyparis nootkatensis*). This tree has experienced several waves of death over an area of more than 200 000 ha caused by freezing injury to the roots of the trees after the premature loss of winter hardiness (physiological resistance to freezing injury). In recent warm winters, the Alaska yellow-cedar has encountered thawing events in late winter (February) warm enough to cause it to lose winter dormancy (Hennon et al., 2006). When temperatures return to the below-freezing levels normal for that time of year, freezing penetrates into the snowless ground, killing the shallow roots (Beier et al., 2008). Consequently, Alaska yellow-cedar is being eliminated quickly from the southern and lower elevation portions of its current distribution, while it gradually migrates, becomes established, and matures in the northern and higher elevations beyond its current distribution. The result is the net loss of commercial benefits from the species for a number of centuries.

4.4.3.2. Interactions between snow and animals

Snow is probably one of the most important climatic drivers affecting Arctic biology and its environment (Callaghan et al., 2005; Møltøfte et al., 2008; Post et al., 2009). The interaction between snow and Arctic animal species is determined by the varying abilities of Arctic species to migrate (Figure 4.22; Forchhammer et al., 2008; Robinson et al., 2009). Migratory caribou, for example, prefer regions with higher snowfall and lichen availability during their autumn and winter migrations (Sharma et al., 2009). However, ice crust formation can obstruct migrations. In the Yamal Peninsula, ice crusts may become as




Figure 4.21. A mid-winter warming event in December 2007 and its impact on vegetation over 1400 km² in sub-Arctic Norway and Sweden. Air temperatures (a) increased at three sites along a transect from Narvik, Norway, to Abisko, Sweden, (68° N) for a few days in December and snow melted (b) before returning. The few snow-free days resulted in the death of some dwarf shrubs in open, alpine habitats (photo left) and coastal pine forests (photo right). Snow remaining in depressions protected vegetation (left insert); whereas unprotected vegetation died (right insert). Source: Bokhorst et al. (2009).

common in the northern part as they currently are in the southern part. Such a development would further constrain the possibility for reindeer to migrate on the peninsula (Bartsch et al., 2010).

Whereas species resident in the Arctic (lemming, musk ox, stoat) and locally migrating (fox, caribou/reindeer, ptarmigan) will experience varying snow conditions throughout the year, long-distance migrating species (waders, geese, gulls, skuas, terns) are influenced only by the conditions when they arrive at their Arctic breeding grounds in spring. A 10% decrease in snow cover, advances egg laying by the pink-footed goose (*Anser brachyrhynchus*) by five to six days, corresponding to a 20% increase in probability of nesting success (Madsen et al., 2007). Such considerable responses in population dynamics to changes in snow cover make species highly sensitive to alterations in climate. For the pink-footed goose population breeding on




Figure 4.22. Schematic illustration contrasting the potential interactions between snow and resident Arctic animal species and between snow and migrating animal species that breed in the Arctic but overwinter in temperate or tropical regions. Changes in local weather conditions in wintering areas, en route, and in the Arctic breeding grounds have been coupled to changes in large-scale teleconnection patterns such as the Arctic Oscillation (AO), the North Atlantic Oscillation (NAO), and the El Niño Southern Oscillation (ENSO). Source: Forchhammer and Post (2004). This indicates that climate change effects embrace considerable geographical ranges. However, the consequences of land-use change and sea level rise have not been included in the scheme and could have further effects.

Svalbard, a 1–2 °C increase in temperature that would probably affect snow cover could potentially double the breeding range there (Jensen et al., 2008), provided that conditions at wintering grounds outside the Arctic remain favorable (Wisze et al., 2008). Thus, climate effects across the entire range of a species become pivotal in estimating effects taking place in the Arctic (Figure 4.22; Forchhammer et al., 2008).

In addition to the apparent direct negative effect of increased snow cover on the populations of resident Arctic species such as musk ox (*Ovibos moschatus*) (Figure 4.23a), often mediated through increased over-winter mortality, changes in snow cover may also interact with animals in an indirect and delayed manner through interactions across trophic levels in Arctic ecosystems. Changes in snow cover determine the length of the Arctic growing season (Schmidt et al., 2006; Meltofte et al., 2008) and, hence, the resource base for Arctic herbivores (Forchhammer et al., 2005). For example, over the period 1970 to 2006, reindeer calf production in Finland increased by almost one calf per 100 females for each day of earlier snow melt (Turunen et al., 2009). Similarly, the decadal increase in spring temperature and advance of spring snow melt and consequently the longer growing seasons of 1996 to 2005 observed in northeast Greenland have had a positive influence on the musk ox population there, but the effects of a long growing season were delayed by one year (Figure 4.23b). The relative importance of direct and delayed effects on Arctic herbivores such as the musk ox may vary across the Arctic depending on local climate conditions (Forchhammer et al., 2008). At Ellesmere Island, years with extensive snow cover delayed the vegetation growth, resulting in a halving of the herbivore nutrition-replenishment period, a drastic drop in musk ox and Arctic hare (*Lepus arcticus*) numbers, and a cascading reduction in the population of their predator, the wolf (*Canis lupus*) (Mech, 2004).

Changes in the micro-topical snow conditions may also




Figure 4.23. Contrasting effects of snow cover on the musk ox population at Zackenberg, northeast Greenland: (a) direct negative effect of early spring snow cover (10 June) on current-year population, and (b) delayed positive effect of increased length of the growing season on the population the following year. The length of the growing season is defined as the period with positive ecosystem assimilation and is closely related to the date of snow melt ($r = -0.84$, $n = 8$, $p < 0.05$). Annual population numbers of musk ox are given as relative values adjusted for (a) density dependence and (b) density dependence and spring snow cover. Data from Forchhammer et al. (2008).

influence the dynamics of northern rodents (Hörnfeldt et al., 2005; Kausrud et al., 2008). A recent comprehensive study by Kausrud et al. (2008) demonstrated that increased humidity and temperature are related to increased hardness of the snowpack, which decreases the available subnivean space, causing a decline in rodent population growth rates. A collapse in rodent population size has cascading effects on predators such as Tengmalm's owl (*Aegolius funereus*) (Hörnfeldt et al., 2005). As some predators have other prey in addition to the rodents, such as ground-nesting birds, the effect of the micro-topical

changes in snow conditions that affect the rodent population dynamics could be related to changes in the populations of ground-nesting bird species (Kausrud et al., 2008). Indeed, since any Arctic animal is part of a community and, hence, interacts with other species within as well as across trophic levels, the interaction between snow and the performance of one species may potentially extend to other species (Figure 4.24; Forchhammer et al., 2008; Callaghan and Johansson, 2009; Post et al., 2009).

In addition to the effects of snow depth, SCD, and timing of the snow season on animals, the texture of snow and extreme events in winter are also critical. In extreme cases, crusts, ice layers, and rain-on-snow events have been implicated in population crashes of reindeer on Svalbard (Aanes et al., 2000; Kohler and Aanes, 2004) and the near extirpation of Peary's caribou (*Rangifer tarandus pearyi*) in High Arctic Canada (Barry et al., 2007). On Banks Island in October 2003, a rain-on-snow event is estimated to have contributed to the deaths of 20 000 musk ox by creating a thick layer of ground ice that made foraging very difficult (Rennert et al., 2009). On the Queen Elizabeth Islands, Canadian High Arctic, major population crashes in caribou have been mainly due to exceptionally unfavorable snow or ice conditions (Miller and Barry, 2009).

The Sámi and Nenets have experienced the increasing frequency of extreme weather events. Nenets reported one rain-on-snow event in which impenetrable ice layers formed during a major two-stage thawing and refreezing event over a 48-hour period across an estimated 60 × 60 km area on the southern Yamal Peninsula in November 2006 (Forbes, 2008; Forbes and Stammer, 2009). The same area was affected by an even more extensive icing event a few months later in January 2007, covering an area approximately 60 × 100 km and causing the death of a large number of reindeer (Forbes and Stammer, 2009; Bartsch et al., 2010). Although the November event was considered unusual, the January event was deemed to be outside the experience of the herders interviewed.

In Fennoscandia, ice crust formation causes reindeer mortality (Moen, 2008) and calf production is reduced (Helle and Kojola, 2008). For example, during the last week of December 2007, a sudden period of warmer weather ruined good grazing pastures in northern Sweden. “*The mild period arrived suddenly, and in one week the temperature was 10 °C.*

Most of the snow melted and then froze again, and the ground was covered in ice. Only two weeks before we thought the guohtun (powder snow) would be good, and now it was completely inaccessible, locked away under the ice.” (R. Stokke, pers. comm., 30 August 2008, Jokkmokk Sweden).

This was probably the same event that damaged vegetation over large areas of northern Norway and Sweden (Bokhorst et al., 2009). In contrast to the deaths of wild animals in response to extreme winter events, the impacts on semi-domesticated reindeer are mitigated by the costly process of supplementing the natural diet with food pellets.

Future warming could be associated with events that cause sudden and dramatic step changes, rather than progressive trends, in animal and plant biodiversity (see Section 4.4.3.1 for mid-winter thaw on vegetation).

4.4.3.3. Interactions between snow and biogeochemical cycles

Until a decade ago, Arctic ecosystems were considered inactive in terms of trace gas fluxes during the long winter period, but recent studies show that winter respiration of CO₂ represents a significant portion of the annual carbon budget (e.g., Fahnestock et al., 1998). As snow acts as an insulator and increases ground temperature, projected increases in snow depth, for example in the High Arctic, will play an important role in biogeochemical cycling during winter. For example, a record high ground temperature recently occurred abruptly in the central Lena River basin, Russia, following increasing precipitation (Iijima et al., 2010).

Soil temperature and vegetation type are the main drivers of respiration rates during winter in the Arctic (Grogan and Jonasson, 2006). However, vegetation types only influence respiration in areas where the snow depth is below a certain threshold (~1 m deep). Tall vegetation that enhances snow accumulation within that threshold results in more effective thermal insulation from severe air temperatures and thereby significantly increases respiratory activity (Grogan and Jonasson, 2006). Experimental manipulation of snow depth in the Swedish sub-Arctic showed that an increase of 20 to 30 cm of snow in March (added to 74 cm and 27 cm in a birch and heath site, respectively) increased the ecosystem respiration




Figure 4.24. Schematic overview of the consequences of increased snow cover on the terrestrial vertebrate community at Zackenberg, northeastern Greenland. Arrows indicate potential direct (solid arrows) and indirect (dashed arrows) effects. Source: Forchhammer et al. (2008).

rates by 77% and 157% compared to control plots. Later in the season, there was no significant effect of the increased snow cover (Larsen et al., 2007b). In High Arctic Canada, Nobrega and Grogan (2007) increased snow thickness from 0.3 m to 1 m, which resulted in a mean total winter efflux increase of around 60% in birch hummock tundra sites. Their results suggest that a moderate increase in snow depth can enhance winter respiration sufficiently to alter the ecosystem annual net carbon exchange from a sink to a source, resulting in a net release of CO₂ to the atmosphere, at least in the short term.

The depth of snow, in particular toward the end of the spring, will also have obvious importance for the hydrology at the onset of the growing season. This, in turn, will have strong impacts on the degree of waterlogging and, hence, the potential emissions of other important greenhouse gases, such as methane (CH₄) and nitrous oxide (N₂O); in that emissions will increase with the extent of waterlogging.

The date of snow melt is important for the growing-season accumulated uptake of carbon, as solar radiation input is high at this time compared with the period in autumn when the snowpack is formed (Callaghan et al., 2005). Euskirchen et al. (2006) estimated that for each day that the growing season increased across the pan-Arctic region over the period 2001 to 2100, the carbon drawdown increased by 9.5 gC/m² per year.

4.4.3.4. Geochemical processes in the snow cover

Analysis of the heavy metal content in snow provides useful information on aerosol composition and long-range distribution patterns of anthropogenic substances emitted into the atmosphere at lower latitudes (Colin et al., 1997; Walker et al., 2003). The effects of heavy metals are many and varied and depend on factors such as the particular metal, the organism, and the mode of uptake (Dietz et al., 1998). Their greatest toxic impacts occur in animals at the higher trophic levels where bioaccumulation through the food chain can result in high concentrations. The few available data on heavy metal concentrations in snow on ice surfaces in the Russian Arctic seas (Melnikov et al., 1994; Gordeev and Lisitzin, 2005; Shevchenko, 2006; Golubeva, 2007) mostly show no evidence of pollution, except in areas near the large industrial centers of the Kola Peninsula (Monchegorsk, Nikel) and Siberia (Norilsk) and along the Northern Sea Route. In the near future, new pollution from the oil and gas industry in the Barents and Kara Seas is possible (AMAP, 2007).

Many factors have led to a significant reduction in on-ice snow volume. These include a decrease in SCD on the Russian Arctic coast (Bulygina et al., 2009); a reduction in Arctic sea-ice extent at the end of the melt season in September (Stroeve et al., 2007); changes in precipitation patterns, particularly shifts from snowfall to rainfall; a delay in the onset of autumn ice formation; and a reduction in multiyear ice (Harbeck et al., 2008). These processes lead to changes in the size of the storage reservoirs for contaminants such as heavy metals (especially mercury), as well as persistent organic pollutants, such as PCBs (polychlorinated biphenyls) and DDT (see Chapter 11, Section 11.3). Changes in the size of the storage reservoirs, and in the processes driving these changes, could increase the delivery of heavy metals to the tundra and coastal ecosystems through changes in dry deposition and wet deposition through rainfall

and fog. However, at the same time, heavy metal accumulation in snow cover on drifting ice will decrease, reducing the amounts of heavy metals transported by sea ice to areas of seasonal melting (i.e., Fram Strait and the northwestern part of the Barents Sea). This could result in a redistribution of heavy metal pollution.

Heavy metals may be deposited in greater quantities over marine areas than terrestrial areas because of the nucleating effects of sea salt, and increased rates of coastal and marine ice-fog formation and fog-related deposition (Garbarino et al., 2002). Conversion of gaseous elemental mercury to halogenated compounds following photochemical reactions in the spring may also contribute to increased levels of mercury over sea ice and water. In areas where snow is not present on the sea ice, the mercury can move more quickly into the seawater through cracks in the ice cover.

Long-term observations on the transport of air masses toward three sites in the Russian Arctic (Vinogradova and Ponomareva, 2007) suggest a reduction in the levels of anthropogenic pollutants in the aerosols over the central part of the Russian Arctic and thus a decrease in the total quantities of these pollutants deposited to the Arctic surface each year. This may result in rivers becoming a proportionately more important sink for these pollutants, if the decrease in atmospheric levels within the Arctic is due to greater deposition to rivers, snow and soil in sub-Arctic river catchments (i.e., closer to the sources). However, for lead, cadmium, and zinc the Arctic is likely to become a more effective trap, because precipitation is projected to increase (Macdonald et al., 2005).

Concentrations of gases in the Arctic atmospheric boundary layer are affected by chemical reactions on ice surfaces in snowpacks. These processes are the result of a combination of factors: snowpacks are permeable, allowing exchange between snowpack interstitial air and the atmosphere (Domine et al., 2008); snowpacks strongly forward-scatter radiation, resulting in sunlight penetration well below the surface (Simpson et al., 2002); and deposition to snowpacks concentrates many compounds. Snowpack reactions affect nitrogen oxides, halogens, ozone, organic compounds, and mercury. Mercury is a particular concern in the Arctic because of its ability to bioaccumulate and biomagnify in food webs and because it can be toxic to biota even in very small quantities. Snow plays a significant role in accumulating and redistributing mercury (Johnson et al., 2008; Steffen et al., 2008). At two sites near Barrow, Alaska, surface snow mercury concentrations increased by 15 to 30 times during a nine-day 'atmospheric mercury depletion event' (a period during which there is a sharp drop in the concentration of gaseous elemental mercury in the lower atmosphere), and much of this mercury was retained until snow melt (Johnson et al., 2008). The mercury concentrations in surface water in a small creek near the sampling sites ranged from 10 to 15 ng/L (i.e., were elevated due to the deposition event) during a ten-day peak snow runoff period (Douglas et al., 2008).

Snow contains nitrate owing to the deposition of atmospheric nitric acid and particulate nitrate. Exposure of the snowpack to ultraviolet radiation (wavelengths below ~340 nm) results in nitrate photodissociation and the formation of nitrogen dioxide (NO₂), nitrite, and hydroxyl radicals (OH) (Honrath et al., 2000; Chu and Anastasio, 2003). NO₂ formed near the ice

surface can be released into the snowpack interstitial air (Boxe et al., 2003). The resulting efflux of nitrogen oxides (NO_x , i.e., NO and NO_2) from the snowpack has been measured (Jones et al., 2001; Beine et al., 2002; Honrath et al., 2002; Oncley et al., 2004). Nitrite is itself photodissociated, forming nitrogen monoxide (NO), and under sufficiently acidic conditions, can also be released in the form of nitrous acid (HNO_2) (Zhou et al., 2001; Amoroso et al., 2006). HNO_2 fluxes have also been measured (Zhou et al., 2001; Honrath et al., 2002; Beine et al., 2003, 2005, 2006; Amoroso et al., 2006) but vary widely; this is attributed to variations in snowpack pH (Beine et al., 2003), although measurement biases have also been suggested (Liao et al., 2006; Kleffmann and Wiesen, 2008). OH formed from nitrate photolysis, and in greater amounts by photolysis of hydrogen peroxide (Chu and Anastasio, 2005; France et al., 2007), is a strong oxidant of organic compounds. It is expected that OH oxidation of ubiquitous snowpack organic matter (discussed in the review by Grannas et al., 2007) occurs and contributes to observed enhancements of carbonyls and carboxylic acids in sunlit snow as well as the processing of anthropogenic organic pollutants that have deposited (Sumner and Shepson, 1999; Dibb and Arsenault, 2002; Grannas et al., 2004). Furthermore, sunlight absorption by uncharacterized organic compounds is significant and may initiate additional, as yet uncharacterized, photochemical reactions in the snowpack (Anastasio and Robles, 2007).

Ozone is destroyed in sunlit snow by a photochemically initiated process (Peterson and Honrath, 2001; Albert et al., 2002; Helmig et al., 2007) (and, at a slower rate, in the dark; Albert et al., 2002). The underlying mechanism is not yet clear. However, ice-surface reactions that release bromide ion as Br_2 or bromine monochloride (BrCl) are believed to be important sources of the active bromine (Br) that is responsible for Arctic boundary layer ozone depletion (see review by Simpson et al., 2007). It is believed that such 'bromine explosion' reactions occur to a significant extent on snowpack surfaces (Simpson et al., 2005; Piot and von Glasow, 2008). Br_2 has been observed in snowpack interstitial air (Foster et al., 2001), and it has been suggested that Br release into interstitial air may be responsible for snowpack ozone destruction even far from the ocean (Peterson and Honrath, 2001). The atmospheric impact of the snowpack ozone destruction has been observed at Summit, Greenland, during summer, where it is the apparent cause of a ~ 1 ppb diurnal variation in ozone concentration (Helmig et al., 2002). Owing to strong surface stability, simulated Arctic ozone concentrations are very sensitive to small variations in the poorly constrained ozone deposition velocity to the Arctic snowpack (Helmig et al., 2007), and ozone destruction within the snowpack, therefore, reduces boundary layer ozone concentrations.

The effects of air-snow surface exchange fluxes are amplified under the stable atmospheric conditions frequently present in the Arctic. Snowpack emissions appear to dominate the springtime budget of NO_x in the stable Arctic atmospheric boundary layer when relatively fresh combustion emissions are absent. Enhanced NO_x concentrations with mid-day peaks attributable to snowpack emissions have been observed at a variety of Arctic locations, with peak NO_x reaching 30 to 50 parts per thousand (ppt) (or NO reaching 10 to 15 ppt) during spring at North American locations (Ridley et al., 2000;

Beine et al., 2002; Honrath and Jaffe, 1992) and 50 to 100 ppt NO_x during summer on the Greenland Ice Sheet (Yang et al., 2002). (These mixing ratios are significantly higher than those at 30 m altitude (Ridley and Orlando, 2003), reflecting the strong surface stability.) Owing to their controlling impact on boundary layer NO_x , snowpack emissions also appear to dominate atmospheric total nitrate above the Arctic snowpack (Morin et al., 2008).

4.4.4. Socio-economic processes and the role of snow cover

4.4.4.1. Water resources and hydropower

Electricity demands are rising in some areas of the Arctic, such as the Northwest Territories and Nunavut in Canada, due to increasing population and heavy industry (Furgal and Prowse, 2008). Projected changes in snow cover and duration will affect the capacity and operations of current and future hydroelectric developments and might resolve some of the rising needs. A more even distribution of water discharge will reduce the need for peak reservoir levels without generating maximum electricity, particularly if precipitation increases (Gode et al., 2007). In areas where winter precipitation is expected to increase (see Section 4.3.2.2), an increase in runoff is also expected. In Swedish sub-Arctic Suova, the increase in runoff is expected to be as much as 53% (ECHAM4OPYC3 model with IPCC A2 emissions scenario) by the end of the 21st century due to increased precipitation (Table 4.3, Gode et al., 2007).

Projected increases in winter rainfall and increased freeze-thaw cycles are expected to lead to an enhanced winter snow melt and a decline in winter storage and, hence, contributing to a more even runoff over the year (Gode et al., 2007; Furgal and Prowse, 2008). The amount of water available for hydropower is also dependent on glacier runoff and this is projected to increase in some areas and decrease in others during the present decade (see Chapter 7). In Sweden, production from hydropower was projected using the EMPS model to simulate the potential use of power plants with increasing runoff and using knowledge on current facilities and potential expansion, etc. The results suggested that the greatest changes in runoff are expected to occur in winter, although there was a more even distribution throughout the year (Table 4.4; Gode et al., 2007). The large variation between the results for the two GCMs used provides a challenge for economic forecasting.

Current hydroelectric power plant capacity and design are based on climatological and hydrological statistics, but as the climate changes, conditions for the power plants will alter. For example, in some regions reservoir capacities may need to be expanded to offset changes in runoff, both for seasonal and total annual runoff. In addition, the construction of hydropower

Table 4.3. Projected percentage increase in runoff using HadAM3H and ECHAM4/OPYC3 for Suova in sub-Arctic Sweden using the A2 and B2 emissions scenarios (Gode et al., 2007).

Year	HadAM-A2	HadAM-B2	ECHAM-A2	ECHAM-B2
2011 – 2040	5.5	3.6	24.1	15.9
2071 – 2100	12	8	53	35

Table 4.4. Changes in runoff and production calculated using the EMPS model on a seasonal basis in Sweden (Gode et al., 2007).

	Reference period 1960 – 1991			HadAM-B2 2071 – 2100			ECHAM-B2 2071 – 2100		
	Winter	Summer	Annual	Winter	Summer	Annual	Winter	Summer	Annual
Runoff (TWh)	12.5	53.5	66.0	21.5	49.9	71.3	30.4	51.2	81.6
Production (TWh)	34.2	28.1	62.3	34.8	31.5	66.3	39.4	35.1	74.5

dams needs to take into account the different future projections for ice conditions (see Chapter 6).

4.4.4.2. Infrastructure development

There has been a rapid and ongoing increase in the development of large-scale wind farms, mines, and oil and gas fields in the European Arctic. This construction entails a relatively widespread infrastructure of roads, buildings, and power lines, often within important reindeer pasture. Disturbance is a source of stress for the animals while they are within or near a development area (Vistnes et al., 2001). Avoidance of certain reindeer pastures can lead to less optimal range use, complications with herding, increased costs, and reduced production. Negative effects such as these may be exacerbated by changing snow conditions that further limit access to food (Kumpula et al., 2007).

Although cumulative impacts are likely to be important (e.g., McCarthy et al., 2005), reindeer herders in the Nenets Autonomous Okrug and the Yamal-Nenets Autonomous Okrug consider unbridled oil and gas development on their territories to be a far greater threat to their resilience than extreme weather such as winter thaw and icing events (Nuttall et al., 2005; Forbes 2008; Forbes and Stammler 2009). This contrasts with the situation elsewhere, such as Nunavut, Alaska, and Sápmi, where scientists and some indigenous politicians have sounded the alarm about climate change (Forbes and Stammler, 2009).

4.4.4.3. Transport

Rising temperatures in the Arctic, particularly decreases in the number of very cold days, later onset of seasonal freezes, and earlier onset of seasonal thaws (as projected for many Arctic areas – see Section 4.3.2), could mean reduced costs of snow and ice control, as is the case in the mid-latitudes with seasonal snow cover. In the United States, snow and ice control accounts for about 40% of annual highway operating budgets in the northern states (NRC, 2008). Climate variables of particular relevance to the transportation sector in Alaska include the extent of sea ice, snow cover, and permafrost. In many northern states, for example, rising winter temperatures will decrease snow and ice removal costs, lessen adverse environmental impacts from the use of salt and chemicals on roads and bridges, extend the construction season, and improve the mobility and safety of passenger and freight travel through reduced winter hazards (NRC, 2008). Climate models project a shortening of the snow cover season over most of the Arctic. This will decrease the operational period of winter road networks that are important for low cost resupply of many northern communities in Canada (Furgal and Prowse, 2008) and shorten the period that snowmobiles can be used for hunting and reindeer herding. Changes in the amount and

timing of the snow cover will also affect the transportation platform that lake and river ice provide in the Arctic during winter (see Chapter 6). Winter roads in Russia (*zimnik*) will be affected differently in different parts of the Russian high latitudes. In general, these roads can be used when temperatures are below -7°C (Peschanskiy, 1967).

4.4.4.4. Forestry

Where precipitation in the boreal region is most abundant (eastern Canada, western Russia, Fennoscandia), an increase in temperature can often result in increased tree growth in healthy trees (Saxe et al., 2001) and a northward and upward extension in range. Many models project a general northward movement of the boreal forest under a warming climate, that will displace between 11% and 50% of the tundra within 100 years (Callaghan et al., 2005; Vygotskaya et al., 2007; Sitch et al., 2008; Wolf et al., 2008; Tchebakova et al., 2009) in a pattern similar to that which occurred during the early Holocene climatic warming (see references from Callaghan et al., 2005). Accelerated tree growth and range extension are important commercially for forest products, recreation, conservation, and capture of atmospheric carbon (Goodale et al., 2002). However, the moisture regime in much of the boreal region is only marginally suitable for forest growth and development. Consequently, reduced growth of boreal trees during warming was widespread over much of the past century in nearly all regions and tree species (Lloyd and Bunn, 2007). A declining trend in seasonal photosynthesis on the boreal landscape, as indicated by satellite sensors over the past 25 years, is the main trend in vast areas (Goetz et al., 2005).

New direct experimental results demonstrate that in at least some boreal evergreen conifer species, growth is largely accomplished by moisture supplied from melting of the winter snowpack (Yarie, 2008). In most of the boreal forest region, temperature increases have made the snow-accumulation season shorter and the warm season longer (see Section 4.3.1.2), so that less of the annual water budget is introduced into the ground in the spring pulse of snowmelt. Broadleaf trees can use the variable summer rains more effectively than most conifers, so this change in the seasonal type of moisture (less snow, more rain) now favors the broadleaf trees over conifers and mosses (Juday, 2009). Boreal broadleaf tree ecosystems are characterized by less storage of carbon than conifer-dominated forests owing to faster and more complete decomposition of the dead organic matter they produce (Gower et al., 2001), and this change could be an important positive feedback to climate warming. In addition, the coniferous trees are more widely used in the timber industry.

Tree rings of northern treeline trees show that even at the northernmost high-elevation treeline in western North America, 40% of trees are limited in growth by temperature-

induced drought stress, which occurs at temperatures above an identifiable, consistent threshold (Wilmking et al., 2004). Tree growth patterns across the entire Northern Hemisphere at high-elevation and high-latitude northern treeline sites now show distinct evidence of 'divergence', in which formerly positive tree growth responses to increases in temperature are weaker, non-existent, or even reversed (D'Arrigo et al., 2004; Wilmking et al., 2004) because recent high temperatures are consistently above the threshold causing drought limitation of growth (Wilmking et al., 2005). Under warmer climatic conditions, the northern treeline would probably not advance uniformly into regions that were formerly too cold (as generally perceived), but would advance in a fragmented manner by occupying parts of the landscape with sufficient moisture, for example from snow accumulations.

In recent decades, conifers on productive, low-elevation sites in the interior of Alaska have been stressed to near their adaptive limits within their current North American distributions (Thompson et al., 1999; Barber et al., 2000; Juday et al., 2005). In central Alaska, spruce growth was correlated with seasonal soil-moisture deficit in unthinned control plots, but not in thinned and fertilized plots (Yarie et al., 1990), suggesting that these management treatments could partly relieve moisture stress. Across south-central Canada, the broadleaved tree aspen (*Populus tremuloides*) experienced a major collapse in productivity during the severe drought of 2001 to 2003. Extensive areas of mature aspen stands died from recent extreme weather, almost certainly because of acute drought stress, insect defoliation, and thaw-freeze events (see Section 4.4.3.1.4) (Frey et al., 2004). These developments have come as wood harvested from aspen trees has assumed greater importance as a commercial forest product in recent years because of technological changes that allow or even require the use of its particular fiber characteristics in new products (Mackes and Lynch 2001).

Snow is an important factor in the decline of one of the most valuable timber species in North America. Alaskan yellow-cedar (*Chamaecyparis nootkatensis*) in the northernmost coastal rainforest region of British Columbia and southeast Alaska has experienced several waves of tree death over an area of more than 200 000 ha (Hennon et al., 2008). The cause of the decline is winter thaw events (see Section 4.4.3.1.5). The net effect of these winter thaw events is the loss of commercial benefits from the species for a number of centuries.

In contrast to the beneficial effects of a deep snow cover on tree growth by providing water, heavy snowfall damages forests in Finland. A modeling assessment of risk, in terms of the number of days per year when the accumulated amount of snow exceeded 20 kg/m², projected that compared to the baseline period 1961 to 1990, the risk of snow-induced forest damage and the amount of damaging snowfalls were predicted to decrease, particularly in the north of Finland (Kilpelainen et al., 2010).

Snow anomalies, as they interact with rising temperatures, also affect the insects that feed on boreal tree species. The European spruce engraver beetle (*Ips typographus*) takes advantage of weak and injured conifers. The beetle population increased in trees damaged by heavy storm and snow damage in the late 1960s and reached outbreak levels during a series of warm years with an acute shortage of moisture in the early

1970s (Heliövaara and Peltonen, 1999). From 1971 to 1981, severe outbreaks of *Ips typographus* in southern Norway damaged trees totaling 5 million m³ of timber (Bakke 1989).

The North American engraver beetle (*Ips perturbatus*) is a wood-boring species that attacks already weakened trees, primarily white spruce (McCullough et al., 1998). Extensive tree injury from increased forest fires, climatic stress, and extreme snow events of the past few decades have created optimum conditions for engraver beetle outbreaks (Werner et al., 2006). Cumulative tree mortality is now heavy in many parts of Alaska (Werner et al., 2006). The complex interactions of engraver-beetle tree host, snow, and temperature were displayed during monitoring of a major outbreak in an experimental forest in central Alaska. Engraver beetle populations initially began to increase in abundant injured trees following a 1983 forest fire (Holsten, 1986). During winter 1984/85, heavy snowfall in the early winter broke branches and tops of mature spruce, and the already high engraver beetle populations increased further during spring and summer 1985 (Werner, 1993). An abnormally low snowfall followed in winter 1985/86, producing drought-like conditions in spring 1986 that weakened spruce and rendered it susceptible to a very large engraver beetle outbreak that resulted in a regional episode of high spruce mortality (Holsten, 1986). This formerly uncommon sequence of high early (November and December) snowfall followed by snow drought the next winter has become more frequent in central Alaska in recent decades. A continuation or intensification of these climate trends would reduce the evergreen conifer component of the forest. Because the conifers produce a generally more commercially valuable wood than hardwoods, and because conifer wood is less rapidly decomposed, such a shift has implications for economic return and carbon storage.

The Siberian silkmoth (*Dendrolimus superans sibiricus*) is one of the major outbreaking insect species in northern Eurasia and has a major control on the establishment and survival of Siberian conifers (Siberian fir *Abies sibirica*), Siberian pine (*Pinus sibirica*), Siberian spruce (*Picea obovata*), and Siberian larch (*Larix sibirica*) (Kharuk et al., 2003). The northern border of silkmoth outbreaks was historically represented by a growing degree-day heat sum (10 °C threshold) of 1400 to 1600 °C (Kharuk et al., 2004). During defoliating outbreaks of this insect, as many as 4.0 million hectares have been affected. The full silkmoth life cycle usually takes two years, but in warmer conditions one generation can develop in a single year, while in colder conditions up to three years may be required. Drought can induce some larvae to shift to the shorter 1-year life cycle, so that the adults of two generations emerge simultaneously, increasing the population sharply (FAO, 2009). Historically, outbreaks occurred at 8- to 11-year intervals following a few years of water shortage, and outbreak cycles are now more frequent (FAO, 2009). Within outbreak areas, low elevations and warm, dry, steep slopes experience higher levels of tree mortality (Kharuk et al., 2007). So far, cold climate and sufficient moisture have limited outbreaks to areas generally south of 60° N (Kharuk et al., 2004). However, in the late 20th century, temperature increases and periodic low snow accumulation years facilitated the movement of the Siberian silkmoth westward in Russia, and the species now represents a serious risk for coniferous forests of Belarus, Baltic nations, and the Nordic countries (Gninenko and Orlinskii, 2002).

4.4.4.5. Natural hazards

Snow avalanches are well understood and safety measures are taken in many alpine regions, but the distribution, frequency, and impacts are less well known in the Arctic. However, climate models project warmer winters, increased snowfall, more frequent mixed precipitation, and likely increases in snowfall amounts during extreme events, which may change avalanche potential in some regions of the Arctic. A number of physically-based snowpack models exist that can be used to estimate change in avalanche potential (e.g., Guseva and Golubev, 1989; Brun et al., 1992; Lehning et al., 1999). To date, there has been no systematic assessment of change in avalanche possible over the Arctic in response to climate change as the snowpack models require very detailed site-specific input data. Lazar and Williams (2008) gave an example of the application of the SNTHERM physical snowpack model to estimate potential change in wet avalanche potential in the Aspen ski areas in the United States. Ongoing research at Svalbard aims to understand the response of mountain slope processes to a changing climate to provide a better understanding of its impacts on avalanche potential (www.skred-svalbard.no).

Slush torrents in the Arctic (Figure 4.25) are events that occur within minutes but often have return frequencies over decades and thus are difficult to document (Bull et al., 1995; Gude and Scherer, 1995). Nevertheless, they have claimed lives and are a major driver of the geomorphology of northern mountain landscapes.

4.4.4.6. Tourism and leisure

Arctic tourism is based on scenery (ice- and snowscapes, mountain and tundra vistas), unique Arctic wildlife (including guided hunting), and traditional indigenous cultures. Climate change could dramatically alter all of these.

Tourism in the Arctic is, at best, a marginal enterprise and is highly vulnerable to positive and negative shifts in demand. With the exception of some major cruise lines traveling to the Arctic from Europe and North America and some Alpine ski operations, it is mainly an industry of small-scale operations. With only Alaska as a possible exception, there is no ‘mass tourism’ in the Arctic, and the huge resorts common at lower latitudes are effectively nonexistent (Pagnan, 2003). The range and extent of tourist activity includes traditional hunting and fishing, expedition-style and destination cruising, dog sledding, and cultural and aboriginal tourism (Notzke, 1999). There is

a long tourism history in the Arctic with northern mainland Norway and Svalbard featuring centrally in early Arctic travel (Viken, 2006). In addition to ship travel, there is considerable air travel and road travel, the latter more prevalent in the European Arctic where access to destinations such as North Cape, Norway, is good (Pagnan, 2003). Accurate numbers of tourists are hard to provide for the Arctic.

Arctic tourism faces three main challenges. The first is the high costs of transportation and of maintaining infrastructure in a harsh setting. The second is the short summer tourist season, in effect only a few weeks overall, which makes it heavily dependent on favorable weather conditions. The third is that Arctic tourism is essentially nature-based tourism with limited opportunity to diversify, meaning that any disruption of the natural setting or the wildlife on which the industry depends can have serious, long-term effects on the industry.

The decline in polar bear populations is at least partly due to changing snow conditions; female polar bears make dens in snow to shelter and give birth to young during winter. Cub mortality may increase when higher temperatures lead to rains early in the breeding season, which can melt the under-snow lairs that cubs need for shelter (Smith and Harwood, 2001; Stirling and Smith, 2004). Loss of sea ice (see Chapter 9) that limits the area for snow accumulation that can be used for denning will cause further stress. The polar bear is the icon of the Arctic world. Its disappearance would be a tragic loss and would greatly diminish the polar experience (Lemelin, 2005).

Scenic attractions will change, resulting in site-specific as well as regional challenges and opportunities. Pagnan (2003) pointed out that the tourism industry in the Arctic relies on traditional perceptions of the Arctic environment and expectations about the experience that relate to ice and snow, mountains and tundra, and wildlife. What it will mean for tourists when the inaccessible becomes accessible, and the ‘inhospitable’ climate appears more hospitable, is not clear. If tourist numbers continue to grow, related in part to changing environmental conditions, perceptions of crowding may well begin to replace perceptions of solitude. However, perceptions of dramatically rapid change in polar regions, constantly stressed by the media, may help increase public interest. Stewart (2007) and Stewart et al. (2007) speculated that land-based tourism activities, such as sport hunting, eco- and nature tourism, retreat tourism, conference tourism, and winter-based tourist activities, could play a more prominent role in western Canadian Arctic communities in the future.




Figure 4.25. Images based on a rare recording of a slush torrent in June 1996 from sub-Arctic Sweden. The first three images show the result of increased saturation of the snowpack and then release of a large amount of water. The fourth image shows the valley in spring with a fan formed by such short-lived events over millennia. Photo: Gude and Scherer (1995).

Snow conditions and their impacts on tourism are not well addressed in the climate change literature. Snow accumulation, duration, and consistency will have an effect on access to attractions and snow-based activities such as dog sledding, skiing, reindeer sledding, skidoo touring, and winter activities in general. Greater snow accumulation leads to access difficulties, but also to new opportunities for snow-based activities (Dawson et al., 2007). Shorter snow duration leads to seasonal challenges for some activities. Change in consistency of the snowpack, including more tundra ice versus snow leads to winter tourism challenges (such as for dog sledding, skidoo touring), and the unpredictability of snow conditions (e.g., winter thaws) could lead to negative experiences for tourists and even hazards, such as avalanches, slush torrents, and floods. Snow conditions affect ecosystems, biodiversity, and landscape amenity value. If scenic value is diminished through environmental change associated with changes in snow, then tourism will be affected.

4.4.4.7. Indigenous cultures, indigenous knowledge, and traditional land use

The Arctic environment is the setting for its indigenous peoples, containing the vital resources on which their livelihoods and cultures depend. Climate change and its consequences are of critical importance to the cultural and economic well-being of Arctic peoples (Snyder and Stonehouse, 2007). Because snow is persistent and dominant in the Arctic landscape, it plays a fundamentally important role that shapes day-to-day life, transport, and resource use (such as reindeer herding and hunting).

An extensive and detailed indigenous knowledge of snow and ice conditions and their effects is sometimes complementary to scientific knowledge. This traditional understanding is reflected in indigenous languages (Ruong, 1964; Turi, 1966; Eira, 1984; Jernsletten, 1997; Ryd, 2001; Krupnik et al., 2004; Magga, 2006). Concepts of different types of snow range from new, light types of snow; to snow transformed by wind and weather and by grazing, digging, and trampling; to ice-related types of snow (Riseth et al., 2011). Of particular importance is the deep snow found near the coastal areas of the Finnish herding region (Helle and Kojola, 2006) and Finnmark, Norway (Tømmervik et al., 2009), which has diminished reindeer numbers in these areas. Also important are the ice layers described in Section 4.3.1.3.1.

An additional concept not yet addressed in snow and ecological research is the ground conditions during the formation of the durable snow of winter, already recorded in 1910 by Turi (Turi, 1966: 53–54; Riseth et al., 2011). Kumpula and Colpaert (2003) reinforced the importance of these conditions by maintaining that a hard snow or ice layer (bottom crust) that hampers foraging throughout winter is probably more important than actual snow accumulation in open, high pasture areas. In contrast, mold formation occurs especially after mild, rainy autumns, when the soil does not have time to freeze before the snow falls (Eriksson, 1976; Pruitt, 1984; Turunen et al., 2009). Kumpula and Colpaert (2003) suggested that a thick snow layer on unfrozen soil in early winter occurs especially in woodland areas (that could be a future analogue of current tundra) and that it promotes mold growth that is

harmful to animals and can kill calves.

Thus far, such insights have not been explored by science, but they highlight the sensitivity of the reindeer grazing system to changing snow conditions beyond the routine snow monitoring programs. As changes in climate and snow conditions render reindeer herding more insecure and less economically productive, there is likely to be a climate-induced shift from a mixed economy to a market-based economy. This would have significant cultural implications for indigenous peoples in the Arctic, even though the current general low-profit situation does not seem to limit the cultural value of herding (Forbes et al., 2006; Caballero et al., 2007; Forbes, 2008).

4.4.4.8. Human health

Human health status reflects the complex interaction of all the individual, social, cultural, nutritional, and socio-economic factors together with the environment (e.g., landscape and snow cover affect the health and well-being of Arctic populations). In the circumpolar north, climate is a major, constantly changing component of the environment. There are two categories of climate-related effects on human health: direct impacts (such as temperature and ultraviolet light), and indirect impacts (such as climate-induced changes in wildlife and zoonotic diseases; Parkinson and Butler, 2005). Other important issues include contaminant concentrations, traditional food security, community adaptation to stress, and community-based monitoring. The impact of climate change on wildlife species is critical to the diet of indigenous residents following a traditional way of life.

Societal change and modernization have many negative consequences for human health, including social and mental health problems as well as increased prevalence of chronic diseases (such as cardiovascular disease and diabetes) and alcohol abuse (Bjerregaard et al., 2004). Changes in climate, such as changes in snow conditions, are likely to add to the ongoing negative impacts of general societal change and modernization in the Arctic. The psycho-social stress is reflected in alcohol abuse, violence, and suicide, and these have all been shown to be associated with changes in lifestyle and living conditions (Curtis et al., 2005) that are affected by the impacts of changing snow conditions on traditional activities (subsistence hunting and gathering as well as recreational activities). The most important health implications of the alcohol abuse are accidents (e.g., drowning and falls), violence, and traumas (e.g., cuts, fractures, head injuries). Currently, many Arctic indigenous and other resident populations are experiencing high mortality rates from injury and suicide and higher hospitalization rates for infants with pneumonia, meningitis, and respiratory infections (Heikkinen et al., 2008; Meyer et al., 2008).

Climate change is already affecting Arctic species, including infectious disease agents, and greater changes are expected (Parkinson, 2008). The thawing of permafrost, extreme weather events (e.g., flooding due to snow melt), and storms (e.g., blizzards) may destroy infrastructure for sanitation and drinking water, leading to an increase in food- and water-borne diseases and respiratory infections (Parkinson and Butler, 2005). Higher ambient temperatures may result in an increase in some temperature-sensitive food-borne diseases, such as gastroenteritis and poisoning. Higher temperatures will benefit

free-living bacteria and parasites as well as insects (Bradley et al., 2005). In addition, climate warming may drive increased dissemination of zoonotic pathogens (e.g., *Giardia*, *Toxoplasma*, and *Echinococcus* species) in water- and food-borne pathways, especially in communities using wildlife as a food source. Small changes in temperature and humidity affect the distribution and behavior of the many vector-borne diseases, as was the case with West Nile virus (Petersen and Roehring, 2001; Parkinson and Butler, 2005; Emerging Infectious Diseases, 2008).

Many communities are now vulnerable to the spread of new and emerging infectious diseases, such as influenza, severe acute respiratory syndrome (SARS), and anti-microbial drug-resistant pathogens (e.g., *Staphylococcus aureus* and tuberculosis) (Emerging Infectious Diseases, 2008). The release of antibacterial pharmaceuticals from human settlements may also change resistance under the cold Arctic conditions (Kallenborn et al., 2008). Climate warming and melting ice and snow may also increase the release of persistent environmental pollutants, which can compromise the immune system in animals and humans and thus increase risk of disease (Kraemer et al., 2005; Hansen et al., 2008).

Wintertime mortality and morbidity will decrease with higher environmental temperatures (Näyhä, 2005). However, extreme weather events, such as storms including blizzards and weather variability, will probably cause adverse health outcomes, especially for the elderly, those with chronic diseases, and children. The physiological adaptive capacity may decrease due to urbanization and an ageing population (Hassi et al., 2005; Mäkinen 2007). Low temperature and low humidity have been associated with increased occurrence of respiratory tract infections, with a decrease in temperature and humidity preceding the onset of the infections (Mäkinen, 2007).

Environmental temperature is closely associated with population mortality (Näyhä, 2005); however, in Yakutsk, Siberia, no increase in mortality has been observed even at temperatures of -48 °C (Donaldson et al., 1998). Seasonal patterns of death from suicide are well documented and have been attributed to climatic factors such as solar radiation and ambient temperature. A recent study from Finland showed that winters with low levels of solar radiation may increase the risk of suicide (Ruuhela et al., 2009). Not only cold, but also air contaminants (e.g., particulates) can increase mortality and morbidity; however, the interaction of air pollution with temperature-related mortality is not understood and needs further research.

Indigenous peoples in the Arctic are aware that climate change is occurring. Observed impacts include a significant thinning of sea- and freshwater ice, a shortening of the winter ice season, reduction in snow cover, changes in the distribution of wildlife and plant species, thawing permafrost, and increased coastal erosion of some shorelines (see Chapter 5). The predicted impacts on the environment, regional economies, and people are far reaching. The reported increase in unusual weather patterns and storm events has significant impacts on travel and hunting and fishing safety (Krupnik and Ray, 2007). For Inuit communities, sea-ice travel is critical for accessing wildlife resources and traveling between communities during winter months (Laidler et al., 2009). The implications of these changes on food security and potential implications on nutritional health among these populations, which receive

significant energy and nutrient contributions to their total diet from these traditional/local foods is only now being investigated. In fact, several focused research projects have been initiated with the communities involved in the present assessment and others in these regions. For example, work on climate and water quality, hunting behavior, women's health, and emerging and chronic diseases in the Arctic are currently underway (Furgal and Seguin, 2006).

For the Inuit, disease is a consequence of transgression against the social or spiritual orders (Richmond and Ross, 2009). Inuit culture places emphasis on social behavior and its relationships with disease. At the same time, 'common sense empiricism' coexists within the Inuit belief system; snow blindness, for example, is common sense pathology and does not require a metaphysical explanation. Snow blindness has been a major problem in the circumpolar area for a long time (Sköld and Axelsson, 2008). While biomedicine is better informed about the workings of the body, traditional Inuit understanding of the relations between person, family, social group, community, and the environment represents a global view of health that is not shared by biomedicine (Bowd, 2005).

Reindeer herding among the Sámi includes many hazardous tasks in potentially dangerous environments, especially during the gathering of the reindeer for migration or slaughter. During these periods the herders use vehicles (i.e., motorcycles, snowmobiles, helicopters, airplanes, boats) to gather the reindeer, and the work is often executed during long working hours in a harsh climate and terrain. For example, most reindeer-herding men spend more than 800 hours per year on snowmobiles (Daerga et al., 2004). The increasing number of work-related fatal accidents among reindeer herders is probably also related to an increasing pressure from the Scandinavian societies to develop profitable reindeer herding companies (Hassler et al., 2004; Tynes and Haldorsen, 2007; Soininen and Pukkala, 2008). This has resulted in external socio-economic pressure and competition between the family companies within the Sámi communities that have, in turn, forced the enterprises to make costly investments in vehicles to save time and expense on personnel. Of the cause-specific mortality, men showed an increased risk of dying from vehicle accidents, snowmobile accidents, drowning, poisoning, and 'other causes'. The number of deaths caused by snowmobiles and terrain vehicles tripled between 1961 and 2000 (Hassler, 2005). Reductions in snow cover would eventually lead to less use of snowmobiles probably because of increased open terrain unsuitable for vehicles and, perhaps, a shift away from reindeer herding in a warmer Arctic. This would result in fewer accidents. However, the psychological results might offset this, and adaptation during the transition period of changing snow conditions could be particularly difficult.

4.5. Suggested strategies for local and regional adaptation

- The main drivers of change in Arctic snow cover come from outside the Arctic, and the ability for Arctic peoples and other Arctic residents to mitigate these changes is very small.
- Adaptation is now required. While adaptation has been a continuous process in the past, the current degree of change,

together with new constraints on adaptation, challenge adaptive capacity.

- There is a need to use existing information effectively, but adaptation also requires better tools from the research community, such as high-resolution models of snow changes, and better communication between researchers and stakeholders.

The current degree and rate of change in snow conditions presents problems for Arctic peoples who cannot migrate as freely as previously (Chapin et al., 2004), and for many Arctic species that characteristically grow slowly, have relatively few offspring, and reproduce late in life, and thus cannot adapt quickly (Callaghan et al., 2005; Loeng et al., 2005). The impact that Arctic communities can have on mitigating likely future changes in snow is likely to be insignificant. As mitigation globally is likely to be a slow process, Arctic communities must adapt.

4.5.1. Natural adaptations

Many Arctic species have already developed adaptations to snow cover (see Sections 4.4.3.1 and 4.4.3.2 and Callaghan et al., 2005). What is unclear is whether and how they might adapt to changing snow conditions. In the short term, animal behavior (such as the timing of the start of migration) might adapt to changing snow-free periods on the tundra and the timing of plant development (phenology) might adapt to changes in the timing of spring snow melt, first by plasticity already existing in the plants' characteristics and later by the selection of particularly well-adapted individuals. Studies show that the onset of development and behavior patterns in animals, plants, and migratory birds have changed by up to six weeks in response to earlier snow melt (Høye et al., 2007). However, both in animals and plants, the rate of mutation and true genetic adaptation to changing snow conditions is likely to be slower than the changes in snow regime. This will lead to mismatch between the distribution of species and the climate (snow regime) envelopes to which they are adapted. Examples include animals with fur or feathers that remain white when the snow has melted and which thus become more vulnerable to predation, animals that need a snow cover for nesting or denning (e.g., lemmings and polar bears), plants that require moisture from deep snow cover (see Sections 4.4.3.1 and 4.4.3.2), and plants that exist only because there is snow cover (Hodson et al., 2008) or because a persistent snow cover excludes competitors (snow bed plants). There is also a perception that earlier snow melt will expose plants at sensitive growth stages to enhanced levels of springtime UV-B radiation. The net result of the mismatch between rapidly changing snow conditions and natural adaptations is that many Arctic species will be replaced by competitors from southern areas as they migrate northward (such as the red fox displacing the Arctic fox) (Tannerfeldt et al., 2002).

Since the publication of the benchmark knowledge in the Arctic Climate Impact Assessment (Callaghan et al., 2005), two perspectives on natural adaptation have developed. First, there is increasing evidence of the importance of extreme warming events in winter on the snowpack and ecosystems (see Box 4.2 and Sections 4.4.2.1 and 4.4.2.2). These events will select for existing species and genotypes that are tolerant

Box 4.2. Changes in snow stratigraphy, impacts on reindeer, and adaptation by herders

The Sámi have a special tool (the *goaivo-soabbi*) for digging through snow to assess density and ice layers as well as vegetation condition for reindeer foraging (Figure 4.26).

The stratigraphy of the snowpack is a record of snow events, temperature fluctuations, wind-compacting actions, and compaction events by reindeer. Ice layers in the upper part of the profile are less detrimental to reindeer than bottom crusts. The Sámi use various management methods, which they can apply to adapt to future changes in stratigraphy (Roturier and Roue, 2009). When ice layers are so hard that weaker reindeer cannot penetrate through the snow, the stronger animals are used to break the ice. Under even more difficult conditions, the herd must be free to search for grazing over a larger area, be moved to another area (Bartsch et al., 2010), or be given supplementary feed; if necessary, weak animals are slaughtered. In contrast, reindeer are allowed to choose their grazing freely on pastures with soft snow (Riseth et al., 2011). Management practices such as these will need to be employed more often or even supplemented by new activities as extreme events are expected to increase (Moen, 2008; Roturier and Roue, 2009).





Figure 4.26. Snow-reindeer interactions: (upper left) reindeer have difficulty digging through deep snow to find food (UNEP, 2007); (upper right) Sámi reindeer herders probe the snowpack to look for problematic layers of compacted snow and ice (Photo: Terry V. Callaghan, Royal Swedish Academy of Sciences); and (lower) examples of snow stratigraphy (Riseth et al., 2011).

of such extreme conditions, while those that cannot adapt will open the ecosystem to invaders from the south that are pre-adapted. Second, there is a recognition (Botkin et al., 2007; cf. Callaghan et al., 1992) that a changing climate will create new genetic variation and new adaptations to the changing conditions. Mechanisms underpinning this process include increased sexual reproduction by plants in longer, warmer growing seasons; new mixes of species as southern species move northward; and isolation of currently large populations as they become fragmented by hydrological changes on the landscape and as rising sea levels create archipelagos.

4.5.2. Adaptations in infrastructure maintenance and development

Arctic residents need information on present and projected snow conditions to be able to adapt the built environment and urban lifestyles to the changing climate. This information includes projections of maximum snow accumulations for snow load calculations, water supply, flood management, avalanche risk, and snow clearing for permafrost stabilization. For example, snow accumulation from blowing snow and snow clearing around the periphery of raised gravel landing strips can have a major impact on the thermal regime and promote permafrost degradation that can lead to subsidence and cracking of runway edges (Allard et al., 2007).

Information that helps mitigate hazards is also required. Avalanche is a well-documented hazard in Canadian and other Arctic communities (Stethem et al., 2003), and there is potential for increased risk in the future in response to the projected increased precipitation over northern latitudes (Christensen et al., 2007). The Québec Government commissioned an avalanche hazard assessment for several communities in Nunavik in 2000 (Lied and Domaas, 2000) in response to an avalanche in the village of Kangiqsualujjuaq on 1 January 1999 that resulted in nine deaths and 25 injuries. The study recommended the relocation of some houses and the investment of CAD 5.6 million in the construction of defense structures to mitigate the hazard.

Changes in snowpack amount and properties linked to climate change may also require revision of snow load calculations for buildings. Maximum snow accumulation is projected to increase over large areas of the Arctic (Figure 4.15), and there is potential for increased frequency of extreme precipitation years (Christensen et al., 2007). In some countries, such as Canada, snow loads are estimated from historical maximum snow depth data with a regional mean snow density taken from historical data (Newark et al., 1989). This approach ignores interannual variability in snowpack density and assumes that snowpack density does not change over time, which may not be the case under a rapidly warming climate. The severe snow winter of 2007/08 caused a number of structural failures and several deaths in Québec and prompted a process to review and update ground-snow load calculations for Canada. Similar reviews are being undertaken in other countries in response to recent building failures and concerns that climate change may increase the snow-load hazard (e.g., Strasser, 2008).

4.5.3. Adaptations in land and resource use

4.5.3.1. Reindeer herding

Reindeer are a major source of food in the Arctic and reindeer herding is a low-intensive land use and a low-profit industry. The changing climate, variable snow regimes, icing over of ranges, and insect harassment (Moen, 2008; Bartsch et al., 2010) are difficult to control. However, reindeer movement over large areas for grazing, usually with seasonal shifts, is a natural adaptation to the Arctic landscape and climate (ACIA, 2005; Tyler et al., 2007), with summer grazing in coastal areas and winter grazing in the taiga areas. The choice of strategy will depend on a number of factors (such as season, snow type, temperature, landscape, and the physical conditions of the animals), and will be influenced by previous experience of unusual weather conditions such as ice layers. Nevertheless, many of the problems in reindeer herding can be traced back to disturbance problems and problems with pastoral balance, for example, related to property rights and the general development of infrastructure. National borders, border closure, and bilateral conventions also have restricted ability to adapt. In the past 30 to 40 years, long-range migration patterns have been restricted (Riseth, 2003; Riseth and Oksanen, 2007) in Fennoscandia and in the Yamal-Nenets area, resulting in unused and underused grazing areas (Caballero et al., 2007; Forbes and Stammer, 2009).

Reindeer response to the variable onset of seasons will initially involve changes in local migration patterns. As the snow season duration decreases, they will migrate earlier to the summer grazing grounds and stay longer on summer and autumn grazing areas. Heat and insect stress are relieved by the reindeer moving to higher areas with more wind and more snow patches; a reduction in snow beds in warmer summers will make this more difficult. In a longer perspective, reindeer husbandry needs to increase its resilience by maintaining a choice of grazing sites. Traditionally, sustainability was obtained by the use of long migration patterns. However, as noted above, this capacity has already been severely limited, while other, competing land uses further restrict the flexible use of the landscape for reindeer grazing (Moen, 2008).

Primary production in the form of graminoid availability and quality may be easier to control. Through improving preferred range quality and availability, reindeer condition will improve (Eilertsen et al., 2000). Reindeer in better condition may then tolerate stochastic and difficult climatic events, such as deep snow (that requires more energy to move over and dig through for food) or ice layers in the snow (that prevent access to food below and limit the smelling cue for the reindeer to detect food) that compromise their survival and production. In addition, varying degrees of avoidance and adaptation may mitigate some of the impacts of a changing climate and snow cover.

From the 1980s onward, complementary forage resources (food pellets) have become increasingly important (Kumpula, 2001) as an adaptive strategy to compensate for forage deficit due to restricted migrations. For example, reindeer management in Norway has used some complementary forage resources and supplementary feeding under difficult winter conditions (Åhman et al., 2002).

Reindeer herding is not only affected by changes in the snow and ice structure, but also by other factors. Adaptation cannot

be explicitly focused on changes in snow conditions; it must include other local factors, and there must be recognition of indigenous knowledge systems (Tyler et al., 2007). Indigenous peoples have successfully occupied the Arctic due to their adaptive capacity (in social, economic, and cultural practices) to adjust to climate variation and change (Nuttall et al., 2005).

4.5.3.2. Conservation

Extreme events related to snow cover dynamics can have profound effects on Arctic animals and plants (Sections 4.4.2.1 and 4.4.2.2). Conservation in the Arctic is currently based on the designation and control of protected areas, of which there are many (CAFF, 1994, 1996). However, this conservation management only moderates direct impacts of humans and does not protect species, ecosystems, or habitats from climate change, such as the extreme events of winter snow melt and icing. New paradigms are required (Usher et al., 2005) and future plans must incorporate flexibility in anticipation that changes in climate, including snow conditions, are likely to continue. For example, rather than designing static nature reserves on a landscape that is frozen in place, there should be an anticipation that disturbance will occur and climate will change (Chapin et al., 2004; Forbes et al., 2009). In addition, species may be moved further northward to a more appropriate climate envelope or fed supplementary material during crises such as rain-on-snow events. Harvest regulations are also a means of conservation management; however, regulations are often rigid and difficult to change in anticipation of changing environmental conditions. An adaptive management approach is required, which in many cases may incorporate the establishment of community-based monitoring. Major action will be required soon if populations of species such as Peary's reindeer are to be saved.

There is a need for innovation in conservation. Interactions between reindeer (*Rangifer tarandus tarandus*) and domestic sheep (*Ovis aries*) have been studied in Norway using controlled experiments and field observations (Eilertsen et al., 2000). Other research has shown that high biodiversity in northern coastal farmland can be maintained by reindeer when the farmland is abandoned, while also improving the health of the reindeer (Eilertsen et al., 2000). Biodiversity hot spots of Arctic-alpine plants in the Scandinavian high mountains that depend on disturbance from grazing are enhanced by reindeer trampling and grazing (Caballero et al., 2007). Thus, the traditional role of reindeer herding could be reinterpreted as a stewardship of the landscape by using reindeer to retard the advance of shrubs and trees and the disappearance of valued flora and fauna.

4.5.3.3. Tourism

The key challenges of climate change for the tourism industry in the Arctic relate to infrastructure, access, attractions, and cultural identity. Opportunities exist for new activities, replacement, and diversification to moderate the negative and benefit the positive impacts of climate change. Vulnerable communities are those whose local or business conditions do not currently demonstrate the capacity to change or support the flexibility to respond to change. Small tourist operations focused on a single Arctic activity, such as dog sledding, may

be in jeopardy over the long term and may need to diversify.

Tourism may shift northward, as cooler regions enjoy warmer summers, while warmer regions like southern Europe suffer increased heat wave frequency, reduced water availability, and poor snow conditions in the alpine resorts. For example, Davos in the Swiss Alps experienced a decrease in snow depth of 12% between the 1960s and 1990s (Beniston et al., 2003). One study (Hamilton et al., 2005) projected that both Canada and Russia would have a 30% increase in tourists with only 1 °C of warming (Stern, 2006). Thus, the market for certain types of tourism (e.g., cruises, whale watching) could prosper in a more 'benevolent' climate. Although currently limited to a few countries, eco- and nature tourism might be expanded, perhaps by offering a new type of product from that traditionally offered. The trend of increased tourism will provide an opportunity for Arctic entrepreneurs who can adapt to the changing conditions. However, the tourism industry is not yet ready to adapt and respond. The pace of social response in the Arctic is slow and there is a limited pool of people – particularly trained individuals – to fill any new jobs. Furthermore, if there is an increase in tourism, there will need to be a development of conservation management regulations to reduce disturbance impacts, such as those ongoing in Svalbard owing to the significant increase in tourism over the past decade (Madsen et al., 2009).

4.5.3.4. Hunting and fishing

Hunting activities are particularly sensitive to snow and ice conditions (Ford and Furgal, 2009). Many indigenous groups and other Arctic residents, particularly hunters and fishers, depend on their ability to predict animal behavior in relation to nature and weather conditions. The changing climate, together with rapid economic change, modernization, and alterations in the food supply, is already affecting Arctic communities (Bjerregaard et al., 2004; Curtis et al., 2005).

4.5.3.5. Agriculture and forestry

The presence of an ice crust with a thickness greater than 20 mm during a single five-day period is considered a dangerous event for winter crops, and when it occurs it generally results in the need for replanting. The decrease in dangerous events for winter crops in a major agricultural region of the Russian Federation (Bulygina et al., 2010a) would suggest that the yield of existing crops would improve significantly and there would be fewer problems for new areas of crops as they extend northward.

4.5.4. Provision of knowledge (scientific and traditional) for adaptation

The provision of relevant knowledge for adapting to a changing snow climate in the Arctic first requires an identification of vulnerabilities and sensitivities to a changing snow regime in order to determine what snow information is required. This is no small task as there is a wide range of snow-related sensitivities in Arctic geomorphological, ecological, and human systems.

Arctic residents rely on snow for water, transportation, food storage, and for building emergency shelters (UNEP, 2007). A reduced snow cover is associated with many community-level

impacts (Figure 4.27), while the potential for increased snow accumulation in some regions will require a reassessment of snow loads and the risk of avalanches and floods. Hunting activities are particularly sensitive to snow and ice conditions (Ford and Furgal, 2009) and knowledge of changes in the timing and amount of snow are important in this respect.

There is a need for better monitoring and forecasting of snow conditions and better projections of future snow conditions. A particular challenge will be to explain transient non-linear changes in phenomena, such as winter thaws and rain-on-snow events, and how these will differ in mountain regions where the sign of snow cover change (more snow or less snow) may alter with elevation.

The provision of relevant information from scientists requires the active involvement and collaboration of community members and local, regional, and national organizations that use the information for decision-making and policy development (Pearce et al., 2009). Recent research has shown that Arctic communities can exhibit a high degree of adaptability to change and can be quick to take advantage of innovation and new opportunities (Ford and Furgal, 2009) if appropriate economic measures are in place. Consequently, greater engagement is needed between the scientific community and Arctic residents in order to incorporate this traditional knowledge in activities such as, for example, interpretation of satellite-derived snow cover products; development of community-based snow monitoring programs; and attempts to better understand the impacts of uncertainties in snow information on local decision-making. The ice-edge monitoring product developed by Noetix Research, Inc., for Polar View (www.noetix.ca/floedge) involved extensive consultations with local hunters and elders to provide Inuktitut terminology for ice features visible on SAR imagery. In northern Fennoscandia, a comparison of indigenous knowledge on snow conditions, data from snow physics measurements, and results from experiments that simulate extreme events led to a better understanding of

processes relevant to reindeer herders (Bokhorst et al., 2008, 2009; Riseth et al., 2011).

Collaboration between scientists and stakeholders will need to improve if scientists are to provide more-relevant projections of change in snow conditions. This would require that scientists evaluate and validate snow information from climate models in conjunction with the user communities in order to establish which variables are important, the accuracy required, and the impact of uncertainties on decision-making, as well as to develop best practice guidelines for the development of snow scenarios for the Arctic. A fundamental issue is the geospatial scaling of information; adaptation is a local process and the provision of local data, such as climate downscaling (see Section 4.3.2.3), will become increasingly important.

4.6. Uncertainties, gaps, and recommendations

- Assessing current changes in snow conditions and projecting future changes and their impacts are limited by availability of standardized pan-Arctic datasets with high-resolution observations, uncertainties in remote sensing technology, and difficulty in applying highly detailed small-scale models to the pan-Arctic scale.
- A new generation of international networking is required to monitor snow and to provide data for parameterization and validation of models.
- The quality and quantity of information from the wide array of tools and techniques available to generate snow-related information for decision-makers is expected to increase over time.




Figure 4.27. An observation, impact, and adaptation diagram for a reduced snow-cover season at Arctic Bay, Nunavut. Source: Nickels et al. (2005).

4.6.1. Major issues

4.6.1.1. Resolving key uncertainties and an agenda for key research priorities

Snow cover characteristics in the Arctic are among the most rapidly changing variables associated with ongoing climatic change. *It is critical to invest time and resources in intercomparison and blending of the various types of information from existing and projected snow datasets within a context of social relevance.*

Each discipline and science component – ground measurements, remote sensing, the impact research community (ecologists, hydrologists, engineers, foresters, reindeer herders, etc), economists, and adaptation planners and decision makers – have their own agendas and processes for furthering their research. However, communication among these communities is generally poor, and there is often a mismatch in information exchange; for example, the scaling and parameters measured by ground-based monitoring and remote sensing of snow may not provide the information most relevant to ecologists, indigenous peoples, and planners. A particular mismatch is that of spatial scaling (in that adaptation requires local information in high detail) and temporal scaling (in that short-duration extreme events cannot be recorded and passed on to the impact community to allow real-time observations of impacts). Within the process as a whole, uncertainty increases along the sequence: recording and projecting snow changes → recording and projecting impacts → calculating the economic and societal consequences of the impacts → developing adaptation strategies. A particular uncertainty involves finding relevant socio-economic assessments of impacts as these are often too numerous, too local in relevance, and largely inaccessible to the wider community.

In response to the lack of a system approach, ***we recommend*** the establishment of formal networking (e.g., similar to the Canadian ArcticNet philosophy) of all the relevant players to exchange information and to ensure that more relevance is gained in future data gathering, interpretation, and projection and that currently inaccessible data be made available. Such a network should strive to secure funding and appropriate facilities for the network components from a stronger basis than any single component. The developing process of SAON (Sustained Arctic Observing Network) could potentially fulfill many of these needs.

4.6.1.2. Improving data acquisition, availability, and a generation of new products

There is a need to secure input information, including traditional and scientific knowledge, for snow modeling projections, and each societal service related to snow cover. The current assessment has, by necessity, drawn on various types of information from numerous archives that are often not linked or compatible. ***We recommend*** that research stations in the Arctic develop a holistic hydroclimatological research and monitoring capacity alongside their present disciplinary foci. ***We also recommend*** that operational snow-related data streams be channeled to a single point of contact. One of the two World Data Centers for Meteorology (in Obninsk, Russia, www.meteo.ru/mcd or in Asheville, North Carolina, www.ncdc.noaa.gov) or the World Data Center for Cryosphere Information (U.S. National

Snow and Ice Data Center in Boulder, Colorado; <http://nsidc.org>) might be such a point of contact.

In addition, ***we recommend*** the development of an international, integrated, historical snow-related *in situ* dataset. This dataset should include all cold season *in situ* information for the period of instrumental observations (in North America after the Second World War and in Northern Eurasia for the past 100 years). To achieve this goal, ***we recommend*** that an international project is sponsored by the meteorological and hydrological services of the Nordic countries, Russia, the United States, and Canada. The project could be organized under the administrative auspices of the Arctic Council and under the scientific guidance of the World Climate Research Programme, via the Climate and Cryosphere (CliC) Project.

4.6.1.3. Facilitating adaptation to changes in snow cover

Estimating the magnitude of change and its impacts as well as the requirement for models to be generally spatially applicable has focused attention on the large scale. However, adaptation is a local process responding to local changes in snow and its impacts (Section 4.3.2.3). ***We recommend*** that there should be an increased focus on modeling and observation of changes in snow and their impacts on the local scale. Data should be made available to authorities that wish to plan adaptation strategies. Downscaling of climate, snow, and impact models is fundamental in this respect. In addition, there is a need to stimulate innovation in order to diversify resources and their usage.

4.6.2. Detailed issues

4.6.2.1. Measurements of snowfall and snow cover parameters

- **Accurate Precipitation Information.** The provision of accurate precipitation information for the Arctic (Section 4.3.1.1) remains an ongoing challenge as the observations are prone to significant random errors and biases (Sevruk, 1982; Goodison et al., 1998) and automation of observations has created new challenges for maintaining the integrity and quality of the observations. A number of procedures have been proposed to correct for biases in frozen precipitation measurements (see Mekis and Hogg, 1999; Yang, 1999; Yang et al., 1999; Bogdanova et al., 2002a,b; Aleksandrov et al., 2005; Sugiura et al., 2006), but the corrected values still carry large random errors at the daily timescales required for many applications. ***We recommend*** using the combination of snowfall, snow cover, and streamflow data over large Arctic river basins (e.g., Bulygina et al., 2007; Shiklomanov et al., 2007) to provide a useful basis for examining the ability to close the water budget and identify possible systematic errors in precipitation datasets.
- **Development of pan-Arctic snow and related climate datasets.** At present, there is no pan-Arctic dataset of *in situ* snow (e.g., SWE) and climate data for understanding large snow cover changes and their impacts on regional hydrology and ecosystem functions. SWE and snow density are measured throughout the Arctic as part of SWE monitoring activities in Russia, Canada, Alaska, and Scandinavia (Brown

and Armstrong, 2008), but there are large data gaps and there has been a general decrease in the number of measuring sites over time. Data are particularly sparse for the tundra region (see Appendix 4.1). **We recommend the production of gridded data for model applications, validation of remote sensing snow data and products, and the development of corresponding pan-Arctic datasets of observed snow cover changes from traditional knowledge.** This will require taking account of sources of inhomogeneity.

- **Homogeneity of time series.** There are known sources of error from changes in procedure, instrumentation, or siting of equipment and gaps in observations for snow and snow-related datasets such as solid precipitation (Section 4.3.1.1). For example, procedural changes were made in the Russian snow depth and course measurement programs in 1950 and 1966 that may have created inconsistencies in the data (Meshcherskaya et al., 1982; Krenke, 1998, updated 2004). In North America, automation at some Canadian meteorological stations (Goodison and Louie, 1986) resulted in the loss of snowfall measurements and required new quality control routines for snow depth measurements obtained from ultrasound sensors. In addition, the daily snow-depth observing network over northern Canada is biased to coastal locations, and these sites can have quite a different climate to inland locations. **We recommend the development of approaches to fill data gaps and take account of biases in the observing networks.**
- **Ongoing evaluation and synthesis of satellite snow cover data.** Monitoring snow cover over the Arctic region (Section 4.3.1.2) is a major challenge for many reasons, including strong local controls on snow cover, frequent cloud cover, large gaps and biases in surface observing networks, and confusion of lake ice and snow cover during the melt season (see Appendix 4.1). The NOAA weekly snow cover product (Robinson et al., 1993) has been the most referenced source of information on variation and trends in Arctic snow cover extent since the late 1960s. However, this product includes changes in the volume and resolution of satellite information over time, as well as differences in the way patchy snow was mapped by analysts. This has resulted in inconsistencies in the mapping of snow that are particularly apparent over the Arctic (Brown et al., 2007). **We recommend the use of a multi-dataset approach for monitoring spring snow cover variability over the Arctic, as Brown et al. (2010) found this provided more robust information along with an estimate of the error in the observations. The ongoing integration and synthesis of Arctic snow cover information from multiple sources would fit well with the role of the new Global Cryosphere Watch proposed by the World Meteorological Organization (Goodison, 2009) and responds to recommendation R3.5 of IGOS-P (Key et al., 2007).**
- **Improved microwave measurements.** Satellite observations using the microwave sensor have been routinely used to map and monitor snow cover since the late 1970s (e.g., Grody and Basist, 1996; Armstrong and Brodzik, 2001; Derksen et al., 2003; Kelly et al., 2003; Appendix 4.1). The ability of microwave sensors to ‘see’ snow through most clouds and at night is particularly attractive for monitoring snow

cover over high-latitude areas and passive microwave has proved useful for monitoring snow melt onset and snow-off dates (Takala et al., 2009; Tedesco et al., 2009) due to its sensitivity to the presence of liquid water in the snowpack. However, there are some special challenges in applying passive microwave algorithms over the Arctic region, including shallow snowpacks, extensive depth hoar, ice layers within the snowpack, and the effect of frozen water bodies. **We recommend the continued development and application of new boreal and tundra algorithms specific to the Arctic region (e.g., Rees et al., 2006; Derksen et al., 2008a, 2009; Lemmetyinen et al., 2009; Rees et al., 2010), which may overcome some of the limitations of previous global SWE algorithms. The development and testing of high-latitude SWE algorithms can be done in conjunction with intensive field campaigns at existing Arctic super-sites (within networks such as INTERACT www.eu-interact.org), as outlined in recommendation 3.4 of IGOS-P (Key et al., 2007).**

4.6.2.2. Traditional Ecological Knowledge

- **Lack of measures of uncertainty.** Science has established measures of uncertainty (e.g., statistical analyses based on probability), but the traditional ecological knowledge (TEK) used throughout this assessment does not. Some observations have high certainty, and survival has depended on them. However, other observations may be biased by particular observers. Currently, there appears to be no way of scaling degrees of certainty. **We recommend that measures of uncertainty be developed and applied.**
- **Lack of scaling perspectives.** TEK provides information at local scales and over varying time periods. Integrating across numerous local observations collected at different time intervals is a major challenge. **We recommend improved networking of community monitoring programs and centers or holders of TEK to develop wider spatial-scale understanding of indigenous perspectives of changing snow conditions and their impacts without losing the specific variability at individual locations.**
- **Lack of appropriate knowledge.** TEK has been accumulated and passed down over generations and is therefore, based on observations of past environmental conditions. However, new developments in the climate system are causing the indigenous peoples to be less able to predict weather and resource availability. **We recommend better and urgent recording of TEK and the development of a forum to discuss, develop, and record the success or otherwise of newly developing knowledge and skills applied during a changing environment.**
- **Loss of TEK.** Use of modern infrastructure and equipment (snowmobiles, motor boats, mobile phones, helicopters) together with changes in the mobility and social structure of indigenous populations has resulted in some loss of TEK that could be relevant to understanding changing snow conditions and their implications. **We recommend, as above, the urgent recording of TEK before it is lost.**
- **Comparing science and TEK.** Natural science, in contrast to TEK, has the general goal to be objective with all its results promptly validated. TEK does not have this goal. It

can however, explain the practical importance of changes in snow conditions that natural science measures. This is important socio-economic information that is missed in scientific databases. **We recommend** that combined methods be developed to use both scientific (instrumental) and traditional ecological knowledge more comprehensively to describe the state of snow cover, its changes, and its impact on environmental services in the Arctic (e.g., Bartsch et al., 2010).

- **Translating snow terminology.** Indigenous peoples and scientists have their own, often sophisticated, terminology for a vast range of snow conditions. While there are dictionaries that linguistically translate some of the indigenous terms, **we recommend** that an overarching standard terminology be developed, with definitions that can be used by all users and providers of snow information. In addition, **we recommend** that the terms be reassessed and that correlations (transform functions) are established among these definitions when and where it is possible. Only then will it be possible to secure input information (including traditional and scientific knowledge) for snow modeling projections and each societal service related to snow cover.

4.6.2.3. Snow modeling and snow cover change scenarios

- **Limitations in general circulation models.** GCMs are unable to simulate the observed rate of decrease in spring snow cover over northern hemisphere high latitudes over the latter half of the 20th century (Brown and Mote, 2009; Section 4.3.2.1). **We recommend** that resolving this inability be an urgent priority. The ability of models to simulate the snow melt process also needs further investigation within the context of Arctic hydrology. This should result in evaluations of feedbacks between the timing of snow melt and broader changes in terrestrial ecosystems.
- **Scaling issues.** The scaling-up and incorporation of key Arctic snow processes to the 10–50 km resolution of regional climate models and the 100–200 km resolution of GCMs is an ongoing challenge (e.g., Déry et al., 2004). Some progress has been made in recent years to model snow and snow processes in Arctic environments (Brun et al., 2008; Section 4.3.2.3), and with sufficient good quality input data, the current generation of high-resolution Arctic snow process models such as CRHM (Pomeroy et al., 2007) and SnowTran-3D (Liston et al., 2007) can provide realistic simulations of the spatial, vertical, and temporal evolution of snowpack properties. **We recommend** the continued and accelerated development and application of high-resolution Arctic snow process models.
- **Models of snow-vegetation interactions.** Snow-vegetation interactions are numerous and complex as they depend both on changing snow conditions and on independent changes in vegetation (Section 4.4.3.1). Results from the recent SnowMIP2 comparison of snow model vegetation schemes (Rutter et al., 2009) revealed that the parameterization of key processes, such as snow unloading, are either nonexistent or based on site-specific data. In addition, the intercomparison highlighted the large uncertainties that exist in the variables required to drive distributed snow process models in re-

analyses and climate models, in particular the timing, amount, and phase of precipitation; incoming longwave radiation; and cloud cover. **We recommend** that improved datasets be collected for parameterization of key processes in snow vegetation models.

- **Sublimation.** A potentially important, but often overlooked process (and hence under-represented topic in this assessment) is the sublimation of snow, especially when enhanced by blowing snow. Sublimation can be a key part of the hydrological cycle locally and regionally (Pomeroy and Li, 2000), and up to 40% of snowfall was estimated to sublimate near Tiksi, Russia (Hirashima et al., 2004). Nonetheless, climate models do not include the enhancement of sublimation by blowing snow, and some models do not include even the direct sublimation of snow from the surface. **We recommend** ongoing efforts to parameterize and up-scale blowing snow sublimation processes for inclusion in climate and hydrological models.
- **Climate model snow-cover projections.** The uncertainties in climate model snow-cover projections (Section 4.3.2.2) due to natural variability, climate model formulation, and emission scenarios need to be evaluated. **We recommend** that the procedures used by Rowell (2006) be carried out for applied snow-related information, such as winter thaw events, snow season start and end date, maximum SWE, date of maximum SWE, snow melt run-off timing and amount. This information should then be provided to the user community, so that they are aware of the magnitude and relative contribution of the various sources of uncertainty in snow cover parameters.

4.6.2.4. Additional issues

- **Current impacts of changing snow conditions.** Observational power in the Arctic is relatively low, and the pathways of information flow from observing particular snow conditions to identifying relevant impacts (implicit throughout Section 4.4) are insecure and often based on correlative rather than causal analyses. **We recommend** capacity building to improve observational power, development of better communication pathways between the observation and impacts on communities and between the observation community and researchers who can deploy experimental methods to elucidate causes of observed changes in snow conditions.
- **Projected impacts of changing snow conditions.** Projected impacts (Section 4.4) are determined mainly through either modeling impacts based on projections of future snow conditions (e.g., hydropower) or experiments that simulate various aspects of projected changes in snow conditions (e.g., vegetation responses). However, models of impacts of projected changes in snow inherit the uncertainties associated with the snow projections, while the impact models have their own uncertainties. On the other hand, field experiments that manipulate snow cover according to projections have various artifacts and need to select relatively few scenarios and target a particular time horizon owing to large cost and space requirements. **We recommend** improvements in the snow projection and impacts models as well as the development and deployment of new large-scale multifaceted snow manipulation experiments.

- **Socio-economic evaluation of impacts of changing snow conditions.** It is difficult to collate information on current socio-economic impacts (Section 4.4.4) of changing snow conditions, because the impacts are usually of local importance and records are held in the relatively inaccessible grey literature of municipalities and various infrastructure authorities such as road and railway maintenance authorities. Projecting socio-economic consequences of projected changes in snow conditions is even more uncertain as socio-economic projections must be built on projections of impacts (e.g., agriculture, forestry, reindeer herding, hydropower), each of which have uncertainties and are themselves built on projections of changing snow and climate that also have uncertainties. ***We recommend an urgent focus on collating relevant information (e.g., from grey literature sources in local authorities and utility companies) and also assessing the information and making it widely available.***
- **Impacts on tourism of changing snow conditions.** There is little information about winter tourism (Section 4.4.4.6), even though this may be important for the local economy. In addition, changes in snow conditions could dramatically improve or damage such local economies depending on local circumstances. ***We recommend a more detailed assessment of the consequences of changing snow conditions in the Arctic for the tourist industry.***

4.7. Conclusions: the human face of snow change

- Changes in snow conditions are likely to provide some opportunities as well as challenges. It is likely that challenges will mainly be experienced by Arctic residents while opportunities will benefit multinational industries.

4.7.1. Opportunities and challenges

Many of the impacts of a changing snow regime will have beneficial consequences for society. These include increased output of hydropower, a more even distribution of water supply and less flood damage, and reduced costs in some areas of snow clearance from roads, airstrips, etc. Current High Arctic areas could become analogues of areas further south, harboring retreating wildlife and maintaining valuable scenic amenities. However, there will also be challenges associated with a changing snow regime. Adverse impacts are already being recorded for northern commercial forests that are suffering drought because of reduced meltwater from snow in spring. Increasing frequency of extreme events in winter is also affecting forest growth, as well as reindeer husbandry, berry production, and the biodiversity and food chains of some important Arctic animals.

4.7.2. ‘Winners and losers’

The global community could suffer from the impacts of a changing snow regime in the Arctic in two fundamental ways. First, if the dominant feedbacks to the climate system from a reduced snow cover are positive, then global warming will be amplified. Second, long-term changes in snow regime and extreme events could threaten iconic species, unique snowscapes, and the perceived image of the Arctic wilderness.

Within the Arctic region, urban residents are likely to benefit from many of the changes in terms of warmer winters, smaller fuel demands, more hydropower available, and less costly maintenance of transport routes. However, in the rural areas, indigenous peoples and other rural Arctic residents will face challenges to their traditional resource management and will need to diversify and adapt. These processes may in themselves be challenging due to insufficient labor pools and training.

4.7.3. Need for policy development

The residents of the Arctic can do little to mitigate global climate change and must adapt to the changes imposed on them. Policy development is therefore required outside the Arctic to strengthen global mitigation measures and within the Arctic to strengthen regional mitigation measures, such as emission controls (from local industry, burning of garbage, marine transportation, emission control, etc.) while ensuring that the institutional structures, training, and investment are available to allow Arctic residents to adapt, pursue opportunities, and overcome challenges.

Acknowledgments

The authors are grateful to the Swedish Department of Environment, the Swedish Environmental Protection Agency (grant number 08/210), and the Swedish Research Council Formas (grant number 204-2009-45) for funding the involvement of the convening lead authors and for facilitating the involvement of Russian contributors. We also thank the other national (United States, Canada, Norway) agencies for funding the participation of their respective lead authors. Many authors contributed written text, figures, tables, and ideas, and are explicitly acknowledged on the title page, but we thank them here also. We also thank Christer Jonasson for kindly providing information on slush torrents. The AMAP SWIPA Secretariat gave valuable support throughout, and we thank the SWIPA Integration Team as well as authors of other SWIPA chapters for their pertinent discussions and encouragement. Finally, we thank the many reviewers and Dr. Barry Goodison, in particular, who provided extensive feedback.

Appendix 4.1. Existing sources for data and information on Arctic snow cover

The ability to monitor snow cover changes over the Arctic depends on the length and characteristics of available datasets and information. The most extensive surface observations are daily snow depth, but the network is still very sparse over large regions of the Arctic (Figure A1) and biased to coastal stations in the Canadian High Arctic. In addition, countries have different observing practices, and the data can be subject to various sources of inhomogeneity.

Long-term datasets are relatively sparse and have been derived from long-term meteorological stations on land and from drifting stations (Figure A2). Analyses of trends in October to May total precipitation (Figures 4.3 and 4.4 and Table 4.1) have been derived from various sectors of the Arctic:

1. Atlantic (60° – 85° N, 50° W – 30° E)
2. North European (60° – 80° N, 30° – 60° E)
3. West Siberian (60° – 80° N, 60° – 100° E)
4. East Siberian (60° – 78° N, 100° – 150° E)
5. Chukchi (60° – 73° N, 150° E – 170° W)
6. Alaskan (60° – 73° N, 170° – 140° W)
7. Canadian (60° – 85° N, 140° – 60° W)

As outlined in Table A1, there is a wide range of needs for snow-related information over a range of scales from real-time input to weather forecast models, to climatological-scale calculations of snow loadings from annual maximum snow depth series covering 20 to 30 years. With the snow climate in the Arctic projected to become more variable in the future (ACIA, 2005), the demand for timely and accurate snow data and information is likely to increase. A comprehensive review of snow observations and data sources was provided by Key et



Figure A1. Spatial distribution of daily snow depth observations in the Global Summary of the Day dataset (NCDC) for March 1991–2000. Source: Ross Brown, Climate Research Division, Science and Technology Branch, Environment Canada, March 2010.




Figure A2. Long-term meteorological stations in the Arctic (red dots) and mean monthly location of North Pole drifting stations (blue dots) during the period 1937 to 2008. Source: Frolov (2010).

Table A1. Examples of applications requiring snow data and information.

Snow variable or derived statistics	Applications
Snow cover start and end dates	Ecological studies, climate monitoring
Snow melt onset date	Flood forecasting, transportation, ecological studies
Daily snow depth	Input to snow analysis products for numerical weather prediction (NWP) and land surface models, ground truth for satellite data, climate monitoring, derived statistics used in many applications
SWE (snow water equivalent) observations once per 10 to 15 days (snow course or transect)	Hydrological forecasting, water resources, validation of land surface and snow cover models
Annual maximum snow depth	Snow load calculations
Snow cover duration, depth, and density	Evaluation of frost penetration and ground thermal regime
Snow stratigraphy and layering including ice crust formation	Avalanche risk, transport, reindeer husbandry, ecology, development and validation of snow models and satellite algorithms
Albedo of snow-covered land from satellite data	Validation of climate models, study of feedback processes
Snow cover extent from satellite data	Input to NWP models, climate monitoring, ecological studies (snow cover start and end dates and duration), location of summer snow patches for reindeer herding

al. (2007) and Brown and Armstrong (2008), and a summary of currently available Arctic snow data sources is provided in Table A2. The following sections review the current state of snow cover information for the Arctic Region.

In situ observations

A comprehensive review of snow observations and data sources was provided by Key et al. (2007) and Brown and Armstrong (2008). The situation has not changed appreciably over the past decade for *in situ* snow depth and SWE observations, with the same data gaps remaining over large regions of northern Canada and Siberia. However, there has been some progress toward creating pan-Arctic snow datasets with the development of a new comprehensive dataset of surface snow observations since 1936 for Russia, the newly independent states of the former Soviet Union, and Fennoscandia (Kitaev et al., 2005; Bulygina et al., 2009).

A gridded ($1^\circ \times 1^\circ$) snow depth dataset for Canada and the United States for the 1960 to 2003 period based on *in situ* daily snow depth observations was developed by Dyer and Mote (2006) and has been recently updated to 2008 (Robinson, Dept. of Geography, Rutgers The State University of New Jersey, USA, pers. comm., 2009). This dataset does not explicitly take account of topography in the interpolation process like the 1979 to 1997 ~ 25 km gridded snow depth and estimated SWE dataset for North America developed by Brown et al. (2003) from objective analysis. However, users should be aware that point snow depth observations are mainly made at open locations near airports and are unlikely to be representative of the surrounding terrain, especially in forested terrain where open areas accumulate less snow and melt out earlier (McKay and Gray, 1981). The daily snow-depth observing network also has large gaps over northern Canada and Siberia, and the observations are biased to coastal locations in the Canadian Arctic that can have a quite different climate compared to inland locations.

Canadian snow depth and snow course data (Brown and Brasnett, 2010) have been updated to 2003/04, but the period of data coverage is highly variable, and there are large data gaps. Site-specific snow datasets from some major research projects (e.g., SHEBA and SnowSTAR) are provided online, but there is no central repository or clearinghouse for Arctic snow data. Increasing automation of climate and weather observations has created homogeneity issues particularly for solid precipitation measurements (Yang et al., 2001). However, some progress has been made in generating pan-Arctic solid precipitation datasets corrected for bias and gauge-dependent errors (Yang et al., 2005).

Care must be taken with the interpretation of trends derived from *in situ* observations due to possible sources of bias and inhomogeneity. For example, snow course measurements in Russia prior to and after 1966 are incompatible due to procedural changes (Krenke 1998, updated 2004; State Committee on Hydrometeorology and Environment Protection of the USSR, 1985). Snow depth measurements in the former Soviet Union also have a discontinuity in or around 1950, when there was a change from taking measurements at mainly sheltered to mainly open sites. Snow depth measurements made at open sites tend to underestimate the snow accumulation compared to surrounding terrain and sheltered sites (Meshcherskaya et al., 1982).

Table A2. Key sources for online snow-related data and information in the Arctic, August 2009.

Institution	Snow data products online
National Snow and Ice Data Center, Colorado	NOAA, MODIS, AMSR-E, passive microwave snow datasets; miscellaneous <i>in situ</i> datasets, including Russian snow transect data from 1966 to 2004 (Krenke, 1998). (www.nsidc.org)
National Snow and Ice Data Center, Colorado	Daily precipitation sums at coastal and island Russian Arctic stations, 1940 – 1990 (Radionov et al., 2004b). (http://nsidc.org/data/g02164.html)
National Snow and Ice Data Center, Colorado	Meteorological data from the Russian Arctic, 1961 – 2000 (Radionov and Fetterer, 2003). (http://nsidc.org/data/g02141.html)
National Snow and Ice Data Center, Colorado	Arctic meteorology and climate Atlas (Fetterer and Radionov, 2000).
PolarView, ESA	Snow cover extent mapping over Eurasian land areas of the Arctic. (www.polarview.org/services/sm.htm)
Environment Canada	Canadian historical daily snow depth and snow course data to 2003/2004. (ftp://ccrp.tor.ec.gc.ca/pub/RBrown)
Canadian Meteorological Centre	Global daily snow depth analysis at 0.3° resolution since 1998. Depth and estimated SWE (snow water equivalent) values over the Northern Hemisphere available online. (http://nsidc.org/data/nsidc-0447.html)
Canada Centre for Remote Sensing	Snow melt-off dates, snow cover fraction, and albedo of snow-covered land from AVHRR, 1982 to 2004 (Zhao and Fernandes, 2009). (http://geogratia.cgdi.gc.ca)
Rutgers University, Global Snow Lab	NOAA weekly and monthly snow cover data for the Northern Hemisphere from 1966. (http://climate.rutgers.edu/snowcover)
National Climatic Data Center, Asheville	U.S. daily snow depth data, daily snow depth observations in <i>Global Summary of The Day</i> . (http://cdo.ncdc.noaa.gov)
University of Alaska, Fairbanks	Bias-corrected precipitation and climatology for the Arctic. (www.uaf.edu/water/faculty/yang/bcp/index.htm)
European Space Agency, GlobSnow	Global weekly and monthly snow cover at 1 km resolution; daily, weekly, and monthly SWE over non-mountainous Northern Hemisphere. (http://globsnow.fmi.fi)
Russian Institute for Hydrometeorological Information, World Data Center (RIHMI-WDC)	Daily snow depth at 223 first-order meteorological stations, from the beginning of observations at each station (the earliest from 1890) until 2006. Update of snow transect data to 2005 (in progress). (http://aisori.meteo.ru/climat)
Institute of Geography, Russian Academy of Sciences	Field data on snow stratigraphy and meteorology at about 10 sites spread over northern Eurasia during several seasons, starting from 1957 until 1997. Includes ~ 300 snow profiles. (Planned to be available online. For now, by request from Andrey Shmakin)
Alaska Snow, Water and Climate Services	Real time and historical snow survey data. (http://ambcs.org)
Environment Yukon	Snow course data. (www.environmentyukon.gov.yk.ca/monitoringenvironment/snow_survey.php)
Indian and Northern Affairs, Water Resources Division, Canada	Historical snow course data online. (http://nwt-tno.inac-ainc.gc.ca/wrd)
WCRP CMIP3 Multi-Model Data	GCM output from CMIP3 runs (snow cover fraction, depth, SWE). (https://esg.llnl.gov/8443)

Satellite observations

The frequency and resolution of satellite monitoring of snow cover has increased significantly since about 2000 with the MODIS, AMSR-E, and QuikSCAT satellite systems providing high-resolution information on snow cover (extent, water equivalent, and melt dates) in the visible and microwave ends of the spectrum. Microwave sensors also provide capabilities for monitoring winter thaw events and ice crust formation; for example, Derksen et al. (2010) were able to detect a regional rain-on-snow event over tundra snow cover with the AMSR-E 36.5 GHz polarization gradient due to a strong response of the horizontal polarization. The trend for increasingly finer resolution snow cover information is seen in the evolution of the NOAA hemispheric snow cover analysis, which was carried out weekly prior to 1997 and daily from 1997 onward, with the final objective being a twice-daily analysis (Helfrich et al., 2007). Over the same period, the spatial resolution of the gridded analysis product available to users has gone from ~200 km (before 1997), to 24 km (from 1997), to 4 km (from 2004).

Satellite observations in the visible and infrared spectral bands provide the most accurate estimates of snow cover extent and offer an opportunity for its mapping and monitoring at a much higher (~500 m) spatial resolution (Hall et al., 2002; Romanov et al., 2003). However, the inability to distinguish between snow-free and snow-covered land beneath the clouds causes a discontinuity both in time series and in the derived spatial distribution of snow cover and, therefore, limits applicability of these products in numerical models. Considerable progress has also been made in recent years in spatial and temporal filtering techniques to intelligently interpolate snow cover information from visible satellite data where cloud cover is obscuring the ground (e.g., Parajka and Bloeschl, 2008). Zhao and Fernandes (2009) developed and applied an intelligent interpolation scheme to produce a pan-Arctic dataset of daily snow cover fraction at a 5-km resolution from 1982 to 2004 with the AVHRR Polar Pathfinder dataset. Major advances have also been made in validating and improving high-resolution MODIS snow cover products (Hall et al., 2002; Hall and Riggs, 2007), and a monthly mean snow cover fraction product is now available from MODIS on a global 0.05° grid from September 2000 where most of the obscuring cloud cover effects have been removed (Hall et al., 2006). Similar improvements have been made in MODIS snow-albedo products to provide spatially and temporally complete data (Moody et al., 2008). Blending of satellite information from visible and infrared and the microwave spectrums (e.g., Romanov et al., 2000; Brodzik et al., 2007; Foster et al., 2011) can also be used to overcome the cloud cover problem, but the blended map may be affected by errors in the microwave snow identification technique.

The NOAA weekly binary snow and no-snow product (Robinson et al., 1993) remains the workhorse for monitoring variability and change in northern hemisphere snow-cover extent with almost continuous weekly data from 1966 (the longest satellite-derived environmental data record). Beginning in June 1999, the weekly NOAA product was replaced by the daily Interactive Multisensor Snow and Ice Mapping System (IMS) product. The maps are digitized to a 1024 × 1024 pixel matrix at 23 km per pixel resolution and a routine has been

developed to reduce these daily maps to a weekly product at the former lower resolution (Ramsay, 1998; Robinson et al., 1999). A major effort has just been completed to create a climate data record with the NOAA dataset, which involved recharting a large number of charts from the 1970s and 1980s with inconsistent mapping of patchy snow (Robinson, Dept. of Geography, Rutgers The State University of New Jersey, USA, pers. comm.). Some care must be used in documenting trends in mountainous regions during the spring/summer ablation period with these data as there is evidence that the change to higher resolution mapping of snow cover in 1999 has resulted in the mapping of smaller amounts of snow in these areas (Déry and Brown, 2007).

Satellite observations using the microwave sensor have been routinely used to map and monitor snow cover since the late 1970s (e.g., Grody and Basist, 1996; Armstrong and Brodzik, 2001; Derksen et al., 2003; Kelly et al., 2003). The ability of microwave sensors to 'see' snow through most clouds and at night is particularly attractive for monitoring snow cover over high-latitude areas. Microwave observations have some potential for providing information on snow depth, although this capability is limited to dry snowpacks only. The well-known limitations of microwave measurements consist of a relatively coarse (currently 10 to 50 km) spatial resolution, difficulty in detecting shallow and melting snow, and an inability to distinguish between snow and cold rocks. As a result, snow cover extent in microwave-based products is frequently underestimated in flat areas, especially in spring and autumn, and is typically overestimated for mountainous areas. Passive microwave has been successful in monitoring snow melt onset and snow-off dates (Takala et al., 2009; Tedesco et al., 2009).

Estimates of SWE over the Northern Hemisphere have been derived from passive microwave sensors (SMMR and SSM/I) since 1976 (e.g., Chang et al., 1987; Armstrong and Brodzik, 2001), but the accuracy of the algorithms is generally acknowledged to be insufficient for many applications. The launch of the higher resolution (~10 km) AMSR-E passive microwave sensor in 2002 promised new advances in mapping SWE over the Arctic (Kelly et al., 2003), but progress has been slow due to a number of ongoing challenges in obtaining SWE values in the Arctic environment. Development of new boreal and tundra algorithms specific to the Arctic region (e.g., Rees et al., 2006; Derksen et al., 2009; Lemmetyinen et al., 2009; Rees et al., 2010) may overcome some of the limitations of previous global SWE algorithms. Passive microwave data have shown some skill for monitoring snow cover end dates in the Arctic (e.g., Brown et al., 2007), providing a means for monitoring variability and change in this important environmental indicator from 1978 with the combined SMMR and SSM/I data record. New high-resolution (5 km) microwave information on the frequency and duration of snow melt events has been produced from the QuikSCAT scatterometer (Wang et al., 2008). This information is available across the pan-Arctic region from 2000 and will be useful for studying phenomena sensitive to melt events. Recently Wang et al. (2009) have combined passive microwave and QuikSCAT data to provide pan-Arctic information on melt onset anomalies over the terrestrial and marine cryosphere.

Snow cover analysis products

Numerical weather prediction requires consistent information on snow cover fraction and depth on daily to twice-daily timescales over the globe for initialization of forecast models (e.g., Brasnett, 1999). This need cannot be completely satisfied from available satellite and surface observing systems, and a number of meteorological centers are generating their own operational snow cover analysis products based on *in situ*, remotely sensed, and modeled information. The trend is for these analyses to be run at higher resolutions (1 to 5 km) and to incorporate more physically-based land surface schemes and snow models. The U.S. National Operational Hydrologic Remote Sensing Center SNOw Data Assimilation System (SNODAS, Carroll et al., 2001) is an example of this approach, which is used to provide 1-km resolution daily information on snow cover (depth, SWE, temperature, melt, sublimation) across the contiguous United States. A technique for generating continuous fields of snow cover characteristics was developed at the Institute of Water Problems of the Russian Academy of Sciences using information on snow extent and water equivalent derived from MODIS, AMSR-E, and a physical snowpack model (Kuchment et al., 2009). The European Space Agency sponsored the GlobSnow project (Kama et al., 2007), which will generate global fields of snow cover extent at 1-km resolution from assimilation of multiple satellite data sources including ERS-2, ATSR-2, Envisat AATSR, and Envisat ASAR.

Information on future changes in snow cover

Projected changes in snow cover fraction and accumulation are available for the 22 GCMs participating in the IPCC Fourth Assessment, for a range of scenarios and model ensemble runs. The scenarios have a number of limitations for Arctic applications, but do provide some idea of large-scale changes in snow cover that can be anticipated to accompany global warming. A variety of methods exist for downscaling more detailed local and regional information on changes in snow cover conditions, including high-resolution nested regional climate and snow process models, which provide detailed information on changes in snowpack properties (e.g., Bavay et al., 2009). Improved high-latitude snow cover simulations are anticipated with the next generation Earth System Models contributing to the IPCC Fifth Assessment. These will have a higher resolution, include improved land surface schemes (e.g., organic soil layers, deeper and more soil layers to resolve permafrost, improved parameterizations of snow-vegetation interactions, and improved treatment of sub-grid scale heterogeneity), as well as dynamic vegetation and carbon cycle parameterization to provide more realistic feedbacks over northern latitudes.

Traditional knowledge

Traditional knowledge can provide important value-added content to data products and information and serves to make the data more useful and relevant to Arctic users. Development of community-based observing programs provide a mechanism for two-way knowledge transfers such as the Gwich'in First Nation IPY environmental monitoring project 'Yeendoo Nanh Nakhweenjit K'atr'ahanahtyaa – Environmental Change and

Traditional Use of the Old Crow Flats in Northern Canada', which includes snow cover monitoring along with a wide range of environmental, wildlife, and cultural variables (<http://classic.ipy.org/development/eoi/proposal-details.php?id=292>). Similar collaborations between Sámi and scientists in Scandinavia are uniting traditional knowledge and scientific information on snow properties and monitoring (<http://icr.arcticportal.org/en/ealat>; Riseth et al., 2011).

Data access and archiving

Quick and easy access to Arctic snow data and information is still a challenge, although most of the satellite-related snow information can be readily searched and downloaded from NSIDC (National Snow and Ice Data Center) or PolarView. A number of operational centers also provide online access to snow products. The situation is not quite so good for *in situ* data, for which national data holdings are not always available online or are out of date. Table A2 provides a snapshot of some of the main snow data sources currently available for the Arctic region. A number of data portals have been established in recent years to facilitate access to datasets, such as Arctic Portal (<http://new.arcticportal.org>); Polar Data Catalogue (www.polardata.ca); Discovery, Access, and Delivery of Data for IPY (<http://nsidc.org/daddi>).

References

- Aanes, R., B.E. Saether and N.A. Oritsland, 2000. Fluctuations of an introduced population of Svalbard reindeer: the effects of density dependence and climatic variation. *Ecography*, 23:437–443.
- AARI, 1985. Arctic Atlas [in Russian]. 204 pp. Arctic and Antarctic Research Institute, Moscow.
- ACIA, 2005. Arctic Climate Impact Assessment. 1042 pp. Cambridge University Press.
- Adam, J.C., A.F. Hamlet and D.P. Lettenmaier, 2009. Implications of global climate change for snowmelt hydrology in the twenty-first century. *Hydrological Processes*, 23:962–972.
- Åhman, B., A. Nilsson, E. Eloranta and K. Olsson, 2002. Wet belly in reindeer (*Rangifer tarandus tarandus*) in relation to body condition, body temperature and blood constituents. *Acta Veterinaria Scandinavica*, 43:85–97.
- Albert, M.R., A.M. Grannas, J. Bottenheim, P.B. Shepson and F.E. Perron, 2002. Processes and properties of snow-air transfer in the high Arctic with application to interstitial ozone at Alert, Canada. *Atmospheric Environment*, 36:2779–2787.
- Aleksandrov, Y.I., N.N. Bryazgin, E.J. Forland, V.F. Radionov and P.N. Syvashchennikov, 2005. Seasonal, interannual and long-term variability of precipitation and snow depth in the region of the Barents and Kara seas. *Polar Research*, 24:69–85.
- Allard, M., R. Fortier, D. Sarrazin, F. Calmels, D. Fortier, D. Chaumont, J.P. Savard and A. Tarussov, 2007. L'impact du réchauffement climatique sur les aéroports du Nunavik : caractéristiques du pergélisol et caractérisation des processus de dégradation des pistes. Final report. 184 pp. Ouranos Consortium. www.ouranos.ca/media/publication/13_Rapport_Allard2_nord_2007.pdf
- AMAP, 1998. AMAP Assessment Report: Arctic Pollution Issues. 859 pp. Arctic Monitoring and Assessment Programme, Oslo, Norway.
- AMAP, 2007. Arctic Oil and Gas 2007. 40 pp. Arctic Monitoring and Assessment Programme, Oslo, Norway.
- AMAP, 2009. AMAP Assessment 2009: Human Health in the Arctic. 254 pp. Arctic Monitoring and Assessment Programme, Oslo, Norway.
- Amoroso, A., H.J. Beine, R. Sparapani, M. Nardino and I. Allegrini, 2006. Observation of coinciding arctic boundary layer ozone depletion and snow surface emissions of nitrous acid. *Atmospheric Environment*, 40:1949–1956.
- Anastasio, C. and T. Robles, 2007. Light absorption by soluble chemical

- species in Arctic and Antarctic snow. *Journal of Geophysical Research-Atmospheres*, 112:D24304.
- Andreadis, K., D. Lettenmaier, L. Tsang, D. Liang and M. Sturm, 2008. Implications of representing snowpack stratigraphy for large-scale passive microwave remote sensing. *American Geophysical Union, Fall Meeting 2008:abstract #C12B-07*.
- Andreadis, K.M., P. Storck and D.P. Lettenmaier, 2009. Modeling snow accumulation and ablation processes in forested environments. *Water Resources Research*, 45:W05429.
- Armstrong, R.L. and M.J. Brodzik, 2001. Recent Northern Hemisphere snow extent: A comparison of data derived from visible and microwave satellite sensors. *Geophysical Research Letters*, 28:3673–3676.
- Atkinson, D.E., R. Brown, B. Alt, T. Agnew, J. Bourgeois, M. Burgess, C. Duguay, G. Henry, S. Jeffers, R. Koerner, A.G. Lewkowicz, S. McCourt, H. Melling, M. Sharp, S. Smith, A. Walker, K. Wilson, S. Wolfe, M.K. Woo and K.L. Young, 2006. Canadian cryospheric response to an anomalous warm summer: A synthesis of the climate change action fund project «The state of the arctic cryosphere during the extreme warm summer of 1998». *Atmosphere-Ocean*, 44:347–375.
- Aziz, O.I.A. and D.H. Burn, 2006. Trends and variability in the hydrological regime of the Mackenzie River Basin. *Journal of Hydrology*, 319:282–294.
- Bakke, A., 1989. The recent Ips typographus outbreak in Norway - Experiences from a control program. *Ecography*, 12:515–519.
- Barber, V.A., G.P. Juday and B.P. Finney, 2000. Reduced growth of Alaskan white spruce in the twentieth century from temperature-induced drought stress. *Nature*, 405:668–673.
- Barry, R.G., R. Armstrong, T. Callaghan, J. Cherry, S. Gearheard, A. Nolin, D. Russell and Z. C., 2007. Chapter 4: Snow. UNEP: Global outlook for Snow and Ice, pp. 39–62. www.unep.org/geo/geo_ice/PDF/full_report_LowRes.pdf
- Bartelt, P. and M. Lehning, 2002. A physical SNO-TACK model for the Swiss avalanche warning Part I: numerical model. *Cold Regions Science and Technology*, 35:123–145.
- Bartsch, A., R.A. Kidd, W. Wagner and Z. Bartalis, 2007. Temporal and spatial variability of the beginning and end of daily spring freeze/thaw cycles derived from scatterometer data. *Remote Sensing of Environment*, 106:360–374.
- Bartsch, A., T. Kumpula, B.C. Forbes and F. Stammer, 2010. Detection of snow surface thawing and refreezing in the Eurasian Arctic using QuikSCAT: implications for reindeer herding. *Ecological Applications*, 20:2346–2358.
- Bavay, M., M. Lehning, T. Jonas and H. Lowe, 2009. Simulations of future snow cover and discharge in Alpine headwater catchments. *Hydrological Processes*, 23:95–108.
- Beier, C.M., S.E. Sink, P.E. Hennon, D.V. D'Amore and G.P. Juday, 2008. Twentieth-century warming and the dendroclimatology of declining yellow-cedar forests in southeastern Alaska. *Canadian Journal of Forest Research-Revue Canadienne De Recherche Forestiere*, 38:1319–1334.
- Beine, H.J., R.E. Honrath, F. Domine, W.R. Simpson and J.D. Fuentes, 2002. NO_x during background and ozone depletion periods at Alert: Fluxes above the snow surface. *Journal of Geophysical Research-Atmospheres*, 107:4584.
- Beine, H.J., F. Domine, A. Ianniello, M. Nardino, I. Allegrini, K. Teinila and R. Hillamo, 2003. Fluxes of nitrates between snow surfaces and the atmosphere in the European high Arctic. *Atmospheric Chemistry and Physics*, 3:335–346.
- Beine, H.J., A. Amoroso, G. Esposito, R. Sparapani, A. Ianniello, T. Georgiadis, M. Nardino, P. Bonasoni, P. Cristofanelli and F. Domine, 2005. Deposition of atmospheric nitrous acid on alkaline snow surfaces. *Geophysical Research Letters*, 32:L10808.
- Beine, H.J., A. Amoroso, F. Domine, M.D. King, M. Nardino, A. Ianniello and J.L. France, 2006. Surprisingly small HONO emissions from snow surfaces at Browning Pass, Antarctica. *Atmospheric Chemistry and Physics*, 6:2569–2580.
- Benedict, J.B., 1990. Lichen mortality due to late-lying snow - results of a transplant study. *Arctic and Alpine Research*, 22:81–89.
- Benestad, R., I. Hanssen and D. Chen, 2008. Empirical-Statistical Downscaling. 228 pp. World Scientific Publishers, University of Gothenburg, Sweden.
- Beniston, M., F. Keller and S. Goyette, 2003. Snow pack in the Swiss Alps under changing climatic conditions: an empirical approach for climate impacts studies. *Theoretical and Applied Climatology*, 74:19–31.
- Berezovskaya, S., D.Q. Yang and D.L. Kane, 2004. Compatibility analysis of precipitation and runoff trends over the large Siberian watersheds. *Geophysical Research Letters*, 31:L21502.
- Bewley, D., J.W. Pomeroy and R.L.H. Essery, 2007. Solar radiation transfer through a subarctic shrub canopy. *Arctic Antarctic and Alpine Research*, 39:365–374.
- Bilbrough, C.J., J.M. Welker and W.D. Bowman, 2000. Early spring nitrogen uptake by snow-covered plants: A comparison of arctic and alpine plant function under the snowpack. *Arctic Antarctic and Alpine Research*, 32:404–411.
- Bjerregaard, P., T.K. Young, E. Dewailly and S.O.E. Ebbesson, 2004. Indigenous health in the Arctic: an overview of the circumpolar Inuit population. *Scandinavian Journal of Public Health*, 32:390–395.
- Bogdanova, E.G., B.M. Ilyin and I.V. Dragomilova, 2002a. Application of a comprehensive bias-correction model to precipitation measured at Russian North Pole drifting stations. *Journal of Hydrometeorology*, 3:700–713.
- Bogdanova, E.G., V.S. Golubev, B.M. Ilyin and I.V. Dragomilova, 2002b. A new model for bias correction of precipitation measurements, and its application to polar regions of Russia. *Russian Meteorology and Hydrology*, 10:68–94.
- Bokhorst, S., J.W. Bjerke, F.W. Bowles, J. Melillo, T.V. Callaghan and G.K. Phoenix, 2008. Impacts of extreme winter warming in the sub-Arctic: growing season responses of dwarf shrub heathland. *Global Change Biology*, 14:2603–2612.
- Bokhorst, S.F., J.W. Bjerke, H. Tømmervik, T.V. Callaghan and G.K. Phoenix, 2009. Winter warming events damage sub-Arctic vegetation: consistent evidence from an experimental manipulation and a natural event. *Journal of Ecology*, 97:1408–1415.
- Botkin, D.B., H. Saxe, M.B. Araujo, R. Betts, R.H.W. Bradshaw, T. Cedhagen, P. Chesson, T.P. Dawson, J.R. Etterson, D.P. Faith, S. Ferrier, A. Guisan, A.S. Hansen, D.W. Hilbert, C. Loehle, C. Margules, M. New, M.J. Sobel and D.R.B. Stockwell, 2007. Forecasting the effects of global warming on biodiversity. *Bioscience*, 57:227–236.
- Bourne, S., 2008. A climate perspective of observed and modeled surface-based temperature inversions in Alaska. Unpublished M.S. thesis. 106 pp. University of Alaska, Fairbanks.
- Bowd, A.D., 2005. Otitis media: Health and social consequences for aboriginal youth in Canada's north. *International Journal of Circumpolar Health*, 64:5–15.
- Bowling, L.C., D.P. Lettenmaier, B. Nijssen, L.P. Graham, D.B. Clark, M. El Maayar, R. Essery, S. Goers, Y.M. Gusev, F. Habets, B. van den Hurk, J.M. Jin, D. Kahan, D. Lohmann, X.Y. Ma, S. Mahanama, D. Mocko, O. Nasonova, G.Y. Niu, P. Samuelsson, A.B. Shmakin, K. Takata, D. Verseghy, P. Viterbo, Y.L. Xia, Y.K. Xue and Z.L. Yang, 2003. Simulation of high-latitude hydrological processes in the Torne-Kalix basin: PILPS phase 2(e) - 1: Experiment description and summary intercomparisons. *Global and Planetary Change*, 38:1–30.
- Boxe, C.S., A.J. Colussi, M.R. Hoffmann, D. Tan, J. Mastromarino, A.T. Case, S.T. Sandholm and D.D. Davis, 2003. Multiscale ice fluidity in NO_x photodesorption from frozen nitrate solutions. *Journal of Physical Chemistry A*, 107:11409–11413.
- Bradley, R.S., F.T. Keimig and H.F. Diaz, 1992a. Climatology of surface-based inversions in the North American Arctic. *Journal of Geophysical Research-Atmospheres*, 97:15699–15712.
- Bradley, R.S., F.T. Keimig and H.F. Diaz, 1992b. Recent changes in the Arctic boundary layer in winter. *Journal of Geophysical Research*, 97:8851–8858.
- Bradley, M.J., S.J. Kutz, E. Jenkins and T.M. O'Hara, 2005. The potential impact of climate change on infectious diseases of Arctic fauna. *International Journal of Circumpolar Health*, 64:468–477.
- Brasnett, B., 1999. A global analysis of snow depth for numerical weather prediction. *Journal of Applied Meteorology*, 38:726–740.
- Brodzik, M.J., R.L. Armstrong and M. Savoie, 2007. Global EASE-Grid 8-day Blended SSM/I and MODIS Snow Cover. National Snow and Ice Data Center, Boulder, Colorado USA. Digital media. <http://nsidc.org/data/nsidc-0321.html>. Accessed: May 3 2011.
- Brown, R.D. and R.L. Armstrong, 2008. Snow-cover data: measurement, products and sources. In: Armstrong, R. and E. Brun (Eds.). *Snow and Climate*, 222 pp. Cambridge University Press.
- Brown, R.D. and B. Brasnett, 2010. Canadian Meteorological Centre (CMC) Daily Snow Depth Analysis Data. National Snow and Ice Data Center, Boulder, Colorado USA. Digital media. http://nsidc.org/data/docs/daac/nsidc0447_CMC_snow_depth/index.html. Accessed: May 3 2011.

- Brown, R.D. and B.E. Goodison, 1996. Interannual variability in reconstructed Canadian snow cover, 1915-1992. *Journal of Climate*, 9:1299-1318.
- Brown, R.D. and P.W. Mote, 2009. The response of northern hemisphere snow cover to a changing climate. *Journal of Climate*, 22:2124-2145.
- Brown, R.D., B. Brasnett and D. Robinson, 2003. Gridded North American monthly snow depth and snow water equivalent for GCM evaluation. *Atmosphere-Ocean*, 41:1-14.
- Brown, R., C. Derksen and L. Wang, 2007. Assessment of spring snow cover duration variability over northern Canada from satellite datasets. *Remote Sensing of Environment*, 111:367-381.
- Brown, R., C. Derksen and L. Wang, 2010. A multi-dataset analysis of variability and change in Arctic spring snow cover extent, 1967-2008. *Journal of Geophysical Research Atmospheres*, 115:D16111.
- Brun, E., E. Martin, V. Simon, C. Gendre and C. Coleou, 1989. An energy and mass model of snow cover suitable for operational avalanche forecasting. *Journal of Glaciology*, 35:333-342.
- Brun, E., P. David, M. Sudul and G. Brunot, 1992. A numerical-model to simulate snow-cover stratigraphy for operational avalanche forecasting. *Journal of Glaciology*, 38:13-22.
- Brun, E., R. Essery and J. Cohen, 2008. Snow cover parameterizations and modeling. In: Armstrong, R. and E. Brun (Eds.). *Snow and Climate*, 222 pp. Cambridge University Press.
- Bull, W.B., P. Schlyter and S. Brogaard, 1995. Lichenometric analysis of the Kärkerieppe slush-avalanche fan, Kärkevagge, Sweden. *Geografiska Annaler Series a-Physical Geography*, 77:231-240.
- Bulygina, O.N., N.N. Korshunova and V.N. Razuvaev, 2007. Changes in snow cover characteristics in recent decades. *Transactions of the Research Institute for Hydrometeorological Information*, 173:54-66.
- Bulygina, O.N., V.N. Razuvaev and N.N. Korshunova, 2009. Changes in snow cover over Northern Eurasia in the last few decades. *Environmental Research Letters*, 4:045026.
- Bulygina, O.N., P.Y. Groisman, V.N. Razuvaev and V.F. Radionov, 2010a. Snow cover basal ice layer changes over Northern Eurasia since 1966. *Environmental Research Letters*, 5:015004.
- Bulygina, O.N., P.Y. Groisman and V.N. Razuvaev, 2010b. Snow cover characteristics over Northern Eurasia. *Geophysical Research Abstracts*, 12:EGU2010-1460.
- Burn, D.H., J.M. Cunderlik and A. Pietroniro, 2004. Hydrological trends and variability in the Liard River basin. *Hydrological Sciences Journal-Journal des Sciences Hydrologiques*, 49:53-67.
- Caballero, R., J.A. Riseth, N. Labba, E. Tyran, W. Musial, E. Motik, A. Boltshauser, P. Hofstetter, A. Gueydon, N. Roeder, H. Hoffmann, M.B. Moreira, I.S. Coelho, O. Brito and A. Gil, 2007. Comparative typology in six European low-intensity systems of grassland management. *Advances in Agronomy*, 96:351-420.
- CAFF, 1994. The state of protected areas in the circumpolar Arctic 1994. CAFF Habitat Conservation Report 1, 151 pp. Directorate for Nature Management, Trondheim, Norway.
- CAFF, 1996. Proposed protected areas in the circumpolar Arctic 1996. CAFF Habitat Conservation Report No. 2, 199 pp. Directorate for Nature Management, Trondheim, Norway.
- Callaghan, T.V. and M. Johansson, 2009. The changing, living tundra: a tribute to Yuri Chernov. In: Golvatch, S.I., O.L. Makarova, A.B. Babenko and L.D. Penev (Eds.). *Species and communities in extreme environments. Festschrift towards the 75th Anniversary and a Laudatio in Honour of Academician Yuri Ivanovich Chernov*, pp. 13-52, Pensoft Publishers.
- Callaghan, T.V., B.M. Svensson, I.S. Jonsdottir and B.A. Carlsson (Eds.), 1992. Clonal plants and climate change. *Proceedings of the conference in Abisko, Sweden, 1990*. *Oikos* 63.
- Callaghan, T.V., L.O. Björn, Y. Chernov, F.S. Chapin, T.R. Christensen, B. Huntley, R.A. Ims, S. Jonasson, M. Johansson, D. Jolly, N. Matveyeva, N. Panikov, W.C. Oechel and G.R. Shaver, 2005. Tundra and Polar Desert Ecosystems In: Corell, R. (Ed.). *Arctic Climate Impacts Assessment: Technical report to the Arctic Council of Ministers*, pp. 243-352, Cambridge University Press.
- Callaghan, T.V., F. Bergholm, T.R. Christensen, C. Jonasson, U. Kokfelt and M. Johansson, 2010. A new climate era in the sub-Arctic: Accelerating climate changes and multiple impacts. *Geophysical Research Letters*, 37:L14705.
- Carroll, T., D. Cline, G. Fall, A. Nilsson, L. Li and A. Rost, 2001. NOHRSC operations and the simulation of snow cover properties for the coterminous U.S. Paper presented at 69th Annual Western Snow Conference, pp. 1-10, Sun Valley, Idaho, April 16-19, 2001.
- Chambers, J.C., 1991. Patterns of growth and reproduction in a perennial tundra forb (*Geum rossii*) - effects of clone area and neighbourhood. *Canadian Journal of Botany*, 69:1977-1983.
- Chang, A.T.C., J.L. Foster and D.K. Hall, 1987. Nimbus 7 SMMR derived global snow cover parameters. *Annals of Glaciology*, 9:39-44.
- Chapin, F.S., G. Peterson, F. Berkes, T.V. Callaghan, P. Angelstam, M. Apps, C. Beier, Y. Bergeron, A.S. Crepin, K. Danell, T. Elmqvist, C. Folke, B. Forbes, N. Fresco, G. Juday, J. Niemela, A. Shvidenko and G. Whiteman, 2004. Resilience and vulnerability of northern regions to social and environmental change. *Ambio*, 33:344-349.
- Christensen, J.H., B. Hewitson, A. Busuioc, A. Chen, X. Gao, I. Held, R. Jones, R.K. Kolli, T. Kwon, R. Laprise, V. Magaña Rueda, L. Mearns, C.G. Menéndez, J. Räisänen, A. Rinke, A. Sarr and P. Whetton, 2007. Regional climate projections. In: Solomon, S., D. Qin, M. Manning, Z. Chen, M. Marquis, K.B. Averyt, M. Tignor and H.L. Miller (Eds.). *Climate Change 2007: The Physical Science Basis. Contribution of Working Group I to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change*, Cambridge University Press.
- Chu, L. and C. Anastasio, 2003. Quantum yields of hydroxyl radical and nitrogen dioxide from the photolysis of nitrate on ice. *Journal of Physical Chemistry A*, 107:9594-9602.
- Chu, L. and C. Anastasio, 2005. Formation of hydroxyl radical from the photolysis of frozen hydrogen peroxide. *Journal of Physical Chemistry A*, 109:6264-6271.
- Chylek, P., V. Srivastava, L. Cahenzli, R.G. Pinnick, R.L. Dod, T. Novakov, T.L. Cook and B.D. Hinds, 1987. Aerosol and graphitic carbon content of snow. *Journal of Geophysical Research-Atmospheres*, 92:9801-9809.
- Clark, M.P. and M.C. Serreze, 2000. Effects of variations in east Asian snow cover on modulating atmospheric circulation over the north pacific ocean. *Journal of Climate*, 13:3700-3710.
- Clarke, A.D. and K.J. Noone, 1985. Soot in the Arctic snowpack - a cause for perturbations in radiative-transfer. *Atmospheric Environment*, 19:2045-2053.
- Cohen, J. and D. Rind, 1991. The effect of snow cover on the climate. *Journal of Climate*, 4:689-706.
- Colin, J.L., B. Lim, E. Herms, F. Genet, E. Drab, J.L. Jaffrezo and C.I. Davidson, 1997. Air-to-snow mineral transfer - Crustal elements in aerosols, fresh snow and snowpits on the Greenland Ice Sheet. *Atmospheric Environment*, 31:3395-3406.
- Cui, X.F., B. Langmann and H.F. Graf, 2007. Summer monsoonal rainfall simulation on the Tibetan Plateau with a regional climate model using a one-way double-nesting system. *Sola*, 3:49-52.
- Curtis, T., S. Kvermmo and P. Bjerregaard, 2005. Changing living conditions, life style and health. *International Journal of Circumpolar Health*, 64:442-450.
- D'Arrigo, R.D., R.K. Kaufmann, N. Davi, G.C. Jacoby, C. Laskowski, R.B. Myneni and P. Cherubini, 2004. Thresholds for warming-induced growth decline at elevational tree line in the Yukon Territory, Canada. *Global Biogeochemical Cycles*, 18:Gb3021.
- Daerger, L., A. Edin-Liljegren and P. Sjölander, 2004. Work-related musculoskeletal pain among reindeer herding Sami in Sweden – a pilot study on causes and prevention. *International Journal of Circumpolar Health*, 63:343-348.
- Davis, R.E., J.P. Hardy, W. Ni, C. Woodcock, J.C. McKenzie, R. Jordan and X. Li, 1997. Variation of snow cover ablation in the boreal forest: A sensitivity study on the effects of conifer canopy. *Journal of Geophysical Research-Atmospheres*, 102:29389-29395.
- Dawson, J., P.T. Maher and D.S. Solcombe, 2007. Climate change, marine tourism, and sustainability in the Canadian Arctic: Contributions from systems and complexity approaches. *Tourism in Marine Environments*, 4:69-83.
- Defoliart, L.S., M. Griffith, F.S. Chapin and S. Jonasson, 1988. Seasonal patterns of photosynthesis and nutrient storage in *Eriophorum vaginatum* L., an arctic sedge. *Functional Ecology*, 2:185-194.
- Derksen, C., A. Walker, E. LeDrew and B. Goodison, 2003. Combining SMMR and SSM/I data for time series analysis of Central North American snow water equivalent. *Journal of Hydrometeorology*, 4:304-316.
- Derksen, C., A. Walker and P. Toose, 2008a. Estimating snow water equivalent in Northern Regions from satellite passive microwave data. In: Woo, M.-k. (Ed.). *Cold Region Atmospheric and Hydrologic*

- Studies, The Mackenzie GEWEX Experience, pp. 195–212.
- Derksen, C., R. Brown and M. MacKay, 2008b. Mackenzie Basin snow cover: variability and trends from conventional data, satellite remote sensing, and Canadian regional climate model simulations. In: Woo, M.-k. (Ed.). Cold Region Atmospheric and Hydrologic Studies, the Mackenzie GEWEX Experience, pp. 213–240.
- Derksen, C., M. Sturm, G.E. Liston, J. Holmgren, H. Huntington, A. Silis and D. Solie, 2009. Northwest Territories and Nunavut snow characteristics from a subarctic traverse: implications for passive microwave remote sensing. *Journal of Hydrometeorology*, 10:448–463.
- Derksen, C., R. Brown and L. Wang, 2010. Terrestrial snow: Arctic. In J. Richter-Menge (Ed.) State of the Climate Report 2009, Arctic Chapter, Bulletin of the American Meteorological Society, 91:S117–S119. www.arctic.noaa.gov/reportcard/snow.html
- Déry, S.J. and R.D. Brown, 2007. Recent Northern Hemisphere snow cover extent trends and implications for the snow-albedo feedback. *Geophysical Research Letters*, 34:L22504.
- Déry, S.J., W.T. Crow, M. Stieglitz and E.F. Wood, 2004. Modeling snow-cover heterogeneity over complex arctic terrain for regional and global climate models. *Journal of Hydrometeorology*, 5:33–48.
- Deser, C., R. Tomas, M. Alexander and D. Lawrence, 2010. The seasonal atmospheric response to projected Arctic sea ice loss in the late twenty-first century. *Journal of Climate*, 23:333–351.
- Dibb, J.E. and M. Arsenault, 2002. Shouldn't snowpacks be sources of monocarboxylic acids? *Atmospheric Environment*, 36:2513–2522.
- Dietz, R., J. Pacyna and D.J. Thomas, 1998. Heavy metals. In: AMAP Assessment Report: Arctic Pollution Issues, pp. 373–524, Arctic Monitoring and Assessment Programme, Oslo, Norway.
- Dingman, S.L., 2002. Snow and Snowmelt. *Physical Hydrology*, pp. 159–209, Prentice Hall.
- Domine, F., M. Albert, T. Huthwelker, H.W. Jacobi, A.A. Kokhanovsky, M. Lehning, G. Picard and W.R. Simpson, 2008. Snow physics as relevant to snow photochemistry. *Atmospheric Chemistry and Physics*, 8:171–208.
- Donaldson, G.C., S.P. Ermakov, Y.M. Komarov, C.P. McDonald and W.R. Keatinge, 1998. Cold related mortalities and protection against cold in Yakutsk, eastern Siberia: observation and interview study. *British Medical Journal*, 317:978–982.
- Douglas, T.A., M. Sturm, W.R. Simpson, J.D. Blum, L. Alvarez-Aviles, G.J. Keeler, D.K. Perovich, A. Biswas and K. Johnson, 2008. Influence of snow and ice crystal formation and accumulation on mercury deposition to the Arctic. *Environmental Science & Technology*, 42:1542–1551.
- Dyer, J.L. and T.L. Mote, 2006. Spatial variability and trends in observed snow depth over North America. *Geophysical Research Letters*, 33:L16503.
- Eilertsen, S.M., I. Schjelderup and S.D. Mathiesen, 2000. Plant quality and harvest in old meadows grazed by reindeer in spring. *Journal of the Science of Food and Agriculture*, 80:329–334.
- Eira, N.I., 1984. Boazobargi giela (The working language in reindeer management). *Dieðit*, 1.
- Emerging Infectious Diseases, 2008. Volume 14: Issue 1. Special Issue: International Polar Year.
- Environment Canada, 1989. Ecoclimatic regions of Canada. Ecological Land Classification Series. No. 23: 1:7,500,000 map + 119 pp. Sustainable Development Branch, Canadian Wildlife Service, Conservation and Protection, Environment Canada, Ottawa, Ontario.
- Eriksson, O., 1976. Snöförhållandenas inverkan på renbetningen (The influence of snow conditions on reindeer pasturing). [in Swedish]. Meddelanden från Växtbiologiska Institutionen, Uppsala University, 2:1–19.
- Essery, R., J. Pomeroy, C. Ellis and T. Link, 2008. Modelling longwave radiation to snow beneath forest canopies using hemispherical photography or linear regression. *Hydrological Processes*, 22:2788–2800.
- Euskirchen, E.S., A.D. McGuire, D.W. Kicklighter, Q. Zhuang, J.S. Clein, R.J. Dargaville, D.G. Dye, J.S. Kimball, K.C. McDonald, J.M. Melillo, V.E. Romanovsky and N.V. Smith, 2006. Importance of recent shifts in soil thermal dynamics on growing season length, productivity, and carbon sequestration in terrestrial high-latitude ecosystems. *Global Change Biology*, 12:731–750.
- Euskirchen, E.S., A.D. McGuire and F.S. Chapin, III, 2007. Energy feedbacks of northern high-latitude ecosystems to the climate system due to reduced snow cover during 20th century warming. *Global Change Biology*, 13:2425–2438.
- Evans, B.M., D.A. Walker, C.S. Benson, E.A. Nordstrand and G.W. Petersen, 1989. Spatial interrelationships between terrain, snow distribution and vegetation patterns at an arctic foothills site in Alaska. *Holarctic Ecology*, 12:270–278.
- Fahnestock, J.T., M.H. Jones, P.D. Brooks, D.A. Walker and J.M. Welker, 1998. Winter and early spring CO₂ efflux from tundra communities of northern Alaska. *Journal of Geophysical Research-Atmospheres*, 103:29023–29027.
- FAO, 2009. Global Review of Forest Pests and Diseases. FAO Forestry Paper, 156, 235 pp. Food and Agriculture Organization of the United Nations, Rome.
- Fernandes, R., H.X. Zhao, X.J. Wang, J. Key, X. Qu and A. Hall, 2009. Controls on Northern Hemisphere snow albedo feedback quantified using satellite Earth observations. *Geophysical Research Letters*, 36:L21702.
- Fetterer, F. and V. Radionov, 2000. Environmental Working Group. Arctic meteorology and climate atlas. Arctic Climatology Project. http://nsidc.org/data/docs/noaa/g01938_ewg_arctic_met_atlas/. Accessed: May 3 2011.
- Fierz, C., R.L. Armstrong, Y. Durand, P. Etchevers, E. Greene, D.M. McClung, K. Nishimura, P.K. Satyawali and S.A. Sokratov, 2009. The international classification for seasonal snow on the ground. IACS Contribution N°1. Technical Documents in Hydrology, 83:IHP-VII.
- Flanner, M.G., C.S. Zender, J.T. Randerson and P.J. Rasch, 2007. Present-day climate forcing and response from black carbon in snow. *Journal of Geophysical Research-Atmospheres*, 112:D11202.
- Flanner, M.G., C.S. Zender, P.G. Hess, N.M. Mahowald, T.H. Painter, V. Ramanathan and P.J. Rasch, 2008. Springtime warming and reduced snow cover from carbonaceous particles. *Atmospheric Chemistry and Physics Discussion*, 8:19819–19859.
- Fletcher, C.G., S.C. Hardiman, P.J. Kushner and J. Cohen, 2009a. The dynamical response to snow cover perturbations in a large ensemble of atmospheric GCM integrations. *Journal of Climate*, 22:1208–1222.
- Fletcher, C.G., P.J. Kushner, A. Hall and X. Qu, 2009b. Circulation responses to snow albedo feedback in climate change. *Geophysical Research Letters*, 36:L09702.
- Forbes, B.C., 2008. Equity, vulnerability and resilience in social-ecological systems: a contemporary example from the Russian Arctic. *Research in Social Problems and Public Policy* 15:203–236.
- Forbes, B.C. and F. Stammer, 2009. Arctic climate change discourse: the contrasting politics of research agendas in the West and Russia. *Polar Research*, 28:28–42.
- Forbes, B.C., M. Bølter, L. Müller-Wille, J. Hukkinen, F. Müller, N. Gunsley and Y. Konstantinov (Eds.), 2006. Reindeer Management in Northernmost Europe: Linking Practical and Scientific Knowledge in Social-Ecological Systems. 397 pp. Springer Verlag.
- Forbes, B.C., F. Stammer, T. Kumpula, N. Meschtyb, A. Pajunen and E. Kaarlejärvi, 2009. High resilience in the Yamal-Nenets social-ecological system, West Siberian Arctic, Russia. *Proceedings of the National Academy of Sciences of the United States of America*, 106:22041–22048.
- Forbes, B.C., F.M. Macias and P. Zetterberg, 2010. Russian Arctic warming and 'greening' are closely tracked by tundra shrub willows. *Global Change Biology*, 16:1542–1554.
- Forchhammer, M. and D. Boertmann, 1993. The muskoxen *Ovibos moschatus* in north and northeast Greenland - population trends and the influence of abiotic parameters on population-dynamics. *Ecography*, 16:299–308.
- Forchhammer, M.C. and E. Post, 2004. Using large-scale climate indices in climate change ecology studies. *Population Ecology*, 46:1–12.
- Forchhammer, M.C., E. Post, T.B.G. Berg, T.T. Høye and N.M. Schmidt, 2005. Local-scale and short-term herbivore-plant spatial dynamics reflect influences of large-scale climate. *Ecology*, 86:2644–2651.
- Forchhammer, M.C., N.M. Schmidt, T.T. Høye, T.B. Berg, D.K. Hendrichsen and E. Post, 2008. Population dynamical responses to climate change. *Advances in Ecological Research*, 40:391–419.
- Ford, J.D. and C. Furgal, 2009. Foreword to the special issue: climate change impacts, adaptation and vulnerability in the Arctic. *Polar Research*, 28:1–9.
- Foster, K.L., R.A. Plastring, J.W. Bottenheim, P.B. Shepson, B.J. Finlayson-Pitts and C.W. Spicer, 2001. The role of Br₂ and BrCl in surface ozone destruction at polar sunrise. *Science*, 291:471–474.
- Foster, J.L., D.A. Robinson, D.K. Hall and T.W. Estilow, 2008. Spring snow

- melt timing and changes over Arctic lands. *Polar Geography*, 31:145–157.
- Foster, J.L., D.K. Hall, J.B. Eyrander, G.A. Riggs, S.V. Nghiem, M. Tedesco, E. Kim, P.M. Montesano, R.E.J. Kelly, K.A. Casey and B. Choudhury, 2011. A blended global snow product using visible, passive microwave and scatterometer satellite data. *International Journal of Remote Sensing*, 32:1371–1395.
- France, J.L., M.D. King and J. Lee-Taylor, 2007. Hydroxyl (OH) radical production rates in snowpacks from photolysis of hydrogen peroxide (H₂O₂) and nitrate (NO₃⁻). *Atmospheric Environment*, 41:5502–5509.
- Frey, B.R., V.J. Lieffers, E.H. Hogg and S.M. Landhäusser, 2004. Predicting landscape patterns of aspen dieback: mechanisms and knowledge gaps. *Canadian Journal of Forest Research-Revue Canadienne de Recherche Forestiere*, 34:1379–1390.
- Frolov, I.E. (Ed.), 2010. Review of the Hydrometeorological Processes in the Arctic Ocean, 2009 [in Russian]. 136 pp. St. Petersburg. AARI Publishing. www.aari.ru/main.php
- Furgal, C. and T.D. Prowse, 2008. Northern Canada. In: Lemmen, D.S., F.J. Warren, J. Lacroix and E. Busch (Eds.). *From Impacts to Adaptation: Canada in a Changing Climate 2007*, pp. 57–118, Government of Canada, Ottawa, ON.
- Furgal, C. and J. Seguin, 2006. Climate change, health, and vulnerability in Canadian northern Aboriginal communities. *Environmental Health Perspectives*, 114:1964–1970.
- Garbarino, J.R., E. Snyder-Conn, T.J. Leiker and G.L. Hoffman, 2002. Contaminants in arctic snow collected over northwest Alaskan sea ice. *Water Air and Soil Pollution*, 139:183–214.
- Gerland, S., J.G. Winther, J.B. Orbaek, G.E. Liston, N.A. Oritsland, A. Blanco and B. Ivanov, 1999. Physical and optical properties of snow covering Arctic tundra on Svalbard. *Hydrological Processes*, 13:2331–2343.
- Gninenko, Y.I. and A.D. Orlinskii, 2002. *Dendrolimus sibiricus* in the coniferous forests of European Russia at the beginning of the twenty-first century. *Bulletin OEPP*, 32:481–483.
- Gode, J., J. Axelsson, S. Eriksson, K. Holmgren, G. Hovsenius, E. Kjellström, P. Larsson, L. Lundström and G. Persson, 2007. Tänkbara konsekvenser för energisektorn av klimatförändringar. Effekter, sårbarhet, anpassning. – Possible consequences of climate change on the energy sector. Effects, vulnerability and adaptation [in Swedish]. *Elforsk rapport*, 7:112.
- Goetz, S.J., A.G. Bunn, G.J. Fiske and R.A. Houghton, 2005. Satellite-observed photosynthetic trends across boreal North America associated with climate and fire disturbance. *Proceedings of the National Academy of Sciences of the United States of America*, 102:13521–13525.
- Golubeva, N.I., 2007. Pollution of Arctic atmosphere by toxic heavy metals - Biology and Oceanography of Northern Sea Route [in Russian]. The Barents and Kara Seas, pp. 173–189, Nauka, Moscow.
- Golubev, V.N., M.N. Petrushina and D.M. Frolov, 2008. Winter regime of temperature and precipitation as a factor of snow-cover distribution and its stratigraphy. *Annals of Glaciology*, 49:179–186.
- Gong, G., D. Entekhabi, J. Cohen and D. Robinson, 2004. Sensitivity of atmospheric response to modeled snow anomaly characteristics. *Journal of Geophysical Research-Atmospheres*, 109:D06107.
- Goodale, C.L., M.J. Apps, R.A. Birdsey, C.B. Field, L.S. Heath, R.A. Houghton, J.C. Jenkins, G.H. Kohlmaier, W. Kurz, S.R. Liu, G.J. Nabuurs, S. Nilsson and A.Z. Shvidenko, 2002. Forest carbon sinks in the Northern Hemisphere. *Ecological Applications*, 12:891–899.
- Goodison, B.E., 2009. WMO Global Cryosphere Watch (GCW), background, concept, status, next steps. 15 pp. EC-PORS-1 Doc. 7.3.1 INF-4(13.VIII.2009), Ottawa, Canada.
- Goodison, B.E. and P.Y.T. Louie, 1986. Canadian methods for precipitation measurement and correction. In: WMO (Ed.). *Instruments and observing methods*, pp. 141–145, WMO/TD.
- Goodison, B.E., P.Y.T. Louie and D. Yang, 1998. WMO solid precipitation measurement intercomparison. Final Report. Instruments and observing methods. Rep. 67. pp. 87. World Meteorological Organization / TD, Geneva. www.wmo.int/pages/prog/www/reports/WMOtd872.pdf
- Gordeev, V.V. and A.P. Lisitsyn, 2005. Heavy metals in the snow and ice cover of the Barents Sea [in Russian]. *Oceanology*, 45:737–744.
- Gower, S.T., O. Krankina, R.J. Olson, M. Apps, S. Linder and C. Wang, 2001. Net primary production and carbon allocation patterns of boreal forest ecosystems. *Ecological Applications*, 11:1395–1411.
- Grannas, A.M., P.B. Shepson and T.R. Filley, 2004. Photochemistry and nature of organic matter in Arctic and Antarctic snow. *Global Biogeochemical Cycles*, 18:Gb1006.
- Grannas, A.M., A.E. Jones, J. Dibb and 32 others, 2007. An overview of snow photochemistry: evidence, mechanisms and impacts. *Atmospheric Chemistry and Physics*, 7:4329–4373.
- Graversen, R.G., T. Mauritsen, M. Tjernström, E. Källén and G. Svensson, 2008. Vertical structure of recent Arctic warming. *Nature*, 451:53–56.
- Grenfell, T.C., S.G. Warren, V.F. Radionov, V.N. Makarov and S.A. Zimov, 2009. Expeditions to the Russian Arctic to survey black carbon in snow. EOS, Transactions of the American Geophysical Union, 90:386.
- Griffith, B., D.C. Douglas, N.E. Walsh, D.D. Young, T.R. McCabe, D.E. Russell, R.G. White, R.D. Cameron and K.R. Whitten, 2002. The Porcupine caribou herd. Biological Science Report, 8–37 pp. U. S. Geological Survey, Biological Resources Division.
- Grody, N.C. and A.N. Basist, 1996. Global identification of snowcover using SSM/I measurements. *IEEE Transactions on Geoscience and Remote Sensing*, 34:237–249.
- Grogan, P. and S. Jonasson, 2006. Ecosystem CO₂ production during winter in a Swedish subarctic region: The relative importance of climate and vegetation type. *Global Change Biology*, 12:1479–1495.
- Groisman, P. and A.J. Soja, 2009. Ongoing climatic change in Northern Eurasia: justification for expedient research. *Environmental Research Letters*, 4:1–7.
- Groisman, P.Y., T.R. Karl, R.W. Knight and G.L. Stenchikov, 1994a. Changes of snow cover, temperature, and radiative heat-balance over the Northern Hemisphere. *Journal of Climate*, 7:1633–1656.
- Groisman, P.Y., T.R. Karl and R.W. Knight, 1994b. Observed impact of snow cover on the heat-balance and the rise of continental spring temperatures. *Science*, 263:198–200.
- Groisman, P.Y., E.L. Genikhovich, R.S. Bradley and B.M. Ilyin, 1997. Assessing surface-atmosphere interactions using former Soviet Union standard meteorological network data .2. Cloud and snow cover effects. *Journal of Climate*, 10:2184–2199.
- Groisman, P.Y., B. Sun, R.S. Vose, J.H. Lawrimore, P.H. Whitfield, E. Førland, I. Hanssen-Bauer, M.C. Serreze, V.N. Razuvaev and G.V. Alekseev, 2003. Contemporary climate changes in high latitudes of the Northern Hemisphere: Daily time resolution. Paper presented at the International Symposium on Climate Change, pp. 51–55. WMO, Beijing, China.
- Groisman, P.Y., R.W. Knight, V.N. Razuvaev, O.N. Bulygina and T.R. Karl, 2006. State of the ground: Climatology and changes during the past 69 years over northern Eurasia for a rarely used measure of snow cover and frozen land. *Journal of Climate*, 19:4933–4955.
- Groisman, P.Y., S.A. Bartalev and N.S.P.D. Team, 2007. Northern Eurasia earth science partnership initiative (NEESPI), science plan overview. *Global and Planetary Change*, 56:215–234.
- Groisman, P., G. Gutman and A. Reissell, 2010. Introduction: climate and land-cover changes in the Arctic. In: Gutman, G. and A. Reissell (Eds.). *Eurasian Arctic Land Cover and Land Use in a Changing Climate*. Springer.
- Gude, M. and D. Scherer, 1995. Snowmelt and slush torrents - Preliminary report from a field campaign in Kärkevagge, Swedish Lappland. *Geografiska Annaler Series a-Physical Geography*, 77A:199–206.
- Guseva, E. and V.N. Golubev, 1989. Thermomechanical mathematical model of the formation of the structure and properties of the snowcover. *GeoJournal*, 19:193–200.
- Hall, D.K. and G.A. Riggs, 2007. Accuracy assessment of the MODIS snow products. *Hydrological Processes*, 21:1534–1547.
- Hall, D.K., G. Riggs, V. Salomonson, N.E. DiGirolamo and K.J. Bayr, 2002. MODIS snow cover products. *Remote Sensing of Environment*, 83:181–194.
- Hall, D.K., G.A. Riggs and V.V. Salomonson, 2006. MODIS/Aqua Snow Cover Monthly L3 Global 0.05Deg CMG, Version 5. <http://nsidc.org/data/docs/daac/modis_v5/myd10cm_modis_aqua_snow_monthly_global_0.05deg_cmg.gd.html> Accessed: May 9, 2011.
- Hamilton, J.M., D.J. Maddison and R.S.J. Tol, 2005. Effects of climate change on international tourism. *Climate Research*, 29:245–254.
- Hansen, J. and L. Nazarenko, 2004. Soot climate forcing via snow and ice albedos. *Proceedings of the National Academy of Sciences of the United States of America*, 101:423–428.
- Hansen, M.C., R.S. DeFries, J.R.G. Townshend, M. Carroll, C. Dimiceli and R.A. Sohlberg, 2003. Global percent tree cover at a spatial resolution of 500 meters: First results of the MODIS vegetation continuous fields

- algorithm. *Earth Interactions*, 7:15.
- Hansen, J., M. Sato, P. Kharecha, G. Russell, D.W. Lea and M. Siddall, 2007. Climate change and trace gases. *Philosophical Transactions of the Royal Society A-Mathematical Physical and Engineering Sciences*, 365:1925–1954.
- Hansen, J.C., B. Deutch and J.Ø. Odland, 2008. Dietary transition and contaminants in the Arctic; emphasis on Greenland. *Circumpolar Health Supplements*, 2, 91 pp.
- Harbeck, J.P., H. Eicken, T. Markus and S.V. Nghiem, 2008. Effects of a changing Arctic sea-ice cover upon on-line snow depth. *American Geophysical Union, Fall Meeting 2008: Abstract C41B-0506*.
- Hardiman, S.C., P.J. Kushner and J. Cohen, 2008. Investigating the ability of general circulation models to capture the effects of Eurasian snow cover on winter climate. *Journal of Geophysical Research-Atmospheres*, 113:D21123.
- Hardy, J.P., R.E. Davis, R. Jordan, W. Ni and C.E. Woodcock, 1998. Snow ablation modelling in a mature aspen stand of the boreal forest. *Hydrological Processes*, 12:1763–1778.
- Hartmann, B. and G. Wendler, 2005. Climatology of the winter surface temperature inversion in Fairbanks, Alaska. Paper presented at the 8th Conference on Polar Meteorology and Oceanography, pp. 1–7. American Meteorological Society.
- Hassi, J., M. Rytönen, J. Kotaniemi and H. Rintamäki, 2005. Impacts of cold climate on human heat balance, performance and health in circumpolar areas. *International Journal of Circumpolar Health*, 64:459–467.
- Hassler, S., 2005. The Health Condition in the Sami Population of Sweden, 1961–2002: Causes of Death and Incidences of Cancer and Cardiovascular Diseases. 81 pp. Umeå University, Umeå.
- Hassler, S., P. Sjölander, R. Johansson, H. Grönberg and L. Damber, 2004. Fatal accidents among reindeer herding Sami in Sweden. *International Journal of Circumpolar Health*, 63:384–388.
- Hedstrom, N.R. and J.W. Pomeroy, 1998. Measurements and modelling of snow interception in the boreal forest. *Hydrological Processes*, 12:1611–1625.
- Hegg, D.A., S.G. Warren, T.C. Grenfell, S.J. Doherty, T.V. Larson and A.D. Clarke, 2009. Source attribution of black carbon in Arctic snow. *Environmental Science & Technology*, 43:4016–4021.
- Heikinen, T., R. Österback, V. Peltola, T. Jartti and R. Vainionpää, 2008. Human metapneumovirus infections in children. *Emerging Infectious Diseases*, 14:101–106.
- Helfrich, S.R., D. McNamara, B.H. Ramsay, T. Baldwin and T. Kasheta, 2007. Enhancements to, and forthcoming developments in the Interactive Multisensor Snow and Ice Mapping System (IMS). *Hydrological Processes*, 21:1576–1586.
- Heliövaara, K. and M. Peltonen, 1999. Bark beetles in a changing environment. In: Hofgaard, A., J.P. Ball, K. Danell and T.V. Callaghan (Eds.). *Ecological Bulletins; Animal responses to global change in the north*, pp. 48–53. Munksgaard International Publishers, Copenhagen, Denmark.
- Helle, T. and I. Kojola, 2006. Population trends of semi-domesticated reindeer in Fennoscandia – evaluation of explanations. In: Forbes, B.C., M. Bølter, L. Müller-Wille, J. Hukkinen, F. Müller, N. Gunsley and Y. Konstantinov (Eds.). *Reindeer Management in Northernmost Europe: Linking Practical and Scientific Knowledge in Social-Ecological Systems*, pp. 319–340. Springer-Verlag.
- Helle, T. and I. Kojola, 2008. Demographics in an alpine reindeer herd: effects of density and winter weather. *Ecography*, 31:221–230.
- Helmig, D., J. Boulter, D. David, J.W. Birks, N.J. Cullen, K. Steffen, B.J. Johnson and S.J. Oltmans, 2002. Ozone and meteorological Summit, Greenland, boundary-layer conditions at during 3–21 June 2000. *Atmospheric Environment*, 36:2595–2608.
- Helmig, D., L. Ganzeveld, T. Butler and S.J. Oltmans, 2007. The role of ozone atmosphere-snow gas exchange on polar, boundary-layer tropospheric ozone – a review and sensitivity analysis. *Atmospheric Chemistry and Physics*, 6:1–16.
- Hennon, P., D. Amore, D. Wittwer, A. Johnson, P. Schaberg, G. Hawley, C. Beier, S. Sink and G. Juday, 2006. Climate Warming, Reduced snow, and freezing injury could explain the demise of yellow-cedar in southeast Alaska, USA. *World Resource Review*, 18:427–445.
- Hennon, P.E., D.V. D'Amore, D.T. Wittwer and J.P. Caouette, 2008. Yellow-cedar decline: conserving a climate-sensitive tree species as Alaska warms. Paper presented at the Integrated restoration of forested ecosystems to achieve multiresource benefits: proceedings of the 2007 national silviculture workshop, pp. 233–245. U.S. Department of Agriculture, Forest Service, Pacific Northwest Research Station, Portland, OR.
- Hines, K.M. and D.H. Bromwich, 2008. Development and testing of Polar Weather Research and Forecasting (WRF) model. Part I: Greenland ice sheet meteorology. *Monthly Weather Review*, 136:1971–1989.
- Hinkler, J., S.B. Pedersen, M. Rasch and B.U. Hansen, 2002. Automatic snow cover monitoring at high temporal and spatial resolution, using images taken by a standard digital camera. *International Journal of Remote Sensing*, 23:4669–4682.
- Hirashima, H., T. Ohata, Y. Kodama, H. Yabuki, N. Sato and A. Georgiadi, 2004. Nonuniform distribution of tundra snow cover in eastern Siberia. *Journal of Hydrometeorology*, 5:373–389.
- Hodson, A., A.M. Anesio, M. Tranter, A. Fountain, M. Osborn, J. Prisco, J. Laybourn-Parry and B. Sattler, 2008. Glacial ecosystems. *Ecological Monographs*, 78:41–67.
- Holko, L., K. Rubinstein, A. Shmakina and Z. Kostka, 2008. Simulation of snow cover characteristics in atmospheric general circulation models and evaluation of simple schemes for simulation of snow water equivalent. Paper presented at the Transport of Water, Chemicals and Energy in the Soil-Plant-Atmosphere System. 16th International Poster Day, pp. 205–212. Bratislava.
- Holland, M.M., J. Finnis and M.C. Serreze, 2006. Simulated Arctic Ocean freshwater budgets in the twentieth and twenty-first centuries. *Journal of Climate*, 19:6221–6242.
- Holsten, E.H., 1986. Preliminary evaluation of an *Ips perturbatus* outbreak in the Bonanza Creek Experimental Forest, Fairbanks, Alaska. *Biological Evaluation R10-86-1*, 8 pp. U.S. Department of Agriculture, Forest Service, Alaska Region, Anchorage, AK.
- Honrath, R.E. and D.A. Jaffe, 1992. The seasonal cycle of nitrogen-oxides in the Arctic troposphere at Barrow, Alaska. *Journal of Geophysical Research-Atmospheres*, 97:20615–20630.
- Honrath, R.E., S. Guo, M.C. Peterson, M.P. Dziobak, J.E. Dibb and M.A. Arsenault, 2000. Photochemical production of gas phase NO_x from ice crystal NO₃. *Journal of Geophysical Research-Atmospheres*, 105:24183–24190.
- Honrath, R.E., Y. Lu, M.C. Peterson, J.E. Dibb, M.A. Arsenault, N.J. Cullen and K. Steffen, 2002. Vertical fluxes of NO_x, HONO, and HNO₃ above the snowpack at Summit, Greenland. *Atmospheric Environment*, 36:2629–2640.
- Hörnfeldt, B., T. Hipkiss and U. Eklund, 2005. Fading out of vole and predator cycles? *Proceedings of the Royal Society B-Biological Sciences*, 272:2045–2049.
- Høy, T.T., E. Post, H. Meltofte, N.M. Schmidt and M.C. Forchhammer, 2007. Rapid advancement of spring in the High Arctic. *Current Biology*, 17:R449–R451.
- Humlum, O., A. Instanes and J.L. Sollid, 2003. Permafrost in Svalbard: a review of research history, climatic background and engineering challenges. *Polar Research*, 22:191–215.
- Iijima, Y., A.N. Fedorov, H. Park, K. Suzuki, H. Yabuki, T.C. Maximov and T. Ohata, 2010. Abrupt increases in soil temperatures following increased precipitation in a permafrost region, Central Lena River Basin, Russia. *Permafrost and Periglacial Processes*, 21:30–41.
- Jensen, R.A., J. Madsen, M. O'Connell, M.S. Wysz, H. Tømmervik and F. Mehlum, 2008. Prediction of the distribution of Arctic-nesting pink-footed geese under a warmer climate scenario. *Global Change Biology*, 14:1–10.
- Jernsletten, N., 1997. Sami traditional terminology: professional terms concerning salmon, reindeer and snow. In: Gaski, H. (Ed.). *Sami culture in a new era. The Norwegian Sami experience*, pp. 86–108. Davvi Girji OS, Karasjok.
- Johansson, C., V.A. Pohjola, C. Jonasson and T.V. Callaghan, 2011. Multi-decadal changes in snow characteristics in sub-Arctic Sweden. *Ambio*, 40:566–574.
- Johnson, K.P., J.D. Blum, G.J. Keeler and T.A. Douglas, 2008. Investigation of the deposition and emission of mercury in arctic snow during an atmospheric mercury depletion event. *Journal of Geophysical Research-Atmospheres*, 113:D17304.
- Jones, A.E., R. Weller, P.S. Anderson, H.W. Jacobi, E.W. Wolff, O. Schrems and H. Miller, 2001. Measurements of NO_x emissions from the Antarctic snowpack. *Geophysical Research Letters*, 28:1499–1502.
- Jones, G.S., J.M. Gregory, P.A. Stott, S.F.B. Tett and R.B. Thorpe, 2005. An AOGCM simulation of the climate response to a volcanic super-

- eruption. *Climate Dynamics*, 25:725–738.
- Jordan, R., 1991. A one-dimensional temperature model for a snow cover: Technical documentation for SNTHERM.89. Special Report, 91-16, U.S. Army Corps of Engineers, Cold Regions Research and Engineering Laboratory.
- Juday, G.P., 2009. Boreal forests and climate change. In: Goudie, A. and D. Cuff (Eds.). *Oxford Companion to Global Change*, pp. 75–84, Oxford University Press.
- Juday, G.P., V. Barber, P. Duffy, H. Linderholm, S. Rupp, S. Sparrow, E. Vaganov and J. Yarie, 2005. Forests, land management, and agriculture. In: *Arctic Climate Impact Assessment*, pp. 781–862, Cambridge University Press.
- Kallenborn, R., J. Fick, R. Lindberg, M. Moe, K.M. Nielsen, M. Tysklind and T. Vasskog, 2008. Pharmaceutical residues in northern European environments: consequences and perspectives. In: Kummerer, K. (Ed.). *Pharmaceuticals in the Environment: Sources, Fate, Effects and Risks*, Third Edition, pp. 61–74, Springer-Verlag.
- Kama, J.-P., J. Lemmetyinen, M. Hallikainen, P. Lahtinen, J. Pulliainen and M. Takala, 2007. Operational snow map production for whole Eurasia using microwave radiometer and ground-based observations. *Proc. IGARSS 2007*, pp. 1456–1459.
- Kappen, L. and F. Valladares, 2007. Opportunistic growth and desiccation tolerance: the ecological success of poikilohydrous autotrophs. In: Pugnaire, F.I. and F. Valladares (Eds.). *Functional Plant Ecology*, pp. 7–65, CRC Press.
- Kappen, L., M. Sommerkorn and B. Schroeter, 1995. Carbon acquisition and water relations of lichens in polar regions – Potentials and limitations. *Lichenologist*, 27:531–545.
- Kattsov, V.M., E. Källén, H. Cattle, J. Christensen, H. Drange, I. Hanssen-Bauer, T. Jóhannessen, I. Karol, J. Räisänen, G. Svensson and S. Vavulin, 2005. Future climate change: Modeling and scenarios for the Arctic. In: *Arctic Climate Impact Assessment – Scientific Report*, pp. 99–150, Cambridge University Press.
- Kattsov, V.M., J.E. Walsh, W.L. Chapman, V.A. Govorkova, T.V. Pavlova and X.D. Zhang, 2007. Simulation and projection of arctic freshwater budget components by the IPCC AR4 global climate models. *Journal of Hydrometeorology*, 8:571–589.
- Kausrud, K.L., A. Mysterud, H. Steen, J.O. Vik, E. Østbye, B. Cazelles, E. Framstad, A.M. Eikeset, I. Mysterud, T. Solhøy and N.C. Stenseth, 2008. Linking climate change to lemming cycles. *Nature*, 456:93–97.
- Kelly, R.E., A.T. Chang, L. Tsang and J.L. Foster, 2003. A prototype AMSR-E global snow area and snow depth algorithm. *IEEE Transactions on Geoscience and Remote Sensing*, 41:230–242.
- Kerkhoven, E. and T.Y. Gan, 2005. Modelling hydrological responses of the Athabasca River basin to climate change by the Modified ISBA Land Surface Scheme. *Regional Hydrological Impacts of Climatic Change - Hydroclimatic Variability*, 296:89–101.
- Key, J.R. and A.C.K. Chan, 1999. Multidecadal global and regional trends in 1000 mb and 500 mb cyclone frequencies. *Geophysical Research Letters*, 26:2053–2056.
- Key, J., M. Drinkwater and J. Ukita, 2007. *Integrated Global Observing Strategy Cryosphere Theme Report*. 1405, 100 pp. Geneva.
- Khan, V., L. Holko, K. Rubinstein and M. Breiling, 2008. Snow cover characteristics over the main Russian river basins as represented by reanalyses and measured data. *Journal of Applied Meteorology and Climatology*, 47:1819–1833.
- Kharuk, V.I., K.J. Ranson, V.V. Kuz'michev and S. Im, 2003. Landsat-based analysis of insect outbreaks in southern Siberia. *Canadian Journal of Remote Sensing*, 29:286–297.
- Kharuk, V.I., K.J. Ranson, A.G. Kozuhovskaya, Y.P. Kondakov and I.A. Pestunov, 2004. NOAA/AVHRR satellite detection of Siberian silkmouth outbreaks in eastern Siberia. *International Journal of Remote Sensing*, 25:5543–5555.
- Kharuk, V.I., K.J. Ranson and E.V. Fedotova, 2007. Spatial pattern of Siberian silkmouth outbreak and taiga mortality. *Scandinavian Journal of Forest Research*, 22:531–536.
- Kilpeläinen, A., H. Gregow, H. Strandman, S. Kellomäki, A. Venalainen and H. Peltola, 2010. Impacts of climate change on the risk of snow-induced forest damage in Finland. *Climatic Change*, 99:193–209.
- King, J.C., J.W. Pomeroy, D.M. Gray, C. Fierz, P.M.B. Föhn, R.J. Harding, R.E. Jordan, E. Martin and C. Plüss, 2008. Snow-atmosphere energy and mass balance. In: Armstrong, R.L. and E. Brun (Eds.). *Snow and Climate*, pp. 70–124, Cambridge University Press.
- Kitaev, L., E. Førland, V. Razuvaev, O.E. Tveito and O. Krueger, 2005. Distribution of snow cover over Northern Eurasia. *Nordic Hydrology*, 36:311–319.
- Kitaev, L.M., V.N. Razuvaev, R. Heino and E. Forland, 2006. Duration of snow cover over northern Europe. [in Russian with English summary]. *Russian Meteorology and Hydrology*:95–100.
- Kleffmann, J. and P. Wiesen, 2008. Technical Note: Quantification of interferences of wet chemical HONO LOPAP measurements under simulated polar conditions. *Atmospheric Chemistry and Physics*, 8:6813–6822.
- Kohler, J. and R. Aanes, 2004. Effect of winter snow and ground-icing on a Svalbard reindeer population: Results of a simple snowpack model. *Arctic Antarctic and Alpine Research*, 36:333–341.
- Kohler, J., O. Brandt, M. Johansson and T. Callaghan, 2006. A long-term Arctic snow depth record from Abisko, northern Sweden, 1913–2004. *Polar Research*, 25:91–113.
- Kraemer, L.D., J.E. Berner and C.M. Furgal, 2005. The potential impact of climate on human exposure to contaminants in the Arctic. *International Journal of Circumpolar Health*, 64:498–508.
- Krenke, A., 1998, updated 2004. Former Soviet Union hydrological snow surveys, 1966–1996. Edited by NSIDC. Boulder, CO: National Snow and Ice Data Center/World Data Center for Glaciology. Digital media. <http://nsidc.org/data/g01170.html>. Accessed: May 10, 2011.
- Krupnik, I. and G.C. Ray, 2007. Pacific walruses, indigenous hunters, and climate change: Bridging scientific and indigenous knowledge. *Deep-Sea Research, Part II - Topical Studies in Oceanography*, 54:2946–2957.
- Krupnik, I., H. Huntington, C. Koonooka and G. Noongwook (Eds.), 2004. *Watching ice and weather our way*. 207 pp. Arctic Studies Center, Smithsonian Institution & Savoonga Whaling Captains Association. Savoonga, Alaska & Washington, D.C.
- Kuchment, L.S., P.Y. Romanov, A.N. Gelfan and V.N. Demidov, 2009. Construction of fields of snow cover characteristics using the satellite information and the models of snowpack formation. *Issledovaniya Zemli iz Kosmosa [Earth Research from Space]*, 4:47–56.
- Kumpula, J., 2001. Productivity of the semi-domesticated reindeer (*Rangifer tarandus tarandus* L.) stock and carrying capacity of pastures in Finland during 1960 – 1990s. *Acta Universitatis Oulensis, A* 350:1–44.
- Kumpula, J. and A. Colpaert, 2003. Effects of weather and snow conditions on reproduction and survival of semi-domesticated reindeer (*R. t. tarandus*). *Polar Research*, 22:225–233.
- Kumpula, J., A. Colpaert and M. Anttonen, 2007. Does forest harvesting and linear infrastructure change the usability value of pastureland for semi-domesticated reindeer (*Rangifer tarandus tarandus*)? *Annales Zoologici Fennici*, 44:161–178.
- Laidler, G.J., J.D. Ford, W.A. Gough, T. Ikummaq, A.S. Gagnon, S. Kowal, K. Qrunnut and C. Irngaut, 2009. Travelling and hunting in a changing Arctic: assessing Inuit vulnerability to sea ice change in Igloodik, Nunavut. *Climatic Change*, 94:363–397.
- Lamb, H.H., 1955. 2-way relationship between the snow or ice limit and 1000–500 Mb thicknesses in the overlying atmosphere. *Quarterly Journal of the Royal Meteorological Society*, 81:172–189.
- Larsen, K.S., A. Ibrom, S. Jonasson, A. Michelsen and C. Beier, 2007a. Significance of cold-season respiration and photosynthesis in a subarctic heath ecosystem in Northern Sweden. *Global Change Biology*, 13:1498–1508.
- Larsen, K.S., P. Grogan, S. Jonasson and A. Michelsen, 2007b. Dynamics and microbial dynamics in two subarctic ecosystems during winter and spring thaw: Effects of increased snow depth. *Arctic, Antarctic and Alpine Research*, 39:268–276.
- Lazar, B. and M. Williams, 2008. Climate change in western ski areas: Potential changes in the timing of wet avalanches and snow quality for the Aspen ski area in the years 2030 and 2100. *Cold Regions Science and Technology*, 51:219–228.
- Leathers, D.J. and D.A. Robinson, 1993. The association between extremes in North American snow cover extent and United States temperatures. *Journal of Climate*, 6:1345–1355.
- Leathers, D.J., A.W. Ellis and D.A. Robinson, 1995. Characteristics of temperature depressions associated with snow cover across the Northeast United States. *Journal of Applied Meteorology*, 34:381–390.
- Lee, Y.H. and L. Mahr, 2004. An evaluation of snowmelt and sublimation over short vegetation in land surface modelling. *Hydrological Processes*, 18:3543–3557.
- Lehning, M., P. Bartelt, B. Brown, T. Russi, U. Stöckli and M. Zimmerli,

1999. SNOWPACK model calculations for avalanche warning based upon a new network of weather and snow stations. *Cold Regions Science and Technology*, 30:145–157.
- Lemelin, R.H., 2005. Wildlife tourism at the edge of the chaos, complex interactions between humans and polar bears in Churchill, Manitoba. In: F. Berkes, R. Huebert, F. H. M. Manseau and A. Diduck (Eds.). *Breaking Ice: Renewable Resource and Ocean Management in the Canadian North*, University of Calgary Press, Calgary, Alberta.
- Lemke, P., J. Ren, R.B. Alley, I. Allison, J. Carrasco, G. Flato, Y. Fujii, G. Kaser, P. Mote, R.H. Thomas and T. Zhang, 2007. Observations: changes in snow, ice and frozen ground. In: Solomon, S., D. Qin, M. Manning, Z. Chen, M. Marquis, K.B. Averyt, M. Tignor and H.L. Miller (Eds.). *Climate Change 2007: The Physical Science Basis. Contribution of Working Group I to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change*, Cambridge University Press.
- Lemmetyinen, J., C. Derksen, J. Pulliainen, W. Strapp, P. Toose, A. Walker, S. Tauriainen, J. Pihlflyckt, J.P. Kärnä and M.T. Hallikainen, 2009. A comparison of airborne microwave brightness temperatures and snowpack properties across the boreal forests of Finland and western Canada. *IEEE Transactions on Geoscience and Remote Sensing*, 47:965–978.
- Liao, W., A.T. Case, J. Mastromarino, D. Tan and J.E. Dibb, 2006. Observations of HONO by laser-induced fluorescence at the South Pole during ANTICI 2003. *Geophysical Research Letters*, 33:L09810.
- Lied, K. and U. Domaas, 2000. Avalanche hazard assessment in Nunavik and on Cote-Nord, Québec, Canada. Norwegian Geotechnical Institute report, 20001130-1, 1130–1131 pp.
- Link, T.E., D. Marks and J.P. Hardy, 2004. A deterministic method to characterize canopy radiative transfer properties. *Hydrological Processes*, 18:3583–3594.
- Liston, G.E., R.B. Haehnel, M. Sturm, C.A. Hiemstra, S. Berezovskaya and R.D. Tabler, 2007. Instruments and methods simulating complex snow distributions in windy environments using SnowTran-3D. *Journal of Glaciology*, 53:241–256.
- Lloyd, A.H. and A.G. Bunn, 2007. Responses of the circumpolar boreal forest to 20th century climate variability. *Environmental Research Letters*, 2:045013.
- Loeng, H., K. Brander, E. Carmack, S. Denisenko, K. Drinkwater, B. Hansen, K. Kovacs, P. Livingston, F. McLaughlin and E. Sakshaug, 2005. Marine systems. In: *Arctic Climate Impact Assessment*, pp. 453–538, Cambridge University Press.
- Ma, Y., S. Chen, F. Hua, H.L. Wei and D.H. Bromwich, 2008. Evaluation of a regional climate model for atmospheric simulation over Arctic river basins. *Chinese Journal of Oceanology and Limnology*, 26:425–433.
- Macdonald, R.W., T. Harner and J. Fyfe, 2005. Recent climate change in the Arctic and its impact on contaminant pathways and interpretation of temporal trend data. *Science of the Total Environment*, 342:5–86.
- Mackes, K.H. and D.L. Lynch, 2001. The effect of aspen wood characteristics and properties on utilization. Paper presented at Proceedings of the symposium on sustaining aspen in western landscapes, pp. 429–440. U.S. Forest Service Proceedings RMRS-P-18, Grand Junction, Colorado, USA.
- Madsen, J., M. Tamstorf, M. Klaassen, N. Eide, C. Glahder, F. Rigét, H. Nyegaard and F. Cottaar, 2007. Effects of snow cover on the timing and success of reproduction in high-Arctic pink-footed geese *Anser brachyrhynchus*. *Polar Biology*, 30:1363–1372.
- Madsen, J., I. Tombre and N.E. Eide, 2009. Effects of disturbance on geese in Svalbard: implications for regulating increasing tourism. *Polar Research*, 28:376–389.
- Magga, O.H., 2006. Diversity in Saami terminology for reindeer, snow, and ice. *International Social Science Journal*, 58:25–34.
- Mäkinen, T.M., 2007. Human cold exposure, adaptation, and performance in high latitude environments. *American Journal of Human Biology*, 19:155–164.
- Marsh, P., J.W. Pomeroy and N. Neumann, 1997. Sensible heat flux and local advection over a heterogeneous landscape at an Arctic tundra site during snowmelt. *Annals of Glaciology*, 25:132–136.
- McCarthy, J.J., M.L. Martello, R. Corell, N.E. Selin, S. Fox, G. Hovelsrud-Broda, S.D. Mathiesen, C. Polsky, H. Selin and N.J.C. Tyler, 2005. Climate change in the context of multiple stressors and resilience. In: *Arctic Climate Impact Assessment*, pp. 945–988, Cambridge University Press.
- McClelland, J.W., R.M. Holmes, B.J. Peterson and M. Stieglitz, 2004. Increasing river discharge in the Eurasian Arctic: Consideration of dams, permafrost thaw, and fires as potential agents of change. *Journal of Geophysical Research-Atmospheres*, 109:D18102.
- McCullough, D.G., R.A. Werner and D. Neumann, 1998. Fire and insects in northern and boreal forest ecosystems of North America. *Annual Review of Entomology*, 43:107–127.
- McKay, G.A. and D.M. Gray, 1981. The distribution of snow cover. In: Gray, D.M. and D.H. Male (Eds.). *Handbook of Snow*, pp. 153–190, Pergamon Press.
- Mech, L.D., 2004. Is climate change affecting wolf populations in the High Arctic? *Climatic Change*, 67:87–93.
- Meehl, G.A., C. Covey, T. Delworth, M. Latif, B. McAvaney, J.F.B. Mitchell, R.J. Stouffer and K.E. Taylor, 2007. The WCRP CMIP3 multimodel dataset - A new era in climate change research. *Bulletin of the American Meteorological Society*, 88:1383–1394.
- Mekis, E. and W.D. Hogg, 1999. Rehabilitation and analysis of Canadian daily precipitation time series. *Atmosphere-Ocean*, 37:53–85.
- Melnikov, S.A., C.V. Lasov, O.V. Rishov, A.N. Gorshkov and A.I. Kuzin, 1994. Zones of relatively enhanced contamination levels in the Russian Arctic seas. *Arctic Research of the United States*, 8:277–283.
- Meltofte, H., T.R. Christensen, B. Elberling, M.C. Forchhammer and M. Rasch, 2008. *High-Arctic Ecosystem Dynamics in a Changing Climate*. 563 pp. Academic Press.
- Meshcherskaya, A.V., N.A. Boldyreva and N.D. Shapaeva, 1982. Mean regional productive soil moisture storage and snow cover depth (statistical analysis and examples of use). 243 pp. Gidrometeoizdat, Leningrad.
- Meteorological Service of Canada, 2000. Canadian Snow Data CD-ROM (digital media). CRYSYS Project, Climate Processes and Earth Observation Division, Meteorological Service of Canada, Downsview, Ontario (<http://ccrp.tor.ec.gc.ca/pub/RBrown>).
- Meyer, A., K. Ladefoged, P. Poulsen and A. Koch, 2008. Population-based survey of invasive bacterial diseases, Greenland, 1995–2004. *Emerging Infectious Diseases*, 14:76–79.
- Miller, F.L. and S.J. Barry, 2009. Long-term control of Peary caribou numbers by unpredictable, exceptionally severe snow or ice conditions in a non-equilibrium grazing system. *Arctic*, 62:175–189.
- Min, S.K., X.B. Zhang and F. Zwiers, 2008. Human-induced arctic moistening. *Science*, 320:518–520.
- Moen, J., 2008. Climate change: Effects on the ecological basis for reindeer husbandry in Sweden. *Ambio*, 37:304–311.
- Molotch, N.P., P.D. Blanken, M.W. Williams, A.A. Turnipseed, R.K. Monson and S.A. Margulis, 2007. Estimating sublimation of intercepted and sub-canopy snow using eddy covariance systems. *Hydrological Processes*, 21:1567–1575.
- Moody, E.G., M.D. King, C.B. Schaaf and S. Platnick, 2008. MODIS-derived spatially complete surface albedo products: Spatial and temporal pixel distribution and zonal averages. *Journal of Applied Meteorology and Climatology*, 47:2879–2894.
- Morin, S., J. Savarino, M.M. Frey, N. Yan, S. Bekki, J.W. Bottenheim and J.M.F. Martins, 2008. Tracing the origin and fate of NO_x in the Arctic atmosphere using stable isotopes in nitrate. *Science*, 322:730–732.
- Näyhä, S., 2005. Environmental temperature and mortality. *International Journal of Circumpolar Health*, 64:451–458.
- Newark, M.J., L.E. Welsh, R.J. Morris and W.V. Dnes, 1989. Revised ground snow loads for the 1990 National Building Code of Canada. *Canadian Journal of Civil Engineering*, 16:267–278.
- Ni, W.G., X.W. Li, C.E. Woodcock, J.L. Roujean and R.E. Davis, 1997. Transmission of solar radiation in boreal conifer forests: Measurements and models. *Journal of Geophysical Research-Atmospheres*, 102:29555–29566.
- Nickels, S., C. Furgal, M. Buell and H. Moquin, 2005. Unikkaaqtigitiit – Putting the human face on climate change: Perspectives from Inuit in Canada. 129 pp. Joint publication of Inuit Tapiriit Kanatami, Nasivvik Centre for Inuit Health and Changing Environments at Université Laval and the Ajunnginiq Centre at the National Aboriginal Health Organization, Ottawa.
- Nobrega, S. and P. Grogan, 2007. Deeper snow enhances winter respiration from both plant-associated and bulk soil carbon pools in birch hummock tundra. *Ecosystems*, 10:419–431.
- Notzke, C., 1999. Indigenous tourism development in the Arctic. *Annals of Tourism Research*, 26:55–76.
- NRC, 2008. Potential impacts of climate change on U.S. transportation. Transportation Research Board special report 290: 298 pp. Committee

- on Climate Change and U.S. Transportation, Transportation Research Board and Division of Earth and Life Studies, National Research Council of the National Academies.
- Nuttall, M., F. Berkes, B.C. Forbes, G. Kofinas, T. Vlassova and G. Wenzel, 2005. Hunting, herding, fishing and gathering: indigenous peoples and renewable resource use in the Arctic. In: *Arctic Climate Impact Assessment*, pp. 649–690, Cambridge University Press.
- Oncley, S.P., M. Buhr, D.H. Lenschow, D. Davis and S.R. Semmer, 2004. Observations of summertime NO fluxes and boundary-layer height at the South Pole during ISCAT 2000 using scalar similarity. *Atmospheric Environment*, 38:5389–5398.
- Overland, J.E. and P.S. Guest, 1991. The arctic snow and air-temperature budget over sea ice during winter. *Journal of Geophysical Research-Oceans*, 96:4651–4662.
- Pagnan, J., 2003. Climate change impact on Arctic tourism- a preliminary review. Paper presented at Climate Change and Tourism, 17 pp. World Tourism Organization, Djerba, Tunisia, April 2003.
- Parajka, J. and G. Blöschl, 2008. Spatio-temporal combination of MODIS images - potential for snow cover mapping. *Water Resources Research*, 44:13.
- Parkinson, A.J., 2008. The International Polar Year, 2007–2008, an opportunity to focus on infectious diseases in Arctic regions. *Emerging Infectious Diseases*, 14:1–3.
- Parkinson, A.J. and J.C. Butler, 2005. Potential impacts of climate change on infectious diseases in the Arctic. *International Journal of Circumpolar Health*, 64:478–486.
- Pearce, T.D., J.D. Ford, G.J. Laidler, B. Smit, F. Duerden, M. Allarut, M. Andrachuk, S. Baryluk, A. Dialla, P. Elee, A. Goose, T. Ikummaq, E. Joamie, F. Kataoyak, E. Loring, S. Meakin, S. Nickels, K. Shappa, J. Shirley and J. Wandel, 2009. Community collaboration and climate change research in the Canadian Arctic. *Polar Research*, 28:10–27.
- Peschanskiy, I.S., 1967. *Ledovedenie i ledotekhnika* [Ice research and ice technology] [in Russian]. 462 pp. Gidrometeoizdat, Leningrad.
- Petersen, L.R. and J.T. Roehrig, 2001. West Nile virus: A reemerging global pathogen. *Emerging Infectious Diseases*, 7:611–614.
- Peterson, M.C. and R.E. Honrath, 2001. Observations of rapid photochemical destruction of ozone in snowpack interstitial air. *Geophysical Research Letters*, 28:511–514.
- Phoenix, G.K. and J.A. Lee, 2004. Predicting impacts of Arctic climate change: Past lessons and future challenges. *Ecological Research*, 19:65–74.
- Piot, M. and R. von Glasow, 2008. The potential importance of frost flowers, recycling on snow, and open leads for ozone depletion events. *Atmospheric Chemistry and Physics*, 8:2437–2467.
- Pomeroy, J.W. and E. Brun, 2001. Physical properties of snow. In: Jones, H.G. (Ed.). *Snow Ecology*, 378 pp. Cambridge University Press.
- Pomeroy, J.W. and L. Li, 2000. Prairie and arctic areal snow cover mass balance using a blowing snow model. *Journal of Geophysical Research-Atmospheres*, 105:26619–26634.
- Pomeroy, J.W., D.S. Bewley, R.L.H. Essery, N.R. Hedstrom, T. Link, R.J. Granger, J.E. Sicart, C.R. Ellis and J.R. Janowicz, 2006. Shrub tundra snowmelt. *Hydrological Processes*, 20:923–941.
- Pomeroy, J.W., D.M. Gray, T. Brown, N.R. Hedstrom, W.L. Quinton, R.J. Granger and S.K. Carey, 2007. The cold regions hydrological process representation and model: a platform for basing model structure on physical evidence. *Hydrological Processes*, 21:2650–2667.
- Pomeroy, J.W., D. Marks, T. Link, C. Ellis, J. Hardy, A. Rowlands and R. Granger, 2009. The impact of coniferous forest temperature on incoming longwave radiation to melting snow. *Hydrological Processes*, 23:2513–2525.
- Popova, V.V., 2004. Structure of multi-year variations of the snow cover depth in North Eurasia. [in Russian with English summary]. *Russian Meteorology and Hydrology*, 8:78–88.
- Popova, V., 2007. Winter snow depth variability over northern Eurasia in relation to recent atmospheric circulation changes. *International Journal of Climatology*, 27:1721–1733.
- Post, E., M.C. Forchhammer, M.S. Bret-Harte, T.V. Callaghan, T.R. Christensen, B. Elberling, A.D. Fox, O. Gilg, D.S. Hik, T.T. Hoye, R.A. Ims, E. Jeppesen, D.R. Klein, J. Madsen, A.D. McGuire, S. Rysgaard, D.E. Schindler, I. Stirling, M.P. Tamstorf, N.J.C. Tyler, R. van der Wal, J. Welker, P.A. Wookey, N.M. Schmidt and P. Aastrup, 2009. Ecological dynamics across the Arctic associated with recent climate change. *Science*, 325:1355–1358.
- Pruitt, W.O., Jr., 1984. Snow and living things. In: Olson, R., R. Hastings and F. Geddes (Eds.). *Northern Ecology and Resource Management. Memorial essays honouring Don Gill*, pp. 51–77, University of Alberta Press.
- Qu, X. and A. Hall, 2006. Assessing snow albedo feedback in simulated climate change. *Journal of Climate*, 19:2617–2630.
- Quinn, P.K., G. Shaw, E. Andrews, E.G. Dutton, T. Ruoho-Airola and S.L. Gong, 2007. Arctic haze: current trends and knowledge gaps. *Tellus Series B-Chemical and Physical Meteorology*, 59:99–114.
- Radionov, V. and F. Fetterer, 2003. Meteorological data from the Russian Arctic, 1961–2000. National Snow and Ice Data Center, Boulder, Colorado. Digital media. <http://nsidc.org/data/g02141.html>.
- Radionov, V.F., N.N. Bryazgin and E.I. Aleksandrov, 1996. The Snow Cover of the Arctic Basin. *Gidrometeoizdat*, St. Petersburg. 124 pp. [in Russian]. (English translation available from Polar Science Center, University of Washington, Seattle, WA 98105; Tech. Rep. APL-UW, TR 9701).
- Radionov, V.F., E.I. Aleksandrov, V.R. Bayborodova, N.N. Bryazgin and A.A. Dement'ev, 2004a. Long-term changes of snow cover period in the Arctic. [in Russian with English summary]. *Data of Glaciological Studies*, 97:136–142.
- Radionov, V.F., Ye.I. Aleksandrov, P.N. Svyashchennikov and F. Fetterer, 2004b. Daily precipitation sums at coastal and island Russian Arctic stations, 1940–1990. National Snow and Ice Data Center, Boulder, Colorado. Digital media. <http://nsidc.org/data/g02164.html>. Accessed: May 10, 2011.
- Räisänen, J., 2007. Warmer climate: less or more snow? *Climate Dynamics*, 30:307–319.
- Ramage, J.M., J.D. Apgar, R.A. McKenney and W. Hanna, 2007. Spatial variability of snowmelt timing from AMSR-E and SSNM passive microwave sensors, Pelly River, Yukon Territory, Canada. *Hydrological Processes*, 21:1548–1560.
- Ramsay, B.H., 1998. The interactive multisensor snow and ice mapping system. *Hydrological Processes*, 12:1537–1546.
- Randall, D.A., R.A. Wood, S. Bony, R. Colman, T. Fichet, J. Fyfe, V. Kattsov, A. Pitman, J. Shukla, J. Srinivasan, J. Stouffer, A. Sumi and K.E. Taylor, 2007. Climate models and their evaluation. In: Solomon, S., D. Qin, M. Manning, Z. Chen, M. Marquis, K.B. Averyt, M. Tignor and H.L. Miller (Eds.). *Climate Change 2007: The Physical Science Basis. Contribution of Working Group I to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change*, pp. 589–662, Cambridge University Press.
- Rauscher, S.A., J.S. Pal, N.S. Diffenbaugh and M.M. Benedetti, 2008. Future changes in snowmelt-driven runoff timing over the western US. *Geophysical Research Letters*, 35:L16703.
- Rawlins, M.A., K.C. McDonald, S. Frolking, R.B. Lammers, M. Fahnestock, J.S. Kimball and C.J. Vorosmarty, 2005. Remote sensing of snow thaw at the pan-Arctic scale using the SeaWinds scatterometer. *Journal of Hydrology*, 312:294–311.
- Rawlins, M.A., M.C. Serreze, R. Schroeder, X.D. Zhang and K.C. McDonald, 2009. Diagnosis of the record discharge of Arctic-draining Eurasian rivers in 2007. *Environmental Research Letters*, 4:045011.
- Rawlins, M.A., M. Steele, M.M. Holland and 27 others, 2010. Analysis of the Arctic system for freshwater cycle intensification: Observations and expectations. *Journal of Climate*, 23:5715–5737.
- Razuvaev, V.N. and O.N. Bulygina, 2006. Variations in snow characteristics over the Russian territory in recent decades. Paper presented at 1st Asia CliC Symposium, pp. 35–38. Yokohama, Japan.
- Reba, M.L., D. Marks, T. Link and J. Pomeroy, 2009. Inter-annual comparison of measured turbulent fluxes over snow at a wind-sheltered and a wind-exposed site using eddy covariance. Paper presented at Hydrology in Mountain Regions: Observations, Processes and Dynamics, pp. 34–40. IAHS Publication, Perugia, July 2007.
- Rees, A., C. Derksen, M. English, A. Walker and C. Duguay, 2006. Uncertainty in snow mass retrievals from satellite passive microwave data in lake-rich high-latitude environments. *Hydrological Processes*, 20:1019–1022.
- Rees, A., J. Lemmetyinen, C. Derksen, J. Pulliainen and M. English, 2010. Observed and modelled effects of ice lens formation on passive microwave brightness temperatures over snow covered tundra. *Remote Sensing of Environment*, 114:116–126.
- Rennett, K.J., G. Roe, J. Putkonen and C.M. Bitz, 2009. Soil thermal and ecological impacts of rain on snow events in the Circumpolar Arctic. *Journal of Climate*, 22:2302–2315.
- Richmond, C.A.M. and N.A. Ross, 2009. The determinants of First Nation

- and Inuit health: A critical population health approach. *Health & Place*, 15:403–411.
- Ridley, B.A. and J.J. Orlando, 2003. Active nitrogen in surface ozone depletion events at alert during spring 1998. *Journal of Atmospheric Chemistry*, 44:1–22.
- Ridley, B., J. Walega, D. Montzka, F. Grahek, E. Atlas, F. Flocke, V. Stroud, J. Deary, J.E. Haugen, D. Jacob, C.G. Jones, M. Koltzow, R. Laprise, A.H. Lynch, S. Pfeifer, M.C. Serreze, M.J. Shaw, M. Tjernstrom, K. Wyser and M. Zagar, 2000. Is the Arctic surface layer a source and sink of NO_x in winter/spring? *Journal of Atmospheric Chemistry*, 36:1–22.
- Rinke, A., K. Dethloff, J.J. Cassano, J.H. Christensen, J.A. Curry, P. Du, E. Girard, J.E. Haugen, D. Jacob, C.G. Jones, M. Koltzow, R. Laprise, A.H. Lynch, S. Pfeifer, M.C. Serreze, M.J. Shaw, M. Tjernstrom, K. Wyser and M. Zagar, 2006. Evaluation of an ensemble of Arctic regional climate models: spatiotemporal fields during the SHEBA year. *Climate Dynamics*, 26:459–472.
- Riseth, J.Å., 2003. Sámi reindeer management in Norway: Modernization challenges and conflicting strategies. In: Jentoft, S., H. Minde and R. Nielsen (Eds.). *Indigenous peoples: Resource management and global rights*, pp. 229–247, Eburon, Delft, Netherlands.
- Riseth, J.Å. and L. Oksanen, 2007. Ressursøkonomiske og økologiske perspektiver på grenseoverskridende reindrift. [in Norwegian]. In: Broderstad, E.G., E. Niemi and I. Sommerseth (Eds.). *Grenseoverskridende reindrift før og etter 1905*, pp. 93–113, Universitetet i Tromsø, Tromsø.
- Riseth, J.Å., H. Tømmervik, E. Helander-Renvall, V. Pohjola, N.T. Labba, N. Labba, E.A. Niia, H. Kuhmunen, A. Schanche, C. Jonasson, C. Johansson, L.-E. Sarri, J.W. Bjerke, E. Malnes and T.V. Callaghan, 2011. Sámi traditional ecological knowledge as a guide to science: snow, ice and reindeer pasture facing climate change. *Polar Record*, 47: 202–217.
- Robinson, D.A., K.F. Dewey and R.R. Heim, 1993. Global snow cover monitoring - an update. *Bulletin of the American Meteorological Society*, 74:1689–1696.
- Robinson, C.H., P.A. Wookey, J.A. Lee, T.V. Callaghan and M.C. Press, 1998. Plant community responses to simulated environmental change at a high arctic polar semi-desert. *Ecology*, 79:856–866.
- Robinson, D.A., J.D. Tarpley and B. Ramsay, 1999. Transition from NOAA weekly to daily Hemispheric snow charts. Paper presented at 10th Symposium on Global Change, pp. 487–490. American Meteorological Society, Dallas, TX.
- Robinson, R.A., H.Q.P. Crick, J.A. Learmonth, I.M.D. Maclean, C.D. Thomas, F. Bairlein, M.C. Forchhammer, C.M. Francis, J.A. Gill, B.J. Godley, J. Harwood, G.C. Hays, B. Huntley, A.M. Hutson, G.J. Pierce, M.M. Rehfish, D.W. Sims, M.B. Santos, T.H. Sparks, D.A. Stroud and M.E. Visser, 2009. Travelling through a warming world: climate change and migratory species. *Endangered Species Research*, 7:87–99.
- Rogers, J.C. and H. van Loon, 1979. Seesaw in winter temperatures between Greenland and northern Europe. Part II: Some oceanic and atmospheric effects in middle and high-latitudes. *Monthly Weather Review*, 107:509–519.
- Romanov, P., G. Gutman and I. Csiszar, 2000. Automated monitoring of snow cover over North America with multispectral satellite data. *Journal of Applied Meteorology*, 39:1866–1880.
- Romanov, P., D. Tarpley, G. Gutman and T. Carroll, 2003. Mapping and monitoring of the snow cover fraction over North America. *Journal of Geophysical Research-Atmospheres*, 108:8619.
- Roturier, S. and M. Roue, 2009. Of forest, snow and lichen: Sámi reindeer herders' knowledge of winter pastures in northern Sweden. *Forest Ecology and Management*, 258:1960–1967.
- Rowell, D.P., 2006. A demonstration of the uncertainty in projections of UK climate change resulting from regional model formulation. *Climatic Change*, 79:243–257.
- Ruong, I., 1964. Jåhkakaska sameby – Jåhkakaska Sámi village. [in Swedish]. In: *Svenska Landsmål och Svenskt Folkliv*.
- Rutter, N., R. Essery, J. Pomeroy and 48 others, 2009. Evaluation of forest snow processes models (SnowMIP2). *Journal of Geophysical Research-Atmospheres*, 114:D06111.
- Ruuhela, R., L. Hiltunen, A. Venäläinen, P. Pirinen and T. Partonen, 2009. Climate impact on suicide rates in Finland from 1971 to 2003. *International Journal of Biometeorology*, 53:167–175.
- Ryd, Y., 2001. Snö : renskötarens Johan Rassa berättar. [Snow - the reindeer herder Johan Rassa tells]. [in Swedish]. pp. 328. Ordfront förlag, Stockholm, Sweden.
- Saxe, H., M.G.R. Cannell, B. Johnsen, M.G. Ryan and G. Vourlitis, 2001. Tree and forest functioning in response to global warming. *New Phytologist*, 149:369–399.
- Schmidt, N.M., C. Baittinger and M.C. Forchhammer, 2006. Reconstructing century-long snow regimes using estimates of high arctic *Salix arctica* radial growth. *Arctic Antarctic and Alpine Research*, 38:257–262.
- Schramm, I., J. Boike, W.R. Bolton and L.D. Hinzman, 2007. Application of TopoFlow, a spatially distributed hydrological model, to the Imnavait Creek watershed, Alaska. *Journal of Geophysical Research-Biogeosciences*, 112:G04s46.
- Semikhatova, O.A., T.V. Gerasimenko and T.I. Ivanova, 1992. Photosynthesis respiration and growth of plants in the Soviet Arctic. In: Chapin III, F.S., R.L. Jefferies, J.F. Reynolds, G.R. Shaver and J. Svoboda (Eds.). *Arctic Ecosystems in a Changing Climate: an ecophysiological perspective*, pp. 169–192, Academic Press.
- Serreze, M.C. and A.J. Etringer, 2003. Precipitation characteristics of the Eurasian Arctic drainage system. *International Journal of Climatology*, 23:1267–1291.
- Serreze, M.C., M.M. Holland and J. Stroeve, 2007. Perspectives on the Arctic's shrinking sea-ice cover. *Science*, 315:1533–1536.
- Sevruk, B., 1982. Methods of correction for systematic error in point precipitation measurement for operational use. *Operational Hydrology Report*, 21, 91 pp. World Meteorological Organization, Geneva, Switzerland.
- Sharma, S., E. Andrews, L.A. Barrie, J.A. Ogren and D. Lavoué, 2006. Variations and sources of the equivalent black carbon in the high Arctic revealed by long-term observations at Alert and Barrow: 1989–2003. *Journal of Geophysical Research-Atmospheres*, 111:D14208.
- Sharma, S., S. Couturier and S.D. Côté, 2009. Impacts of climate change on the seasonal distribution of migratory caribou. *Global Change Biology*, 15:2549–2562.
- Sherstyukov, B.G., A.G. Sherstyukov and P.Y. Groisman, 2008. Impact of surface air temperature and snow cover depth on the upper soil temperature variations in Russia. *Fall Meeting Supplement*, 89:Abstract GC41A-0674.
- Shevchenko, V.P., 2006. Influence of aerosols on the Arctic environment and marine sedimentation [in Russian]. 226 pp. Nauka, Moscow.
- Shklomanov, A.I. and R.B. Lammers, 2009. Record Russian river discharge in 2007 and the limits of analysis. *Environmental Research Letters*, 4:045015.
- Shklomanov, A.I., R.B. Lammers, M.A. Rawlins, L.C. Smith and T.M. Pavelsky, 2007. Temporal and spatial variations in maximum river discharge from a new Russian data set. *Journal of Geophysical Research-Biogeosciences*, 112:G04s53.
- Shindell, D.T., M. Chin, F. Dentener and 31 others, 2008. A multi-model assessment of pollution transport to the Arctic. *Atmospheric Chemistry and Physics*, 8:5353–5372.
- Shmakin, A.B., 2010. Climatic characteristics of snow cover over North Eurasia and their change during the last decades. *Ice and Snow*, 1:43–57.
- Shmakin, A.B., D.V. Turkov and A.Y. Mikhailov, 2009. Model of snow cover considering its layered structure and seasonal evolution. *Earth Cryosphere*, XIII:69–79.
- Sicart, J.E., J.W. Pomeroy, R.L.H. Essery, J. Hardy, T. Link and D. Marks, 2004. A sensitivity study of daytime net radiation during snowmelt to forest canopy and atmospheric conditions. *Journal of Hydrometeorology*, 5:774–784.
- Simpson, W.R., M.D. King, H.J. Beine, R.E. Honrath and X.L. Zhou, 2002. Radiation-transfer modeling of snow-pack photochemical processes during ALERT 2000. *Atmospheric Environment*, 36:2663–2670.
- Simpson, W.R., L. Alvarez-Aviles, T.A. Douglas, M. Sturm and F. Domine, 2005. Halogens in the coastal snow pack near Barrow, Alaska: Evidence for active bromine air-snow chemistry during springtime. *Geophysical Research Letters*, 32:L04811.
- Simpson, W.R., R. von Glasow, K. Riedel and 22 others, 2007. Halogens and their role in polar boundary-layer ozone depletion. *Atmospheric Chemistry and Physics*, 7:4375–4418.
- Sitch, S., C. Huntingford, N. Gedney, P.E. Levy, M. Lomas, S.L. Piao, R. Betts, P. Ciais, P. Cox, P. Friedlingstein, C.D. Jones, I.C. Prentice and F.I. Woodward, 2008. Evaluation of the terrestrial carbon cycle, future plant geography and climate-carbon cycle feedbacks using five Dynamic Global Vegetation Models (DGVMs). *Global Change Biology*, 14:2015–2039.
- Sköld, P. and P. Axelsson, 2008. The northern population development; Colonization and mortality in Swedish Sápmi, 1776–1895.

- International Journal of Circumpolar Health, 67:27–42.
- Slater, A.G., C.A. Schlosser, C.E. Desborough and 32 others, 2001. The representation of snow in land surface schemes: Results from PILPS 2(d). *Journal of Hydrometeorology*, 2:7–25.
- Smith, T.G. and L.A. Harwood, 2001. Observations of neonate ringed seals, *Phoca hispida*, after early break-up of the sea ice in Prince Albert Sound, Northwest Territories, Canada, spring 1998. *Polar Biology*, 24:215–219.
- Snyder, J.M. and B. Stonehouse (Eds.), 2007. *Prospects for Polar Tourism*. 318 pp. Cabi Publishing.
- Soininen, L. and E. Pukkala, 2008. Mortality of the Sami in Northern Finland 1979–2005. *International Journal of Circumpolar Health*, 67:43–55.
- Solberg, E.J., P. Jordhoy, O. Strand, R. Aanes, A. Loison, B.E. Saether and J.D.C. Linnell, 2001. Effects of density-dependence and climate on the dynamics of a Svalbard reindeer population. *Ecography*, 24:441–451.
- Solomon, S., D. Qin, M. Manning, Z. Chen, M. Marquis, K.B. Averyt, M. Tignor and H.L. Miller (Eds.), 2007. *Climate Change 2007: The Physical Science Basis*. Contribution of Working Group I to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change. 996 pp. Cambridge University Press.
- St Jacques, J.M. and D.J. Sauchyn, 2009. Increasing winter baseflow and mean annual streamflow from possible permafrost thawing in the Northwest Territories, Canada. *Geophysical Research Letters*, 36:L01401.
- Starr, G. and S.F. Oberbauer, 2003. Photosynthesis of arctic evergreens under snow: Implications for tundra ecosystem carbon balance. *Ecology*, 84:1415–1420.
- Starr, G., S.F. Oberbauer and L.E. Ahlquist, 2008. The photosynthetic response of Alaskan tundra plants to increased season length and soil warming. *Arctic Antarctic and Alpine Research*, 40:181–191.
- State Committee on Hydrometeorology and Environment Protection of the USSR, 1985. *Observation manual for hydrometeorological stations and posts*. [in Russian]. Issue 3 Volume 1, 300 pp. Gidrometeoizdat, Leningrad.
- Steffen, A., T. Douglas, M. Amiot, P. Ariya, K. Aspmo, T. Berg, J. Bottenheim, S. Brooks, F. Cobbett, A. Dastoor, A. Dommergue, R. Ebinghaus, C. Ferrari, K. Gardfeldt, M.E. Goodsite, D. Lean, A.J. Poulain, C. Scherz, H. Skov, J. Sommar and C. Temme, 2008. A synthesis of atmospheric mercury depletion event chemistry in the atmosphere and snow. *Atmospheric Chemistry and Physics*, 8:1445–1482.
- Stendel, M., V.E. Romanovsky, J.H. Christensen and T. Sazonova, 2007. Using dynamical downscaling to close the gap between global change scenarios and local permafrost dynamics. *Global and Planetary Change*, 56:203–214.
- Stern, N., 2006. *The Economics of Climate Change: The Stern Review*. 700 pp. Cambridge University Press.
- Stethem, C., B. Jamieson, P. Schaerer, D. Liverman, D. Germain and S. Walker, 2003. Snow avalanche hazard in Canada – a review. *Natural Hazards*, 28:487–515.
- Stewart, E.J., 2007. Sustainable cruise tourism in Arctic Canada: An integrated coastal management approach. *Tourism in Marine Environments* 3:77–88.
- Stewart, E.J., S.E.L. Howell, D. Draper, J. Yackel and A. Tivy, 2007. Sea ice in Canada's Arctic: Implications for cruise tourism. *Arctic*, 60:370–380.
- Stirling, I. and T.G. Smith, 2004. Implications of warm temperatures, and an unusual rain event for the survival of ringed seals on the coast of southeastern Baffin Island. *Arctic*, 57:59–67.
- Storck, P., D.P. Lettenmaier and S.M. Bolton, 2002. Measurement of snow interception and canopy effects on snow accumulation and melt in a mountainous maritime climate, Oregon, United States. *Water Resources Research*, 38:1223.
- Strasser, U., 2008. Snow loads in a changing climate: new risks? *Natural Hazards and Earth System Sciences*, 8:1–8.
- Stroeve, J., M.M. Holland, W. Meier, T. Scambos and M. Serreze, 2007. Arctic sea ice decline: Faster than forecast. *Geophysical Research Letters*, 34:L09501.
- Sturm, M., J. Holmgren and G.E. Liston, 1995. A seasonal snow cover classification-system for local to global applications. *Journal of Climate*, 8:1261–1283.
- Sturm, M., J.P. McFadden, G.E. Liston, F.S.I. Chapin, C.H. Racine and J. Holmgren, 2001a. Snow-shrub interactions in Arctic tundra: A hypothesis with climatic implications. *Journal of Climate*, 14:336–344.
- Sturm, M., C. Racine and K. Tape, 2001b. Climate change – Increasing shrub abundance in the Arctic. *Nature*, 411:546–547.
- Su, F.G., J.C. Adam, L.C. Bowling and D.P. Lettenmaier, 2005. Streamflow simulations of the terrestrial Arctic domain. *Journal of Geophysical Research-Atmospheres*, 110:D08112.
- Sugiura, K., T. Ohata and D.Q. Yang, 2006. Catch characteristics of precipitation gauges in high-latitude regions with high winds. *Journal of Hydrometeorology*, 7:984–994.
- Sumner, A.L. and P.B. Shepson, 1999. Snowpack production of formaldehyde and its effect on the Arctic troposphere. *Nature*, 398:230–233.
- Takala, M., J. Pulliainen, S.J. Metsamäki and J.T. Koskinen, 2009. Detection of Snowmelt Using Spaceborne Microwave Radiometer Data in Eurasia From 1979 to 2007. *IEEE Transactions on Geoscience and Remote Sensing*, 47:2996–3007.
- Tannerfeldt, M., B. Elmhagen and A. Angerbjörn, 2002. Exclusion by interference competition? The relationship between red and arctic foxes. *Oecologia*, 132:213–220.
- Tape, K., M. Sturm and C. Racine, 2006. The evidence for shrub expansion in Northern Alaska and the Pan-Arctic. *Global Change Biology*, 12:686–702.
- Tchebakova, N.M., T.A. Blyakharchuk and E.I. Parfenova, 2009. Reconstruction and prediction of climate and vegetation change in the Holocene in the Altai-Sayan mountains, Central Asia. *Environmental Research Letters*, 4:045025.
- Tedesco, M., M. Brodzik, R. Armstrong, M. Savoie and J. Ramage, 2009. Pan arctic terrestrial snowmelt trends (1979–2008) from spaceborne passive microwave data and correlation with the Arctic Oscillation. *Geophysical Research Letters*, 36:L21402.
- Thompson, R.S., K.H. Anderson and P.J. Bartlein, 2009. Atlas of relations between climatic parameters and distributions of important trees and shrubs in North America. 1650-A, 1650-B. <http://pubs.usgs.gov/pp/p1650-a> and <http://pubs.usgs.gov/pp/p1650-b/> Accessed: May 10, 2011.
- Tieszen, L.L., 1974. Photosynthetic competence of the subnivean vegetation of an arctic tundra. *Arctic and Alpine Research*, 6:253–256.
- Tømmervik, H., B. Johansen, J.Å. Riseth, S.R. Karlsen, B. Solberg and K.A. Høgda, 2009. Above ground biomass changes in the mountain birch forests and mountain heaths of Finnmarksvidda, northern Norway, in the period 1957–2006. *Forest Ecology and Management*, 257:244–257.
- Trenberth, K.E., P.D. Jones, P. Ambenje, R. Bojariu, D. Easterling, A. Klein Tank, D. Parker, F. Rahimzadeh, J.A. Renwick, M. Rusticucci, B. Soden and P. Zhai, 2007. Observations: Surface and atmospheric climate change. In: Solomon, S., D. Qin, M. Manning, Z. Chen, M. Marquis, K.B. Averyt, M. Tignor and H.L. Miller (Eds.). *The Physical Science Basis*. Contribution of Working Group I to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change, pp. 235–336, Cambridge University Press.
- Turi, J.O., 1966. *Turi's Book of Lapland*. [English translation of the Danish translation of the original 1910 publication: Muittalus samid sirra.] 293 pp. Library of Congress classification: DL971.L2. Anthropological Publications, Oosterhout, The Netherlands.
- Turunen, M., P. Soppela, H. Kinnunen, M.L. Sutinen and F. Martz, 2009. Does climate change influence the availability and quality of reindeer forage plants? *Polar Biology*, 32:813–832.
- Tye, A.M., S.D. Young, N.M.J. Crout, H.M. West, L.M. Stapleton, P.R. Poulton and J. Laybourn-Parry, 2005. The fate of N-15 added to high Arctic tundra to mimic increased inputs of atmospheric nitrogen released from a melting snowpack. *Global Change Biology*, 11:1640–1654.
- Tyler, N.J.C., J.M. Turi, M.A. Sundset, K.S. Bull, M.N. Sara, E. Reinert, N. Oskal, C. Nellesmann, J.J. McCarthy, S.D. Mathiesen, M.L. Martello, O.H. Magga, G.K. Hovelsrud, I. Hanssen-Bauer, N.I. Eira, I.M.G. Eira and R.W. Corell, 2007. Saami reindeer pastoralism under climate change: Applying a generalized framework for vulnerability studies to a sub-arctic social-ecological system. *Global Environmental Change-Human and Policy Dimensions*, 17:191–206.
- Tynes, T. and T. Haldorsen, 2007. Mortality in the Sami population of North Norway, 1970–98. *Scandinavian Journal of Public Health*, 35:306–312.
- UNEP, 2007. *Global Outlook for Ice and Snow*. 235 pp. UNEP/GRID, Arendal, Norway.
- United States Department of Commerce, National Oceanic and Atmospheric Administration and National Geophysical Data Center, 2006. 2-minute Gridded Global Relief Data (ETOPO2v2), June 2006. Digital Data. <http://www.ngdc.noaa.gov/mgg/fliers/06mgg01.html>.

Accessed: May 10, 2011.

- Usher, M.B., T.V. Callaghan, G. Gilchrist, B. Heal, G.P. Juday, H. Loeng, M.A. Muir and P. Prestud, 2005. Principles of conserving the Arctic's biodiversity. In: Arctic Climate Impact Assessment, pp. 539–596, Cambridge University Press.
- Viken, A., 2006. Swalbard, Norway. In: Baldacchino, G. (Ed.). Extreme tourism: lessons from the world's cold water islands, pp. 129–149. Elsevier.
- Vikhamar-Schuler, D., S. Beldring, E.J. Førland, L.A. Roald and T. Engen-Skaug, 2006. Snow cover and snow water equivalent in Norway: current conditions (1961–90) and scenarios for the future (2071–2100). Met.no Report 01/2006 Climate: 34 pp.
- Vinogradova, A.A. and T.Y. Ponomareva, 2007. Sources and sinks of anthropogenic microelements in the Arctic atmosphere: tendencies in variations from 1981 to 2005 [English translation]. Atmospheric and Oceanic Optics, 20:433–441.
- Vistnes, I., C. Nellemann, P. Jordhøy and O. Strand, 2001. Wild reindeer: impacts of progressive infrastructure development on distribution and range use. Polar Biology, 24:531–537.
- Voeikov, A.I., 1952. Snow cover: Its Impact on Climate, Soil and Weather. Methods of Snow Investigation. Izdatelstvo AN SSSR, Moscow-Leningrad.
- Vygodskaya, N.N., P.Y. Groisman, N.M. Tchepakova, J.A. Kurbatova, O. Panforyov, E.I. Parfenova and A.F. Sogachev, 2007. Ecosystems and climate interactions in the boreal zone of northern Eurasia. Environmental Research Letters, 2:045033.
- Walden, V.P., A. Mahesh and S.G. Warren, 1996. Comment on, “Recent changes in the North American Arctic boundary layer in winter”, by R.S. Bradley et al. Journal of Geophysical Research-Atmospheres, 101:7127–7134.
- Walker, M.D., D.A. Walker, J.M. Welker, A.M. Arft, T. Bardsley, P.D. Brooks, J.T. Fahnestock, M.H. Jones, M. Losleben, A.N. Parsons, T.R. Seastedt and P.L. Turner, 1999. Long-term experimental manipulation of winter snow regime and summer temperature in arctic and alpine tundra. Hydrological Processes, 13:2315–2330.
- Walker, D.A., W.D. Billings and J.G. De Molenaar, 2001. Snow-vegetation interactions in tundra environments. In: Jones, H.G., J.W. Pomeroy, D.A. Walker and R.W. Hoham (Eds.). Snow Ecology: an interdisciplinary examination of snow-covered ecosystems, pp. 266–324, Cambridge University Press.
- Walker, T.R., S.D. Young, P.D. Crittenden and H. Zhang, 2003. Anthropogenic metal enrichment of snow and soil in north-eastern European Russia. Environmental Pollution, 121:11–21.
- Walland, D.J. and I. Simmonds, 1997. Modelled atmospheric response to changes in Northern Hemisphere snow cover. Climate Dynamics, 13:25–34.
- Walser, M.L., 2009. International Arctic Science Committee (Content Partner); Maggie L. Walser (Topic Editor). 2009. Nunavut climate change case study. In: Cutler J. Cleveland (Ed.) Encyclopedia of Earth. First published in the Encyclopedia of Earth January 2, 2008; Last revised September 14, 2009; Retrieved September 24, 2009. http://www.eoearth.org/article/Nunavut_climate_change_case_study?topic=49664.
- Walsh, J.E., X. Zhou, D. Portis and M.C. Serreze, 1994. Atmospheric contribution to hydrologic variations in the Arctic. Atmosphere-Ocean, 32:733–755.
- Wang, L.B., C. Derksen and R. Brown, 2008. Detection of pan-Arctic terrestrial snowmelt from QuikSCAT, 2000–2005. Remote Sensing of Environment, 112:3794–3805.
- Wang, L., C. Derksen, S. Howell, G.J. Wolken, M. Sharp and T. Markus, 2009. Integrated Pan-Arctic melt onset detection from satellite microwave measurements. Paper presented at 66th Eastern Snow Conference, pp. 131–138. Niagara-on-the-Lake, Ontario, Canada.
- Warren, S.G. and W.J. Wiscombe, 1980. A model for the spectral albedo of snow. II: snow containing atmospheric aerosols. Journal of the Atmospheric Sciences, 37:2734–2745.
- Warren, S.G. and W.J. Wiscombe, 1985. Dirty snow after nuclear war. Nature, 313:467–470.
- Werner, R.A., 1993. Response of the engraver beetle, *Ips perturbatus*, to semiochemicals in white spruce stands of interior Alaska. USDA Forest Service Pacific Northwest Research Station Research Paper, 0882-5165, 1–9 pp.
- Werner, R.A., K.F. Raffa and B.L. Illman, 2006. Dynamics of phytophagous insects and their pathogens in Alaskan boreal forests. In: Chapin III, F.S., M.W. Oswood, K. van Cleve, L.A. Viereck and D.L. Verbyla (Eds.). Alaska's Changing Boreal Forest, pp. 133–146, Oxford University Press.
- Wilby, R.L., S.P. Charles, E. Zorita, B. Timbal, P. Whetton and L.O. Mearns, 2004. Guidelines for Use of Climate Scenarios Developed from Statistical Downscaling Methods. 27 pp. Supporting material of the IPCC. Environment Agency of England and Wales.
- Wilmking, M., G.P. Juday, V.A. Barber and H.S.J. Zald, 2004. Recent climate warming forces contrasting growth responses of white spruce at treeline in Alaska through temperature thresholds. Global Change Biology, 10:1724–1736.
- Wilmking, M., R. D'Arrigo, G.C. Jacoby and G.P. Juday, 2005. Increased temperature sensitivity and divergent growth trends in circumpolar boreal forests. Geophysical Research Letters, 32:L15715.
- Wis, M., N. Dendoncker, J. Madsen, M. Rounsevell, M. Jespersen, E. Kuijken, W. Courtens, C. Verschuere and F. Cottaar, 2008. Modelling pink-footed goose (*Anser brachyrhynchus*) wintering distributions for the year 2050: potential effects of land-use change in Europe. Diversity and Distributions, 14:721–731.
- Wolf, A., T.V. Callaghan and K. Larson, 2008. Future changes in vegetation and ecosystem function of the Barents Region. Climatic Change, 87:51–73.
- Woo, M.K., 1980. Hydrology of a small lake in the Canadian High Arctic. Arctic and Alpine Research, 12:227–235.
- Woo, M.K. and X.J. Guan, 2006. Hydrological connectivity and seasonal storage change of tundra ponds in a polar oasis environment, Canadian High Arctic. Permafrost and Periglacial Processes, 17:309–323.
- Woo, M.K. and R. Thorne, 2003. Streamflow in the Mackenzie Basin, Canada. Arctic, 56:328–340.
- Woo, M.K. and K.L. Young, 2003. Hydrogeomorphology of patchy wetlands in the High Arctic, polar desert environment. Wetlands, 23:291–309.
- Woo, M.K., R. Thorne, K. Szeto and D.Q. Yang, 2008. Streamflow hydrology in the boreal region under the influences of climate and human interference. Philosophical Transactions of the Royal Society B-Biological Sciences, 363:2251–2260.
- Yang, D.Q., 1999. An improved precipitation climatology for the Arctic Ocean. Geophysical Research Letters, 26:1625–1628.
- Yang, D.Q., S. Ishida, B.E. Goodison and T. Gunther, 1999. Bias correction of daily precipitation measurements for Greenland. Journal of Geophysical Research-Atmospheres, 104:6171–6181.
- Yang, D.Q., B. Goodison, J. Metcalfe, P. Louie, E. Elomaa, C. Hanson, V. Golubev, T. Gunther, J. Milkovic and M. Lapin, 2001. Compatibility evaluation of national precipitation gauge measurements. Journal of Geophysical Research-Atmospheres, 106:1481–1491.
- Yang, J., R.E. Honrath, M.C. Peterson, J.E. Dibb, A.L. Sumner, P.B. Shepson, M. Frey, H.W. Jacobi, A. Swanson and N. Blake, 2002. Impacts of snowpack emissions on deduced levels of OH and peroxy radicals at Summit, Greenland. Atmospheric Environment, 36:2523–2534.
- Yang, D.Q., B.S. Ye and A. Shiklomanov, 2004. Discharge characteristics and changes over the Ob River watershed in Siberia. Journal of Hydrometeorology, 5:595–610.
- Yang, D.Q., D. Kane, Z.P. Zhang, D. Legates and B. Goodison, 2005. Bias corrections of long-term (1973–2004) daily precipitation data over the northern regions. Geophysical Research Letters, 32:L19501.
- Yarie, J., 2008. Effects of moisture limitation on tree growth in upland and floodplain forest ecosystems in interior Alaska. Forest Ecology and Management, 256:1055–1063.
- Yarie, J., K. Vancleve and R. Schlentner, 1990. Interaction between moisture, nutrients and growth of white spruce in interior Alaska. Forest Ecology and Management, 30:73–89.
- Ye, B.S., D.Q. Yang and D.L. Kane, 2003. Changes in Lena River streamflow hydrology: Human impacts versus natural variations. Water Resources Research, 39:1200.
- Zhao, H.X. and R. Fernandes, 2009. Daily snow cover estimation from Advanced Very High Resolution Radiometer Polar Pathfinder data over Northern Hemisphere land surfaces during 1982–2004. Journal of Geophysical Research-Atmospheres, 114:D05113.
- Zhou, X.L., H.J. Beine, R.E. Honrath, J.D. Fuentes, W. Simpson, P.B. Shepson and J.W. Bottenheim, 2001. Snowpack photochemical production of HONO: a major source of OH in the Arctic boundary layer in springtime. Geophysical Research Letters, 28:4087–4090.

5. Changing Permafrost and its Impacts

COORDINATING LEAD AUTHORS: TERRY V. CALLAGHAN, MARGARETA JOHANSSON

LEAD AUTHORS: OLEG ANISIMOV, HANNE H. CHRISTIANSEN, ARNE INSTANES, VLADIMIR ROMANOVSKY, SHARON SMITH

CONTRIBUTING AUTHORS: MICHEL ALLARD, F. STUART CHAPIN III, TORBEN R. CHRISTENSEN, BERND ETZELMULLER, STEFAN FRONZEK, DAVID GILICHINSKY, LARRY HINZMAN, HANS-WOLFGANG HUBBERTEN, OLE HUMLUM, M. TORRE JORGENSEN, PETER KUHRY, ANTONI LEWKOWICZ, SERGEI S. MARCHENKO, A. DAVID MCGUIRE, JULIAN MURTON, NAUM G. OBERMAN, PAUL OVERDUIN, MARK PARSONS, SVETLANA A. RENEVA, EDWARD A.G. SCHUUR, IGOR SEMILETOV, NATALIA SHAKHOVA, NIKOLAY I. SHIKLOMANOV, ANDREI A. VELICHKO, YU ZHANG

Contents

Key Findings	2	5.4. Strategies for adapting to climate change effects in permafrost regions	43
Summary	3	5.4.1. Facilitating adaptation at the regional scale	44
5.1. Introduction	3	5.4.2. Adaptation at the local scale	45
5.2. Past, current and future states of permafrost and causes of change	5	5.5. Uncertainties and recommendations	48
5.2.1. Permafrost in the past	6	5.5.1. Data needs and priorities for permafrost research	48
5.2.2. State of present-day terrestrial and subsea permafrost and controlling factors	8	5.5.2. External use of improved understanding of permafrost .	48
5.2.3. Projections of future permafrost states	12	5.6. Conclusions	49
5.3. Impacts of changes in permafrost distribution and extent	18	5.6.1. Recent advances in understanding	49
5.3.1. Hydrological processes and responses to thawing permafrost	19	5.6.2. The human face of permafrost change	49
5.3.2. Geomorphological processes	20	5.6.3. ‘Winners and losers’	49
5.3.3. Ecological processes	28	Acknowledgments	49
5.3.4. Feedbacks to climate through trace gas emissions and albedo changes	31	Appendix 5.1. Sources of information and data	50
5.3.5. Socio-economic issues	38	References	51

Key Findings

- Permafrost warming, typically between 0.5 and 2 °C, generally continues in the Arctic. New data show permafrost warming has continued over the past decade in the eastern and High Arctic of Canada, in the northern Nordic regions and Svalbard, in the Russian European North and in western Siberia, although there was a reduced rate of warming during the past decade in western North America. Areas with warm, ice-rich permafrost showed lower warming rates than areas with cold permafrost or bedrock.
- An updated assessment of trends in active-layer thickness (ALT) over the past two decades shows ALT has increased at sites in Scandinavia and the Russian Arctic, but surprisingly, increases in North America have only been reported from the interior of Alaska and only over the past five years.
- New projections of ground temperature throughout the pan-Arctic area suggest that by the end of the 21st century, late-Holocene permafrost in the Northern Hemisphere may be actively thawing at the southern boundary of the permafrost region and some Late Pleistocene permafrost could start to thaw at some locations.
- Regional models project that by the end of the 21st century, the upper 2 to 3 metres of permafrost will thaw over 16% to 20% of the area currently underlain by permafrost in Canada and that there will be widespread permafrost degradation over about 57% of the total area of Alaska. In Russia, increases in ground temperature of 0.6 to 1 °C by 2020 have been projected.
- Recent analyses indicate contrasting changes in hydrology in permafrost regions over past decades: landscape dryness is increasing in the boreal forest, particularly in areas of discontinuous permafrost, whereas some sub-Arctic areas are experiencing waterlogging when permafrost thaws.
- Biodiversity and ecosystem processes on land and in freshwaters are being affected by changes in hydrology. Recent studies show that the thawing of ice-rich permafrost is leading to the draining of wetlands resulting in a loss of habitat in some areas whereas in others, thawing permafrost is leading to impeded drainage and a shift in biodiversity to wetland vegetation. Thaw slumping may affect ecosystems sooner than air warming alone.
- Since the Arctic Climate Impact Assessment was published in 2005, new research has demonstrated the viability and diversity of organisms preserved in ancient permafrost.
- New measurements and estimates of soil carbon pools in permafrost indicate that there is more soil carbon in permafrost than previously thought. This carbon is likely to play a more important role in feedbacks to climate during permafrost thawing than earlier calculations suggested.
- Very high emissions of the powerful greenhouse gas nitrous oxide have recently been discovered from two locations in terrestrial permafrost regions of the Arctic. Although the importance of the process cannot be generalized across the Arctic, the strong radiative forcing potential of the gas suggests important potential contributions to climate forcing.
- High concentrations of subsea methane from the Laptev Sea have recently been recorded throughout the water column and in the atmosphere. Although more measurements are needed from other seas with different permafrost shelf conditions, the current observations reinforce concerns about a major feedback to the climate system from thawing and destabilization of subsea permafrost.
- Recent studies at some locations in the Arctic show increases in thermokarst development which are specifically important where ice-wedges degrade or palsas (peat mounds with a frozen core) decline. Permafrost degradation is also found likely to increase slope instability by increasing the amount of rockfalls and rockslides, and to increase rates of rock glacier movement. In areas with coastal permafrost, warming of permafrost may also increase coastal erosion.
- There is an increased acknowledgment and consideration of climate change and its impacts on permafrost in engineering design particularly for structures for which the consequences of failure are high. New maps based on a probabilistic approach of infrastructure susceptibility to permafrost thaw in Eurasia show that in large areas of Russia, especially in a zone along the coast, buildings and engineered structures have high vulnerability to ongoing change in climate and permafrost.

Summary

Permafrost is soil, rock, sediment or other earth material that remains at or below 0 °C for two or more consecutive years. It has an important influence on the biogeophysical environment and also on human activity. Engineering and hydrological properties of permafrost as well as landscape hydrology, geomorphology and biological processes will change if permafrost warms and thaws. Thawing permafrost will affect populations locally and globally.

Current and projected changes in permafrost conditions are likely to result from the interaction of several factors and processes, particularly increasing air temperatures that are generally leading to permafrost degradation. However, local factors are also important, including snow cover, vegetation, organic layer thickness, thermal properties of the earth material, soil moisture/ice content and drainage conditions. Changes in these local factors through natural processes or environmental disturbance associated with human activity can lead to changes in permafrost conditions.

Observations from permafrost monitoring sites throughout the Arctic, including North America, Russia and Scandinavia generally indicate that permafrost temperatures have increased, typically by 0.5 to 2 °C since the late 1970s, although the rate and magnitude of the increase varies regionally. Areas with warm ice-rich permafrost showed lower warming rates than areas with cold permafrost or bedrock. Monitoring of active-layer thickness (ALT) indicates decadal trends that vary by region. A progressive increase in ALT has been observed in some Nordic sites, the Russian European North, East Siberia, and Chukotka with disappearance of permafrost from the upper several metres over the past 20- to 30-year period at several low Arctic Nordic, Canadian and European Russian sites. North American sites show a progressive increase of ALT during the last five years only at a limited number of sites in the Alaskan Interior, and ALT on the Alaskan North Slope and in the northwestern Canadian Arctic has been relatively stable since 1995.

Permafrost models, driven by projections of Arctic warming by general circulation models (GCMs), project that by the end of the 21st century the upper 2 to 3 m of permafrost will thaw over 16–20% of the area underlain by permafrost in Canada. In Alaska, mean annual ground temperature (MAGT) at 2 m depth could be above 0 °C everywhere southward of 66° N except for small patches at high altitude in the Alaska Range and Wrangell Mountains. An area of approximately 850 000 km² (about 57% of the total area of Alaska) is projected to experience widespread permafrost degradation and could contain areas where permafrost disappears completely. In Russia, permafrost changes of a +0.6 to +1 °C increase in ground temperature have been projected by 2020.

When permafrost starts to thaw, waterlogging occurs in some predominantly flat areas, whereas ponds dry in others. These opposing outcomes of thawing permafrost have profound impacts on infrastructure, ecology, and greenhouse gas emissions. In northern mountain areas thawing permafrost can also lead to rock slope instability. Also, coastal erosion will increase as permafrost thaws because much of the Arctic coastline is composed of unconsolidated materials, many of which are ice-rich and sensitive to increased air temperature

and changes in the length of seasonal sea-ice cover.

Since the publication of the Arctic Climate Impact Assessment (ACIA, 2005) and the Fourth Assessment of the Intergovernmental Panel on Climate Change (e.g., Solomon et al., 2007), knowledge about the preservation and activity of life in permafrost has increased. Furthermore, recent work has shown that carbon pools in permafrost soils are much larger than previously recognized: around 1400 to 1850 gigatonnes (Gt) of carbon are located in terrestrial permafrost regions. Although model projections suggest that tundra is likely to remain a weak sink of atmospheric carbon dioxide (CO₂), there are great uncertainties and the emissions of methane (CH₄) and nitrous oxide (N₂O) (much stronger greenhouse gases than CO₂) from permafrost areas have the potential to substantially increase radiative forcing. In addition, Arctic coastal seas underlain by subsea permafrost host an extremely large carbon pool: the Arctic continental shelf could contain around 1300 Gt of carbon, of which 800 Gt is CH₄, some of which could be available for sudden release under the appropriate conditions. A release of only 1% of this reservoir would more than triple the atmospheric mixing ratio of CH₄, potentially triggering abrupt climate change.

Increasing ground temperature and thawing permafrost can cause ground subsidence in areas of ice-rich permafrost. Infrastructure design takes into account that there may be some degree of permafrost thaw in response to changes in the ground thermal regime associated with construction activities and infrastructure operation. Climate change is an additional factor that needs to be accounted for, and in some areas this is already being done for design of major structures.

Climate feedbacks from thawing permafrost in the Arctic can help to stimulate a global response to climate change. However, mitigation by local communities will be relatively insignificant and they must therefore adapt to the changing conditions. Adaptation through engineering is already taking place and appropriate technology is available, but costly. To formulate and implement other adaptation strategies a range of tools must be developed. These include hazard index calculations, high spatial resolution projections of permafrost change and probabilistic active-layer change maps.

Thawing permafrost offers few opportunities but many challenges. Large multinational industries and developers will face the need for greater economic investment to stabilize infrastructure over longer periods, whereas individual residents will face disruption to communication routes and even resettlement in some cases. However, when permafrost completely disappears at its southern margins, communities will benefit as they will no longer require special infrastructure design features related to permafrost.

5.1. Introduction

Permafrost is soil, rock, sediment or other earth material that remains at or below 0 °C for two or more consecutive years (Brown and Péwé, 1973). It underlies most of the surfaces of the terrestrial Arctic (French, 2007) while coastal and subsea permafrost exist around Arctic coastlines.

Progressing from the soil surface downward, there is an active layer which freezes and thaws seasonally, a transient layer that can remain frozen in some summers (Shur et al., 2005),

and then permafrost (Figure 5.1). Most subsea permafrost is not subject to the seasonal variation seen on land, since its upper temperature is controlled by bottom seawater temperatures. As long as sediment temperatures are cryotic (i.e., less than 0 °C), the sediment is classified as permafrost, whether or not it contains ice. Unfrozen zones (taliks) can occur within permafrost, for example under large water bodies. Terrestrial permafrost thickness ranges from a few tens of centimeters at the southern limit of the permafrost zone to about 1500 m in the north of the Arctic region. Active-layer thickness is influenced by climate and local factors and can vary from less than 0.5 m in vegetated, organic terrain to more than 10 m in areas of exposed bedrock.

The proportion of the landscape underlain by permafrost generally becomes greater with increasing latitude from the southern limits of the permafrost zone to the High Arctic. This transition is reflected in isolated islands and sporadic permafrost at the southern margins, more extensive but discontinuous permafrost further north, and more or less continuous permafrost found everywhere except beneath large bodies of water or newly aggraded land in the High Arctic (Brown et al., 1998; Figure 5.2).

Permafrost has an important influence on the biogeophysical environment and also on human activity, largely because it often contains ice. The engineering and hydrological properties of earth material, as well as its influence on biological processes will therefore change if permafrost warms and thaws. The strength and stability of frozen ground is strongly related to temperature, and can decrease as ground ice melts. This has major implications for infrastructure performance (Instanes et al., 2005), especially if the ground is ice-rich. Permafrost also influences surface and subsurface hydrology as frozen ground restricts the mobility of groundwater. Changes in the permafrost can lead both to drying and waterlogging of the landscape which has important implications for water sources,

infrastructure, ecology, and biogeochemical cycling (e.g., land/air exchange of greenhouse gases). Permafrost moderates properties of the active layer that affect greenhouse gas fluxes and also contains vast reserves of historically sequestered carbon (Tarnocai et al., 2009) that, if released, could act as a positive feedback to climate warming.

Climate, in particular air temperature, is one of the main factors influencing the areal extent and thickness of permafrost as well as its thermal condition. The projected future increase in air temperature is therefore expected to result in changing permafrost conditions. However, local factors are also important in influencing the energy balance at the ground surface and the response of permafrost to changes in climate (Williams and Smith, 1989; Yershov, 1998; French, 2007). These factors include snow cover, vegetation, soil organic layer thickness, thermal properties of the earth materials, soil moisture/ice content and drainage conditions. Changes in these local factors through natural processes or environmental disturbance associated with human activity can thus lead to changes in permafrost conditions. Forest fires for example, can cause removal of vegetation cover and the insulating organic layer and result in warming and thawing of permafrost. Shifting shorelines resulting from river erosion and sediment deposition can also result in permafrost degradation as areas become inundated. However, permafrost formation can also occur as formerly flooded areas are exposed to lower air temperatures. Permafrost formation can also occur in newly exposed land such as the bottom of drained lakes (e.g., Mackay and Burn, 2002), in deglaciated areas in front of the Greenland Ice Sheet and local glaciers, and in areas of coastal uplift or sedimentation such as deltas (e.g., Dyke et al., 1997; Taylor, 1991). At a pan-Arctic scale, permafrost formation at present is relatively rare, but is locally important.

Human activity associated with the construction and operation of infrastructure can also lead to changes in




Figure 5.1. Distribution of permafrost and permafrost features along a conceptual transect from the sub-Arctic to the continental shelves.




Figure 5.2. Extent and type of permafrost in the Northern Hemisphere. Source: International Permafrost Association, Brown et al. (1998).

the ground surface and alterations in the ground thermal regime. Land clearance and removal of organic matter during construction activities, result in a reduction in the buffer layer and warming of the ground, increases in thaw depth, and possible degradation of permafrost. The placement of heated structures on (e.g., buildings) or in (e.g., pipelines) permafrost can also result in thawing.

Not all areas underlain by permafrost are equally vulnerable to short-term thaw. Southern areas underlain by ice-rich permafrost and areas of sporadic and discontinuous permafrost are likely to be most impacted by increased air temperature. In contrast, the cold thick permafrost of Siberia and the North American High Arctic might experience modest surface warming but the massive frozen materials at depth are likely to be stable for millennia. Such variation in the sensitivity of permafrost to climate warming differentially affects the vulnerability of ecological processes and human activities to change. Adaptation of biological systems to changes in permafrost is an ongoing process and is part of a two-way interaction between vegetation and permafrost. However, human adaptation to changes in permafrost is a relatively new dimension that involves multiple aspects of land use and infrastructure development that incur cultural and economic costs, rather than new opportunities.

This chapter provides a synthesis of current knowledge of existing and projected changes in Arctic permafrost conditions and their likely impacts on society. This adds to the recent benchmark assessments of the Arctic Climate Impact

Assessment (ACIA, 2005) and the Fourth Assessment of the Intergovernmental Panel on Climate Change (e.g., Solomon et al., 2007) by focusing on more recent information and new topics. The chapter reports recent changes in permafrost conditions and provides a synthesis of new projections of future change and its implications for natural systems and society. This information is used to highlight how adaptations to changing permafrost conditions might occur in the natural world and how society might develop socio-economic adaptation strategies. The chapter concludes by listing important gaps in understanding and recommends priority actions. Many types of knowledge sources are drawn on (e.g., field observations and monitoring, experimental and modeling activities), with the focus on new data acquired during the International Polar Year projects and output from the Ninth International Conference on Permafrost (NICOP) in 2008 and the Third European Conference on Permafrost (EUCOP III) in 2010.

5.2. Past, current and future states of permafrost and causes of change

- Permafrost warming, typically between 0.5 and 2 °C since the late 1970s, generally continues in the Arctic. New data show permafrost warming has continued over the past decade in the eastern and high Arctic of Canada, in the northern Nordic regions and Svalbard, in the Russian European North and in western Siberia, although there was a reduced rate of warming during the past decade

in western North America. Areas with warm, ice-rich permafrost showed lower warming rates than areas with cold permafrost or bedrock.


- An updated assessment of trends in ALT over the past two decades shows ALT has increased at sites in Scandinavia and the Russian Arctic, but surprisingly, increases in North America have only been reported from the interior of Alaska and only over the past five years.
- New projections of ground temperature throughout the pan-Arctic area suggest that by the end of the 21st century, late-Holocene permafrost in the Northern Hemisphere may be actively thawing at the southern boundary of the permafrost region and some Late Pleistocene permafrost could start to thaw at some locations.
- Regional models project that by the end of the 21st century the upper 2 to 3 m of permafrost will thaw over 16% to 20%

of the area currently underlain by permafrost in Canada and that there will be widespread permafrost degradation over about 57% of the total area of Alaska during this period. In Russia, increases in ground temperature of 0.6 to 1 °C by 2020 have been projected.


5.2.1. Permafrost in the past

Knowledge about past permafrost distribution and dynamics leads to a better understanding of the significance and scale of recent changes in the thermal state and distribution of permafrost, and this knowledge-base has increased recently. It also facilitates the projection of possible rates and pathways of future permafrost degradation. There are two principal reasons for this. First, the main present-day features of permafrost distribution, both vertically and laterally, were formed during the past 100 000 years. Second, with persistent future climate warming, changes in current permafrost will reflect its history:

Last Interglacial optimum (125 ky BP)



Last glacial maximum (20 - 18 ky BP)



Holocene (6 - 5.5 ky BP)





Figure 5.3. Permafrost distribution during the last interglacial period (125 ky BP), the last glacial maximum (20 to 18 ky BP), and during the Holocene climatic optimum (6 to 5.5 ky BP) based on paleo-reconstructions by Velichko and Faustova (2009), and Velichko and Nechaev (2009).

the first permafrost to begin to thaw will be the youngest Little Ice Age permafrost, followed by mid- and late-Holocene permafrost, and lastly, Late Pleistocene permafrost.

5.2.1.1. Past climate and permafrost development

Permafrost is a product of a cold climate. Thus, in the past, whenever and wherever the Earth's climate became cold enough, permafrost has developed (Yershov, 1998). Progressive cooling of the Earth's climate, which started about 40 million years ago, caused expansion of the surface area occupied by ice masses and permafrost. Since then, the Earth's climate has been generally conducive to the existence of permafrost at high latitudes and high elevations in both the Northern Hemisphere and Southern Hemisphere.

Huge changes in climate and other environmental characteristics including northern hemisphere permafrost distribution occurred across the northern high latitudes during the Pleistocene (roughly the past 1.5 million years; see also Figure 5.3). These changes were driven by the Milankovitch cycles in solar radiation received by the Earth's surface (Milankovitch, 1930; Imbrie and Imbrie, 1979; Melnikov and Smulsky, 2009). Climate variations on the glacial-interglacial time-scale were also responsible for dramatic changes in global sea level. During the last glacial maximum (around 20 ky BP), sea level was 120 to 140 m lower than at present. Thus, practically all present-day Siberian Arctic shelves and a significant proportion of the North American Arctic shelves (e.g., the Beaufort) were dry land that was exposed to extremely cold climatic conditions (Hubberten and Romanovskii, 2001; Overduin et al., 2007; Velichko and Faustova, 2009; Velichko and Nechaev, 2009; see also Figure 5.3). During this period, terrestrial permafrost up to 500 m thick was formed on the inner shelf areas, but was thinner towards the shelf edge due to the shorter exposure time of land to the cold air.

Climate was also the major factor affecting permafrost during the transition periods from glacial to interglacial conditions and during the interglacial periods. However, within low-lying Arctic coastal areas, sea-level rise was also a

major driving force of permafrost degradation. During these warm periods, other environmental changes, such as changes in hydrology and vegetation, started to play increasingly important roles in the preservation or degradation of permafrost until eventually, changes in permafrost on the millennia and century time-scales were driven as much by changes in vegetation and hydrology as by changes in climate (Velichko and Nechaev, 2005; Jorgenson et al., 2010).

5.2.1.2. Magnitude and rate of changes

During the last glacial maximum, permafrost underlay more land area than today (see Figure 5.3). The climatic transition from the last glacial period to the current interglacial period was associated with a rapid thaw of permafrost both from the top and bottom at the southernmost limits of its Late Pleistocene maximum distribution, although some permafrost formation also occurred (e.g., in areas of coastal uplift). With climate warming in progress, rapid permafrost degradation in the Northern Hemisphere became more extensive. The rate of permafrost thawing, which varied from a few millimeters to several tens of centimetres per year, depended to a significant extent on permafrost ice content and the texture of thawing sediments. By the time of the Holocene optimum (5 to 9 ky BP; see Figure 5.3), permafrost had completely disappeared from most of the territory of deglaciated Europe, from northern Kazakhstan, and from a significant proportion of western Siberia in northern Eurasia (Velichko and Nechaev, 2009; Velichko and Faustova, 2009). In areas where the upper several hundred metres of permafrost was ice-rich, such as in the Pechora River basin and in the northern and central parts of western Siberia, permafrost did not disappear completely and is still present at great depth (200 m and deeper) (Balobaev et al., 1983; Baulin, 1985; Melnikov and Grechishchev, 2002) (Figure 5.4).

During the Holocene optimum, much of the continuous terrestrial permafrost zone in the Arctic was generally stable with no widespread thaw. However, where near-surface permafrost was ice-rich, many thermokarst lakes developed



Figure 5.4. Present-day distribution of permafrost of different ages in Russia. Source: after Lisitsyna and Romanovskii (1998).

causing localized thawing under those lakes that were sufficiently deep (MacDonald et al., 2006; Walter et al., 2007a). The rate of thawing both in the vertical and lateral direction was several centimetres to several tens of centimetres per year. Several thousand years after the Holocene optimum, permafrost started to thaw from the bottom up in this continuous permafrost zone (Osterkamp and Gosink, 1991), but the rate of thaw was only a few centimetres per year.

Holocene climate has been generally, much more stable and warmer than during the Late Pleistocene. However, there were several relatively cold intervals that lasted several centuries in the Middle and Late Holocene (6 to 2 ky BP: Velichko and Nechaev, 2005). During these periods, new, fairly shallow, short-lived permafrost appeared and disappeared several times in some landscape types found within the sporadic and discontinuous permafrost zones near the southern boundary of the present-day permafrost (Figures 5.2 and 5.4). The last and probably the coldest of such intervals was the Little Ice Age that dominated most of the Northern Hemisphere climate between around 1600 and 1850. During this period, shallow permafrost (15 to 25 m, e.g., Romanovsky et al., 1992) was established within the sediments that had been predominantly unfrozen during most of the Holocene. Present-day warming initiated the Little Ice Age permafrost thawing that is ongoing today (see Section 5.2.2.2). In the High Arctic, the reconstructed ground surface temperature record for a small island site shows that there was a muted response of permafrost to the Little Ice Age due to the maritime climate, compared to sites influenced by a more continental regime (Taylor et al., 2006). These reconstructions also show that cyclical fluctuations in permafrost temperature, related to decadal cycles in atmospheric circulation patterns are superimposed on the longer-term warming of permafrost since the Little Ice Age.

5.2.2. State of present-day terrestrial and subsea permafrost and controlling factors

5.2.2.1. Distribution of permafrost

Permafrost areas presently occupy 23% to 25% of the terrestrial parts of the Northern Hemisphere, most of which is in the Arctic (Brown et al., 1998). Continuous permafrost dominates the northernmost land areas while its distribution becomes discontinuous in the sub-Arctic landscape (Figure 5.2). However, continuous permafrost extends into the boreal forest (taiga) regions with a continental climate in some areas (e.g., Burn and Kokelj, 2009; and compare permafrost distribution in Figure 5.2 with forest distribution in figure 1 of Callaghan et al., 2002). Permafrost is divided into four zones based on the percentage of land that it underlies: continuous permafrost (90% to 100%), discontinuous permafrost (50% to 90%), sporadic permafrost (10% to 50%), and isolated islands of permafrost (0% to 10%) (Brown et al., 1998).

Permafrost thickness reaches a maximum of 1500 m in Siberia (French, 2007) in areas which were not covered by glaciers for substantial periods, whereas it is generally less than 400 m thick in areas covered by glaciers during the last glaciation, such as in North America (French, 2007). Very detailed permafrost mapping exists for Russia and Alaska,

while Canadian mapping is less detailed, and European and Greenland permafrost is only mapped in low detail. The circum-Arctic permafrost map (see Figure 5.2) also includes some information on the distribution of key permafrost landforms (see also Section 5.3.2.1), but there is no complete systematic mapping of permafrost landforms at this scale.

The occurrence of subsea permafrost has been demonstrated by several geophysical studies involving drilling on the Siberian, Chukchi and Beaufort shelves but data are mostly unpublished. Subsea permafrost occurs in the continental shelves of the Arctic Ocean adjacent to Russia (Figure 5.5), Alaska, Canada, Greenland, and Svalbard (Baranov, 1960; Vigdorchik, 1980; Osterkamp, 2001) where it is likely to exist beneath depths of water of up to 100 m (Mackay, 1972; Osterkamp and Harrison, 1982; Osterkamp and Fei, 1993; Hinz et al., 1998). Due to changes in sea level and to shoreline erosion, the present configuration of subsea permafrost in the Beaufort Sea resembles a wedge or tabular sheet extending from the Arctic Ocean coast down to 100 m water depth, a distance of up to 100 km (Osterkamp and Fei, 1993). On the huge Siberian shelf, the 100 m water depth may be over 700 km offshore (Romanovskii et al., 1998).

5.2.2.2. Recent changes in permafrost temperature, and active-layer thickness and extent

5.2.2.2.1. Recent changes in permafrost temperature

A recent coordinated field campaign conducted during the International Polar Year (2007/2008) collected permafrost temperature data throughout the Arctic (Romanovsky et al., 2010b) and enhanced the existing permafrost monitoring network by establishing more than 300 new permafrost boreholes. This recent snapshot (Christiansen et al., 2010; Romanovsky et al., 2010a; Smith et al., 2010; Figure 5.6) shows a general decrease in permafrost temperature with increasing latitude although this relationship varies regionally. For example, the influence of warm ocean currents on the climate of northern Scandinavia, Svalbard and northwestern




Figure 5.5. Extent of subsea permafrost distribution (orange), superimposed on bathymetry. Map based on Brown et al. (1998). Note: see Figure 5.2 for details of terrestrial permafrost.




Figure 5.6. Mean annual ground temperature (MAGT) determined at the depth of zero annual amplitude, or the nearest adjacent measurement point during the International Polar Year. Source: Romanovsky et al. (2010b).

Russia (McBean et al., 2005) results in higher permafrost temperatures in these regions compared to other High Arctic regions at a similar latitude. In the discontinuous permafrost zone, permafrost temperatures fall within a narrow range, with mean annual ground temperatures at the level of zero annual amplitude being generally warmer than -2°C . However, there is still much spatial variability within this zone due to the variability of local factors such as snow cover, vegetation and the presence of an insulating (organic) layer (Smith et al., 2010; Romanovsky et al., 2010a). A greater range in permafrost temperature is found within the continuous permafrost zone where mean annual ground temperature can be as low as -15°C in the High Arctic, although permafrost at temperatures below -10°C is only presently found at monitoring sites in the Canadian Archipelago and northern Russia.

Over the past two to three decades, there has been a general warming of permafrost across the circum-Arctic permafrost region (Lemke et al., 2007; Romanovsky et al., 2007; Brown and Romanovsky, 2008). Observations from permafrost monitoring sites throughout the Northern Hemisphere, including North America (e.g., Smith et al., 2005a, 2010; Osterkamp, 2008), Russia (e.g., Malkova, 2008; Oberman, 2008; Romanovsky et al., 2008a, 2010a) and Scandinavia (Harris and Isaksen, 2008; Christiansen et al., 2010) generally indicate that the magnitude of the increase in permafrost temperature varies regionally. The magnitude has typically been between 0.5 and 2°C at the depth of zero annual amplitude since the late 1970s (Figure 5.7). Warming rates have been much lower for warm ice-rich permafrost at temperatures close to 0°C than for colder permafrost ($< -2^{\circ}\text{C}$) or bedrock (Romanovsky et al., 2010b). Overall, the range in permafrost temperature is about 1°C





Figure 5.7. Ground temperature at depths between 10 and 20 m for boreholes across the circumpolar northern permafrost regions (Romanovsky et al., 2010b). Data sources are as follows: North America (Smith et al., 2010), Russia (Romanovsky et al., 2010a) and Svalbard (Isaksen et al., 2007b; Christiansen et al., 2010).

smaller than 30 years ago (Romanovsky et al., 2010b).

Variability in the rate of temperature change is exemplified in Alaska and the Mackenzie valley region of the Northwest Territories Canada, a region which has experienced an increase in air temperature of about 1.5 °C over the past century. Permafrost temperatures at depths of 10 to 20 m in this region have increased by a few tenths of a degree per decade in the south and central area and about 1 °C per decade in the north (e.g., the Arctic Coastal Plain, Mackenzie Delta region) since the 1980s (Kanigan et al., 2008; Osterkamp, 2008; Romanovsky et al., 2008b; Smith, et al., 2005a, 2010; Burn and Kokelj, 2009). Ground temperatures measured recently at Herschel Island, Yukon, and associated modeling suggest that permafrost temperature at 20 m depth may have increased by 1.9 °C over the past century (Burn and Zhang, 2009). However, there has been a decrease in the rate of permafrost temperature increase in western North America since 1998 (Smith et al., 2010), a year with the warmest air temperatures on record for this region. In general, air temperatures have been lower since 1998 and the ground temperatures have shown a similar pattern. The smaller increases in permafrost temperature observed in the more southerly areas where permafrost is thinner and at temperatures close to 0 °C, are due to latent heat effects, associated with phase changes (thawing and freezing), that dominate the ground thermal regime (especially where permafrost is ice-rich) (Smith et al. 2005a, 2010; Romanovsky et al., 2010b).

In the colder permafrost (about -15 °C) of the High Arctic tundra, ground temperatures are more responsive to changes in air temperature due to the lack of a buffer layer (little vegetation, thin snow cover) and the lack of phase changes. At Alert, Nunavut, permafrost at a depth of 15 m warmed by about 0.1 °C per year between 1994 and 2002 (Smith et al., 2003, 2005a) in response to warmer air temperatures and more recent observations indicate that this trend is continuing (Smith et al., 2010). These observations are consistent with those of other Arctic areas such as Scandinavia and Svalbard where recent increases in shallow ground temperatures have also been observed (Isaksen et al., 2007a,b; Harris and Isaksen, 2008; Johansson et al., 2008; Christiansen et al., 2010).

An increase in climatic variability (both extremely cold

and extremely warm years) occurred in European Russia during the past decade. This led to a considerable increase in permafrost temperatures. In the Russian European North and in northwestern Siberia, temperatures at the depth of zero annual amplitude generally increased between 1974 and 2007. Increases of up to 2 °C occurred at colder permafrost sites and up to 1 °C at warmer permafrost sites (Brown and Romanovsky, 2008; Oberman, 2008; Romanovsky et al., 2008b, 2010a).

The very limited data available show that permafrost is actively degrading within submerged Arctic shelves (Zhigarev, 1997; Rachold et al., 2007) under both the thermal and chemical impact of overlying seawater. However, the rate and exact location of this degradation are mostly not known.

5.2.2.2.2. Recent changes in active-layer thickness

Recent results from high-latitude Arctic sites within the Circumpolar Active Layer Monitoring (CALM) program (see Appendix 5.1), indicate substantial interannual fluctuations in ALT, primarily in response to variations in summer air





Figure 5.8. Distribution of northern hemisphere CALM sites (see Figure 5.4 for detailed permafrost map) and examples of the trends in active-layer thickness at a selection of sites (indicated by red dots). The active-layer measurements were obtained from bedrock, sediment and organic-rich sites. Site numbers correspond to the CALM nomenclature and the entire CALM data archive is available at www.udel.edu/Geography/calm/data/data-links.html.

temperature (e.g., Smith et al., 2009a; Popova and Shmakin, 2009; Figure 5.8). Decadal trends in ALT vary by region. A progressive increase in ALT has been observed in some Nordic sites (e.g., Akerman and Johansson, 2008), northeastern Greenland (Christiansen et al., 2008), the Russian European North (e.g., Oberman and Mazhitova, 2001; Mazhitova et al., 2008), eastern Siberia (e.g., Fyodorov-Davydov et al., 2008), and Chukotka (e.g., Zamolodchikov et al., 2008). Disappearance of permafrost over the past few decades has been reported at several lower latitude Arctic sites, including Nordic (e.g., Akerman and Johansson, 2008), Canadian (e.g., Smith et al., 2008a), and European Russian (e.g., Mazhitova et al., 2008; Oberman, 2008) sites, that are mainly peatlands in the sporadic and discontinuous zones. In eastern Siberia, the observed changes in ALT have resulted in degradation of the ice- and organic-rich transient layer on top of permafrost (Shur et al., 2005).

Trends in ALT are different for North American sites. A progressive increase in ALT is evident only at sites in the Alaskan interior, where in 2007 the maximum ALT for the 18-year observation period occurred (Viereck et al., 2008). Active-layer thickness at the Alaskan North Slope and northwestern Canadian Arctic sites is relatively stable, without pronounced trends during the 1995 to 2008 period (e.g., Streletskiy et al., 2008; Smith et al., 2009a).


Active-layer thickness varies between years and extremely warm years can result in greater increases in ALT. In the maritime High Arctic Nordic CALM site in Svalbard, interannual variation was as high as 30 cm during an eight-year period (Christiansen and Humlum, 2008). Canadian monitoring sites showed responses in ALT, consistent with those of other cryospheric components, to the extreme warming in 1998 that resulted in a longer thaw season (Atkinson et al., 2006). The greatest increases in thaw occurred at the more northerly sites, especially those lacking a vegetation cover or an organic surface soil layer (Smith et al., 2009a).

5.2.2.2.3. Recent changes in permafrost extent

A new study, published since the Arctic Climate Impact Assessment in 2005 (ACIA, 2005), has addressed regional permafrost changes in the Russian European North (Oberman and Liygin, 2009). This covered a wide area and included a variety of bioclimatic, topographic and permafrost conditions as well as all three permafrost zones, while providing unique information on recent dynamics of the frozen ground during the 1970 to 2005 period.

Observations during the 1970 to 2005 period at some sites in this region indicate significant (by several metres) thawing of the permafrost in the uppermost near-surface layer. In addition to these changes in permafrost thickness, the area underlain by permafrost has also decreased. The permafrost boundary shifted northward by 30 to 40 km in the Pechora lowlands and up to 80 km on the foothills in the eastern part of the region (Figure 5.9). Large areas in the discontinuous and southernmost part of the continuous permafrost zones have been affected by thawing. This has led to deepening of existing taliks and to the formation of new ones. As a result, the boundary of continuous permafrost has moved northward by 15 to 20 km in the lowlands and by 30 to 50 km in the foothills.

Similar observations have been made in eastern Canada (Quebec) where the southern boundary of the permafrost has shifted northward by 130 km during the past 50 years (Thibault and Payette, 2009). Permafrost has degraded since 1957 at sites in the sub-Arctic peatlands of northern Quebec, with the rate of loss increasing to 5.3% per year since 1993 (Payette et al., 2004). In one location, the area occupied by palsas decreased by 23% between 1957 and 2001 (Vallée and Payette, 2007). In western Canada, permafrost has degraded over the last 100 to 150 years at five southern sites, with the degradation ranging between 30% and 65%, while as much as 50% of permafrost in



peat plateaus thawed over 50 years at four sites in the northern part of the discontinuous permafrost zone of the Mackenzie Valley (Beilman and Robinson, 2003). In Tanana Flats, central Alaska, areas with thermokarst fens and bogs increased from 39% to 47% of the area over 46 years (Jorgenson et al., 2001).

5.2.2.3. Factors controlling the current state and dynamics of permafrost

5.2.2.3.1. Terrestrial permafrost

Changes in permafrost temperature and active-layer thickness are generally consistent with trends in air temperature. While past air temperature has been important for the formation of permafrost, current air temperature is important for the continuing existence of permafrost, since air temperatures below freezing are required to keep the ground from thawing. Variations in snow cover are also an important driver of permafrost temperature: warming of permafrost in the late 1980s and early 1990s in Alaska, for example, may be mainly due to a series of thicker snow covers (Osterkamp, 2008). In the High Arctic, changes in snow cover were found to counteract changes in air temperature. As a result, permafrost temperature may rise during periods of lower air temperature if more snow occurs (Taylor et al., 2006).

The presence of a surface buffering layer (including a peat layer) as well as ice-rich material can be important factors that lead to persistence of permafrost through warming events. For example, ground ice with an age of 740 ky BP found in the central Yukon Territory (northwestern Canada) may have persisted within the discontinuous zone through several interglacial cycles and exposure to warmer climates (Froese et al., 2008). Permafrost at temperatures close to 0 °C is also observed in the peatlands of the southern part of the permafrost zone that has persisted through the warming following the Little Ice Age, due to the insulation provided by the peat (Smith et al., 2008a; Kokfelt et al., 2010). The importance of organic layers influencing the response of permafrost to climate change has also been explored in modeling studies (Woo et al., 2006b, 2007; Yi et al., 2007; Lawrence et al., 2008). Model results suggest that the increase in thaw will be lower in response to climate warming in areas with an insulating organic layer. Thus, peat could preserve permafrost against the projected warming in many northern areas. However, higher resilience of permafrost protected by a thick organic layer can be threatened by various natural and human-induced surface disturbances, such as forest, tundra, or peatland fires and agricultural or engineering activities (e.g., Viereck et al., 2008; Smith et al., 2008a). Surface geomorphological processes, such as erosion, thermal erosion, various slope processes, and thermokarst, may also destroy this protective organic layer and dramatically accelerate permafrost degradation in the areas affected (Kokelj et al., 2009; Jorgenson et al., 2010).

5.2.2.3.2. Subsea permafrost

Most Arctic subsea permafrost is inundated relict terrestrial permafrost. There are some exceptions, for example the refreezing of freshwater river discharge onto the cryotic seabed, or the formation of permafrost in areas such as deltas, where sediment accumulation raises the seabed close to the water

surface, permitting bottom-fast ice formation in winter. Since this depends on local conditions, these exceptions are limited in spatial extent.

Once the previous coastal terrestrial areas are inundated, ground temperature and salinity at the current seabed are controlled by sea ice dynamics and the temperature regime of the sea bottom water. In most locations, the sea-ice dynamics are assumed to be relatively stable at seawater temperatures just below 0 °C.

5.2.3. Projections of future permafrost states

Global circulation models project a 1.4 to 5.8 °C increase in global air temperature during the 21st century (ACIA, 2005) with an increase of 3 to 6 °C projected for the Arctic by 2080 (see Chapter 3, Section 3.2). This warming would induce permafrost degradation (i.e., thawing of the frozen ground, thickening of the active layer, and a reduction in spatial extent).

Permafrost projections differ in geographical extent and spatial resolution, and depend largely on the resolution of the forcing climatic and environmental parameters (soil, vegetation etc.), and on the permafrost model used. Several types of permafrost model of different complexity, computational design, and data requirements have been developed and used in various applications. A survey of permafrost modeling approaches was reported by Riseborough et al. (2008). See also Box 5.1.

Over the past decade, several studies have projected the impacts of climate warming on permafrost in the 21st century. Most ACIA (2005) projections were equilibrium projections as they assumed that the ground thermal regime is in equilibrium with the current atmospheric climate (Box 5.1). A major recent advance has been to simulate ground temperature dynamics such that the transient changes of permafrost can be projected (Box 5.1). The following sections report Arctic-wide and regional projections.

5.2.3.1. Arctic-wide permafrost projections

The GIPL2/MPI (Geophysical Institute Permafrost Lab, University of Alaska Fairbanks) parallel transient model (Marchenko et al., 2008, 2010) was used to assess possible changes in permafrost thermal state and active-layer thickness for the entire northern hemisphere permafrost domain. Input parameters to the model include spatial datasets of mean monthly air temperature and precipitation, prescribed vegetation, and thermal properties of the multi-layered (500 m in depth) soil column and water content (which are specific to each vegetation and soil class, and to geographical location). An ensemble of five IPCC GCMs was used for climate forcing, most of which were among the best-performing models for the Arctic and sub-Arctic (see Chapter 3): ECHAM5, GFDL21, CCSM, HADcm and CCCMA (based on the A1B emissions scenario). The model output has been scaled to a horizontal resolution to 0.5° latitude and longitude. According to this specific climate scenario, projections of future changes in permafrost suggest that by the end of the 21st century, late-Holocene permafrost in the Northern Hemisphere may be actively thawing at the southern boundary of the permafrost domain and Late Pleistocene permafrost could start to thaw at some locations (Figure 5.10). However, there is some cold

Box 5.1. Permafrost modeling approaches

Permafrost models link climate, particularly air temperature and precipitation, with the state of the frozen ground, which is typically characterized by ground temperature and the depth of maximum seasonal thawing (active-layer thickness). Soil and vegetation properties largely govern this relationship, and most permafrost models include them explicitly.

There are two conceptually different modeling approaches: one based on ‘equilibrium models’ and the other based on ‘transient models’. Equilibrium models are relatively simple and assume that the ground thermal regime is in equilibrium with the atmospheric climate thus neglecting the time lag between climatic forcing and its impact on the frozen ground. Such models have relatively low data requirements, using mean monthly temperature and precipitation data as climatic forcing together with a few edaphic parameters characterizing soil thermal properties, snow and vegetation. Owing to their computational design and inherent limitations, such models may only be used to describe active-layer thickness and temperature in the uppermost near-surface permafrost layer. Despite these limitations, equilibrium models have been employed in many studies to construct permafrost projections at a variety of geographical scales, from regional to hemispheric (Sazonova et al., 2004; Anisimov and Reneva, 2006; Sushama et al., 2006; Saito et al., 2007; Duchesne et al., 2008; Marchenko et al., 2008; Romanovsky et al., 2008a). Results obtained with this type of model are referred to as ‘equilibrium permafrost projections’ later in this chapter.

More advanced, transient models simulate the dynamics of the ground temperature regime and seasonal thawing/freezing, so that transient responses of permafrost to changing climatic and environmental conditions may be projected. Computationally, they are much more expensive than equilibrium models, and in most cases require additional climate forcing data, such as solar radiation, wind, cloudiness, and air humidity at a daily or monthly resolution. The most sophisticated models of this type include dynamically coupled blocks that calculate changes in soil moisture and thermal properties at every time step rather than using prescribed constant soil-specific values for these parameters, as is the case in equilibrium model calculations. Although transient models have high predictive capacity, their application is limited, particularly over large regional and hemispheric

scales, because many of the necessary forcing data are often unavailable (Zhang et al., 2008a,b).

An inherent limitation of conventional equilibrium and transient models is their deterministic nature, which contrasts with actual permafrost parameters that are intrinsically stochastic and largely governed locally by small-scale variability in soil, vegetation, snow parameters, and topography.

Many potential applications of permafrost models, such as cold-region engineering, require probabilistic metrics. A new type of stochastic permafrost model has thus been developed recently, this is known as a ‘probabilistic permafrost model’. Unlike conventional models, they calculate statistical ensembles representing potential states of permafrost under prescribed conditions (Anisimov et al., 2002; Anisimov, 2009). This new methodology is fully harmonized with the ensemble approach that is used to construct probabilistic climatic projections based on results derived from several GCMs. However, it also provides important information that directly addresses the practical needs of stakeholders and may be used in various applications such as the risk assessment of potential infrastructure damage, evaluations of other threshold-driven processes, and impacts associated with thawing permafrost.

The approaches described above are based on stand-alone permafrost models and require independent climatic data. Another approach is to incorporate permafrost directly into GCMs by improving parameterization of the related ground processes (Stendel and Christensen, 2002; Lawrence et al., 2008; Wania et al., 2009): these models are known as ‘coupled models’. However, these generally only consider the upper few metres (3 to 6 m) of the ground and do not adequately consider time lag effects (Burn and Nelson, 2006). This can lead to significant overestimates of permafrost thaw (Burn and Nelson, 2006; Delisle, 2007) as deeper ground should be considered for a more realistic projection (Nicolisky et al., 2007; Lawrence et al., 2008).

A special group of models is that used for mountain permafrost projections. In complex mountainous terrain, vertical and horizontal heat fluxes both play an equally important role in the thermal regime and modeling is undertaken in three-dimensional space.

bias for this particular climate forcing in comparison with the CRU2 dataset, especially for the northwestern Eurasia area (the Russian North). These projections were therefore adjusted in compliance with the CRU2 dataset (Mitchell and Jones, 2005) using the difference between observed, interpolated, and projected climate data during the 1981 to 2000 period.

5.2.3.2. Regional permafrost projections

5.2.3.2.1. Alaska

New and detailed results from modeled permafrost dynamics in Alaska have become available since the Arctic Climate Impact Assessment (ACIA, 2005). The GIPL2 model has been used to investigate how observed and projected changes in

climatic parameters (mainly air temperature and precipitation) influence permafrost dynamics in Alaska (Marchenko et al., 2008). The model was validated using precise ground temperature measurements from shallow boreholes across Alaska (Romanovsky and Osterkamp, 1997).

The model was run at a resolution of 0.5° latitude $\times$ 0.5° longitude spanning the entire Alaskan permafrost domain for the 1900 to 2100 time interval. The CRU2 dataset (Mitchell and Jones, 2005) was used as climate forcing for the period 1900 to 2000. The future climate scenario was derived from the MIT-2D integrated global system model developed at the Massachusetts Institute of Technology (Sokolov and Stone, 1998), using a gradual doubling of atmospheric CO₂ concentration that corresponds to the IPCC A1B emissions scenario.

Ground temperatures were compared at depths of 2, 5,




Figure 5.10. Arctic-wide projections of ground temperature for 2010 (upper), 2050 (middle) and 2090 (lower) using the GIPL-model.

and 20 m for three snapshots in time: 2000, 2050 and 2100 (Marchenko et al., 2008; Figure 5.11). In comparison with present-day conditions, model results show the greatest changes in temperature for the 2050 and 2100 time slices will occur at 2 m depth (Figure 11 top row). By the end of the 21st century, mean annual ground temperatures at 2 m depth could be above 0 °C everywhere southward of 66° N except for small patches at high altitude in the Alaska Range and Wrangell Mountains (Figure 5.11 top right). An area of approximately 850 000 km² (about 57% of the total area of Alaska) could experience widespread permafrost degradation and by 2100 could contain areas in which permafrost will completely disappear in addition to areas where thawing is still ongoing. (The term ‘thawing permafrost’ indicates a depressed permafrost table and a residual thawed layer – ‘talik’ – between the seasonally frozen layer and permafrost table that exists throughout the year.)

According to the model results, the extent of the area with mean annual ground temperatures at 5 m depth above 0 °C in 2000 is approximately 125 000 km² but will be around 659 000 km² (about of 45% of the total area of Alaska) by 2100 and extend into the Alaskan interior (Figure 5.11 middle right). While permafrost temperatures at 20 m depth could change significantly (although remaining below 0 °C), model results suggest the area with mean annual ground temperatures above 0 °C at this depth will increase by less than 100 000 km² between 2000 and 2100 (Figure 5.11 bottom row). Projected changes in permafrost temperature are more pronounced in areas that currently have colder permafrost than those where temperature is presently close to 0 °C or in peatlands with a deep organic layer.

The simulated mean values of active-layer thickness for the whole Alaskan permafrost domain are 0.78, 1.33 and 2.4 m for 2000, 2050, and 2100, respectively. The projected area of thawing permafrost (for areas where the permafrost table is located deeper than 3 m) also increased (Marchenko et al., 2008), from 65 000 km² in 2000, to 240 000 km² by 2050, to 720 000 km² by 2100 (Figure 5.12).

5.2.3.2.2. Canada

Since the Arctic Climate Impact Assessment (ACIA, 2005), several studies have projected permafrost conditions over the 21st century for all or part of Canada. Zhang et al. (2008a,b) simulated permafrost distribution for the whole Canadian landmass at a resolution of 0.5° latitude × 0.5° longitude using a dynamic model driven by six climate change scenarios. Simulated change in near-surface ground temperature was much greater than for deeper layers and the ground thermal regime was in strong disequilibrium with the climate conditions projected for the 21st century (Zhang et al., 2008a). However, thawing of the upper part of permafrost does not imply complete loss of permafrost because changes in deeper ground temperature lag behind those at the surface, as is clear from long-term measurements in deep boreholes (e.g., Osterkamp, 2005).

The upper 2 to 3 m of permafrost is projected to thaw over 16% to 20% of the area currently underlain by permafrost in Canada by the end of the 21st century (Zhang et al., 2008a,b). This is a much smaller estimate than earlier estimates from equilibrium projections, for example, Kettles et al. (1997) had projected a 43% reduction. Permafrost thaw would continue beyond the 21st century even if air temperature stops increasing because of the disequilibrium between deeper ground thermal




Figure 5.11. Projected mean annual ground temperature at 2 m, 5 m, and 20 m depths in 2000, 2050, and 2100 using climate forcing from MIT-2D model output for the 21st century. Source: Marchenko et al. (2008).




Figure 5.12. Projected active-layer thickness and extent of thawing permafrost area in 2000, 2050, and 2100 using climate forcing from MIT-2D model output for the 21st century. Source: Marchenko et al. (2008).

regime and the current climatic conditions. The model results suggest that active-layer thickness would increase significantly, by 0.3 to 0.7 m (or 41% to 104%), and supra-permafrost taliks would appear in many southern regions. About 9% to 22% of land with permafrost in Canada would contain taliks by the end of the 21st century, and the permafrost table would be 1.9 to 5.0 m deeper, mainly due to the formation of taliks. Other modeling studies also suggested the formation of taliks with climate warming (e.g., Delisle, 2007; Duchesne et al., 2008), and taliks have already been observed in some regions (Oberman, 2008). Permafrost thaw would also occur from the bottom up in some southern regions (as observed by Johansson et al., 2008 in northern Sweden). However, concurrent changes in snow conditions (depth, annual duration, timing) with climate change could somewhat mitigate permafrost thaw (Zhang et al., 2008c; Taylor et al., 2006).

Changes in ground thermal regime in northeastern Canada from the present (1961 to 1990) to the future (2041 to 2070) were simulated by Sushama et al. (2006) at a 45×45 km resolution using a one-dimensional heat conduction model (Goodrich, 1982) driven by surface temperature and snow depth from the Canadian Regional Climate Model (Laprise et al., 2003). Sushama and co-workers projected significant warming in near-surface ground temperature and an increase in active-layer thickness of more than 50% over most of the continuous permafrost region in northeast Canada. Duchesne et al. (2008) simulated permafrost conditions for the Mackenzie River Valley at a higher spatial resolution (1×1 km) and results suggested that permafrost degradation would occur mainly through deepening of active-layer thickness and the development of taliks.

Woo et al. (2007, 2008) used a probabilistic approach to project the range in thaw depth that would occur in response to climate warming over the 21st century in the Mackenzie Valley region, an area where recent increases in air temperature have been the greatest. The results for the boreal and tundra environments indicate that thaw depth will increase 15% to 40% over the 21st century in response to warming, with smaller increases occurring where a thick organic layer is present (Woo et al., 2007).

There has been limited exploration of climate change impacts on mountain permafrost within the polar regions. The distribution of permafrost in mountainous areas is particularly complex (e.g., Lewkowicz and Ednie, 2004). Within the Yukon Territory of Canada the existence of mountain and latitudinal permafrost is difficult to delineate as permafrost may exist at sea level in this region. Advances have been made in recent years to model and map the current distribution of mountain permafrost over this extensive region at high resolution (Lewkowicz and Ednie, 2004; Bonnaventure and Lewkowicz, 2008; Lewkowicz and Bonnaventure, 2008). An empirical stochastic model was developed by Haeberli (1973) based on topographic parameters and snow cover (known as the Basal Temperature of Snow (BTS) method). This work has now been extended to include the effects of climate change and to characterize the sensitivity of mountain permafrost within three basins in the Yukon Territory to warming and to project future equilibrium permafrost distribution (Bonnaveure and Lewkowicz, 2010). Increases in mean annual air temperature of up to 5°C were considered in the analysis and results

suggest climate change could have significant impacts on permafrost extent and spatial distribution in the southern Yukon area indicating loss of permafrost in two of the three basins considered.

5.2.3.2.3. The Nordic Area

Lowland permafrost is rare in Fennoscandia but exists in the northern parts of Norway, Finland and Sweden mainly as palsa mires. The spatial distribution of palsa mires in sub-Arctic Fennoscandia is highly correlated with air temperature and precipitation patterns (Luoto et al., 2004a). Fronzek et al. (2006) developed a correlative model using climate-envelope techniques to simulate areas climatically suitable for palsa mires as a function of monthly temperature and precipitation. Results indicated that it was likely ($>66\%$) that palsa mires would disappear completely by the end of the 21st century under scenarios of medium (A1B scenario) and moderately high (A2 scenario) greenhouse gas emissions (Fronzek et al., 2010). For a low emissions (B1) scenario, it was more likely than not ($>50\%$) that conditions over a small fraction of the current palsa distribution could sustain palsas until the end of the 21st century.

Most of Fennoscandia has alpine topography. However, overall changes in permafrost distribution have to date only been modeled on the basis of air temperature (Figure 5.13) (Harris et al., 2009). In Svalbard, Isaksen et al. (2007a) demonstrated recent warming and showed that the extreme year of 2006 lies at the upper percentile of projected climate scenarios for the area. A one-dimensional heat flow model was calibrated with high accuracy, and forced by a suite of empirically downscaled IPCC AR4 GCMs (Benestad, 2007). The model results projected a warming of permafrost, and the development of a significantly thicker active layer and taliks both in bedrock and sedimentary material by 2100 (Etzelmüller et al., 2011). For Iceland, future climate change impacts on permafrost are represented by a sensitivity study for increased temperatures and snow cover based on four shallow boreholes. As in the Scandinavian mountains, Iceland experiences relatively warm permafrost close to the thawing point due to high geothermal activity, a maritime climate and associated snow cover. Even small changes in temperature and snow cover almost immediately result in degradation of permafrost in the mountain settings (Etzelmüller et al., 2007, 2008; Farbrót et al., 2007). High geothermal gradients in Iceland restrict the thickness of permafrost, and facilitate a faster response to climate change than in Svalbard or the Scandinavian mountains.

5.2.3.2.4. Russia

New projections of future changes in permafrost in the Russian European North (Marchenko et al., 2009, 2010; Stendel et al., 2010) have a horizontal resolution of only 4 km. Averaged data for the period 2030 to 2049 suggest significant change (Figure 5.14) and project that by the end of the 21st century, late-Holocene permafrost may be actively thawing at all locations within the Pechora River catchment. Also, some Late Pleistocene permafrost to the north of the Pechora River catchment could start to thaw in some locations. The model results also show how different types of ecosystem affect the stability and thermal state of permafrost.




Figure 5.13. Projected changes in permafrost within the Nordic countries based on changes in air temperature. The effects of snow cover and topography are not considered. Source: compiled by the University of Oslo (UiO), Norway, based on data provided by UiO, the Norwegian Meteorological Institute, the University Centre in Svalbard, and the Geological Survey of Norway.

Oberman and Liygin (2009) used a statistical model linking air and ground temperatures to construct regional permafrost projections for 2020. The model was validated using permafrost monitoring data from a large number of observational sites and boreholes in the north European part of Russia. The forcing climate scenario was based on an extrapolation of air temperature trends calculated for the 1970 to 2005 period from observations at weather stations.

Results project more pronounced changes in permafrost in the eastern part of the study region by 2020 (Figure 5.15) with ground temperature increasing by 0.6 to 1.0 °C. This is consistent with the projected pattern of changes in air temperature. It is also consistent with the dominance of coarse grained soils and bedrocks that have relatively high thermal conductivity and are therefore more responsive to climatic warming than other soil types.

5.2.3.2.5. Model inter-comparison challenges

Results of predictive permafrost models presented in this section reflect a wide range of geographical scales, from the pan-Arctic to the local scale. Although the models differ conceptually in complexity and level of detail, most may be applied at a range of scales if the forcing data are available. For a given level of data availability, there is an optimal range in model complexity beyond which there is a reduction in predictive performance. There are either too many parameters required by the model and an inadequate amount of empirical information to uniquely identify these parameters, or the model is too simple to account for important processes and to fully exploit available empirical information. The interplay between data availability and complexity of computational algorithm is a key constraint in seamless predictive permafrost modeling and model intercomparison.




Figure 5.14. Modeled mean annual ground temperature for the Pechora River catchment, Russia, at the bottom of the active layer (upper) and active-layer thickness and seasonal frost penetration (lower) for 1980 to 1999 (left) and averaged for 2030 to 2049 (right). The results are derived from the GIPL-1.3 equilibrium permafrost model run using the 4×4 km HIRHAM5 climate scenario. Source: Stendel et al. (2010).

5.3. Impacts of changes in permafrost distribution and extent

- Recent analyses indicate contrasting changes in hydrology in permafrost regions over past decades: landscape dryness is increasing in the boreal forest, particularly in areas of discontinuous permafrost, whereas some sub-Arctic areas are experiencing waterlogging when permafrost thaws.
- Biodiversity and ecosystem processes on land and in freshwaters are being affected by changes in hydrology. Recent studies show that thawing of ice-rich permafrost is leading to the draining of wetlands resulting in a loss of habitat in some areas whereas in others, thawing permafrost is leading to impeded drainage and a shift in biodiversity to wetland vegetation. Thaw slumping may affect ecosystems sooner than air warming alone.
- Since the Arctic Climate Impact Assessment was published in 2005, new research has demonstrated the viability and diversity of organisms preserved in ancient permafrost.
- New measurements and estimates of soil carbon pools in permafrost indicate that there is more soil carbon in permafrost than previously thought. This carbon is likely to play a more important role in feedbacks to climate during permafrost thawing than earlier calculations suggested.
- Very high emissions of the powerful greenhouse gas nitrous oxide have recently been discovered from terrestrial permafrost in Arctic regions. Although the importance of the process cannot be generalized across the Arctic, the strong radiative forcing potential of the gas suggests important potential contributions to climate forcing.
- High concentrations of subsea CH_4 from the Laptev Sea have recently been recorded throughout the water column and in the atmosphere. Although more measurements are needed from other seas with different permafrost shelf conditions, the current observations reinforce concerns about a major feedback to the climate system from thawing and destabilization of subsea permafrost.
- Recent studies at some locations in the Arctic show




Figure 5.15. Changes projected in permafrost by 2020 in the Russian European North. Source: Oberman and Liygin (2009).

increases in thermokarst development which are specifically important where ice-wedges degrade or palsas (peat mounds with a frozen core) decline. Permafrost degradation is also found likely to increase slope instability by increasing the amount of rockfalls and rockslides, and to increase rates of rock glacier movement. In areas with coastal permafrost, warming of permafrost may also increase coastal erosion.

- Although there has been limited scientific evidence to date that observed climate warming has been the direct cause of failure of engineering structures on permafrost, new studies are suggesting that this effect is sometimes important.

5.3.1.1. Hydrological processes and responses to thawing permafrost

Hydrological processes considered in this chapter concern the direct impacts of thawing permafrost at the landscape level, but not consequences for river flow as these are addressed in Chapter 6.

5.3.1.1.1. Interactions between hydrological processes and permafrost

Important hydrological processes in the terrestrial Arctic include snow and rainfall precipitation, redistribution of snow by strong wind, snowmelt, damming of snowmelt runoff by the snowpack, surface storage in small depressions and ponds, infiltration and storage in the substrate (e.g., soil), evaporation, transpiration, and runoff (Woo, 1986). The primary control on local hydrological processes is dictated by the presence or

absence of permafrost, but they are also influenced by the thickness of the active layer and by the total thickness of the underlying permafrost. As permafrost becomes thinner or decreases in areal extent, the interaction of surface and sub-permafrost ground water processes becomes more important.

The inability of soil moisture to infiltrate deeper groundwater zones due to ice-rich permafrost, maintains very wet soils across the Arctic region in general, and particularly in flat areas and where the frozen layer is near the ground surface (Kane et al., 2004). Although not common, drought conditions have been observed in Arctic Alaska (Kane et al., 2008). These very dry conditions accompanied unusual environmental responses, which included low or no flow in small rivers and the very uncommon occurrence of tundra fire due to the exceptionally dry surface organic layer together with an increased frequency of lightning (Mack et al., 2011). These areas have relatively high evapotranspiration and sensible heat transfer, and a low conductive heat transfer due to the insulative properties of thick organic soils. In contrast, in the slightly warmer regions of the sub-Arctic, the thinner or discontinuous permafrost and permafrost-free areas often have quite dry surface soils as soil moisture infiltration is not as restricted. Whether the surface soils are wet or dry greatly affects ecosystem dynamics, fire frequency, the surface energy budget through latent and sensible heat fluxes, and biogeochemical cycling (including trace gas feedback to the climate system).

Short-term active-layer dynamics and longer-term permafrost dynamics affect water storage and run-off. As the climate warms, the active layer thickens, and there is

greater storage capacity for soil moisture and greater lags and delays introduced into the hydrological response times to precipitation. When the permafrost is very close to the ground surface, stream and river discharge peaks are higher and base flow is lower. As permafrost becomes thinner, there can be more connections between surface and subsurface water. As permafrost extent decreases, there will be more infiltration to groundwater and the timing of stream runoff will change. Permafrost degradation will result in increased winter stream flows, decreased summer peak flows, and changes in stream water chemistry. Thawing permafrost is also associated with several geomorphological processes, some of which (e.g., talik formation and thermokarst, as described in the following section) are hydrologically important as they permit drainage of soil moisture throughout the year, promoting drying of the surface.

5.3.1.2. Recent changes in landscape hydrology due to permafrost thaw

A number of recent analyses indicate that landscape dryness has increased in some areas of the Arctic whereas in others it has decreased. Landscape dryness has increased over the past several decades in the boreal forest, particularly in areas of discontinuous permafrost (Yoshikawa and Hinzman, 2003; Smith et al., 2005b; Riordan et al., 2006; Bunn et al., 2007; Goetz et al., 2007; Figure 5.16). In the southern discontinuous permafrost zone of western Siberia, Smith et al. (2005b) reported an 11% to 13% decrease in lake area between 1973 and 1998. Also, in sub-Arctic areas in Alaska, historical aerial photographs have been used to document a decrease in waterbodies due to subsurface drainage or tapping of thermokarst lakes and other factors (Yoshikawa and Hinzman, 2003; Riordan et al., 2006). Drainage of thaw lakes in the western Canadian Arctic between Inuvik in the Northwest Territories and the Beaufort Sea may

be related to melting of channels through ice-rich permafrost. Retrogressive thaw slumps could also trigger lake drainage and Lantz and Kokelj (2008) have noted that slump activity in the region has increased since 1950, probably due to warming temperatures. Slumping may also be promoted through the expansion of taliks (which could increase with warmer lake temperatures) adjacent to the lakes and the increase in ground temperature that results from the disturbance of the organic mat that accompanies the initial slump (Kokelj et al., 2009).

Although warmer conditions associated with climate warming might be expected to result in increased permafrost thawing and increased lake drainage, there appears to be a complex interaction between climate, ice-wedge cracking, retrogressive thaw slumps and lake hydrology (Marsh et al., 2009). As a result, in contrast to drying of thermokarst lakes, some areas are currently experiencing waterlogging when permafrost thaws, such as in sub-Arctic Sweden (e.g., Johansson et al., 2006; Figure 5.17). Using Landsat satellite imagery Smith et al. (2005b) reported a 12% increase in lake area in the continuous permafrost zone in western Siberia between 1973 and 1998. Also, Walter et al. (2006) reported a 15% increase in lake area near Cherskii, Russia. In the Altai Mountains in Siberia, lake area increased by 52% between 1952 and 2007, with the greatest increase after 1972 (Borodavko, 2009). In northwest Canada, Plug et al. (2008) found both large increases and large decreases in lake area over time, and found also that lake area was strongly dependent on cumulative precipitation in the preceding 12-month period.

5.3.2. Geomorphological processes

Geomorphological processes change the land surface affecting human habitability, natural resources, and ecosystem function. Knowledge of the interactions among the different geomorphological processes and permafrost dynamics is crucial for facilitating adaptation to changes and impacts of




Figure 5.16. Drying of thermokarst lakes in (a) Alaska (Yoshikawa and Hinzman, 2003) and (b) Siberia (Smith et al., 2005b).




Figure 5.17. Waterlogging in areas with thawing permafrost in sub-Arctic Sweden – a comparison between the situation in 1970 (upper plot) and in 2000 (lower plot). Source: Christensen et al. (2004).

these processes. Although some geomorphological responses to thawing permafrost can potentially create local hazards, the importance of this field of study is only recently being recognized and significant attempts are being made to monitor the different geomorphological processes addressed here.

5.3.2.1. Thermokarst

5.3.2.1.1. Thermokarst landforms and processes

Thermokarst is a general term relating to the melt of ground ice and the very irregular surface landforms produced through

permafrost degradation. Thawing can be controlled by natural or human-induced geomorphical, vegetational or climatic processes (French, 2007). These processes are capable of rapid and extensive modification of the landscape.

Permafrost degrades in a continuum from rising temperatures in frozen ground (which increase the unfrozen water content and reduce the load-bearing strength of the ground) to complete thawing of ice-rich ground (which causes the surface to subside and creates depressions in the ground, termed ‘thermokarst’). The types of thermokarst landforms and their ecological implications are extremely variable depending on climate, topography, soil texture, hydrology, amounts and types of ground ice, and heat transfer mechanisms (Figure 5.18). These landforms and processes generally occur at mean annual air temperatures as high as +2 °C, and as low as -20 °C in the High Arctic, and vary greatly in completeness of degradation. Thawing can occur downward from expansion of the active layer, laterally from water and radiation, internally from groundwater intrusion, and upward from the bottom due to geothermal heat flux.

Lateral degradation from an expanding deep thermokarst lake in continuous permafrost, leads to talik formation and intermediate degradation, but complete degradation of permafrost is rare because of the thickness of the permafrost. In contrast, lateral degradation from a thermokarst lake in the discontinuous zone quickly leads to complete degradation because permafrost is thinner. At least 22 thermokarst landforms have been differentiated (Jorgenson and Osterkamp, 2005) and they can be at various stages of degradation and stabilization (Burn and Smith, 1990; Leibman and Kizyakov, 2006; Jorgenson et al., 2008; Veremeeva and Gubin, 2008).

The number and extent of hillslope thermokarst landforms (e.g., active-layer detachment slides and thaw slumps) have been quantified recently using aerial photographs (Lantuit and Pollard, 2008; Lantz and Kokelj, 2008; Gooseff et al., 2009). However, this is difficult because thermokarst landforms range in size from small thermokarst pits to large thermokarst lakes, and surface conditions vary from water to different vegetation structures that confound remote sensing. A regional study for Alaska revealed that within the discontinuous permafrost zone, 5% of the area had thermokarst, 62% had permafrost, 21% was unfrozen with no recent permafrost, and 12% was undetermined (Jorgenson et al., 2008). In the continuous permafrost zone, thermokarst terrain was evident on 13.5% of the area, and 1.5% was unfrozen under deep non-thermokarst lakes. The high prevalence of thermokarst landforms in the colder continuous permafrost region was attributed by Jorgenson and co-workers to the occurrence of massive ice in the form of ice wedges, and to problems differentiating between actively and inactively degrading landforms.

5.3.2.1.2. Changes in thermokarst landforms

Rates of change in thermokarst have frequently been determined using remote sensing of waterbodies because they tend to be spectrally distinct, although detecting trends using only a few periods of moderate-scale Landsat (28 to 80 m) imagery is problematic. Waterbodies have recently both decreased and increased in frequency in the Arctic permafrost regions (see Section 5.3.1.2).



Figure 5.18. Common thermokarst landforms, including (a) thermokarst lakes, (b) retrogressive thaw slump associated with glacial thermokarst, (c) thermokarst fens and bogs, and (d) thermo-erosional gullies. Photographs by M.T. Jorgenson.

Thaw slumps and active-layer detachment slides have been increasing in the Northwest Territories, Canada (Lewkowicz and Harris, 2005; Lantz and Kokelj, 2008; Lacelle et al., 2010), northwestern Alaska (Gooseff et al., 2009), Russia (Leibman, 1995), and along the Arctic coast (Lantuit and Pollard, 2008). In the southern permafrost region of Canada, where most of the permafrost was formed during the Little Ice Age, 9% of the permafrost has degraded into thermokarst bogs and fens since it was formed (Vitt et al., 2000), and field monitoring indicates that lateral rates of thawing are accelerating (Camill, 2005). Across four sites representing different regions in Alaska, aerial photograph analysis revealed that the total area affected by thermokarst increased 3.5–8% over about 50 years (Jorgenson et al., 2008).

Predicting the geomorphological responses of thermokarst terrain to future climate warming is complicated by the complex interaction of biophysical factors. These create strong negative feedbacks from vegetation-soil processes (see Section 5.3.3.2) that make permafrost more resilient to warming and disturbance, as well as positive feedbacks from thaw settlement and water impoundment that make permafrost more vulnerable to warming (Jorgenson et al., 2010). Vegetation-soil feedbacks can reduce deep soil temperature by 7 °C and help permafrost to persist at mean annual air temperatures of up to +2 °C, while water impounded by thaw settlement can increase ground temperature by 10 °C, and make permafrost vulnerable to thawing at mean annual air temperatures as low as -20 °C (Jorgenson et al., 2010). These feedbacks are larger than the projected climate warming of 3 to 6 °C for much of the Arctic, and greatly complicate a prediction of how permafrost will respond to climate warming.

5.3.2.2. Periglacial landforms and processes

Periglacial environments are defined by mean annual air temperatures below 3 °C (or 5 °C in windy regions) and the most important ecological boundary by which they are delimited is the treeline. Periglacial landforms are controlled largely by the presence and thermal state of permafrost, and these landforms are key indicators of changes in permafrost and are also important in determining landscape stability.

5.3.2.2.1. Ice-wedge polygons

Ice-wedge or tundra polygons are probably the most widespread periglacial landforms in lowland continuous and discontinuous permafrost areas (Figure 5.19). Because their borders are underlined by networks of ice wedges, their presence implies large volumes of ground ice near the surface of the terrain (Harry and Gozdzik, 1988). During warming it is likely that the resulting ground thawing of ice wedges will affect permafrost landscapes significantly, leading to disturbed topography and drainage patterns – a first stage in thermokarst development. However, the impact of warming on polygonal terrain is likely to be very variable in the Arctic, depending on regional climatic regimes and local terrain conditions. The ice-wedge responses in the cold continuous permafrost zone will be less pronounced than responses further south, near the boundary between continuous and discontinuous permafrost. Changes in snowmelt that affect the water regime, together with summer precipitation have already led to destruction of ice-wedge networks through thermo-erosion (Fortier et al., 2007). For example, cessation of ice-wedge development

occurred during the 20th century in the Mackenzie Delta region of northern Canada (Kokelj et al., 2007).

The response of ice wedges to climate change is largely controlled through the basic physics of thermal contraction cracking that governs their initiation and growth, in addition to thermally induced seasonal movements of the active layer and upper permafrost (Mackay, 2000). Thermal contraction cracking occurs in the coldest winter periods, when ground temperature drops to -15°C at the top of the permafrost. This typically occurs during cold events, when near-surface rapid atmospheric cooling occurs, and air temperature drops 10 to 20°C (e.g., from -10°C to -35°C) over short periods (Christiansen, 2005; Fortier and Allard, 2005). The fast ground cooling then leads to a rate of ground contraction which exceeds the soil strength, leading the soil to crack open. Although the cracks close to some extent when the ground starts to warm in spring, the cracks remain open until snowmelt, at which point water flows in and freezes, forming ice veins that grow into ice wedges over the years.

Even with the climate warming projected for the coming decades, it is expected that meteorological conditions in the coldest winter months will continue to sustain ice-wedge formation, and that ice-wedge polygons will continue to be active Arctic landforms. However, during warming, the active layer in polygon centers and over ice-wedge tops will probably get deeper by several centimetres or tens of centimetres. Thawing of ice-wedge tops will lead to localized thaw settlement producing deeper troughs along the polygon sides. This settlement will affect vegetation, local drainage, and snow cover distribution in winter, leading to changes in cracking activity, but with no immediate major geomorphological change.

Thawing of ice wedges under cold temperatures in northern Alaska typically causes surface degradation only and rarely leads to the intermediate degradation that is characterized by the formation of a talik (Jorgenson et al., 2006). Also in northern Alaska, thermokarst associated with ice-wedge degradation increased from 0.5% of the land area in 1945 to 4.4% of the land area in 2001, based on aerial photograph analysis of small-scale features (Jorgenson et al., 2006).

Ice-wedge polygons are especially sensitive to thermal erosion induced by the flow of running water in the ice-wedge troughs. Excess surface flow in the short summer period



Figure 5.19. Ice-wedge polygons. Photo: Ulrich Neuman, Kolibri Geo Services



Figure 5.20. Recently eroded tunnel and disturbed topography developed by meltwater from thawing of ice-wedges on Bylot Island, Canada. Photo Michel Allard.

eventually erodes the ice-wedges because of the large amount of heat supply from convection. Tunnels and ditches develop along the ice-wedge networks and lead to ground collapse and very significant terrain disturbances (Figure 5.20) (Fortier et al., 2007) as a first stage in thermokarst development. It is possible that, as the frequency of rapid spring melts and rain events in summer increase, thermo-erosional events over polygonal terrain will occur more often. This is most likely to expose to risk some man-made structures built over ice-wedges such as roads, runways and pipelines.

The frequency of frost cracking will be reduced in the southern part of the permafrost zone as winters become warmer and cooling events occur less frequently, or if a thicker snow cover accumulates that enables insulation of the ground from atmospheric cooling. Field experiments have indeed demonstrated that a thick snow cover (more than 60 to 80 cm) locally prevents frost cracking (Kokelj et al., 2007). However, even under a warmer climate, sites cleared of snow will continue to endure thermal cracking, a process that seriously affects man-made structures such as roads and runways (see Section 5.3.5.1.3).

5.3.2.2.2. Pingos

Pingos are ice-cored hills, typically conical in shape, that grow and persist only in a permafrost environment (Mackay, 1998). They range in height from a few metres to several tens of metres (Figure 5.21) and are found in continuous and discontinuous permafrost regions. Pingos are important biodiversity hot spots (Section 5.3.3.1).

The core of massive ice in pingos is mainly formed by water injected under pressure. Two types of pingos are recognized. First, hydraulic, open system pingos, into which the water is injected by artesian pressure, that is, where a hydraulic gradient in the surrounding terrain would drive groundwater to the formation site (e.g., Ross et al., 2007). Second, hydrostatic, closed system pingos, into which the water is concentrated by pore-water expulsion in the soil. This is caused by permafrost aggradation beneath the bottoms of drained lakes that are underlain by saturated sediments. Hydraulic system pingos are less understood than hydrostatic system pingos, which are abundant in flat plains covered by hundreds of lakes in Canada (e.g., Mackay, 1979, 1998).



Figure 5.21. Four open system pingos in different stages of development at Reindalen, Svalbard, April 2008. The tallest pingo is 30 m high, the closest is 100 m in diameter. Photo: Hanne H. Christiansen.

Observations and a drained lake experiment (Mackay, 1997) have shown that pingos form when a shallow lake suddenly drains due to geomorphological changes, and permafrost aggrades from all directions in the newly exposed sediments of the previously unfrozen lake bottom (a sub-lake talik). Over the years, this builds up the pressures that will concentrate the water into a bulb, pushing the terrain upward over it and creating a mound that will eventually freeze totally, making an ice core. Many tundra lakes drain suddenly when their banks breach due to coastal or fluvial erosion, or when their water flows over ice-wedges and rapidly erodes a drainage outlet by thermo-erosion. Pingos ultimately collapse when cracks on the sides and summits expose the ice core to the warm summer atmosphere; a crater-like depression may develop in the core of the mound, sometimes occupied by a thaw lake; and slumps occur on slopes. Pingo development is a natural cyclical process, with a single cycle taking up to several thousands of years.

The impacts of climate warming on Arctic pingos over the coming decades are difficult to project quantitatively, given the complex interactions between heat exchange and the groundwater under pressure, and local geomorphological controls on different water sources. For hydrostatic system pingos, which still have a lens of pressurized unfrozen water beneath the ice core, a change in their complex internal thermal regime may affect their stability or growth rate. As hydraulic system pingos are controlled by the supply of water from outside the pingo itself, their activity will also largely depend on changes in the surrounding environment. These include changes to glaciers that have an unfrozen zone and can provide the water. However, some controls are non-climatic, for example, springs are often under geological control, and sometimes the activity of geological faults creates feeding channels for the steady water supply needed.

Overall, degradation of collapsing pingos (Figure 5.22) is likely to accelerate and the number of degrading pingos could increase with time, leading to increased thermokarst landscape development. However, continued coastal erosion as well as increased thermo-erosion of ice-wedges are likely to result in the draining of lakes, which will favor permafrost expansion under newly exposed lake beds. Therefore, inception of new pingos is not impossible in regions that will remain cold enough for some time.

5.3.2.2.3. Palsas and peat plateaus

Palsas are peat mounds with a frozen core and located in the southern parts of the permafrost zone (Seppälä, 1988). Declines of palsas, palsa mires and peat plateaus (both extent and abundance) have been observed in North America (Payette et al., 2004; Camill, 2005; Sannel and Kuhry, 2009) and northern Europe (Zuidhoff and Kolstrup, 2000; Luoto and Seppälä, 2003; Akerman and Johansson, 2008; Sannel and Kuhry, 2008) due to a warming climate (see Section 5.2.2). Thermal erosion of palsas and peat plateaus often results in the development of thermokarst lakes (see Section 5.3.2.1).

5.3.2.2.4. Frost weathering

Frost weathering results from freezing and thawing of water within rock or mineral particles (Matsuoka and Murton, 2008) and can lead to rock fractures and slope instability that can create hazards. The 9% volumetric expansion of water as it changes from liquid to solid phase has traditionally been considered the main causal mechanism of frost weathering, although recently the role of ice segregation within certain bedrock lithologies has been recognized as potentially of greater significance (Hallet, 2006). The main difference between the two processes is that volumetric expansion arises from *in situ* freezing of water, whereas ice segregation involves water migration within freezing or frozen ground (Rempel, 2007). Volumetric expansion occurs at the freezing point of the water occupying pores or cracks and requires a high saturation level (>90%) of the rock. In contrast, ice segregation can occur in unsaturated rock. The presence of capillary and adsorbed water with a freezing point below 0 °C allows unfrozen porewater to migrate through partially frozen rock to supply progressive growth of ice lenses. The resulting rock fracture can occur at temperatures considerably below 0 °C (Walder and Hallet, 1985; Akagawa and Fukuda, 1991; Hallet et al., 1991), depending partly on the pore structure (Matsuoka, 2001a). If ice segregation in bedrock permafrost is widespread, there may be considerable potential for significantly increased rock slope instability associated with rising ground temperatures




Figure 5.22. Pingos (indicated by arrows) in ice-wedge polygon terrain on a terrace covered with thaw lakes on Bylot Island, Canada. The eroded pingos along the riverbank and on the island are collapsing. Photo: Michel Allard.

and thickening active layers in a period of climate warming.

Recent experiments simulating a bedrock active layer above permafrost have shown that moist, porous rock (chalk) behaves remarkably like moist, frost-susceptible soil, with both substrates experiencing ice enrichment and fracture/fissuring of near-surface permafrost (Murton et al., 2006). At the start of the experiments, the rock was unweathered and lacked visible fractures. However, after repeated cycles of active-layer freezing and thawing, fractures filled with segregated ice had formed in the transition zone between the active layer and the permafrost (Figure 5.23) due to downward migration of water in summer and upward advance of freezing at the beginning of winter.

The importance of ice segregation relative to volumetric expansion increases with decreasing thermal gradients and increasing duration of freezing (Powers and Helmuth, 1953; Walder and Hallet, 1985). Rempel et al. (2004) suggested that the maximum possible disjoining pressure is governed by the temperature depression below the bulk-melting point, even in the absence of large temperature gradients, and therefore slow ice segregation in bedrock may be possible at greater depths where the frozen permeability of rock limits the actual amount of heave produced. Thus, over long time-scales, ice segregation may be highly significant in frozen steep bedrock slopes, where the presence of ice-rich fractured bedrock may be critically important in releasing rockfalls and rockslides during climate warming and permafrost degradation (Gruber and Haeberli, 2007).

5.3.2.3. Slope processes and permafrost-related geo-hazards

5.3.2.3.1. Rock glaciers and glacier-permafrost interaction

Rock glaciers are characteristic large-scale flow features of frozen rock material that is the geomorphological result of a cold climate, with conditions for permafrost formation in high-relief regions (Humlum, 1999). They are located at the foot of rock free-faces with a high supply of talus and, when active, typically take the form of 20- to 100-m thick tongue- or lobe-shaped bodies, with cascading frontal slopes standing at the angle of repose (Figure 5.24). Rock glaciers may be as much as several kilometres long, but are typically 200 to 800 m measured parallel to the flow direction (Barsch, 1996). Their surface is covered by coarse (0.2 to 5 m) rock fragments, and displays a 1- to 5-m high curving transverse furrow-and-ridge topography. Active rock glaciers typically flow downslope by permafrost creep of the order of 0.1 to 1 m per year (e.g., Barsch, 1996; Haeberli et al., 2006), that is, they are more sluggish than normal glaciers, but are nevertheless highly efficient agents of coarse debris transport (Humlum, 2000).

The limited recent evidence on the effect of climate change on rock glaciers suggests that when rock glacier permafrost temperature approaches 0 °C, the creep rate may increase (e.g., Leonard et al., 2005; Roer et al., 2005; Krainer and Mostler, 2006; Kääb et al., 2007). Presumably, this is because more liquid water will be present within the ice at higher temperatures.

The existing evidence on rock glacier dynamics is, however, conflicting (Janke, 2005), suggesting the importance of several factors in addition to air temperature. These include changes in rockfall intensity and snow avalanche frequency. Climatic

change resulting in increased snow precipitation and increased snow drifting might result in a higher frequency of snow avalanches on leeward slopes. This may result in increased creep rates of rock glaciers lining the foot of such slopes, as snow avalanches represent an important source of water for ice formation in rock glaciers and for the supply of rock debris to those glaciers (Humlum et al., 2007). Rock weathering rates of the bedrock in the headwalls above rock glaciers are controlled by temperature and variations in moisture (and ice) content,



Figure 5.23. Fractures formed by ice segregation in Totternhoe Stone (a type of English chalk) following twenty-four cycles of bidirectional freezing of an active layer above permafrost. The fractures are filled with segregated ice and occur primarily in near-surface permafrost and at the base of the active layer. Some narrow cracks are also visible in the upper part of the active layer, caused by downward freezing from the rock surface. The block is 450 mm high and 300 mm wide. Photo Julian Murton, University of Sussex, UK.



Figure 5.24. Rock glaciers creeping from a cirque (left) and directly from a free face (right) on Disko Island, central West Greenland. The rock glacier to the left is about 1100 m long. The mountains are about 900 m high. Photo: Ole Humlum, University of Oslo, Norway, 8 July 1999.

and climate is thus important for the rock weathering rate and rockfall frequency (Humlum, 1997). Thus, the relation between rock glacier dynamics and climate change is complex, and still only partially understood. It is likely, however, that warming of rock glacier permafrost temperatures to near 0 °C may result in a period of intensified rock glacier creep, promoting increased slope activity.

Observations of fossil rock glaciers in the Faroe Islands (Humlum, 1998) provide empirical evidence for increased rock glacier creep and local instability during periods of warming (in this case the end of the Younger Dryas period). However, the period of increased rock glacier creep ends when the ice bodies have been reduced to a critical thickness.

5.3.2.3.2. Rockfalls

A ‘rockfall’ is the fall of relatively small ($< 10 \text{ m}^3$) fragments of rock debris that are released from bedrock cliffs by weathering, often accumulating to form a talus (Figure 5.25). Rockfall in periglacial environments has been widely attributed to frost wedging, that is, the widening of cracks and joints by ice during freezing and detachment of debris from cliffs during thaw. Rockfalls may also be triggered by stress-release, progressive failure along joints, or build-up of hydrostatic pressure within a rock mass (André, 2003) and some researchers view the role of freeze-thaw in rockfall as relatively trivial.

The timing of rockfalls when freeze-thaw cycles are assumed to be most frequent, particularly during spring thaw (e.g., Rapp, 1960; Luckman, 1976; Coutard and Francou, 1989), remains the main reason for seeing frost wedging as the foremost cause of rockfall in cold environments. In Japan, Matsuoka and Sakai (1999) observed peak rockfall rate 5 to 15 days after melting of the cliff face, when seasonal thaw reached an estimated depth of 1 m, and found that intensive rockfall activity is rarely associated with either diurnal freeze-thaw cycles or precipitation events. Other rockfall inventories, however, emphasize diurnal variations, rather than seasonal trends (Coutard and Francou, 1989) and the importance of precipitation events. As a result it is difficult to predict the climatic controls on rockfall intensities.

Despite the difficulty in predicting climatic controls, thawing permafrost is likely to affect rockfall intensity. It is very likely that bedrock fracturing by ice segregation (Section 5.3.2.2.4) is significant for rockwall stability in regions of mountain permafrost, and for landform development in such



Figure 5.25. Talus accumulation produced by rockfalls and debris flows. Endalen, central Svalbard. Photo: Ole Humlum, 5 August 2000.

areas in general. Presumably, most segregated ice is found within the topmost 1 to 2 m of bedrock permafrost (French, 2007), so climatic change leading to permafrost thaw would be expected to result in initially higher rockfall intensity, followed by a decrease after this critical layer thawed.

5.3.2.3.3. Rockslides and rock avalanches

Rockslides or rock avalanches represent larger parts of steep rock slopes, which slide or fall downslope (Figure 5.26). This movement can occur at the scale of centimetres per year, but can also be very quick, transporting large amounts of rock all the way to the valley bottom in one event. The greatest geohazard is attached to events on rock slopes located above lakes or the sea as these cause a risk of tsunamis. Rockslides and rock avalanches are influenced by many factors, such as earthquakes and water pressure in the rock. Large rockslides are known to have occurred in several parts of the world, particularly during deglaciation, and these were often associated with increased tectonic activity as the crust is isostatically adjusted. Permafrost formation and thaw can also affect rockslides and rock avalanches.

When rockslides start moving, cracks open in the rockslope, and the rate of movement is monitored at sites where there is increased risk of damage to settlements and infrastructure. Permafrost has been identified in some rockslide areas. If permafrost thaws or forms due to climatic changes, rocksliding might increase and rock avalanches could even occur (Dramis et al., 1995). Nearly all the literature on permafrost in steep rock slopes and its influence on rocksliding is from non-Arctic areas such as the European Alps, where some three-dimensional modeling has been undertaken to help understand the consequences of rising ground temperature (Wegmann et al., 1998; Gruber et al., 2004). To study how permafrost can affect rocksliding and rock avalanches in the Arctic, more ground temperature observations are needed from rockslide areas in potential permafrost areas. Even if the risk from increasing rockslides and rock avalanches could be important to settlements and infrastructure, projection is not yet possible.

5.3.2.3.4. Solifluction

Solifluction is defined as the slow downslope movement of the active layer over permafrost, or over the seasonally frozen



Figure 5.26. Opening of a 10 to 15 m deep crack in the rockslide area, Nordnes, northern Norway, with the Storjorden below, September 2005. Photo: Hanne Christiansen, UNIS, Svalbard.

layer in other periglacial, non-permafrost environments. Solifluction can take place on slopes in an undifferentiated fashion or may give rise to landforms that include stripes, steps, lobes and sheets. The process is a combination of frost creep and gelifluction and typical surface velocities are 1 to 9 cm/y (Matsuoka, 2001b). Velocity profiles with depth are concave downslope in areas of warm permafrost and seasonally frozen ground in the discontinuous zone, where autumn freezing is from the surface downward. Convex downslope velocity profiles develop in areas of cold permafrost where freezing is also from the permafrost table upward. The environmental boundary between the two has not been delineated, but is thought to correspond to the boundary of the zone of continuous permafrost. Recent advances in solifluction studies have taken place through a combination of field monitoring (Harris et al., 2007) and laboratory simulation (Harris et al., 2008).

The impact of climate change on solifluction is inferred from understanding of processes and observations during warm summers, and is linked to the distribution of ice within the active and transient layers. A warm summer in an area with two-sided freezing (i.e. freezing from the ground surface downward and from the permafrost surface upward) will result in enhanced late-summer movements, as the base of the active layer and the top part of the transient layer thaw relatively quickly, inducing high porewater pressures. This is similar to what happens in a normal summer, but the depth and amount of movement will usually be greater (Lewkowicz and Clarke, 1998). In an area with one-sided freezing (i.e. from the ground surface downward), most movement normally takes place during and immediately following snowmelt and there may be little or no movement later on (Kinnard and Lewkowicz, 2005). However, a warm summer in which the transient layer thaws will result in movements similar to those in an area of two-sided freezing.

Projection of these differences into the future has not been done and will depend on the rate of ground ice replenishment in the transient layer versus the frequency at which the active layer becomes thicker. Overall, it can be expected that rates of solifluction are likely to increase in the warmer and/or wetter climates that are expected in the Arctic in future, providing permafrost continues to persist.

These enhanced movements may have several impacts. They could increase sediment delivery from slopes to streams and lakes, which could in turn affect aquatic ecosystems. Solifluction can also affect shallow foundations of built structures because of differential movements. However, most structures on permafrost are constructed with foundations that extend well below the active layer, but thicker active layers produced by a warmer climate may allow deeper movements, which could cause problems in the future.

5.3.2.4. Permafrost-glacier interactions

Permafrost-glacier interactions are important to consider when projecting the impacts of changes in glaciers on permafrost. Receding glaciers expose new land to permafrost formation, if the deglaciated areas experience enough ground cooling. Land uplift due to isostatic adjustment as glaciers recede also creates possibilities for permafrost to form. Furthermore, stagnant dead glacier ice (e.g., in ice-cored moraines which are buried

below a significant amount of debris) might be preserved if located in a permafrost environment with a debris cover thicker than the active layer. Thermokarst landforms can also develop from thawing of ice-cored moraines, but such a landscape is traditionally considered as still undergoing areal deglaciation, and thus typically characterized as glacial. In addition, as glaciers become thinner, their thermal characteristics might change and they could become ‘cold-based’ glaciers, thus increasing the potential for permafrost to form beneath the glacier. Glacier-derived rock glaciers are an example of direct interaction between glacial deposits and permafrost.

5.3.2.5. Coastal and marine processes

Sea ice and ground ice both limit and enhance erosion processes, especially as more than 65% of the Arctic coastline is composed of unconsolidated material (Lantuit et al., 2011), and much of which is ice-bearing or ice-rich. A substantial amount of the Arctic coastline is ice-bound for most of the year, and is thus protected from erosion and deposition. However, despite shallow shelf water, a high ground-ice content and the generally fine-grained unconsolidated material found in lowland sedimentary coasts, render such coasts sensitive to waves and storm surges during the short summer period. These coasts therefore experience relatively high annual erosion rates. Bedrock coastlines are not generally subject to any significant erosion or deposition (Figure 5.27).

In the nearshore zone, where the water depth is less than the maximum ice thickness, bottom-fast ice develops (Figure 5.1). Bottom-fast ice can result in simultaneous preservation and thawing of the permafrost. The high thermal conductivity of the ice creates a thermal diode, shunting heat out of the sediment during the winter months. In some locations where the sediment is already thawed, this creates a frozen active layer beneath the seabed. On the other hand, salt exclusion from the forming sea ice creates highly concentrated brines under pressure (Overduin et al., 2008), sufficiently saline to be unfrozen at temperatures as cold as -10 °C. These brines penetrate the upper sediment and thaw the pore ice under cryotic conditions. In general, subsea permafrost in the bottom-fast ice zone is quasi-stable. Once the water depth exceeds the maximum ice thickness, salt water penetrates into the sediment, and heat transfer from bottom water warms the permafrost. Both processes result in phase change in the sediment pore space, although the sediment remains cryotic and assumes an almost uniform temperature profile near the freezing point determined by its salinity. Submarine permafrost is also subject to degradation from below due to geothermal heat flux (Lachenbruch, 1957).

Most of the significant drivers for coastal erosion point toward increased erosion. These include reductions in sea-ice thickness, extent and duration, which over the past decades have exceeded most forecast scenarios. A resulting increase in open water in the coastal zone brings increased fetch for wave action impinging on the coast, increased heat exchange with the shallow shelf sea water during the summer months, and changes in shelf salinity. Many studies have suggested that the frequency of storm events is increasing (e.g., Are et al., 2008) with a resultant increase in sea-surface height at the coastline due to storm surges. Over fifty years of tide gauge data have now been accumulated for parts of the Siberian Arctic coast, showing a sea-level rise of 2.5 mm/y (Proshutinsky et




Figure 5.27. Distribution of coastal erosion and deposition in the Arctic. Source: Lantuit et al. (2011).

al., 2007; see also Chapter 11, Section 11.2). The sedimentary coastal bluffs are sensitive to increased air temperature, which increases thermo-abrasion and thermo-denudation of the coast. Increased ground heat flux thaws ground ice at the top of the permafrost, leading to subsidence and increasing sea-level rate rise relative to land surface elevation. These physical drivers will probably all lead to a system-wide increase in sediment flux in the Arctic, which has already been observed from satellites (Pozdnyakov et al., 2005) in the nearshore zone.

5.3.3. Ecological processes

Permafrost interacts closely with biodiversity and ecosystem processes in the Arctic, and changes in permafrost regimes will affect Arctic ecology. Permafrost moderates soil temperature, drainage, nutrient availability, micro- and mesorelief, rooting depth and plant stability, and disturbance regimes for those species (particularly plants) that live on permafrost. It also provides a total environment for those species that live within permafrost and preserves life from the past. In turn, vegetation moderates ground surface temperature and facilitates disturbance regimes, such as forest fires, that affect permafrost. Understanding of the interactions between permafrost and Arctic ecosystems has advanced since the Arctic Climate Impact Assessment and the Fourth Assessment of the Intergovernmental Panel on Climate Change and two particularly important issues have emerged. First, the uncertainty of the implications of permafrost thaw for soil water content, subsequent ecosystem development, and greenhouse gas emissions. Second, the preservation and activity of life in permafrost.

5.3.3.1. Life on permafrost – impacts of thawing permafrost on biodiversity

No species are dependent on permafrost (although some ancient microbes might be preserved in it) and at the circumpolar scale, no ecosystems are restricted by the presence of permafrost: both tundra ecosystems and boreal forests can be underlain by permafrost or can occur where it is absent. However, at the landscape scale, the presence of permafrost strongly influences plant species composition (Camill, 1999) and restricts the types of plant that can grow in terrestrial ecosystems. The presence of permafrost affects drainage and determines the presence or absence of fundamental ecosystem types and their species biodiversity: lakes, wetlands, meadows or heaths. Also, shallow active layers restrict the diversity and productivity of trees while cold soils that limit decomposition and nutrient cycling favor vegetation with a low diversity of plant species, and particularly mosses (Van der Wal and Brooker, 2004) that can reduce tree seedling establishment (Camill et al., 2010). At the small scale, active soil movement provides microsites for the establishment of seedlings while preventing plants with rhizomes from establishing (Jonasson, 1986; Jonasson and Callaghan, 1992). Permafrost features that result in soil uplift and drainage (e.g., pingos and baidgerahks) create microsites favorable for biodiversity hot-spots that support, for example, diverse plants and also animals such as snowy owl, as well as lemming nests, wolf dens, and Arctic fox earths (Walker, 1995). Although Arctic vegetation has a simple vertical structure, there is a complex horizontal structure of repeated patterns associated with patterned

ground (Matveyeva and Chernov, 2000).

Impacts of thawing permafrost on biodiversity are likely to be numerous and diverse. In many areas of the Arctic, thawing permafrost is leading to the disappearance of lakes and ponds (Section 5.3.3.1) and this will affect biodiversity along the gradient: freshwater ecosystems $\Rightarrow$ wetlands $\Rightarrow$ meadows $\Rightarrow$ heaths. In the polar deserts of the High Arctic, the maintenance of a high water table is critical for the existence of patchy wetlands, which provide hydrological and ecological conditions important to plants, insects, birds and rodents (Woo and Young, 1998). A high water table is maintained by a shallow active layer that restricts drainage. Increase in active-layer thickness resulting from warming of the ground that may accompany climate change will improve drainage and lower the water table. Slumping and erosion that may accompany thawing of ice-rich permafrost can lead to the draining of these wetlands, resulting in a loss of wildlife habitat (Woo and Young, 2006; Woo et al., 2006a). In other areas, thawing permafrost is impeding drainage (Smith et al., 2005b; Johansson et al., 2006) leading to a shift in biodiversity from former dwarf shrub vegetation of dry organic soil to tall shrubs of wetter soils and eventually wetland sedges (Malmer et al., 2005) and bog mosses. In the boreal peatlands of Manitoba, Canada, a plant succession from black spruce (*Picea mariana*) trees to *Sphagnum* moss during permafrost thaw resulted in a doubling of peat accumulation (Camill et al., 2001).

Thawing permafrost is associated with gradual or episodic disturbance (slumping) of the land surface that can affect large areas (Section 5.3.2), with various impacts on biodiversity. It damages existing vegetation, particularly forests when trees become unstable and fall (Figure 5.28) while disturbed organic soils and deeper groundwater systems can occur that yield greater transport of cations, and dissolved and particulate organic carbon, thereby creating favorable conditions for the establishment of spruce trees as well as various shrubs (Lloyd et al., 2003). Slightly drier soils along thermokarst banks promote the introduction of woody species as compared to adjacent tundra. Such processes may accompany a northward expansion of the treeline. Disturbance can also open new niches for the establishment of an enriched flora. Lantz et al. (2009) found that in the Mackenzie Delta region of northern Canada, thaw slumping disturbance could provide opportunities for rapid colonization of species beyond their present range and that the disturbed sites may act as highly productive seed sources within the larger undisturbed terrain. However, disturbance can also facilitate the establishment of invasive species of detriment to conservation interests and land use. Thaw slumping impacts on Low-Arctic terrestrial ecosystems may be more immediate than the response of the ecosystems to air warming alone (Lantz et al., 2009).

The biodiversity of animal species will be affected by the type of land surface (habitat) resulting from thawing permafrost. For the extreme scenario where thawing permafrost leads to increased drainage and soil drying, the animals associated with freshwaters (e.g., fish and waterbirds) could be replaced by mammalian herbivores and ground-nesting birds etc. However, the opposite scenario applies to the sub-Arctic palsa mires that occur in northern Fennoscandia, Canada, and Siberia. These are heterogeneous and biologically rich environments resulting from the gradients in the water table and the nutrient-

rich versus nutrient-poor microhabitats. The palsa mires are projected to almost disappear from northern Fennoscandia by 2050 (Section 5.2.3.2), which would affect biodiversity at the global scale because they are important breeding habitat for birds (CAFE, 2001). This is due to the heterogeneous nature of the environment and to the existence of shallow water that provides abundant food (insects). The disappearance of palsa mires would therefore cause a reduction in populations of migrating birds such as waders that occur exclusively in areas with palsa mires (Luoto et al., 2004b).

Permafrost thaw also leads to rapid changes in the freshwater environment that are likely to affect biodiversity in the shorter term. Kokelj et al. (2008) and Thompson et al. (2008) observed elevated levels of conductivity (reflecting changes in lake chemistry) in small lakes in the Mackenzie Delta region of northern Canada affected by recent (after 1950 - Lantz and Kokelj, 2008) active thermokarst slumping relative to undisturbed lakes. Sloughing of banks (slumping) enhances thawing and erosion, while exposing buried organic material from which soluble material is released (Kokelj and Burn, 2005) and transported by runoff. However, dissolved organic matter was observed to be lower in lakes affected by thermokarst activity (Kokelj et al., 2005). Permafrost disturbance will be an important factor influencing tundra lake chemistry as warming continues in the Arctic and, as freshwater biodiversity is strongly related to water chemistry, changes in biodiversity can be expected. Some of these changes may affect species of local and commercial value (e.g., various fish species).



Figure 5.28. 'Drunken forest' occurs when the ground becomes unstable due to thawing permafrost. Photo: Trofim Maximov, Institute for Biological Problems of Cryolithozone, Russian Academy of Sciences, Yakutsk, Russia.

5.3.3.2. Life on permafrost – impacts of changes in biodiversity on permafrost

Biodiversity (particularly of vegetation) affects permafrost in four fundamental ways: (i) by directly insulating and protecting permafrost; (ii) by indirectly insulating permafrost through its capacity to trap snow; (iii) by affecting land surface albedo and thereby modifying soil temperature (see Section 5.3.4.1); and (iv) creating the conditions for fire that can result in permafrost warming and thaw. In the case of fire, this would occur in the short term through the direct effect of the fire and in the long term because of the effect on surface albedo and vegetation insulating capacity.

Vegetation associated with areas of drier peat or organic soil, insulates the active layer and protects the permafrost (Woo et al., 2006b, 2007; Yi et al., 2007; Smith et al., 2009a). Vegetation-soil feedbacks reduce deep soil temperature by 7 °C and help permafrost to persist at mean annual air temperatures of up to +2 °C (Jorgenson et al., 2010). This has led to ‘ecosystem-protected permafrost’ such as that in sub-Arctic *palsa* mires where the permafrost is sporadic in the lowlands. While disturbance to the vegetation could result in permafrost thaw, undisturbed vegetation could allow patchy permafrost to persist even during climate warming (Shur and Jorgensen, 2007).

Snow-vegetation interactions are complex (see Chapter 4). Vegetation, particularly shrubs, can trap snow and cause an increase both in snow depth and snow cover duration. Studies have shown that snow cover insulates the soil. For example, experimental accumulation of snow increased soil temperature over winter by 0.5 to 9 °C (15 cm soil depth) in the sub-Arctic (Seppälä, 2003; Dorrepaal et al., 2004) and by 6 to 15 °C at 50 cm depth in Alaska, depending on the height of the snow-accumulating fence (Walker et al., 1999; Hinkel and Hurd, 2006). Increased snow depth will therefore disconnect permafrost from the low winter temperatures that protect it and will lead to increased thaw (Section 5.2.3.2).

Vegetation has a fundamental impact on surface albedo. Various changes in biodiversity will decrease albedo and increase the positive albedo feedback to the atmosphere (i.e., warming). These include more shrubs in the tundra (Silapaswan et al., 2001; Sturm et al., 2001; Euskirchen et al., 2009), expansion of boreal forest into regions now occupied by tundra (Chapin et al., 2005), and the replacement of summer-green conifers (larch) and other deciduous treeline tree species by evergreen conifers such as pine and spruce (Kharuk et al., 2005; Wolf et al., 2008) (see Section 5.3.4.1 for the feedback effects). Feedbacks to climate from changing biodiversity also include sequestration of carbon from the air, which will help reduce air warming, and increased evapotranspiration that in turn leads to local cooling (see Section 5.3.4.1 for feedback effects).

A major impact of changing vegetation on permafrost owing to general climate warming is likely to be an increased frequency in fire due to drier conditions in existing tundra and forest areas. Also, as projected changes in vegetation (Callaghan et al., 2005; Kaplan and New, 2006; Wolf et al., 2008) are likely to result in more combustible material (graminoids replaced by shrubs, deciduous mountain birch replaced by evergreen trees etc.) the frequency of fire is likely to increase still further. Burning of the insulating organic soil layer (e.g., peat) as well as the vegetation cover can lead to warming of

the bare ground surface by as much as 6 °C above the mean annual air temperature, thawing of permafrost and, if ice-rich, to subsidence and ponding (Smith et al., 2008a). On the North Slope of Alaska, lightning strikes have increased tenfold since 2000 and in 2007 a fire occurred covering 1000 km², which was more than the sum of all known fires on the North Slope since 1950 (Jones et al., 2009; Mack et al., 2011; Figure 5.29). More frequent forest fires result in a change in biodiversity of vegetation (from trees to graminoids) that further affects snow trapping and albedo.

The integrated net effect of all the vegetation change feedbacks to permafrost dynamics is still unquantified, but likely to be significant.

5.3.3.3. Life in permafrost

Since the benchmark assessments of the Arctic Climate Impact Assessment (ACIA, 2005) and the Fourth Assessment of the Intergovernmental Panel on Climate Change (see Anisimov et al., 2007), there have been rapid developments in the understanding of biodiversity in permafrost and its importance.

Significant numbers (10³ to 10⁷ cells per gram) of various viable ancient microorganisms are known to be present within permafrost from polar regions. In the Arctic, they have been isolated from frozen cores extracted down to 400-m depth in the Mackenzie Delta region of northern Canada (Gilichinsky, 2002). They have been extracted from permafrost in areas with high ground temperature (-2 °C) near the southern permafrost border in Siberia and also areas with low temperature (-17 °C), such as from High Arctic Ellesmere Island within the Canadian Arctic Archipelago (at 80 °N). Permafrost is a depository of viable anaerobic and aerobic, spore-forming and spore-less bacteria, green algae and cyanobacteria (Vishnivetskaya, 2008), yeast (Faizutdinova et al., 2005), and mycelium fungi (Ozerskaya et al., 2008). It also contains organic compounds resulting from metabolic activity such as the pigments chlorophyll *a*, *b* and pheophytin (Erokhina et al., 2004), biologically active intra- and extracellular enzymes (Vorobyova et al., 1997), and biogenic methane (Rivkina et al., 2007). Organs and



Figure 5.29. Tundra fire on the North Slope of Alaska in 2007 resulted in thawing of the upper 5 to 10 cm layer of permafrost. Photo: Michelle Mack.

individuals of higher systematic levels have also been found in permafrost, such as mosses (Gilichinsky et al., 2001), seeds (Yashina et al., 2002) and protozoan flagellates, infusoria and amoeba (Shatilovich et al., 2005). Although permafrost is usually regarded as an extreme habitat that limits life, its cold-adapted biomass is many times higher than that of the overlying soil cover. The age of the isolates corresponds to the duration of the permanently frozen state of the embedding strata, and date back 3 million years in northern Siberia (and probably 25 million years in Antarctica) (Gilichinsky et al., 2007). The organisms preserved in permafrost are the only life forms known to have retained viability over geological time. Current and projected permafrost thawing (Sections 5.2.2.2 and 5.2.2.3) will expose modern ecosystems and environments to relic life, with largely unknown consequences.

The activity of life forms demonstrated by microbiological and biogeochemical processes occurring below the freezing point remains open to debate. Bacteria are able to grow at temperatures below 0 °C if the medium is not frozen (Gilichinsky et al., 1993) and at least part of the permafrost community grows at temperatures between -2 and -10 °C (Bakermans et al., 2006; Steven et al., 2006). Anabolic metabolism that leads to the formation of bacterial lipids occurs down to -20 °C (Rivkina et al., 2000) and bacteria are able to carry out redox reactions between -17 and -28 °C after thousands to millions of years within permafrost (Rivkina et al., 2004). Cell viability and growth on media implies a high capacity for DNA repair in the frozen environment (Gilichinsky et al., 2008) and long-term survival is closely tied to cellular metabolic activity and DNA repair (Johnson et al., 2007). Consequently, although DNA is usually degraded rapidly in most environments, it has survived within permafrost over geological time (Willerslev et al., 2003, 2004; Lydolph et al., 2005; Hansen et al., 2006; Vishnivetskaya et al., 2006).

The occurrence of viable Cenozoic microorganisms within permafrost may provide a window into microbial life as it was before the impact of humans (Tiedje et al., 1994). If the relict and modern communities have different sensitivities to antibiotics and heavy metals, the old genes may have modern applications – or conversely, may create new problems if they are released from thawing permafrost. Bacterial and plant viruses were found in 500- to 100 000-year old ice from the Greenland Ice Sheet (Castello et al., 2005). This indicates that viruses potentially dangerous to humans could also be present in permafrost. The preservation of influenza A RNA was recently reported in ice (Shoham, 2005) and lakes on the East Siberian Sea coast that are visited by large numbers of migratory birds that could potentially spread such viruses (Zhang et al., 2006). There is also the possibility that viruses within the bodies of people that died in epidemics and who were buried in the upper permafrost layers that are now thawing, could again become prevalent.

Conceptually, the presence of life in the permafrost could help to resolve fundamental scientific issues such as the period for which life can be preserved on Earth, or on planets such as Mars.

The overall relationship between life preserved in permafrost and current/future climate warming is complex but can be generalized as follows: only those organisms (beneficial or harmful) in the upper layers of permafrost could be released by air warming and permafrost thawing, but climate change

research (e.g., ice-core drilling) and increased accessibility to areas of ancient permafrost could lead to intended or accidental access to ancient, viable life forms.

5.3.4. Feedbacks to climate through trace gas emissions and albedo changes

5.3.4.1. Albedo and evapotranspiration

Vegetation and permafrost interact in many complex ways (see Section 5.3.3). Climate warming and its impacts on permafrost will lead to significant changes in vegetation (see Section 5.3.3.1). The ability of trees and shrubs to trap snow increases albedo and short vegetation that is covered by snow in winter absorbs only about 5–15% of incident radiation (Callaghan et al., 2005; McGuire et al., 2007). In contrast, tall black spruce can intercept about 95% of incident radiation (Juday et al., 2005). Although vegetation changes to date appear to have had minimal effects on atmospheric heating in Arctic Alaska (Chapin et al., 2005), complete conversion to shrub tundra has the potential to increase summer heating by around 6 to 21 W/m² per decade. Complete conversion of tundra to tree cover in northern Alaska is estimated to increase summer heating by around 26 W/m² (Chapin et al., 2005). In addition, black carbon (soot) from more frequent wildfires (and coal burning at lower latitudes) is now falling on snow and ice, making them darker and thus less reflective (see Chapter 4, Section 4.3.1.3.2). In contrast, wildfires and ecosystems produce tiny particles (termed ‘aerosols’) that are carried in the atmosphere and reflect incoming solar radiation, producing a cooling effect (see Section 5.3.4.2.3). Although these feedbacks are usually measured and modeled in terms of their effects on air and/or canopy temperature, soil and permafrost temperatures are expected to follow this pattern based on geographical analogues of air/soil temperature relationships and vegetation type. However, shading by a denser canopy may have local and temporary effects on soil temperatures.

Local disturbance and logging may also affect energy exchange with the atmosphere. For example, while fire disturbance often reduces albedo shortly after the fire, it also provides the opportunity for shrubs, and eventually deciduous broadleaf trees to develop, which will generally raise albedo. Along these lines, insect and pathogen outbreaks that result in loss of canopy foliage may cause short-term changes in albedo and start successional pathways that lead to the replacement of conifers by deciduous broadleaf trees. Thus, disturbance regimes that increase the proportion of non-forested lands and deciduous forests could reduce energy absorption and result in cooling (Chapin et al., 2000) that could to some extent preserve permafrost.

In Siberia, 55% of the coniferous forest on continuous permafrost soils is deciduous (larch, *Larix* sp.) with consequently high winter albedo. Although the two evergreen conifers (Siberian spruce, *Picea obovata*; Siberian pine, *Pinus sibirica*) also grow well on permafrost soils, *Larix* usually dominates because of its additional fire resistance. However, a recent advance of evergreen conifers into the *Larix* zone is related to increased temperature and precipitation over the past 30 years (Kharuk et al., 2005). Undergrowth of evergreen

conifers decreases winter albedo, a positive feedback to climate warming and permafrost degradation. In North America, where crown fires predominate (McGuire et al., 2002), deciduous stands usually have a well-developed second canopy layer of spruce (Wirth, 2005).

After these vegetation types are disturbed by fire or logging, a sometimes sparse post-fire vegetation and the lack of a deciduous pioneer phase result in a high and sustained production of sensible heat (Schulze et al., 1999). Severe fires in the Russian Far East and probably elsewhere can cause the collapse of permafrost and prevent the recovery of trees, effectively increasing albedo by converting conifer forests into ecosystems dominated by deciduous herbs and shrubs for hundreds of years.

Changes in vegetation resulting from climate change, thawing permafrost and disturbance affect the sequestration of atmospheric CO₂ by ecosystems and evapotranspiration, both of which could result in cooling. The balance and integrated net effect of the opposing feedbacks, although likely to be significant, remain unquantified as they are difficult to model because effects vary over different scales of time and space (see Chapter 11, Section 11.1 on physical feedbacks and forcings). However, vegetation modeling studies to quantify impacts of climate warming in the Arctic and the role of feedbacks, suggested that forests in the eastern Canadian Arctic would have a net negative feedback on climate warming through increased sequestration of carbon, whereas forests in Arctic Russia would have a net positive feedback on climate warming through decreased albedo (Betts and Ball, 1997; Betts, 2000). More recently, vegetation models applied to the Barents region found that changes in vegetation decreased albedo by 18% (Wolf et al., 2008) but increased evapotranspiration (Göttel et al., 2008), leading to a cooling of 1 °C in spring in the eastern part of the region.

5.3.4.2. Terrestrial trace gas emissions

Exchange of carbon between the land and the atmosphere is currently mediated mainly by the generally carbon-rich active layer. However, permafrost also contains vast stores of carbon sequestered during the Holocene or even earlier in some areas. The ultimate strength of the feedback from permafrost carbon to climate change depends both on the pool size of organic carbon stored in permafrost and the rate of release to the atmosphere (Schuur et al., 2008). ACIA (2005) concluded that key issues in relation to terrestrial trace gas emissions as affected by permafrost processes include the overall carbon balance and the potential for increased CH₄ emissions. Since the Arctic Climate Impact Assessment, a new key issue has become the need to revise earlier calculations of trace gas emissions in order to correct for previously under-estimated carbon stocks. Several studies and a major review of the sensitivity of the overall Arctic carbon balance (McGuire et al., 2009) have addressed these problems. In addition, some surprising new findings have been published in relation to non-CO₂ trace gas emissions (e.g., N₂O). The following section reports new estimates of the pool size of stored carbon, while subsequent sections address current and potential future rates of its release to the atmosphere and the possible global consequences of this release.

5.3.4.2.1. Carbon stocks

New estimates of terrestrial carbon pools are significantly higher than those presented in the Arctic Climate Impact Assessment (ACIA, 2005). Permafrost together with the active layer above it contains about twice as much carbon as is found in the global atmosphere (Schuur et al., 2008), that is, more than 1400 to 1850 Gt in the circumpolar North, including almost 300 Gt in the form of peat (McGuire et al., 2009; Tarnocai et al., 2009). Earlier studies suggested that northern peat deposits stored about 500 Gt of carbon (Gorham, 1991; Botch et al., 1995), with an estimated 278 Gt of this total located in permafrost regions. Most of the perennially frozen peat deposits are found in *palsa* and peat plateau bogs where relatively dry surfaces promote the existence of permafrost.

Recent work has shown permafrost soil carbon pools to be much larger at depth than previously recognized because of cryogenic (freeze-thaw) mixing (Bockheim, 2007; Bockheim and Hinkel, 2007) and sediment deposition (Schirrmeister et al., 2002; Zimov et al., 2006b). A detailed study of the North American Arctic quantified 98 Gt of carbon in the top 1 m of soil, an apparent 75% increase over previous comparable estimates that had been extrapolated from far fewer data (Ping et al., 2008). While the level of measurement detail represented by this North American study is not available for the permafrost region as a whole, recent syntheses of available data indicate that the entire northern circumpolar permafrost region may contain 1024 Gt of soil carbon in the surface 0 to 3 m depth, with an additional 648 Gt of carbon locked in deep layers (~25 m thick) of aeolian and alluvial 'yedoma' sediments (407 Gt), and deltaic deposits (241 Gt) of large Arctic rivers (Zimov et al., 2006a,b; Schuur et al., 2008; Tarnocai et al., 2009). This 0 to 3 m permafrost-zone soil carbon estimate of 1024 Gt represents a large fraction of global soil carbon stocks, which have been estimated to be 2300 Gt (from 0 to 3 m depth, peatlands not included) (Jobbagy and Jackson, 2000). Much of the carbon stored in Arctic permafrost regions, even old carbon (Dorrepal et al., 2009), is highly labile and decomposes quickly under favorable moisture and temperature conditions. Although the potential release of carbon could therefore be very significant, the rate of permafrost thaw (see Section 5.2.2.2 and 5.2.3) and the subsequent changes in soil moisture are highly uncertain.

5.3.4.2.2. Current carbon and other trace gas fluxes

Many new measurements of carbon fluxes have been made since the Arctic Climate Impact Assessment (ACIA, 2005), and a complex picture emerges in which CH₄ emissions assume particular significance in terms of radiative forcing.

The annual source-sink CO₂ exchange between the terrestrial ecosystem and the atmosphere fluctuates dramatically over decadal time scales at tundra and forest sites (Oechel et al., 2000; Barr et al., 2007; Dunn et al., 2007). Spatial variability is also high across tundra sites from the European Arctic (Heikkinen et al., 2004), Siberia (Corradi et al., 2005), Alaska (Kwon et al., 2006), Greenland (Soegaard et al., 2000; Grøndahl et al., 2006), Svalbard (Lloyd, 2001), and northern Scandinavia (Aurela et al., 2004; Johansson et al., 2006) and boreal forest sites (Lloyd et al., 2002; Milyukova et al., 2002; D'Arrigo et al., 2004; Wilmking et al., 2004). The variability of CO₂ exchange in Arctic tundra ecosystems is driven primarily by variability in

growing-season timing and duration and moisture conditions, the latter related to permafrost occurrence and dynamics. Overall, field studies conducted to date suggest that tundra regions in the Arctic are currently sources of carbon to the atmosphere under conditions that become dry and mesic (e.g., in well-drained settings or in warm and dry years) and are carbon sinks under wet conditions (e.g., in poorly-drained settings or in cold and wet years). Regional modeling studies indicate that tundra regions across the Arctic have recently been acting as a weak sink of atmospheric CO₂ and are likely to continue to be a weak sink throughout the 21st century in response to the projected changes in climate (Callaghan et al., 2005; Euskirchen et al., 2006; Sitch et al., 2007; McGuire et al., 2009).

5.3.4.2.3. Sensitivity of ecosystem carbon balance to future permafrost thaw

Carbon dioxide

Overall, the net effect of warming and permafrost thaw on CO₂ exchange is not clear: once permafrost thaws, the direction of feedbacks to the climate system depends largely on landscape wetness and dryness but this varies from region to region and with time (see Section 5.3.1). Permafrost degradation can proceed through gradual but widespread thickening of the active layer and talik formation. This will expose previously frozen deposits to anaerobic decomposition contributing to surface fluxes. In addition, landscape processes such as thermokarst erosion and fire, while more localized, can rapidly remobilize the frozen carbon pool and expose it to both aerobic and anaerobic pathways for decomposition. Hence, biogeochemical, periglacial and vegetation processes will play a key role in carbon feedbacks from ecosystems in permafrost terrain (Schuur et al., 2008).

Field and modeling studies both indicate that warming could cause release of carbon as CO₂ through enhanced decomposition in aerobic Arctic soils (i.e., soils that are not saturated with water and where the water table drops) (Oechel et al., 1995; McGuire et al., 1995, 2007; Christensen et al., 1998; Arneeth et al., 2002; Dorrepaal et al., 2009) and from soils that thaw in areas of discontinuous permafrost (Goulden et al., 1998). Large releases of CO₂ are possible if landscape drying were to become pervasive in areas of continuous permafrost because ponds and wetlands comprise a substantial part of the landscape (Smol and Douglas, 2007). Indeed, a number of analyses have indicated that landscape dryness has increased over the past several decades in the boreal forest, particularly in areas of discontinuous permafrost (Smith et al., 2005b; Riordan et al., 2006; Goetz et al., 2007; Bunn et al., 2007). In contrast, CO₂ emissions from soils are likely to decrease if permafrost thaws in situations where drainage is impeded and decomposition is diminished because of anaerobic conditions (Christensen et al., 1998, 2004) and moss production is increased (Turetsky et al., 2000): permafrost thawing in Manitoba that displaces black spruce trees by *Sphagnum* moss is estimated to result in a doubling of carbon sequestration in peat (Camill et al., 2001).

The effect of thermokarst on trace gas fluxes varies over time as plant successions follow ground subsidence (Schuur et al., 2008). A study focused on upland thermokarst in Alaska

demonstrated changes in plant and soil processes as a function of time since thermokarst disturbance was initiated. Increased thaw and ground surface subsidence increased net and gross primary productivity as plant growth was stimulated by thaw (Vogel et al., 2009). Species composition changed along with changes in plant growth rates, as graminoid-dominated moist acidic tundra shifted to shrub-dominated tundra with increasing thaw (Schuur et al., 2007). Increased carbon uptake by plants initially offset increased ecosystem respiration such that this thermokarst was a net sink of carbon 15 years after the initiation of thaw, even though decomposition of older carbon deep in the soil was already taking place (Schuur et al., 2009; Vogel et al., 2009). Over subsequent decades of thaw, plant growth rates remained high but increased old soil carbon losses eventually offset increased carbon uptake and this thermokarst became a net source of carbon to the atmosphere (Vogel et al., 2009). The documented emission rates suggested that 4.5 to 6.0 kg C / m², or 9.5% to 13% of the soil organic matter pool could be lost on a century time scale (Schuur et al., 2009). If these rates were a typical response to widespread permafrost thawing across the permafrost zone, resulting annual net carbon emissions could be similar in scale in the future to current biospheric emissions from land use change.

Methane

The concept of a potential CH₄ ‘bomb’ from wet permafrost regions has been widely recognized and there have been new insights into the dramatic dynamics of permafrost thawing in Siberia and associated expansion of thaw lakes with huge organic carbon deposits (Zimov et al., 2006a) that form local CH₄ hotspots (Walter et al., 2006, 2007a,b). Methane release is a common pathway of carbon loss in lowland thermokarst areas where drainage is restricted (Strom and Christensen, 2007; Myers-Smith et al., 2008) and any increased release is of concern because CH₄ has a 25-fold greater heat trapping capacity than CO₂ on a century time scale (Solomon et al., 2007). Recent measurements in autumn at a High Arctic site in northeastern Greenland showed that CH₄ emissions can be concentrated in time within the seasonal cycle as well as in space: up to 50% of the total annual CH₄ emissions may take place during the freeze-up period (Mastepanov et al., 2008).

In northern Sweden, changes in permafrost dynamics, their effects on ecosystems and their feedbacks on climate in terms of increased CH₄ emissions counteract the negative feedback of increased CO₂ sequestration by vegetation (Christensen et al., 2004; Johansson et al., 2006; Figure 5.30). Synthesis of carbon fluxes at the catchment-scale level showed that changes in the sources of CH₄ through increased permafrost thawing may also change the sign (cooling to warming) of the current radiative forcing, due to the stronger impact per gram of CH₄ relative to CO₂. In a study of lowland thermokarst in three Canadian peatlands, carbon accumulation in surface soil organic matter was higher in unfrozen bogs and in areas where permafrost had degraded in comparison to areas where permafrost was intact (Turetsky et al., 2007), consistent with an Alaskan upland study (Section 5.3.3.1). Permafrost thaw in this lowland system promoted the release of CH₄ as waterlogged conditions predominated in *Sphagnum* spp. moss lawns that replaced the feathermoss / black spruce forest where permafrost degraded.




Figure 5.30. Spatial distribution of changes in annual net exchange of carbon dioxide (CO_2) equivalents for the period 1970 to 2000, where both CO_2 and methane (CH_4) are incorporated, Stordalen, northern Sweden. GWP_{100} represents Global Warming Potentials over 100 years. Source: Johansson et al. (2006).

Methane release was hypothesized to potentially offset the observed surface soil carbon accumulation for at least 70 years until plant and ecosystem succession in the moss lawn created conditions more like the unfrozen bogs that stored surface soil carbon but released smaller amounts of CH_4 . These findings are consistent with the studies of decadal-scale vegetation change as a consequence of permafrost thaw in sub-Arctic Sweden (see above: Box 5.2) (Christensen et al., 2004; Malmer et al., 2005; Johansson et al., 2006).

Overall, therefore, the complexity of the different radiative forcing of CO_2 and CH_4 is superimposed on the complexity of the contrasting responses of these greenhouse gases to varying effects of permafrost thaw. Hence, to assess impacts on climate, the atmospheric carbon balance must be weighed in a radiative forcing perspective (Christensen et al., 2007; Schuur et al., 2008).

Biogenic volatile organic compounds

There have also been recent measurements of biogenic volatile organic compounds (BVOC), including the first report of methanol emissions (Holst et al., 2010) from sub-Arctic wetlands underlain by discontinuous permafrost (Bäckstrand et al., 2008, 2010). Biogenic volatile organic compounds can be highly reactive in the atmosphere or can form aerosols and cloud condensation nuclei that scatter and absorb radiation. Areas of permafrost thaw represented by wetland vegetation (*Eriophorum* and *Sphagnum*) showed the highest fluxes of non-methane volatile organic compounds (NMVOCs) compared with neighboring areas not undergoing thaw, represented by palsas with cold peat and plant communities with feather mosses and dwarf shrubs (Bäckstrand et al., 2008). As NMVOCs could account for about 5% of total net

Box 5.2. Processes in methane release from the seabed and subsequently from sea to atmosphere

The possible sources of CH_4 in the Arctic coastal seas include sediment microbial activity, natural seeps, and gas hydrate destabilization (Kvenvolden et al., 1993). Methanogenesis can occur at any depth (Koch et al., 2009). The present understanding of the mechanisms that control the current thermal state and stability of submarine permafrost and of seabed CH_4 deposits is mostly based on modeling results. These results are very controversial and suggest a wide range of possible current states of submarine permafrost (Soloviev et al., 1987; Kvenvolden et al., 1992, 1993; Kim et al., 1999; Delisle, 2000; Romanovskii and Hubberten, 2001; Romanovskii et al., 2005; Gavrilov, 2008). Saline waters affect permafrost formation (Osterkamp, 2001), and according to Osterkamp and Harrison (1985) the reduction in thickness of ice-bearing permafrost determined by the salinity of sub-permafrost waters can be hundreds of metres. In addition, Delisle (2000) predicted that open taliks can form under the warming effect of large river flows. However, Romanovskii et al. (2000) and Romanovskii and Hubberten (2001) argued against downward destabilization of subsea permafrost and suggested that upward warming through the geothermal heat flux predominated.

Destabilization becomes evident by the formation of CH_4 migration pathways through the seabed (Kvenvolden, 2002). They appear as pockmarks, mud volcanoes, funnels, chimneys, and pingo-like structures, and they might not be morphologically specified (Hovland et al., 1993; Judd, 2004; Paull et al., 2007). Additional pathways could be via submerged thaw lakes, which by the time of inundation were underlain by taliks, thereby providing a vent (Romanovskii et al., 2005). In addition, depressions found in the East Siberian Arctic Shelf bottom topography could be interpreted as a typical thermokarst terrain similar to the landscape characteristic of the Siberian Lowland (Schwenk et al., 2006; Rekant et al., 2009).

Subsea permafrost does not necessarily represent a rocklike, ice-bonded layer but is sometimes ice free under negative temperatures due to freezing-point depression by salinity, which allows gases to escape (Himenkov and Brushkov, 2007). A number of additional factors allow temporary permeability of submarine permafrost, and these include permafrost breaks due to thermal contraction, settling and adjustment of sediments, and endogenous seismicity (Osterkamp and Romanovsky, 1999). Gaseous CH_4 can escape through the seabed into the water by means of air voids, channels of unfrozen water, and fissures within the ice (Biggar et al., 1998; McCarthy et al., 2004; Arenson and Sego, 2006).

carbon exchange, permafrost thaw could lead to a significant increase in NMVOC emissions that affect the carbon balance of ecosystems as well as atmospheric chemistry, radiation scattering and cloud formation. The consequences of permafrost thaw via NMVOC emission are not yet quantified over large areas.

Nitrous oxide

Recently, Repo et al. (2009) discovered very high emissions of the powerful greenhouse gas N_2O from ‘peat circles’ in permafrost regions in the Russian Arctic. Elberling et al. (2010) also reported high N_2O emissions of 34 mg N/m^2 per day in permafrost cores taken from northeastern Greenland and incubated in a laboratory, that equate to daily N_2O emissions from tropical forests on a mean annual basis. Although the importance of the process cannot be generalized across the Arctic, the strong radiative forcing potential of N_2O (298 compared with CO_2 ; Solomon et al., 2007) suggests important potential contributions to climate forcing that need to be calculated.

Lateral transport of carbon

The vertical emission and sequestration of carbon from a particular terrestrial area is accompanied by lateral transport of carbon as dissolved organic carbon (DOC), dissolved inorganic carbon (DIC) and particulate organic carbon (POC) from land to stream to lake to river to sea. Carbon can be effluxed to the atmosphere from the water as CO_2 or CH_4 , or can be exported to the ocean in the form of bicarbonates (HCO_3^-) and carbonates (CO_3^{2-}) where the carbon, initially from terrestrial areas, is sequestered over the long term (Humborg et al., 2010). Relative to other ocean basins, river transport of terrigenous carbon to the Arctic Ocean basin is about tenfold higher than average (McGuire et al., 2009). Extensive new data from previously unstudied Siberian streams and rivers over a large area of peatland in the permafrost region, suggest that mobilization of currently frozen, high-latitude soil carbon is likely over the coming century in response to the projected Arctic warming (Frey and Smith, 2005). Whereas cold, permafrost-influenced catchments release little DOC to streams, considerably higher concentrations are found in warm, permafrost-free catchments and these concentrations are related to the area of non-frozen peatland. Frey and Smith (2005) calculated that an increase in mean annual temperature to more than -2°C would lead to 700% increases in stream DOC concentrations and 2.7 to 4.3 Tg/y (29% to 46%) increases in DOC flux to the Arctic Ocean. Already, analysis of the structural composition of DOC transported in the Kolyma River, Russia, and some of its tributaries shows a transition from loss of present-day carbon from surface horizons during spring flood to loss of old, previously stabilized carbon from deeper soil layers by the end of the summer period (Neff et al., 2006). However, in contrast, Humborg et al. (2010) suggested that thawing of permafrost would not necessarily result in a positive feedback to warming because increased mineralization of soil organic carbon could be counter-balanced to some extent by increased weathering and DIC formation. Indeed, a decrease in DOC export relative to water discharge in the Yukon River during summer and autumn was recorded by Striegl et al. (2005, 2007) and DIC has increased (Walvoord and Striegl, 2007), thereby increasing the carbon sink term (Humborg et al., 2010).

5.3.4.2.3. Global implications of high latitude terrestrial greenhouse gas emissions

Despite recent advances in measuring CH_4 emissions, the major variations in the rate of growth of global atmospheric

CH_4 cannot be explained. The atmospheric CH_4 growth rate has shown a decade of unexplained variation (down to zero) but a substantial rate of increase since 2007 (www.esrl.noaa.gov/gmd) and it is possible that part of this substantial recent increase is due to an increasing source from wetlands at high northern latitudes.

Recent studies have highlighted the importance of permafrost carbon pools in the millennium-scale development of the global terrestrial carbon cycle and its interaction with the climate system. For instance, MacDonald et al. (2006) suggested a role for rapid early development of circum-Arctic peatlands in the coincident ice core records of atmospheric CO_2 and CH_4 . In addition, Walter et al. (2006) indicated that thermokarst lake formation and associated increases in CH_4 emissions contributed to post-glacial warming. Considering the future, Zhuang et al. (2006) focused on an area more extensive than the Arctic (southward to 50°N) and projected that a current net source of carbon to the atmosphere of 276 Tg C/y would increase to 473 Tg C/y by 2100 in response to climate scenarios, permafrost thaw, CO_2 fertilization of photosynthesis, and fire. This estimate contrasts with models of the Arctic that project this area will remain, as currently, a small sink of carbon throughout the coming century (although the uncertainty is high) (Callaghan et al., 2005; Euskirchen et al., 2006; Sitch et al., 2007; McGuire et al., 2009). However, results from a coupled carbon and climate model simulation suggested that even the higher carbon source estimates from areas south of 50°N would exert relatively small radiative forcing on the global climate system compared to anthropogenic emissions (Zhuang et al., 2006; McGuire et al., 2009).

To project the future role of permafrost carbon pools in the future global carbon cycle, a key need is to revise earlier conclusions on trace gas emissions to correct for the previously under-estimated Arctic carbon stocks (Tarnocai et al., 2009), but on the other hand, to include recent downward revisions of projected permafrost thaw (see Box 5.1). Furthermore, few of the modeling studies considered the potential effects of fire, which is a disturbance agent that has the potential for the rapid release of large stocks of carbon to the atmosphere. This release can occur not only in the direct and immediate combustion of organic matter, but also by removal of the protective organic layer above the permafrost that exposes the remaining carbon stocks to decomposition from substantial soil warming and permafrost thawing (Rocha and Shaver, 2009, 2011; Mack et al., 2011). The fires produce black carbon (soot) that enhances snow melt and results in some degree of permafrost preservation, but the overwhelming balance of the two processes results in significant net permafrost thaw and carbon loss. In a long-term perspective, peatlands (nutrient-poor areas) in sub-Arctic permafrost regions have a lower net carbon accumulation rate than those in boreal non-permafrost regions. Hence, future warming might increase carbon sequestration in current sub-Arctic ecosystems. In contrast, ground subsidence and increased precipitation are likely to increase the proportion of fens (nutrient-rich wetlands), which historically have lower net carbon accumulation rates (Kuhry and Turunen, 2006).

Overall, it is difficult to resolve the complexity of measured variations in trace gas fluxes into projections of future radiative forcing due to permafrost thaw. Although even high estimates of radiative forcing contribute relatively little to the global system

compared with anthropogenic carbon emissions (Zhuang et al., 2006; McGuire et al., 2009), recent measurements of CH_4 and N_2O fluxes suggest a future ‘wildcard’ (Corell et al., 2008).

5.3.4.3. Trace gas emissions from subsea permafrost

Since the Arctic Climate Impact Assessment (ACIA, 2005), there have been recent advances in measuring and estimating large-scale emissions of carbon from the Arctic coastal seas (e.g., Shakhova et al., 2010a). These new studies have resulted in much higher estimates of carbon emissions than those from earlier studies, with more profound implications for feedback to the climate system.

Arctic coastal seas host two distinct reservoirs of carbon: organic matter that could, under appropriate conditions, provide a substrate for CH_4 production and previously-formed CH_4 preserved within the seabed reservoirs some of which are permafrost. Organic-matter reservoirs consist of sediments that form during times of ocean transgressions and also of terrestrial organic matter, accumulated when the continental shelf was dry (Kleiber and Niessen, 2000; Vetrov and Romankevich, 2004; see Section 5.2.1.2). Seabed CH_4 reservoirs store natural gas, CH_4 -hydrates and CH_4 -bearing fluids (Soloviev et al., 1987; Ginsburg and Soloviev, 1994; Kvenvolden, 2002). Models suggest that the transgression of the Arctic Ocean over the previously exposed continental shelf during the past 10 000 years has increased the temperature of the surface sediment up to $+12^\circ\text{C}$ (Soloviev et al., 1987; Kvenvolden, 1988, 1991) while measurements show that submarine permafrost is close to the thawing point in some areas (Rachold et al., 2007).

Fluxes of CO_2 and CH_4 represent significant components of the marine carbon cycle in the Arctic seas that had not previously been included in estimates of the regional carbon

balance (Semiletov et al., 2007, 2011; Semiletov and Pipko, 2007; Macdonald et al., 2010; Pipko et al., 2011). Estimates of the combined CO_2 summertime evasion (for the period 2003 to 2008) from the Laptev Sea and the East Siberian Sea range between 4.2 Tg carbon (lower estimate) and 21 Tg carbon (moderate estimate) (Semiletov et al., 2010, see also Figure 5.31). Both values are of the same order of magnitude as the annual organic-matter accumulation in the Russian Arctic seas, 9 Tg C/y, a value almost equal to the gross organic-matter accumulation in the pelagic World Ocean (Vetrov and Romankevich, 2004). Decaying terrestrial organic matter dominates over marine organic matter as a source of CO_2 to the atmosphere in this area and terrestrially-derived CO_2 within the Siberian Shelf seas could be an important and so far underestimated source to the atmosphere. This source will probably increase with the projected future warming, as permafrost thawing is projected to increase, as are river discharge and coastal erosion.

Measurements of CH_4 include high sea bottom concentrations of 94 nM at the 20 m isobath in the Beaufort Sea (Kvenvolden et al., 1992) and increasing concentrations of dissolved CH_4 in the East Siberian Arctic Shelf between 1994 and 2008 that reached 900 nM in plume areas. In September 2005, about 45% of the study area exhibited concentrations of dissolved CH_4 of over 30 nM, 23% at more than 50 nM, and about 10% at more than 100 nM (Figure 5.32; Shakhova et al., 2007a,b; Shakhova and Semiletov, 2007; Shakhova et al., 2010 a,b). Cramer and Franke (2005) also measured elevated concentrations of dissolved CH_4 (≤ 46 nM) in the middle water in the central Laptev Sea. Concentrations of dissolved CH_4 in the surface water beneath the fast ice measured in April 2007 at one location reached 5000 nM. Many bubbles were observed entrapped within the fast ice and this confirmed ebullition as the predominant mechanism of CH_4 transport through the




Figure 5.31. Air-sea CO_2 fluxes and surface salinity in the East Siberian Sea in 2003 (left), and in 2004 (right – to show interannual variability) (modified from Semiletov et al., 2007). Bold black lines (0-line) mark change in flux direction, which agrees with the position of the hydrological frontal zone (salinity 23 line) (modified from Semiletov et al., 2005). The predominant substrate for CO_2 production comes from coastal erosion of terrestrial organic carbon in retreating ice-complexes.




Figure 5.32. Dissolved methane distribution in the surface water of the East Siberian Arctic Shelf for the period 2003 to 2008. Source: Shakhova et al. (2008a).

water column (Shakhova et al., 2008a). In total, it was shown that during 2003 to 2008, more than 50% of the studied area of the East Siberian Arctic Shelf served as a source of CH_4 to the atmosphere (Shakhova et al., 2008b).

Increases in CH_4 concentration in the atmospheric layer above the sea surface reached up to 8.2 ppm in the East Siberian Arctic Shelf during 2005 (Figure 5.33a), while the average mixing ratio of atmospheric CH_4 was 2.4 ppm. This measured average was comparable to average background concentrations of CH_4 measured in the atmosphere above the shallow marine sites affected by active vents and/or seepages from decaying hydrates (Shakhova et al., 2008a, 2010a,b). The increases sometimes occurred as pulses (Figure 5.33b). In 2006, an increased mixing ratio of CH_4 (up to 10%) was observed up to 1800 m above the sea surface (Shakhova et al., 2008a,b, 2010a).

The destabilization of submarine permafrost has significant implications for global climate. Current estimates of the amount of CH_4 that could be released from the Arctic continental

shelf (7 million km^2) during the short Arctic summer (100 days), based only on diffusive fluxes, is as high as 5 Tg of CH_4 (Shakhova et al., 2010b). This is a considerable increase on the ~ 0.1 Tg previously estimated by Kvenvolden et al. (1993).

The current estimate reflects the contribution of only a very small fraction of the total CH_4 fluxes and other significant components exist. One such component is CH_4 release during the deep autumn convection, which allows water from the East Siberian Arctic Shelf to mix from top to bottom (Kulakov et al., 2003). A significant late-summer potential CH_4 release to the atmosphere might therefore occur during only a few weeks (Shakhova et al., 2010b).

Another mechanism of CH_4 ventilation is deep convection in the flaw polynyas (band-like ice-free areas), which form simultaneously with land-fast ice in November. Flaw polynyas reach tens of kilometres in width and migrate out of fast ice hundreds of kilometres northward (Smolyanitsky et al., 2003), providing a pathway for CH_4 to escape to the atmosphere during the Arctic winter. Fluxes from the European Arctic polynyas are 20- to 200-fold higher than the ocean average and, as long as concentrations of dissolved CH_4 in the bottom water do not exceed 50 nM, can reach 0.02 Tg CH_4 a year (Damm et al., 2007).

A significant amount of CH_4 could also be released during the ice break-up period from areas not affected by polynyas. In these areas, dissolved CH_4 accumulates beneath the sea ice as it does in northern lakes (Semiletov, 1999). Additional release of CH_4 via these mechanisms would contribute to an increase in the diffusive fraction of air-sea CH_4 exchange, but the most important and still unmeasured component is ebullition. Assuming that ebullition might contribute to the total transport of CH_4 in the East Siberian Arctic Shelf as much as it does in northern lakes (50% to 90%), the annual release might reach from 10 to 50 Tg of CH_4 . Note that this amount does not include non-gradual or sudden releases of CH_4 , which are likely to take place in some areas where hydrates decay (Leifer et al., 2006).

The amount of CH_4 that could theoretically be released in the future is enormous. The volume of gas hydrates that




Figure 5.33. Methane release from the East Siberian Arctic Shelf: (a) mixing ratio of methane in the atmospheric layer above the sea surface measured along the ship route in September 2005 (b) pulse character of the methane release. Source: Shakhova et al. (2008b).

underlie the Arctic Ocean seabed is estimated at 2000 Gt of CH_4 (Makogon et al., 2007). About 85% of the Arctic Ocean sedimentary basins occur within the continental shelf so that within the East Siberian Arctic Shelf alone, which comprises about 30% of the area of the Arctic shelf, hydrate deposits could contain around 500 Gt of CH_4 . An additional two-thirds of that amount (around 300 Gt) is stored in the form of free gas (Ginsburg and Soloviev, 1994). Because most submarine permafrost is relict terrestrial permafrost, the carbon pool held can be estimated from knowledge on current terrestrial carbon storage to include not less than 500 Gt of carbon within a 25 m thick permafrost body (Zimov et al., 2006a), 2 to 65 Gt of CH_4 as hydrates (McGuire et al., 2009) together with a significant amount of non-hydrate carbon. The total amount of carbon preserved within the Arctic continental shelf is still debatable but it could be around 1300 Gt of carbon, from which 800 Gt is previously formed CH_4 ready to be suddenly released when appropriate pathways develop. Release of only 1% of this reservoir would more than triple the atmospheric mixing ratio of CH_4 , probably triggering abrupt climate change, as predicted by modeling results (Archer and Buffett, 2005).

5.3.5. Socio-economic issues

Information on social and economic issues related to changes in permafrost in the Arctic is not easily available (Glomsrød, 2006). In order to assess the impacts of changes in permafrost on socio-economics, it is of paramount importance to have an understanding of the present situation and the different variables and factors that affect development scenarios. The Arctic Climate Impact Assessment examined the potential impacts of climate change on Arctic infrastructure (Instanes et al., 2005). Particular concerns were associated with permafrost warming and degradation, coastal erosion, the stability and maintenance of transport routes, and industrial development. It was concluded that adaptation, mitigation, and monitoring techniques will be necessary to minimize the potentially serious detrimental impacts.

Permafrost regions are not densely populated. Duhaime and Caron (2006) gave a broad definition of the Arctic, including land areas with discontinuous and sporadic permafrost, and estimated the Arctic population at over 9.9 million in 2002 (Table 5.1).

The country with by far the greatest proportion of the Arctic population is the Russian Federation. As a result, this country also has the majority of the infrastructure associated with population centers and the presence of permafrost (Table 5.1).

Bogoyavlenskiy and Siggner (2004) gave a more narrow definition of the Arctic, and estimated the circumpolar Arctic population at about 4 million. Of some 370 settlements in tundra regions, more than 80% are located on the coast where permafrost is commonly present. Coastal Arctic regions have concentrations of industrial facilities associated with oil and gas activities, such as the Prudhoe Bay region in northern Alaska and the Pechora Basin in Russia, as well as exploration in the Mackenzie Delta-Beaufort region with the potential for future development. There are also several mines within the permafrost regions, with exploration ongoing and the potential for further mineral resource development. In most parts of the Arctic, human settlements are dominated by relatively small communities, whereas in northern Russia there are large cities with over 100 000 inhabitants and river ports with developed urban transportation and industrial infrastructure largely serving the needs of the extracting industries.

Several towns and cities in permafrost areas of the Russian Arctic have a population of around 50 000 citizens and require a substantial infrastructure to function (Table 5.2). Further east, the Sakha (Yakutia) Republic has a population of around one million; with the capital Yakutsk being the largest city and having a population of around 200 000.

Furgal and Prowse (2008) estimated that the population in the Canadian northern territories will increase from 104 000 in 2005 to 121 700 in 2031 under a moderate population growth scenario. Based on a report by the US Arctic Research Commission (2003), Alaska has a population of around 500 000 in permafrost areas, the main proportion (80%) living in sporadic permafrost areas with permafrost extent less than 50%.

The economic and strategic importance of the Arctic is high, due to the abundance of natural resources and raw materials. Military activity during the Cold War period and recent economic development has increased construction activity related to infrastructure, oil and gas facilities, transport networks, communication lines, industrial projects, and engineering maintenance systems. All of these developments

Table 5.1. Arctic population in 2002 in relation to permafrost area (Duhaime and Caron, 2006).

Country	Population, 1000s	Percentage of Arctic population	Percentage of country's population	Permafrost distribution
Alaska, United States	648	6.5	0.2	All types
Canada	113	1.1	0.4	All types
Greenland	56	0.6	100.0	All types
Iceland	289	2.9	100.0	Not continuous
Faroe Islands	47	0.5	100.0	None
Norway (including Svalbard)	465	4.7	10.1	All types
Sweden	509	5.1	5.7	Not continuous
Finland	645	6.5	12.4	Not continuous
Russian Federation	7144	72.1	5.0	All types
TOTAL	9915	100.0		

Table 5.2. Industrial cities of the Russian Arctic (population data from Russian Statistical agency 2009: www.gks.ru/bgd/regl/b09_109/Main.htm).

Region	City	Population	Main industrial activity or natural resource	Comment
Murmansk Oblast	Murmansk	311 200	Harbor, ship repair	Seasonal frost
	Severomorsk	53 500	Ship building	Seasonal frost
	Kandalaksha	36 600	Aluminum	Seasonal frost
	Apatity	61 600	Apatite	Seasonal frost
	Kirovsk	30 200	Apatite	Seasonal frost
	Monchegorsk	48 100	Nickel	Seasonal frost
	Olenegorsk	22 400	Iron	Sporadic permafrost
	Kovdor	19 100	Iron	Seasonal frost
	Zapolyarnyy	17 700	Nickel	Sporadic permafrost
Komi Republic	Nikel	15 000	Nickel	Sporadic permafrost
	Vorkuta	71 400	Coal	Continuous permafrost
Yamalo-Nenets Autonomous Okrug	Inta	33 400	Coal	Continuous permafrost
	Urengoy	118 700	Gas	Continuous permafrost
Taymir Autonomous Okrug	Nadim	47 300	Gas	Discontinuous permafrost
	Norilsk	203 900	Nickel, copper, cobalt, non-ferrous	Continuous permafrost
Sakha (Yakutia) Republic	Yakutsk	264 100		Continuous permafrost
	Neryungri	63 200	Coal	Continuous permafrost
	Aldan	23 500	Gold	Continuous permafrost
Chukotka Autonomous Okrug	Anadyr	12 600	Gold, coal, non-ferrous	Continuous permafrost
Magadan Oblast	Magadan	114 800	Gold, silver, non-ferrous	Discontinuous permafrost

have taken place with an awareness of current permafrost conditions. However, projected climate-driven changes in permafrost (see Section 5.2.3) are likely to affect both these and future developments, beyond current planning and engineering provisions.

5.3.5.1. Effect on infrastructure

Infrastructure is defined as facilities with permanent foundations or the essential elements of a community. It includes schools, hospitals, various types of building and structure, and facilities such as roads, railways, airports, harbors, power stations, and power, water, and sewage lines. Infrastructure forms the basis for regional and national economic growth.

Climate change is likely to have significant impacts on existing Arctic infrastructure and will influence the design of future development in the region (ACIA, 2005). In most cases, engineering solutions are available to address climate change impacts on permafrost, thus the issue is more economic than technological. In addition, it is possible that the uncertainty associated with projections of future climate change will increase the cost of new projects in the Arctic. Permafrost engineers must address the problem of preserving infrastructure under projected future climate conditions. One solution is to construct new buildings as existing ones are damaged and abandoned. It is possible that this method will be inadequate, since the required rate of new construction rises exponentially using the climate projections. In areas of warm, discontinuous permafrost, it is very difficult to find economic solutions to address the impacts of climate change on foundations or structures. These areas, together with the coastal zone containing saline permafrost, where the combined problems of increased wave action, sea-level rise, and thermal erosion have no simple engineering solutions, present the greatest challenges in a changing climate.

5.3.5.1.1. Buildings

Engineering problems associated with warming and thawing of permafrost are well documented. They include deformation and damage to buildings and development of thermokarst in northern Russian cities. In June 2002, an apartment building was ruined in the small town of Chersky in the lower Kolyma Region. It happened due to thawing permafrost under the foundation. In summer 2006, at the parking place in Yakutsk, several cars fell into a huge thermokarst crater caused by thawing permafrost (André and Anisimov, 2009). However, these impacts may be associated with warming of the ground that can accompany construction and operation of infrastructure and inappropriate engineering design rather than the direct effects of a changing climate.

It is often not possible to differentiate effects on constructions damaged, between those effects related to increased permafrost temperature due to changes in climate, and those resulting from changes to the ground caused by other factors (Instanes, 2003). For example: site conditions are often different to the assumed design site conditions; design of the structure did not take into account appropriate load conditions, active-layer thickness and permafrost temperature; the contractor did not carry out the construction according to the design; the maintenance program was not carried out according to plan; and, the structure is not used according to design assumptions.

Although there has been limited scientific evidence to date that observed climate warming has been the direct cause of failure of engineering structures on permafrost, new studies are suggesting that this effect is sometimes important. A study of historical air temperature in Spitsbergen, central Yakutia, and Alaska (Instanes and Anisimov, 2008) suggested that piled foundations have not suffered sufficient loss in bearing capacity to become unstable due to the observed increases in air temperature. However, the loss in capacity of piles in the period 2000 to 2007 could be the early warning of potentially

detrimental impacts of a changing climate. In addition, an increase in the active layer thickness may induce frost-jacking of installed piles and this may present a bigger threat to pile and foundation stability than loss of bearing capacity.

Oberman (2003a) performed a case study for multi-storey buildings in the city of Vorkuta in northwestern Russia. Buildings constructed on thawed soil (taliks) show very little deterioration with time (line 5 and 6, Figure 5.34). For buildings constructed on permafrost (lines 1 to 4) the deformation coefficient progressively increased with time. Oberman (2003a) reports that one 5-story residential building was abandoned less than 10 years after it was constructed and will be demolished, although the expected lifetime of the construction was 50 years (Figure 5.34).

Catastrophic deformations of buildings are confined to the 1980s. These are the years characterized by the greatest temperature increase in permafrost composed of Quaternary mineral deposits and peat. According to Romanovsky et al. (2010a) this increase in permafrost temperature is due to the combination of increasing air temperature and increasing snow depth (Figures 5.35 and 5.36).

Six to seven years after construction, the deformation coefficient of buildings is increasing rapidly. This is an indication that engineering-geocryological conditions are changing rapidly and are not the same as assumed in the initial design considerations. According to Oberman (2003a), the reason for such changes in conditions can only be natural degradation of permafrost.

In addition to effects of thawing permafrost on more-or-less flat areas of continuous permafrost, projected increases in temperature, precipitation, and storm magnitude and frequency are very likely to increase the frequency of avalanches and landslides (see Section 5.3.2), while slow downslope movements over time can also have implications for infrastructure. In some areas, the probability of severe impacts on settlements, roads, and railways from these events is very likely to increase. In some coastal areas, rockfalls might lead to local tsunamis thereby widening the impact on coastal structures. Structures located on sites prone to slope failure are very likely to be more exposed to slide activity as groundwater amounts and pore water pressures increase. An increasing probability of slides coupled with increasing traffic and population concentrations is very likely to require expensive mitigation measures to maintain a defined risk level. The best way to address these problems is to incorporate the potential for increasing risk in the planning process for new settlements and transport routes.

5.3.5.1.2. Pipelines

The conclusion from a recent study of the permafrost-related performance of the Trans-Alaska Pipeline since its inception in 1977 was that global climate change is not expected to threaten its future operation or integrity (Johnson and Hegdal, 2008). However, increased maintenance may be expected.




Figure 5.34. (a) Deformation coefficients used to evaluate structural integrity of multi-storey buildings in Vorkuta in northwestern Russia (Oberman, 2003a). A deformation coefficient (C_d) of 1, means that no deterioration will take place. Increasing C_d indicates increasing deterioration of the building and a value of 9 means that major repairs or demolition of the building is necessary. (b) Catastrophic deformations of buildings are remarkably confined to only one of three decades (i.e. to the 1980s). These are the years characterized by the greatest increase in temperatures of permafrost composed of mineral Quaternary deposits and peat.




Figure 5.35. Mean annual air temperature and maximum winter snow depth recorded at the Vorkuta meteorological station, northwestern Russia. Source: Romanovsky et al. (2010a).

Similar conclusions have been drawn from Canadian studies. Currently, there are three small-diameter pipelines operating in northern Canada, with the longest being the 869 km oil pipeline transecting the discontinuous permafrost zone from Norman Wells in the Northwest Territories to Zama, Alberta. The Norman Wells pipeline, in operation since 1985, is an ambient line and is the only oil pipeline in North America that is completely buried in permafrost. An extensive monitoring program carried out by the pipeline operator and the Canadian Government (e.g., Naviq Consulting Inc and AMEC Earth and Environmental, 2007; Smith et al., 2008a; Burgess et al., 2010) concluded that although climate change was not considered in the design, thaw penetration and thaw settlement beneath the right-of-way has remained generally within design values. Climate change effects have been largely obscured by the effects of vegetation clearing and thermal effects of the pipe (Burgess and Smith, 2003; Smith et al., 2008a), especially during the first decade of operation as permafrost was responding to an abrupt change in ground surface temperature of about 2 °C. Warming of permafrost is occurring in the adjacent undisturbed terrain which is consistent with rising air temperatures (Smith et al., 2005a) and these effects of ongoing climate warming on the pipeline right-of-way are projected to become more apparent over the longer-term, becoming the dominant influence after 25 to 50 years of pipeline operation (Smith and Riseborough, 2010).

In contrast to the situation in Alaska and Canada, the rapid expansion of pipeline construction in Russian permafrost areas has caused problems with above-ground pipelines due to thawing of ice-rich soils and frost heave of pipeline foundations (Perlshtein, 2008). On average, about 35 000 failures are registered annually affecting the 350 000 km long network of




Figure 5.36. Time series of ground temperatures at 10 and 15 m depth at different locations within the Vorkuta research region. All the boreholes numbered above have the following landscape description: ZS-124 – peatland with ice wedge polygons; KT-36 flat surface of an alluvial-marine terrace; P-92 – gently sloping surface of an alluvial-lacustrine plain; P-57 – flat surface of an alluvial-lacustrine plain; BK-1615 – catchment of a glacial-marine plain; DS-3 – ice wedge polygons on a glacial-marine plain; YA-1 – within a water track on an erosional plain. Source: Romanovsky et al. (2010a).

pipelines in western Siberia: more than 20% are most probably due to deformations and weakening of foundations induced by permafrost thaw (Anisimov and Reneva, 2006). Uplift of 1.5 m due to frost heave has been observed in a single year along the Urengoy pipeline (Pazinyak, 2001). These effects are likely to be related to construction (i.e., right-of-way clearing and leveling, etc.) and to operation of the pipelines and not directly linked to climate change.

Many of the failures in Arctic Russia occurred on marginal pipelines connecting the extracting facilities at specific locations with larger hubs partly because construction and maintenance of smaller pipelines are under relatively loose control compared to main transportation lines. Nevertheless, damage to such pipelines may have dramatic environmental impacts. In 1994, the break of the pipeline connecting the *Vozel* oilfield extracting facilities with the hub 'Golovnyue Souruzhenija', resulted in a spill of 160 000 tons of oil-containing liquid, the world's largest terrestrial oil spill. Soil contamination in the surrounding area is still high, 15 years later. Although a Russian commission concluded that the cause of the leak was corrosion, surveyors and local operating engineers argued that it was caused by differential thaw settlement which was estimated to be 0.5 to 1.5 m (Oberman, 2007). Similarly, thermokarst and uneven ground settlement led to significant deformation of a 45 km-long test pipeline section in the Pechora region after a few years of construction. Although it is debatable whether the real cause was inappropriate engineering design, the experience illustrates high vulnerability of constructions built in sporadic permafrost environments to changes in the thermal state of the frozen ground (Oberman, 2003b).

5.3.5.1.3. Roads, railroads and runways

Changes in weather and climate extremes can have considerable impact on transportation systems (Peterson et al., 2008). In permafrost regions, the possible climate impacts on road operations are related to degradation of the pavement structure due to permafrost warming and thawing. This can lead to

reduced traffic speed, higher accident risk (landslide), and road closure.

Kondratiev (2008) presented an evaluation of recent construction of railroads and highways on permafrost in Russia and China over the past 10 years. For more than 100 years, construction experience of roads and railroads on ice-rich permafrost soils shows that thaw settlement and frost heave have occurred with or without climate warming. The lifetime of a road on ice-rich permafrost is relatively short, typically less than 20 years. It is therefore expected that road systems will be upgraded regularly and that a gradual adaptation to climate change is possible. In Alaska, the runway serving the Prudhoe Bay oilfields has been reconstructed due to settling from thawing permafrost (Hinzman et al., 2005). In Nunavik, permafrost degradation is threatening the integrity of roads and airfields (Ministère des Transports, 2005).

Since its completion in 1975, the Svalbard airport runway has experienced pavement unevenness mainly caused by thaw subsidence (and consequent frost heave) of the ice-rich soil layers in the embankment (Instanes and Mjurreke, 2005). Observed climate warming was not found to be responsible for the recent damage to the runway and the projected climate scenarios do not pose an immediate threat. However, compared to the current situation, maintenance costs will probably increase during climate warming, but it is possible to gradually adjust the runway to a warmer climate by applying insulation or more frequent maintenance.

In the polar regions, the stable solid platform provided by frozen ground is utilized for winter transportation, and also for resource exploration and construction activities. Thawing of permafrost and changes in the length of the thaw season could have an effect on economic activity in these regions through changes in the seasonal scheduling and shortening of the period over which these activities may take place (Prowse et al., 2009). The timing of the freezing and thawing of the active layer will be important, as will frost penetration in non-permafrost areas within the discontinuous permafrost zone. It is anticipated that the length of the freezing season will decrease in response to climate warming and during extreme, warm years that the thaw season may be extended (e.g., Atkinson et al., 2006; Smith et al., 2009a).

5.3.5.1.4. Effluent storage

In a changing climate, structures need to maintain their integrity over periods of many decades to centuries as structural failure may have significant consequences, such as the release of contaminated effluents into the surrounding environment, with consequent impacts on ecosystems and human health. Remedial action may be required to maintain the structural integrity of such sites. For high-risk projects such as water retaining structures, tailings and storage facilities for hazardous waste, the environmental protection agencies can apply the principle of ‘perpetual’ design (discussed further in Section 5.4).

5.3.5.2. Natural resources

5.3.5.2.1. Fossil fuels

The Arctic contains large amounts of fossil fuels and is an important supplier of oil and gas to the global market (Table 5.3).

According to Lindholt (2006), 97% of total Arctic oil and gas production is located in Russia and Alaska (Alaska contributes 20% of total US production). Most fields are located onshore, but there are substantial reserves in the Beaufort Sea and Pechora Sea. In addition, Canada, Greenland and the Barents Sea are potential locations for future major oil and gas activities. The undiscovered resources of global oil and gas reserves are estimated at 20.5% and 27.6%, respectively (Lindholt, 2006). The United States Geological Survey has estimated the undiscovered resources of oil and oil-equivalent natural gas at 412 000 million barrels of oil equivalent (Bird et al., 2008).

The Arctic Monitoring and Assessment Programme has published an assessment of oil and gas activities in the Arctic (AMAP, 2007). The main findings relevant to the present study are that oil and gas activity in the Arctic is likely to increase and that the technology and use of best practices have lowered environmental impacts to date, but that additional risks may occur as conditions change or new areas are explored and developed. It is possible that climate change will have both positive and negative financial impacts on the exploration, production, and transportation activities of this industry.

Oil and gas are mainly transported within the Arctic through pipelines and in tankers. Climate change impacts on oil and gas development have so far been minor, but are likely to result in financial costs and benefits in the future. For example, the warming and thawing of permafrost, on which buildings, pipelines, airfields, and coastal installations supporting oil development are located, is very likely to adversely affect these structures and the costs of maintaining them (see Section 5.3.5.1).

5.3.5.2.3. Mining

The Arctic holds large stores of minerals, ranging from coal to gemstones and fertilizers (Lindholt, 2006) and is an important contributor of raw materials to national and global economies. It is also expected that the Arctic contains large reserves of undiscovered resources of raw materials. However, many known reserves are not exploited at present due to inaccessibility.

Russia extracts the largest quantities of minerals, including nickel, copper, platinum, apatite, tin, diamonds, and gold, mostly on the Kola Peninsula but also in Siberia (see Table 5.2). Three diamond mines are currently operating in the Canadian Arctic, and it is likely that mining activity there will increase in the future (Prowse et al., 2009). The main deposits include coal, cobalt, copper, barium, beryllium, bismuth, diamonds, gold, iron, lead, lithium, nickel, niobium, silver, tantalum, tungsten, uranium, and zinc. Coal and gold mining continues in Alaska, along with the extraction of lead and zinc deposits from the Red Dog Mine, which contains two-thirds of the US zinc resources.

Mining activities in the Arctic are likely to benefit from improved transportation conditions, although the actual extraction process is unlikely to be much affected by climate

Table 5.3. Arctic petroleum reserves as a percentage of the global total (Lindholt, 2006).

Reserves	Oil, %	Gas, %
Production	10.5	25.5
Proven reserves	5.3	21.7
Undiscovered resources	20.5	27.6

change. However, climate change effects on permafrost will possibly affect those maintenance, waste and tailing containment facilities that rely on frozen conditions to isolate contaminants from the environment. Mining facilities with roads on permafrost are likely to experience higher maintenance costs as the permafrost thaws (Instanes et al., 2005). Any expansion in oil and gas activities and mining in the Arctic is likely to require the expansion of air, sea, and land transportation systems (see Section 5.3.5.1.3).

5.3.5.3. Relocation of communities

Inuit communities are located in predominately low-lying coastal zones, and many already have to take action to protect shorelines and buildings, and to consider future relocation as a result of encroaching erosion and existing damage (Furgal and Prowse, 2008). Four indigenous communities in Alaska are planning relocation due to coastal erosion and flooding (Bronen, 2008). However, according to Bronen (2008) this process is problematic for various reasons, including: the lack of a government agency with the authority to relocate communities; lack of funding specifically designed for relocation; lack of criteria for selecting relocation sites; and, the lack of a governmental organization responsible for the strategic planning of relocation. As a consequence, while adaptation is technically possible, governance issues are hindering appropriate responses to climate change impacts on coastal permafrost.

5.4. Strategies for adapting to climate change effects in permafrost regions

- For more than 100 years, construction experience of roads and railroads on ice-rich permafrost soils shows that thaw settlement and frost heave have occurred with or without climate warming.
- The added problem of climate-driven permafrost thaw now requires more maintenance of existing structures, and more effective design and practice with a forward vision for new structures.
- There is an increased acknowledgment and consideration of climate change and its impacts on permafrost in engineering design, particularly for structures for which there are high consequences of failure. New maps based on a probabilistic approach of infrastructure susceptibility to permafrost thaw in Eurasia show that large areas of Russia, especially in a zone along the coast have a high susceptibility of buildings and engineered structures to ongoing changes in climate and permafrost.
- Much of the literature on geohazards, social science and policy in polar regions, fails to adequately address issues related to the effects of climate change on permafrost, so developing adaptation strategies could be difficult.

Thawing permafrost is just one of many stressors that will lead to environmental change to which we need to adapt. Direct adaptations to thawing permafrost *per se* involve infrastructure, whereas other impacts of thawing permafrost, such as impacts on ecosystems, require adaptations (to opportunities and

problems) that also involve globalization, changes in culture, and socio-economic issues. This assessment addresses direct adaptations of infrastructure development that arise from thawing permafrost induced by climate change. The impact that Arctic communities can have on mitigating future changes in climate, and therefore permafrost, is likely to be insignificant. As mitigation at a global scale is likely to be a slow process, Arctic communities, governance and organizations outside the Arctic but with involvement in Arctic infrastructure, must therefore adapt. Some of these adaptations will be to processes that take place over long periods and that are continuous over time, whereas rapid changes (e.g., following threshold exceedence and extreme events) may even require the development of emergency contingency plans.

Construction work and infrastructure development in ice-rich permafrost is very likely to cause thawing of the underlying ice-rich permafrost and frost heave problems if proper engineering solutions are not applied. The Fourth Assessment of the Intergovernmental Panel on Climate Change acknowledged this problem with the statement “*Although several recent scientific and media reports have linked widespread damage to infrastructure with climate change [...], the effect of heated buildings on underlying ice-rich permafrost can easily be mistaken for a climate-change impact*” (Anisimov et al., 2007). For example, the majority (but not all: see Sections 5.3.5.1.1 and 5.3.5.1.2) of damage to structures in the Russian permafrost regions in the period 1980 to 2000 resulted mainly from poor maintenance rather than climatic change (Kronik, 2001). The added problem of climate-driven permafrost thaw now requires more effective design and practice with a forward vision. However, much of the literature treating geohazards, social science and policy in polar regions fails to adequately address issues related to the effects of climate change on permafrost (Nelson et al., 2002), so developing adaptation strategies could be difficult.

Furgal and Prowse (2008) stated that adaptation of northern infrastructure to climate change will mainly involve approaches already in use to reduce thermal and mechanical impacts of ground disturbance, see for example Instanes (2003), Instanes and Instanes (2008), and Kondratiev (2008). Adaptive responses require monitoring in order to evaluate infrastructure performance, to determine if changes in permafrost condition deviate from those predicted, and to decide whether additional adaptation measures are required.

The US Arctic Research Commission Permafrost Task Force (2003) listed the following strategies related to infrastructure in permafrost areas and global warming:

- To consider climate change, as predicted by global circulation models, weighed by associated probabilities, to make decisions regarding new infrastructure on permafrost more credible.
- To fund a denser network of environmental monitoring.
- To substantially increase federal funding for contaminant research in cold (permafrost) regions.

In the construction industry, various methods have been suggested to address temperature-related foundation problems. Techniques to reduce warming and thawing, such as heat pumps, convection embankments, thermosyphons, winter-ventilated ducts, and passive cooling systems, are already common practice

in North America, Scandinavia, and Russia (Instanes et al., 2005). For example, a majority of the 80 flat loop thermosyphon foundations examined in northern Canada have demonstrated that this design provides an economical foundation system that will function for some time even with climate warming affecting the permafrost (Holubec et al., 2008). Instanes and Instanes (2008) advocated a foundation system in permafrost regions using a heat pump system. The system has been used on six different buildings on continuous permafrost in Longyearbyen and Sveagruva, Svalbard. It was found to be a good solution for buildings with on-ground (no elevation of the structure above ground) foundations over ice-rich permafrost soils. These types of foundation require insulation material underneath the concrete floor slab and a cooling system underneath the insulation to prevent thawing of the underlying ice-rich permafrost. This type of foundation design may also be beneficial to mitigate the effect of possible future climate warming on the structure. The heat pump cooling system is designed to decrease the temperature of the soils supporting the permafrost foundations to a design value. The heat extracted from the ground is used for heating the building above.

Facilities constructed several years ago and which need to maintain their integrity over long periods present a particular challenge as they were not designed for the warmer conditions of today or for those projected for the future. Remedial action may therefore be required if additional thawing of permafrost associated with climate warming, and subsequent changes in soil strength and settlement exceed the original design values. This may include modifications to pad or embankment design or the use of passive cooling to ensure frozen conditions in the future (Prowse et al., 2009). Waste-containment facilities that depend on encapsulation of waste in permafrost, ice-cored water retention structures, or dams to isolate contaminants from the environment are examples of structures that may require remedial action to maintain their structural integrity. The effects of climate change have been incorporated in the design of such structures in Canada since the mid-1990s. Examples are structures to contain mine tailings or related to reclamation of DEW line sites (e.g., Hayley, 2004; Hayley and Horne, 2008; Prowse et al., 2009). Designing for climate change can include the use of techniques to promote and maintain frozen conditions (such as passive cooling devices like thermosyphons) and improved cover designs to provide additional insulation or the use of convective cooling, as was used for waste rock piles at the Diavik diamond mine in the Northwest Territories, Canada (e.g., MEND, 2004; Arenson et al., 2007; Pham et al., 2008a,b). Other measures can include employment of a geomembrane layer that will also provide defense against loss of containment (Hayley and Horne, 2008).

5.4.1. Facilitating adaptation at the regional scale

Comprehensive high-resolution permafrost projections are needed to develop strategies of adaptation to the effects of warming on infrastructure in the Arctic on a regional scale. Many of the geomorphological processes resulting from thawing permafrost are relatively well studied and may be predicted using process-oriented models coupled with scenarios of climate change. Smith and Burgess (2004) mapped the sensitivity of permafrost

in Canada to warming and characterized areas in terms of the potential for thaw settlement and therefore highlighted areas where impacts of warming may have implications for infrastructure design. A numeric index was suggested by Nelson et al. (2002) to evaluate the potential threats to engineered structures due to warming and thawing of permafrost. The more recent study by Anisimov and Lavrov (2004) used a modified hazard index that also includes soil salinity, which is particularly important in the vicinity of the Arctic shoreline.

The basic assumption behind these ‘settlement indices’ is that the potential threats to infrastructure appear when seasonal thawing propagates deeper into the ground, and that high ice content and salinity of the soil increase the susceptibility of the existing structures to such threats. A recent map of the distribution of the hazard index over northern Eurasia, calculated using the 2050 GFDL-based climatic projection under the IPCC B2 emissions scenario, is illustrated in Figure 5.37 (Anisimov and Lavrov, 2004; Instanes and Anisimov, 2008).

Hazard index calculations partition the permafrost region into areas with ‘low’, ‘moderate’, and ‘high’ susceptibility of the infrastructure to climate-induced change. A zone in the high-susceptibility category extends discontinuously around the Arctic Ocean, indicating high potential for coastal erosion. Large parts of central Siberia, particularly the Sakha Republic (Yakutia), and the Russian Far East show moderate or high susceptibility.

Particular concern is associated with the Yamal Peninsula, which falls into the highest risk zone because of the ongoing expansion of the oil and gas extracting and transportation industry into this region. Despite the relatively low temperatures, frozen ground in this area is already unstable, largely because of its high salinity, and thus even small increases in temperature may cause extensive thawing of permafrost and ground settlement. Areas of lower susceptibility are associated with mountainous terrain, landscapes in which bedrock is at or near the surface, and permafrost with low ice content.

Hazard index maps such as the one shown in Figure 5.37 provide support in decision-making with regard to strategies of adaptation to projected changes, including the various engineering applications discussed previously. Particular solutions depend on the regional permafrost projection, are structure-specific, and are often based on cost-benefit analysis. Life expectancy should be incorporated in the design of each construction, as should aging of the structures as this amplifies the effect of a decrease in the load-bearing capacity of the frozen ground.

Until recently, the intrinsically deterministic nature of models that neglect the stochastic variability of permafrost parameters was one of the factors complicating realistic evaluation of potential threats to the infrastructure at regional geographical scales. Unlike these conventional models, the new type of models that have recently been developed (Anisimov et al., 2002; Anisimov, 2009) take into account the probabilistic nature of climatic projections and small-scale spatial variability of permafrost parameters, such as ground temperature and active-layer thickness. Aside from portraying the level of uncertainty on maps representing spatial distribution of permafrost parameters, output from a stochastic model can be used to construct a series of maps depicting the probability of the parameters to exceed given thresholds within specified regions.

Probabilistic maps deliver important information supplementing traditional maps, which depict only ‘average’




Figure 5.37. Predictive map of potential threats to infrastructure for 2050 in Russian permafrost regions. Colors denote regions with high, moderate, and low susceptibility of buildings and engineered structures to ongoing climatic and permafrost changes (updated from Instanes and Anisimov, 2008). Compared to the original publication, areas with isolated permafrost islands within the sporadic zone have been eliminated using the IPA digital map of permafrost and ground ice conditions. Major oil and gas pipelines and oil and gas fields have been added.

or ‘typical’ values. The probability approach requires the construction of several maps for a region, each for a given threshold. The more thresholds used, the better the set of probabilistic maps in representing the spatially distributed probability density function (PDF) of permafrost parameters.

An example of a probabilistic active-layer thickness map for the northern Eurasian permafrost region under the current climatic conditions is given in Figure 5.38 (Anisimov, 2009). Similar maps may be constructed for permafrost temperature, which is a key parameter that is accounted for in the design of pile foundations in permafrost regions. Such maps have direct implications in predictive permafrost hazard assessment. They indicate the proximity of the current state of permafrost in any region to the threshold beyond which structures designed for prescribed climatic conditions may become unstable.

5.4.2. Adaptation at the local scale

Esch and Osterkamp (1990) summarized engineering concerns related to permafrost warming (Table 5.4). The Arctic Climate Impact Assessment addressed these challenges and typical engineering projects that are likely to be affected by climate change (Instanes et al., 2005).

5.4.2.1. Permafrost engineering design criteria for climate change

In engineering science, there are generally two main design approaches: the deterministic approach and the probabilistic approach.

In the *deterministic approach*, fixed values are assigned to input parameters and calculations are performed with one set of values to arrive at a solution; sensitivity analyses may be performed by changing the fixed values and comparing solutions. In permafrost regions, most of the smaller and more basic projects are being analyzed using deterministic methods, but work is advancing on defining appropriate parameters.

The *probabilistic approach* recognizes that uncertainty exists in the solution to a problem. The uncertainty can be attributed both to the deterministic model and to the inherent variability of the input parameters that support the calculation. In permafrost regions, larger projects with more agency oversight are moving toward more probabilistic methods and in some cases risk-based analysis. Meyer (2008) recently advocated a risk-oriented, probabilistic design procedure in order to define design characteristics for components that could be affected by changing environmental and climatic factors.

Probability of active-layer thickness exceeding threshold limits




Figure 5.38. Probabilistic map of active-layer thickness for Eurasia under current climatic conditions. The scale shows probabilities of active-layer thickness exceeding the threshold limits assigned to each panel. Source: Anisimov (2009).

The design lifetime of a structure in permafrost areas typically varies between 15 and 75 years (Table 5.5). Buildings and infrastructure constructed on permafrost and designed for permafrost conditions are, therefore, unlikely to be adversely impacted during typical engineering design lifetimes. However, the concept and requirement of ‘perpetual design’ is becoming more common. For high-risk projects such as water-retaining structures, tailings and storage facilities for hazardous waste, the environmental protection agencies can apply such principles to the design.

5.4.2.1.1. Risk-based evaluation

Bush et al. (1998) presented a methodology for considering the impact of projected climate change within the framework of the engineering design process; see also Hayley and Horne (2008). They also explained how the same methodology can be

used to identify and prioritize concerns about existing facilities with respect to climate change impacts. The method involves a multi-step approach that first assesses the sensitivity of a given project to climate change and then the consequences of any potential failures (Bush et al., 1998). The relationship between sensitivity and consequences defines the risk that climate change poses to the project. The degree of sensitivity and the severity of the consequences are used to determine what level of climate-change impact analysis should be carried out for a given project (Table 5.6).

The sensitivity of a particular infrastructure project to climate change is determined by a number of factors, including initial soil and permafrost temperature, the temperature dependence of the material properties, the project lifetime, and the existing over-design or safety margin that might be included in the design for other reasons.

Table 5.4. Climate change impact and related engineering problem.

Climate change impact	Engineering problem	Adaptation suggestion
Thawing of permafrost (development of taliks)	Decrease in effective pile length in permafrost	Increase pile length
	Progressive mass movements (landslides)	Relocation
	Progressive surface settlements	Artificial cooling of foundations
Increased active-layer thickness	Thaw settlement during seasonal thawing	Insulation
	Increased frost heave forces on piles	Increase pile length, protection / treatment of pile in active layer to reduce frost heave forces
	Increased total and differential frost heave during winter	
Warming of permafrost at depth	Increased creep rate of existing piles and footings	Increase pile length, and depth and area of footings. Reduce foundation load.
	Reduced ad-freeze bond strength for piles	Artificial cooling of foundations.
	Increased creep of embankment footings	

Table 5.5. Typical design lifetime for structures in permafrost areas.

Structure	Lifetime
Roads	15 to 20 years
Oil and gas pipelines	30 years
Buildings	30 to 50 years
Railroads	50 years
Bridges and underpasses	75 to 100 years

Recently, Hayley and Horne (2008) described a screening process for engineering projects that includes a procedure for qualitative assessment of climate sensitivity, based on soil type and permafrost temperature. This procedure has been applied to engineering projects in northern Canada. Currently, this procedure does not have official status in Canada, but the method provides a useful tool to evaluate the climate sensitivity of engineering projects.

This approach requires site-specific analyses. Several recent site-specific analyses of the effect of climate warming on engineering projects are available in the literature (Clarke et al., 2008; Hayley and Horne, 2008; Instanes and Anisimov, 2008; Nishimura et al., 2009a,b; Zhou et al., 2009). These analyses give an indication of how specific structures respond to climate warming so that their climate sensitivities can then be determined.

5.4.2.1.2. Probability of occurrence based on output from general circulation models

An alternative approach to developing permafrost engineering design criteria for climate change is to use the output from downscaled general circulation models (GCMs) to construct scenarios of future air temperature at given locations between the present time and a set time in the future, such as 2100. These data can be used to investigate how the probability of occurrence of active-layer thickness and permafrost temperature at depth changes with time and climate scenario (Instanes, 2003). In this manner, climate warming can be

treated like any other environmental load (such as earthquakes, wind, waves, currents). It is believed that this approach could also incorporate the concept of ‘perpetual design’.

5.4.2.1.3. Monitoring

Monitoring of existing structures on permafrost, follow-up of historical data, and back-calculation of known failures are important to gain a better understanding of long-term behavior of structures on permafrost. For existing projects such as the Norman Wells pipeline in northern Canada, monitoring programs are important not only for facilitating the mitigation of environmental impacts associated with the project (Naviq Consulting Inc and AMEC Earth and Environmental, 2007; Prowse et al., 2009; Burgess et al., 2010) but also for mitigating the effects of ongoing climate change. The monitoring results and their dissemination in publicly available databases (Smith et al., 2004, 2008c) are also important for the design of future hydrocarbon projects, including the incorporation of climate change. Recognition of the importance of baseline information on permafrost condition and ongoing monitoring of permafrost thermal state, led the Canadian Government to enhance the permafrost monitoring program in the Mackenzie region. This helps ensure that impacts related to hydrocarbon development in the region, including those associated with climate change, would be minimized. These efforts have already generated key data (Smith et al., 2008d, 2009b) that are being incorporated in project design and contributing to the regulatory process.

5.4.2.1.4. Heritage

Permafrost preserves ancient life forms. It also preserves more recent records of human culture and biota that are of considerable value to archaeologists and paleontologists, respectively. As permafrost thaws, these unique records will be destroyed. An adaptive response is to survey areas of thawing permafrost from the perspective of interrogating and, if possible, conserving its archives of past environments, cultures and biota: this is currently being done to document the numerous tombs of the 2500 year-old lost Scythian civilization that are preserved by permafrost in the Altai mountains (Goossens et al., 2007).

Table 5.6. Engineering risk levels (Bush et al. 1998).

Likelihood (Bush et al., 1998)	Frequent	Probable	Occasional	Remote	Improbable
Probability of occurrence in one single year (Instanes, 2003)	50%	20%	10%	1%	0.01%
Predicted number of occurrences (Instanes, 2003)	Once in 2 years	Once in 5 years	Once in 10 years	Once in 100 years	Once in 10 000 years
Consequence					
Negligible	C	C	D	D	D
Minor	A	B	B	C	C
Major	A	A	B	B	C
Catastrophic	A	A	A	A	B

Risk level A: Detailed quantitative analyses are required. Refine input parameters with additional investigation and testing. Perform full-scale monitoring program with periodic evaluation of performance. Independent expert review required.

Risk level B: Semi-quantitative (or limited quantitative) analyses are required. In addition to requirements for C, perform limited quantitative analysis. Use engineering judgment for input parameters. Monitor permafrost performance. Perform full quantitative evaluation for projects with limited precedence.

Risk level C: Qualitative analyses are required. Apply expert judgment. Document result of evaluation. Perform quantitative evaluation for projects with limited precedence in design, function, or construction method.

Risk level D: Analyses not required. No action required.

5.5. Uncertainties and recommendations

5.5.1. Data needs and priorities for permafrost research

- Permafrost dynamics are observed in many ways, both in the field and remotely. However, there is insufficient interaction among the various observation communities. *There is a need to better integrate observing techniques including the further development of remote sensing to complement in situ observations and expansion of in situ observations to validate and explain information derived from remote sensing and modeling.*
- Field based observation sites and networks are sparse relative to the geographic extent and environmental complexity of the Arctic. However, these are extremely important as they provide the data (permafrost temperature, ice content, active-layer thickness etc.) to understand baseline conditions and to characterize change. They are also essential to reduce uncertainty in predictions of future conditions and field data are also used to better understand how permafrost conditions influence the biophysical environment and processes. *We urgently recommend the maintenance and enhancement of field observation sites and networks.*
- There is yet no comprehensive circumpolar assessment of thermokarst extent. While thermokarst development has been quantified in many small areas, confidence in the rates of change is limited by the sparse time series of historical imagery and the sensitivity of the measurements to seasonal phenology and interannual differences in precipitation. There is a lack of sufficient data and models to predict the distribution of ground ice, a dominant factor controlling the magnitude of thaw settlement. In addition, there are no satisfactory methods to remotely sense permafrost degradation in ice-poor soils. *Further progress in assessing the response of thermokarst terrain to climate change requires large advances in data acquisition, monitoring, and modeling as well as integration of permafrost, geomorphic, hydrological, thermal, ground-ice, and ecosystem-succession models to address the full range of complex biophysical interactions.*
- There are considerable uncertainties in modeling future permafrost distribution and dynamics. These include an under-representation of the ice content and the organic layer and its importance in insulating permafrost during climatic warming. Permafrost models also fail to adequately represent the disequilibrium that has arisen because some current permafrost is related to past climates. This results in a lag period between a climatic change and a response of the permafrost. *We recommend therefore, that priority be given to acquiring baseline information of specific relevance to model refinement.*
- There is too little integration of climate-cryosphere research. *We recommend the development of integrated research programs that include other components of the cryosphere, such as hydrological systems with permafrost and snow permafrost interaction, to give a holistic understanding of the climate-cryosphere system.*

- Permafrost landform dynamics and their climatic and local controls are poorly understood relative to permafrost temperatures and active-layer thickness. *It is necessary therefore, to extend permafrost observations to include permafrost landform dynamics and their drivers.*
- The underlying sources of important oscillations in atmospheric methane concentrations are poorly understood, but are most likely to be related to northern wetland dynamics. *It is therefore necessary and important to gather more data for year-round in situ emission dynamics.*
- Arctic carbon stocks have previously been underestimated. *A key need is to revise these earlier estimates and to project the future role of permafrost carbon pools in the global carbon cycle.*
- Measurements of carbon emissions from permafrost areas on land and sea are biased to vertical fluxes. However, there is also important lateral transport of carbon, such as in polynyas. Seasonal observations of such transport are hindered by sea-ice formation and movement. *Techniques need to be developed and deployed to measure lateral fluxes of carbon in the shelf environment.*
- Changing permafrost conditions are likely to have considerable socio-economic effects but it is difficult to bridge the gap between the science of permafrost and the assessments of socio-economic impacts, which are studied by different communities with different cultures of publication. *There should be a strengthening and integration of the projections of changing permafrost with socio-economic aspects of thawing.*

5.5.2. External use of improved understanding of permafrost

- Although there is a current move to refine the inclusion of knowledge of permafrost processes in climate models, *there is a need to set research priorities for developing the use of permafrost-related products in larger-scale climate and earth system models in a coupled manner.*
- While permafrost-related data are generally available to the scientific community, particularly within the discipline, other science disciplines and local stakeholders are often unaware of data on permafrost changes, their implications, and their uncertainties. *We recommend that the availability of permafrost-related data be increased for use by a variety of users, particularly those planning adaptation, including those outside the research community, such as engineers and land-use planners.*
- Research into impacts of thawing permafrost often needs to work at spatial and temporal scales that are currently inadequately represented in permafrost research. For example, responses of ecosystems and biogeochemical cycling as well as infrastructure may respond to temporal thresholds and extreme events while development of adaptation strategies is spatially a local process that requires local permafrost projections. *We recommend that more priority be given to downscaling models of permafrost change to scales appropriate to local decision-makers and that projection of impacts of changing permafrost focus more on responses to thresholds and extreme events.*

5.6. Conclusions

5.6.1. Recent advances in understanding

There is a growing awareness of the increased thawing of permafrost and its importance (ACIA, 2005; Solomon et al., 2007). However, many uncertainties existed in the projections of permafrost condition, its responses to climate warming, and its impacts particularly on greenhouse gas emissions. For example, there was a realization of the potential importance of carbon fluxes from degrading terrestrial permafrost and particularly the ‘wildcard’ of potential methane release from subsea permafrost, but this was poorly quantified. In addition, the observing networks of permafrost thermal state and active-layer thickness were sparse and integration of results was tentative.

Since the benchmark studies of the Arctic Climate Impact Assessment (ACIA, 2005) and the Fourth Assessment of the Intergovernmental Panel on Climate Change (Asimov et al., 2007), there have been many advances in the understanding of permafrost responses to climate warming, although some uncertainties remain. Some of these advances have appeared through the intensive program of permafrost research during the International Polar Year (IPY) and the Ninth International Conference on Permafrost (for which the proceedings have been published, see Kane and Hinkel, 2008). In particular, a coordinated international effort during the IPY has led to a more complete and updated baseline of the current permafrost thermal state and a characterization of changes that have occurred over the past 20 to 30 years throughout the Arctic.

Major advances include recent observations of increased methane levels in the atmosphere above the sea surface in the East Siberian Sea, reaching 8.2 ppm during 2005, and estimates that more than 50% of the East Siberian Arctic Shelf area studied served as a source of methane to the atmosphere between 2003 and 2008. Furthermore, there has been a significant upward revision in estimates of carbon stocks occurring in terrestrial permafrost. Both advances have significant implications for the potential amplification of climate warming. In addition, models projecting change in permafrost condition have been significantly improved by including deeper permafrost as well as the organic layer, resulting in lower estimates of future permafrost thaw. Interactions between climate-driven thawing of permafrost and biological processes are complex but nevertheless understanding has improved. In particular, there is a new recognition of the importance of permafrost in preserving past life, sometimes in a viable form.

5.6.2. The human face of permafrost change

This assessment explores the socio-economic implications of thawing permafrost together with the possibilities for adapting to its impacts. Major new messages are that the technology is available to adapt buildings and other infrastructure to thawing permafrost, and that previously recorded incidents of infrastructure failure were probably more related to engineering and design problems than to climate change. There has also been an increased effort in recent years to incorporate climate change into the design of major structures.

An important concept that needs emphasizing is that the science of permafrost needs to progress simultaneously

at two different spatial scales. First, the large regional scale is important to integrate the impacts of permafrost thawing on feedbacks to regional and local climate: this information, because of the potential size of the climate forcing and its global impacts should be used to drive global mitigation responses. Second, Arctic residents and those organizations outside the Arctic but with economic responsibilities/opportunities within the Arctic, need to adapt to local changes in permafrost and their consequences. As this adaptation is a local process, local projections are increasingly required from the permafrost research community.

5.6.3. ‘Winners and losers’

In contrast to other components of the changing Arctic cryosphere such as snow (see Chapter 4), thawing permafrost offers few opportunities but many challenges. Again, unlike the impacts of changing snow cover, thawing permafrost will result in few ‘winners’. However, when permafrost is completely lost at the southern margins of the current permafrost zone, communities will benefit in that they will no longer require special engineering design of infrastructure related to permafrost, and activities and land uses operating south of the current permafrost boundary (e.g., forestry and agriculture) are likely to migrate northward in some areas. Another possible advantage is that an increase in winter base flow in rivers could alleviate the need for freshwater supplies to large towns in Arctic Russia during winter. Overall, most of those involved in the Arctic can be regarded as ‘losers’: the large multinational industries and developers will face greater economic investment to stabilize infrastructure over longer periods, whereas individual residents will face disruption to communication routes and even resettlement in some cases.

Acknowledgments

The authors are grateful to the Swedish Department of Environment, the Swedish Environmental Protection Agency (grant number F-159-08) and the Swedish Research Council FORMAS (grant number 204-2009-45) for funding the involvement of the convening lead authors and for facilitating the involvement of Russian contributors. We also thank other national (United States, Canada, Norway) agencies for funding the participation of their respective lead authors. Many authors contributed written text, figures, tables and ideas and they are explicitly acknowledged on the title page, but we thank them here also. The AMAP SWIPA Secretariat gave valuable support throughout, and we thank the SWIPA Integration Team as well as authors of other SWIPA chapters for their pertinent discussions and encouragement. Finally we thank the numerous reviewers.

Appendix 5.1. Sources of information and data

Observational data

Observations of permafrost condition, including its thermal state and active-layer thickness are essential baseline data requirements for the design of Arctic infrastructure, to improve models to predict future permafrost condition, and to improve assessments of climate change impacts. Although there has been some development in the use of remote sensing of permafrost and related phenomena (Zhang et al., 2004; Duguay et al., 2005), most permafrost-related data, especially historical data, are from *in situ* measurements. These data meet a variety of user needs but their point-based nature and non-uniform spatial distribution presents some limitations, including utilization for spatial modeling purposes.

A key provider of this type of information is the Global Terrestrial Network for Permafrost (GTN-P) which was established under the Global Climate Observing System. GTN-P consists of two components (Burgess et al., 2000): the Thermal State of Permafrost (TSP), which conducts measurements of ground temperature in boreholes; and the Circumpolar Active Layer Monitoring (CALM) network, which provides measurements of active-layer thickness (e.g., Shiklomanov et al., 2008).

The GTN-P provides ongoing data on permafrost condition and the summary data are posted periodically on the websites for GTN-P (www.gtnp.org) and CALM (www.udel.edu/Geography/calm). The monitoring network was enhanced during the International Polar Year (Figure 5A.1) through the establishment of new permafrost observatories to address geographical gaps (Romanovsky et al., 2010b). An important dataset is the IPY snapshot which provides a database (Romanovsky et al. 2010b) and map (see Figure 5.8) that summarizes the thermal state of permafrost for the IPY period, 2007 to 2009 and provides a baseline against which future change can be measured in the Arctic. Data products

associated with the IPY are also being developed by various national organizations (see for example, Smith et al., 2008b; Juliussen et al., 2010).

The CALM network is a global network of sites at which data on active-layer thickness and dynamics are collected (Brown et al., 2000; Nelson et al., 2008). CALM was established in the early 1990s to observe and detect the long-term response of the active layer and near-surface permafrost to changes in climate. The CALM network incorporates 168 sites in Arctic, sub-Arctic, Antarctic, and mountainous regions. Several sites constitute longitudinal and latitudinal transects across northwestern North America, Europe and the Nordic region, and northeastern and northwestern Russia. About 70% of sites are located in Arctic and sub-Arctic lowlands in the zone of continuous permafrost. Regions of discontinuous and mountainous permafrost contain 20% and 11% of sites, respectively (Shiklomanov et al., 2008).

Historical permafrost data often exist within research data collections held by diverse institutions, including academia, government agencies and national and international data centers. The International Permafrost Association (IPA) has endeavored to compile much of this disaggregated data through the Global Geocryological Database (GGD); a metadata collection describing data in diverse locations around the world (Parsons et al., 2008). Building on from the GGD, the World Data Center for Glaciology at the National Snow and Ice Data Center in Boulder, has published two compendia of permafrost related data: Circumpolar Active-layer Permafrost System (CAPS) version 1 (IPA DIWG, 1998) and version 2 (IPA SCDIC, 2003). The IPY snapshot database is an update of these earlier data products. The data products provide information on monitoring site parameters, soil temperature, cryosols, and climatologies, as well as maps, metadata and bibliographies. They provide reasonable data snapshots and some time-series data but they are not current as the GTN-P databases will be when fully functional. Considerable efforts exist in various countries through government agencies to provide national/regional, freely accessible and downloadable information related to permafrost and of interest to a variety of users (see for example, Juliussen et al., 2010; Smith et al., 2004, 2009b).

There is likely to be a wealth of historical information that could be compiled into digital databases, but while some of these datasets will have been well managed, the utility of others may be limited (Parsons et al., 2008). Part of the reason for this is that the datasets may have been largely in the possession of individual researchers that are no longer available to provide documentation regarding site characteristics, measurement methods, instrumentation, accuracy and precision of measurements. Periglacial process data are also increasingly being collected but there is a lack of coordinated data management arrangements. However, some progress is being made in the management of process data, for example by the Norwegian IPY project and the associated NORPERM database (Juliussen et al., 2010).

Other limitations of existing data sets, such as those for the active layer and permafrost thermal state, also include a lack of continuity in the data record or a short data record. In addition,




Figure 5A.1. Long-term monitoring sites (blue dots) and sites that were established or where measurements were resumed during the International Polar Year (red dots). The sites are superimposed on the permafrost zones. Source: Romanovsky et al. (2010b).

there is an uneven distribution of study sites and a number of regional gaps exist. Although various analytical and modeling techniques are available to fill both temporal and spatial gaps (through for example spatially distributed models, Sazonova and Romanovsky 2003; Sazonova et al. 2004; Romanovsky et al., 2007), these synthetic datasets are not generally available.

References

- ACIA, 2005. Impacts of a Warming Arctic: Arctic Climate Impacts Assessment. 1042 pp. Cambridge University Press.
- Akagawa, S. and M. Fukuda, 1991. Frost heave mechanism in welded tuff. *Permafrost and Periglacial Processes*, 2:301–309.
- Akerman, H.J. and M. Johansson, 2008. Thawing permafrost and thicker active layers in sub-arctic Sweden. *Permafrost and Periglacial Processes*, 19:279–292.
- AMAP, 2007. Arctic Oil and Gas 2007. 40 pp. Arctic Monitoring and Assessment Programme, Oslo, Norway.
- André, M.F., 2003. Do periglacial landscapes evolve under periglacial conditions? *Geomorphology*, 52:149–164.
- André, M.F. and O. Anisimov, 2009. Tundra and permafrost-dominated taiga. In: Slaymaker, O., T. Spencer and C. Embleton-Hamann (Eds.). *Geomorphology and Global Environmental Change*, pp. 344–367. Cambridge University Press.
- Anisimov, O.A., 2009. Stochastic modelling of the active-layer thickness under conditions of the current and future climate. *Earth Cryosphere*, 3:36–45.
- Anisimov, O.A. and C.A. Lavrov, 2004. Global warming and permafrost degradation: risk assessment for the infrastructure of the oil and gas industry. *Technologies of oil and gas industry*, 3:78–83.
- Anisimov, O. and S. Reneva, 2006. Permafrost and changing climate: The Russian perspective. *Ambio*, 35:169–175.
- Anisimov, O.A., N.I. Shiklomanov and F.E. Nelson, 2002. Variability of seasonal thaw depth in permafrost regions: a stochastic modeling approach. *Ecological Modelling*, 153:217–227.
- Anisimov, O.A., D.G. Vaughan, T.V. Callaghan, C. Furgal, H. Marchant, T.D. Prowse, H. Vilhjalmsón and J.E. Walsh, 2007. Polar regions (Arctic and Antarctic). in: Parry, M.L., O.F. Canziani, J.P. Palutikof, P.J. van der Linden and C.E. Hanson (Eds.), *Climate Change 2007: Impacts, Adaptation and Vulnerability*. Contribution of Working Group II to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change, pp. 653–685. Cambridge University Press.
- Archer, D. and B. Buffett, 2005. Time-dependent response of the global ocean clathrate reservoir to climatic and anthropogenic forcing. *Geochemistry Geophysics Geosystems*, 6:Q03002.
- Are, F., E. Reimnitz, M. Grigoriev, H.W. Hubberten and V. Rachold, 2008. The influence of cryogenic processes on the erosional arctic shoreface. *Journal of Coastal Research*, 24:110–121.
- Arenson, L.U. and D.C. Sego, 2006. The effect of salinity on the freezing of coarse grained sands. *Canadian Geotechnical Journal*, 43:325–337.
- Arenson, L.U., S.M. Springman and D.C. Sego, 2007. The rheology of frozen soils. *Applied Rheology*, 17:1–14.
- Arneth, A., J. Kurbatova, O. Kolle, O.B. Shibistova, J. Lloyd, N.N. Vygodskaya and E.D. Schulze, 2002. Comparative ecosystem-atmosphere exchange of energy and mass in a European Russian and a central Siberian bog II. Interseasonal and interannual variability of CO₂ fluxes. *Tellus Series B-Chemical and Physical Meteorology*, 54:514–530.
- Atkinson, D.E., R. Brown, B. Alt, T. Agnew, J. Bourgeois, M. Burgess, C. Duguay, G. Henry, S. Jeffers, R. Koerner, A.G. Lewkowicz, S. McCourt, H. Melling, M. Sharp, S. Smith, A. Walker, K. Wilson, S. Wolfe, M.K. Woo and K.L. Young, 2006. Canadian cryospheric response to an anomalous warm summer: A synthesis of the climate change action fund project “The state of the arctic cryosphere during the extreme warm summer of 1998”. *Atmosphere-Ocean*, 44:347–375.
- Aurela, M., T. Laurila and J.P. Tuovinen, 2004. The timing of snow melt controls the annual CO₂ balance in a subarctic fen. *Geophysical Research Letters*, 31:L16119.
- Bäckstrand, K., P.M. Crill, M. Mastepanov, T.R. Christensen and D. Bastviken, 2008. Non-methane volatile organic compound flux from a subarctic mire in Northern Sweden. *Tellus Series B-Chemical and Physical Meteorology*, 60:226–237.
- Bäckstrand, K., P.M. Crill, M. Jackowicz-Korczyński, M. Mastepanov, T.R. Christensen and D. Bastviken, 2010. Annual carbon gas budget for a subarctic peatland, Northern Sweden. *Biogeosciences*, 7:95–108.
- Bakermans, C., H.L. Ayala-del-rio, M.A. Ponder, T. Vishnivetskaya, D. Gilichinsky, M.F. Thomashow and J.M. Tiedje, 2006. *Psychrobacter cryohalolentis* sp nov and *Psychrobacter arcticus* sp nov., isolated from Siberian permafrost. *International Journal of Systematic and Evolutionary Microbiology*, 56:1285–1291.
- Balobaev, V.T., A.V. Pavlov and G.Z. Perlshtein, 1983. Thermophysical investigations of Siberian permafrost. 215 pp. Nauka Publishing House, Novosibirsk.
- Baranov, I.Y., 1960. Geocryological map of the USSR, scale 1:10,000,000, Znanie publisher.
- Barr, A.G., T.A. Black, E.H. Hogg, T.J. Griffis, K. Morgenstern, N. Kljun, A. Theede and Z. Nesic, 2007. Climatic controls on the carbon and water balances of a boreal aspen forest, 1994–2003. *Global Change Biology*, 13:561–576.
- Barsch, D., 1996. Rockglaciers. Indicators for the Present and Former Geocology in High Mountain Environments. 331 pp. Springer.
- Baulin, V.V., 1985. Permafrost in Oil- and Gas-Production Regions of the Soviet Union. 176 pp. Nedra Publishing House, Moscow.
- Beilman, D.W. and S.D. Robinson, 2003. Peatland permafrost thaw and landform type along a climatic gradient. Paper presented at Eighth International Conference on Permafrost, pp. 61–66. Balkema Publishers.
- Benestad, R.E., 2007. Novel methods for inferring future changes in extreme rainfall over Northern Europe. *Climate Research*, 34:195–210.
- Betts, R.A., 2000. Offset of the potential carbon sink from boreal forestation by decreases in surface albedo. *Nature*, 408:187–190.
- Betts, A.K. and J.H. Ball, 1997. Albedo over the boreal forest. *Journal of Geophysical Research-Atmospheres*, 102:28901–28909.
- Biggar, K.W., S. Haidar, M. Nahir and P.M. Jarrett, 1998. Site investigations of fuel spill migration into permafrost. *Journal of Cold Regions Engineering*, 12:84–104.
- Bird, K.J., R.R. Charpentier, D.L. Gautier, D.W. Houseknecht, T.R. Klett, J.K. Pitman, T.E. Moore, C.J. Schenk, M.E. Tennyson and C.J. Wandrey, 2008. Circum-Arctic resource appraisal: estimates of undiscovered oil and gas north of the Arctic Circle. U.S. Geological Survey Fact Sheet. 4 pp. U.S. Geological Survey, Menlo Park, CA.
- Bockheim, J.G., 2007. Importance of cryoturbation in redistributing organic carbon in permafrost-affected soils. *Soil Science Society of America Journal*, 71:1335–1342.
- Bockheim, J.G. and K.M. Hinkel, 2007. The importance of “Deep” organic carbon in permafrost-affected soils of arctic Alaska. *Soil Science Society of America Journal*, 71:1889–1892.
- Bogoyavlenskiy, D. and A. Siggner, 2004. Arctic Demography. In: Einarsson, N., J.N. Larsen, A. Nilsson and O.R. Young (Eds.). *Arctic Human Development Report (AHDR)*, pp. 27–41. Arctic Institute, Akureyri, Iceland.
- Bonnaventure, P.P. and A.G. Lewkowicz, 2008. Mountain permafrost probability mapping using the BTS method in two climatically dissimilar locations, northwest Canada. *Canadian Journal of Earth Sciences*, 45:443–455.
- Bonnaventure, P.P. and A.G. Lewkowicz, 2010. Modelling climate change effects on the spatial distribution of mountain permafrost at three sites in northwest Canada. *Climatic Change*, 105:293–312.
- Borodavko, P.S., 2009. Climate-related changes in thermokarst terrain in Russian Altay Mountains. *Geophysical Research Abstracts*, 11:EGU2009-1803.
- Botch, M.S., K.I. Kobak, T.S. Vinson and T.P. Kolchugina, 1995. Carbon pools and accumulation in peatlands of the former Soviet Union. *Global Biogeochemical Cycles*, 9:37–46.
- Bronen, R., 2008. Alaskan communities’ rights and resilience. *Climate change and displacement*, 31:30–32.
- Brown, R.J.E. and T.L. Péwé, 1973. Distribution of permafrost in North America and its relationship to the environment: A review, 1963–1973. Paper presented at Permafrost: North American Contribution. Second International Conference on Permafrost, National Academy of Sciences, pp. 71–100.
- Brown, J. and V.E. Romanovsky, 2008. Report from the International Permafrost Association: State of permafrost in the first decade of the 21(st) century. *Permafrost and Periglacial Processes*, 19:255–260.

- Brown, J., O.J. Ferrians, Jr., J.A. Heginbottom and E.S. Melnikov, 1998. Circum-Arctic map of permafrost and ground-ice conditions. <http://nsidc.org/data/ggd318.html>. Accessed: October 13, 2010.
- Brown, J., K.M. Hinkel and F.E. Nelson, 2000. The Circumpolar Active Layer Monitoring (CALM) program: historical perspectives and initial results. *Polar Geography*, 24:165–258.
- Bunn, A.G., S.J. Goetz, J.S. Kimball and K. Zhang, 2007. Northern high latitude ecosystems respond to recent climate change. *EOS Transactions American Geophysical Union*, 88:333–335.
- Burgess, M.M. and S.L. Smith, 2003. 17 years of thaw penetration and surface settlement observations in permafrost terrain along the Norman Wells pipeline, Northwest Territories, Canada. Paper presented at Eighth International Conference on Permafrost, pp. 107–112. A. A. Balkema.
- Burgess, M.M., S.L. Smith, J. Brown, V. Romanovsky and K. Hinkel, 2000. Global Terrestrial Network for Permafrost (GTNet-P): permafrost monitoring contributing to global climate observations. *Geological Survey of Canada Current Research*. 2000-E14. 8 pp.
- Burgess, M.M., J. Oswell and S.L. Smith, 2010. Government-industry collaborative monitoring of a pipeline in permafrost - the Norman Wells Pipeline experience, Canada. Paper presented at GEO2010 - Proceedings, 63rd Canadian Geotechnical Conference and 6th Canadian Conference on Permafrost, pp. 579–586.
- Burn, C.R. and S.V. Kokelj, 2009. The environment and permafrost of the Mackenzie Delta area. *Permafrost and Periglacial Processes*, 20:83–105.
- Burn, C.R. and F.E. Nelson, 2006. Comment on “A projection of severe near-surface permafrost degradation during the 21st century” by David M. Lawrence and Andrew G. Slater. *Geophysical Research Letters*, 33:L21503.
- Burn, C.R. and M.W. Smith, 1990. Development of thermokarst lakes during the Holocene at sites near Mayo, Yukon Territory. *Permafrost and Periglacial Processes* 1:161–176.
- Burn, C.R. and Y. Zhang, 2009. Permafrost and climate change at Herschel Island (Qikiqtaruk), Yukon Territory, Canada. *Journal of Geophysical Research-Earth Surface*, 114:F02001.
- Bush, E., D.A. Etkin, D. Hayley, E. Hivon, B. Ladanyi, B. Lavender, G. Paoli, D. Riseborough, J. Smith and M. Smith, 1998. *Climate Change Impacts on Permafrost Engineering Design*. 40 pp. Environmental Adaptation Research Group, Environment Canada.
- CAFF, 2001. Arctic Flora and Fauna: Status and Conservation. 266 pp. Arctic Council Programme for the Conservation of Arctic Flora and Fauna, Helsinki.
- Callaghan, T.V., B.R. Werkman and R.M.M. Crawford, 2002. The tundra-taiga interface and its dynamics: Concepts and applications. *Ambio*, 12:6–14.
- Callaghan, T.V., L.O. Björn, Y. Chernov, F.S. Chapin, T.R. Christensen, B. Huntley, R.A. Ims, S. Jonasson, M. Johansson, D. Jolly, N. Matveyeva, N. Panikov, W.C. Oechel and G.R. Shaver, 2005. Tundra and polar desert ecosystems In: *Arctic Climate Impact Assessment*, pp. 243–352. Cambridge University Press.
- Camill, P., 1999. Patterns of boreal permafrost peatland vegetation across environmental gradients sensitive to climate warming. *Canadian Journal of Botany-Revue Canadienne de Botanique*, 77:721–733.
- Camill, P., 2005. Permafrost thaw accelerates in boreal peatlands during late-20th century climate warming. *Climatic Change*, 68:135–152.
- Camill, P., J.A. Lynch, J.S. Clark, J.B. Adams and B. Jordan, 2001. Changes in biomass, aboveground net primary production, and peat accumulation following permafrost thaw in the boreal peatlands of Manitoba, Canada. *Ecosystems*, 4:461–478.
- Camill, P., L. Chihara, B. Adams, C. Andreassi, A. Barry, S. Kalim, J. Limmer, M. Mandell and G. Rafert, 2010. Early life history transitions and recruitment of *Picea mariana* in thawed boreal permafrost peatlands. *Ecology*, 91:448–459.
- Castello, J.D., S.O. Rogers, J.E. Smith, W.T. Starmer and Y. Zhao, 2005. Plant and bacterial viruses in the Greenland ice sheet. In: Castello, J.D. and S.O. Rogers (Eds.). *Life in Ancient Ice*, pp. 196–207. Princeton University Press.
- Chapin III, F.S., A.D. McGuire, J. Randerson, R. Pielke, D. Baldocchi, S.E. Hobbie, N. Roulet, W. Eugster, E. Kasischke, E.B. Rastetter, S.A. Zimov and S.W. Running, 2000. Arctic and boreal ecosystems of western North America as components of the climate system. *Global Change Biology*, 6:211–223.
- Chapin III, F.S., M. Sturm, M.C. Serreze, J.P. McFadden, J.R. Key, A.H. Lloyd, A.D. McGuire, T.S. Rupp, A.H. Lynch, J.P. Schimel, J. Beringer, W.L. Chapman, H.E. Epstein, E.S. Euskirchen, L.D. Hinzman, G. Jia, C.L. Ping, K.D. Tape, C.D.C. Thompson, D.A. Walker and J.M. Welker, 2005. Role of land-surface changes in Arctic summer warming. *Science*, 310:657–660.
- Christensen, T.R., S. Jonasson, A. Michelsen, T.V. Callaghan and M. Havstrom, 1998. Environmental controls on soil respiration in the Eurasian and Greenlandic Arctic. *Journal of Geophysical Research-Atmospheres*, 103:29015–29021.
- Christensen, T.R., T.R. Johansson, H.J. Åkerman, M. Mastepanov, N. Malmer, T. Friborg, P. Crill and B.H. Svensson, 2004. Thawing subarctic permafrost: Effects on vegetation and methane emissions. *Geophysical Research Letters*, 31:L04501.
- Christensen, T.R., T. Johansson, M. Olsrud, L. Ström, A. Lindroth, M. Mastepanov, N. Malmer, T. Friborg, P. Crill and T.V. Callaghan, 2007. A catchment-scale carbon and greenhouse gas budget of a subarctic landscape. *Philosophical Transactions of the Royal Society A-Mathematical Physical and Engineering Sciences*, 365:1643–1656.
- Christiansen, H.H., 2005. Thermal regime of ice-wedge cracking in adventdalen, Svalbard. *Permafrost and Periglacial Processes*, 16:87–98.
- Christiansen, H.H. and O. Humlum, 2008. Interannual variations in active layer thickness in Svalbard. Paper presented at Ninth International Conference on Permafrost, pp. 257–262. Institute of Northern Engineering, Fairbanks, Alaska.
- Christiansen, H.H., C. Sigsgaard, O. Humlum, M. Rasch and B.U. Hansen, 2008. Permafrost and periglacial geomorphology at Zackenberg. In: Meltotte, H., T.R. Christensen, B. Elberling, M.C. Forchhammer and M. Rasch (Eds.). *High-Arctic Ecosystem Dynamics in a Changing Climate. Ten years of monitoring and research at Zackenberg Research Station, Northeast Greenland*. *Advances in Ecological Research*, 40:151–174.
- Christiansen, H.H., B. Etzelmüller, K. Isaksen, H. Juliussen, H. Farbrøt, O. Humlum, M. Johansson, T. Ingeman-Nielsen, L. Kristensen, J. Hjort, P. Holmlund, A.B.K. Sannel, C. Sigsgaard, H.J. Åkerman, N. Foged, L.H. Blikra, M.A. Pernosky and R.S. Ødegard, 2010. The thermal state of permafrost in the Nordic area during the International Polar Year 2007–2009. *Permafrost and Periglacial Processes*, 21:156–181.
- Clarke, J., C. Fenton, A. Gens, R. Jardine, C. Martin, D. Nethercot, S. Nishimura, S. Olivella, C. Reifen, P. Rutter, F. Strasser and R. Toumi, 2008. A multi-disciplinary approach to assess the impact of global climate change on infrastructure in cold regions. Paper presented at Ninth International Conference on Permafrost, pp. 279–284. Institute of Northern Engineering, Fairbanks, Alaska.
- Corell, R.W., J.H. Susan and M. Jerry, 2008. Emerging challenges. Methane from the Arctic: global warming wildcard. In: Harrison, P. (Ed.). *UNEP Year Book 2008*, pp. 37–48.
- Corradi, C., O. Kolle, K. Walter, S.A. Zimov and E.D. Schulze, 2005. Carbon dioxide and methane exchange of a north-east Siberian tussock tundra. *Global Change Biology*, 11:1910–1925.
- Coutard, J.P. and B. Francou, 1989. Rock temperature-measurements in two Alpine environments - implications for frost shattering. *Arctic and Alpine Research*, 21:399–416.
- Cramer, B. and D. Franke, 2005. Indications for an active petroleum system in the Laptev Sea, NE Siberia. *Journal of Petroleum Geology*, 28:369–383.
- D'Arrigo, R.D., R.K. Kaufmann, N. Davi, G.C. Jacoby, C. Laskowski, R.B. Myneni and P. Cherubini, 2004. Thresholds for warming-induced growth decline at elevational tree line in the Yukon Territory, Canada. *Global Biogeochemical Cycles*, 18:GB3021.
- Damm, E., U. Schauer, B. Rudels and C. Haas, 2007. Excess of bottom-released methane in an Arctic shelf sea polynya in winter. *Continental Shelf Research*, 27:1692–1701.
- Delisle, G., 2000. Temporal variability of subsea permafrost and gas hydrate occurrences as function of climate change in the Laptev Sea, Siberia. *Polarforschung*, 68:221–225.
- Delisle, G., 2007. Near-surface permafrost degradation: How severe during the 21st century? *Geophysical Research Letters*, 34:L09503.
- Dorrepaal, E., R. Aerts, J.H.C. Cornelissen, T.V. Callaghan and R.S.P. van Logtestijn, 2004. Summer warming and increased winter snow cover affect *Sphagnum fuscum* growth, structure and production in a sub-Arctic bog. *Global Change Biology*, 10:93–104.
- Dorrepaal, E., S. Toet, R.S.P. van Logtestijn, E. Swart, M.J. van de Weg, T.V. Callaghan and R. Aerts, 2009. Carbon respiration from subsurface peat accelerated by climate warming in the subarctic. *Nature*, 460:616–619.

- Dramis, F., M. Govi, M. Guglielmin and G. Mortara, 1995. Mountain permafrost and slope instability in the Italian Alps - The Val Pola landslide. *Permafrost and Periglacial Processes*, 6:73–81.
- Duchesne, C., J.F. Wright and M. Ednie, 2008. High-resolution numerical modeling of climate change impacts to permafrost in the vicinities of Inuvik, Norman Wells, and Fort Simpson, NT, Canada. Paper presented at Ninth International Conference on Permafrost, pp. 385–391. Institute of Northern Engineering, Fairbanks, Alaska.
- Duguay, C.R., T. Zhang, D.W. Leverington and V.E. Romanovsky, 2005. Satellite remote sensing of permafrost and seasonally frozen ground. In: Duguay, C.R. and A. Pietroniro (Eds.). *Remote Sensing in Northern Hydrology*, pp. 91–118, American Geophysical Union.
- Duhaime, G. and A. Caron, 2006. The economy of the circumpolar Arctic. In: Glomsrød, S. and I. Aslaksen (Eds.). *The Economy of the North*, pp. 17–26, Statistics Norway.
- Dunn, A.L., C.C. Barford, S.C. Wofsy, M.L. Goulden and B.C. Daube, 2007. A long-term record of carbon exchange in a boreal black spruce forest: means, responses to interannual variability, and decadal trends. *Global Change Biology*, 13:577–590.
- Dyke, L.D., J.M. Aylsworth, M.M. Burgess, F.M. Nixon and F. Wright, 1997. Permafrost in the Mackenzie Basin, its influences on land-altering processes, and its relationship to climate change. In: Cohen, S.J. (Ed.). *Mackenzie Basin Impact Study, Final Report*, pp. 112–117, Environment Canada.
- Elberling, B., H.H. Christiansen and B.U. Hansen, 2010. High nitrous oxide production from thawing permafrost. *Nature Geoscience*, 3:332–335.
- Erokhina, L.G., A.V. Shatilovich, O.P. Kaminskaya and D.A. Gilichinskii, 2004. [Spectral properties of ancient green algae from buried ice in the high-latitude polar regions of Antarctica]. *Mikrobiologiya*, 73:571–573.
- Esch, D.C. and T.E. Osterkamp, 1990. Cold regions engineering: Climatic warming concerns for Alaska. *Journal of Cold Regions Engineering*, 4:6–14.
- Etzelmüller, B., H. Farbrøt, A. Gudmundsson, O. Humlum, O.E. Tveit and H. Björnsson, 2007. The regional distribution of mountain permafrost in Iceland. *Permafrost and Periglacial Processes*, 18:185–199.
- Etzelmüller, B., T.V. Schuler, H. Farbrøt and A. Gudmundsson, 2008. Permafrost in Iceland: Thermal state and climate change impact. Paper presented at Ninth International Conference on Permafrost, pp. 421–426. Institute of Northern Engineering, Fairbanks, Alaska.
- Etzelmüller, B., T.V. Schuler, K. Isaksen, H.H. Christiansen, H. Farbrøt and R. Benestad, 2011. Modeling the temperature evolution of Svalbard permafrost during the 20th and 21st century. *The Cryosphere*, 5:67–79.
- Euskirchen, E.S., A.D. McGuire, D.W. Kicklighter, Q. Zhuang, J.S. Clein, R.J. Dargaville, D.G. Dye, J.S. Kimball, K.C. McDonald, J.M. Melillo, V.E. Romanovsky and N.V. Smith, 2006. Importance of recent shifts in soil thermal dynamics on growing season length, productivity, and carbon sequestration in terrestrial high-latitude ecosystems. *Global Change Biology*, 12:731–750.
- Euskirchen, E.S., A.D. McGuire, F.S. Chapin, III, S. Yi and C.C. Thompson, 2009. Changes in vegetation in northern Alaska under scenarios of climate change, 2003–2100: implications for climate feedbacks. *Ecological Applications*, 19:1022–1043.
- Faizutdinova, R.S.N., V. Duda, L. Petrovskaya and D. Gilichinsky, 2005. Yeasts isolated from ancient permafrost. In: Castello, J.D. and S.O. Rogers (Eds.). *Life in Ancient Ice*, pp. 118–126, Princeton University Press.
- Farbrøt, H., B. Etzelmüller, T.V. Schuler, A. Gudmundsson, T. Eiken, O. Humlum and H. Björnsson, 2007. Thermal characteristics and impact of climate change on mountain permafrost in Iceland. *Journal of Geophysical Research-Earth Surface*, 112:F03S90.
- Fortier, D. and M. Allard, 2005. Frost-cracking conditions, Bylot Island, Eastern Canadian Arctic Archipelago. *Permafrost and Periglacial Processes*, 16:145–161.
- Fortier, D., M. Allard and Y. Shur, 2007. Observation of rapid drainage system development by thermal erosion of ice wedges on Bylot island, Canadian Arctic Archipelago. *Permafrost and Periglacial Processes*, 18:229–243.
- French, H.M., 2007. *The Periglacial Environment*. 478 pp. John Wiley and Sons.
- Frey, K.E. and L.C. Smith, 2005. Amplified carbon release from vast West Siberian peatlands by 2100. *Geophysical Research Letters*, 32:L09401.
- Froese, D.G., J.A. Westgate, A.V. Reyes, R.J. Enkin and S.J. Preece, 2008. Ancient permafrost and a future, warmer arctic. *Science*, 321:1648–1648.
- Fronzek, S., M. Luoto and T.R. Carter, 2006. Potential effect of climate change on the distribution of palsa mires in subarctic Fennoscandia. *Climate Research*, 32:1–12.
- Fronzek, S., T.R. Carter, J. Räisänen, L. Ruokolainen and M. Luoto, 2010. Applying probabilistic projections of climate change with impact models: a case study for sub-arctic palsa mires in Fennoscandia. *Climatic Change*, 99:515–534.
- Furgal, C. and T.D. Prowse, 2008. Northern Canada. In: Lemmen, D.S., F.J. Warren, J. Lacroix and E. Bush (Eds.). *From Impacts to Adaptation: Canada in a Changing Climate*, pp. 58–118.
- Fyodorov-Davydov, D.G., A.L. Kholodov, V.E. Ostroumov, G.N. Kraev, V.A. Sorokovikov, S.P. Davudov and A.A. Merekalova, 2008. Seasonal thaw of soils in the north Yakutian ecosystems. Paper presented at Ninth International Conference on Permafrost, pp. 481–486. Institute of Northern Engineering, Fairbanks, Alaska.
- Gavrilov, A.V., 2008. *Cryolithosphere of the East Siberian Arctic Shelf (current state and evolution during the late Pleistocene and Holocene)*. Doctor of Science thesis. Moscow State University.
- Gilichinsky, D., 2002. Permafrost as a microbial habitat. In: Bitton, G. (Ed.). *Encyclopedia of Environmental Microbiology*, pp. 932–956. Wiley.
- Gilichinsky, D.A., V.S. Soina and M.A. Petrova, 1993. Cryoprotective properties of water in the Earth cryolithosphere and its role in exobiology. *Origins of Life and Evolution of the Biosphere*, 23:65–75.
- Gilichinsky, D., A. Shatilovich, E. Spirina, R. Faizutdinova, S. Gubin, E. Rivkina, E. Vorobyova and V. Soina, 2001. How long the life might be preserved? The terrestrial model for astrobiology. Paper presented at The Bridge between the Big Bang and Biology, pp. 25–37, Consiglio Nazionale delle Ricerche of Italy, Rome.
- Gilichinsky, D.A., G.S. Wilson, E.I. Friedmann, C.P. McKay, R.S. Sletten, E.M. Rivkina, T.A. Vishnivetskaya, L.G. Erokhina, N.E. Ivanushkina, G.A. Kochkina, V.A. Shcherbakova, V.S. Soina, E.V. Spirina, E.A. Vorobyova, D.G. Fyodorov-Davydov, B. Hallet, S.M. Ozerskaya, V.A. Sorokovikov, K.S. Laurinavichyus, A. Shatilovich, J.P. Chanton, V.E. Ostroumov and J.M. Tiedje, 2007. Microbial populations in Antarctic permafrost: Biodiversity, state, age, and implication for astrobiology. *Astrobiology*, 7:275–311.
- Gilichinsky, D., T. Vishnivetskaya, M. Petrova, E. Spirina, V. Mamykin and E. Rivkina, 2008. Bacteria in permafrost. In: Margesin, R., F. Schinner, J.-C. Marx and C. Gerday (Eds.). *Psychrophiles: From Biodiversity to Biotechnology*, pp. 83–102. Springer-Verlag.
- Ginsburg, G.D. and V.A. Soloviev, 1994. *Submarine Hydrates*. 199 pp. VNIIOkeanogeologia, Sankt Petersburg.
- Glomsrød, S., 2006. The economy of the North: An introduction. In: Glomsrød, S. and I. Aslaksen (Eds.). *The Economy of the North*, pp. 9–16. Statistics Norway.
- Goetz, S.J., M.C. Mack, K.R. Gurney, J.T. Randerson and R.A. Houghton, 2007. Ecosystem responses to recent climate change and fire disturbance at northern high latitudes: observations and model results contrasting northern Eurasia and North America. *Environmental Research Letters*, 2:045031.
- Goodrich, L.E., 1982. The influence of snow cover on the ground thermal regime. *Canadian Geotechnical Journal*, 19:421–432.
- Gooseff, M.N., A. Balser, W.B. Bowden and J.B. Jones, 2009. Effects of hillslope thermokarst in northern Alaska. *EOS, Transactions American Geophysical Union*, 90:29–30.
- Goossens, R., A.B.J. De Wulf, W. Gheyle, B. Van Bever, M. Vanommeslaeghe, D. Dossche and D. Devriendt, 2007. The frozen tombs of the Altai Mountains inventarisation and conservation. Paper presented at Proceedings of the XXI International CIPA Symposium. Vol. XXXVI-5/ C53:346. 349 pp., The International Archives of the Photogrammetry, Remote Sensing and Spatial Information Sciences.
- Gorham, E., 1991. Northern peatlands: role in the carbon cycle and probable responses to climatic warming. *Ecological Applications*, 1:182–195.
- Göttel, H., J. Alexander, E. Keup-Thiel, D. Rechid, S. Hagemann, T. Blome, A. Wolf and D. Jacob, 2008. Influence of changed vegetations fields on regional climate simulations in the Barents Sea Region. *Climatic Change*, 87:35–50.
- Goulden, M.L., S.C. Wofsy, J.W. Harden, S.E. Trumbore, P.M. Crill, S.T. Gower, T. Fries, B.C. Daube, S.M. Fan, D.J. Sutton, A. Bazzaz and J.W. Munger, 1998. Sensitivity of boreal forest carbon balance to soil thaw. *Science*, 279:214–217.
- Grøndahl, L., T. Friborg and H. Soegaard, 2006. Temperature and snow-melt controls on interannual variability in carbon exchange in high

- Arctic. *Theoretical and Applied Climatology*, 88:111–125.
- Gruber, S. and W. Haeberli, 2007. Permafrost in steep bedrock slopes and its temperature-related destabilization following climate change. *Journal of Geophysical Research-Earth Surface*, 112:F02S18.
- Gruber, S., L. King, T. Kohl, T. Herz, W. Haeberli and M. Hoelzle, 2004. Interpretation of geothermal profiles perturbed by topography: The Alpine Permafrost boreholes at Stockhorn Plateau, Switzerland. *Permafrost and Periglacial Processes*, 15:349–357.
- Haeberli, W., 1973. Die Basistemperatur der winterlichen Schneedecke als möglicher Indikator für die Verbreitung von Permafrost in den Alpen. *Zeitschrift für Gletscherkunde und Glazialgeologie*, 1-2:221–227.
- Haeberli, W., B. Hallet, L. Arenson, R. Elconin, O. Humlum, A. Kääb, V. Kaufmann, B. Ladanyi, N. Matsuoka, S. Springman and D. Vonder Mühll, 2006. Permafrost creep and rock glacier dynamics. *Permafrost and Periglacial Processes*, 17:189–214.
- Hallet, B., 2006. Geology - Why do freezing rocks break? *Science*, 314:1092–1093.
- Hallet, B., J.S. Walder and C.W. Stubbs, 1991. Weathering by segregation ice growth in microcracks at sustained sub-zero temperatures: verification from an experimental study using acoustic emissions. *Permafrost and Periglacial Processes*, 2:283–300.
- Hansen, A.J., D.L. Mitchell, C. Wiuf, L. Panikert, T.B. Brand, J. Binladen, D.A. Gilichinsky, R. Ronn and E. Willerslev, 2006. Crosslinks rather than strand breaks determine access to ancient DNA sequences from frozen sediments. *Genetics*, 173:1175–1179.
- Harris, C. and K. Isaksen, 2008. Recent warming of European permafrost: evidence from borehole monitoring. Paper presented at Ninth International Conference on Permafrost, pp. 655–661. Institute of Northern Engineering, Fairbanks, Alaska.
- Harris, C., M. Luetschg, M.C.R. Davies, F. Smith, H.H. Christiansen and K. Isaksen, 2007. Field instrumentation for real-time monitoring of periglacial solifluction. *Permafrost and Periglacial Processes*, 18:105–114.
- Harris, C., J.S. Smith, M.C.R. Davies and B. Rea, 2008. An investigation of periglacial slope stability in relation to soil properties based on physical modelling in the geotechnical centrifuge. *Geomorphology*, 93:437–459.
- Harris, C., L.U. Arenson, H.H. Christiansen, B. Etzemüller, R. Frauenfelder, S. Gruber, W. Haeberli, C. Hauck, M. Hölzle, O. Humlum, K. Isaksen, A. Kääb, M.A. Kern-Lütschg, M. Lehning, N. Matsuoka, J.B. Murton, J. Nötzli, M. Phillips, N. Ross, M. Seppälä, S.M. Springman and D.V. Mühll, 2009. Permafrost and climate in Europe: Monitoring and modelling thermal, geomorphological and geotechnical responses. *Earth-Science Reviews*, 92:117–171.
- Harry, D.G. and J.S. Gozdzik, 1988. Ice wedges: growth, thaw transformation and paleoenvironmental significance. *Journal of Quaternary Science*, 3:39–55.
- Hayley, D.W., 2004. Climate change - an adaptation challenge for northern engineers. The PEGG, Newspaper of the APEGGA. January, 3 pp. Association of Professional Engineers, Geologists and Geophysicists of Alberta, Canada.
- Hayley, D.W. and B. Horne, 2008. Rationalizing climate change for design of structures on permafrost: A Canadian perspective. Paper presented at Ninth International Conference on Permafrost, pp. 681–686. Institute of Northern Engineering, Fairbanks, Alaska.
- Heikinen, J.E.P., T. Virtanen, J.T. Huttunen, V. Elsakov and P.J. Martikainen, 2004. Carbon balance in East European tundra. *Global Biogeochemical Cycles*, 18:GB1023.
- Himenkov, A.N. and A.V. Brushkov, 2007. Introduction onto the Structural Geocryology. 279 pp. Science, Moscow.
- Hinkel, K.M. and J.K. Hurd, Jr., 2006. Permafrost destabilization and thermokarst following snow fence installation, Barrow, Alaska, USA. *Arctic, Antarctic and Alpine Research*, 38:530–539.
- Hinz, K., G. Delisle and M. Block, 1998. Seismic evidence for the depth extent of permafrost in shelf sediments of the Laptev Sea, Russian Arctic. Paper presented at The Seventh International Conference on Permafrost, pp. 453–457. Collection Nordicana, Yellowknife, Canada.
- Hinzman, L.D., N.D. Bettez, W.R. Bolton, F.S. Chapin, III, M.B. Dyurgerov, C.L. Fastie, B. Griffith, R.D. Hollister, A. Hope, H.P. Huntington, A.M. Jensen, G.J. Jia, T. Jorgenson, D.L. Kane, D.R. Klein, G. Kofinas, A.H. Lynch, A.H. Lloyd, A.D. McGuire, F.E. Nelson, W.C. Oechel, T.E. Osterkamp, C.H. Racine, V.E. Romanovsky, R.S. Stone, A.D. Stow, M. Sturm, C.E. Tweedie, G.L. Vourlitis, M.D. Walker, D.A. Walker, P.J. Webber, J.M. Welker, K. Winker and K. Yoshikawa, 2005. Evidence and implications of recent climate change in northern Alaska and other arctic regions. *Climatic Change*, 72:251–298.
- Holst, T., A. Arneth, S. Hayward, A. Ekberg, M. Mastepanov, M. Jackowicz-Korczynski, T. Friborg, P.M. Crill and K. Bäckstrand, 2010. BVOC ecosystem flux measurements at a high latitude wetland site. *Atmospheric Chemistry and Physics*, 10:1617–1634.
- Holubec, L., J. Jardine and B. Watt, 2008. Flat loop evaporator thermosyphon foundations: design, construction, and performance in the Canadian permafrost regions. Paper presented at Ninth International Conference on Permafrost, pp. 735–740. Institute of Northern Engineering, Fairbanks, Alaska.
- Hovland, M., A.G. Judd and R.A. Burke, 1993. The global flux of methane from shallow submarine sediments. *Chemosphere*, 26:559–578.
- Hubberten, H.-W. and N.N. Romanovskii, 2001. Terrestrial and offshore permafrost evolution of the Laptev Sea region during the last Pleistocene-Holocene glacial-eustatic cycle. Paper presented at Permafrost response to economic development, environmental security and natural resources. Proceedings of NATO-ARW, pp. 43–60. Kluwer.
- Humborg, C., C.M. Mörtz, M. Sundbom, H. Borg, T. Blenckner, R. Giesler and V. Ittekkot, 2010. CO₂ supersaturation along the aquatic conduit in Swedish watersheds as constrained by terrestrial respiration, aquatic respiration and weathering. *Global Change Biology*, 16:1966–1978.
- Humlum, O., 1997. Active layer thermal regime at three rock glaciers in Greenland. *Permafrost and Periglacial Processes*, 8:383–408.
- Humlum, O., 1998. Rock glaciers on the Faeroe Islands, the north Atlantic. *Journal of Quaternary Science*, 13:293–307.
- Humlum, O., 1999. Late-Holocene climate in central West Greenland: meteorological data and rock-glacier isotope evidence. *Holocene*, 9:581–594.
- Humlum, O., 2000. The geomorphic significance of rock glaciers: estimates of rock glacier debris volumes and headwall recession rates in West Greenland. *Geomorphology*, 35:41–67.
- Humlum, O., H.H. Christiansen and H. Juliussen, 2007. Avalanche-derived rock glaciers in Svalbard. *Permafrost and Periglacial Processes*, 18:75–88.
- Imbrie, J. and K.P. Imbrie, 1979. *Ice Ages: Solving the Mystery*. 224 pp. Harvard University Press.
- Instanes, A., 2003. Climate change and possible impact on Arctic infrastructure. Paper presented at Eighth International Conference on Permafrost (ICOP), pp. 461–466. Balkema Publishers.
- Instanes, A. and O.A. Anisimov, 2008. Climate change and Arctic infrastructure. Paper presented at Ninth International Conference on Permafrost, pp. 779–784. Institute of Northern Engineering, Fairbanks, Alaska.
- Instanes, B. and A. Instanes, 2008. Foundation design using a heat pump cooling system. Paper presented at Ninth International Conference on Permafrost, pp. 785–788. Institute of Northern Engineering, Fairbanks, Alaska.
- Instanes, A. and D. Mjurreke, 2005. Svalbard airport runway. Performance during a climate-warming scenario. Paper presented at 7th International Conference on Bearing Capacity of Roads and Airfields (BCRA), pp. 461–466, Trondheim, Norway, June 27–29.
- Instanes, A., O. Anisimov, L. Brigham, D. Goering, B. Ladanyi, J.O. Larsen and L.N. Khrustalev, 2005. Infrastructure: buildings, support systems, and industrial facilities. In: *Arctic Climate Impact Assessment*, pp. 907–944, Cambridge University Press.
- IPA DIWG (compilers), 1998. Circumpolar Active-layer Permafrost System (CAPS). International Permafrost Association Data and Information Working Group. National Snow and Ice Data Centre / World Data Center for Glaciology. Digital media: <http://nsidc.org/data/g01175.html>. Accessed: October 13, 2010.
- IPA SCDIC (compilers), 2003. Circumpolar Active-layer Permafrost System, version 2. Parsons, M. and T. Zhang (Eds.). International Permafrost Association Standing Committee on Data Information of Data Information and Communication (IPA SCDIC). National Snow and Ice Data Center / World Data Center for Glaciology. Digital media: <http://nsidc.org/data/g01175.html>. Accessed: 1 May 2011.
- Isaksen, K., R.E. Benestad, C. Harris and J.L. Sollid, 2007a. Recent extreme near-surface permafrost temperatures on Svalbard in relation to future climate scenarios. *Geophysical Research Letters*, 34:L17502.
- Isaksen, K., J.L. Sollid, P. Holmlund and C. Harris, 2007b. Recent warming of mountain permafrost in Svalbard and Scandinavia. *Journal of Geophysical Research-Earth Surface*, 112:F02S04.

- Janke, J.R., 2005. Long-term flow measurements (1961–2002) of the Arapaho, Taylor, and Fair rock glaciers, Front Range, Colorado. *Physical Geography*, 26:313–336.
- Jobbagy, E.G. and R.B. Jackson, 2000. The vertical distribution of soil organic carbon and its relation to climate and vegetation. *Ecological Applications*, 10:423–436.
- Johansson, T., N. Malmer, P.M. Crill, T. Friborg, J.H. Akerman, M. Mastepanov and T.R. Christensen, 2006. Decadal vegetation changes in a northern peatland, greenhouse gas fluxes and net radiative forcing. *Global Change Biology*, 12:2352–2369.
- Johansson, M., H.J. Akerman, C. Jonasson, T.R. Christensen and T.V. Callaghan, 2008. Increasing permafrost temperatures in subarctic Sweden. Paper presented at Ninth International Conference on Permafrost, pp. 851–856. Institute of Northern Engineering, Fairbanks, Alaska.
- Johnson, E.R. and L.A. Hegdal, 2008. Permafrost-related performance of the Trans Alaska Oil Pipeline. Paper presented at Ninth International Conference on Permafrost, pp. 857–864. Institute of Northern Engineering, Fairbanks, Alaska.
- Johnson, S.S., M.B. Hebsgaard, T.R. Christensen, M. Mastepanov, R. Nielsen, K. Munch, T. Brand, M. Thomas, P. Gilbert, M.T. Zuber, M. Bunce, R. Ronn, D. Gilichinsky, D. Froese and E. Willerslev, 2007. Ancient bacteria show evidence of DNA repair. *Proceedings of the National Academy of Sciences of the United States of America*, 104:14401–14405.
- Jonasson, S., 1986. Influence of frost heaving on soil chemistry and the distribution of plant growth forms. *Geografiska Annaler*, 68A:185–195.
- Jonasson, S. and T.V. Callaghan, 1992. Root mechanical properties related to disturbed and stressed habitats in the Arctic. *New Phytologist*, 122:179–186.
- Jones, B.M., C.A. Kolden, R. Jandt, J.T. Abatzoglou, F. Urban and C.D. Arp, 2009. Fire behavior, weather, and burn severity of the 2007 Anaktuvuk River tundra fire, North Slope, Alaska. *Arctic, Antarctic and Alpine Research*, 41:309–316.
- Jorgenson, M.T. and T.E. Osterkamp, 2005. Response of boreal ecosystems to varying modes of permafrost degradation. *Canadian Journal of Forest Research-Revue Canadienne de Recherche Forestiere*, 35:2100–2111.
- Jorgenson, M.T., C.H. Racine, J.C. Walters and T.E. Osterkamp, 2001. Permafrost degradation and ecological changes associated with a warming climate in central Alaska. *Climatic Change*, 48:551–579.
- Jorgenson, M.T., Y.L. Shur and E.R. Pullman, 2006. Abrupt increase in permafrost degradation in Arctic Alaska. *Geophysical Research Letters*, 33:L02503.
- Jorgenson, M.T., Y. Shur and T.E. Osterkamp, 2008. Thermokarst in Alaska. Paper presented at Ninth International Conference on Permafrost, pp. 869–876. Institute of Northern Engineering, Fairbanks, Alaska.
- Jorgenson, M.T., V. Romanovsky, J. Harden, Y. Shur, J. O'Donnell, E.A.G. Schuur, M. Kanevskiy and S. Marchenko, 2010. Resilience and vulnerability of permafrost to climate change. *Canadian Journal of Forest Research-Revue Canadienne de Recherche Forestiere*, 40:1219–1236.
- Juday, G.P., V. Barber, P. Duffy, H. Linderholm, S. Rupp, S. Sparrow, E. Vaganov, J. Yarie, E. Berg, R. D'Arrigo, O. Eggertsson, V.V. Fyryaev, E.H. Hogg, S. Huttunen, G. Jacoby, V.Y. Kaplunov, S. Kellomaki, A.V. Kirilyanov, C.E. Lewis, S. Linder, M.M. Naurzbaev, F.I. Pleshikov, U.T. Runesson, Y.V. Savva, O.V. Sidorova, V.D. Stakanov, N.M. Tchekakova, E.N. Valendik, E.F. Vedrova and M. Wilmsking, 2005. Forests, land management, and agriculture. *Arctic Climate Impact Assessment*, pp. 781–862. Cambridge University Press.
- Judd, A.G., 2004. Natural seabed gas seeps as sources of atmospheric methane. *Environmental Geology*, 46:988–996.
- Juliussen, H., Christiansen, H.H., Strand, G.S., Iversen, S., Midtømme, K. and Ronning, J.S. (2010). NORPERM, the Norwegian Permafrost Database – a TSP NORWAY IPY legacy. *Earth System Science Data*, 2, 235–246. doi:10.5194/essd-2-235-2010.
- Kääb, A., R. Frauenfelder and I. Roer, 2007. On the response of rockglacier creep to surface temperature increase. *Global and Planetary Change*, 56:172–187.
- Kane, D.L. and K.M. Hinkel (Eds.), 2008. Ninth International Conference on Permafrost. Institute of Northern Engineering, University of Alaska Fairbanks. Proceedings available at www.nicop.org.
- Kane, D.L., R.E. Gieck, D.C. Kitover, L.D. Hinzman, J.P. McNamara and D.Q. Yang, 2004. Hydrological cycle on the North Slope of Alaska. In: Kane, D.L. and D. Yang (Eds.). *Northern Research Basins Water Balance*, pp. 224–236, IAHS Press.
- Kane, D.L., L.D. Hinzman, R.E. Gieck, J.P. McNamara, E.K. Youcha and J.A. Oatley, 2008. Contrasting extreme runoff events in areas of continuous permafrost, Arctic Alaska. *Hydrology Research*, 39:287–298.
- Kanigan, J.C.N., C.R. Burn and S.V. Kokelj, 2008. Permafrost response to climate warming south of treeline, Mackenzie Delta, Northwest Territories, Canada. Paper presented at Ninth International Conference on Permafrost, pp. 901–906. Institute of Northern Engineering, Fairbanks, Alaska.
- Kaplan, J.O. and M. New, 2006. Arctic climate change with a 2 °C global warming: Timing, climate patterns and vegetation change. *Climatic Change*, 79:213–241.
- Kettles, I.M., C. Tarnocai and S.D. Bauke, 1997. Predicted permafrost distribution in Canada under a climate warming scenario. *Current Research, Geological Survey of Canada*, 1997-E:109–115.
- Kharuk, V.I., M.L. Dvinskaya, K.J. Ranson and S.T. Im, 2005. Expansion of evergreen conifers to the larch-dominated zone and climatic trends. *Russian Journal of Ecology*, 36:164–170.
- Kim, B., G. Grikurov and V. Soloviev, 1999. High resolution seismic studies in the Laptev Sea Shelf: First results and future needs. In: Kassens, H., H.A. Bauch, I.A. Dmitrenko, H. Eicken, H.-W. Hubberten, M. Melles, J. Thiede and L.A. Timokhov (Eds.). *Land-Ocean System in the Siberian Arctic: Dynamics and History*, pp. 683–694.
- Kinnard, C. and A.G. Lewkowicz, 2005. Movement, moisture and thermal conditions at a turf-banked solifluction lobe, Kluane Range, Yukon territory, Canada. *Permafrost and Periglacial Processes*, 16:261–275.
- Kleiber, H.P. and F. Niessen, 2000. Variations of continental discharge pattern in space and time: implications from the Laptev Sea continental margin, Arctic Siberia. *International Journal of Earth Sciences*, 89:605–616.
- Koch, K., C. Knoblauch and D. Wagner, 2009. Methanogenic community composition and anaerobic carbon turnover in submarine permafrost sediments of the Siberian Laptev Sea. *Environmental Microbiology*, 11:657–668.
- Kokelj, S.V. and C.R. Burn, 2005. Geochemistry of the active layer and near-surface permafrost, Mackenzie delta region, Northwest Territories, Canada. *Canadian Journal of Earth Sciences*, 42:37–48.
- Kokelj, S.V., R.E. Jenkins, D. Milburn, C.R. Burn and N. Snow, 2005. The influence of thermokarst disturbance on the water quality of small upland lakes, Mackenzie Delta Region, Northwest Territories, Canada. *Permafrost and Periglacial Processes*, 16:343–353.
- Kokelj, S.V., M.F.J. Pisarcic and C.R. Burn, 2007. Cessation of ice-wedge development during the 20th century in spruce forests of eastern Mackenzie Delta, Northwest Territories, Canada. *Canadian Journal of Earth Sciences*, 44:1503–1515.
- Kokelj, S.V., B. Zajdlik, M.S. Thompson and R.E.L. Jenkins, 2008. Thawing permafrost and temporal variation in the electrical conductivity of water in small tundra lakes, Mackenzie Delta Region, NWT. Paper presented at Ninth International Conference on Permafrost, pp. 965–970. Institute of Northern Engineering, Fairbanks, Alaska.
- Kokelj, S.V., T.C. Lantz, J. Kanigan, S.L. Smith and R. Coutts, 2009. Origin and polycyclic behaviour of tundra thaw slumps, Mackenzie Delta region, Northwest Territories, Canada. *Permafrost and Periglacial Processes*, 20:173–184.
- Kokfelt, U., N. Reuss, E. Struyf, M. Sonesson, M. Rundgren, G. Skog, P. Rosen and D. Hammarlund, 2010. Wetland development, permafrost history and nutrient cycling inferred from late Holocene peat and lake sediment records in subarctic Sweden. *Journal of Paleolimnology*, 44:327–342.
- Kondratiev, V.G., 2008. Geocryological Problems Associated with Railroads and Highways. Paper presented at Ninth International Conference on Permafrost, pp. 977–982. Institute of Northern Engineering, Fairbanks, Alaska.
- Krainer, K. and W. Mostler, 2006. Flow velocities of active rock glaciers in the Austrian Alps. *Geografiska Annaler Series A-Physical Geography*, 88:267–280.
- Kronik, Y.A., 2001. Hazards and safety of infrastructures in permafrost region. Paper presented at Second conference of Russian permafrost scientists, pp. 138–147. Moscow State University, Moscow, June 6–8.
- Kuhry, P. and J. Turunen, 2006. Postglacial development of boreal and subarctic peatlands. In: Wieder, R.K. and D.H. Vitt (Eds.). *Boreal Peatland Ecosystems* pp. 25–46, Springer-Verlag.

- Kulakov, M., V. Stanovoy and S. Kirillov, 2003. Oceanography of the East-Siberian Sea. Paper presented at ESSS Workshop 2003, 10 pp., International Arctic Research Centre, Malaga, Spain, October 11–18.
- Kvenvolden, K.A., 1988. Methane hydrates and global climate. *Global Biogeochemical Cycles*, 2:221–229.
- Kvenvolden, K.A., 1991. A review of Arctic gas hydrates as a source of methane in global change. Paper presented at International Conference on the Role of the Polar Regions in Global Change, pp. 696–701.
- Kvenvolden, K.A., 2002. Methane hydrate in the global organic carbon cycle. *Terra Nova*, 14:302–306.
- Kvenvolden, K.A., T.D. Lorenson and M.D. Lilley, 1992. Methane in the Beaufort Sea on the continental shelf of Alaska. *EOS Transactions American Geophysical Union*, 73:309.
- Kvenvolden, K.A., M.D. Lilley, T.D. Lorenson, P.W. Barnes and E. McLaughlin, 1993. The Beaufort Sea continental shelf as a seasonal source of atmospheric methane. *Geophysical Research Letters*, 20:2459–2462.
- Kwon, H.J., W.C. Oechel, R.C. Zulueta and S.J. Hastings, 2006. Effects of climate variability on carbon sequestration among adjacent wet sedge tundra and moist tussock tundra ecosystems. *Journal of Geophysical Research-Biogeosciences*, 111:G03014.
- Lacelle, D., J. Bjornson and B. Lauriol, 2010. Climatic and geomorphic factors affecting contemporary (1950–2004) activity of retrogressive thaw slumps on the Aklavik Plateau, Richardson Mountains, NWT, Canada. *Permafrost and Periglacial Processes*, 21:1–15.
- Lachenbruch, A.H., 1957. Thermal effects of the ocean on permafrost. *Bulletin of the Geological Society of America*, 68:1515–1530.
- Lantuit, H. and W.H. Pollard, 2008. Fifty years of coastal erosion and retrogressive thaw slump activity on Herschel Island, southern Beaufort Sea, Yukon Territory, Canada. *Geomorphology*, 95:84–102.
- Lantuit, H., P.P. Overduin, N. Couture, F. Aré, D. Atkinson, J. Brown, G. Cherkashov, D. Drozdov, D. Forbes, A. Graves-Gaylord, M. Grigoriev, H.-W. Hubberten, J. Jordan, T. Jorgenson, R. Odegard, S. Ogorodov, W.H. Pollard, V. Rachold, S. Sedenko, S. Solomon, F. Steenhuisen, I. Streletskaia and A. Vasiliev, 2011. The Arctic Coastal Dynamics Database: A new classification scheme and statistics on arctic permafrost coastlines. *Estuaries and Coasts*, 16:1–18.
- Lantz, T.C. and S.V. Kokelj, 2008. Increasing rates of retrogressive thaw slump activity in the Mackenzie Delta region, NWT, Canada. *Geophysical Research Letters*, 35:L06502.
- Lantz, T.C., S.V. Kokelj, S.E. Gergel and G.H.R. Henry, 2009. Relative impacts of disturbance and temperature: persistent changes in microenvironment and vegetation in retrogressive thaw slumps. *Global Change Biology*, 15:1664–1675.
- Laprise, R., D. Caya, A. Frigon and D. Paquin, 2003. Current and perturbed climate as simulated by the second-generation Canadian Regional Climate Model (CRCM-II) over northwestern North America. *Climate Dynamics*, 21:405–421.
- Lawrence, D.M., A.G. Slater, V.E. Romanovsky and D.J. Nicolsky, 2008. Sensitivity of a model projection of near-surface permafrost degradation to soil column depth and representation of soil organic matter. *Journal of Geophysical Research-Earth Surface*, 113:F02011.
- Leibman, M.O., 1995. Cryogenic landslides on the Yamal Peninsula, Russia: preliminary observations. *Permafrost and Periglacial Processes*, 6:259–264.
- Leibman, M. and A. Kizyakov, 2006. Massive ground ice and corresponding relief in the Kara sea region. *Geophysical Research Abstracts*, 8:05096.
- Leifer, I., B.P. Luyendyk, J. Boles and J.F. Clark, 2006. Natural marine seepage blowout: Contribution to atmospheric methane. *Global Biogeochemical Cycles*, 20:GB3008.
- Lemke, P., J. Ren, R.B. Alley, I. Allison, J. Carrasco, G. Flato, Y. Fujii, G. Kaser, P. Mote, R.H. Thomas and T. Zhang, 2007. Observations: changes in snow, ice and frozen ground. *Climate Change 2007: The Physical Science Basis. Contribution of Working Group 1 to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change*, pp. 339–383, Cambridge University Press.
- Leonard, E.M., P. Staab and S.G. Weaver, 2005. Kinematics of Spruce Creek rock glacier, Colorado, USA. *Journal of Glaciology*, 51:259–268.
- Lewkowicz, A.G. and P.R. Bonnaventure, 2008. Interchangeability of mountain permafrost probability models, northwest Canada. *Permafrost and Periglacial Processes*, 19:49–62.
- Lewkowicz, A.G. and S.A. Clarke, 1998. Late-summer solifluction and active layer depths, Fosheim Peninsula, Ellesmere Island, Canada. Paper presented at Seventh International Conference on Permafrost, pp. 641–646. Québec City, June 23–27.
- Lewkowicz, A.G. and M. Ednie, 2004. Probability mapping of mountain permafrost using the BTS method, Wolf Creek, Yukon Territory, Canada. *Permafrost and Periglacial Processes*, 15:67–80.
- Lewkowicz, A.G. and C. Harris, 2005. Frequency and magnitude of active-layer detachment failures in discontinuous and continuous permafrost, northern Canada. *Permafrost and Periglacial Processes*, 16:115–130.
- Lindholt, L., 2006. Arctic natural resources in a global perspective. In: Glomsrød, S. and I. Aslaksen (Eds.). *The Economy of the North*, pp. 27–40, Statistics Norway.
- Lisitsyna, O.M. and N.N. Romanovskii, 1998. Dynamics of permafrost in Northern Eurasia during the last 20,000 years. Paper presented at Seventh International Permafrost Conference, pp. 675–681. Yellowknife, Canada, June 23–27.
- Lloyd, C.R., 2001. The measurement and modelling of the carbon dioxide exchange at a high Arctic site in Svalbard. *Global Change Biology*, 7:405–426.
- Lloyd, J., O. Shibistova, D. Zolotoukhine, O. Kolle, A. Arneth, C. Wirth, J.M. Styles, N.M. Tchekbakova and E.D. Schulze, 2002. Seasonal and annual variations in the photosynthetic productivity and carbon balance of a central Siberian pine forest. *Tellus Series B-Chemical and Physical Meteorology*, 54:590–610.
- Lloyd, A.H., K. Yoshikawa, C.L. Fastie, L. Hinzman and M. Fraver, 2003. Effects of permafrost degradation on woody vegetation at arctic treeline on the Seward Peninsula, Alaska. *Permafrost and Periglacial Processes*, 14:93–101.
- Luckman, B.H., 1976. Rockfalls and rockfall inventory data - some observations from Surprise-Valley, Jasper-National-Park, Canada. *Earth Surface Processes and Landforms*, 1:287–298.
- Luoto, M. and M. Seppälä, 2003. Thermokarst ponds as indicators of the former distribution of palsas in Finnish lapland. *Permafrost and Periglacial Processes*, 14:19–27.
- Luoto, M., S. Fronzek and F.S. Zuidhoff, 2004a. Spatial modelling of palsa mires in relation to climate in northern Europe. *Earth Surface Processes and Landforms*, 29:1373–1387.
- Luoto, M., R.K. Heikkinen and T.R. Carter, 2004b. Loss of palsa mires in Europe and biological consequences. *Environmental Conservation*, 31:30–37.
- Lydolph, M.C., J. Jacobsen, P. Arctander, M.T.P. Gilbert, D.A. Gilichinsky, A.J. Hansen, E. Willerslev and L. Lange, 2005. Beringian paleoecology inferred from permafrost-preserved fungal DNA. *Applied and Environmental Microbiology*, 71:1012–1017.
- MacDonald, G.M., D.W. Beilman, K.V. Kremenetski, Y.W. Sheng, L.C. Smith and A.A. Velichko, 2006. Rapid early development of circumarctic peatlands and atmospheric CH₄ and CO₂ variations. *Science*, 314:285–288.
- Macdonald, R.W., L.G. Anderson, J.P. Christensen, L.A. Miller, I.P. Semiletov and R. Stein, 2010. The Arctic Ocean: Budgets and fluxes. In: Liu, K.-K., L. Atkinson, R. Quinones and L. Talaue-McManus (Eds.). *Carbon and Nutrient Fluxes in Continental Margins: A Global Synthesis*, pp. 291–303, Springer Verlag.
- Mackay, J.R., 1972. Offshore permafrost and ground ice, Southern Beaufort Sea. *Canadian Journal of Earth Sciences*, 9:1550–1561.
- Mackay, J.R., 1979. Pingos of the Tuktoyaktuk peninsula area, Northwest Territories. *Géographie Physique et Quaternaire*, 33:3–61.
- Mackay, J.R., 1997. A full-scale field experiment (1978–1995) on the growth of permafrost by means of lake drainage, western Arctic coast: A discussion of the method and some results. *Canadian Journal of Earth Sciences*, 34:17–33.
- Mackay, J.R., 1998. Pingo growth and collapse, Tuktoyaktuk Peninsula Area, Western Arctic Coast, Canada: A long-term field study. *Géographie Physique et Quaternaire*, 52:271–323.
- Mackay, J.R., 2000. Thermally induced movements in ice-wedge polygons, western Arctic coast: A long-term study. *Géographie Physique et Quaternaire*, 54:41–68.
- Mackay, J.R. and C.R. Burn, 2002. The first 20 years (1978–1979 to 1998–1999) of ice-wedge growth at the Illisarvik experimental drained lake site, western Arctic coast, Canada. *Canadian Journal of Earth Sciences*, 39:95–111.
- Makogon, Y.F., S.A. Holditch and T.Y. Makogon, 2007. Natural gas-hydrates - A potential energy source for the 21st Century. *Journal of Petroleum Science and Engineering*, 56:14–31.

- Malkova, G.V., 2008. The last twenty-five years of changes in permafrost temperature in the European Russian Arctic. Paper presented at Ninth International Conference on Permafrost, pp. 1119–1124. Institute of Northern Engineering, Fairbanks, Alaska, 2008.
- Malmer, N., T. Johansson, M. Olsrud and T.R. Christensen, 2005. Vegetation, climatic changes and net carbon sequestration in a North-Scandinavian subarctic mire over 30 years. *Global Change Biology*, 11:1895–1909.
- Marchenko, S., V. Romanovsky and G. Tipenko, 2008. Numerical modeling of spatial permafrost dynamics in Alaska. Paper presented at Ninth International Conference on Permafrost, pp. 1125–1130. Institute of Northern Engineering, Fairbanks, Alaska, 29 June – 3 July.
- Marchenko, S., V.E. Romanovsky, A. Rinke, M. Stendel and P. Kuhry, 2009. Permafrost dynamics modeling in European Russian North using a high spatial resolution RCM. *EOS Transaction American Geophysical Union*, 90:Abstract GC31A-0683.
- Marchenko, S., V. Romanovsky, O. Bulygina and V. Razuvaev, 2010. Observed and projected changes in climate, permafrost, and active layer in Northern Eurasia and their relation to permafrost carbon pool. Paper presented at Third European Conference on Permafrost, Longyearbyen, Svalbard, 13–17 June.
- Marsh, P., M. Russell, S. Pohl, H. Haywood and C. Onclin, 2009. Changes in thaw lake drainage in the Western Canadian Arctic from 1950 to 2000. *Hydrological Processes*, 23:145–158.
- Mastepanov, M., C. Sigsgaard, E.J. Dlugokencky, S. Houweling, L. Strom, M.P. Tamstorf and T.R. Christensen, 2008. Large tundra methane burst during onset of freezing. *Nature*, 456:628–630.
- Matsuoka, M., 2001a. Microgelivation versus macrogelivation: Towards bridging the gap between laboratory and field frost weathering. *Permafrost and Periglacial Processes*, 12:299–313.
- Matsuoka, N., 2001b. Solifluction rates, processes and landforms: a global review. *Earth-Science Reviews*, 55:107–134.
- Matsuoka, N. and J. Murton, 2008. Frost weathering: Recent advances and future directions. *Permafrost and Periglacial Processes*, 19:195–210.
- Matsuoka, N. and H. Sakai, 1999. Rockfall activity from an alpine cliff during thawing periods. *Geomorphology*, 28:309–328.
- Matveyeva, N. and Y. Chernov, 2000. Biodiversity of terrestrial ecosystems. In: Nutall, M. and T.V. Callaghan (Eds.). *The Arctic: Environment, People, Policy*, pp. 233–273. Harwood Academic Publishers.
- Mazhitova, G.G., G. Malkova, O. Chestnykh and D. Zamolodchikov, 2008. Recent decade thaw depth dynamics in the European Russian Arctic based on the Circumpolar Active Layer Monitoring (CALM) data. Paper presented at Ninth International Conference on Permafrost, pp. 1155–1160. Institute of Northern Engineering, Fairbanks, Alaska.
- McBean, G., G. Alekseev, D. Chen, E. Førland, J. Fyfe, P.Y. Groisman, R. King, H. Melling, R. Vose and P.H. Whitfield, 2005. Arctic climate: past and present. In: *Arctic Climate Impact Assessment*, pp. 21–60. Cambridge University Press.
- McCarthy, K., L. Walker and L. Vigoren, 2004. Subsurface fate of spilled petroleum hydrocarbons in continuous permafrost. *Cold Regions Science and Technology*, 38:43–54.
- McGuire, A.D., J.M. Melillo, D.W. Kicklighter and L.A. Joyce, 1995. Equilibrium responses of soil carbon to climate change: Empirical and process-based estimates. *Journal of Biogeography*, 22:785–796.
- McGuire, A.D., C. Wirth, M. Apps, J. Beringer, J. Clein, H. Epstein, D.W. Kicklighter, J. Bhatti, F.S. Chapin, B. de Groot, D. Efremov, W. Eugster, M. Fukuda, T. Gower, L. Hinzman, B. Huntley, G.J. Jia, E. Kasischke, J. Melillo, V. Romanovsky, A. Shvidenko, E. Vaganov and D. Walker, 2002. Environmental variation, vegetation distribution, carbon dynamics and water/energy exchange at high latitudes. *Journal of Vegetation Science*, 13:301–314.
- McGuire, A.D., F.S. Chapin, III, C. Wirth, M. Apps, J. Bhatti, T. Callaghan, T.R. Christensen, J.S. Clein, M. Fukuda, T. Maximov, A. Onuchin, A. Shvidenko and E. Vaganov, 2007. Responses of high latitude ecosystems to global change: Potential consequences for the climate system. In: Canadell, J.G., D.E. Pataki and L.F. Pitelka (Eds.). *Terrestrial Ecosystems in a Changing World*, pp. 297–310. Springer-Verlag.
- McGuire, A.D., L.G. Anderson, T.R. Christensen, S. Dallimore, L.D. Guo, D.J. Hayes, M. Heimann, T.D. Lorenson, R.W. Macdonald and N. Roulet, 2009. Sensitivity of the carbon cycle in the Arctic to climate change. *Ecological Monographs*, 79:523–555.
- Melnikov, E.S. and S.E. Grechishchev (Eds.), 2002. *Permafrost and Oil and Gas Development*. 402 pp. GEOS Publishing House.
- Melnikov, V.P. and J.J. Smulsky, 2009. *Astronomical Theory of Ice Ages: New Approximations, Solutions and Challenges*. 85 pp. Academic Publishing House, Novosibirsk.
- MEND, 2004. Covers for reactive tailings located in permafrost review. (Mine Environmental Neutral Drainage Program). MEND Report 1.61.4. 6 pp.
- Meyer, M.D., 2008. *Design Standards for US Transportation Infrastructure. The Implications of Climate Change. The Potential Impacts of Climate Change on US*. 30 pp. Transportation Research Board of the National Academies.
- Milankovitch, M., 1930. *Mathematische Klimalehre und Astronomische Theorie der Klimaschwankungen* [Mathematical Climatology and the Astronomical Theory of Climate Change]. 176 pp. Gebrüder Borntraeger, Berlin.
- Milyukova, I.M., O. Kolle, A.V. Varlagin, N.N. Vygodskaya, E.D. Schulze and J. Lloyd, 2002. Carbon balance of a southern taiga spruce stand in European Russia. *Tellus Series B-Chemical and Physical Meteorology*, 54:429–442.
- Ministère des Transports, 2005. *Transportation plan of Nord-du-Québec. Analysis*. 89 pp. Ministère des Transports, Coordination du Nord-du-Québec.
- Mitchell, T.D. and P.D. Jones, 2005. An improved method of constructing a database of monthly climate observations and associated high-resolution grids. *International Journal of Climatology*, 25:693–712.
- Murton, J.B., R. Peterson and J.C. Ozouf, 2006. Bedrock fracture by ice segregation in cold regions. *Science*, 314:1127–1129.
- Myers-Smith, I.H., J.W. Harden, M. Wilkening, C.C. Fuller, A.D. McGuire and F.S. Chapin, III, 2008. Wetland succession in a permafrost collapse: interactions between fire and thermokarst. *Biogeosciences*, 5:1273–1286.
- Naviq Consulting Inc. and AMEC Earth and Environmental, 2007. *Monograph on the Norman Wells Pipeline Geotechnical Design and Performance - 2006 Update*. 214 pp.
- Neff, J.C., J.C. Finlay, S.A. Zimov, S.P. Davydov, J.J. Carrasco, E.A.G. Schuur and A.I. Davydova, 2006. Seasonal changes in the age and structure of dissolved organic carbon in Siberian rivers and streams. *Geophysical Research Letters*, 33:L23401.
- Nelson, F.E., O.A. Anisimov and N.I. Shiklomanov, 2002. Climate change and hazard zonation in the circum-Arctic permafrost regions. *Natural Hazards*, 26:203–225.
- Nelson, F.E., N.I. Shiklomanov, K.M. Hinkel and J. Brown, 2008. Decadal results from the Circumpolar Active Layer Monitoring (CALM) program. Paper presented at Ninth International Conference on Permafrost, pp. 1273–1280. Institute of Northern Engineering, Fairbanks, Alaska.
- Nicolsoy, D.J., V.E. Romanovsky, V.A. Alexeev and D.M. Lawrence, 2007. Improved modeling of permafrost dynamics in a GCM land-surface scheme. *Geophysical Research Letters*, 34:L08501.
- Nishimura, S., A. Gens, S. Olivella and R.J. Jardine, 2009a. THM-coupled finite element analysis of frozen soil: formulation and application. *Géotechnique*, 59:159–171.
- Nishimura, S., C.J. Martin, R.J. Jardine and C.H. Fenton, 2009b. A new approach for assessing geothermal response to climate change in permafrost regions. *Géotechnique*, 59:213–227.
- Oberman, N.G., 2003a. Ecological and geological problems of the urban territories in the North-Eastern European Russia. Paper presented at Northern cities and environment, pp. 222–227. Vorkuta, Russia.
- Oberman, N., 2003b. Infrastructure damage due to permafrost collapse. In: Kuhry, P. (Ed.). *Sustainable Development of the Pechora Region in a Changing Environment and Society (Spice)*. International Scientific Cooperation Projects. European Commission.
- Oberman, N., 2007. Global warming and permafrost changes in Pechora-Urals region. *Exploration and Protection of Natural Resources*, 4:63–68.
- Oberman, N.G., 2008. Contemporary permafrost degradation of northern European Russia. Paper presented at Ninth International Conference on Permafrost, pp. 1305–1310. Institute of Northern Engineering, Fairbanks, Alaska.
- Oberman, N.G. and A.M. Liygin, 2009. Predicting permafrost degradation: case study of North European Russia. *Exploration and Protection of Natural Resources*, 7:15–20.
- Oberman, N.G. and G.C. Mazhitova, 2001. Permafrost dynamics in the northeast of European Russia at the end of the 20th century. *Norwegian Journal of Geography* 55:241–244.

- Oechel, W.C., G.L. Vourlitis, S.J. Hastings and S.A. Bochkarev, 1995. Change in arctic CO₂ flux over two decades: Effects of climate change at Barrow, Alaska. *Ecological Applications*, 5:846–855.
- Oechel, W.C., G.L. Vourlitis, S.J. Hastings, R.C. Zulueta, L. Hinzman and D. Kane, 2000. Acclimation of ecosystem CO₂ exchange in the Alaskan Arctic in response to decadal climate warming. *Nature*, 406:978–981.
- Osterkamp, T.E., 2001. Subsea permafrost. In: Steele, J.H., S.A. Thorpe and K.K. Turekian (Eds.). *Encyclopedia of Ocean Sciences*, pp. 2902–2912, Elsevier.
- Osterkamp, T.E., 2005. The recent warming of permafrost in Alaska. *Global and Planetary Change*, 49:187–202.
- Osterkamp, T.E., 2008. Thermal state of permafrost in Alaska during the fourth quarter of the twentieth century. Paper presented at Ninth International Conference on Permafrost, pp. 1333–1338. Institute of Northern Engineering, Fairbanks, Alaska.
- Osterkamp, T.E. and T. Fei, 1993. Potential occurrence of gas hydrates in the continental shelf near Lonely, Alaska. Paper presented at Sixth International Conference on Permafrost, pp. 500–505, Beijing, China.
- Osterkamp, T.E. and J.P. Gosink, 1991. Variations in permafrost thickness in response to changes in paleoclimate. *Journal of Geophysical Research-Solid Earth and Planets*, 96:4423–4434.
- Osterkamp, T.E. and W.D. Harrison, 1982. Temperature measurements in subsea permafrost off the coast of Alaska. Paper presented at Fourth Canadian Permafrost Conference, pp. 238–249. Natural Research Council Canada, Ottawa, Canada.
- Osterkamp, T.E. and W.D. Harrison, 1985. Sub-sea permafrost: Probing, thermal regime, and data analyses, 1975–1981. Summary report. 108 pp. Geophysical Institute, Fairbanks, Alaska.
- Osterkamp, T.E. and V.E. Romanovsky, 1999. Evidence for warming and thawing of discontinuous permafrost in Alaska. *Permafrost and Periglacial Processes*, 10:17–37.
- Overduin, P.P., H.-W. Hubberten, V. Rachold, N.N. Romanovskii, M.N. Grigoriev and M. Kasymkaya, 2007. The evolution and degradation of coastal and offshore permafrost in the Laptev and Eastern Siberian seas during the last climatic cycle. *Geological Society of America, Special Paper*, 426:97–111.
- Overduin, P.P., V. Rachold and M.N. Grigoriev, 2008. The state of subsea permafrost in the western Laptev nearshore zone. Paper presented at Ninth International Conference on Permafrost, pp. 1345–1350. Institute of Northern Engineering, Fairbanks, Alaska.
- Ozerskaya, S., G. Kochkina, N. Ivanushkina and D. Gilichinsky, 2008. Frost in permafrost. In: Margesin, R. (Ed.). *Permafrost Soils*, pp. 85–96. Springer Verlag.
- Parsons, M.A., S.L. Smith, V.E. Romanovsky, N.I. Shiklomanov, H.H. Christiansen, P.P. Overduin, T. Zhang, M.R. Balks and J. Brown, 2008. Managing permafrost data: past approaches and future directions. Paper presented at Ninth International Conference on Permafrost, pp. 1369–1374. Institute of Northern Engineering, Fairbanks, Alaska.
- Paull, C.K., W. Ussler, S.R. Dallimore, S.M. Blasco, T.D. Lorenson, H. Melling, B.E. Medioli, F.M. Nixon and F.A. McLaughlin, 2007. Origin of pingo-like features on the Beaufort Sea shelf and their possible relationship to decomposing methane gas hydrates. *Geophysical Research Letters*, 34:L01603.
- Payette, S., A. Delwaide, M. Caccianiga and M. Beauchemin, 2004. Accelerated thawing of subarctic peatland permafrost over the last 50 years. *Geophysical Research Letters*, 31:L18208.
- Pazinyak, V.V., 2001. Frost heave as a destabilization factor of oil-and-gas industry objects. Puchino, Russia.
- Perlshtein, G., 2008. Russian Approaches to Permafrost Engineering (Plenary Paper). Paper presented at Ninth International Conference on Permafrost, pp. 1391–1398. Institute of Northern Engineering, Fairbanks, Alaska.
- Peterson, T.P., M. McGuirk, T.G. Houston, A.H. Horvitz and M.F. Wehner, 2008. Climate variability and change with implications for transportation. The Potential Impacts of Climate Change on U.S. Transportation. 90 pp. Transportation Research Board of the National Academies, USA.
- Pham, H.-N., D.C. Sego, L.U. Arenson, D. Blowes and L. Smith, 2008a. Convective heat transfer and waste rock piles under permafrost environment. Paper presented at 61st Canadian Geotechnical Conference, pp. 940–947. Canadian Geotechnical Society, Edmonton.
- Pham, H.-N., L.U. Arenson and D.C. Sego, 2008b. Numerical analysis of forced and natural convection in waste-rock piles in permafrost environments. Paper presented at “Ninth International Conference on Permafrost”, pp. 1411–1416. Institute of Northern Engineering, Fairbanks, Alaska.
- Ping, C.L., G.J. Michaelson, M.T. Jorgenson, J.M. Kimble, H. Epstein, V.E. Romanovsky and D.A. Walker, 2008. High stocks of soil organic carbon in the North American Arctic region. *Nature Geoscience*, 1:615–619.
- Pipko, I.I., I.P. Semiletov, S.P. Pugach, I. Wählström and L.G. Anderson, 2011. Interannual variability of air-sea CO₂ fluxes and carbonate system parameters in the East Siberian Sea. *Biogeosciences Discussions*, 8:1227–1273.
- Plug, L.J., C. Walls and B.M. Scott, 2008. Tundra lake changes from 1978 to 2001 on the Tuktoyaktuk Peninsula, western Canadian Arctic. *Geophysical Research Letters*, 35:L03502.
- Popova, V.V. and A.B. Shmakin, 2009. The Influence of Seasonal Climatic Parameters on the Permafrost Thermal Regime, West Siberia, Russia. *Permafrost and Periglacial Processes*, 20:41–56.
- Powers, T.C. and R.A. Helmuth, 1953. Theory of volume changes in hardened Portland cement paste during freezing. *Proceedings of Highway Research Board* 32:285–297.
- Pozdnyakov, D.V., A.A. Korosov, L.H. Pettersson and O.M. Johannessen, 2005. MODIS evidences the river run-off impact on the Kara Sea trophy. *International Journal of Remote Sensing*, 26:3641–3648.
- Proshutinsky, A., I. Ashik, S. Hakkinen, E. Hunke, R. Krishfield, M. Maltrud, W. Maslowski and J. Zhang, 2007. Sea level variability in the Arctic Ocean from AOMIP models. *Journal of Geophysical Research-Oceans*, 112:C04S08.
- Prowse, T.D., C. Furgal, R. Chouinard, H. Melling, D. Milburn and S.L. Smith, 2009. Implications of climate change for economic development in northern Canada: Energy, resource, and transportation sectors. *Ambio*, 38:272–281.
- Rachold, V., D.Y. Bolshiyakov, M.N. Grigoriev, H.-W. Hubberten, R. Junker, V.V. Kunitsky, P. Overduin and S. W., 2007. Nearshore Arctic subsea permafrost in transition. *EOS*, 88:149–156.
- Rapp, A., 1960. Recent development of mountain slopes in Kärkevagge and surroundings, Northern Sweden. *Geografiska Annaler A*, 42:71–200.
- Rekant, P., V. Tumskoi, T. Gusev, T. Schwenk, F. Spiess, G. Chercashov and H. Kassens, 2009. Distribution and peculiarity of bedding of the sub-sea permafrost near Semenovskoe and Vasilievskoe shoals (Laptev Sea) revealed by high-resolution seismic profiling [in Russian]. In: Kassens, H., A.P. Lisitzin, J. Thiede, Y.I. Polyakova and L.A. Timokhov (Eds.). *System of the Laptev Sea and the adjacent arctic seas: Modern environments and paleoceanography*, Nauchnyi Mir, Moscow.
- Rempel, A.W., 2007. Formation of ice lenses and frost heave. *Journal of Geophysical Research-Earth Surface*, 112:F02S21.
- Rempel, A.W., J.S. Wettlaufer and M.G. Worster, 2004. Premelting dynamics in a continuum model of frost heave. *Journal of Fluid Mechanics*, 498:227–244.
- Repo, M.E., S. Susiluoto, S.E. Lind, S. Jokinen, V. Elsakov, C. Biasi, T. Virtanen and P.J. Martikainen, 2009. Large N₂O emissions from cryoturbated peat soil in tundra. *Nature Geoscience*, 2:189–192.
- Riordan, B., D. Verbyla and A.D. McGuire, 2006. Shrinking ponds in subarctic Alaska based on 1950–2002 remotely sensed images. *Journal of Geophysical Research-Biogeosciences*, 111:G04002.
- Riseborough, D., N. Shiklomanov, B. Ertelmueller, S. Gruber and S. Marchenko, 2008. Recent advances in permafrost modelling. *Permafrost and Periglacial Processes*, 19:137–156.
- Rivkina, E.M., E.I. Friedmann, C.P. McKay and D.A. Gilichinsky, 2000. Metabolic activity of permafrost bacteria below the freezing point. *Applied and Environmental Microbiology*, 66:3230–3233.
- Rivkina, E., K. Laurinavichius, J. McGrath, J. Tiedje, V. Shcherbakova and D. Gilichinsky, 2004. Microbial life in permafrost. In: Horneck, G., A.C. Levasseur Regourd, B.M. Rabin and K.B. Slenzka (Eds.). *Space Life Sciences: Search for Signatures of Life, and Space Flight Environmental Effects on the Nervous System*, pp. 1215–1221, Pergamon-Elsevier Science Ltd.
- Rivkina, E., V. Shcherbakova, K. Laurinavichius, L. Petrovskaya, K. Krivushin, G. Kraev, S. Pecheritsina and D. Gilichinsky, 2007. Biogeochemistry of methane and methanogenic archaea in permafrost. *FEMS Microbiology Ecology*, 61:1–15.
- Rocha, A.V. and G.R. Shaver, 2009. Advantages of a two band EVI calculated from solar and photosynthetically active radiation fluxes. *Agricultural and Forest Meteorology*, 149:1560–1563.

- Rocha, A.V. and G.R. Shaver, 2011. Burn severity influences post-fire CO₂ exchange in arctic tundra. *Ecological Applications*, 21:477–489.
- Roer, I., A. Kaab and R. Dikau, 2005. Rockglacier kinematics derived from small-scale aerial photography and digital airborne pushbroom imagery. *Zeitschrift für Geomorphologie*, 49:73–87.
- Romanovskii, N.N. and H.W. Hubberten, 2001. Results of permafrost modelling of the lowlands and shelf of the Laptev Sea region, Russia. *Permafrost and Periglacial Processes*, 12:191–202.
- Romanovskii, N.N., A.V. Gavrilov, A.L. Kholodov, G.P. Pustovoi, H.-W. Hubberten, F. Nissen and H. Kassens, 1998. Map of predicted off-shore permafrost distribution on the Laptev Sea shelf. Paper presented at Seventh International Conference on Permafrost, pp. 967–973. Collection Nordicana, Yellowknife, Canada.
- Romanovskii, N.N., H.W. Hubberten, A.V. Gavrilov, V.E. Tumskey, G.S. Tipenko, M.N. Grigoriev and C. Siegert, 2000. Thermokarst and land-ocean interactions, Laptev Sea Region, Russia. *Permafrost and Periglacial Processes*, 11:137–152.
- Romanovskii, N.N., H.W. Hubberten, A.V. Gavrilov, A.A. Eliseeva and G.S. Tipenko, 2005. Offshore permafrost and gas hydrate stability zone on the shelf of East Siberian Seas. *Geo-Marine Letters*, 25:167–182.
- Romanovsky, V.E. and T.E. Osterkamp, 1997. Thawing of the active layer on the coastal plain of the Alaskan Arctic. *Permafrost and Periglacial Processes*, 8:1–22.
- Romanovsky, V.E., L.S. Garagula and N.V. Seregina, 1992. Freezing and thawing of soils under the influence of 300- and 90-year periods of temperature fluctuation. Paper presented at International Conference on the Role of Polar Regions in Global Change, pp. 543–548. Geophysical Institute, Fairbanks, Alaska.
- Romanovsky, V.E., S. Gruber, A. Instanes, H. Jin, S.S. Marchenko, S.L. Smith, D. Trombotto and K.M. Walter, 2007. Frozen Ground. *UNEP Global Outlook for Ice & Snow*, pp. 181–200. United Nations Environment Programme.
- Romanovsky, V.E., A.L. Kholodov, S.S. Marchenko, N.G. Oberman, D.S. Drozdov, G.V. Malkova, N.G. Moskalenko, A.A. Vasiliev, D.O. Sergeev and M.N. Zheleznyak, 2008a. Thermal state and fate of permafrost in Russia: first results of IPY. Paper presented at Ninth International Conference on Permafrost, pp. 1511–1518. Institute of Northern Engineering, Fairbanks, Alaska.
- Romanovsky, V.E., S.S. Marchenko, R. Daanen, D.O. Sergeev and D.A. Walker, 2008b. Soil climate and frost heave along the permafrost/ecological North American Arctic transect. Paper presented at Ninth International Conference on Permafrost, pp. 1519–1524. Institute of Northern Engineering, Fairbanks, Alaska.
- Romanovsky, V.E., D.S. Drozdov, N.G. Oberman, G.V. Malkova, A.L. Kholodov, S.S. Marchenko, N.G. Moskalenko, D.O. Sergeev, N.G. Ukraintseva, A.A. Abramov, D.A. Gilichinsky and A.A. Vasiliev, 2010a. Thermal state of permafrost in Russia. *Permafrost and Periglacial Processes*, 21:136–155.
- Romanovsky, V.E., S.L. Smith and H.H. Christiansen, 2010b. Permafrost thermal state in the polar northern hemisphere during the International Polar Year 2007–2009: a synthesis. *Permafrost and Periglacial Processes*, 21:106–116.
- Ross, N., P.J. Brabham, C. Harris and H.H. Christiansen, 2007. Internal structure of open system pingos, Adventdalen, Svalbard: The use of resistivity tomography to assess ground-ice conditions. *Journal of Environmental and Engineering Geophysics*, 12:113–126.
- Saito, K., M. Kimoto, T. Zhang, K. Takata and S. Emori, 2007. Evaluating a high-resolution climate model: Simulated hydrothermal regimes in frozen ground regions and their change under the global warming scenario. *Journal of Geophysical Research-Earth Surface*, 112:F02S11.
- Sannel, A.B.K. and P. Kuhry, 2008. Permafrost dynamics and landscape changes in a subarctic peat plateau, northern Sweden. Paper presented at Ninth International Conference on Permafrost, pp. 265–266. Institute of Northern Engineering, Fairbanks, Alaska.
- Sannel, A.B.K. and P. Kuhry, 2009. Holocene peat growth and decay dynamics in sub-arctic peat plateaus, west-central Canada. *Boreas*, 38:13–24.
- Sazonova, T.S. and V.E. Romanovsky, 2003. A model for regional-scale estimation of temporal and spatial variability of active layer thickness and mean annual ground temperatures. *Permafrost and Periglacial Processes*, 14:125–139.
- Sazonova, T.S., V.E. Romanovsky, J.E. Walsh and D.O. Sergueev, 2004. Permafrost dynamics in the 20th and 21st centuries along the East Siberian transect. *Journal of Geophysical Research-Atmospheres*, 109:D01108.
- Schirrmeister, L., C. Siegert, T. Kuznetsova, S. Kuzmina, A. Andreev, F. Kienast, H. Meyer and A. Bobrov, 2002. Paleoenvironmental and paleoclimatic records from permafrost deposits in the Arctic region of Northern Siberia. *Quaternary International*, 89:97–118.
- Schulze, E.D., J. Lloyd, F.M. Kelliher, C. Wirth, C. Rebmann, B. Lühker, M. Mund, A. Knohl, I.M. Milyukova, W. Schulze, W. Ziegler, A.B. Varlagin, A.F. Sogachev, R. Valentini, S. Dore, S. Grigoriev, O. Kolle, M.I. Panforyov, N. Tchebakova and N.N. Vygodskaya, 1999. Productivity of forests in the Eurosiberian boreal region and their potential to act as a carbon sink – a synthesis. *Global Change Biology*, 5:703–722.
- Schuur, E.A.G., K.G. Crummer, J.G. Vogel and M.C. Mack, 2007. Plant species composition and productivity following permafrost thaw and thermokarst in alaskan tundra. *Ecosystems*, 10:280–292.
- Schuur, E.A.G., J. Bockheim, J.G. Canadell, E. Euskirchen, C.B. Field, S.V. Goryachkin, S. Hagemann, P. Kuhry, P.M. Lafleur, H. Lee, G. Mazhitova, F.E. Nelson, A. Rinke, V.E. Romanovsky, N. Shiklomanov, C. Tarnocai, S. Venevsky, J.G. Vogel and S.A. Zimov, 2008. Vulnerability of permafrost carbon to climate change: Implications for the global carbon cycle. *Bioscience*, 58:701–714.
- Schuur, E.A.G., J.G. Vogel, K.G. Crummer, H. Lee, J.O. Sickman and T.E. Osterkamp, 2009. The effect of permafrost thaw on old carbon release and net carbon exchange from tundra. *Nature*, 459:556–559.
- Schwenk, T., V. Spiess, P. Reikant, E. Gusev and H. Kassens, 2006. Structure of Late Quaternary sediments and submarine permafrost in the Laptev Sea – Results from multichannel seismic surveys during Expedition Transdrift X. Paper presented at Eighth Workshop on Russian-German Cooperation: Laptev Sea System, 79, St. Petersburg, Russia, 7–9 February.
- Semiletov, I.P., 1999. Aquatic sources and sinks of CO₂ and CH₄ in the polar regions. *Journal of the Atmospheric Sciences*, 56:286–306.
- Semiletov, I.P. and I.I. Pipko, 2007. Sinks and sources of carbon dioxide in the Arctic Ocean. *Transactions of Russian Academy of Sciences*, 414:642–645.
- Semiletov, I., O. Dudarev, V. Luchin, A. Charkin, K.H. Shin and N. Tanaka, 2005. The East Siberian Sea as a transition zone between Pacific-derived waters and Arctic shelf waters. *Geophysical Research Letters*, 32:L10614.
- Semiletov, I.P., I.I. Pipko, I. Repina and N.E. Shakhova, 2007. Carbonate chemistry dynamics and carbon dioxide fluxes across the atmosphere-ice-water interfaces in the Arctic Ocean: Pacific sector of the Arctic. *Journal of Marine Systems*, 66:204–226.
- Semiletov, I., N. Shakhova, M. Grigoriev, I.I. Pipko and D. O., 2010. On the role of missed components of carbon cycling in the east Siberian Arctic shelf. Paper presented at State of the Arctic Conference. Poster available at <http://soa.arcus.org/sites/soa.arcus.org/files/sessions/1-4-challenges-arctic-system-studies/pdf/semiletov.pdf>. 16–19 March.
- Semiletov, I.P., I.I. Pipko, N.E. Shakhova, O.V. Dudarev, S.P. Pugach, A.N. Charkin, C.P. McRoy, D. Kosmach and O. Gustafsson, 2011. On the biogeochemical signature of the Lena River from its headwaters to the Arctic Ocean. *Biogeosciences Discussions*, 8:2093–2143.
- Seppälä, M., 1988. Palsas and related forms. In: Clark, M.J. (Ed.). *Advances in Periglacial Geomorphology*, pp. 247–278, John Wiley and Sons.
- Seppälä, M., 2003. An experimental climate change study of the effect of increasing snow cover on active layer formation of a palsa, Finnish Lapland. Paper presented at Eighth International Conference on Permafrost, 1013–1016 pp., Swets and Zeitlinger, 2003.
- Shakhova, N. and I. Semiletov, 2007. Methane release and coastal environment in the East Siberian Arctic shelf. *Journal of Marine Systems*, 66:227–243.
- Shakhova, N., I. Semiletov, A. Salyuk, N. Bel'cheva and D. Kosmach, 2007a. Methane anomalies in the near-water atmospheric layer above the shelf of East Siberian Arctic shelf. *Transactions of Russian Academy of Sciences*, 415:764–768.
- Shakhova, N., I. Semiletov and N. Belcheva, 2007b. The great Siberian rivers as a source of methane on the Russian Arctic shelf. *Transactions of Russian Academy of Sciences*, 414:734–736.
- Shakhova, N., I. Semiletov, A. Salyuk, N. Belcheva, D. Kosmach and V.I. Sergienko, 2008a. On the role of the East-Siberian Shelf in the modern methane cycle and global change. *Harold of the East-Siberian Branch of Russian Academy of Sciences*, 4:164–176.
- Shakhova, N.E., I.P. Semiletov, V.I. Sergienko, A.N. Salyuk, N.N. Belcheva and D.A. Kosmach, 2008b. On the role of the East Siberian Arctic Shelf in the modern marine methane cycle. *Change of Natural Environment and Climate- natural and possible consequent human-induced*

- catastrophes, pp. 164-176, Russian Academy of Science, Moscow.
- Shakhova, N., I. Semiletov, A. Salyuk, V. Yusupov, D. Kosmach and Ö. Gustafsson, 2010a. Extensive methane venting to the atmosphere from sediments of the East Siberian Arctic shelf. *Science*, 327:1246-1250.
- Shakhova, N., I. Semiletov, I. Leifer, A. Salyuk, P. Rekant and D. Kosmach, 2010b. Geochemical and geophysical evidence of methane release over the East Siberian Arctic Shelf. *Journal of Geophysical Research-Oceans*, 115:C08007.
- Shatilovich, A.V., L.A. Shmakova, S.V. Gubin, A.V. Gudkov and D.A. Gilichinskii, 2005. Viable protozoa in late Pleistocene and Holocene permafrost sediments. *Doklady Biological Sciences*, 401:136-138.
- Shiklomanov, N.I., F.E. Nelson, D.A. Streletskiy, K.M. Hinkel and J. Brown, 2008. The Circumpolar Active Layer Monitoring (CALM) Program: Data Collection, Management, and Dissemination Strategy. Paper presented at Ninth International Conference on Permafrost, pp. 1647-1652. Institute of Northern Engineering, Fairbanks, Alaska.
- Shoham, D., 2005. Viral pathogens of humans likely to be preserved in natural ice. In: Castello, J.D. and S.O. Rogers (Eds.). *Life in Ancient Ice*, pp. 208-226, Princeton University Press.
- Shur, Y.L. and M.T. Jorgenson, 2007. Patterns of permafrost formation and degradation in relation to climate and ecosystems. *Permafrost and Periglacial Processes*, 18:7-19.
- Shur, Y., K.M. Hinkel and F.E. Nelson, 2005. The transient layer: Implications for geocryology and climate-change science. *Permafrost and Periglacial Processes*, 16:5-17.
- Silapaswan, C.S., D.L. Verbyla and A.D. McGuire, 2001. Land cover change on the Seward Peninsula: The use of remote sensing to evaluate the potential influences of climate warming on historical vegetation dynamics. *Canadian Journal of Remote Sensing*, 27:542-554.
- Sitch, S., A.D. McGuire, J. Kimball, N. Gedney, J. Gamon, R. Engstrom, A. Wolf, Q. Zhuang, J. Clein and K.C. McDonald, 2007. Assessing the carbon balance of circumpolar Arctic tundra using remote sensing and process modeling. *Ecological Applications*, 17:213-234.
- Smith, S.L. and M.M. Burgess, 2004. Sensitivity of permafrost to climate warming in Canada. *Geological Survey of Canada Bulletin*, 579, 24 p.
- Smith, S.L. and D.W. Riseborough, 2010. Modelling the thermal response of permafrost terrain to right-of-way disturbance and climate warming. *Cold Regions Science and Technology*, 60:92-103.
- Smith, S.L., M.M. Burgess and A.E. Taylor, 2003. High Arctic permafrost observatory at Alert, Nunavut - analysis of a 23 year data set. Paper presented at Eighth International Conference on Permafrost, pp. 1073-1078. A.A. Balkema.
- Smith, S.L., M.M. Burgess, D. Riseborough, T. Coultish and J. Chartrand, 2004. Digital summary database of permafrost and thermal conditions - Norman Wells Pipeline study sites. *Geological Survey of Canada, Open File 4635*, 104 pp.
- Smith, S.L., M.M. Burgess, D. Riseborough and F.M. Nixon, 2005a. Recent trends from Canadian permafrost thermal monitoring network sites. *Permafrost and Periglacial Processes*, 16:19-30.
- Smith, L.C., Y. Sheng, G.M. MacDonald and L.D. Hinzman, 2005b. Disappearing Arctic lakes. *Science*, 308:1429-1429.
- Smith, S.L., M.M. Burgess and D.W. Riseborough, 2008a. Ground temperature and thaw settlement in frozen peatlands along the Norman Wells pipeline corridor, NWT Canada: 22 years of monitoring. Paper presented at Ninth International Conference on Permafrost, pp. 1665-1670. Institute of Northern Engineering, Fairbanks, Alaska.
- Smith, S.L., A.G. Lewkowicz and C.R. Burn, 2008b. Thermal state of permafrost in Canada: a contribution to the International Polar Year. Paper presented at Ninth International Conference on Permafrost, Extended Abstracts, pp. 295-296. Institute of Northern Engineering, Fairbanks, Alaska.
- Smith, S.L., M.M. Burgess, D. Riseborough and J. Chartrand, 2008c. Permafrost and terrain research and monitoring sites of the Norman Wells to Zama pipeline - Thermal data collection and case histories, April 1985 to September 2001. *Geological Survey of Canada, Open File:5331*.
- Smith, S.L., T.-N. Nguyen, D.W. Riseborough, M. Ednie, S. Ye and J. Chartrand, 2008d. Preliminary ground-thermal data for permafrost-monitoring sites established in 2007 between Fort Good Hope and Norman Wells, Northwest Territories. *Geological Survey of Canada Current Research*. 2008-20. 12 pp.
- Smith, S.L., S.A. Wolfe, D.W. Riseborough and F.M. Nixon, 2009a. Active-layer characteristics and summer climatic indices, Mackenzie Valley, Northwest Territories, Canada. *Permafrost and Periglacial Processes*, 20:201-220.
- Smith, S.L., J. Chartrand, T.N. Nguyen, D.W. Riseborough, M. Ednie and S. Ye, 2009b. Geotechnical database and descriptions of permafrost monitoring sites established 2006-07 in the central and southern Mackenzie Corridor. *Geological Survey of Canada, Open File 6041*. 188 pp.
- Smith, S.L., V.E. Romanovsky, A.G. Lewkowicz, C.R. Burn, M. Allard, G.D. Clow, K. Yoshikawa and J. Throop, 2010. Thermal state of permafrost in North America: A contribution to the International Polar Year. *Permafrost and Periglacial Processes*, 21:117-135.
- Smol, J.P. and M.S.V. Douglas, 2007. Crossing the final ecological threshold in high Arctic ponds. *Proceedings of the National Academy of Sciences of the United States of America*, 104:12395-12397.
- Smolyanitsky, V., I. Karelin, V. Karklin and B. Ivanov, 2003. Sea ice of the Eastern Siberian Sea: Ice conditions, albedo, and surface contamination, ice mass exchange. Paper presented at ESSS Workshop 2003, 5 pp., International Arctic Research Centre, Malaga, Spain.
- Søgaard, H., C. Nordstrøm, T. Friberg, B.U. Hansen, T.R. Christensen and C. Bay, 2000. Trace gas exchange in a high-Arctic valley. 3. Integrating and scaling CO₂ fluxes from canopy to landscape using flux data, footprint modeling, and remote sensing. *Global Biogeochemical Cycles*, 14:725-744.
- Sokolov, A.P. and P.H. Stone, 1998. A flexible climate model for use in integrated assessments. *Climate Dynamics*, 14:291-303.
- Solomon, S., D. Qin, M. Manning, Z. Chen, M. Marquis, K.B. Averyt, M. Tignor and H.L. Miller (Eds.), 2007. *Climate Change 2007: The Physical Science Basis. Contribution of Working Group I to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change*, 996 pp. Cambridge University Press.
- Soloviev, V.A., G.D. Ginzburg, E.V. Telepnev and Y.N. Mikhaleuk, 1987. *Cryothermia and gas hydrates in the Arctic Ocean*. 150 pp. Sevmoregologia, Leningrad.
- Stendel, M. and J.H. Christensen, 2002. Impact of global warming on permafrost conditions in a coupled GCM. *Geophysical Research Letters*, 29:4.
- Stendel, M., J.H. Christensen, S. Marchenko, R. Daanen and V.E. Romanovsky, 2010. Size matters - Very high resolution permafrost simulations on the 4 km scale in northeast European Russia. Paper presented at Third European Conference on Permafrost, Longyearbyen, Svalbard.
- Steven, B., R. Leveille, W.H. Pollard and L.G. Whyte, 2006. Microbial ecology and biodiversity in permafrost. *Extremophiles*, 10:259-267.
- Streletskiy, D.A., N.I. Shiklomanov, F.E. Nelson and A.E. Klene, 2008. Thirteen years of observations at Alaskan CALM sites: Long-term active layer and ground surface temperature trends. Paper presented at Ninth International Conference on Permafrost, pp. 1727-1732, Fairbanks, Alaska.
- Striegl, R.G., G.R. Aiken, M.M. Dornblaser, P.A. Raymond and K.P. Wickland, 2005. A decrease in discharge-normalized DOC export by the Yukon River during summer through autumn. *Geophysical Research Letters*, 32:L21413.
- Striegl, R.G., M.M. Dornblaser, G.R. Aiken, K.P. Wickland and P.A. Raymond, 2007. Carbon export and cycling by the Yukon, Tanana, and Porcupine rivers, Alaska, 2001-2005. *Water Resources Research*, 43:W02411.
- Strom, L. and T.R. Christensen, 2007. Below ground carbon turnover and greenhouse gas exchanges in a sub-arctic wetland. *Soil Biology & Biochemistry*, 39:1689-1698.
- Sturm, M., C. Racine and K. Tape, 2001. Climate change - Increasing shrub abundance in the Arctic. *Nature*, 411:546-547.
- Sushama, L., R. Laprise and M. Allard, 2006. Modeled current and future soil thermal regime for northeast Canada. *Journal of Geophysical Research-Atmospheres*, 111:D18111.
- Tarnocai, C., J.G. Canadell, E.A.G. Schuur, P. Kuhry, G. Mazhitova and S. Zimov, 2009. Soil organic carbon pools in the northern circumpolar permafrost region. *Global Biogeochemical Cycles*, 23:GB2023.
- Taylor, A.E., 1991. Marine transgression, shoreline emergence: evidence in seabed and terrestrial ground temperatures of changing relative sea levels, Arctic Canada. *Journal of Geophysical Research-Solid Earth and Planets*, 96:6893-6909.
- Taylor, A.E., K.L. Wang, S.L. Smith, M.M. Burgess and A.S. Judge, 2006. Canadian Arctic permafrost observatories: Detecting contemporary

- climate change through inversion of subsurface temperature time series. *Journal of Geophysical Research-Solid Earth*, 111:B02411.
- Thibault, S. and S. Payette, 2009. Recent permafrost degradation in bogs of the James Bay Area, northern Quebec, Canada. *Permafrost and Periglacial Processes*, 20:383-389.
- Thompson, M.S., S.V. Kokelj, T.D. Prowse and F. Wrona, 2008. The impact of sediments derived from thawing permafrost on tundra lake water chemistry: an experimental approach. pp. 1763-1767. *Proceedings of the 9th Permafrost International Conference*, Institute of Northern Engineering, Fairbanks, Alaska.
- Tiedje, J.M., G.B. Smith, S. Simkins, W.E. Holben, C. Finney and D.A. Gilichinsky, 1994. Recovery of DNA, denitrifiers and patterns of antibiotic sensitivity in microorganisms from ancient permafrost soils of Eastern Siberia. In: Gilichinsky, D.A. (Ed.). *Viable Microorganisms in Permafrost*, pp. 83-98, Russian Academy of Sciences.
- Turetsky, M.R., R.K. Wieder, C.J. Williams and D.H. Vitt, 2000. Organic matter accumulation, peat chemistry, and permafrost melting in peatlands of boreal Alberta. *Ecoscience*, 7:379-392.
- Turetsky, M.R., R.K. Wieder, D.H. Vitt, R.J. Evans and K.D. Scott, 2007. The disappearance of relict permafrost in boreal North America: Effects on peatland carbon storage and fluxes. *Global Change Biology*, 13:1922-1934.
- US Arctic Research Commission, 2003. *Climate Change, Permafrost, and Impacts on Civil Infrastructure*. U.S. Arctic Research Commission Special Report. 01-03, 72 pp. Permafrost Task Force.
- Vallée, S. and S. Payette, 2007. Collapse of permafrost mounds along a subarctic river over the last 100 years (northern Québec). *Geomorphology*, 90:162-170.
- van der Wal, R. and R.W. Brooker, 2004. Mosses mediate grazer impacts on grass abundance in arctic ecosystems. *Functional Ecology*, 18:77-86.
- Velichko, A.A. and M.A. Faustova, 2009. Glaciation during the Late Pleistocene. In: Velichko, A.A. (Ed.). *Paleoclimates and paleoenvironments of extra-tropical area of the Northern Hemisphere. Late Pleistocene - Holocene*, pp. 32-42, GEOS, Moscow.
- Velichko, A.A. and V.P. Nechaev (Eds.), 2005. *Cenozoic Climatic and Environmental Changes in Russia*. 226 pp.
- Velichko, A.A. and V.P. Nechaev, 2009. Subaerial cryolithozone of the Northern Hemisphere during the Late Pleistocene and Holocene. In: Velichko, A.A. (Ed.). *Paleoclimates and Paleoenvironments of Extra-tropical area of the Northern Hemisphere. Late Pleistocene - Holocene*, pp. 42-49, GEOS, Moscow.
- Veremeeva, A. and S. Gubin, 2008. Approaches to allocation of terrain complexes (landscapes) in areas of thermokarst development. Paper presented at Ninth International Conference on Permafrost, pp. 1827-1831. Institute of Northern Engineering, Fairbanks, Alaska.
- Vetrov, A.A. and E.A. Romankevich, 2004. *Carbon Cycle in the Russian Arctic Seas*. 331 pp. Springer Verlag.
- Viereck, L.A., N.R. Werdin-Pfister, C.A. Phyllis and K. Yoshikawa, 2008. Effect of wildfire and fireline construction on the annual depth of thaw in a black spruce permafrost forest in interior Alaska: A 360 year record of recovery. Paper presented at Ninth International Conference on Permafrost, pp. 1845-1850. Institute of Northern Engineering, Fairbanks, Alaska.
- Vigdorchik, M.E., 1980. *Submarine Permafrost on the Alaskan Continental Shelf*. 118 pp. Westview Press.
- Vishnivetskaya, T., 2008. Viable cyanobacteria and green algae from the permafrost. In: Margesin, R. (Ed.). *Permafrost Soils*, pp. 73-84, Springer Verlag.
- Vishnivetskaya, T.A., M.A. Petrova, J. Urbance, M. Ponder, C.L. Moyer, D.A. Gilichinsky and J.M. Tiedje, 2006. Bacterial community in ancient Siberian permafrost as characterized by culture and culture-independent methods. *Astrobiology*, 6:400-414.
- Vitt, D.H., L.A. Halsey and S.C. Zoltai, 2000. The changing landscape of Canada's western boreal forest: the current dynamics of permafrost. *Canadian Journal of Forest Research*, 30:283-287.
- Vogel, J., E.A.G. Schuur, C. Trucco and H. Lee, 2009. Response of CO₂ exchange in a tussock tundra ecosystem to permafrost thaw and thermokarst development. *Journal of Geophysical Research-Biogeosciences*, 114:G04018.
- Vorobyova, E., V. Soina, M. Gorlenko, N. Minkovskaya, N. Zalinova, A. Mamukelashvili, D. Gilichinsky, E. Rivkma and T. Vishnivetskaya, 1997. The deep cold biosphere: facts and hypothesis. *Federation of European Microbiological Societies, Microbiology Reviews*, 20:277-290.
- Walder, J. and B. Hallet, 1985. A theoretical model of the fracture of rock during freezing. *Geological Society of America Bulletin*, 96:336-346.
- Walker, D.A., 1995. Patterns and causes of Arctic plant community diversity. In: Chapin III, F.S. and C. Körner (Eds.). *Arctic and Alpine Biodiversity*, pp. 3-20, Springer.
- Walker, M.D., D.A. Walker, J.M. Welker, A.M. Arft, T. Bardsley, P.D. Brooks, J.T. Fahnestock, M.H. Jones, M. Losleben, A.N. Parsons, T.R. Seastedt and P.L. Turner, 1999. Long-term experimental manipulation of winter snow regime and summer temperature in arctic and alpine tundra. *Hydrological Processes*, 13:2315-2330.
- Walter, K.M., S.A. Zimov, J.P. Chanton, D. Verbyla and F.S. Chapin III, 2006. Methane bubbling from Siberian thaw lakes as a positive feedback to climate warming. *Nature*, 443:71-75.
- Walter, K.M., M.E. Edwards, G. Grosse, S.A. Zimov and F.S. Chapin III, 2007a. Thermokarst lakes as a source of atmospheric CH₄ during the last deglaciation. *Science*, 318:633-636.
- Walter, K.M., L.C. Smith and F.S. Chapin III, 2007b. Methane bubbling from northern lakes: present and future contributions to the global methane budget. *Philosophical Transactions of the Royal Society A-Mathematical Physical and Engineering Sciences*, 365:1657-1676.
- Walvoord, M.A. and R.G. Striegl, 2007. Increased groundwater to stream discharge from permafrost thawing in the Yukon River basin: Potential impacts on lateral export of carbon and nitrogen. *Geophysical Research Letters*, 34:L12402.
- Wania, R., I. Ross and I.C. Prentice, 2009. Integrating peatlands and permafrost into a dynamic global vegetation model: 1. Evaluation and sensitivity of physical land surface processes. *Global Biogeochemical Cycles*, 23:GB3014.
- Wegmann, M., G.H. Gudmundsson and W. Haeberli, 1998. Permafrost changes in rock walls and the retreat of alpine glaciers: A thermal modelling approach. *Permafrost and Periglacial Processes*, 9:23-33.
- Willerslev, E., A.J. Hansen, J. Binladen, T.B. Brand, M.T.P. Gilbert, B. Shapiro, M. Bunce, C. Wiuf, D.A. Gilichinsky and A. Cooper, 2003. Diverse plant and animal genetic records from Holocene and Pleistocene sediments. *Science*, 300:791-795.
- Willerslev, E., A.J. Hansen, R. Ronn, T.B. Brand, I. Barnes, C. Wiuf, D. Gilichinsky, D. Mitchell and A. Cooper, 2004. Long-term persistence of bacterial DNA. *Current Biology*, 14:R9-R10.
- Williams, P.J. and M.W. Smith, 1989. *The Frozen Earth: Fundamentals of Geocryology*. 306 pp. Cambridge University Press.
- Wilmking, M., G.P. Juday, V.A. Barber and H.S.J. Zald, 2004. Recent climate warming forces contrasting growth responses of white spruce at treeline in Alaska through temperature thresholds. *Global Change Biology*, 10:1724-1736.
- Wirth, C., 2005. Fire regime and tree diversity in boreal forests: Implications for the carbon cycles. In: Scherer-Lorenzen, M., C. Körner and E.-D. Schulze (Eds.). *Ecological Studies, Forest Diversity and Function: Temperate and Boreal Systems*, pp. 309-345, Springer Verlag.
- Wolf, A., T.V. Callaghan and K. Larson, 2008. Future changes in vegetation and ecosystem function of the Barents Region. *Climatic Change*, 87:51-73.
- Woo, M.K., 1986. Permafrost hydrology in North America. *Atmosphere-Ocean*, 24:201-234.
- Woo, M.K. and K.L. Young, 1998. Characteristics of patchy wetlands in a polar desert environment, Arctic Canada.
- Woo, M.K. and K.L. Young, 2006. High Arctic wetlands: Their occurrence, hydrological characteristics and sustainability. *Journal of Hydrology*, 320:432-450.
- Woo, M.K., K.L. Young and L. Brown, 2006a. High Arctic patchy wetlands: Hydrologic variability and their sustainability. *Physical Geography*, 27:297-307.
- Woo, M.K., M. Mollinga and S.L. Smith, 2006b. Simulating active layer thaw in a boreal environment. *Géographie Physique et Quaternaire*, 60:9-17.
- Woo, M.K., M. Mollinga and S.L. Smith, 2007. Climate warming and active layer thaw in the boreal and tundra environments of the Mackenzie Valley. *Canadian Journal of Earth Sciences*, 44:733-743.
- Woo, M.K., M. Molligna and S.L. Smith, 2008. Modeling maximum active layer thaw in boreal and tundra environments using limited data. In: Woo, M.K. (Ed.). *Cold Region Atmospheric and Hydrologic Studies. The Mackenzie GEWEX Experience*, pp. 125-138, Springer-Verlag.
- Yashina, S.G., S.V. Gubin, E.V. Shabaeva, E.F. Egorova and S.V. Maksimovich, 2002. Viability of higher plant seeds of late pleistocene age from

- permafrost deposits as determined by in vitro culturing. *Doklady Biological Sciences*, 383:151–154.
- Yershov, E., 1998. *General Geocryology*. 580 pp. Cambridge University Press.
- Yi, S.H., M.K. Woo and M.A. Arain, 2007. Impacts of peat and vegetation on permafrost degradation under climate warming. *Geophysical Research Letters*, 34:L16504.
- Yoshikawa, K. and L.D. Hinzman, 2003. Shrinking thermokarst ponds and groundwater dynamics in discontinuous permafrost near Council, Alaska. *Permafrost and Periglacial Processes*, 14:151–160.
- Zamolodchikov, D., A. Kotov, D. Karelin and V. Razzhivin, 2008. Recent climate and active layer changes in Northeast Russia: regional output of Circumpolar Active Layer Monitoring (CALM). Paper presented at Ninth International Conference on Permafrost, pp. 2021–2027. Institute of Northern Engineering, Fairbanks, Alaska.
- Zhang, T., R.G. Barry and R.L. Armstrong, 2004. Application of satellite remote sensing techniques to frozen ground studies. *Polar Geography*, 28:163–196.
- Zhang, G., D. Shoham, D. Gilichinsky, S. Davydov, J.D. Castello and S.O. Rogers, 2006. Evidence of influenza A virus RNA in Siberian lake ice. *Journal of Virology*, 80:12229–12235.
- Zhang, Y., W.J. Chen and D.W. Riseborough, 2008a. Disequilibrium response of permafrost thaw to climate warming in Canada over 1850–2100. *Geophysical Research Letters*, 35:L02502.
- Zhang, Y., W.J. Chen and D.W. Riseborough, 2008b. Transient projections of permafrost distribution in Canada during the 21st century under scenarios of climate change. *Global and Planetary Change*, 60:443–456.
- Zhang, Y., W. Chen and D.W. Riseborough, 2008c. Modeling long-term dynamics of snow and their impacts on permafrost in Canada. Paper presented at Ninth International Conference on Permafrost, pp. 2055–2060. Institute of Northern Engineering, Fairbanks, Alaska.
- Zhigarev, L.A., 1997. *Submarine Permafrost*. 320 pp. Moscow State University Press.
- Zhou, F., Zhang, A., Li, R. and Hoeve, E., 2009. Spatio-temporal simulation of permafrost geothermal response to climate change scenarios in a building environment. *Cold Regions Science and Technology*, 56: 141–151.
- Zhuang, Q.L., J.M. Melillo, M.C. Sarofim, D.W. Kicklighter, A.D. McGuire, B.S. Felzer, A. Sokolov, R.G. Prinn, P.A. Steudler and S.M. Hu, 2006. CO₂ and CH₄ exchanges between land ecosystems and the atmosphere in northern high latitudes over the 21st century. *Geophysical Research Letters*, 33:L17403.
- Zimov, S.A., E.A.G. Schuur and F.S. Chapin, III, 2006a. Permafrost and the global carbon budget. *Science*, 312:1612–1613.
- Zimov, S.A., S.P. Davydov, G.M. Zimova, A.I. Davydova, E.A.G. Schuur, K. Dutta and F.S. Chapin, III, 2006b. Permafrost carbon: Stock and decomposability of a globally significant carbon pool. *Geophysical Research Letters*, 33:L20502.
- Zuidhoff, F.S. and E. Kolstrup, 2000. Changes in peat distribution in relation to climate change in Laivadalen, northern Sweden, especially 1960–1997. *Permafrost and Periglacial Processes*, 11:55–69.

6. Changing Lake and River Ice Regimes: Trends, Effects and Implications

COORDINATING LEAD AUTHOR: TERRY PROWSE

LEAD AUTHORS: KNUT ALFREDSEN, SPYROS BELTAOS, BARRIE BONSAI, CLAUDE DUGUAY, ATTE KORHOLA, JAMES MCNAMARA, WARWICK F. VINCENT, VALERY VUGLINSKY, GESA WEYHENMEYER

CONTRIBUTING AUTHORS: KATEY WALTER ANTHONY, BRECK BOWDEN, VLADIMIR BUZIN, YONAS DIBIKE, NIKOLAUS GANTNER, LARRY HINZMAN, LEIF LIA, TAHA OUARDA, REINHARD PIENITZ, JAMES D. REIST, MORTEN STICKLER, JAN WECKSTRÖM, FRED WRONA

Contents

Key Findings	2	6.5. Effects of changing freshwater ice covers	24
Summary	2	6.5.1. Hydrological effects	24
6.1. Introduction	4	6.5.2. Ecological effects	31
6.1.1. Objectives, methodology and structure	4	6.5.3. Socio-economic consequences and adaptation options .	38
6.1.2. Physical description of lake and river ice	5	6.6. Major uncertainties and future research	42
6.1.3. Spatial extent	6	6.6.1. Observation networks	42
6.1.4. Physical, ecological and socio-economic importance ...	7	6.6.2. Trend analysis and climatic linkage	43
6.2. Sources of information	8	6.6.3. Predictive modeling	43
6.2.1. Surface-based observations	9	6.6.4. Advanced evaluations of socio-economic	
6.2.2. Remote sensing	10	impacts and adaptation options	44
6.3. Role in the climate system	11	Acknowledgments	45
6.3.1. Effects on local climate and large-scale		References	45
climatic feedbacks	11		
6.3.2. Climatic controls	13		
6.4. Changes: past and future	14		
6.4.1. Paleo-historical changes	14		
6.4.2. Trends of the instrumental period and			
linkage with climate	17		
6.4.3. Projected changes	21		

Key Findings

- Paleolimnological records of some High Arctic lakes indicate that recent (past 100 year) reductions in ice conditions are significant and associated with profound changes in biological productivity and diversity.
- The end of the past century has seen a decline in systematic observations of ice conditions in the Arctic and changes in observational techniques, making circumpolar assessments of ice phenology difficult.
- While ice-covered locations in more southern regions have been shown to be the most thermally sensitive to warming, recent evidence indicates that changes in ice cover duration have been greater at some High Arctic locations than in regions farther south.
- Reductions in lake-ice duration will modify thermal conditions that can lead to (i) enhanced evaporation and potential loss of shallow lakes and (ii) enhanced mixing, which can turn these Arctic systems into sinks for contaminants.
- Loss of ice cover will also lead to increased methane emissions from Arctic lakes and levels of exposure to ultraviolet radiation that exceed those due to atmospheric ozone depletion, although these could be mitigated by catchment processes producing changes in water budgets and organic inputs.
- Changes in ice-cover dynamics will alter the frequency and magnitude of extreme ice-jam floods, thereby affecting riparian and under-ice ecology as well as hazards to Arctic communities and infrastructure.
- Decreases and loss of river- and lake-ice transportation routes are producing large costs for Arctic communities and industry, and these are likely to increase in the future. Moreover, economically viable adaptation options are extremely limited.

Summary

Unlike the other major global cryospheric components that either blanket large expanses (e.g., snow, permafrost, and sea ice) or are concentrated in large volumes in specific locations (e.g., glaciers and ice sheets), lake and river ice are interwoven into the terrestrial landscape through the major freshwater flow and storage networks. As such, freshwater ice has enormous significance to physical, ecological and socio-economic systems. In discussing its role, it is important to note that the hydrological influence on this cryospheric component extends well outside the Arctic via the main northward-flowing rivers.

Surface-based observations have provided much of the information about the response of lake and river ice to climate. The earliest long-term ice observations on Arctic lakes and rivers date back to the 17th and 18th centuries. Since the middle of the 20th century, national programs of ice-thickness measurements have been carried out in most Northern countries. Unfortunately, there appears to have been a significant decline in a number of ice-observation programs over the past two decades. Moreover, there tend to be fewer observations carried out at higher latitudes as opposed to more southerly locations. To supplement current observations and to extend the historical record, a number of other methods have been used, including isotopes, tree scars, and buried taxa. Unfortunately, a transition to remote sensing by regular observational programs has not yet been realized in any circumpolar country.

Given that ice-covered freshwater bodies of various sizes represent a considerable fraction of the northern high-latitude sub-Arctic and tundra landscape, they need to be considered in any form of climate modeling of Arctic terrestrial environments. The degree to which the atmosphere is influenced depends on several factors, including the magnitude, timing, location, and duration of ice cover. A significant shortening of the freshwater ice duration period can have profound impacts on local, regional, and even larger-scale climate over the Arctic. The formation, growth, decay and break-up processes of ice cover differ markedly between lakes and rivers, but all are influenced by similar climatic variables that control surface heat fluxes. In addition to changes in such variables, other indirect controls, such as landscape hydrology, can significantly affect freshwater-ice phenologies. Hence, through modifications of terrestrial hydrology, climate also plays an indirect role in affecting freshwater-ice phenologies.

The longest-term records of freshwater ice changes in the Arctic have been derived from paleolimnological analyses. Remote Arctic lakes have the greatest potential as natural monitors and recorders of past variation in ice cover. Over past millennia, the Arctic has experienced appreciable change to lake and river networks brought about by changes in other cryospheric components, including wide-scale glacier recessions and thawing permafrost. Paleo-historical analyses of lakes from selected sources around the circumpolar Arctic indicate that proxies of lake primary production remained low throughout the middle and late Holocene, in agreement with cold prevailing conditions and prolonged ice cover. Pronounced increases in whole-lake productivity, however, occurred during the warm period of the Holocene Thermal Maximum, consistent with decreased ice cover and its influences on

in-lake dynamics. Ice-cover duration then steadily increased in concert with Neoglacial cooling but was interrupted during the Medieval Warm Period (MWP), when it became equally short or shorter than today. Longer periods of ice cover returned during the Little Ice Age (LIA) when Arctic lakes became less productive than during the MWP – the dominant control on productivity being the duration of the ice-free season. Paleolimnological evidence from some Arctic lakes suggests that longer ice-free seasons have been experienced at various times since the beginning of the 19th century. Additional evidence of accelerated lake ice melt comes from lakes that had been perennially ice-covered or characterized by extended periods of ice cover. It has been inferred from some records that many Arctic lakes may have crossed an important ecological threshold as a result of recent warming.

Based on observational records of freshwater ice, numerous trend analyses have been completed, mainly focused on relatively simple characteristics such as the timing of autumn freeze-up and spring break-up, ice-cover duration, and ice thickness. A compilation of long-term records across the Northern Hemisphere for the period 1846 to 1995 indicates that freeze-up has become later by an average of 6.3 days per 100 years and break-up has become earlier by an average of 5.8 days per 100 years, resulting in an average reduction in ice duration of 12.1 days per 100 years. Only one site, however, was located north of the Arctic Circle, reflecting the lack of high-latitude, long-term observation sites. Subsequent analysis of a smaller set of lakes around the Northern Hemisphere (again, non-Arctic) with records extending to 2004/05 indicates that the average rate of change in both events was noted to increase from +6.3 to +10.7 days per 100 years for freeze-up and -5.8 to -8.8 days per 100 years for break-up, thereby further reducing average ice duration by 12.1 to 19.5 days per 100 years.

Many shorter-term regional studies have also been conducted, but they exhibit appreciable spatial and interdecadal variability. Most trends toward shorter freshwater-ice duration over much of the circumpolar North closely correspond to increasing air temperature trends and timing of the 0 °C isotherm. Broad spatial patterns in ice trends have also been linked to major atmospheric circulation patterns, different phases of which can cause contrasting ice conditions across individual continents and between opposite sides of the circumpolar North.

Some important south-north contrasts have also been identified in freshwater-ice trends. Examples from Finland and Sweden show greater sensitivity to warming at the more temperate latitudes although contrasting latitudinal results have been noted for south-north regions of Canada. The degree to which this reflects the effects of either more recent or higher latitude warming or a combination of both is unclear. Comprehensive, large-scale records of river- and lake-ice thickness are rare. One dataset compiled for Canada over the past 50 years does not reveal any obvious trends over the latter part of the 20th century. However, when comparing the past two decades to the previous 30-year period, reductions in maximum ice thickness have been observed on nearly all rivers and lakes within Arctic Russia. Overall, explaining the reasons for any of these regional contrasts requires further investigation into regional climatic differences and potential incompatibilities of different observational methods.

Most degree-day projections of future freshwater-ice regimes indicate a continued reduction in freshwater-ice duration in all northern regions. However, empirical relationships between freshwater-ice dates and air-temperature indices may not be reliable under future climatic conditions. Few future projections have been made using global or regional climate models, one analysis of lakes between 40° and 75° N for the period 2040 to 2079 projects an expansion of the summer stratification period: 5 to 20 days earlier freeze-up, 10 to 30 days earlier break-up, and an overall decrease in lake-ice duration of about 15 to 50 days. Maximum lake-ice thickness was also projected to decrease by 10 to 50 cm. Owing to the projected increase in winter snowfall, high-latitude regions are likely to develop increased surface white ice, especially as the ice cover also thins.

Few attempts have been made to project future changes in river-ice cover; however, projected decreases in south-north gradients in air temperature suggest that the severity of break-up and related ice-jam flooding may be reduced on some large, northward-flowing rivers. This would have major implications for northern infrastructure and riparian ecosystems. Changes in the magnitude of the spring snowmelt, however, will mitigate the effect of changing air-temperature gradients on break-up conditions. Location and severity of river-ice break-up could also be modified by changes in hydraulic gradients, particularly in coastal river deltas affected by rising sea level. With continued winter warming, dynamic ice jams caused by mid-winter break-ups will increasingly intrude into higher latitudes; there is already evidence of such events occurring in the sub-Arctic.

Decreases in lake-ice duration combined with higher temperatures during the increasingly long open-water period will lead to increased evaporation and lowering of lake levels. Some very shallow northern basins are likely to dry out and possibly become athalassic systems (inland saline lakes), unless there is a compensating increase in precipitation. Recent evidence suggests that this may have already happened to some ponds that have been permanent water bodies for millennia. By contrast, decreases in ice-cover thickness are likely to increase the unfrozen water volume and available under-ice habitat, particularly in those lakes that currently freeze to the bed. Where such thinning ice receives enhanced snow-loading from projected winter increases in precipitation, pulsing of lake water into downstream river channels will increase.

Aquatic ecology of lakes and rivers will be affected by an array of interacting processes resulting from changes to freshwater-ice regimes. In general, adjustments in the timing of freeze-up and break-up on lakes will affect a wide range of related biological aspects of seasonality. Some changes are likely to be gradual, others abrupt as systems pass critical ecological thresholds. Changes are also likely both to have positive and negative effects. Of particular concern is the change in river dynamics associated with ice break-up, which has been shown to be critical to the ecological health of river deltas.

Two socio-economic sectors that will be affected by changes in high-latitude freshwater-ice regimes are transportation and hydroelectric energy production. Changes in ice regimes will reduce the capacity for transport on ice roads that are critical to the resupply of remote communities and mining centers, which cannot use air access for the transport of heavy loads. For Northerners with a traditional subsistence-based lifestyle, ice-based travel may become increasingly hazardous and reduce the

ability to undertake some traditional harvesting methods. As the ice cover thins and the season is reduced, initial adaptation measures for the continued use of major ice roads could include modifications to ice-road construction techniques or transport schedules. However, continued warming will preclude ice roads as a major component of northern transport, and will necessitate the development of alternative forms of transportation, such as land-based road or rail networks, the capital costs for which are likely to be significant. Hydroelectric operations will both benefit and be challenged by changes in ice conditions that affect the rivers in which they operate and provide regulation. Monitoring and mitigating such problems will be a particular issue for hydroelectric power producers with remote facilities. The importance of river ice on hydroelectric operations may also be indirectly affected by future energy adaptations.

To facilitate comparisons of river- and lake-ice observations from around the circumpolar latitudes, there is a need for an international circumpolar effort to assemble and compile a comprehensive archive of existing information and the adoption of standardized methods of *in situ* observation. Moreover, a special focus should be placed on adopting remote sensing approaches to augment the *in situ* observation networks. This would require some form of international collaborative effort, one that could perhaps be undertaken by an international agency such as the World Meteorological Organization. Once the archive is established, a time series of spatial trends in ice phenologies should be conducted and links made to controlling trends and patterns in climate.

Fully assessing how climate has and will affect river-ice processes can only be accomplished by developing more advanced ice break-up models that consider future combined changes to landscape hydrology, in-stream hydraulics, and ice mechanics. While advancements are being made in modeling changes in lake ice, more validation efforts are required across a range of hydro-climatic regimes and lake sizes, and modeling needs to be expanded to include related effects on lentic (still water) and lotic (moving water) ecosystems. Model validation will also need to be undertaken, especially to help identify key non-linear and/or step changes.

Direct and indirect effects of changes in freshwater ice regimes will both have cascading impacts on socio-economic systems. The suitability of adaptation options can only be properly assessed through a broad range of cost-benefit analyses and additional socio-economic modeling, which also take into account cultural values held by Northern residents. Given the importance of many ice-affected socio-economic sectors, key locations of such activities should be considered in the selection of long-term observing and validation sites for lake and river ice. This is likely to maximize the socio-economic benefits of conducting future freshwater ice and climate change research in the Arctic.

6.1. Introduction

- Lake and river ice are interwoven into the terrestrial landscape through the major freshwater flow and storage networks and as a result have enormous significance for the physical, ecological and socio-economic systems within the Arctic.

- Freshwater ice plays an influential role in all terrestrial water storage and flow networks in the Arctic, although the hydrological influence on northern lake- and river-ice regimes originates well outside the Arctic, such as via the headwaters of the large northward-flowing rivers.
- River ice is the source of major hydrological extremes on rivers in cold regions, producing annual peak water levels that frequently exceed those under open-water conditions even though at much lower discharge.
- The Arctic contains a variety of types of ice-covered lakes, the genesis and evolution of which are largely dependent on other components of the cryosphere.
- Northern lakes tend to be most abundant in glaciated, permafrost peatlands where they can occupy a significant part of the terrestrial landscape.

6.1.1. Objectives, methodology and structure

The overall objective of this chapter is to evaluate the effects of climate on lake- and river-ice regimes in the Arctic, as well as the effects and implications of changes in these regimes for the related physical, ecological and socio-economic systems. For this report, the geographical boundary of the Arctic has been liberally defined to ensure that material from more broadly defined circumpolar northern environments (which have high relevance to Arctic conditions) is included. Having a broader geographical focus is particularly important for this chapter because many of the ice-covered flow systems entering the Arctic originate at latitudes well to the south of the Arctic Circle.

This report generally focuses on literature published since, or not covered by, the Arctic Climate Impact Assessment (ACIA, 2005). Although some aspects of lake and river ice were addressed by ACIA (e.g., Walsh et al., 2005; Wrona et al., 2005) and in assessments by the Intergovernmental Panel on Climate Change (IPCC) (e.g., Fitzharris et al., 1995; Anisimov et al., 2001, 2007), there has never been a comprehensive international treatment focused primarily on these two cryospheric components. The present review attempts to fill this gap and at the same time advance understanding of how lake- and river-ice regimes have changed and are projected to change under altered climatic regimes. Given the more substantial treatment of lake and river ice in the present report, in addition to the new post-ACIA material included here, a substantial amount of literature that predates the ACIA report on subjects that were previously missed or only given cursory attention is also included. Such subjects cover not only the physical characteristics of lake and river ice and their association with climate, but also a suite of related effects, particularly those with ecological and socio-economic implications. In addition, and where possible, information about potential adaptation options is also included.

The remainder of Section 6.1 contains background material to place in context the importance of change in freshwater ice regimes in the Arctic. This includes a brief review of the physical nature (Section 6.1.2), geographical extent (Section 6.1.3), and socio-economic importance (Section 6.1.4) of lake and river ice in the circumpolar North. Subsequent sections of the chapter address: the sources of information about lake and river ice; the role of lake and river ice in the climate system;

how lake- and river-ice regimes have changed historically and are projected to change in the future; the major future effects of changes in lake- and river-ice regimes on the physical, ecological, and socio-economic systems of the Arctic as well as potential adaptation options; and the major uncertainties and need for future research.

6.1.2. Physical description of lake and river ice

Ice-covered freshwater ecosystems are dominant features of the terrestrial environment of the near-polar latitudes. This section briefly reviews the characteristics of freeze-up, growth, and break-up of lake and river ice at high latitudes. For more details see the reviews by Adams (1981), Ashton (1986), Beltaos (1995a, 2008a), and Prowse (2005), as well as later sections of this chapter.

Where open-water conditions prevail during the summer months, an ice cover will first begin to form along the margins of lakes and rivers as the water column cools from net energy losses to the atmosphere. For lakes and rivers, the efficiency of autumn cooling depends on surface area to volume ratios. Thus, large shallow lakes and rivers cool more rapidly than their small

deep counterparts. Under calm conditions on lakes, a stable ice cover will eventually extend over the entire water surface and, with additional heat loss, begin to grow vertically downward, forming relatively transparent (typically referred to as ‘black’, ‘blue’, or ‘congelation’) ice. The rate of ice growth per unit of heat loss will decrease as the ice thickens and progressively insulates the underlying water column from the atmosphere.

In contrast to lakes, ice forms under much more dynamic conditions on rivers. Although large sheets of ice may develop on large, slow-moving rivers, the more common progression to freeze-up involves the formation of frazil ice, which begins as microscopic ice particles within the turbulent flow and evolves to various surface forms (such as frazil slush and pans) as the ice continues to grow and accrete. Transported downstream, these floating pans will eventually reach a sufficiently high surface concentration that they will bridge across and constrict a river cross-section (Figure 6.1a). Other incoming ice will then accumulate behind such ice and cause freeze-up to advance upstream. Depending on flow velocities and the strength of the accumulating ice, the initial ice cover may collapse, shove downstream, and thicken until it has sufficient internal strength to resist the application of forces from upstream. As in the




Figure 6.1. Various stages of river-ice development: (a) a schematic illustration of dynamic ice formation on rivers leading to freeze-up (water levels decrease downstream of the ice accumulation and increase upstream with ‘backwater’ storage); (b) backflow from the adjacent river channel during break-up feeding into a connected ice-covered lake; (c) a rapidly advancing river ice break-up front; and (d) a schematic illustration of a dynamic break-up front showing the rapid transition in water temperature, enhanced thickness of break-up accumulation, and elevated backwater, which can produce flooding. Modified from Prowse (2000).

case of lakes, subsequent ice growth will then largely occur by downward vertical growth.

Growth of lake and river ice continues throughout the winter as heat is progressively lost from the water column. Depending on the severity of the winter and the depth of the water body, some lakes and rivers within the Arctic will totally freeze to the bed, thereby acting as a barrier to water flow and related aquatic biota. By contrast, some Arctic rivers can have sections that remain open all winter largely due to strong turbulence or local heat sources, such as from groundwater. These are the freshwater equivalent of marine 'polynya'.

Ice growth may also be influenced by surface snow accumulation, which can act as an additional surface insulator and hence slow ice growth. It can, however, also promote the growth of surface ice through the formation of 'snow', 'white', or 'slush' ice. This occurs when sufficient snow accumulates on the ice surface to depress the existing ice cover below its hydrostatic water level, thereby flooding or 'slushing' some of the surface snow. Subsequent refreezing of this slushed snow leads to white-ice formation, which can be rapid compared to the deeper growth of further black ice, because it is more directly exposed to atmospheric cooling. White ice tends not to be a major feature of Arctic conditions and is more prevalent at temperate latitudes because snow loads are, for the most part, relatively small. The exception is where snow accumulates early in the season when the ice cover is relatively thin. White ice (as noted in Section 6.3.2.1.), is an important feature of lake- and river-ice covers because of its strong effect on ice-surface and water-column radiation regimes.

Icings (also known in German as 'aufeis' for 'ice on top' or 'naled' in Russian) are another form of freshwater ice that forms in river channels and which is similar in structure to the previously described white ice. In general, icings are surficial accumulations formed by water flowing onto the surface of an ice cover or ground, usually as a result of some localized flow resistance in a channel that forces water to the surface or, in the case of smaller rivers and streams, from groundwater seepage (e.g., van Everdingen, 1990). They can accumulate as a widespread sheet of ice or as a localized mound depending on the rate of flow versus surface freezing. In cases where the process continues throughout the winter and where an icing deposit may be fed by a number of seepage points, entire channels and even floodplains can be coated to thicknesses several times the depth of the open-water channel or the thickness of ice that would occur from normal freezing of the underlying flow. Some icings in Russia are estimated to be hundreds of kilometres long, 0.5 to 1.0 m thick, and more than 1000 m wide (e.g., Sokolov, 1986; Sokolov et al., 1987). In terms of icings formed by groundwater seepage, the total volume contained in Russian Arctic river basins alone is estimated at 100 km³ (Sokolov, 1986). Large icing accumulations can pose a flood hazard, especially where they plug narrow flow channels, such as through culverts, or where their mass decreases the flow until it overtops banks (Prowse, 2005). In a somewhat similar fashion, large quantities of frazil ice may accumulate to form a potentially dangerous type of ice jam, the 'hanging dam' that can also lead to enhanced flooding in the spring (Ashton, 1986). Typically, however, most spring flooding occurs as the result of break-up of floating ice covers.

As with freeze-up, the break-up of freshwater ice tends to

be more dramatic on rivers than on lakes (Figure 6.1). Both ice covers go through a pre-breakup period of ablation: first losing surface layers of snow, then ice-surface melting, and in rivers, accelerated thinning of the ice bottom as flow velocities increase. At very high latitudes where the ice ablation season is very short compared to the season for ice growth, freshwater ice on lakes may exist in a perennial form, developing only moats of summer meltwater. Freshwater ice can experience significant reductions in mechanical strength brought about by the internal absorption of solar radiation, particularly during the spring as incoming radiation seasonally increases and the highly reflective snow layers are ablated (e.g., Hicks et al., 2008). This can be important to the dynamics of break-up on rivers, which typically generate the most important hydrological event of the year (see Section 6.5.1.1). Water levels during spring break-up often far exceed those possible under open-water conditions at equivalent levels of discharge, as shown in Figure 6.2a for a station on a major tributary of the Mackenzie River (de Rham et al., 2008a). For the entire Mackenzie basin, almost half (13 of 28) of the hydrometric stations were found to have annual peak water-level events occurring exclusively under ice break-up conditions. As illustrated in Figure 6.2b, latitude was not found to be a major controlling factor, and other physical influences, such as elevation and slope, seem important. However, even for sites dominated by open water, ice conditions were found to be important because they can significantly elevate water levels during the spring break-up period. For example, as illustrated in a dimensionless stage versus discharge plot of all station types (Figure 6.2c), a spring break-up flow (Q_i) of only 10% of the open-water flow (Q_o) produces a nominal water depth of at least 50% of that for open-water conditions. Within the totally ice-dominated regime of the curve, a flow equivalent to only 25% of the open-water discharge will produce an equivalent nominal water depth during spring break-up. At the extreme end, an equivalent open-water discharge will produce an approximate 50% increase in nominal water depth during the spring break-up event. Such a curve exemplifies the importance of river ice in the generation of extreme high-stage events on northern rivers. As detailed in later sections, such events can be detrimental to the built environment but are also crucial to the ecosystem health of many Arctic aquatic environments, particularly riparian zones and river deltas.

6.1.3. Spatial extent

Unlike the other major global cryospheric components that either blanket large expanses (e.g., snow, permafrost, and sea ice) or are concentrated in large volumes in specific locations (e.g., glaciers and ice sheets), lake and river ice are interwoven into the terrestrial landscape through the major freshwater flow and storage networks. As such, freshwater ice has enormous significance to a variety of physical, ecological and socio-economic systems. In discussing the areal extent and volume of Arctic freshwater ice, it is important to note that the hydrological influence of this cryospheric component extends well outside the Arctic. For example, the major northward-flowing rivers of North America (Mackenzie) and Russia (Lena, Ob, Yenisey) have their headwaters in more temperate latitudes, and ice-related effects in such locations have the potential to influence downstream Arctic environments. In the case of river ice, Bennett and Prowse (2010) estimated that about 56% of





Figure 6.2. (a) Example of a return-period plot for a station on a major tributary to the Mackenzie River, Canada, in which break-up events (triangles) become increasingly important with longer return periods in producing annual high water levels as compared to open-water events (circles); (b) locations of ice (triangles), open-water (circles) and mixed (square) high-stage regimes in the Mackenzie River basin; and (c), for these regime classifications, the related dimensionless discharge (Q) versus water level (Y) curve for ice (i) and open-water (o) conditions. After de Rham et al. (2008a).

the northern-hemisphere river network, extending southward to 33° N in North America and 27° N in Eurasia, experiences conditions conducive to some ice formation (Figure 6.3). Moreover, cold conditions existing for half the year are found on river headwaters as far south as 50° and 27° N in these two continents, respectively. For large rivers in cold continental regions, such as the Lena and lower Mackenzie, or at high latitudes, such as the Yukon, ice conditions can persist for more than six months over the entire river length. By contrast, for rivers with more temperate headwaters, only sections (e.g., 73% of Ob River length) experience such long-term ice effects.

The spatial extents of temporal ice regimes in lakes are expected to be similar to those described for rivers. A large proportion of the above-noted regime classifications, however, are found outside the polar latitudes and, for the most part, lakes within these southern regions do not play a direct role in the Arctic. The exception would be lakes belonging to the hydrological networks draining to the Arctic, most notably including those such as Great Slave Lake, Lake Athabasca, Lake Baikal and Great Bear Lake, although the latter is partly found north of the Arctic Circle.

The Arctic contains a variety of lake types, their genesis and evolution largely dependent on components of the cryosphere, particularly glaciers, permafrost and river ice. Examples include post-glacial lakes remaining from the Pleistocene or that have evolved in the deglaciated environment, thermokarst lakes and ponds, and rarer forms, including karst, meteoritic impact crater, stamukhi (Section 6.5.2.3), tectonic and volcanic lakes



(e.g., McNight et al., 2008; Pienitz et al., 2008). In the case of areas north of around 45° N, northern lakes tend to be most abundant in glaciated, permafrost peatlands (with 14.4 lakes per 1000 km²) and least abundant in unglaciated, permafrost-free terrain (with 1.2 lakes per 1000 km²) (Smith et al., 2007). Overall, thermokarst lakes and ponds represent the most abundant and productive aquatic ecosystems in the Arctic (Vincent et al., 2008b). They are most common in flat-lying regions underlain by fine-grained, ice-rich sediment (French, 2007), and are found extensively in the lowland regions of western and northern Alaska (Hinkel et al., 2005), Canada (Cote and Burn, 2002; Marsh et al., 2009) and Siberia, where they comprise about 90% of lakes in the permafrost zone (Walter et al., 2006). See Section 6.3.1 for further discussion about lake coverage in relation to climatic influences.

6.1.4. Physical, ecological and socio-economic importance

The Arctic Climatic Impact Assessment established freshwater ice cover as an important component of Arctic hydrology that influences many physical, chemical, and biological processes operating in lentic and lotic systems (Walsh et al., 2005; Wrona et al., 2005). Lake ice directly affects many limnological properties and processes, including solar radiation inputs and their spectral signature for photobiological and photochemical processes; ultraviolet radiation; air-water gas exchange; water-column heat budgets; stratification and under-ice mixing;




Figure 6.3. Air-temperature based isotherm delineations of river ice regimes. Source: Bennett and Prowse (2010).

biogeochemical dynamics; and the entrainment of terrestrial inputs, including contaminants (e.g., see review by Vincent et al., 2008b). River ice exerts a similar broad range of controls on lotic systems, including the productivity and diversity of instream and riparian habitat, carbon inputs, dissolved oxygen levels, sediment transport and river morphology, and hydrological extremes, such as winter low flows and floods (Prowse, 2001a,b; Prowse and Culp, 2008). Within the Arctic, lake and river ice also permit the seasonal development of a suite of private and public transportation routes linking northern communities, thereby providing an inexpensive way to resupply remote resource industries and ready access for supporting traditional subsistence-based lifestyles, which depend on these lentic and lotic ecosystems (Nuttall et al., 2005; Furgal and Prowse, 2008; Prowse et al., 2009a,b).

The largest economic costs of lake and river ice are associated with the dramatic ice and flooding that accompany dynamic freeze-up and break-up events. Many Arctic communities were established at the confluence of rivers or where rivers enter lakes, and these sites are known to be highly susceptible to ice-jam formation. For example, the relocation of the administrative center from Aklavik, Canada, in the center of the Mackenzie River Delta, to Inuvik, higher up on the eastern banks of the Delta, was conducted to avoid ice-induced flooding. Although there are no summary figures for the costs of ice-jam flooding in the Arctic, the annual cost for North America is approximately 280 million USD (converted to 2009 values from Carlson, 1989; Gerard and Davar, 1995) and, for a single event in eastern Russia, the cost exceeded 124 million USD (2001, converted to 2009 values from Brakenridge et al., 2001). Damage from ice action and flooding also poses major economic costs for in-channel uses of northern rivers including bridges, pipelines and drilling platforms, transportation, and hydroelectric power generation. For example, designing around river-ice effects has been estimated to translate

into losses of tens of millions of dollars per year for one northern hydroelectric power producer in Canada, further amounts also being spent just to monitor and mitigate ice problems (Burrell, 2008). In addition, there is the hazard to life associated with the risks of on-ice travel, ranging from commercial traffic on ice roads to the use of back-country lake- and river-ice networks for travel and access to traditional food sources by northern residents (e.g., Ford et al., 2008). More details on hydrological, ecological and socio-economic impacts are discussed in Section 6.5.

6.2. Sources of information

- Surface-based observations have provided much of the information regarding the response of lake and river ice to climate, the earliest long-term ice observations dating back to the 17th and 18th centuries.
- Over the past two decades, there appears to have been a significant decline in a number of ice observations, and there are fewer observations carried out at higher latitudes compared to more southerly locations.
- To extend the historical record, a number of other methods have been used, including isotopes, tree scars, and taxa buried in lake and pond sediments.
- For several years, remote sensing has been seen as the technology that would eventually supersede surface-based observations of river and lake ice, but this has not yet been realized in any circumpolar country.
- A majority of the historical trends about lake and river ice have been derived from surface-based observations. These are now in a state of decline, however, and remote-sensing approaches are emerging as an observational product that should increase the geographical range of coverage.

6.2.1. Surface-based observations

Surface-based observations have provided much of the information regarding the response of lake and river ice to climate. The earliest long-term ice observations on Arctic lakes and rivers date back to the 17th and 18th centuries. In Finland, for example, observations of ice cover break-up on the Tornionjoki River were initiated in 1693 (Kuusisto and Elo, 2000); in Sweden, on the Torneträsk River in 1700 and in Lake Mälaren in 1711; and in Russia, on the Neva River at the beginning of the 18th century. However, such long-term ice break-up records are available for a very limited number of sites. In general, most river- and lake-ice observational networks were established between the latter part of the 19th century and the beginning of the 20th century. During this period, regular observations were initiated on lakes and rivers of the United States, Canada, Russia, Scandinavia, and Western Europe, mostly under the responsibility of national hydrology and environmental agencies. The first observation programs involved the determination of basic lake- and river-ice regime characteristics (mainly dates of freeze-up or ice-on and break-up or ice-off). As the number of sites on the northern lakes and rivers of North America and Eurasia grew, the range of observed characteristics also increased. For example, dates of formation of first ice, complete freeze-over of the water body, initiation of ice melt, and when the water body becomes clear of ice also began to be recorded (Lenormand et al., 2002). Since the middle of the 20th century, national programs of ice thickness measurements have been carried out in most northern countries, some starting even earlier. In the former Soviet Union and in Canada, such measurements were initiated on rivers and lakes in the 1940s and 1950s, and were accompanied by measurements of the thickness of snow cover on ice (Vuglinsky and Gronskaia, 2006). In Finland, since the late 1970s, snow ice (white ice) thickness and snow thickness on ice have been measured in addition to the total thickness of the ice cover (Korhonen, 2006).

It is important to note that many countries use different methods of ice-regime observations. This relates especially to dates of ice formation, and to duration of freeze-up and break-up. For example, some countries document the initiation of break-up, while others register the date when the water body becomes completely ice-free. This is an important distinction when examining variability and trends in ice records from different sources, given that the entire break-up process can

last for up to four weeks at a single site (Prowse et al., 2007a). Therefore, one of the primary objectives for improving instrumental records of lake- and river-ice regimes should be to standardize methods for measuring basic ice characteristics used in different countries.

Ice observations are usually kept in national archives and sometimes, after having been generalized, are published in various reports. In the past century, the data were most commonly published in annual reference books. In addition to publications, national electronic hydrological and cryospheric databases containing ice observation data have been extensively developed over the past 20 to 25 years. The Global Lake and River Ice Phenology Database containing observations from many countries (until about 1996) is available through the National Snow and Ice Data Center (NSIDC) at the University of Colorado at Boulder, United States (Table 6.1) (Benson and Magnuson, 2007). This database contains freeze-up and break-up dates, as well as other ice-cover descriptive data for 748 lakes and rivers across the Northern Hemisphere. Of the 429 water bodies that have records longer than 19 years, 287 are in North America and 141 are in Eurasia; 170 have records longer than 50 years, and 28 have records longer than 100 years. A few have data prior to 1845. However, Table 6.1 shows that the number of stations decreases with latitude, particularly north of the Arctic Circle. Table 6.1 also includes those stations used by Magnuson et al. (2000) in an analysis of long-term records (see Section 6.4.2.1). In general, such data allow the analysis of broad spatial patterns and time series of freshwater-ice cover. The NSIDC has developed a web-based user interface that allows users to search the database and retrieve data according to various parameters. The interface includes a link to more general information about the lakes and rivers in the database (Benson and Magnuson, 2007).

In the near future (2012/13), surface-based river- and lake-ice thickness data will be available from the International Data Centre on the Hydrology of Lakes and Reservoirs (HYDROLARE), which is operated at the State Hydrological Institute (Russian Federation) under the auspices of the World Meteorological Organization (WMO). The objective of the center is the establishment, development, and regular updating of a global database on the hydrological regime of lakes and reservoirs, including river and lake ice data. The first tranche of data is expected to be received from WMO countries during 2010 for input to the database.

Table 6.1. Number of lake and river observation sites north of specified latitudes contained in the current Global Lake and River Ice Phenology Database (GLRIPD) and those used by Magnuson et al. (2000).

	Number of stations north of 50° N	Number of stations north of 55° N	Number of stations north of 60° N	Number of stations north of 66° N
GLRIPD sites				
Total number of sites	465	317	244	90
Sites with post-1996 data	0	0	0	0
Sites with post-1990 data	152	110	88	44
Sites with post-1980 data	353	257	213	73
Sites with post-1970 data	381	273	222	76
Long-term sites (over 150 years) used by Magnuson et al. (2000)	9	6	6	1

Surface-based observations were once the most important source of information regarding lake- and river-ice conditions. The declining state of these networks since the mid-1980s has led to serious geographical and temporal gaps for several lake and river ice parameters. For example, Figure 6.4 shows the precipitous decline evident during the latter part of the 20th century in observations recorded in Canadian, Russian, Swedish, and global databases. Although some of this decline is due to a reduction in the number of observing stations, some may also be due to a lack of reporting to national and international data centers. The two main reasons for the dramatic decline in the surface-based networks are the automation of meteorological stations near lake- and river-ice observation sites, and financial cutbacks (e.g., Lenormand et al., 2002). Another shortcoming of the databases is that they do not include ice-observation data (e.g., water level to bottom of ice-depth measurements, ice effects on water-level recordings and/or direct visual observations) that are routinely collected as part of national river hydrometric programs, and which can be excellent sources of information related to river-ice dynamics (see Section 6.5.1). Significant effort would be required to extract comparative information from the original archives (e.g., de Rham et al., 2008a; Goulding et al., 2009a; von de Wall et al., 2009).

Some attempts have been made to reverse this trend of declining observation programs. In Canada, for example, a number of ice-thickness monitoring sites have been re-established by the Canadian Ice Service (CIS) as a contribution to the International Polar Year (IPY). In addition, at least two volunteer observational networks have recently been established in North America: IceWatch in Canada (www.naturewatch.ca/english/icewatch) and the Lake Ice and Snow Observatory Network (ALISON) in Alaska (www.gi.alaska.edu/alison). Various surface air-temperature indices are often employed to link trends in freshwater ice to the corresponding climate (see Section 6.4.2.2). These indices (e.g., degree-day calculations) can also be used to estimate phenological dates of break-up and freeze-up. This is particularly useful in regions where direct ice observations are not available and surface-temperature measurements from existing meteorological stations are incorporated to assess historical trends and/or projected future changes to ice phenology over specified regions.

Isotopes have also been used to index changes in lake and river ice. For example, vertical sectioning of river-ice cores and analysis of their oxygen-hydrogen isotopes has been used to provide an indirect record of the source of varying flow contributions (e.g., from lake water, groundwater, or direct precipitation) occurring during the complete period of winter ice growth (e.g., Gibson and Prowse, 2002). Analyses of sediment deposition records in riparian environments (e.g., ox-bow lakes), using a combination of isotopic and related geochemical analyses, have been used to interpret historical (multi-century) records of flood and related ice-jam events (e.g., Wolfe et al., 2006). Ice-related flood events on lakes and rivers have also been determined using ice-induced scars on trees (e.g., Bégin, 2000, 2001; Prowse and Culp, 2008). However, most of the isotopic and ice-scar data analyses have typically been conducted at single sites and at lower latitudes. Nevertheless, significant high-latitude work has been undertaken using changes in the taxa (i.e., siliceous




Figure 6.4. Historical evolution of the number of lake-ice and river-ice observation sites recorded in various databases. Data are from the Global Lake and River Ice Phenology Database (GLRIPD) (Benson and Magnuson, 2007); the Canadian Ice Database (CID) (Lenormand et al., 2002); the Swedish Meteorological and Hydrological Institute (SMHI, provided by G. Weyhenmeyer); and the Russian State Hydrological Institute (provided by V. Vuglinsky; note the scale difference for this latter data set).

algal and chitinous invertebrate remains) buried in lake and pond sediments to obtain long-term records of warming trends and historical changes in freshwater-ice cover. The strength of such inferences is based on the understanding that changes in ice-cover duration and, hence, longer growing seasons increase primary production and cause taxonomic shifts in algal and invertebrate communities. Since most of the analyses have been conducted on ponds and relatively shallow lakes, caution must be used in extrapolating results to larger lake systems. A synthesis of relevant paleo-information is provided in Section 6.4.1 to give a paleo-historical background to changes in Arctic freshwater-ice conditions.

6.2.2. Remote sensing

For several years, remote sensing has been seen as the technology that would eventually supersede surface-based observations of river and lake ice, at least for simple ice phenology and possibly for ice dynamics (e.g., break-up floods). Unfortunately, this transition has not yet been realized in any circumpolar country. However, considerable research has focused on evaluating the ability of different satellite remote-sensing datasets and related methods to derive freshwater-ice parameters on Arctic lakes and rivers. For example, the historical satellite archive from the Advanced Very High Resolution Radiometer (AVHRR) optical sensor has recently been used to assess trends in lake-ice phenology over 36 large lakes in Canada (six located in the Arctic; see Section 6.4.2.1) from 1984 to 2004 (Latifovic and Pouliot, 2007). Some studies have also shown the potential of AVHRR and the Moderate Resolution Imaging Spectroradiometer (MODIS) to monitor break-up dates on very large northern-hemisphere rivers (e.g., Pavelsky and Smith, 2004). The spatial resolution of most satellite sensors providing high (daily) temporal resolution has simply been too coarse for monitoring the majority of river-ice parameters. Another problem with optical data is that they suffer from atmospheric interference (e.g., clouds) and polar darkness, which limits ice-phenology parameter retrievals during crucial

times (especially during freeze-up).

The microwave region of the electromagnetic spectrum is perhaps more useful for the monitoring and study of lake-ice phenological processes because of its all-weather and polar-darkness imaging capability. For example, passive microwave data from the Defense Meteorological Satellite Program Special Sensor Microwave/Imager (SSM/I) 85 GHz brightness temperature channel has been used to detect spatial phenology changes over Great Slave Lake, Northwest Territories, Canada (Schertzer et al., 2003). However, the 85 GHz channel is susceptible to considerable atmospheric interference, and its spatial resolution is still relatively coarse (12.5 km), which can lead to large brightness temperature differences between water and land (Cavaliere et al., 1999). Nonetheless, it has been shown that ice regimes in the main section of lakes (i.e., away from shore that can contaminate the coarse-resolution pixels) can be monitored when passive microwave is used synergistically with radar altimeter data.

Kouraev et al. (2007a) developed an approach to monitor ice cover on Lake Baikal by combining satellite altimetry (TOPEX/Poseidon, Jason-1, ENVISAT, and Geosat Follow-On) with SSM/I data. The new approach allowed a reconstruction of the ice regime in the southern as well as the central and northern parts of the lake from 1992 to 2004 (Kouraev et al., 2007b). Kouraev et al. (2008) further demonstrated that the combination of passive and active microwave (altimeter) data could be extended to other large lakes and interior seas of the Eurasian continent – the Caspian and Aral Seas, Lake Ladoga and Lake Onega – and possibly to the large northern lakes of Canada, such as Great Slave Lake and Great Bear Lake.

More recently, Howell et al. (2009) developed algorithms to detect melt onset, water clear of ice, and freeze onset dates on Great Bear Lake and Great Slave Lake, Canada, using moderate resolution (~4 km) spaceborne scatterometer data from QuikSCAT (Quick Scatterometer satellite). Some researchers have also used high-resolution (30 m) ERS-1 or ERS-2 (European Remote Sensing satellite) synthetic aperture radar (SAR) imagery to monitor ice formation, the thickening of ice cover, and freezing to the bottom of shallow (e.g., less than ~2 m) Arctic and sub-Arctic lakes in Alaska (Jeffries et al., 1994; Morris et al., 1995) and northern Manitoba, Canada (Duguay et al., 1999; Duguay and Lafleur, 2003). Duguay et al. (2002) utilized RADARSAT-1 SAR imagery for monitoring ice growth and decay and related processes of shallow sub-Arctic (tundra and forest) lakes in northern Manitoba, Canada. Nolan et al. (2003) used ERS-2 and RADARSAT-1 data, together with a numerical ice model, to gain an understanding of the ice dynamics on Lake El'gygytyn, northeastern Siberia. The value of higher resolution RADARSAT imagery (8 m) has also been demonstrated for the mapping of river-ice types (Weber et al., 2003).

Ice thickness has been estimated with some success through the synergistic use of optical and SAR data on shallow Arctic lakes (e.g., Duguay and Lafleur, 2003). Coarse resolution Advanced Microwave Scanning Radiometer - Earth Observing System (AMSR-E) data acquired in the 6 to 18 GHz frequency range have also been shown to be suitable for estimating ice thickness on very large lakes (Kang et al., 2010). In addition, recent work has demonstrated the possibility of determining total ice thickness of snow and ice on medium to large lakes from

snow-surface elevation data acquired by spaceborne radar and laser altimeters (e.g., Kouraev et al., 2008). However, due to the failure of one of three lasers of the Geoscience Laser Altimeter System (GLAS) instrument shortly after the launch of the Ice Cloud and Land Elevation Satellite (ICESat), measurements are very limited temporally. The replacement ICESat-2, scheduled for launch in 2015, will provide an opportunity to further explore the potential of laser altimetry for estimating snow and ice thickness on northern lakes.

Operational ice monitoring from large lakes is conducted by the Canadian Ice Service (CIS) and the National Oceanic and Atmospheric Administration (NOAA) National Environmental Satellite, Data, and Information Service (NESDIS) in the United States. The CIS began operational weekly monitoring of ice extent on large lakes in 1995 using NOAA AVHRR (1.1 km) and RADARSAT ScanSAR (100 m) imagery to meet the Canadian Meteorological Centre's needs for lake-ice coverage in numerical weather prediction models. The amount of ice on each lake (in tenths) is determined by visual inspection of AVHRR and RADARSAT imagery. The program started with 34 lakes (in 1995) and has now reached 136 lakes (mostly in Canada with a few in the United States). Using this dataset, it is possible to derive dates of complete freeze-over and when water is clear of ice with an accuracy of ± 1 week, a temporal resolution not sufficient for climate change studies. The accuracy of the information in the CIS lake-ice coverage database depends on the amount of cloud cover over a particular lake (NOAA AVHRR imagery is cloud dependent) and the frequency of RADARSAT coverage. In 1997, NESDIS started to generate a daily snow and ice product at a resolution of about 24 km with the Interactive Multisensor Snow and Ice Mapping System (IMS). The IMS incorporates a wide variety of satellite imagery (AVHRR, GOES, SSM/I, etc.) as well as derived mapped products (e.g., U.S. Air Force Snow and Ice Analysis) and surface observations. The coarse resolution of the 24-km product allowed mapping of ice extent on only the largest lakes of the Northern Hemisphere. Since February 2004, a 4-km resolution product has become available, which permits determination of ice extent on lakes of this resolution or greater on a daily basis.

Significant advances have taken place on the research front and in the development of operational products, and capabilities for ice monitoring of many lakes and rivers of the Arctic at high spatial (50 to 100 m) and temporal resolution (daily) are foreseen in the not too distant future. The Sentinel satellite missions of the European Space Agency (ESA, 2011 to 2012) and the RADARSAT constellation (2014 to 2016) of the Canadian Space Agency (CSA) will provide the technology needed to achieve the goals set by the Global Climate Observing System (GCOS) regarding the accuracy for determining freeze-up and break-up dates (± 1 to 2 days).

6.3. Role in the climate system

6.3.1. Effects on local climate and large-scale climatic feedbacks

- Lake and river ice need to be considered in climate modeling given the large fraction of the northern high-latitude, sub-Arctic and tundra landscape that they occupy.

- The degree to which the atmosphere is influenced depends on several factors including the magnitude, timing, location and duration of ice cover.
- A significant shortening of the freshwater ice duration period can affect local, regional, and even larger-scale climate over the Arctic.
- Ice-cover duration and, to a lesser degree, thickness have been shown to play roles in the annual energy and water balance of large Arctic river basins, such as the Mackenzie, Canada.

In the Arctic, the meteorological and climatological effects of freshwater ice within the terrestrial landscape are mostly confined to the local scale, with the greatest effects produced by ice cover on large lakes. The presence or absence of ice directly modifies atmospheric heating of lakes and rivers through changes in latent and sensible heat fluxes, absorption and reflection of short-wave radiation, and long-wave radiation emissivity of the surface. This in turn affects local climatic factors, primarily surface-air temperature, but also precipitation, evaporation, and low-level cloud cover. The degree to which the atmosphere is influenced depends on several factors including the magnitude, timing, location, and duration of ice cover (e.g., Rouse et al., 2005). Ice-covered freshwater bodies of various sizes represent a considerable fraction of the high-latitude, sub-Arctic and tundra landscape (see Section 6.1.3), and as such need to be considered in any type of climate modeling of Arctic terrestrial environments (e.g., Samuelsson et al., 2010). For example, the surface area of lakes in the Mackenzie River Basin of northwestern Canada is about 144 000 km² or 8% of the total area (Bussi eres, 2002), while in the northern Hudson Bay Lowlands, Bello and Smith (1990) estimated the lake coverage to be 41% of the landscape. Other high-latitude regions, such as Alaska, northern Scandinavia, and northern Russia, also exhibit a substantial areal coverage by lakes (e.g., Ljungemyr et al., 1996). The lateral dimensions of large rivers can also approach those of small lakes, and the scale of their climatic impacts is likely to be comparable. The greatest effects are expected for the deltas of large river systems in which the network of tributary channels and interconnected ponds and lakes encompasses a vast region of the landscape (see Section 6.5.2.3). As a result, a significant shortening of the freshwater-ice duration period can have profound impacts on local, regional, and even large-scale climate over the Arctic (e.g., Rouse et al., 2005).

Climatic impacts from terrestrial water bodies are fairly well documented during open-water periods, but less is known regarding ice-covered conditions, with most information focusing on transitions in spring and autumn. During spring, an ice-covered water body has a significantly different energy balance to that of snow-free land, with nearshore zones usually characterized by cooler spring air temperatures. Studies have shown that the inclusion of lakes in numerical weather-prediction models can produce a springtime cooling of near-surface air temperature of up to several degrees Celsius in the vicinity of lakes when they are ice-covered (e.g., Mackay et al., 2009). For large river deltas, ice break-up has been determined as the critical event impacting the thermal regime of local to regional climate. Arrival of the break-up front

causes a rapid clearing of snow and ice leading to a dramatic reduction in surface albedo. During a dynamic break-up, local air temperatures have been found to rise rapidly, by as much as 5 °C, whereas thermal break-up (with less flooding) had minimal effects on surface temperature. Biological impacts can also be highly visible, since slight increases in radiative warming could raise air temperatures above a critical threshold value that stimulates budding and early-spring plant growth (Prowse, 2000). These processes are scale dependent and, therefore, ecological impacts resulting from changes in ice cover on small rivers and streams would be primarily restricted to very local effects (e.g., to the riparian zone; Prowse and Gridley, 1993).

Regional to large-scale climatic feedbacks from freshwater bodies are mainly associated with big lakes and, to some degree, large river-delta systems. With regard to the former, there have only been a few modeling and observational studies that have examined the impact of lakes on regional to large-scale climate. As expected, results revealed a significant enhancement of latent heat flux and suppression of sensible heat flux when freshwater lakes are present (e.g., Nagarajan et al., 2004; Rouse et al., 2005). One of the most comprehensive analyses related to freshwater-climate links in the Arctic was undertaken in the Mackenzie GEWEX (Global Energy and Water Cycle Experiment) Study that comprised a series of large-scale hydrological and related atmospheric and land-atmosphere studies of the Mackenzie River Basin. Results demonstrated that ice-cover duration and, to a lesser degree, ice thickness play significant roles in the annual energy and water balance of large river basins such as the Mackenzie River Basin. This is mainly because ice cover prohibits evaporative exchange with the atmosphere for several months of the year. For large lakes, the evaporative and sensible heat fluxes reach their maxima during autumn and early winter mainly due to the greater frequency of cold air masses over relatively warm lake surfaces (Rouse et al., 2003). Such heat fluxes remain large as long as there is open water. For example, significant evaporation from Great Slave Lake occurs over a period ranging from six to seven months (Blanken et al., 2007). Moisture from this evaporation can be an important source for subsequent precipitation within the Mackenzie River Basin (e.g., Szeto, 2002). Unfortunately, precipitation measurements are typically so sparse that the contribution of lakes cannot be quantified from direct measurements. Nonetheless, large-lake evaporation in autumn and early winter is known to trigger frequent downwind snow squalls, as seen from passive microwave satellite images of the Great Slave Lake and Great Bear Lake region (i.e., similar to the Canadian Laurentian Great Lakes). However, no substantive studies have yet been pursued on this feature (Walker et al., 2000). It should be noted that many of the findings from the Mackenzie GEWEX Study are also applicable to other high-latitude regions of the world (Rouse et al., 2007).

Samuelsson et al. (2010) used a numerical regional climate model to determine how the presence of lakes affected regional to large-scale climate over Europe. Results showed that the incorporation of the observed lake network into the model resulted in a warming effect on European climate for all periods except mid-winter to mid-spring when ice cover was present. The warming was particularly pronounced during autumn and winter, and over regions that have a high concentration of lakes. Locally, the presence of lakes enhanced convective

precipitation by 20% to 40% in late summer and early autumn; however, this precipitation was reduced by more than 70% during early summer.

High-latitude lakes are more prone to be affected by climate variability and change than the surrounding landscapes, mainly due to their strong absorption of solar radiation during the ice-free period. Therefore, shorter ice duration will act to increase annual net radiation, heat storage, and evaporative and sensible heat fluxes (Rouse et al., 2007). Such increases in net radiation will add to the heat content of the lake, as was shown for Great Slave Lake in the Mackenzie River Basin during the unusually warm year of 1998 when the ice-free period was about 40 days longer than normal (Schertzer et al., 2007). The larger heat storage will subsequently increase open-water evaporation and the overall sensible heat flux, particularly during autumn and early winter (for large lakes), which can then augment lake-effect snowfall by depositing more snow on downwind terrestrial locations.

6.3.2. Climatic controls

- In addition to the various climatic variables that control surface heat fluxes, freshwater-ice processes and phenologies are also controlled by landscape hydrology.
- Through modifications of terrestrial hydrology, climate also plays an indirect role in affecting freshwater-ice phenologies.
- In the case of lakes, runoff inputs directly influence freeze-up and break-up through the direct addition of heat, the modification of surface albedo, and/or the creation of intra-lake currents and mixing.
- The entire ice regime of rivers, including phenology, ice-cover thickness, and ice-jamming processes, is strongly influenced by hydrological variables.

6.3.2.1. Direct controls

The formation, growth, decay, and break-up processes of the ice cover differ markedly between lakes and rivers, but all are influenced by similar climatic variables that control surface heat fluxes, such as solar radiation, air temperature, humidity, precipitation, wind speed, and cloud cover, etc. (Ashton, 1986; Walsh et al., 2005). River and lake size and depth have a strong effect on the timing of freeze-up, owing to the heat content of large water bodies. Freeze-up dates can vary by as much as two months between small and large lakes in the same region; however, size has no similar effect on break-up, which may only vary by about two weeks (Rouse et al., 2007). Air-temperature indices are often used for approximate prediction of ice-cover phenology and thickness (Borshch et al., 2001; Vuglinsky and Gronskaia, 2006), but the resulting correlations are site-specific as they tacitly assume that all other relevant climatic variables are either constant or singly related to air temperature (Beltaos and Prowse, 2009). Physically based process models quantify the synergistic effects of the relevant climatic variables, but may require specialized input data that are not always available (Duguay et al., 2003; Liu et al., 2006; Saloranta and Andersen, 2007). Prediction of break-up timing is hampered by knowledge gaps with respect to climatic effects on the composition of the ice cover, which partly controls internal decay by absorption

of solar radiation (e.g., Hicks et al., 2008). Not only does ice composition differ between rivers and lakes, it can also change during the ice season, thus altering absorption characteristics (Walsh et al., 2005). A key mechanism in promoting change in cover composition is the winter loading of snowfall; if sufficient snow accumulates to depress the ice cover below the hydrostatic water level, surface flooding (or 'slushing') will result and with subsequent refreezing will become highly reflective surface layers of white ice (see Section 6.1.3).

6.3.2.2. Indirect controls

6.3.2.2.1. Lake ice

In addition to direct atmospheric budget controls of lake ice, mechanical action of wind and landscape hydrology can also significantly affect ice timing and duration. Inflow from streams or land runoff can influence break-up, affecting the phenology by adding heat inputs, creating currents within the lake, or both. In the case of small lakes, for example, the spreading of spring meltwater on the surface can play an important role in decreasing surface albedo and, hence, can indirectly advance the radiation decay of the ice cover (Woo and Heron, 1989; Grenfell and Perovich, 2004). For large lakes, such processes are primarily limited to the margins where meltwater moats typically develop at the early stages of break-up or by the inflow of warmer water from rivers, which accelerates the break-up process. For example, MODIS satellite imagery over Great Slave Lake from 2004 to 2006 (Figure 6.5) shows a crack forming in the ice cover during break-up near the large inflow from the Slave River. The largest indirect hydrological control relates to the volume and temperature of surface water and groundwater as these control the open-water heat budgets of lakes. As noted in Section 6.3.2, the heat storage of lakes greatly affects the timing of autumn freeze-up (e.g., Blanken et al., 2007). The duration of the ice-free period of summer warming is particularly important for stratified lakes where an earlier start to the stratified season can significantly increase the period over which a lake warms, leading to a greater increase in mean summer lake temperatures than would be expected simply from summer air temperatures (Austin and Colman, 2007).

6.3.2.2.2. River ice

In rivers, the entire ice regime, including phenology, ice-cover thickness, and ice-jamming processes, is strongly influenced by hydrological variables, such as the flow regime and the base level, both of which are partly controlled by climate (Beltaos, 2008b; Beltaos and Burrell, 2008). For example, high autumn discharge tends to delay freeze-up, while high spring discharge tends to advance break-up and enhance the severity of ensuing ice jams and related flooding. The effects of discharge on river-ice processes arise from its controlling influence on flow hydrodynamics, including such variables as depth, velocity, erosional capacity, forces applied on the ice cover, and water surface slope. In terms of water surface slope, an additional influencing factor is the elevation of the water body into which a river may drain, such as another river, a lake, or the ocean. The effect of changes in the ocean is discussed in Section 6.5.1.1. Complexity is further amplified by antecedent conditions (freeze-up levels and ice-cover thickness) playing a significant




Figure 6.5. MODIS imagery from 2004 showing ice break-up on Great Slave Lake, with a crack and initial melt forming near the Slave River inflow. Numbers indicate Julian days. Source: Howell et al. (2009).

role in the timing and evolution of break-up events, which often generate extreme ice jams and floods. Although existing process-based modeling capability (Liu et al., 2006) can largely account for many direct and indirect climatic effects, breakup-related phenomena have not yet been adequately quantified (Beltaos, 2008c; see also Section 6.5.1.1).

6.4. Changes: past and future

6.4.1. Paleo-historical changes

- Arctic lakes act as natural recorders of past variation in ice cover because their biological activity is closely coupled to the physical properties of stratification and ice cover, and because their fossil record has been little disturbed by human activities.
- All proxies of lake primary production remained low throughout the middle and late Holocene, in agreement with cold prevailing conditions and prolonged ice cover. Pronounced increases in whole-lake productivity, however, occurred during the warm period of the Holocene Thermal Maximum, consistent with decreased ice cover and its influences on in-lake dynamics.
- Ice-cover duration became equally short or shorter than it is now during the Medieval Warm Period. Arctic lakes were also more productive during the Medieval Warm Period than in the subsequent Little Ice Age – the dominant control on productivity being the duration of the ice-free season.
- During the Little Ice Age, ice-cover duration lengthened and probably led to anoxic conditions in lake bottom waters in some parts of the Arctic.
- Since the beginning of the 19th century, some Arctic lakes have experienced longer ice-free seasons, or accelerated ice melt in the case of some that have been perennially ice-covered.

- Inferences from some Arctic lake records suggest that many lakes may have crossed an important ecological threshold as a result of recent warming.

To assess the significance of changes in modern properties of lake and river ice, it is essential to place recent observations in a longer-term context. However, long-term monitoring data about the freezing and thawing of Arctic lakes are scarce. Inferences into past freshwater changes can be made by examining samples that record environmental conditions in the paleolimnological record. Paleolimnological analyses can provide annual to millennial time series of the composition of lentic biological communities, biogeochemical processes, and changes in lake physical conditions, which can be used for analyses of climate effects on lakes (Battarbee et al., 2005). Detailed analysis of lake sediments can identify the mechanisms by which climate affects lakes, as well as how climatic variability may interact with other regulatory processes over timescales inaccessible by standard limnological approaches (Leavitt et al., 2009).

Remote Arctic lakes have high potential as natural monitors and recorders of past variation in ice cover because their biological activity is closely coupled to the physical properties of stratification and ice cover, and because their fossil record has been little disturbed by human activities. However, since most paleo-analyses have been conducted on ponds and relatively shallow lakes, the data must be used circumspectly to infer changes on larger lake systems. The following sections summarize evidence from proxy climate and paleolimnological data with regard to the nature and causes of past variability in Arctic climate and lake ice conditions over the Holocene interglacial period and the more recent Anthropocene period.

6.4.1.1. Holocene variability in lake ice conditions

Many physical, chemical, and biological changes occur in Arctic lakes that are either directly or indirectly affected by snow

and ice cover (see Section 6.5). Recently, attempts have been made to directly link changes in lake biological communities (mainly diatoms, which are important primary producers in Arctic lakes and preserve well in sediments) to the measured or empirically modeled duration of ice cover using extensive modern calibration datasets together with careful statistical analyses (Korhola, 2007). The central ecological argument behind the approach is that an extensive layer of ice and snow would dramatically affect limnological conditions, resulting in marked changes in biological communities (Douglas and Smol, 1999). In years with cold summers, with more extensive ice cover, diatoms from aerophilous (oxygen supplied) and shallow habitats will dominate. Conversely, during warmer years, there is less extensive ice cover and taxa characteristic of deeper-water substrates and planktonic habitats will increase in abundance relative to the shallow-water benthic taxa (Smol and Douglas, 2007a). Eventually, in deeper lakes, thermal stratification may also occur (or be prolonged) during the summer months, further altering the composition of the diatom communities. Increased stratification has been shown to favor small-celled diatoms with a high surface area to volume ratio (Rühland et al., 2008; Winder et al., 2009). Using a pan-European dataset of species abundance for 252 diatom taxa in 459 mountain and sub-Arctic lakes, Thompson et al. (2005) developed a transfer function to infer duration of ice cover based on different diatom assemblage species compositions. These are now being developed for application to lakes at higher latitudes.

In the absence of suitable transfer functions, less precise ice-cover reconstructions are commonly based on changes in species assemblage and the known ecological and life-history characteristics of the organisms. However, if ice and snow cover change in a lake, there should be changes not only in the relative frequencies of different taxa, but also in overall primary production in the lake. Moreover, the length of ice cover can also drive changes in key limnological variables, including nutrient levels, mixing regimes, gas exchange and, in poorly buffered sites, fluctuations in lake-water pH that can be inferred from biotic and abiotic proxies (Douglas and Smol, 1999). The importance of each of these factors is site-specific and varies over time; thus, multiple hypotheses explaining past changes in proxies are often warranted.

Numerous paleolimnological studies exist for Arctic lakes covering the entire Holocene, yet studies focusing explicitly on ice-cover duration are scarce and limited to small and shallow systems. Michelutti et al. (2007) used many paleolimnological techniques including reflectance spectroscopy and diatoms to infer past trends in primary production and lake-water pH from the sediments of a small lake on Baffin Island in the Canadian Arctic. Pronounced increases in whole-lake productivity and lake-water pH were noted during the warm periods of the Holocene Thermal Maximum (~10 000 to 8000 BP) and during the recent climatic warming, consistent with the hypothesis of decreased ice cover and its influences on in-lake dynamics, particularly dissolved inorganic carbon. All proxies of lake primary production remained low throughout the middle and late Holocene, in agreement with cold prevailing conditions and prolonged ice cover. However, maximum recent values of their reconstructed parameters were again either directly comparable to or exceeded values attained during the early Holocene. There are many examples of lakes on Baffin Island

that show similar developmental characteristics (see Wolfe and Smith, 2004).

Almost parallel development regarding ice-cover duration was observed by Cremer et al. (2004) in a weakly thermally stratified lake in the Ural Mountains of northern Russia. Using diatoms and a range of geochemical indices (e.g., total carbon, total organic carbon, total sulfur), they concluded that ice-free conditions prevailed in the lake during the Holocene Thermal Maximum and were characterized by high biological productivity and strong growth of planktonic diatoms. Since then, the duration of the open-water period gradually decreased in concert with Neoglacial cooling, followed by a return to conditions similar to those during the Holocene Thermal Maximum beginning a few hundred years ago.

More detailed studies have increasingly been conducted, some based on annually laminated sediment sequences, covering the past few millennia with a focus on finer-scale climate oscillations. Tomkins et al. (2009) combined the results from a varve (a layer of sediment deposited in a lake in a single year) chronology that included records of a novel sediment feature ('sedimentary pellets'), which they interpreted as an ice-cover indicator, to construct a 1000-year proxy record of ice-cover extent and dynamics on a perennially ice-covered, High Arctic lake on Ellesmere Island. Sedimentary pellet frequency from multiple sediment cores suggested that the most notable period of reduced ice cover was from about 1891 to present. Another period of ice-cover mobility was suggested from about 1582 to 1774, while persistent ice cover is inferred during the 1800s and prior to 1582. The proxy ice-cover record was found to correspond well with regional proxy temperature and paleoecological records, especially during the 1800s and 1900s.

Over approximately the past millennium, evidence indicates that lakes in the Arctic were more productive during the Medieval Warm Period and less productive during the subsequent cooler Little Ice Age – the dominant control on productivity being the duration of the open-water season. Tiljander et al. (2003) discovered a suite of organic-rich sediments from a varved lake in Finland with dates including the Medieval Warm Period (980 to 1250). During this time interval, less mineral material accumulated on the lake bottom than at any other time in the 3000-year sequence analyzed, suggesting a prolonged open-water period and negligible winter snow cover. In contrast, extremely thin varves and low sediment accumulation prevailed during the Little Ice Age in many lakes throughout the Arctic, suggesting an extensive ice cover and a short growing season (e.g., Lamoureux and Bradley, 1996; Hughen et al., 2000; Moore et al., 2001; Smith et al., 2004; Besonen et al., 2008; Bird et al., 2009). Prolonged ice cover also led to widespread anoxic conditions in lake bottom waters. For example, it has been reported that Lower Murray Lake in northern Ellesmere Island suffered widespread anoxic conditions from about 1700 to the mid-19th century, when the coldest episode of the late Holocene occurred in that region (Besonen et al., 2008).

6.4.1.2. Anthropocene variability in lake ice conditions

There are many examples of profound aquatic responses to recent Arctic warming. For example, Douglas et al. (1994)

applied modern paleolimnological techniques to study the environmental history of a series of ponds on Ellesmere Island in the Canadian High Arctic. Their sediment profile results showed that, following several millennia of relative ecological stability, episodes of nearly complete species turnover in diatom taxa occurred, beginning in the 19th century. The species changes detected showed a proliferation of littoral taxa, indicating more complex periphytic diatom communities, as well as increases in the percentages of moss epiphytes, all of which require a longer ice-free season to develop in the harsh Arctic environment.

Other paleolimnological studies, using similar procedures, have also documented pronounced ecosystem shifts in the circumpolar Arctic, based not only on diatoms but also on other taxa representing different levels in the food web (e.g., Korhola et al., 2002; Sorvari et al., 2002; Quinlan et al., 2005; Rühland and Smol, 2005; Solovieva et al., 2005; Michelutti et al., 2006). The critical controlling role of ice cover in producing such shifts is evident in the results of a comparative sedimentary study of two lakes from northern Ellesmere Island with nearly identical limnological features, but different local climate and, therefore, degree of ice coverage (Keatley et al., 2008). The lakes recorded strikingly different changes in diatom assemblage, with the ice-covered lake tracking little ecological change, whereas the less-shaded lake recorded changes in its recent sediments consistent with warming.

Further evidence of accelerated lake-ice melt comes from lakes that had been perennially ice-covered or characterized by

extended periods of ice cover. For example, in the rarely ice-free Sawtooth Lake situated in the Sawtooth Mountain Range of central Ellesmere Island, Perren et al. (2003) could not identify diatoms or chrysophyte cysts in sediment corresponding to the past 2500 years except since the 1920s when a rapid colonization of relatively diverse diatom algal flora occurred. The recent nature of this assemblage suggests a decrease in ice cover and a concomitant increase in light and nutrient availability for algal production over the past about 80+ years. Similarly, in Upper Dumbell Lake on northern Ellesmere Island, very few diatoms were recorded in sediments before about 1950, presumably due to harsh ice conditions (Doubleday et al., 1995). Only with accelerated warming over the past few decades did enough of the shallow-water moat thaw in summer to allow small, benthic taxa to increase in abundance. Still farther north, on Ward Hunt Island, Antoniades et al. (2007) recorded a similar appearance of diatoms, as well as dramatic increases in production (recorded by fossil algal pigments), in the recent sediments of Canada's northernmost lake (83°05' N, 74°10' W; Figure 6.6). The period of relative stability throughout much of the sediment core prior to the diatom and pigment shifts suggests that the lake's biology has been affected more by environmental change during the past two centuries than at any point during the preceding eight millennia (Antoniades et al., 2007).

In an attempt to synthesize the circumpolar paleolimnological records, Smol et al. (2005) compiled a dataset of 55 biostratigraphic profiles and estimated the amount of compositional change or turnover between the sediment




Figure 6.6. Change in the abundance and composition of algal communities over the past eight millennia, as inferred from fossil diatom and pigment profiles in Ward Hunt Lake sediments. Ward Hunt Lake is located on a small island north of Ellesmere Island in the Canadian Arctic. The most pronounced shifts occurred during the past two centuries. These abrupt changes are associated with a loss of ice cover and associated limnological and bio-optical changes in the water column. Recent change is indicated by the grey shaded area at the top of the figure. After Antoniades et al. (2007), which gives full details for each pigment profile.

samples at each site over the same time period (~150 years) using numerical procedures. They made the following conclusions: areas of the Arctic that were expected to have warmed the most also showed the greatest degree of compositional change; ecological change had occurred at several trophic levels; and the ecological characteristics of the species involved indicated that changes were driven primarily by climate warming. However, while most freshwater ecosystems show signs of pronounced change associated with warming in the High Arctic, similar changes were not detectable in lakes and ponds of northern Québec and Labrador (Pienitz et al., 2004). This remarkable regional stability at timescales of decades to hundreds of years is consistent with decadal observational (e.g., Serreze et al., 2000) and tree-ring (D'Arrigo et al., 2003) data that reveal climatic stability or even slight cooling over the western subpolar North Atlantic and adjoining land areas of eastern sub-Arctic Canada. It also suggests that northern Québec and Labrador may experience less short-term or delayed climate change relative to other Arctic regions and that they could be the ultimate bellwether of large-scale circumpolar change (Pienitz et al., 2004).

More recently, a meta-analysis of fossil diatom records from more than 200 lakes in the Northern Hemisphere revealed spatially structured but temporally coherent changes in species composition since the 19th century (Rühland et al., 2008). By comparing only a subset of highly resolved fossil time series with 30 to 100 years of environmental monitoring, and selecting only lakes in undisturbed catchments, Rühland and co-workers demonstrated that reorganization of community composition is correlated with change in ice cover and related limnological conditions (mixing and light regimes), rather than change in the influx of nutrients. They further inferred that many Arctic lakes may have crossed an important ecological threshold as a result of unprecedented atmospheric warming.

6.4.2. Trends of the instrumental period and linkage with climate

- Long-term records for the Northern Hemisphere (1846 to 1995) indicate the following (although only one site was located north of the Arctic Circle):
 - freeze-up has become later (average +6.3 d/100 y)
 - break-up has become earlier (average -5.8 d/100 y)
 - ice duration has decreased (average 12.1 d/100 y).
- A subsequent analysis of a much smaller subset of only lakes from the same archive with records to 2004/05 indicates the following further changes:
 - later freeze-up (+10.7 d/100 y)
 - earlier break-up (-8.8 d/100 y)
 - reduction in average ice duration (19.5 d/100 y)
 - strong and consistent changes after the mid-1990s probably influenced this rate change but different sample sizes and/or periods of record may also have played a role.
- Many shorter-term regional studies have also been conducted, but they exhibit appreciable spatial and

interdecadal variability. Much of this is likely to be due to analytical differences in the number and location of station data and the various record lengths used for trend calculations.

- Most trends toward shorter freshwater ice duration over much of the circumpolar North closely correspond to increasing air temperature trends and, more specifically, timing of the 0 °C isotherm.
- Broad spatial patterns in ice trends have also been linked to major atmospheric circulation patterns, different phases of which can cause contrasting ice conditions (e.g., shorter versus longer ice duration) across individual continents and between opposite sides of the circumpolar North.
- Some important south-north contrasts, however, have also been identified in freshwater ice trends. Examples from Scandinavia show more pronounced change (later freeze-up and earlier break-up) occurring in southern than in northern lakes, perhaps indicating greater sensitivity to warming at the more temperate latitudes.
- Contrasting results, albeit involving a more recent period, have been noted for south-north regions of Canada based on records obtained by remote sensing. The degree to which this reflects the effects of either more recent or higher-latitude warming or a combination of both is unclear.
- Large-scale, comprehensive records of river- and lake-ice thickness are rare. One dataset compiled for Canada over the past 50 years does not reveal any obvious trends over the latter part of the 20th century. However, reductions in maximum ice thickness have been observed on nearly all rivers and lakes within Arctic Russia over the past two decades compared to the previous 30-year period.

6.4.2.1. Trends in instrumental records

Historical evaluations of changes in freshwater ice conditions over the circumpolar Arctic have proven difficult to synthesize owing to a variety of issues, including the limited number of detailed observations; different observational periods of record; varying *in situ* observational methodologies and/or phenological definitions; and changes in observation methods, such as from *in situ* to remote sensing (see also Section 6.2). As a result, most trend analyses have focused on relatively simple characteristics that are easy to glean from most agency records, such as the timing of autumn freeze-up and spring break-up, ice-cover duration, and ice thickness. The majority of these have been summarized by Walsh et al. (2005). They range from long-term records (~150 years or more) from a small set of observation sites around the Northern Hemisphere (Magnuson et al., 2000; Table 6.1) to several significant shorter-term (100 years or less) regional analyses over Arctic and sub-Arctic Russia (Ginzburg et al., 1992; Soldatova, 1993; Smith, 2000), northern Scandinavia (Zachrisson, 1989; Kuusisto and Elo, 2000), and northern areas of North America (Jasek, 1999; Sagarin and Micheli, 2001; Zhang et al., 2001). A detailed review of historical trends in the ice phenology of northern rivers was provided by Beltaos and Prowse (2009).

The long-term records originally analyzed by Magnuson et al. (2000) focused on the period 1846 to 1995, and included

39 time series of freeze-up or break-up from 26 sites (5 rivers, 19 lakes) with records of more than 100 years during this period. Only one site was north of the Arctic Circle (Table 6.1), reflecting the lack of high-latitude long-term observation sites. Overall, 38 of the 39 time series showed either later freeze-up (15 sites averaging +6.3 d/100 y) or earlier break-up (24 sites averaging -5.8 d/100 y), thus resulting in an average reduction in ice duration of 12.1 d/100 y¹.

In a subsequent analysis (by B.J. Benson and J.J. Magnuson, reported by Koç et al., 2009) of a smaller set of only northern-hemisphere lakes (9 sites for freeze-up and 17 for break-up) for the winters 1855/56 to 2004/05 from the same GLRIP database (Figure 6.7), the rate of change in both events is noted to increase: from +6.3 to +10.7 d/100 y for freeze-up and -5.8 to -8.8 d/100 y for break-up, thereby further reducing average ice duration by 12.1 to 17.4 d/100 y. It is unknown how much of this increased rate of change results from different sample sizes or periods of record. However, some is certainly due to the strong and consistent changes in timing that are evident after the mid-1990s (Figure 6.7), which is also the end of the previous period of analysis by Magnuson et al. (2000).

Among most of the shorter-term regional studies noted above, which typically contained far more sites than those used in the long-term evaluation by Magnuson et al. (2000), there is appreciable spatial and interdecadal variability. Much of this is due to analytical differences in the number and location of station data, and the various record lengths used for trend calculations. For example, river-ice trends in North America for the latter half of the 20th century exhibit a major spatial distinction between western and eastern regions, with the west showing significant and the east, small or insignificant trends toward earlier break-up (Walsh et al., 2005). Similar spatial trends were determined by Duguay et al. (2006) for Canadian lake-ice break-up. For Eurasia, Vuglinsky and Granskaya (2006) found that average freshwater-ice duration decreased between two 20-year periods (1950–1979 and 1980–2000) by 2 to 10 days for lakes and rivers in European Russia, and by 3 to 7 days for rivers and 4 to 14 days for lakes in Asian parts of Russia. The reductions were attributed to earlier spring break-up and later autumn freeze-up.

Some important south-north contrasts have also been identified in freshwater-ice trends. For example, an investigation of Finnish lakes (with the longest time series from the early 19th century) showed that, with the exception of the far North, ice-cover duration has become significantly shorter due to later freeze-up and earlier break-up (Korhonen, 2006). Similarly, findings from Sweden for the period 1961 to 1990 show a rapid advancement in lake ice break-up of -0.92 d/y at southern latitudes, whereas the rate was significantly less at only -0.25 d/y for Arctic lakes (Weyhenmeyer et al., 2005). Contrasting results, albeit involving a more recent period, have been noted for south-north regions of Canada. Based on AVHRR imagery, Latifovic and Pouliot (2007) extended *in situ* records for 36

Canadian lakes for the 1950s to 2004 and developed new records for six high-latitude lakes from 1985 to 2004. Similar to most of the studies noted above, the majority of the sites showed earlier break-up (averaging -0.18 d/y) and delayed freeze-up (averaging +0.12 d/y) dates for the entire period. For the more recent period from 1970 to 2004, the rates increased to an average of -0.23 d/y and +0.16 d/y, respectively. As noted by Prowse and Brown (2010), however, the most rapid rates of change occurred in the six high-latitude lakes (primarily on the Canadian Archipelago) for the even more recent period of 1985 to 2004. For these lakes, changes in timing associated with earlier break-up and later freeze-up averaged -0.99 d/y and +0.76 d/y. This translates into an ice-cover reduction rate of 1.75 d/y, or about 4.5 times that found for the more southern parts of Canada for the most rapid depletion period of 1970 to 2004. The degree to which this reflects the effects of either more




Figure 6.7. Long-term records of freeze-up, break-up and ice-cover duration for northern-hemisphere lakes. The plots present a 2007 update by B.J. Benson and J.J. Magnuson (Koç et al., 2009) of data originally presented by Magnuson et al. (2000) and based on records contained in the Global Lake and River Ice Phenology (GLRIP) database housed at the National Snow and Ice Data Center, University of Colorado at Boulder, USA. Note: stations are non-Arctic but included because of their unique long-term record length. After Koç et al. (2009).

¹ In this context, '+' and '-' refer to later and earlier, respectively, and the use of different reference intervals for reporting changes in subsequent shorter-term studies is discussed in subsequent sections. It should also be noted that there are typographical errors in the table of record lengths for freeze-up reported by Magnuson et al. (2000), with the last digit of the 100+ records missing in the published article but contained in the Global Lake and River Ice Phenology Database (GLRIP).

recent or higher-latitude warming or a combination of both is unclear. Explaining the reasons for any of the regional contrasts will require further investigation into factors such as regional differences in controlling heat fluxes, as well as differences that may arise from the use of different observational methods (e.g., *in situ* vs remote sensing).

In addition to basic observations of freeze-up and break-up timing, some trend analysis has also been conducted on other phenological characteristics of river-ice break-up. For example, in a study of rivers of the Mackenzie River Basin for the period 1970 to 2002, de Rham et al. (2008b) determined that both the initiation and timing of peak water levels occurred an average of 0.12 d/y earlier. Focusing specifically on the northern part of the basin, the Mackenzie River Delta, Goulding et al. (2009b) showed that spring streamflow pulse and the timing of melt initiation have advanced by 1.1 d/decade and 2.0 d/decade, respectively (both non-significant over the period 1974 to 2006). In addition, the ablation period (from melt initiation to the onset of break-up) has increased over the 33-year record. This agrees with results from Smith (2000) for Russian Arctic rivers, where a trend toward a longer pre-breakup was noted and suggested to be a potential driver of more frequent thermal break-ups in the future. Goulding et al. (2009b) also found a significant decrease in peak ice thickness of 4 cm/decade and a significant increase in freeze-up stage by 27 cm/decade, although considerable interannual variability was evident.

Large-scale, comprehensive records of river- and lake-ice thickness are rare. One dataset compiled for Canada over the past 50 years (Lenormand et al., 2002) does not reveal any obvious trends over the latter part of the 20th century (Lemke et al., 2007). However, reductions in maximum ice thickness of 2 to 14 cm have been observed on nearly all rivers and lakes within Arctic Russia over the past two decades compared to the previous 30-year period (Vuglinsky and Gronskeya, 2006). The largest decreases were found in rivers within Siberia (Ob: 5 to 10 cm; Yenisey: 6 to 14 cm; lower Lena: 11 to 15 cm). With reference to the interpretation of trends in ice-cover thickness, it should be pointed out that caution must be used when employing records from systems that have become regulated during the period of interest. For example, there has been a marked increase in ice thickness at the Tuoy-Haya station in Russia after the river site was impounded to become the Vilyuiskoye reservoir (2360 km²) (Figure 6.8). The increase can be attributed to changes in ice dynamics, hydraulics, and

water-ice heat fluxes resulting from the storage. Including such records in any trend analysis of the effects of changing climate, without accounting for regulation-induced effects on ice growth, could lead to incorrect interpretations.

6.4.2.2. Linkage of trends to climatic factors

Freshwater ice duration, thickness, and composition are influenced by a diverse set of hydraulic and hydroclimatic variables that often span the entire ice season (see Section 6.3). Given this complexity, establishing relationships between freshwater ice trends and climate has generally been conducted simply using air temperature (see Section 6.2). Ice thickness is the variable most frequently linked to such a readily available, single climatic variable. For example, Vuglinsky and Gronskeya (2006) established a relationship between maximum river-ice thickness and winter air temperature in European Russia. Air temperature, however, has also been used to explain the more complex phenological timing of freeze-up and break-up. Statistically, air temperature during the preceding autumn and spring months is often able to explain 60% to 70% of the variance in the timing of ice break-up and freeze-up on lakes and rivers (Walsh et al., 2005). As noted by Prowse and Bonsal (2004), a first approximation of river-ice response to climatic change based on the analyses of various cold regions indicates that a long-term mean increase of 2 to 3 °C in autumn and spring air temperature has produced an approximate 10-day delay in freeze-up and a 15-day advance in break-up. For one specific period (1870 to 1950), it was found that a 3 °C rise in April temperature was associated with about a 15-day advance in break-up (Zachrisson, 1989). This concurs with the typical 5 d/°C rate of change in phenological data for many lakes and a few rivers around the Northern Hemisphere (Magnuson et al., 2000). As a result, trends toward shorter freshwater-ice duration over much of the circumpolar North closely correspond to the increasing air temperature trends observed over most of this region.

Another approach to assessing climatic linkages to freshwater-ice break-up and freeze-up timing has involved relating these events to 0 °C isotherm dates as defined by Bonsal and Prowse (2003). This variable has the advantage of not being constrained by the traditional seasonal definitions of temperature normally used in large-scale climatic studies. For several rivers within Canada, Lacroix et al. (2005) determined




Figure 6.8. Step-change in maximum ice-cover thickness at the Tuoy-Haya station before regulation (river channel, 1951 to 1967) and after regulation (nearshore zone of Vilyuiskoye reservoir, 1969 to 2007). Data sourced from the State Hydrological Institute, St. Petersburg, Russia.

that break-up dates were highly correlated to the timing of spring 0 °C isotherms over most of the country; however, these relationships were much weaker and less spatially coherent during autumn. In terms of Canadian lakes, similar spatial and temporal patterns have been found between trends (1966 to 1995) in autumn and spring 0 °C isotherms and lake freeze-up and break-up dates. In general, this included significant trends toward earlier springs and earlier break-up dates over most of western Canada, and little change in the onset of lower temperatures and freeze-up dates over the majority of the country in autumn (Duguay et al., 2006).

Since air temperature varies sinusoidally over the year, the calendar dates on which the smoothed air temperature falls below 0 °C (in autumn) and rises above 0 °C (in spring) are arc cosine functions of the smoothed air temperature, and the fraction of the year during which the ambient air temperature is below 0 °C can be estimated by $(1/\pi) \arccos(T_m/T_a)$, where T_m and T_a are the mean and amplitude of the annual air temperature cycle (Weyhenmeyer et al., 2005; Livingstone et al., 2010). This arc cosine approach has been validated for more than 40 years of historical ice phenology data from 196 lakes spanning 13° of latitude in Sweden. Due to the form of this function, the timing of ice break-up (and freeze-up) tends to be more sensitive to variations in air temperature at lower latitudes where mean annual air temperatures are higher, than at higher latitudes where mean annual air temperatures are lower. In other words, the timing of lake-ice break-up appears to respond to changes in air temperature in a non-linear fashion dependent on latitude (Blenckner and Chen, 2003; Weyhenmeyer et al., 2004, 2005). As outlined in the previous section, this non-linear response has been identified in lake-ice trend analyses over Sweden and Finland. An opposite latitudinal trend might apply to the data in Canada, although the reasons for these opposing trends requires further investigation, as noted in Section 6.4.2.1.

6.4.2.3. Linkage of trends to atmospheric circulation patterns

Although freshwater ice-cover duration over the circumpolar North has, for the most part, significantly decreased in response to increasingly warmer conditions during the 20th century, the patterns have varied regionally, primarily due to climate impacts associated with large-scale atmospheric and oceanic oscillations. Teleconnection patterns originating over the Pacific and Atlantic Oceans account for a substantial amount of the observed 20th century northern-hemisphere temperature trends and variability, especially during winter and spring (Hurrell, 1996; Serreze et al., 2000). For example, the El Niño-La Niña / Southern Oscillation (ENSO), Pacific North American (PNA) pattern, and Pacific Decadal Oscillation (PDO) are closely linked to winter and early spring temperature variability over much of North America, particularly to the west. This includes higher temperatures associated with El Niño events and positive phases of the PNA and PDO, which are all representative of a deepened Aleutian Low (and vice versa) (e.g., Wallace et al., 1995; Bonsal et al., 2001). The most notable pattern in the Pacific involved a shift toward a deeper Aleutian Low after 1976 that has been associated with the trend toward higher winter and spring temperatures over western North America (e.g., Trenberth, 1990). The deeper low and

associated cyclonic surface circulation allow for more frequent incursions of warm Pacific air into northwestern North America and thus shorter ice durations (especially, earlier break-ups) in this region (see Figure 6.9). In fact, several studies have demonstrated convincingly that ENSO, the PNA, and the PDO have had significant impacts on the ice phenology of Arctic lakes and rivers within North America including the mid-1970s interdecadal shift (e.g., Benson et al., 2000; Robertson et al., 2000; Bonsal et al., 2006; Blenckner et al., 2007).

In Europe, parts of northern Asia, and northeastern North America, the North Atlantic Oscillation (NAO) (or the Arctic Oscillation (AO) with which it is strongly associated) is known to influence large-scale climate, especially air temperature, in winter and spring (e.g., Hurrell, 1995). In particular, a positive NAO (representative of a deepened Icelandic Low in the North Atlantic) is associated with higher temperatures over Europe and northern Asia and lower than normal values over northeastern Canada (and vice versa) (Hurrell, 1996). The intensified counter-clockwise circulation of the Icelandic Low results in cold northerly air advection into eastern Canada and greater frequencies of warm maritime flow into Europe and northern Asia (Figure 6.9). As a result, a strong winter NAO/AO signal has been detected in the ice phenology of lakes and rivers in Estonia, Finland, Sweden, and northwestern Russia (Livingstone, 2000; Yoo and D'Odorico, 2002; Blenckner et al., 2004, 2007; Karetnikov and Naumenko, 2008), and for Lake Baikal in Siberia (Livingstone, 1999; Todd and Mackay, 2003). These oscillations have also been shown to impact freshwater-ice duration in northeastern Canada (Bonsal et al., 2006). A higher occurrence of positive NAO and AO in the later decades of the 20th century is consistent with the winter and spring cooling observed over most of northeastern North America and warming in Europe and northern Asia. This, along with the Aleutian Low shift in 1976, helps explain the west to east gradient in air temperature and associated freshwater-ice duration observed over Arctic regions of North America during the latter 50 years of the 20th century. It is also consistent with the observed trends toward shorter ice duration in much of Scandinavia and western Russia. Notably, from around 2000 to the present, persistent warm temperature anomalies have occurred in two localized areas, including eastern Siberia and northeastern Canada and Baffin Bay, which is in contrast to temperatures observed during the latter part of the 20th century. This is the result of a northward displacement and strengthening of the Aleutian Low and a weakening of the Icelandic Low, the latter being reflective of a trend toward more negative NAO and AO values since the turn of the century (Overland and Wang, 2005). Although not specifically analyzed, it is likely that these two regions have been associated with shorter freshwater-ice duration during this period.

The connection between the Pacific and Atlantic large-scale oscillations shown in Figure 6.9 were not consistent through the 20th century, although some recent studies have indicated a seesaw relationship linking the Aleutian and Icelandic Lows that acts on interdecadal timescales (e.g., Honda and Nakamura, 2001; Luchin et al., 2002). The linkage was weak from the mid-1950s through the mid-1960s and particularly strong from the 1920s to the 1940s and from the late 1960s through the 1990s. It consists of Aleutian Low anomalies of a given sign developing in mid-winter followed by the occurrence (through Rossby




Figure 6.9. Schematic illustration showing typical cold-season atmospheric circulation patterns associated with the El Niño / Southern Oscillation (ENSO), the Pacific Decadal Oscillation (PDO), the Pacific North American (PNA), and the North Atlantic Oscillation / Arctic Oscillation (NAO/AO). Positive phases of ENSO, the PDO, and the PNA (shown here) are associated with a deeper than normal Aleutian Low causing higher temperatures and resultant shorter freshwater-ice duration over northwestern North America. Positive phases of the NAO/AO (shown here) are associated with a deeper than normal Icelandic Low causing lower temperatures and resultant longer freshwater-ice duration over northeastern Canada, and higher temperatures and resultant shorter freshwater-ice duration over Europe and northern Asia. Note that opposite phases of these circulation patterns (i.e., La Niña events and negative PDO, PNA, NAO/AO) are associated with weaker than normal Aleutian and Icelandic Lows, causing opposite temperature changes and freshwater ice durations than shown here.

wave propagation) of Icelandic Low anomalies with opposite sign about one month later (Honda and Nakamura, 2001). This then affects surface temperatures over northwestern North America, Europe, and northern Asia (Honda et al., 2005). The seesaw in surface pressure and resultant impacts on surface temperature (see Figure 6.9) are likely to be reflected in results from Pavelsky and Smith (2004) who determined that break-up dates on the Mackenzie and Lena Rivers (from 1992 to 2003) showed a consistent negative correlation. They attributed this relationship to variability in the PDO, where in seven of the ten years a positive PDO index (i.e., deeper Aleutian Low) was associated with earlier break-up on the Mackenzie and later ice-off dates on the Lena (consistent with a weaker than normal Icelandic Low). Further research is required to determine correlations between freshwater-ice dates over various regions of the circumpolar North and corresponding linkage to large-scale atmospheric circulation patterns.

It should be noted that recent extreme warm periods over the Arctic have been attributed to distinct atmospheric circulation patterns that are generally not captured by the standard teleconnection indices. The best-documented case has been the summer of 2007 when anomalously high temperatures and associated extreme sea-ice loss over the western Arctic were linked both to a very unusual atmospheric circulation pattern that resembled the PNA, but was much stronger and shifted northward (L'Heureux et al., 2008), and to a dipolar

circulation pattern consisting of a northeastward shift to the AO and NAO centers of action, dubbed the Arctic Rapid Change Pattern (ARP) by Zhang et al. (2008). These recent atmospheric 'hot spots' may be suggestive of a new climate state for the Arctic (Overland et al., 2008), thus making future changes to freshwater-ice duration more uncertain.

In addition to large-scale teleconnections, a few studies have attempted to relate freshwater ice phenology to regional or synoptic atmospheric circulation patterns. For example, in a study of 50 lakes in Sweden and Finland ranging from 58° to 69° N for the period 1961 to 2002, Blenckner et al. (2004) found that regional zonal and meridional circulation indices explained a larger portion of observed variability in freeze-up and especially break-up dates when compared to the larger-scale autumn and winter NAO index. It was therefore concluded that regional circulation indices are a useful tool for climate impact assessment of freshwater ice and require additional examination over other regions within the circumpolar North.

6.4.3. Projected changes

- Recently, there have been concerted efforts to model changes to future freshwater ice phenologies using climate output from global climate models (GCMs) and regional climate models (RCMs). For example, modeling of hypothetical lakes of varying depth for northern land masses between

40° and 75° N indicates that future warming by the period 2040 to 2079 will result in the following:

- an overall increase in lake water temperature, with summer stratification starting earlier and extending later into the year, resulting in the timing of freeze-up being delayed by 5 to 20 days
- break-ups that are 10 to 30 days earlier
- a decrease in lake-ice duration of about 15 to 50 days
- decreases in maximum lake-ice thickness by 10 to 50 cm
- a likely increase in surface white ice, especially as the ice cover also thins (owing to projected increases in winter snowfall at high latitudes).
- Modeling of future changes to river-ice regimes has been restricted to a few rivers, with no regional studies conducted.
- Projected decreases in south-north gradients in air temperature suggest that the severity of break-up and related ice-jam flooding may be reduced on some large, northward-flowing rivers, but effects might be mitigated by other factors, including changes in the magnitude of spring snowmelt.

Similar to the assessment of historical trends in freshwater-ice characteristics (Section 6.4.2), the quantification of future changes to lake and river ice is primarily based on degree-day methodologies as inferred by projected temperature changes from climate models. Results from these studies show a continued reduction in freshwater-ice duration (of varying degrees) in all Northern regions. For example, over European Russia and western Siberia, Borshch et al. (2001) applied a uniform warming of 2 °C to assess changes in river-ice duration. It was determined that break-up would be advanced by 4 to 10 days and freeze-up delayed by 4 to 12 days, with the greatest changes in western regions of Russia. Relying on the 5 d/°C rate of change in phenological break-up dates estimated by Magnuson et al. (2000), Prowse et al. (2002a) approximated that a projected increase in spring air temperature of 3 to 7 °C by the end of this

century (as determined from several GCMs) would result in a 15- to 35-day advance in river-ice break-up in northern regions of Canada. A more detailed analysis based on average monthly temperature change projections (relative to 1961–1990 using the IPCC A2 emissions scenario from seven GCMs) for the 30-year period centered on the 2050s (2040–2069), found that spring 0 °C isotherm dates will occur 6 to 10 days earlier over northern regions of Canada. Autumn changes were even more pronounced (~10 to 12 days later) (Prowse et al., 2007a; Figure 6.10). Given the close correspondence between 0 °C isotherm dates and lake-ice (e.g., Duguay et al., 2006) and river-ice (e.g., Lacroix et al., 2005) break-up and freeze-up dates during the instrumental record, it may be hypothesized that by the middle of the 21st century freshwater-ice duration over much of northern Canada will be about 20 days shorter than during the 1961 to 1990 baseline period (Prowse et al., 2007a). Subsequent analyses of future 0 °C isotherm changes along the four major Arctic rivers (Lena, Mackenzie, Ob, Yenisey) by Prowse et al. (2010) indicate that pronounced changes in river ice will occur along some of these rivers.

As noted by Bonsal and Prowse (2003), however, these empirical relationships between freshwater-ice dates and air-temperature indices may not be reliable under future climatic conditions due to changes in the composition of major heat fluxes on which the temperature relationships are founded. Furthermore, as outlined in Section 6.4.2, the historical timing of freshwater-ice break-up in some regions of the North has responded to changes in air temperature in a non-linear fashion that was dependent on latitude (Blenckner and Chen, 2003; Weyhenmeyer et al., 2004, 2005), thus complicating the use of spatially uniform degree-day and freshwater-ice change relationships.

There have only been a few preliminary analyses that have modeled changes in future freshwater-ice phenologies using climate output from GCMs. In the case of lakes, Dibike et al. (2010) incorporated a one-dimensional lake simulation model (MyLake) and atmospheric forcing data from the ERA-40 global re-analysis dataset (Uppala et al., 2005) to simulate lake-ice phenology and composition for all land masses in a




Figure 6.10. Projected changes to spring and autumn 0 °C isotherm dates over Canada for the 30-year period centered on the 2050s (2040–2069). Source: Prowse et al. (2007a).




Figure 6.11. Change in simulated mean dates of freeze-up, ice break-up, and ice-cover duration between current (1960–1999) and future (2040–2079) climatic periods. Source: Dibike et al. (2010).

40° to 75° latitudinal band with hypothetical lakes positioned at a resolution of 2.5° latitude and longitude. Differences in driving climatic variables between a current (1960–1999) and future (2040–2079) run of the Canadian Global Climate Model (CGCM3) were applied to the ERA-40 current data as input to the MyLake model to project future ice conditions. Results indicated that future warming will result in an overall increase in lake-water temperature, with summer stratification starting earlier and extending later into the year and, hence, the timing of freeze-up being delayed by 5 to 20 days (Figure 6.11). Break-up was projected to occur 10 to 30 days earlier, resulting in an overall decrease in lake-ice duration of about 15 to 50 days. Maximum lake-ice thickness was also modeled to decrease by 10 to 50 cm. Change in snow loads and related ice-cover composition were also modeled. In general, maximum snow depth changed by -20 to +10 cm and white ice by -20 to +5 cm, depending on the geographical location and other climate parameters – the high latitudes being an area of projected increases in winter snowfall that can promote white-ice formation particularly with thinner ice cover.

There are fewer projections of future climate change impacts on river ice than lake ice, and none have been conducted at regional scales. One large-river example is provided by Andrishak and Hicks (2008), who applied a one-dimensional hydrodynamic model to assess climate change impacts on ice-cover extent and duration on the Peace River in Canada.

Incorporation of air-temperature projections (for the 2050s using the IPCC A2 emissions scenario) from the second generation Canadian Global Climate Model resulted in an average reduction in ice duration of 28 days (13 days later for freeze-up and 15 days earlier for break-up).

Much less is known about changes in more complex variables such as ice composition and, in the case of rivers, the frequency and severity of ice jams. One of the more important potential changes to river ice relates to the severity of break-up advance (see also Section 6.5.1.1). Whether temporal shifts in river-ice duration will produce more or less severe break-up events (i.e., floods) remains unknown, largely because of the complicating role of precipitation, which has the potential both to control the driving (snowmelt runoff) and resisting (ice thickness, strength, composition) forces that affect break-up severity. Although some very limited, site-specific predictions of change in these two cryospheric components (snow and river ice) have been made to estimate the effect on river-ice break-up severity (Beltaos et al., 2006), broad-scale analyses have not been undertaken.

As suggested by Prowse et al. (2006), changes in the thermal gradients affecting the advance of the spring freshet on northward-flowing rivers could produce significant changes to the dynamics and related flooding that accompany river-ice break-up. Recent analysis of 0 °C isotherms along the four major Arctic rivers (Lena, Mackenzie, Ob, Yenisey) by Prowse et al.

(2010) suggests that future warming could lead to a reduction in the thermal gradients. The 0 °C isotherm was used because it was noted to approximate the timing of river-ice break-up (e.g., Bonsal and Prowse, 2003; Lacroix et al., 2005; see also Section 6.4.2.2). Figure 6.12 illustrates average projected changes in 0 °C conditions on the four largest Arctic rivers based on average values of four GCMs for two future time periods, 2041–2070 and 2071–2100, and referenced to current climate (1979–2008). All four rivers exhibit progressively earlier timing of the 0 °C isotherm over their entire length. They also show a tendency to greater warming in a downstream (primarily south to north) direction, with the greatest change being for the Lena River. Such a reduction in the current climatic gradient is likely to lead to a more thermal type of break-up (see Section 6.5.1.1 for a description of break-up dynamics) characterized by reduced ice action and ice-jam flooding. This would have major ecological implications for riparian ecosystems, such as river deltas (see Section 6.5.2.3).

Given that large-scale teleconnections have been shown to influence air temperature and associated river-ice characteristics over much of the Northern Hemisphere (Section 6.4.2.3), knowledge of future changes in the frequency and magnitude of these oscillations could provide insight into future freshwater-ice regimes. At present, however, the effects of climate change on large-scale teleconnection patterns remain uncertain due to the lack of agreement concerning the future frequency and structure of atmospheric and oceanic modes among the various climate models (Prowse et al., 2007a). For example, with respect to El Niño, GCMs from the most recent (2007) IPCC assessment offer a wide range of possibilities with respect to the future occurrence and variability of these events (Guilyardi et al., 2009). Because El Niño significantly affects climate over many regions of the Northern Hemisphere and is often associated with variations in other Pacific-related teleconnections, such as the PDO and PNA, knowledge of its future occurrence would assist in projecting regional changes in future river-ice duration and dynamics. The majority of climate change investigations have indicated increased occurrence in the positive phases of the NAO and AO in association with future warming (e.g., Rind et al., 2005). This would result in continued warming over northern Eurasia and cooling over northeastern North America with implications for freshwater-ice duration over these regions (see Figure 6.9).

In summary, predicting the state and fate of freshwater ice over the next century will require a number of significant advances, the most difficult being for river ice. For the simpler case of lake ice, improvements will need to be made in the physical modeling of the full-season thermal regime. This is especially important in determining the timing of freeze-up and in considering the increasing role of precipitation (e.g., snow accumulation) that affects ice-growth rates, ice-cover composition, ablation rates, and the timing of break-up. As for most other surface variables, refinements will be made to properly downscale (statistically or dynamically) the requisite variables that control surface energy exchanges, including atmospheric coupling to account for feedback in the case of large lakes. Site-specific to broad-scale predictions of change in most lake-ice characteristics would be possible with the advancements noted above (Prowse et al., 2008).

6.5. Effects of changing freshwater ice covers

6.5.1. Hydrological effects

- Many projected changes to freshwater ice systems will be affected by companion changes in other cryospheric components, particularly snow and permafrost.
- Changes in break-up severity are a major concern because of their importance to flooding on northern rivers, which can have positive and negative impacts.
- The location and severity of river-ice break-up could also be modified by changes in hydraulic gradients, particularly in coastal deltas affected by rising sea level.
- Mid-winter break-ups will increasingly intrude into higher latitudes; there is already evidence of such events occurring in the sub-Arctic.
- Ice-regime changes are also likely to affect river low-flows through modifications of ice-induced hydraulic storage and icing accumulation / ablation that have historically supplied flow during low-flow summer months.
- Decreases in ice duration combined with higher summer temperatures will lead to increased lake evaporation, lowering of lake levels, and potential drying out of shallow basins. Recent evidence suggests that this may have already happened to some ponds that have been permanent water bodies for millennia.
- Winter pulsing of water from lakes to downstream rivers will occur as ice-cover thins and winter precipitation loads increase.

A brief physical description of river ice processes was provided in Section 6.1.2, but to aid in understanding how climate change may affect river-ice flow regimes the following subsections provide more details about how key climatic variables control hydraulic and mechanical conditions associated with some specific ice-induced hydrological extremes. There are, however, a number of other cryo-hydrological changes that will affect freshwater-ice systems. To varying degrees, such changes have been reviewed in other chapters, particularly those dealing with snow and permafrost. The major changes are briefly summarized in this introductory section and considered in more detail in subsequent sections.

One of the most significant changes in other cryospheric components that will affect both lake and river ice is the change in winter precipitation. Recent research (e.g., Zhang et al., 2007) suggests that there has been a global latitudinal redistribution of precipitation from lower to higher latitudes. Moreover, future projections for higher latitudes suggest that such changes will mean increases in winter precipitation and snow-water equivalents (Bates et al., 2008; Brown and Mote, 2009). This will also result in greater snow loading of freshwater-ice covers and, as explained below, could affect thermal insulation influencing ice-growth rates, ice-cover depression and the formation of surface snow ice, and winter pulsing of flow displaced from lakes. Increased winter snow accumulation, unless interrupted by mid-winter melt, should also translate into a larger spring




Figure 6.12. Projected changes in spring air temperature (average March to May) along the four largest Arctic rivers for two future time periods (2041–2070 and 2071–2100) compared to the current climate (1979–2008): (left column) current and projected 0°C isotherm dates along the main-stem reaches of the four large Arctic rivers; (centre column) current and projected air temperature at the time when the upstream sections of the 2000-km main-stem reach 0°C ; and (right column) associated differences in air temperature between current and future climates. The solid blue and red lines are the GCM-ensemble means, while shading denotes the full range of projected GCM values. Source: Prowse et al. (2010).

snowpack. As already documented for some large northern rivers and alpine catchments, both the magnitude and timing of spring discharge are strongly linked to change in snow cover during the spring melt season (e.g., Yang et al., 2007, 2009; Stewart, 2009). Assuming that future spring-melt conditions (e.g., intensity and duration of heat fluxes) are similar to those for the current climate, a larger snowpack should translate into a larger melt volume and river discharge. Several studies have shown that winter discharge in the major Eurasian Arctic rivers is already increasing (see White et al., 2007). Larger winter baseflow and spring snowmelt volumes could increase the forces that drive river ice and have major implications for break-up severity, javes (a steep water wave associated with the release of an ice jam on a river), and ice-jam floods. If sufficiently large, mid-winter melt of a catchment snowpack also has the potential to initiate ice break-up.

While changes in snowfall are most important to spring ice events, other seasonal changes in river flow created by changing permafrost conditions (e.g., Hinzman et al., 2005; White et al., 2007) can also have implications for freshwater-ice processes. Overall, thawing permafrost and the associated development of more groundwater flow systems are projected to increase river baseflow, some of which has already occurred during winter in parts of the Northwest Territories, Canada (St. Jacques and Sauchyn, 2009). Combined with any summer and autumn increases in precipitation, this should lead to higher flows at the time of winter ice formation. Higher flows and stage at freeze-up raise the possibility of thicker ice accumulations, increased hydraulic storage of water, and even the potential for autumn freeze-up ice jams and related flooding (Beltaos and Prowse, 2009). Increased groundwater flow will also mean more heat transfer to rivers, which should translate into some thinning of ice cover, or where flow is concentrated, even the opening or broadening of freshwater polynyas (e.g., Prowse, 2001b). Increased groundwater flow will also thin ice cover in lakes, creating more unfrozen volume beneath the ice. This has important implications, especially for shallow systems that freeze to the bed, for the availability of under-ice winter habitat, and for the migration of fish species. In extreme cases of permafrost thaw and groundwater development, talik development (i.e., zones of localized unfrozen ground) beneath lakes could lead to their drainage and the elimination of ice covers.

Many hydrological changes operating in the Arctic are controlled by synergies among cryospheric components. Further details of many of these are reviewed in the following sections.

6.5.1.1. River-ice floods and javes

Large aggregate thickness and extreme underside roughness are two characteristics of river-ice jams that combine to generate very high water levels relative to those occurring for the same discharge under open-water conditions. Although freeze-up jams can cause flooding under certain hydro-climatic conditions, it is break-up jamming that typically generates the most extreme floods, owing to the much higher break-up flows (Beltaos, 2008d). The release of a major jam is also of concern since it is often attended by a steep water wave that can be metres high and is characterized by greatly amplified flow velocities and hydrodynamic forces. This release is also known as a jave, short for ‘jam release wave’ (Beltaos, 2008e). Ice jams and javes have

many socio-economic and ecological impacts, not all of which are negative (Sections 6.1.4, 6.5.2 and 6.5.3). For example, water- and ice-related damage as well as disruption of aquatic life and habitat are partially balanced by the replenishment of fragile ecosystems with water and nutrients. River ice jams are known to occur in all Arctic and sub-Arctic regions (Catalogue on ice jams in the former USSR, 1978; Beltaos et al., 1990; White and Eames, 1999; Beltaos and Prowse, 2009).

As soon as mild weather sets in (normally in spring), river-ice covers begin to experience thermal and hydro-mechanical change. Factors that *resist* ice-cover dislodgement, such as thickness, strength and attachment to channel boundaries, diminish. At the same time, factors that promote or *drive* dislodgement, such as hydrodynamic forces and water-surface width, increase. This concept is illustrated in Figure 6.13, which traces the evolution of driving and resisting factors, termed ‘forces’ for simplicity, during the pre-breakup period. Break-up is initiated when the driving force exceeds the resisting force. If the resisting force (point A) is near the lower limit of the driving force, negligible or no jamming occurs, and the break-up event is termed ‘thermal’ to signify that it is dominated by thermally induced decay of the ice cover. Non-thermal events are called ‘mechanical’ because the ice cover retains a significant amount of its mechanical competence when it is first dislodged. The upper part of the mechanical range is termed ‘dynamic’ because the break-up is now dominated by the large driving forces. Major ice jams and javes typically occur during dynamic break-ups.

In the Arctic, dynamic break-up and jamming events are typically driven by large spring runoff that primarily results from rapid snowmelt, which often occurs in southern, sub-Arctic portions of large river basins. Where the general flow direction is northward, the rising flows encounter increasingly competent ice cover, owing to spatial gradients in air temperature. Rainfall may be a significant spring runoff factor in sub-Arctic regions, and a dominant one for mid-winter break-ups. The latter are triggered by rain-on-snow events and lead to highly dynamic conditions.

Changes in the flooding potential of ice jams and javes are difficult to detect and quantify because they involve highly complex phenomena and hydro-climatic interactions. As a result, relevant literature about climate interactions and the severity of ice jams, particularly at high latitudes, is relatively scarce. The following is indicative of the current knowledge base. In northwestern Canada, a slight trend toward increasing peak annual break-up water levels beginning in the 1970s has been detected for the Yukon River at Dawson (latitude ~64° N) (Janowicz, 2009). Ice break-up on Alaskan rivers moderated during the 1995 to 2005 period, but the particularly destructive 2009 break-up (Janowicz, 2009) may be heralding a different trend. In sub-Arctic Canada, trends toward more frequent mid-winter floods and more severe spring floods have been detected in a few case studies (Beltaos, 2002, 2004; Prowse et al., 2002a).

On Russian rivers, the risk of ice-jam flooding increases from south to north and west to east, while there is a temporal trend toward more severe events on rivers in eastern Siberia (Buzin, 2007; Buzin and Kopalani, 2008). This is exemplified by the Lena River (Figure 6.14), where the catastrophic flood of 2001 devastated the city of Lensk. Elsewhere in Russia, there is a diverse pattern of change. In some regions (northern and central European territories of Russia and western Siberia), almost no change has been observed. For Scandinavia, mid-winter break-




Figure 6.13. Schematic illustration of driving and resisting factors leading to different types of river-ice break-up events. Point A refers to a spring break-up and point B to a mid-winter event with smaller decreases in ice resistance because of lower levels of incoming solar radiation. Adapted from Beltaos (1982).

up events in Norway (Knut Alfredsen, Norwegian University of Science and Technology, Trondheim, pers. comm., 2009) appear to be occurring more frequently and with more severity in recent years, but similar to most other regions, no analysis has yet been published.

It is difficult to project how a changing climate will affect the frequency and severity of ice-jam floods and javes, owing to the multitude of relevant hydro-climatic controls (Section 6.3.2), although some attempts have been made. Beltaos and Prowse (2009) discussed how each climatic control may affect ice-jam regimes under a changing climate, but cautioned that projection of the synergistic effects of all controls requires detailed, site-specific studies. For example, the projected changes in thermal gradients along rivers are likely to affect river-ice dynamics (see Section 6.4.3). This effect may be negated, however, by an earlier melt, which will result in reduced pre-breakup insolation and associated ice decay. The latter effect is illustrated in Figure 6.13, which indicate that (other factors being equal) the pre-breakup decrease in resisting force would be less pronounced under an earlier-melt regime.

A relatively general projection is that mid-winter break-up and associated dynamic ice jams will increasingly intrude into higher latitudes of the Northern Hemisphere (Prowse et al., 2002a; Beltaos and Burrell, 2003; Prowse and Bonsal, 2004; Beltaos and Prowse, 2009). Such intrusion is not likely to affect Arctic areas where the winters will remain uniformly cold despite future warming, but there is already evidence of the northward shift of mid-winter break-up. On the Klondike River (Yukon Territory, Canada), an unusual period of mild weather and rain in December 2002 resulted in early break-up and jamming (Janowicz, 2009). Although this jam only caused minor flooding at the time, it froze in place when the cold weather resumed, creating a thick 'plug' with major spring break-up implications: in late April 2003, the lower Klondike valley experienced one of the most severe break-up floods on record.

For Norway, downscaled scenarios from climate models suggest that more frequent ice runs are likely to occur in the future, with possible jamming at new locations (Asvall, 2009), whereas more 'frazil-risk' days can be expected in Finland

(Huokuna et al., 2009). Some attempts have been made to predict changes in future ice-jam flood conditions for Russian rivers. For example, research at the Russian State Hydrological Institute evaluated conditions for the very near-term period of 2010 to 2015, based on the results of the HadCM3 and ECHAM4 GCMs for two climate change scenarios. Changes to flood magnitudes were assessed using regional correlations with river discharge. The following describes the major results regarding ice jams, as summarized by Buzin (2007) and Buzin and Kopalani (2007, 2008). In general, the authors concluded that with the expected rise in river discharge in winter, there would be an increased probability of major ice jams in spring. Some of this is due to change in streamwise thermal gradients (see Section 6.4.3). A recently discovered feature of downstream ice clearance is that the break-up front on the northward-flowing Russian rivers is often delayed at latitudes of 58° to 60° N due to sharp spatial gradients in spring air temperature. At this point under an altered future climate, the positive-sign anomalies in the upper reaches of the rivers change to negative-sign anomalies further downstream and result in powerful ice

Maximum ice-jam water level, m




Figure 6.14. Chronological diagram of maximum ice-jam water levels on the Lena River near the city of Lensk, Russia. The vertical axis represents water level referenced to a local datum. The red line refers to the local level of flood inundation. Data provided by V. Vuglinsky, Russian State Hydrological Institute.

jams. The projection shows that spring ice-jam floods on the Lena River and other Siberian rivers will become more frequent (1.2 to 1.5 times more frequent) and more severe (a 35% to 60% increase in peak break-up water levels). In northern parts of the European territories of Russia, recurrent ice jams are expected on the rivers Severnaya Dvina, Sukhona, Vug, and Pechora. On average, maximum jam levels might increase 10% to 12% and on individual river sections 36% to 48%. However, the frequency of flooding is projected to increase by a factor of 1.2, at most. Many populated areas on the shores of these rivers (Shenkursk, Kholmogory, Archangelsk, Naryan-Mar) are expected to be periodically flooded. In this region, there is also a threat of powerful spring ice jams on the Sukhona River near the city of Veliky Ustyug. The water level elevation caused by an ice jam would increase 24% to 36%, compared to the highest level under stationary conditions. These estimates of potential change in the frequency and scale of ice-jam floods should be considered as averaged over large territories, and may be different for individual rivers and river reaches.

The location and severity of ice jamming can be modified not only by changes in thermal gradients (see Section 6.4.3), but also by changes in hydraulic gradients. While differential changes in water levels among intersecting rivers and lakes could have this effect, the largest changes in hydraulic gradient are likely to result at river mouths and deltas that enter marine systems (e.g., see Arctic mega delta discussion by Anisimov et al., 2007). This is because of the anticipated rise in sea level, which is projected to be significant even over the next 100 years. Increases as high as those predicted by the IPCC (e.g., 0.18 to 0.59 m; Bates et al., 2008) or in more recent analyses that place more focus on rapid changes in ice-sheet flow (e.g., 0.7 to 2.0 m; Pfeffer et al., 2008; Grinsted et al., 2010; also see Section 11.2, this volume, on sea level change) are more than ample for the sea level to extend significantly back up into low-slope, Arctic river deltas. The net rise (relative to the land) may be moderated or enhanced by concurrent vertical motions of the land surface. For example, glacio-isostatic adjustment varies considerably around the Arctic, from uplift in the Canadian Archipelago, Greenland and Norway, to subsidence along the Beaufort Sea and Siberian coasts (Walsh et al., 2005). Tectonic motion and local loading of the crust by sediment (e.g., in river deltas) can also cause vertical adjustments.

Overall, a net rise in sea level would shift the location where the river water surface meets the largely flat profile of the sea-controlled channel (Beltaos and Prowse, 2001). At such sites, the water surface slope decreases sharply, thereby enhancing hydraulic conditions conducive to ice jam formation (e.g., Beltaos, 1995b). The higher the base level rise, the further upstream such effects are likely to migrate (Figure 6.15). Riverside communities and nearby infrastructure may be particularly vulnerable. At the same time, riparian ecosystems that depend on regular flooding generated by ice jams for replenishment could also be affected (see Section 6.5.2.3). Such changes could be further exacerbated by a related upstream increase of naturally-built levee height from lateral, ice-jam induced sediment deposition (Hill et al., 2001), which would in turn lead to reduced frequency of overbank flooding in areas still subject to ice jamming.

In general, projections for specific rivers and sites will require quantitative analysis of many factors, in addition to

purely climatic variables that can be furnished by GCMs and RCMs under specific greenhouse gas emissions scenarios. Such factors include the flow hydrograph during the entire ice season (autumn, winter, spring), freeze-up levels, ice-cover thickness and strength, as well as river planform, bathymetry, and hydraulic characteristics. The effects of changes in these factors on the severity and frequency of ice-jam floods could be assessed using numerical process models (Liu et al., 2006). However, serious gaps in the quantitative knowledge of break-up processes remain an impediment to accurate prediction (Beltaos, 2008e).

6.5.1.2. River-flow abstraction

Hydrological extremes produced by ice on northern rivers include not only flood-related phenomena, but also low flows. Flow minima are especially important where rivers are used, for example, to supply municipal or industrial users or in the dilution of wastewater. The occurrence and magnitude of low flows during the ice season are directly affected by ice formation, which entails three types of flow abstraction via temporary storage of water (Gerard, 1981, 1990; Beltaos and Prowse, 2009), all of which are sensitive to climatic variability and change. The first and most obvious is the storage due to freezing of river water to form the ice cover. This effect is most pronounced shortly after freeze-up when ice growth is most rapid. Although generally negligible on large rivers, this type of abstraction can be significant in very small streams, especially during the freeze-up period. Less obvious, but far more pronounced, are the two other abstraction mechanisms: icings and hydraulic storage.

Icings (Section 6.1.2) can be so extensive in some northern systems that they significantly reduce the magnitude of flow on downstream larger-order rivers (e.g., Gerard, 1981; Sokolov, 1986). Icings effectively sequester baseflow during the winter months, thereby enhancing low flows, and then release water during the summer. Yoshikawa et al. (2007) estimated that an icing field in the Kuparuk River in Alaska stores around 27% of potential winter baseflow. Some accumulations are so large that they control the routing of flow during spring melt and sustain flow during the warmer summer months (e.g., Grey and MacKay, 1979). In extreme cases, icings tend to be relatively permanent features of rivers. For example, the Kongukut River in Alaska has an existing icing field that was first observed by the Franklin party in 1828. Aerial photography shows that this and many other icings in Alaska have not changed in extent during the past 50 years (Yoshikawa et al., 2007), although their future existence and role in the hydrological cycle depends on future climatic conditions.

The hydraulic storage of water also greatly influences low-flow conditions both on large and small Arctic rivers. In general, the presence of an ice cover causes channel water levels to rise, owing to its additional hydraulic resistance and flotation depth (keel). As the ice cover continues to propagate upstream, a fraction of the incoming flow is abstracted to fill the space created by the higher stage and, consequently, downstream flow is reduced. Beltaos (2009) showed that relative abstraction (expressed as a fraction of the incoming flow) increases with increasing concentration of ice arriving at the upstream edge of the ice cover, but decreases with increasing thickness of the




Figure 6.15. Schematic illustration of potential change resulting from a rise in the base level of a river. Water surface slope decreases sharply at point 1. With a net rise of the base level, frequent jamming that occurs near point 1 will shift to point 2.

newly formed cover. Hydraulic storage abstraction ceases once the process of ice-cover formation is completed although this can last for many weeks during the autumn freeze-up period on large northern rivers. Importantly, this ice-induced low flow can be the flow minimum for the year, even lower than that which occurs during the main winter period when landscape runoff is at a minimum (Prowse and Carter, 2002). Moreover, the final release of this water at the time of the succeeding break-up event can significantly augment the spring snowmelt event, although this is rarely accounted for in spring freshet analyses. On the Mackenzie River in Canada, for example, Prowse and Carter (2002) found that almost 20% of the spring freshet could be due to the release of water abstracted during the previous autumn freeze-up (Figure 6.16) and the percentage would be even higher if the melt of ice-stored water was also included.

Icings and freeze-up are both highly sensitive to change in heat exchange at the river surface, and hence the amount of ice forming. Other factors being equal, warmer freeze-up weather would result in reduced abstraction and, thus, improved low-flow conditions. If icings shrink or even disappear, however, then the seasonal hydrograph on icing-dominated systems will change, much in the same way as when glaciers disappear and are no longer available to supply baseflow during the late summer dry periods (see Chapter 7). This could have important implications for aquatic biota (see Section 6.5.2.2), especially if the icings (e.g., those largely accumulating from groundwater sources) also play an important role in determining stream water chemistry.

An indirect climatic control pertains to freeze-up discharge, which influences the initial thickness of the ice cover. Although projections remain to be finalized (Bates et al., 2008), it is generally believed that because of changes in precipitation and permafrost regimes, autumn flows are likely to increase in northern river systems. Higher flow velocities are likely to lead

to thicker ice accumulations, but given that ice thickness is also likely to decrease because of generally warmer temperatures, the final combined effect of these two factors on ice-induced low flows remains uncertain.




Figure 6.16. Occurrence of low-flow depression from ice-induced hydraulic storage and subsequent release during the spring freshet in the Mackenzie River, Canada. Storage occurs during autumn freeze-up (November), shown as the dark blue area of the declining hydrograph in about November to December. The line above the depression indicates assumed flow without this effect. Release of stored flow occurs during the spring hydrograph noted by dark blue shading. The magnitude of spring events is likely to decrease if ice-storage effects in seasonally transferring water are lost under future climatic conditions. After Prowse and Carter (2002).

6.5.1.3. Lake water budgets and flow enhancement

Lake ice plays an important role in the evaporation regime of northern lakes, as was reviewed in Section 6.3. Specifically, its reduction with climatic warming, along with increased summer heating of the open water, should increase lake evaporation. The significance of this process is likely to be more important for shallower lakes than deeper lakes, at least in the early stages of climatic warming. Overall, shallower lakes are more sensitive to enhanced warming because of the shorter duration of their ice cover and more rapid heating during the open-water period due to their lower volume to surface area ratios. Greater total heating will mean proportionately more evaporation and, when combined with their shallower depths, translate into larger relative decreases in water level. Prowse et al. (2006) suggested that some very shallow (e.g., <1 to 2 m) northern basins are likely to dry out and possibly become athalassic saline systems, unless there is a compensating increase in water inflow from increased precipitation. This may already be occurring based on evidence provided by Smol and Douglas (2007b). They suggest that, despite wetter conditions, a recent increase in evaporation due to higher temperatures and extended ice-free conditions has led to the complete summer drying of some ponds in the Canadian High Arctic that had been permanent water bodies for millennia. By contrast, for winter periods decreases in ice-cover thickness are likely to increase the unfrozen water volume of some lake systems, particularly those that currently freeze to the bed (e.g., Figure 6.17).

Change in precipitation on lake-ice covers is also apt to produce an additional hydrological effect via snow loading and volume displacement. Winter loading of lake ice by snow tends to depress the ice cover and force water from the lake basin into outlet streams, causing an increase in downstream discharge (e.g., Prowse, 2005, 2009). Such additions are important modifiers of the winter flow regime, particularly in areas of low winter discharge. The effect increases in direct proportion to the snow load to ice thickness ratio. Assuming that future climate will lead to an increase in snow load and a decrease in ice thickness, winter flows from northern lakes should be enhanced, although the timing and magnitude will be determined by the characteristics of future winter precipitation events. For example, if future precipitation is concentrated into fewer higher magnitude events, as some models predict, winter spikes might develop in the flow of northern rivers.

6.5.1.4. Sediment transport and geomorphology

Although lake ice is known to produce some geomorphological effects on lake shorelines, the dynamics of river ice are most important to the fluxes of sediment and changes in riverine morphology (e.g., Prowse, 2005). Climate change is likely to cause major changes in river ice dynamics (see Sections 6.4.3 and 6.5.1.1), particularly along the long northward-flowing rivers. The Arctic Climate Impact Assessment (Walsh et al., 2005; Wrona et al., 2005) noted that changes in river ice regimes would affect channel-forming processes, suspended sediment transport to the Arctic Ocean, and the productivity of riparian, delta, estuarine, and marine shelves near coastal margins.

As context for understanding how the geomorphological

role of river ice will change under an altered climate, it is important to recognize that ice plays a dual role in high-latitude fluvial geomorphology, acting as a resisting force keeping material intact and as a driving or erosive force. An example of the former is where ice is frozen to the stream bed (e.g., anchor ice) and effectively shelters sediments from the erosive actions of streamflow (e.g., McNamara et al., 2008). The loss of protective layers of bedfast ice under a warming climate could, therefore, produce enhanced erosion.

Significant changes are also likely to result from increases or decreases in the erosive forces of ice, particularly those associated with javes and ice jamming, which are characterized by high stage and flow velocities (Section 6.5.1.1). As reviewed by Prowse (2005), some of the major effects of ice as a driving force include the following:

- concentration of flow and bed scour leading to changes in the position and/or depth of the thalweg (deepest line of the river channel)
- suspended sediment concentrations during break-up that can be several times the equivalent discharge under open-water conditions
- increased material size and magnitude of bed load transport from break-up javes
- creation of erosional features such as high-level benches and undercut banks
- over-steepening of banks and initiation of slope failures, particularly in areas where ice-rich permafrost is exposed
- depositional features along banks varying from localized boulder accumulations (boulder buttresses, barricades, ridges, pavements) to thick layers of sediment, which can raise bank heights and are a particular development feature of northern deltas.




Figure 6.17. Images from ERS-1 (top: 20 April 1993) and ERS-2 (bottom: 16 April 2003) satellites showing ice cover over an area of the North Slope of Alaska (Sagavanirktok River). The light blue areas on the shallow lakes and river channels indicate the presence of ice with water underneath, while the dark blue and black areas represent lakes and river channels that are frozen to their bed (i.e., grounded ice). In 1993, the conditions were colder (thicker ice) than in 2003, which explains why more ice was frozen to the bed. Source: unpublished data but based on techniques outlined by Brown et al. (2010).

One overarching and highly important geomorphical effect of river ice is its erosive action in modifying channel widths. While some studies have hypothesized that channels are enlarged by break-up ice erosion accompanying infrequent high-stage events, other evidence has suggested that overbank losses of flow due to ice jams may even promote channel narrowing (reviewed by Prowse, 2005). More recently, however, additional information (Boucher et al., 2009; McNamara and Kane, 2009) confirms that ice erosion can produce enlarged channels if a minimum ice-jam frequency is exceeded. Hence, it is likely that changes in the break-up dynamics of northward-flowing rivers will have major consequences not only for their sediment transport regimes, but also for their overall morphology. Morphological features that affect the capacity of a channel to convey floodwater and those that affect habitat are most significant (Prowse and Culp, 2008).

6.5.2. Ecological effects

- Changes in the timing of freeze-up and break-up on lakes will affect a wide range of related biological aspects of seasonality.
- Some changes are likely to be gradual, but others are likely to be more abrupt as systems cross critical ecological thresholds; positive and negative effects will result.
- Changes in ice-induced hydrological connectivity and lake stratification could lead to the loss of some species and the establishment of others.
- Changes in river ice are also likely to have wide-ranging effects on the behavior and biological response of stream biota; positive and negative effects will result.
- Changes in river dynamics associated with break-up are of particular concern because of their effect on river geomorphology, vegetation, sediment and nutrient fluxes, and sustainment of riparian aquatic habitats.

6.5.2.1. Lentic systems

High-latitude lakes are covered by ice for six to twelve months each year, and this has a wide-ranging influence on their ecology. Future changes in lake-ice conditions may cause shifts in physical, chemical, and biological properties, including increases in the duration of open-water conditions and subsequent availability of light for primary production. Some changes, however, may be more abrupt as the lake crosses critical ecological thresholds (e.g., step changes in the stratification regime or the loss of ice dams that retain some freshwater lakes in the High Arctic) (Wrona et al., 2006).

6.5.2.1.1. Physical effects

The most critical climate thresholds for lake ecosystems are those affecting the area and volume of standing water, while changes in the ice regime and surrounding catchments can have major impacts on aquatic habitat size and integrity and geochemical inputs (Vincent and Laybourn-Parry, 2008). In general, such changes are most apparent for relatively shallow systems, in some cases leading to their complete disappearance. For example, permafrost thawing and the production of surface

to groundwater flow systems have been responsible for the elimination of many small water bodies in Siberia (Smith et al., 2005). Similarly, increased evaporative losses related to decreases in ice-cover duration (see Section 6.5.1.3) can lead to the loss of aquatic habitats, such as the drying of High Arctic ponds (Smol and Douglas, 2007b). In other regions the accelerated melting of permafrost over the past 50 years has created new basins for lakes and ponds, and increased development of shallow-water ecosystems (Payette et al., 2004; Walter et al., 2006).

The surface area and depth of lakes and ponds affect ice formation. For example, lakes shallower than about 2 m regularly freeze to the bottom (i.e., lake ice typically forms to 2-m depth in most regions of the Arctic). Two possible consequences exist if the ice regime is altered. If winters become locally warmer and precipitation (as snow) increases, then ice thickness will decrease. Consequently, habitable depths for shallow lakes and ponds on tundra previously frozen to the bottom are likely to increase and enhanced invertebrate and/or fish survival may be possible (see Section 6.5.2.1.3). Another potential consequence will be a more rapid ice loss the following spring (related to a thinner ice cover) leading to an earlier open-water season and an earlier start to spring and summer production.

For some polar lakes, ice dams from glaciers or ice shelves are the primary structures retaining the freshwater, and their collapse can result in catastrophic drainage (e.g., Mueller et al., 2003; Vincent et al., 2009). The seasonal production and melting of ice dams along the Arctic coastline are responsible for stamukhi lakes (see Section 6.5.2.3), which are important biogeochemical processing sites for large river inputs to the Arctic Ocean that may be subject to climate-related impacts in the future (Galand et al., 2008a).

Climate change is resulting in earlier dates of ice break-up (see Section 6.4.2) and, for extreme High Arctic lakes, is resulting in the onset of summer ice-free conditions in lakes that in the past have been covered by perennial ice (Mueller et al., 2009; Vincent et al., 2009). Both snow and ice affect underwater ultraviolet (UV) radiation and photosynthetically available radiation (PAR). For example, in early June in meromictic (permanently stratified) Lake A on Ellesmere Island the under-ice PAR was only 0.45% of above-ice values. Removal of snow from a 12 m² area on this lake resulted in a 13-fold increase in PAR under the ice and a 16-fold increase in biological exposure to UV radiation (Belzile et al., 2001). Model results suggested that such changes in snow cover would have a much greater effect on underwater UV exposure than moderate stratospheric ozone depletion (Vincent et al., 2007). In some ice-covered lakes, much of the photosynthetic production in the water column is associated with a deep maximum of phytoplankton or photosynthetic sulfur bacteria. In Lake A, past changes in planktonic production as inferred from pigment concentrations in sediments may be attributable to climate-related changes in snow and ice cover (Antoniades et al., 2009).

For some lakes, the loss of ice can result in the loss of vertical habitat structure and cooling (Vincent et al., 2008a). As part of the modeling of broad spatial patterns of changes in lake ice noted in Section 6.4.3, Dibike et al. (2010) evaluated changes in water temperature and thermal structure in lakes across the

Northern Hemisphere. For example, Figure 6.18 shows the mean annual cycle of simulated water-temperature profiles in hypothetical lakes of 20-m depth along longitudinal transects at 105° W and 90° E, representing cross-sections through central continental areas of North America and Asia, respectively. For the two selected profiles, higher-latitude lakes along 105° W show less summer stratification than those along 90° E, which could be due to differences in relative coldness and/or elevation of the two regions. As noted by the authors, the projections are only intended to evaluate broad spatial patterns, and more site-specific modeling of lake types at higher spatial resolution is required to probe such regional differences. In general, however, results suggest that future warming will result in an overall increase in water temperature, with summer stratification starting earlier and extending later into the year.

Warming of the underlying water column by radiation is controlled to varying degrees by the thickness and composition of the snow- and lake-ice cover; white and black ice, for example, have different levels of albedo and transmissivity. In combination with water color and transparency, this affects heating rates, depths and mixing (e.g., Cahill et al., 2005). Earlier thinning and loss of ice cover also contribute to enhanced heating of the water column, which ultimately sets conditions for earlier and shallower development of the thermocline by increasing temperature differentials between surface and bottom waters. Longer open-water periods can further enhance overall lake warming, the combined effect being to drive high-latitude lakes from monomixis (a single period of mixing each year) to dimixis (the water column stratified for part of the summer). This threshold effect as a




Figure 6.18. Modeled mean annual cycle of daily profiles in water temperature in lakes during (a and b) 1960–1999 and (c and d) 2040–2079 as well as (e and f) the corresponding change between these periods at 5° latitude intervals along example longitudinal transects on (a, c, and e) 105° W and (b, d, and f) 90° E. Source: Dibike et al. (2010).

result of water temperature rising above the point of maximum density ($\sim 4^{\circ}\text{C}$), can affect many other habitat properties, such as nutrient regimes and water-column oxygenation (see also Section 6.5.2.1.3).

6.5.2.1.2. Chemical effects

The unproductive lakes of the Arctic strongly reflect processes operating in the contributing catchments. For example, direct linkages between terrestrial processes and dissolved organic carbon (DOC) concentrations in lake waters are well known. Terrestrial DOC plays a key role in aquatic ecosystems as it affects primary and secondary productivity, community structure and metabolic balances, availability of dissolved nutrients and metals, and the thermal structure and optical properties of water bodies. Temporal changes in DOC concentrations have been attributed to changes in runoff, temperature, solar radiation, soil moisture, growing season length, and atmospheric deposition chemistry (Williamson et al., 1999 and references therein). Changes in the seasonal variability can also have far-reaching biological consequences (Weyhenmeyer, 2009a). In Sweden, for example, water chemistry changes in lakes are still more pronounced south of the Arctic (Weyhenmeyer, 2008, 2009b), but this could change in response to the accelerated thawing of permafrost (see also Chapter 5).

Lake ice has a controlling influence on oxygen conditions, and even moderately productive lakes can be driven to anoxia during winter ice conditions (e.g., Laurion et al., 2010). This in turn affects a great variety of biological and biogeochemical processes. The shift of lakes from cold monomictic (continuous mixing in summer) or polymictic (multiple episodes of mixing in summer, favored by cold temperatures; e.g., Lac à l'Eau Claire in Nunavik, Canada; Milot-Roy and Vincent, 1994) to dimictic (stratified in summer) will increase the possibility of oxygen depletion and even anoxia in the bottom waters during their periods of summer stratification, thereby reducing habitat availability for high oxygen-demanding biota such as Arctic char (*Salvelinus alpinus*). Conversely, the corollary of such conditions is a shorter duration of winter ice cover, which acts as a barrier to oxygenation from the atmosphere and prevents wind-induced mixing. In northern temperate lakes, severe oxygen depletion under the ice can lead to the 'winter kill' of resident fish. This is likely to be reduced in a warmer climate with reduced ice duration, with potential cascading effects on lower trophic levels (e.g., Balayla et al., 2010).

Thermokarst or thaw lakes, a major class of high-latitude aquatic ecosystems, are also sensitive to shifts in oxygen. Lake ice affects the concentration of greenhouse gases in two ways: by acting as a physical barrier to efflux to the atmosphere, and by modifying oxygen tension in the water column and sediments that in turn affect the balance of methanogenesis (production of methane) versus methanotrophy (breakdown of methane). The production of methane (methanogenesis) by microbes in lake sediments is an anaerobic process favored by anoxia. Anoxia is common year-round in organic-rich lake sediments and within centimetres of the sediment-water interface due to microbial oxygen consumption that exceeds the rates of oxygen diffusion through the water column and sediments. Anoxia in lake bottoms is enhanced during summer and winter stratification. These effects are receiving increasing attention in permafrost thaw lakes (thermokarst

lakes and ponds) (Vincent and Laybourn-Parry, 2008). Water-column profiles and surface sediment analyses of dissolved gases (carbon dioxide and methane) in 34 shallow monomictic and deeper dimictic thermokarst lakes of the Kolyma lowlands during 1994, 2002, and 2010 showed anoxic conditions and high methane concentrations prevalent in surface sediments of all lakes (Zimov et al., 2001). Concentrations of dissolved gases were significantly elevated in the bottom waters of stratified Siberian thermokarst lakes, a phenomenon that has long been observed in non-thermokarst lake systems (Rudd and Hamilton, 1978; Michmerhuizen et al., 1996). Breton et al. (2009) also observed widespread supersaturation of methane in 46 Nunavik lakes regardless of mixing regimes. Studies in the Nunavik thaw ponds show that some are highly stratified and likely to be producing methane in their anoxic bottom waters for almost all of the year (Laurion et al., 2010).

Methane production in thermokarst lake sediments continues throughout the winter ice-cover period (Walter et al., 2006, 2008a). Spring ice melt in thermokarst and non-thermokarst lakes releases large quantities of methane and carbon dioxide to the atmosphere via diffusion (Michmerhuizen et al., 1996; Phelps et al., 1998) and ebullition (Walter et al., 2008a). In winter, methane bubbles released from the lake bottom by ebullition become entrained in lake ice as it thickens at the surface (Walter et al., 2006; Figure 6.19). Some gas escapes during winter as bubbles move beneath the ice to cracks or open-hole hotspot seeps, where vigorous rates of bubbling can maintain relatively ice-free holes year round. However, large volumes of methane are trapped and stored in lake ice throughout winter and released to the atmosphere during spring ice melt (Walter et al., 2008a).



Figure 6.19. Methane bubbles trapped within lake ice cover (top: photo by Katey Walter Anthony as part of a NASA-funded research project) and ignition of methane when released and lighted (bottom: UAF photo by Todd Paris).

The bubbles in the ice provide information on the location of discrete methane-seep production in lakes and can be detected by SAR, which may provide a remote sensing approach to scaling up estimates of methane fluxes to the regional and circumpolar scale (Walter et al., 2008b).

Loss of ice cover and associated enhanced warming of these permafrost lakes could greatly increase methane production from the vast wetland-lake regimes of northern latitudes (Section 6.1.3) (Nozhevnikova et al., 1997; Metje and Frenzel, 2007). However, thermodynamic controls over biological methane production also affect methane oxidation, commonly an aerobic (oxygen-requiring) bacterial process that converts methane to the less potent greenhouse gas carbon dioxide (Rudd et al., 1974) and enhances oxygen depletion under ice (Rudd and Hamilton, 1978). The net balance of the two processes in scenarios of future warming in lakes is uncertain, although short-term sediment warming experiments on Swedish lake sediments suggested that temperature sensitivity was a stronger control over methane production than oxidation, which was governed by substrate availability (Duc et al., 2010). This implied that elevated temperatures will enhance methanogenesis, which may cause increased methane release from sediments until methane oxidation increases in response to higher methane levels. The end result is difficult to predict, especially as changes in the oxygen dynamics of high-latitude lakes induced by ice-related shifts in water budgets and levels, stratification, and mixing could also affect the relative balance of methanogenesis and methanotrophy. Relevant greenhouse gas studies of these types of lentic systems include those by Walter et al. (2006, 2007a,b, 2008a,b), Breton et al. (2009), Duc et al. (2010), and Laurion et al. (2010).

Ice cover and the associated thermal stratification (Section 6.5.2.1.1) play a significant role in the fate of contaminants supplied to northern lakes, such as by stream inflow or direct atmospheric deposition. In the case of inflow, thermal structure is known to affect the amount of contaminant retention. For example, in Amituk Lake of the Canadian High Arctic 59% of the annual mercury load flowing into the lake traversed the lake as a mercury-rich buoyant current immediately beneath the ice, ultimately leaving the lake via its outflow. Only later in the summer, when the ice had disappeared and the water column had warmed to become isothermal, did the inflowing mercury and other solutes mix into the lake water (Semkin et al., 2005). The inflow of contaminants under changing ice conditions is of particular concern because their inflow to lakes might be enhanced by other cryospheric changes on the landscape (e.g., thawing permafrost and melting of snow and glaciers) that result in the release of historically deposited contaminants (e.g., Klaminder et al., 2008; Faïn et al., 2009). In the absence of lake inflow, ice cover and associated thermal stratification may still play a role in influencing the vertical distribution of contaminants.

Changes in ice cover are also likely to affect the fate of volatile chemicals deposited directly from the atmosphere. Lake sediment records are commonly used to investigate trends in contaminant levels (Stern et al., 2005; Outridge et al., 2007; Muir et al., 2009) and carry the potential to distinguish between possible climatic effects and changes in atmospheric deposition of (mostly volatile) contaminants to lakes and surrounding catchments. In general, an expansion of the ice-free period will result in a

shorter period during which contaminants can re-volatilize from the snow and ice cover but a longer period for direct deposition to the lake water. For photosensitive contaminants that enter ice-covered lakes, alterations to the light regime produced by changes in ice-cover thickness and composition (see Section 6.4.3) could alter their chemistry (e.g., Hammerschmidt et al., 2006), although little is known about the role played by photosensitivity in the overall cycling of contaminants. In general, in-lake production, metabolism, and (photo-)degradation rates of certain contaminants may be enhanced by longer ice-free periods (Hammerschmidt et al., 2006).

Opening of ice-free zones and increases in water temperature from the loss of ice cover may also affect in-lake processing of contaminants. Greater methylation of mercury, for example, is likely to result from higher temperatures, particularly in shallow zones. Higher water temperature is also likely to increase pelagic production and thereby enhance algal scavenging of mercury, a proposed entry pathway for mercury to food webs (Outridge et al., 2007). Overall, higher water temperatures associated with a decrease in ice cover, and related changes in food and energy pathways and/or productivity (benthic to pelagic), are likely to modify contaminant transfer through such lakes (Chételat and Amyot, 2009; Carrie et al., 2010; Gantner et al., 2010a,b).

6.5.2.1.3. Biological effects

Ice is a key physical component that both structures and regulates abiotic and biotic processes within Arctic aquatic ecosystems. Biotic responses are induced at an individual, population, or community level depending upon the nature (rate, direction, magnitude, spatial scale) of abiotic change. Accordingly, shifts in ice characteristics will cascade through ecosystems, resulting in widespread alterations. For example, in addition to effects at the individual level (e.g., displacement from preferred habitat, alteration in growth rates) and population level (e.g., changes in distribution and abundance), changes in ice will affect trophic coupling, potentially engender mismatches between physical drivers and biotic responses, and affect phenological events such as the timing of key system transitions and life history shifts in biota.

In the case of photosynthetic production in lakes, the duration of open water is particularly critical. For example, the 250 000-year paleolimnological record from Lake El'gygytyn, an ancient crater lake in the Siberian Arctic, suggested that periods of the highest primary productivity were associated with warm, ice-free summer conditions, while the lowest rates were associated with periods of perennial ice coated by snow (Melles et al., 2007). In addition to improved light conditions for photosynthesis, measured levels of primary productivity could be further compounded by alterations in other environmental factors, such as increased wind-induced mixing and entrainment of nutrients into the euphotic zone (the surface layer with enough light for net photosynthesis), and catchment geochemical inputs.

Changes in the timing of freeze-up and break-up on lakes will also affect important biological aspects of seasonality, which is defined as a predictable change or pattern in a time series that recurs or repeats over a one-year period. For example, the seasonal succession of plankton has been well described in many north temperate lakes and is strongly

coupled with the freeze-up and break-up of ice cover and summer thermal stratification (Sommer, 1989). A variety of structural and functional ecosystem changes in such lakes have been coupled to the changes in seasonality, in particular to an earlier ice break-up and an earlier onset of stratification, and provide insights into how Arctic lakes may respond. One of the most obvious effects of an earlier timing of temperate lake-ice break-up has been an advanced spring phytoplankton bloom (Weyhenmeyer et al., 1999; Gerten and Adrian, 2002; Winder and Schindler, 2004; Peeters et al., 2007) often resulting in an earlier zooplankton biomass peak (Straile, 2000; Gerten and Adrian, 2000). However, a synchronous response to these higher spring temperatures is usually restricted to fast-growing plankton, while slow-growing species with complex life histories show species-specific responses (Winder and Schindler, 2004; Adrian et al., 2006).

Changes in lake-ice regimes will have significant impacts on primary productivity and related trophic relationships in Arctic lakes. For example, increased temperatures and stratification associated with decreases in ice cover, accompanied by larger nutrient inputs, may favor the development of certain phytoplankton. In the case of noxious blooms of cyanobacteria, this could be a significant concern. Seasonality of the plankton is also likely to be affected by temporal changes in ice coverage given that flagellate plankton have been observed to be abundant below the ice in Arctic lakes, whereas diatoms appear once ice is gone. In general, although photosynthesis does take place beneath an ice cover, it is expected that primary production will increase with decreased ice thickness and snow cover (e.g., Vincent et al., 2008c). Evidence for this is provided by present conditions where snow-free ice conditions can lead to bloom concentrations of photosynthetic flagellates (Weyhenmeyer et al., 1999). However, in Arctic regions projected to experience increases in surface accumulations of snow and/or the formation of white ice (see Section 6.4.3), under-ice plankton abundance could be negatively affected. Such changes in snow and white-ice coverage are also likely to affect levels of secondary productivity. Fish production in northern alpine lakes, for example, has been linked to snow depth (e.g., Borgström and Museth, 2005; Prowse et al., 2007b).

Changes in water-column stratification associated with increased duration of open water can potentially result in the loss of some species and the establishment of others. For example, the diverse, highly stratified communities of single-celled Archaea in High Arctic lakes are likely to be disrupted by future changes in ice cover (Pouliot et al., 2009). By contrast, increased open water can allow the development of new trophic levels and even the establishment of aquatic bird species (Vincent et al., 2009). Warmer, more nutrient-rich dimictic conditions may also favor cladocerans (see Sorvari et al., 2002). Importantly, this could result in increased bioaccumulation of methylmercury relative to copepod-dominated zooplankton communities (Chételat and Amyot, 2009), with the potential for increased mercury transfer to fish and humans, although effects of biodilution may counteract this effect (Gantner et al., 2010a).

Depending upon latitude, as well as lake characteristics such as depth, morphometry, and elevation, early thermocline development (Section 6.5.2.1.1) will profoundly alter lake ecosystems as well as the cold-water fish species present. Using lake trout in North America with temperature preferences of

10 to 12 °C as an example, under climate warming southern (southern boreal) lakes will experience earlier and perhaps deeper thermocline formation than at present. Accordingly, the metalimnion (middle layer of a thermally stratified lake) and hypolimnion (lower layer of a thermally stratified lake) volumes will be smaller. These areas are used as a summer thermal refuge by lake trout (*Salvelinus namaycush*) at southern latitudes to escape epilimnion (upper mixed layer of a lake) temperatures of more than 12 °C; thus, smaller volumes of preferred habitat will lead to stress for individuals, likely to be associated with population consequences such as lowered growth and/or a decline in numbers. In mid-latitude lakes (e.g., 60° N, northern boreal), lake trout tend to use the upper layers of water, which more closely approximate their thermal preferences and thereby promote growth. Projected effects of earlier ice loss and radiative heating suggest that shallower and earlier thermocline development (which will decrease the availability of this habitat) will have parallel consequences to those described above for more southern lakes (Mackenzie-Grieve and Post, 2006), despite the habitat being used differently. At least over the near future, suitable thermal habitats for lake trout in Arctic lakes are likely to remain similar to those at present or increase in volume, thus promoting lake trout growth (provided that all other factors are equal). The key environmental drivers producing this scenario are shifts in the timing of lake-ice melt combined with a longer heating season.

The effects of wind are a complicating factor in ice dynamics and thermal structure affecting habitats. Earlier ice loss results in larger fetches being open earlier and longer. Wind-driven mixing of surface waters will almost certainly interact with heating to complicate thermocline development and depth; however, the nature of such effects remains unclear. Although general logic models and trends connecting ice loss to fish populations can be developed, high local and interannual variability of effects will be very likely. Given that lake trout are generally long-lived, such climate change signals may not be readily discernible within the populations. Moreover, decreased occurrences of winter fishkills due to oxygen depletion events will generally be an additional effect of reduced ice-cover duration (Stefan and Fang, 1997). However, the significance of this is likely to vary by latitude and lake characteristics.

Ice cover also affects the migration and dispersal of aquatic organisms. A small number of Arctic lakes are permanently ice-covered (e.g., Vincent et al., 2008a), and in hydrological terms these are poorly connected to their surroundings. In these lakes, melt-out is typically restricted to a narrow moat. This greatly limits the wind-induced mixing of inflowing stream water and limits the presence of some biota, such as aquatic birds. Increased melting of ice and snow in both the catchment and lakes in a warmer climate may result in an increased overflow and, consequently, a greater hydrological connectivity between the lakes (Kusumastuti et al., 2008; see also Figure 6.1c). Conversely, changes in ice jams in large river ecosystems, particularly in their delta environments, could cause less frequent flooding of higher elevation lakes that rely on such events for water, sediment and nutrient supply (e.g., Prowse et al., 2002b; Peters and Prowse, 2006; Lesack and Marsh, 2007) (see Section 6.5.1.1 regarding physical sensitivity of delta systems to changes in flooding regimes and Section 6.5.2.3 for biological effects).

6.5.2.2. Lotic systems

6.5.2.2.1. Physical effects

In Arctic rivers, ice is important in defining the in-stream habitat for fish, invertebrates, and aquatic plants (Prowse, 2001a; Huusko et al., 2007), and climate change will have a profound impact on the future ice regime (Section 6.5.1.1). Various forms of river ice will directly create important habitats and will alter river geomorphology through erosion and sedimentation processes (Section 6.5.1.4). River ice will also influence the behavior and biological response of stream biota (Huusko et al., 2007) and, therefore, will play a central role in their growth, survival and reproduction.

Surface ice creates shelter habitats for fish in areas that are too exposed for use during open-water periods (Stickler et al., 2007; Linnansaari et al., 2009). A reduction in such ice shelter will, therefore, lead to a loss of suitable winter habitat during the period when the water temperature has not yet reached the level to cause changes in fish habitat use. In small and steep streams, winter formation of ice will define habitat availability and distribution independently of changes in discharge (Stickler et al., 2010). In such environments, a shorter ice season will influence habitat diversity. In addition, with future climate warming, an increased number of winter warm spells leading to mid-winter ice break-up may have a significant influence on habitat availability. Many Arctic rivers that currently have bed-fast ice, and thereby no available winter habitat, may shift into a regime with a floating ice cover. This will create new habitat for winter survival of species in these rivers.

By altering geomorphology and vegetation in Arctic rivers, river ice processes, particularly ice break-up, have important effects on channel development and maintenance (Section 6.5.1.4). A reduction or disappearance of these processes in the future may lead to degradation of existing habitat or changes in habitat composition over time. This will influence biological productivity and biodiversity over the long term (Prowse, 2001b).

6.5.2.2.2. Chemical effects

Long periods with complete ice cover can decrease dissolved oxygen (DO) concentration in river water to a level harmful for the survival of invertebrates and fish (Prowse, 2001a). Several factors influence the decline in DO after the complete freeze-over of a stream. Of particular importance are the water-column and riverbed oxygen demands (Prowse, 2005). In rivers dominated by autumn flows of low-level DO, the decline from loss of air-water re-aeration can be particularly important. Further development of DO over winter is dependent on the source and chemical properties of winter discharge, residence time, and influx of oxygen-consuming material. It is important to note that changes in DO of ice-covered rivers do not follow a general pattern but are a complex product of a number of factors (Prowse, 2005). Changes in winter-season length, ice thickness, and the number of zones with broken ice cover could allow species sensitive to low DO concentrations to utilize larger habitats in the river and thereby increase survival (Wrona et al., 2005). Changes in ice cover may also strongly influence nutrient cycling in Arctic rivers. Greenwald et al. (2008) and Zarnetske et al. (2008) concluded

from fieldwork conducted on streams on the North Slope of Alaska that climate warming will not significantly expand the thickness of the hyporheic zone – a zone of benthic substrate through which stream water readily flows, found in most Arctic rivers. The thaw basin under Arctic streams flowing over permafrost may increase, but the hyporheic zone currently only occupies the upper part of the thaw basin and might not deepen substantially in the future. However, the season of flowing water in the Arctic is expected to lengthen substantially, and thus the opportunity for nutrient and organic matter processing in the hyporheic zone will also be modified. This shift in the seasonality of nutrient processing may have important impacts on biota in Arctic streams and rivers.

Currently the spring break-up of river ice causes significant bank erosion that delivers large quantities of sediment and nutrients to streams and rivers (Prowse et al., 2006). Increased nutrient loading might be considered a benefit if it stimulates additional productivity in streams but could also be a problem if it alters the structure of the benthic biotic community (e.g., Bowden et al., 1999; Prowse, 2001b). Furthermore, increased sediment loading is likely to impair stream biota by increasing turbidity, which will decrease light penetration (and thus decrease primary production), increase abrasion of sensitive biota, and when accumulated in benthic habitats, restrict access to interstitial spaces in substrate and reduce intra-gravel flow. If the spring break-up intensity decreases in the future, then less sediment and fewer nutrients may be delivered to rivers during the relatively short spring freshet.

However, greater variability in future temperature and the form (rain or snow) and intensity of precipitation will lead to increased surface and bank erosion (e.g., Lamoureux and Lafreniere, 2009; see also Chapter 5). This may increase sediment transport to streams and the load of associated nutrients. Nutrient and sediment loading will be especially large if future warming increases the formation of thermokarst features that directly affect water bodies. Bowden et al. (2008) and Gooseff et al. (2009) concluded that, in the long term, the negative impacts of increased sediment load would outweigh the positive effects of increased nutrient loading. Thus, future warming in the Arctic is likely to alter water quality in ways that could be detrimental to some macroinvertebrates and fish living in Arctic rivers and streams.

6.5.2.2.3. Biological effects

Changes in the seasonality of ice in Arctic streams will alter the timing and magnitude of sediment and nutrient delivery. Such changes will be driven largely by increasing temperature and will affect terrestrial and aquatic environments. Most lotic environments in the Arctic depend on or are limited by allochthonous (material originating from outside the water body) inputs from the landscape, making terrestrial-aquatic linkages important factors. In addition, terrestrial environments may respond differently to changes in light than aquatic environments. The life-cycle of higher vascular plants is driven by daily and seasonal photoperiods. Since the photoperiod will not change, short-term responses by such terrestrial plants to a longer potential growing season will be limited; however, long-term changes may include shifts in species composition. By contrast, productivity and growth

of microbial communities in soils and algae in streams and rivers are related to the photoperiod to a lesser extent. Such communities are often limited by light and/or temperature, and respond readily to changes in these variables as well as to changes in nutrient supply. Thus, aquatic microbial communities and algal assemblages may track changes in light and temperature (as a result of reduced ice cover). In-stream productivity or nutrient demand may thus increase, creating or intensifying asynchrony among nutrient delivery/allochthonous inputs (regeneration in soils by microbes, nutrient uptake by terrestrial plants, and surface and subsurface nutrient leaching to streams) and nutrient use and recycling within streams. In turn, this asynchrony in seasonal patterns of nutrient production and use may cause a shift in species composition and productivity in streams and rivers. Eventually, the terrestrial environment may adapt to the warmer climate through succession, but at this time it is not clear whether or how a modified terrestrial ecosystem in the Arctic will affect aquatic ecosystems.

Changes in ice cover can also have a direct impact on fish productivity and mortality. For example, for Atlantic salmon (*Salmo salar*) adapted to complete ice cover, removal of an ice cover has been shown to produce significant negative effects on their energy budget (Finstad et al., 2004a). Energy deficiency is important to winter survival, and a change in ice cover can reduce their ability to survive winter (Finstad et al., 2004b). Anchor-ice formation on the bed of streams also influences habitat availability and use. The response of fish to anchor ice is dependent on the severity of the ice formation, with related behavior spanning from avoidance to active use (Huusko et al., 2007). Periods with heavy formation of anchor ice can lead to increased movement in fish (Stickler et al., 2007), which is considered a problem due to increased use of energy during the winter period. The future development of anchor ice will depend on local climate and flow conditions. Longer freeze-up periods with higher flow, for example, could extend the period during which anchor ice develops. Winter break-ups and subsequent re-freezing could also increase the number of anchor-ice formation periods. Increased anchor-ice formation and release can also enhance anchor ice-induced sediment transport (Prowse, 2001a), which could have additional negative biological consequences for fish and benthic biota.

Movement of salmonids to overwintering habitats mostly occurs prior to ice formation in rivers; however, local movements between habitats also occur after ice formation (Jakober et al., 1998; Linnansaari et al., 2009). Extensive anchor ice precludes access, whereas patchy anchor ice and ice-covered areas appear to be preferred (Linnansaari et al., 2009). Accordingly, reduced ice cover or duration on river systems is likely to result in a tradeoff between increased habitat (or access to such) with that habitat being less preferred due to lack of surface ice cover. Access, primarily by migratory anadromous salmonids, to key overwintering habitats may thus provide benefits to overall population survival and productivity.

The Arctic Climate Impact Assessment identified changes in break-up timing as one of the greatest freshwater-ice effects of a changing climate (Wrona et al., 2005). A concern particularly identified was the development of mid-winter ice break-ups (Section 6.5.1.1), an event poorly studied in regard to impacts on aquatic ecosystems, particularly those at high

latitude. Based on research in a more temperate, southern environment, however, Cunjak et al. (1998) demonstrated that mid-winter ice break-ups may have large impacts on the survival of different life stages of Atlantic salmon and that more frequent mechanical winter break-ups could result in increased mortality. The ice-scour damage associated with such events will also influence the composition of riparian and aquatic vegetation, typically leaving elevational tiers of vegetation type corresponding to break-up frequency and severity (Prowse and Culp, 2008). Hence, in a situation with reduced break-ups, the ice-controlled vegetation pattern is likely to diminish or disappear, producing a more monoculture environment. By contrast, more mechanical break-ups will increase the level of vegetation disturbance and removal.

Large-scale changes in ice-cover duration and break-up timing will alter flow regimes and thereby influence Arctic rivers as migratory routes, affecting the timing of fish runs or even the migration of large mammals such as caribou (Sharma et al., 2009). Changes in flow timing in spring will also influence conditions for fish out-migration (Reist et al., 2006a,b). The loss of an ice cover is likely to increase the risk of predation on stream-living animals from mammalian and avian predators due to the loss of critical in-stream shelter. Moreover, winter and related ice formation could act as a 'bottleneck' for survival of fish and invertebrates. Results reported by Huusko et al. (2007) suggest that the variability in creating such bottlenecks among rivers is highly context dependent and controlled by the life stage of the fish, local habitat, and the related type of ice regime. Overall, the large and complex scope of potential changes in future river-ice regimes outlined in Sections 6.5.1.1 and 6.5.1.2 will make predictions of future biological responses difficult, particularly considering the current rather limited knowledge of high-latitude lotic systems.

6.5.2.3. River delta ecosystems

A number of major river deltas are found along the Arctic coast as well as on the rivers that drain into the Arctic Ocean. Major examples of the former include the Yukon, Colville, Indigirka, Kolyma, Lena, and Mackenzie river deltas, and of the latter, the Peace-Athabasca and Slave river deltas (e.g., Prowse et al., 2006); both the Lena and Mackenzie are considered to be mega deltas (Anisimov et al., 2007). Much of this area, however, is a riparian environment composed of numerous distributaries and a multitude of small basins connected by varying degrees to the channel network.

The annual flow and water-balance regimes of these delta systems are dominated by the spring freshet, and although driven by discharge arising from southern headwaters, it is the effects of river-ice break-up that produce the highest flood stages (e.g., Goulding et al., 2009a,b). It has been recognized for some time that the water budget and nutrient-sediment supply of delta riparian zones are heavily dependent on ice-jam floodwaters (see Section 6.5.2.1.3 and Figure 6.1c). The strength of this dependence has been reinforced by recent work on the Mackenzie River Delta, which contains about 45 000 riparian lakes. Specifically, decreases in the severity of river-ice break-up has lessened the flooding of high closure lakes, which has the potential to result in the loss of some of these water bodies and changes in the biogeochemical processing of river water

by the floodplain ecosystem (Figure 6.20) (Lesack and Marsh, 2007). Hence, as discussed in Section 6.5.1.1 and as found for another delta in the headwaters of the Mackenzie River (the Peace-Athabasca Delta), future climate conditions that produce thinner ice and reduced spring runoff (due to a smaller winter snowpack) will lead to overall reductions in ice-jam flooding (Beltaos et al., 2006). This could pose a major threat to the health of riparian ecosystems, both for resident biota and for those that use them for migratory purposes, such as waterfowl.

Reductions in the erosional forces of river ice as a result of decreases in break-up intensity (Section 6.5.1.4) are also likely to alter the extent of particle release from riparian zones to lakes and rivers and affect riparian vegetation communities (e.g., Prowse, 2001b). Given the importance of particles for microbial colonization and biogeochemical processes in many northern waters (e.g., Galand et al., 2008b), as well as for underwater light attenuation (e.g., Retamal et al., 2008), this could result in changes in biogeochemical processing rates, primary production, and greenhouse gas fluxes (Vallières et al., 2008).

Freshwater environments at the coast are also prone to the effects of changing ice conditions. In the High Arctic, for example, fjords can be blocked by thick multi-year sea ice and ancient ice shelves, resulting in an extensive layer of freshwater called an ‘epishelf lake’. These environments are proving to be microbial ecosystems with diverse biological communities; however, they are extremely vulnerable to ongoing climate warming and the loss of ice. Observations along the northern coastline of Ellesmere Island, Canada, have shown that many of these unique ecosystems have been driven to extinction as a result of recent climate change, and that they are sensitive indicators of climate change (Veillette et al., 2008). Other ice-dependent freshwater lakes at the High Arctic coast are becoming inundated with seawater as a result of the loss of integrity of their retaining ice dams (e.g., Vincent et al., 2009), and the extensive, microbiologically rich ice-bound lakes on ice shelves are disappearing completely as a result of their melting and collapse (Mueller et al., 2008).

Stamukhi lakes are another important class of coastal freshwater system that have implications for the marine environment. These ephemeral lagoons occur throughout

winter, spring, and early summer along the Arctic coastline and form behind pressure ridges (‘stamukhi’) of thick, partially grounded sea ice near large river inflows. Recent studies on the stamukhi lake, Lake Mackenzie (Figure 6.21), have revealed it to have an active microbial ecosystem with distinct physical and microbiological properties. This type of circumpolar ecosystem is likely to play a key functional role in processing riverine inputs to the Arctic Ocean (Galand et al., 2008a), which could be significantly altered by the effects of climate change (Dumas et al., 2006).

6.5.3. Socio-economic consequences and adaptation options

- Transportation and hydroelectric production are two of the socio-economic sectors most vulnerable to change in freshwater-ice regimes; ice roads are currently a vital link for industry and northern communities.
- Continued warming will preclude ice roads as a major form of northern transportation; alternative forms of transportation will be needed, but the capital costs of these are likely to be enormous.
- Changes to ice regimes will make the practice of some traditional subsistence-based lifestyles potentially hazardous and may reduce the ability to undertake some traditional harvesting methods.
- Hydroelectric operations will both benefit and be challenged by changes in river-ice conditions; the potential for winter break-ups is likely to pose operational challenges to ensuring that flow releases do not cause damage downstream.
- Monitoring and mitigation of ice-related problems will be a particular issue for hydropower producers with remote facilities.
- The importance of river ice to hydroelectric operations may be affected by future energy adaptations involving renewable but non-storable energy sources that require less regular hydroelectric operations to maintain a continuous energy supply.




Figure 6.20. Classification of lakes in the Mackenzie River delta according to the extent of their isolation from the river. Ice-jam floodwaters are responsible for flooding of the riparian lake systems more hydraulically unconnected to the main flow system. Source: after Emmerton et al. (2007).




Figure 6.21. Schematic illustration of a stamukhi lake. The inflow from the Mackenzie River is trapped near shore behind the stamukhi (pressure ridge of sea ice), forming Lake Mackenzie. Source: modified from Galand et al. (2008a).

6.5.3.1. Northern infrastructure, transportation, and traditional lifestyles

Lake and river ice provide seasonal transportation platforms throughout the Arctic. Many northerners depend on this natural network for access to hunting, fishing, and reindeer herding or trapping areas, often in support of traditional subsistence-based lifestyles (e.g., Furgal and Prowse, 2008; Prowse and Brown, 2010). Changes in ice regimes, however, will make such access more uncertain and potentially hazardous, for example, due to shorter ice duration, thinner and less stable ice regimes, and mid-winter thaws. Moreover, these changes may reduce the ability to undertake some traditional harvesting methods. For example, lake and river ice have been used as a stable and long-term platform for the deployment of specific fishing gear (e.g., gillnets); the loss of these platforms will require adaptation of traditional practices (Reist et al., 2006c). Ice-based travel also provides the principal transportation route for some isolated communities and industrial developments (Vuglinsky and Gronskaya, 2006; Prowse et al., 2009a).

Open-water transport on rivers and lakes has been the historical method of transport to many northern population and industrial centers, particularly along major northward-flowing rivers. These transportation links are so important that nuclear-powered ice breakers are used on Russian rivers to expand the shipping season, such as along several hundred kilometres of the Yenisey River between Igaraka or Dudinka and its northern outlet. Any increase in the ice-free season from climate warming will reduce the costs of such operations and enhance south-north and north-south transport, the latter becoming increasingly important as the Arctic becomes an expanding source of resources. For example, a six- to nine-week reduction in the ice season on the Mackenzie River could result in a 50% increase in the use of barge-based transport (Lonergan et al., 1993). However, in the case of major lake and river ice-based transportation systems, such as the complex terrestrial and water network built around the inland icebreaker system of Russia, any projected changes in the ice season would require

major coordination challenges in formulating new schedules or constructing new storage terminals and relay points.

Beyond the main rivers, there also exists a winter ice-road network composed of a combination of private and public lake and river crossings that link all-season road systems, communities, and remote industrial and mining complexes. Such networks are especially important for parts of northern Canada, such as the Northwest Territories, where the public roads system almost doubles during winter, or the vast territory of Nunavut, where there are no long-distance all-season highways (Prowse et al., 2009a). Similarly, annual ice roads are also constructed across vast areas of the Russian North primarily north of 60° N but extending from the Kola Peninsula to as far as the Bering Sea coast.

Although scientific publications that explicitly detail the importance of ice roads to northern communities are rare (e.g., Ford et al., 2008), there are many accounts in the public press when such networks are affected by unseasonably warm weather. To illustrate the significance of these events, one recent example is described here based on accounts provided by Carlson (2010). Specifically, mild weather in March 2010 caused the province of Manitoba, Canada, to close a 2200-km winter road network composed of muskeg (bogland), lakes, and rivers. The road system had deteriorated to the point of stranding numerous freight haulers and local drivers on thawed winter roads, necessitating emergency evacuations. Typically, the road carries more than 2500 shipments each year to more than 30 000 First Nations people. In response to dwindling construction supplies, rising food and fuel prices, and a related rise in unemployment, First Nations Chiefs declared a state of emergency in eleven communities. Carlson et al. (2010) also noted that because of deteriorating conditions approximately 600 km of the winter road system have been relocated to land since 2001 (Government of Manitoba, 2010) and spending on winter roads has tripled since 1999 (Government of Manitoba, 2009).

Ice roads are also critical to the resupply of the complex of mining centers, which cannot use air access for the transport

of heavy loads, fuel, and large equipment. One example is the 600-km long Tibbitt to Contwoyto Winter Road in northern Canada, which travels over 495 km of frozen tundra, lakes, and rivers (Figure 6.22). Although it typically operates for only two months per year (February and March), at an approximate annual cost of CAD 10 million, it carries up to 8000 truck loads per year, each weighing an average of 30 tonnes, with the load capacity rising as the ice thickens and increases in bearing strength. It has been estimated to contribute significantly to the territorial and national annual economies – approximately CAD 800 million and CAD 350 million, respectively, in 2001 but rising significantly with enhanced northern development (EBA Engineering Consultants, 2001). A similar example is the 360-km long winter road in the Chukotka region of Russia constructed each winter from the ocean port Pevek, over tundra, lakes, and streams to the Kupol gold and silver mine at Bilibino (Noble, 2009). In such cases, reductions in ice duration, thickness, or mechanical strength (e.g., related to changes in the amount and/or timing of snow-cover loading) could have major implications for such remote developments. For some Arctic centers, changes in ice-related transport can have both positive and negative effects. In the case of Arkhangelsk on the Northern Dvina River, Russia, an increased shipping period and freight turnover from the inland navigation fleet would result from a decrease in ice duration, but on the other hand, delays in the building of ice-road crossings would create substantial difficulties for local freight and public transportation (e.g., Ginzburg, 1989).

Initially, adaptation to the reduction in the size of maximum loads that can be safely transported on northern ice roads could involve (i) modifications to techniques involved in ice-road construction, such as by enhanced surface flooding or spray-ice layering; or (ii) where transport capacity is not already maximized, modification of transport schedules to concentrate more on the coldest part of winter (Prowse et al., 2009a). Continued warming will preclude ice roads as a major form of northern transportation, and there will be a need for alternative forms of transportation. In cases where an open-water network is feasible, transport by barge could be possible. For land-locked locations, however, the only viable option for heavy-load transport will be the construction of land-based road or rail networks. The initial capital costs of these, however, are likely to be enormous, especially where they must pass over terrain that is also projected to experience significant permafrost thaw and subsidence from climate change.

Although relatively rare, there is also some infrastructure within the Arctic that is located in river channels, such as the developing gas fields of the Mackenzie River Delta. The flood-damage exposure of such facilities depends on how climate will affect the severity of ice-jam and related backwater flooding. For coastal locations, the effect of sea level rise must also be factored into assessing such flood risks (see Section 6.5.1.1). One method identified to avoid these potential impacts involves the use of river barges for production facilities as opposed to being entirely land based (Prowse et al., 2009a).

6.5.3.2. Hydroelectric power

Production of hydroelectric power is important in several Arctic countries, the operations of which are seasonally constrained by the effects of river ice that could markedly change under




Figure 6.22. Example of large loads transported on the Tibbitt to Contwoyto Winter Road in northern Canada, which is composed of many long reaches across frozen lakes and rivers. Photo courtesy of Joint Venture Management Committee, partnership between DeBeers Canada, Inc.; BHP Billiton, Ltd; and Diavik Diamond Mines, Inc.

future climatic conditions. At present, the total installed capacity in the Arctic countries (2006 data) is approximately 80 GW (Figure 6.23), but for many areas, unregulated large northern rivers still hold vast potential (e.g., Prowse et al., 2004, 2009a). With the future projections of inflow, this potential will probably increase for most of the Arctic region (Hamududu and Killingtveit, 2010).

Changes in ice conditions can affect hydroelectric operations in a number of ways, both positively and negatively. For example, the estimation of ice loads on facilities such as dams, intakes, outlets, and gates is important both for engineering design and operations (Comfort et al., 2003). A shorter ice season and thinner ice cover (Sections 6.4.3 and 6.5.1.1) could reduce the static ice loads on dams, but on the other hand, a more unstable winter with mechanical ice break-ups could increase the dynamic loads on in-channel facilities. More unstable winter conditions could also lead to weakened ice and consequently a reduction in ice loads.

Many power plants in Arctic regions have operational restrictions or guidelines during the winter period to avoid

ice problems (Foulds, 1988). A shorter ice season will reduce the need to enforce such constraints and permit more optimum use of river flow (Beltaos and Prowse, 2009). By contrast, however, a longer freeze-up period is also likely to increase the period during which such constraints are needed during the remaining ice season.

Some of the most costly ice-induced effects on hydroelectric production result from the blocking of forebays, intakes, and diversion tunnels. Blockage usually results from two sources, both of which could be altered by future ice regimes. First, the intensity and magnitude of frazil ice formation is projected to increase or decrease depending on relative changes in autumn air temperature and flow regimes compared to current climatic conditions (Beltaos and Prowse, 2009). While decreases in frazil ice production will ease constraints on hydropower production, increases (see Section 6.5.1.1) can cause blocking of trash racks and intake structures (Andersson and Andersson, 1992; Ettema et al., 2009), thereby reducing production and increasing operational costs. Moreover, it could also initiate ice problems in downstream river reaches as inflowing production water is forced to bypass intakes. Reaches downstream of intakes are usually characterized by early ice formation and low winter-flow, and sudden releases of water may initiate mechanical break-ups, resulting in ice jamming and erosion damage. In a future with less stable conditions and a longer freeze-up period, this problem may increase in some areas, but it is also likely that it will be reduced in the most southern, temperate river systems. Second, in regions where there is an increase in the intensity or frequency of mid-winter warming spells and, therefore, an increased potential for mechanical winter break-ups (Section 6.5.1), clogging of intakes by drifting ice will cause a loss of water, thus decreasing production. This will be a problem particularly for secondary intakes used in

water transfer in high-head systems (Lokna, 2006). Monitoring and mitigation of such problems will be an issue especially for hydropower producers with remote facilities.

Ice jams and subsequent flooding can also threaten hydropower structures in rivers (Beltaos, 2007). Climate change has the capacity both to increase and decrease the magnitude and frequency of these extreme events (Sections 6.4.3 and 6.5.1.1), although their spatial distribution relative to hydropower facilities has not yet been established. In addition to intake and transfer restrictions, ice formation can also influence production through jamming and water level increases in the afterbay.

Although hydropower dams are equipped with spillways to pass floods, the function of which is crucial to dam safety, ice formation can have an impact on the capacity and functionality of these structures (Lia, 1997). In a period with more frequent mid-winter ice break-ups (Section 6.5.1.1), spillway functionality may be affected, particularly in spillway systems with tunnels or gates.

The strength of ice on hydropower impoundments is strongly influenced by reservoir operations such as the lowering of water levels during winter. In a future with shorter winters and a thinner ice cover, particularly along the shoreline and at intakes and outlets, the safety of using reservoir ice for transportation may be compromised. However, such changes in reservoir ice conditions could also lead to some positive impacts for reservoir design and management. At present, a significant amount of reservoir ice is grounded on the banks (e.g., up to 8% of active storage) (Seidou et al., 2007) as water levels are progressively lowered for winter hydroelectric production. Future climate conditions will decrease this volume of inactive storage and reduce some of the current negative consequences, including (i) part of the storage volume being unavailable



Figure 6.23. Location and size of major hydroelectric facilities located in ice-dominated river regimes of the circumpolar North. All such stations will require major modifications to current operational regimes and possibly infrastructure modifications based on projected changes to freshwater ice regimes (due to data availability, the figure may not show all existing plants). Source: Knut Alfredsen, Norwegian University of Science and Technology, Trondheim.

Installation, MW
 ● < 600
 ● 600 - 2000
 ● > 2000

during winter when electricity demand is high; (ii) grounded ice having the same effect as an additional dead pool storage, forcing the design of larger and costlier structures; (iii) the immobilized water only becoming available at the end of winter when streamflows are large (and demand for electricity is low) thereby increasing flood risk and the probability of spilling; and (iv) grounded ice changing the effective storage curve during winter, which if unaccounted for in dam operations leads to suboptimal decisions (Seidou et al., 2006, 2007). Reductions in any or all of these will provide benefits to hydroelectric operations.

The importance of river ice on hydroelectric operations may also be indirectly affected by future energy adaptations. For example, a reduction in greenhouse gas emissions will require the production of more renewable energy and lead to the introduction of more non-storable energy sources such as windpower. In such a system, load balancing is needed to maintain a continuous supply, and hydropower is ideally suited for this, being renewable, storable in reservoirs, and able to be run with simple start and stop routines (e.g., Benítez et al., 2008). This will have implications for the operational strategies of hydropower producers toward a peaking schedule, and this must be considered when impacts of changes in river ice are evaluated. Generally, peaking operation of hydropower plants in rivers is considered an environmental challenge (e.g., Bradford, 1997; Saltveit et al., 2001; Bruno et al., 2009), and peaking during the ice season further increases potential problems (Scruton et al., 2008). Balancing the variable production from non-storable renewables could lead to a less regular operation of the hydropower system, thereby increasing the potential problems linked to break-up and ice jamming in rivers downstream of hydropower outlets. Additional future variables not addressed here are the potential changes in energy demand and changes in energy prices in the face of future climate. Both of these factors will influence production and thereby have an influence on the future ice problems of the hydroelectric power industry.

6.6. Major uncertainties and future research

6.6.1. Observation networks

- Current river- and lake-ice observation programs in the circumpolar latitudes employ a disparate set of methods and approaches, making it difficult to compare data or conduct large-scale spatial and temporal analyses.
- There should be an international circumpolar effort to assemble and compile a comprehensive freshwater-ice data record that includes data from all forms of available instrumental records.
- There should be a standardization of *in situ* observation methods to facilitate intercomparison of data.
- Given the remoteness of much of the high latitudes, a special focus should be placed on adopting remote sensing approaches to augment the *in situ* networks.
- A number of sites from representative regions should be established around the circumpolar North for

conducting long-term monitoring and intercomparison of observational techniques; this will require an international collaborative effort, perhaps one that could be undertaken by an international agency, such as the World Meteorological Organization.

The current state of river- and lake-ice observation in the circumpolar latitudes is composed of a disparate set of programs with varying purposes and approaches. As a result, data about even simple ice phenologies are difficult to compare and observations are often only conducted on regional or national scales, with few attempts to understand change on a circumpolar basis. Although some attempts have been made to centralize the archiving of freshwater-ice information, even these have not been comprehensive of all available records, either because they are difficult to obtain from some countries or regions or because they are difficult to extract from original data sources (e.g., original hydrometric charts and related metadata). In consideration of the above, two recommendations for improvement can be made. The first is that there should be an international circumpolar effort to assemble and compile a comprehensive freshwater-ice data record, which includes data from all forms of available instrumental records and applies relevant quality assurance and control measures. To allow the resulting data to be used in subsequent analyses, there should also be a quantification of data-source errors, such as of temporal error variability for use in time-series analysis of ice phenology dates. Archiving of the original and processed data should be conducted at a recognized international facility, such as the World Data Centre for Glaciology at the National Snow and Ice Data Center, Boulder, Colorado. Second, to improve the comparability of future data, there should be a standardization of *in situ* methods for observing basic freshwater-ice characteristics. This will also require some form of international collaborative effort, perhaps one that could be undertaken by an international agency, such as the World Meteorological Organization and potentially through their developing program, Global Cryosphere Watch.

Ground-based observations are essential not only to establish time-series evaluations of change, but also to provide essential information for improving understanding of freshwater-ice characteristics, processes, and effects and for validating and improving remote sensing approaches and various forms of numerical simulation models. Where freshwater-ice data are collected as an ancillary product for other purposes, there is an opportunity to improve current observation methods in ways that will vastly improve the value to freshwater-ice studies. For example, many river hydrometric programs measure only part of the total ice thickness when conducting under-ice discharge measurements. A simple modification to the thickness measurement aspect of the program (i.e., complete ice thickness) would make available thousands of additional ice-thickness measurements per year around the circumpolar North. Given the controlling effect of snow, it would also be beneficial to include a simple measurement of surface snow depth. Specific guidelines exist for improving such programs (e.g., Canadian hydrometric surveys, Prowse, 1990; IGOS, 2007) and could be used to guide a circumpolar initiative to revamp and unify circumpolar freshwater-ice *in situ* observing programs. To further broaden at least some forms of ice observation, it would be advantageous to make further

use of, or even expand, some of the volunteer networks that have been established, such as Canadian 'Ice Watch' (www.naturewatch.ca/english/icewatch) or the Alaska Lake Ice and Snow Observatory Network (www.gi.alaska.edu/alison).

In unifying the ice observation networks, it is also important that a set of representative regions around the circumpolar North be established for long-term monitoring, preferably including those that already have a lengthy and more comprehensive historical record. Sites with existing paleo-records, or the potential to provide superior forms of such records, might be particularly good candidates. Further to this end, such sites should be the focus of a suite of ice-related modeling efforts, to take advantage of the comprehensive observation datasets, which can be used to facilitate validation and updating of the relevant models. Given this, it would also seem practical in the selection of such 'supersites' to consider the data needs of these models, which could require, for example, information about ecological or socio-economic factors.

Given the spatial scale of the circumpolar North, the remoteness of many regions, and the high costs of *in situ* monitoring programs, remote sensing has long been touted as a promising means to monitor, at least, lake- and river-ice phenology at regional to hemispheric scales. Unfortunately, to date there are only a few remote sensing-derived freshwater-ice operational products, and these do not meet the temporal requirements set by climate programs such as the Global Climate Observing System (accuracy of ± 1 to 2 days for freeze-up and break-up dates) or their spatial resolutions are too coarse (e.g., 4 km IMS product) for ice monitoring on water bodies other than large lakes. Although new approaches have recently been presented in the literature, they require further testing and refinement before application to operational monitoring. Further work should focus on (i) the evaluation of the potential and limits of optical (e.g., Moderate Resolution Imaging Spectroradiometer, MODIS; Advanced Along-Track Scanning Radiometer, AATSR; Medium Resolution Imaging Spectrometer, MERIS) and microwave (e.g., AMSR-E; Advanced Synthetic Aperture Radar, ASAR; and RADARSAT, synthetic aperture radar) data for ice-cover monitoring, and (ii) the development of approaches that make use of optical and microwave data in a synergistic manner for the creation of lake- and river-ice products at a variety of spatial and temporal resolutions for operational and research needs. Key sites need to be established at regional locations around the circumpolar North for validation of all such products. In addition, there needs to be a comparison of conventional *in situ* observations (e.g., ice phenological dates) with historical satellite-derived data (e.g., data from AVHRR; Scanning Multichannel Microwave Radiometer, SMMR; and Special Sensor Microwave Imager, SSM/I). This will ensure some continuity in the transition between the surface-based and satellite observations (e.g., as after the 1980s when *in situ* observations at many lake- and river-ice sites were discontinued). Beyond the observation of basic ice phenology, remote sensing also offers the opportunity to observe some of the dynamics associated with freshwater ice, such as the generation of steep hydraulic gradients and ice-jam floods by river ice during both freeze-up and break-up, with the use of satellite laser altimeter systems (e.g., GLAS on ICESat or future systems with similar capabilities).

6.6.2. Trend analysis and climatic linkage

- Once a broader freshwater-ice dataset for the circumpolar North is assembled, a comprehensive time series of spatial trends in ice phenologies should be conducted.
- Existing archive data should be further mined for information about changes in temporal and spatial characteristics of river-ice break-up dynamics.
- In exploring the role of climate in controlling trends in freshwater-ice characteristics, assessments should be conducted at a number of scales.
- A special focus should be placed at the scale of major Arctic rivers, including the study of climatic controls exerted in their more temperate mid-latitude headwaters.

With a successful assembly of additional freshwater-ice observational data, there will be an opportunity to more comprehensively analyze time series and spatial trends in ice phenologies and to quantify linkage with similar trends in climatic characteristics and patterns. Even with existing records, however, there is an opportunity to assess more broadly the trends and variability in the temporal and spatial characteristics of river-ice break-up dynamics and to link these to climatic forcing. To date, this has only been conducted for the Mackenzie River in Canada (de Rham et al., 2008b; Goulding et al., 2009b), although similar hydrometric data on which these analyses were conducted exist for other parts of Canada and in other circumpolar countries. Such broader-scale analyses are considered a prerequisite to understanding how climate variability and change has controlled and could control such extreme events.

In exploring the role of climate on a broader regime of trends in freshwater-ice characteristics (i.e., from simple ice phenologies to extreme-event dynamics), assessments should be conducted at a number of scales and approaches. These include basic correlations with simple climatic variables, such as temperature and precipitation, as well as linkage to regional synoptic and large-scale atmospheric circulation patterns, and major atmospheric teleconnections. In the case of large-scale atmospheric patterns, a special focus should be placed on how such systems both control regional variations and produce responses across the circumpolar North. Identification of robust climatic linkage with freshwater-ice characteristics and trends could also offer the opportunity to use such relationships for predicting future effects under altered climatic regimes, although the stability of such relationships under modified climatic conditions also needs to be considered in any such evaluation. Given that some river-ice effects are strongly controlled by catchment-scale processes, such as the dynamics and severity of river-ice break-up fronts, a focus also needs to be placed at the scale of major Arctic river basins, such as the Lena, Mackenzie, Ob, and Yenisey. The river-ice dynamics throughout these river systems are influenced by climatic controls exerted well south of the Arctic Circle in the climatically more temperate mid-latitudes.

6.6.3. Predictive modeling

- To achieve improved prediction of river-ice regimes, advancements need to be made in integrated models that

consider future combined changes to landscape hydrology, water-ice-air energy exchanges, in-stream hydraulics, and ice mechanics.

- More validations of existing lake ice models are required across a range of hydro-climatic regimes and lake sizes.
- Predictive modeling of lake- and river-ice systems should be expanded from primarily physical characteristics to include effects on lentic and lotic ecosystems.
- Model validation is a prerequisite for using climate scenarios to evaluate the future effects of climate on ice-controlled aquatic systems, many of which may be characterized by non-linear and/or step changes that are unlikely to be identified fully without such field testing.

Although some prediction of future lake- and river-ice conditions might be possible using climatic analogues (see Section 6.6.2), achieving a more detailed understanding of future freshwater-ice responses suitable for the evaluation of many related impacts will also require the use of physically or mechanistically based models operating at various scales of complexity. In the case of relatively simple lake-ice growth and decay models, achieving a successful explanatory coupling with climatic drivers will provide useful tools for (i) determining what climatic variables are reflected in freeze-up and break-up dates and, hence, how freeze-up and break-up observations might be used as adjuncts to more conventional (e.g., air temperature and precipitation) climate monitoring in data-sparse areas; (ii) understanding sources of uncertainty or complications in interpreting freeze-up and break-up data (e.g., confounding effects of temperature and snowfall); (iii) estimating the magnitude of natural variability in freeze-up and break-up dates for use in climate change detection studies; (iv) estimating the potential impacts of projected climate change on freeze-up and break-up dates, and hence ice-cover duration, as well as ice thickness and type (congelation ice versus white ice); and (v) reconstructing ice phenology and filling in gaps (missing years of observations) in historical records.

In the case of more complex modeling of river-ice conditions, additional cryospheric and hydrological responses to climate will also need to be modeled (see reviews by Prowse et al., 2008; Beltaos and Prowse, 2009). Of particular importance is the role of climate in determining the magnitude of the winter snowpack and its timing and rate of melt, which control the magnitude and rate of the major driving force controlling break-up, jave formation and release, and associated water levels (see Section 6.5.1.1). Similarly, atmospheric conditions control the resisting forces, such as ice thickness and mechanical strength. Achieving suitable coupling of atmospheric and river-ice hydraulic, thermodynamic, and mechanical models will be a major research task, but one that is essential to obtain an understanding of the effects of climate on extreme events in northern systems, make reliable predictions of future conditions, and institute proper adaptation measures (e.g., flood prevention infrastructure; see Section 6.6.4).

Predictive modeling should not be restricted to the purely physical characteristics and effects of lake and river ice. As noted in section 6.5.2, freshwater ice in northern regions is a critical component of aquatic systems and affects a suite of

often interrelated physical, chemical, and biological forms and processes. Much of the biological productivity and biodiversity of northern aquatic systems is controlled by ice-related conditions and processes. If the cascading effects of changes in lake- and river-ice are to be understood, then improved response models that include a suite of algorithms linking the interrelated processes need to be produced for northern lentic and lotic systems. While some such models do exist (e.g., Saloranta and Andersen, 2007; see Section 6.4.3), they have not been fully validated or tested under a complete range of hydroclimatic conditions found across the Arctic. Such validation is a prerequisite for using climate scenarios to evaluate the future effects of climate on ice-controlled aquatic systems, many of which may be characterized by non-linear and/or step changes that are unlikely to be identified fully without such testing (e.g., Wrona et al., 2006). As noted in Section 6.6.1, the variability in aquatic systems needs to be factored into the regional selection of long-term representative sites for future observation and physically based studies. Of particular additional importance in site selection should be a consideration of locations that have the potential to be ‘hot spots’ (i.e., locations that show disproportionately high reaction rates relative to changes in ice and climate conditions) or experience ‘hot moments’ (i.e., periods of time that exhibit disproportionately high reaction rates relative to longer intervening time periods) (McClain et al., 2003).

6.6.4. Advanced evaluations of socio-economic impacts and adaptation options

- Direct and indirect effects of changes in freshwater ice will both have cascading impacts on socio-economic systems.
- Although some potential adaptation options to such impacts have been identified, they still require economic evaluation and option comparisons.
- Additional cultural values must also be taken into account when considering potential adaptations to traditional ways of life practiced by northerners.
- Only through a broad range of cost-benefit analyses and additional socio-economic modeling can the suitability of relevant adaptation options be properly assessed.
- Given the importance of many ice-affected socio-economic sectors in the Arctic, key locations of such activities should be considered in the selection of long-term observation and validation sites for lake and river ice. By doing so, it is likely to maximize the socio-economic benefits of conducting future freshwater ice and climate change research in the Arctic.

In addition to the effects on aquatic systems, changes in freshwater ice regimes are likely to have cascading effects on socio-economic systems (Section 6.5.3). While it is important to understand how biological systems might adapt to changing ice regimes, it is equally or more important to evaluate how these biological changes might affect socio-economic systems and, more broadly, how other ice-related changes might also affect them. In the first case, it is known that traditional and commercial economies are likely to be affected by changes in

aquatic productivity and diversity from altered ice regimes, particularly as they relate to fisheries (Reist et al., 2006a,b,c; Furgal and Prowse, 2008). However, the magnitude of the biological effects remains to be quantified and, similarly, the real cost to traditional and commercial economies. Only through such additional biological and socio-economic modeling of effects can the suitability of relevant, previously defined adaptation options (e.g., changes to fisheries approaches and equipment or relocation of fisheries and possibly resource-based communities) be properly assessed.

In the second case of direct ice-change effects on socio-economic systems, there is also a lack of quantification, primarily because the specific details of expected physical changes to ice regimes remain largely unknown. In Section 6.5.3, some possible adaptation options for hydroelectric facilities (e.g., infrastructure adjustment and changes to operational flow strategies) and ice-road networks (e.g., enhanced ice making, intensification of traffic flow, and land-based road construction) were identified, but these still require economic evaluation and option comparisons. In the case of ice roads, the possibility of adapting to the loss of ice roads through the construction of land-based systems in the Arctic is further complicated by the need to know how related permafrost-affected landscapes will also be affected by changing climate and the costs to construct and maintain such facilities. Just as the responses of lake and river ice to climate change depend on changes in other cryospheric components (e.g., permafrost and snow) so do the adaptation options that need to be assessed through coupled socio-economic models. Furthermore, given the importance of many ice-affected socio-economic sectors in the Arctic, it is recommended that key locations be considered in the selection of long-term observation and validation sites for lake and river ice. By doing so, it is likely to maximize the socio-economic benefits of conducting future freshwater ice and climate change research in the Arctic.

Acknowledgments

The lead author wishes to acknowledge the support of the Canadian Natural Sciences and Engineering Research Council, ArcticNet, Environment Canada, and the Arctic Monitoring and Assessment Programme Secretariat in helping to produce this chapter. Support provided to the other authors by other granting agencies, too numerous to mention here, are also gratefully acknowledged.

References

ACIA, 2005. Arctic Climate Impact Assessment. 1024 pp. Cambridge University Press.

Adams, W.P., 1981. Snow and ice on lakes. In: Gray, D.M. and D.M. Male (Eds.). *Handbook of Snow*, pp. 437-474, Blackburn Press.

Adrian, R., S. Wilhelm and D. Gerten, 2006. Life-history traits of lake plankton species may govern their phenological response to climate warming. *Global Change Biology*, 12:652-661.

Andersson, A. and L.O. Andersson, 1992. Frazil ice formation and adhesion on trash racks. Paper presented at the 11th International Symposium on Ice, II, pp. 671-682, Banff, Canada, 15-19 June 1992.

Andrishak, R. and F. Hicks, 2008. Simulating the effects of climate change on the ice regime of the Peace River. *Canadian Journal of Civil Engineering*, 35:461-472.

Anisimov, O., B. Fitzharris, J.O. Hagen, R. Jeffries, F. Nelson, T.D. Prowse and D. Vaughan, 2001. Polar regions (Arctic and Antarctic). *Climate*

Change 2001, Impacts, Adaptation, and Vulnerability. Contribution of Working Group II to the Third Assessment Report of the Intergovernmental Panel on Climate Change, pp. 801-841, Cambridge University Press.

Anisimov, O.A., D.G. Vaughan, T.V. Callaghan, C. Furgal, H. Marchant, T.D. Prowse, H. Viljalmarsson and J.E. Walsh, 2007. Polar regions (Arctic and Antarctica). In: Perry, M.L., O.F. Canziani, J.P. Palutikof, P.J. van der Linden and C.E. Hanson (Eds.). *Climate Change 2007: Impacts, Adaptation and Vulnerability. Contribution of Working Group II to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change*, pp. 653-685, Cambridge University Press.

Antoniades, D., C. Crawley, M.S.V. Douglas, R. Pienitz, D. Andersen, P.T. Doran, I. Hawes, W. Pollard and W.F. Vincent, 2007. Abrupt environmental change in Canada's northernmost lake inferred from fossil diatom and pigment stratigraphy. *Geophysical Research Letters*, 34:L18708.

Antoniades, D., J. Veillette, M.-J. Martineau, C. Belzile, J. Tomkins, R. Pienitz, S. Lamoureux and W.F. Vincent, 2009. Bacterial dominance of phototrophic communities in a High Arctic lake and its implications for paleoclimate analysis. *Polar Science*, 3:147-161.

Ashton, G.D. (Ed.), 1986. *River and Lake Ice Engineering*. 485 pp. Water Resources Publications.

Asvall, R.P., 2009. River ice implications related to water power production in Norway. Paper presented at the 15th Workshop on the Hydraulics of Ice Covered Rivers, pp. 232-237, CGU-HS Committee on River Ice Processes and the Environment, St. John's, Canada, 15-17 June 2009.

Austin, J.A. and S.M. Colman, 2007. Lake Superior summer water temperatures are increasing more rapidly than regional air temperatures: A positive ice-albedo feedback. *Geophysical Research Letters*, 34:L06604.

Balayla, D., T.L. Lauridsen, M. Søndergaard and E. Jeppesen, 2010. Larger zooplankton in Danish lakes after cold winters: are winter fish kills of importance? *Hydrobiologia*, 646:159-172.

Bates, B.C., Z.W. Kundzewicz, S. Wu and J.P. Palutikof (Eds.), 2008. *Climate Change and Water. Technical Paper of the Intergovernmental Panel on Climate Change*. 210 pp. IPCC Secretariat.

Battarbee, R.W., N.J. Anderson, E. Jeppesen and P.R. Leavitt, 2005. Combining palaeolimnological and limnological approaches in assessing lake ecosystem response to nutrient reduction. *Freshwater Biology*, 50:1772-1780.

Bégin, Y., 2000. Ice-push disturbances in high-Boreal and Subarctic lakeshore ecosystems since AD 1830, northern Québec, Canada. *The Holocene*, 10:179-189.

Bégin, Y., 2001. Tree-ring dating of extreme lake levels at the subarctic-boreal interface. *Quaternary Research*, 55:133-139.

Bello, R. and J.D. Smith, 1990. The effect of weather variability on the energy balance of a lake in the Hudson Bay Lowlands, Canada. *Arctic and Alpine Research*, 22:98-107.

Beltaos, S., 1982. Notes on Ice Hydraulics. Environmental Hydraulics Section, Hydraulics Division, National Water Research Institute, Canada Centre for Inland Waters.

Beltaos, S. (Ed.), 1995a. *River Ice Jams*. 372 pp. Water Resources Publications.

Beltaos, S., 1995b. Ice jam processes. In: Beltaos, S. (Ed.). *River Ice Jams*, pp. 71-104, Water Resources Publications, Highlands Ranch, Colorado.

Beltaos, S., 2002. Effects of climate on mid-winter ice jams. *Hydrological Processes*, 16:789-804.

Beltaos, S., 2004. Climate impacts on the ice regime of an Atlantic river. *Nordic Hydrology*, 35:81-99.

Beltaos, S., 2007. River ice breakup processes: recent advances and future directions. *Canadian Journal of Civil Engineering*, 34:703-716.

Beltaos, S. (Ed.), 2008a. *River Ice Breakup*. 462 pp. Water Resources Publications.

Beltaos, S., 2008b. Onset of breakup. In: Beltaos, S. (Ed.). *River Ice Breakup*, pp. 167-206, Water Resources Publications, Highlands Ranch, Colorado.

Beltaos, S., 2008c. Challenges and opportunities in the study of river ice processes. Paper presented at the 19th International Ice Symposium of IAHR, 1:3-27, Vancouver, Canada, 6-11 July 2008.

Beltaos, S., 2008d. Ice jams. In: Beltaos, S. (Ed.). *River Ice Breakup*, pp. 207-246, Water Resources Publications, Highlands Ranch, Colorado.

Beltaos, S., 2008e. Progress in the study and management of river ice jams.

- Cold Regions Science and Technology, 51:2–19.
- Beltaos, S., 2009. River flow abstraction due to hydraulic storage at freezeup. *Canadian Journal of Civil Engineering*, 36:519–523.
- Beltaos, S. and B.C. Burrell, 2003. Climatic change and river ice breakup. *Canadian Journal of Civil Engineering*, 30:145–155.
- Beltaos, S. and B. Burrell, 2008. Climatic aspects. In: Beltaos, S. (Ed.). *River Ice Breakup*, pp. 377–406, Water Resources Publications, Highlands Ranch, Colorado.
- Beltaos, S. and T.D. Prowse, 2001. Climate impacts on extreme ice-jam events in Canadian rivers. *Hydrological Sciences Journal*, 46:157–181.
- Beltaos, S. and T. Prowse, 2009. River-ice hydrology in a shrinking cryosphere. *Hydrological Processes*, 23:122–144.
- Beltaos, S., R. Gerard, S. Petryk and T.D. Prowse, 1990. Field studies and research needs. NHRI Science Report. 2:121 pp. Environment Canada.
- Beltaos, S., T. Prowse, B. Bonsal, R. MacKay, L. Romolo, A. Pietroniro and B. Toth, 2006. Climatic effects on ice-jam flooding of the Peace-Athabasca Delta. *Hydrological Processes*, 20:4031–4050.
- Belzile, C., W.F. Vincent, J.A.E. Gibson and P. Van Hove, 2001. Bio-optical characteristics of the snow, ice, and water column of a perennially ice-covered lake in the High Arctic. *Canadian Journal of Fisheries and Aquatic Sciences*, 58:2405–2418.
- Benitez, L.E., P.C. Benitez and G.C. van Kooten, 2008. The economics of wind power with energy storage. *Energy Economics*, 30:1973–1989.
- Bennett, K.E. and T.D. Prowse, 2010. Northern Hemisphere geography of ice-covered rivers. *Hydrological Processes*, 24:235–240.
- Benson, B. and J. Magnuson, 2007. Global lake and river ice phenology database. National Snow and Ice Data Center/World Data Center for Glaciology, Boulder, Colorado, USA. Digital media. <http://nsidc.org/data/g01377>.
- Benson, B.J., J.J. Magnuson, R.L. Jacob and S.L. Fuenger, 2000. Response of lake ice breakup in the Northern Hemisphere to the 1976 interdecadal shift in the North Pacific. *Verhandlungen der Internationalen Vereinigung für Theoretische und Angewandte Limnologie*, 27:2770–2774.
- Besonen, M.R., W. Patridge, R.S. Bradley, P. Francus, J.S. Stoner and M.B. Abbott, 2008. A record of climate over the last millennium based on varved lake sediments from the Canadian High Arctic. *The Holocene*, 18:169–180.
- Bird, B.W., M.B. Abbott, B.P. Finney and B. Kutchko, 2009. A 2000 year varve-based climate record from the central Brooks Range, Alaska. *Journal of Paleolimnology*, 41:25–41.
- Blanken, P.D., W.R. Rouse and W.M. Schertzer, 2007. The time scales of evaporation from Great Slave Lake. In: Woo, M.K. (Ed.). *Cold Region Atmospheric and Hydrologic Studies, The Mackenzie GEWEX Experience*, pp. 181–196, Springer Verlag.
- Blenckner, T. and D.L. Chen, 2003. Comparison of the impact of regional and North Atlantic atmospheric circulation on an aquatic ecosystem. *Climate Research*, 23:131–136.
- Blenckner, T., M. Järvinen and G.A. Weyhenmeyer, 2004. Atmospheric circulation and its impact on ice phenology in Scandinavia. *Boreal Environment Research*, 9:371–380.
- Blenckner, T., R. Adrian, D.M. Livingstone, E. Jennings, G.A. Weyhenmeyer, D.G. George, T. Jankowski, M. Järvinen, C.N. Aonghusa, T. Noges, D. Straile and K. Teubner, 2007. Large-scale climatic signatures in lakes across Europe: A meta-analysis. *Global Change Biology*, 13:1314–1326.
- Bonsal, B.R. and T.D. Prowse, 2003. Trends and variability in spring and autumn 0°C-isotherm dates over Canada. *Climatic Change*, 57:341–358.
- Bonsal, B.R., A. Shabbar and K. Higuchi, 2001. Impacts of low frequency variability modes on Canadian winter temperature. *International Journal of Climatology*, 21:95–108.
- Bonsal, B.R., T.D. Prowse, C.R. Duguay and M.P. Lacroix, 2006. Impacts of large-scale teleconnections on freshwater-ice break/freeze-up dates over Canada. *Journal of Hydrology*, 330:340–353.
- Borgström, R. and J. Museth, 2005. Accumulated snow and summer temperature – critical factors for recruitment to high mountain populations of brown trout (*Salmo trutta* L.). *Ecology of Freshwater Fish*, 14:375–384.
- Borshch, S.V., B.M. Ginzburg and I.I. Soldatova, 2001. Modeling the development of ice phenomena in rivers as applied to the assessment of probable changes in ice conditions at various scenarios of the future climate. *Water Resources*, 28:194–200.
- Boucher, É., Y. Bégin and D. Arseneault, 2009. Impacts of recurring ice jams on channel geometry and geomorphology in a small high-boreal watershed. *Geomorphology*, 108:273–281.
- Bowden, W.B., D. Arscott, D. Pappathanasi, J. Finlay, J.M. Glime, J. LaCroix, C.-L. Liao, A. Hershey, T. Lampella, B. Peterson, W. Wollheim, K. Slavid, B. Shelley and M.B. Chesterton, 1999. Roles of bryophytes in stream ecosystems. *Journal of the North American Benthological Society*, 18:151–184.
- Bowden, W.B., M.N. Gooseff, A. Balser, A. Green, B.J. Peterson and J. Bradford, 2008. Sediment and nutrient delivery from thermokarst features in the foothills of the North Slope, Alaska: Potential impacts on headwater stream ecosystems. *Journal of Geophysical Research-Biogeosciences*, 113:G02026.
- Bradford, M.J., 1997. An experimental study of stranding of juvenile salmonids on gravel bars and in side channels during rapid flow decreases. *Regulated Rivers: Research and Management*, 13:395–401.
- Brakenridge, G.R., E. Anderson and S. Caquard, 2001. 2001 Global register of extreme flood events. www.dartmouth.edu/%7Efloods/Archives/2001sum.htm.
- Breton, J., C. Vallières and I. Laurion, 2009. Limnological properties of permafrost thaw ponds in northeastern Canada. *Canadian Journal of Fisheries and Aquatic Sciences*, 66:1635–1648.
- Brown, R.D. and P.W. Mote, 2009. The response of northern hemisphere snow cover to a changing climate. *Journal of Climate*, 22:2124–2145.
- Brown, R.S., C.R. Duguay, R.P. Mueller, L.L. Moulton, P.J. Doucette and J.D. Tagestad, 2010. Use of synthetic aperture radar to identify and characterize overwintering areas of fish in ice-covered arctic rivers: a demonstration with broad whitefish and their habitats in the Sagavanirktok River, Alaska. *Transactions of the American Fish Society*, 139:1711–1722.
- Bruno, M.C., B. Maiolini, M. Carolli and L. Silveri, 2009. Impact of hydropowering on hyporheic invertebrates in an Alpine stream (Trentino, Italy). *International Journal of Limnology*, 45:157–170.
- Burrell, B.C., 2008. Introduction. In: Beltaos, S. (Ed.). *River Ice Breakup*, pp. 1–19, Water Resource Publications, Highlands, Colorado, USA.
- Bussières, N., 2002. Thermal features of the Mackenzie basin from NOAA AVHRR observations for summer 1994. *Atmosphere-Ocean*, 40:233–244.
- Buzin, V.A., 2007. Risk of flooding on the rivers of Russia: The analysis of tendencies and possible development of a situation in the near future. [in Russian]. Paper presented at the Modelling and analysis of safety and risk in the complex systems, III. Risk in engineering and ecology, pp. 496–501. International Scientific School MASR, St. Petersburg, Russia, 4–8 September 2007.
- Buzin, V.A. and Z.D. Kopalani, 2007. The inundations on the rivers of Russia with the current weather-change trends. The up-to-date trends to the alteration of climate. [in Russian]. *Uchenye zapiski RSHMU*, 5:43–54.
- Buzin, V.A. and Z.D. Kopalani, 2008. Ice jam flooding on the rivers of Russia: risks of their occurrence and forecasting [in Russian]. Paper presented at the Conference on water resource systems management under extreme conditions, pp. 282–283, Moscow, Russia, June 2008.
- Cahill, K.L., J.M. Gunn and M.N. Futter, 2005. Modelling ice cover, timing of spring stratification, and end-of-season mixing depth in small Precambrian Shield lakes. *Canadian Journal of Fisheries and Aquatic Sciences*, 62:2134–2142.
- Carlson, R., 1989. Cold Regions Engineering Research: Strategic Plan. *Journal of Cold Regions Engineering*, 3:172–190.
- Carlson, K.B., 2010. End of the Roads. *National Post*, March 20, 2010:A10.
- Carrie, J., F. Wang, H. Sanei, R.W. Macdonald, P.M. Outridge and G.A. Stern, 2010. Increasing contaminant burdens in an arctic fish, burbot (*Lota lota*), in a warming climate. *Environmental Science and Technology*, 44:316–322.
- Catalogue of ice jams in the former USSR, 1978. Catalogue of ice dam and ice jam sectors on the rivers of the former USSR [in Russian]. *Hydrometeoizdat*, 1–2:260 pp. and 288 pp.
- Cavalieri, D.J., C.L. Parkinson, P. Gloersen, J.C. Comiso and H.J. Zwally, 1999. Deriving long-term time series of sea ice cover from satellite passive-microwave multisensor data sets. *Journal of Geophysical Research-Oceans*, 104:15803–15814.
- Chételat, J. and M. Amyot, 2009. Elevated methylmercury in High Arctic *Daphnia* and the role of productivity in controlling their distribution. *Global Change Biology*, 15:706–718.
- Comfort, G., Y. Gong, S. Singh and R. Abdelnour, 2003. Static ice loads on dams. *Canadian Journal of Civil Engineering*, 30:42–68.

- Cote, M.M. and C.R. Burn, 2002. The oriented lakes of Tuktoyaktuk Peninsula, western Arctic coast, Canada: A GIS-based analysis. *Permafrost and Periglacial Processes*, 13:61–70.
- Cremer, H., A. Andreev, H.W. Hubberten and F. Wischer, 2004. Paleolimnological reconstructions of holocene environments and climate from Lake Lyadhej-To, Ural Mountains, Northern Russia. *Arctic, Antarctic and Alpine Research*, 36:147–155.
- Cunjak, R.A., T.D. Prowse and D.L. Parrish, 1998. Atlantic salmon (*Salmo salar*) in winter: “the season of parr discontent”? *Canadian Journal of Fisheries and Aquatic Sciences*, 55:161–180.
- D’Arrigo, R., B. Buckley, S. Kaplan and J. Woollett, 2003. Interannual to multidecadal modes of Labrador climate variability inferred from tree rings. *Climate Dynamics*, 20:219–228.
- de Rham, L.P., T.D. Prowse, S. Beltaos and M.P. Lacroix, 2008a. Assessment of annual high-water events for the Mackenzie River basin, Canada. *Hydrological Processes*, 22:3864–3880.
- de Rham, L.P., T.D. Prowse and B.R. Bonsal, 2008b. Temporal variations in river-ice break-up over the Mackenzie River Basin, Canada. *Journal of Hydrology*, 349:441–454.
- Dibike, Y., T.D. Prowse, T. Saloranta and R. Ahmed, 2010. Evolution of northern hemisphere lake-ice characteristics and thermal structures in a changing climate. Paper presented at the Proceedings of 20th IAHR International Symposium on Ice, 12 pp., Lahti, Finland, 14–18 June 2010.
- Doubleday, N.C., M.S.V. Douglas and J.P. Smol, 1995. Paleoenvironmental studies of black carbon deposition in the High Arctic – a case study from Northern Ellesmere Island. *Science of the Total Environment*, 160–61:661–668.
- Douglas, M.S.V. and J.P. Smol, 1999. Freshwater diatoms as indicators of environmental change in the High Arctic. In: Stoermer, E.F. and J.P. Smol (Eds.). *The Diatoms: Applications for the Environmental and Earth Sciences*, pp. 227–244, Cambridge University Press.
- Douglas, M.S.V., J.P. Smol and W. Blake Jr., 1994. Marked post-18th century environmental change in High Arctic ecosystems. *Science*, 266:416–419.
- Duc, N.T., D. Crill and D. Bastviken, 2010. Implications of temperature and lake characteristics on methane formation and oxidation in lake sediments. *Biogeochemistry*, 100:185–196.
- Duguay, C.R. and P.M. Lafleur, 2003. Determining depth and ice thickness of shallow sub-Arctic lakes using space-borne optical and SAR data. *International Journal of Remote Sensing*, 24:475–489.
- Duguay, C.R., W.R. Rouse, P.M. Lafleur, L.D. Boudreau, Y. Crevier and T.J. Pultz, 1999. Analysis of multi-temporal ERS-1 SAR data of subarctic tundra and forest in the northern Hudson Bay Lowland and implications for climate studies. *Canadian Journal of Remote Sensing* 25:21–33.
- Duguay, C.R., T.J. Pultz, P.M. Lafleur and D. Drac, 2002. RADARSAT backscatter characteristics of ice growing on shallow sub-Arctic lakes, Churchill, Manitoba, Canada. *Hydrological Processes*, 16:1631–1644.
- Duguay, C.R., G.M. Flato, M.O. Jeffries, P. Ménard, K. Morris and W.R. Rouse, 2003. Ice-cover variability on shallow lakes at high latitudes: model simulations and observations. *Hydrological Processes*, 17:3465–3483.
- Duguay, C.R., T.D. Prowse, B.R. Bonsal, R.D. Brown, M.P. Lacroix and P. Ménard, 2006. Recent trends in Canadian lake ice cover. *Hydrological Processes*, 20:781–801.
- Dumas, J.A., G.M. Flato and R.D. Brown, 2006. Future projections of landfast ice thickness and duration in the Canadian Arctic. *Journal of Climate*, 19:5175–5189.
- EBA Engineering Consultants Ltd., 2001. Tibbitt to Contwoyto Winter Road: Project Description Report. 153 pp.
- Emmerton, C.A., L.F.W. Lesack and P. Marsh, 2007. Lake abundance, potential water storage, and habitat distribution in the Mackenzie River Delta, western Canadian Arctic. *Water Resources Research*, 43:W05419.
- Ettema, R., G. Kirkil and S. Daly, 2009. Frazil ice concerns for channels, pump-lines, penstocks, siphons, and tunnels in mountainous regions. *Cold Regions Science and Technology*, 55:202–211.
- Faïn, X., C.P. Ferrari, A. Dommergue, M.R. Albert, M. Battle, J. Severinghaus, L. Arnaud, J.M. Barnola, W. Cairns, C. Barbante and C. Bontou, 2009. Polar firn air reveals large-scale impact of anthropogenic mercury emissions during the 1970s. *Proceedings of the National Academy of Sciences of the United States of America*, 106:16114–16119.
- Finstad, A.G., T. Forseth, T.F. Næsje and O. Ugedal, 2004a. The importance of ice cover for energy turnover in juvenile Atlantic salmon. *Journal of Animal Ecology*, 73:959–966.
- Finstad, A.G., O. Ugedal, T. Forseth and T.F. Næsje, 2004b. Energy-related juvenile winter mortality in a northern population of Atlantic salmon (*Salmo salar*). *Canadian Journal of Fisheries and Aquatic Sciences*, 61:2358–2368.
- Fitzharris, B., I. Allison, R.J. Braithwaite and 10 others, 1995. Chapter 7: The cryosphere: changes and their impacts. *Climate Change 1995, Impacts, Adaptations and Mitigation of Climate Change. Scientific-Technical Analyses. Intergovernmental Panel on Climate Change*, pp. 241–265, Cambridge University Press.
- Ford, J.D., T. Pearce, J. Gilligan, B. Smit and J. Oakes, 2008. Climate change and hazards associated with ice use in Northern Canada. *Arctic, Antarctic and Alpine Research*, 40:647–659.
- Foulds, D.M., 1988. Optimum operation of hydro-electric plants during the ice regime of rivers. A Canadian experience. *National Research Council of Canada*, 31107:90 pp.
- French, H., 2007. *The Periglacial Environment*. 3rd edition. 478 pp. John Wiley and Sons Ltd.
- Furgal, C. and T.D. Prowse, 2008. Northern Canada. In: Lemmen, D.S., F.J. Warren, J. Lacroix and E. Bush (Eds.). *From Impacts to Adaptation: Canada in a Changing Climate 2007*, pp. 57–118, Government of Canada.
- Galand, P.E., C. Lovejoy, J. Pouliot, M.E. Garneau and W.F. Vincent, 2008a. Microbial community diversity and heterotrophic production in a coastal Arctic ecosystem: A stamukhi lake and its source waters. *Limnology and Oceanography*, 53:813–823.
- Galand, P.E., C. Lovejoy, J. Pouliot and W.F. Vincent, 2008b. Heterogeneous archaeal communities in the particle-rich environment of an arctic shelf ecosystem. *Journal of Marine Systems*, 74:774–782.
- Gantner, N., M. Power, D. Iqaluk, M. Meili, H. Borg, M. Sundbom, K.R. Solomon, G. Lawson and D.C. Muir, 2010a. Mercury concentrations in landlocked Arctic char (*Salvelinus alpinus*) from the Canadian Arctic. Part I: insights from trophic relationships in 18 lakes. *Environmental Toxicology and Chemistry*, 29:621–632.
- Gantner, N., D.C. Muir, M. Power, D. Iqaluk, J.D. Reist, J.A. Babaluk, M. Meili, H. Borg, J. Hammar, W. Michaud, B. Dempson and K.R. Solomon, 2010b. Mercury concentrations in landlocked Arctic char (*Salvelinus alpinus*) from the Canadian High Arctic. Part II: influence of lake biotic and abiotic characteristics on geographic trends in 27 populations. *Environmental Toxicology and Chemistry*, 29:633–643.
- Gerard, R., 1981. Regional analysis of low flows: a cold region example. Paper presented at the 5th Canadian Hydrotechnical Conference, pp. 95–113, Canadian Society for Civil Engineering, Fredericton, New Brunswick, Canada, 26–27 May 1981.
- Gerard, R., 1990. Hydrology of floating ice. In: Prowse, T.D. and C.S.L. Ommanney (Eds.). *Northern Hydrology, Canadian Perspectives*, National Hydrology Research Institute Science Report, pp. 103–134, Environment Canada.
- Gerard, R. and K.S. Davar, 1995. Introduction. In: Beltaos, S. (Ed.). *River Ice Jams*, pp. 1–28, Water Resources Publications, Highlands Ranch, CO.
- Gerten, D. and R. Adrian, 2000. Climate-driven changes in spring plankton dynamics and the sensitivity of shallow polymictic lakes to the North Atlantic Oscillation. *Limnology and Oceanography*, 45:1058–1066.
- Gerten, D. and R. Adrian, 2002. Species-specific changes in the phenology and peak abundance of freshwater copepods in response to warm summers. *Freshwater Biology*, 47:2163–2173.
- Gibson, J.J. and T.D. Prowse, 2002. Stable isotopes in river ice: identifying primary over-winter streamflow signals and their hydrological significance. *Hydrological Processes*, 16:873–890.
- Ginzburg, B.M., 1989. Calculation of probabilistic characteristics of ice regime for Northern Siberia rivers. [in Russian]. Paper presented at Ice 1987, pp. 80–85, Proceedings of conferences and meetings on hydrotechnics. Methodological problems of northern hydrotechnical construction and questions of prolongation of the navigation season, Energoatomizdat.
- Ginzburg, B.M., K.N. Polyakova and I.I. Soldatova, 1992. Secular changes in dates of ice formation on rivers and their relationship with climate change. *Russian Meteorology and Hydrology*, 12:57–64.
- Goosseff, M.N., A. Balser, W.B. Bowden and J.B. Jones, 2009. Effects of hillslope thermokarst in northern Alaska. *EOS*, 90:29–36.
- Goulding, H.L., T.D. Prowse and S. Beltaos, 2009a. Spatial and temporal patterns of break-up and ice-jam flooding in the Mackenzie Delta, NWT. *Hydrological Processes*, 23:2654–2670.
- Goulding, H.L., T.D. Prowse and B. Bonsal, 2009b. Hydroclimatic controls

- on the occurrence of break-up and ice-jam flooding in the Mackenzie Delta, NWT, Canada. *Journal of Hydrology*, 379:251–267.
- Government of Manitoba, 2009. Winter Roads in Manitoba. www.gov.mb.ca/mit/winter/index.
- Government of Manitoba, 2010. Winter Road System Closing as a Result of Melting Conditions. <http://news.gov.mb.ca/news/index.html?archive=2010-3-01&item=7955>.
- Greenwald, M.J., W.B. Bowden, M.N. Gooseff, J.P. Zarnetske, J.P. McNamara, J.H. Bradford and T.R. Brosten, 2008. Hyporheic exchange and water chemistry of two arctic tundra streams of contrasting geomorphology. *Journal of Geophysical Research*, 113:G02029.
- Grenfell, T.C. and D.K. Perovich, 2004. Seasonal and spatial evolution of albedo in a snow-ice-land-ocean environment. *Journal of Geophysical Research*, 109:C01001.
- Grey, B.J. and D.K. MacKay, 1979. Aufeis (overflow ice) in rivers. Paper presented at the Canadian Hydrology Symposium 79, pp. 139–163, National Research Council of Canada.
- Grinsted, A., J.C. Moore and S. Jevrejeva, 2010. Reconstructing sea level from paleo and projected temperatures 200 to 2100 AD. *Climate Dynamics*, 34:461–472.
- Guilyardi, E., A. Wittenberg, A. Fedorov, M. Collins, C.Z. Wang, A. Capotondi, G.J. van Oldenborgh and T. Stockdale, 2009. Understanding El Niño in ocean-atmosphere general circulation models. Progress and Challenges. *Bulletin of the American Meteorological Society*, 90:325–340.
- Hammerschmidt, C.R., W.F. Fitzgerald, C.H. Lamborg, P.H. Balcom and C.M. Tseng, 2006. Biogeochemical cycling of methylmercury in lakes and tundra watersheds of Arctic Alaska. *Environmental Science and Technology*, 40:1204–1211.
- Hamududu, B. and ÅKillingtveit, 2010. Estimating effects of climate change on global hydropower production. Paper presented at Hydropower 10. Sixth International Conference on Hydropower, Tromsø, Norway, 1–3 February 2010.
- Hicks, F., W. Cui and G. Ashton, 2008. Heat transfer and ice cover decay. In: Beltaos, S. (Ed.). *River Ice Breakup*, pp. 67–123, Water Resources Publications, Highlands Ranch, Colorado, USA.
- Hill, P.R., C.P. Lewis, S. Desmarais, V. Kauppaymuthoo and H. Rais, 2001. The Mackenzie Delta: sedimentary processes and facies of a high-latitude, fine-grained delta. *Sedimentology*, 48:1047–1078.
- Hinkel, K.M., R.C. Frohn, F.E. Nelson, W.R. Eisner and R.A. Beck, 2005. Morphometric and spatial analysis of thaw lakes and drained lake basins in the western Arctic Coastal Plain, Alaska. *Permafrost and Periglacial Processes*, 16:327–341.
- Hinzman, L.D., N.D. Bettez, W.R. Bolton and 32 others, 2005. Evidence and implications of recent climate change in northern Alaska and other arctic regions. *Climatic Change*, 72:251–298.
- Honda, M. and H. Nakamura, 2001. Interannual seesaw between the Aleutian and Icelandic lows. Part II: Its significance in the interannual variability over the wintertime Northern Hemisphere. *Journal of Climate*, 14:4512–4529.
- Honda, M., S. Yamane and H. Nakamura, 2005. Impacts of the Aleutian-Icelandic low seesaw on surface climate during the twentieth century. *Journal of Climate*, 18:2793–2802.
- Howell, S.E.L., L.C. Brown, K.K. Kang and C.R. Duguay, 2009. Variability in ice phenology on Great Bear Lake and Great Slave Lake, Northwest Territories, Canada, from SeaWinds/QuikSCAT: 2000–2006. *Remote Sensing of Environment*, 113:816–834.
- Hughen, K.A., J.T. Overpeck and R.F. Anderson, 2000. Recent warming in a 500-year palaeotemperature record from varved sediments, Upper Soper Lake, Baffin Island, Canada. *The Holocene*, 10:9–19.
- Huokuna, M., J. Aaltonen and N. Veijalainen, 2009. Frazil ice problems in changing climate conditions. Paper presented at the 15th Workshop on River Ice, pp. 118–126, CGU-HS Committee on River Ice Processes and the Environment, Edmonton, Canada, 15–17 June 2009.
- Hurrell, J.W., 1995. Decadal trends in the North Atlantic Oscillation – regional temperatures and precipitation. *Science*, 269:676–679.
- Hurrell, J.W., 1996. Influence of variations in extratropical wintertime teleconnections on Northern Hemisphere temperature. *Geophysical Research Letters*, 23:665–668.
- Huusko, A., L. Greenberg, M. Stickler, T. Linnansaari, M. Nykänen, T. Vehanen, S. Koljonen, P. Louhi and K. Alfredsen, 2007. Life in the ice lane: The winter ecology of stream salmonids. *River Research and Applications*, 23:469–491.
- IGOS, 2007. Integrated Global Observing Strategy Cryosphere Theme Report – For the Monitoring of our Environment from Space and from Earth. World Meteorological Organization, WMO/TD 1405:114.
- Jakober, M.J., T.E. McMahon, R.F. Thurow and C.G. Clancy, 1998. Role of stream ice on fall and winter movements and habitat use by bull trout and cutthroat trout in Montana headwater streams. *Transactions of the American Fisheries Society*, 127:223–235.
- Janowicz, J.R., 2009. Observed trends in the river ice regimes of Northwest Canada. Paper presented at the 17th International Northern Research Basins Symposium and Workshop, pp. 145–156, Iqaluit-Pangnirtung-Kuujuuaq, Canada, 12–18 August 2009.
- Jasek, M.J., 1999. 1998 break-up and flood on the Yukon River at Dawson – Did El Niño and climate change play a role? In: Shen, H.T. (Ed.). *Ice in Surface Waters*, pp. 761–768, Balkema, Rotterdam.
- Jeffries, M.O., K. Morris, W.F. Weeks and H. Wakabayashi, 1994. Structural and stratigraphic features and ERS 1 synthetic aperture radar backscatter characteristics of ice growing on shallow lakes in NW Alaska, winter 1991–1992. *Journal of Geophysical Research-Oceans*, 99:22459–22471.
- Kang, K.-K., C.R. Duguay, S.E. Howell, C.P. Derksen and R.E.G. Kelly, 2010. Sensitivity of AMSR-E brightness temperatures to the seasonal evolution of lake ice thickness. *IEEE Geoscience and Remote Sensing Letters*, 7:751–755.
- Karetnikov, S.G. and M.A. Naumenko, 2008. Recent trends in Lake Ladoga ice cover. *Hydrobiologia*, 599:41–48.
- Keatley, B.E., M.S.V. Douglas and J.P. Smol, 2008. Prolonged ice cover dampens diatom community responses to recent climatic change in High Arctic lakes. *Arctic, Antarctic and Alpine Research*, 40:364–372.
- Klaminder, J., K. Yoo, J. Rydberg and R. Giesler, 2008. An explorative study of mercury export from a thawing palsamire. *Journal of Geophysical Research*, 113:G04034.
- Koç, N., B. Njåstad, R. Armstrong, R.W. Corell, D.D. Jensen, K.R. Leslie, A. Rivera, Y. Tandong and J.-G. Winther (Eds.), 2009. *Melting snow and ice: a call for action*. 92 pp. Narayana Press.
- Korhola, A., 2007. Interpretation of diatom data. In: Elias, S. (Ed.). *Encyclopaedia of Quaternary Science*, pp. 494–507, Elsevier Scientific Publisher.
- Korhola, A., S. Sorvari, M. Rautio, P.G. Appleby, J.A. Dearing, Y. Hu, N. Rose, A. Lami and N.G. Cameron, 2002. A multi-proxy analysis of climate impacts on the recent development of subarctic Lake Saanaajärvi in Finnish Lapland. *Journal of Paleolimnology*, 28:59–77.
- Korhonen, J., 2006. Long-term changes in lake ice cover in Finland. *Nordic Hydrology*, 37:347–363.
- Kouraev, A.V., S.V. Semovski, M.N. Shimaraev, N.M. Mognard, B. Légresy and F. Rémy, 2007a. Observations of Lake Baikal ice from satellite altimetry and radiometry. *Remote Sensing of Environment*, 108:240–253.
- Kouraev, A.V., S.V. Semovski, M.N. Shimaraev, N.M. Mognard, B. Légresy and F. Rémy, 2007b. The ice regime of Lake Baikal from historical and satellite data: Relationship to air temperature, dynamical, and other factors. *Limnology and Oceanography*, 52:1268–1286.
- Kouraev, A.V., M.N. Shimaraev, O.I. Buharizin, M.A. Naumenko, J.-F. Crétau, N. Mognard, B. Légresy and F. Rémy, 2008. Ice and snow cover of continental water bodies from simultaneous radar altimetry and radiometry observations. *Surveys in Geophysics*, 29:271–295.
- Kusumastuti, D.I., M. Sivapalan, I. Struthers and D.A. Reynolds, 2008. Thresholds in the storm response of a lake chain system and the occurrence and magnitude of lake overflows: Implications for flood frequency. *Advances in Water Resources*, 31:1651–1661.
- Kuusisto, E. and A.R. Elo, 2000. Lake and river ice variables as climate indicators in Northern Europe. *Verhandlungen der Internationalen Vereinigung für Theoretische und Angewandte Limnologie*, 27:2761–2764.
- L'Heureux, M.L., A. Kumar, G.D. Bell, M.S. Halpert and R.W. Higgins, 2008. Role of the Pacific-North American (PNA) pattern in the 2007 Arctic sea ice decline. *Geophysical Research Letters*, 35:L20701.
- Lacroix, M.P., T.D. Prowse, B.R. Bonsal, C.R. Duguay and P. Ménard, 2005. River ice trends in Canada. Paper presented at the 13th Workshop on the Hydraulics of Ice Covered Rivers, pp. 41–55, Canadian Geophysical Union, Committee on River Ice Processes and the Environment, Hanover, NH, USA., 5–16 September 2005.
- Lamoureux, S.F. and R.S. Bradley, 1996. A late Holocene varved sediment record of environmental change from northern Ellesmere Island, Canada. *Journal of Paleolimnology*, 16:239–255.
- Lamoureux, S.F. and M.J. Lafreniere, 2009. Fluvial impact of extensive

- active layer detachments, Cape Bounty, Melville Island, Canada. Arctic, Antarctic and Alpine Research, 41:59–68.
- Latifovic, R. and D. Pouliot, 2007. Analysis of climate change impacts on lake ice phenology in Canada using the historical satellite data record. Remote Sensing of Environment, 106:492–507.
- Laurion, I., W.F. Vincent, S. MacIntyre, L. Retamal, C. Dupont, P. Francus and R. Pienitz, 2010. Variability in greenhouse gas emissions from permafrost thaw ponds. Limnology and Oceanography, 55:115–133.
- Leavitt, P.R., S.C. Fritz, N.J. Anderson and 14 others, 2009. Paleolimnological evidence of the effects on lakes of energy and mass transfer from climate and humans. Limnology and Oceanography, 54:2330–2348.
- Lemke, P., J. Ren, R. Alley, I. Allison, J. Carrasco, G. Flato, Y. Fujii, G. Kaser, P. Mote, R. Thomas and T. Zhang, 2007. Observations: Changes in snow, ice and frozen ground. In: Solomon, S., D. Qin and M. Manning (Eds.). Climate Change 2007: The Physical Science Basis. Contribution of Working Group I to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change, pp. 337–384, Cambridge University Press.
- Lenormand, F., C.R. Duguay and R. Gauthier, 2002. Development of a historical ice database for the study of climate change in Canada. Hydrological Processes, 16:3707–3722.
- Lesack, L.F.W. and P. Marsh, 2007. Lengthening plus shortening of river-to-lake connection times in the Mackenzie River Delta respectively via two global change mechanisms along the arctic coast. Geophysical Research Letters, 34:L23404.
- Lia, L., 1997. Ice in spillways in connection with dam safety. Paper presented at Hydropower '97. Proceedings of the 3rd International Conference, 2 pp., Trondheim, Norway, 30 June–2 July 1997.
- Linnansaari, T., K. Alfredsen, M. Stickler, J.V. Arnekleiv, A. Harby and R.A. Cunjak, 2009. Does ice matter? Site fidelity and movements by Atlantic salmon (*Salmo salar* L.) parr during winter in a substrate enhanced river reach. River Research and Applications, 25:773–787.
- Liu, L., H. Li and H.T. Shen, 2006. A two-dimensional comprehensive river ice model. Paper presented at the 18th IAHR International Symposium on Ice, pp. 69–76, Sapporo, Japan, August 28 – September 1, 2006.
- Livingstone, D.M., 1999. Ice break-up on southern Lake Baikal and its relationship to local and regional air temperatures in Siberia and to the North Atlantic Oscillation. Limnology and Oceanography, 44:1486–1497.
- Livingstone, D.M., 2000. Large-scale climatic forcing detected in historical observations of lake ice break-up. Verhandlungen der Internationalen Vereinigung für Theoretische und Angewandte Limnologie, 27:2775–2783.
- Livingstone, D.M., R. Adrian, T. Blenckner, G. George and G.A. Weyhenmeyer, 2010. Lake ice phenology. In: George, G. (Ed.). Impact of Climate Change on European Lakes, pp. 51–61, Springer.
- Ljungemyr, P., N. Gustafsson and A. Omstedt, 1996. Parameterization of lake thermodynamics in a high-resolution weather forecasting model. Tellus Series A, 48:608–621.
- Lokna, A., 2006. The Bjoreio Brook Inlet. Physical model studies for ice run and hydraulic capacities. MSc thesis. Department of Hydraulic and Environmental Engineering. 89 pp. NTNU, Trondheim, Norway.
- Loneragan, S., R. Difrancesco and M.K. Woo, 1993. Climate change and transportation in northern Canada - an integrated impact assessment. Climatic Change, 24:331–351.
- Luchin, V.A., I.P. Semiletov and G.E. Weller, 2002. Changes in the Bering Sea region: atmosphere-ice-water system in the second half of the twentieth century. Progress in Oceanography, 55:23–44.
- MacKay, M.D., P.J. Neale, C.D. Arp and 17 others, 2009. Modeling lakes and reservoirs in the climate system. Limnology and Oceanography, 54:2315–2329.
- Mackenzie-Grieve, J.L. and J.R. Post, 2006. Projected impacts of climate warming on production of lake trout (*Salvelinus namaycush*) in southern Yukon lakes. Canadian Journal of Fisheries and Aquatic Sciences, 63:788–797.
- Magnuson, J.J., D.M. Robertson, B.J. Benson, R.H. Wynne, D.M. Livingstone, T. Arai, R.A. Assel, R.G. Barry, V. Card, E. Kuusisto, N.G. Granin, T.D. Prowse, K.M. Stewart and V.S. Vuglinski, 2000. Historical trends in lake and river ice cover in the Northern Hemisphere. Science, 289:1743–1746.
- Marsh, P., M. Russell, S. Pohl, H. Haywood and C. Onclin, 2009. Changes in thaw lake drainage in the Western Canadian Arctic from 1950 to 2000. Hydrological Processes, 23:145–158.
- McClain, M.E., E.W. Boyer, C.L. Dent, S.E. Gergel, N.B. Grimm, P.M. Groffman, S.C. Hart, J.W. Harvey, C.A. Johnston, E. Mayorga, W.H. McDowell and G. Pinay, 2003. Biogeochemical hot spots and hot moments at the interface of terrestrial and aquatic ecosystems. Ecosystems, 6:301–312.
- McNamara, J.P. and D.L. Kane, 2009. The impact of a shrinking cryosphere on the form of arctic alluvial channels. Hydrological Processes, 23:159–168.
- McNamara, J.P., J.A. Oatley, D.L. Kane and L.D. Hinzman, 2008. Case study of a large summer flood on the North Slope of Alaska: Bedload transport. Hydrology Research, 39:299–308.
- McNight, D.M., M.N. Gooseff, W.F. Vincent and B.J. Peterson, 2008. High-latitude rivers and streams. In: Vincent, W.F. and J. Laybourn-Parry (Eds.). Polar Lakes and Rivers, pp. 83–102, Oxford University Press.
- Melles, M., J. Brigham-Grette, O.Y. Glushkova, P.S. Minyuk, N.R. Nowaczyk and H.W. Hubberten, 2007. Sedimentary geochemistry of core PG1351 from Lake El'gygytyn – a sensitive record of climate variability in the East Siberian Arctic during the past three glacial-interglacial cycles. Journal of Paleolimnology, 37:89–104.
- Metje, M. and P. Frenzel, 2007. Methanogenesis and methanogenic pathways in a peat from subarctic permafrost. Environmental Microbiology, 9:954–964.
- Michelutti, N., M.S.V. Douglas, A.P. Wolfe and J.P. Smol, 2006. Heightened sensitivity of a poorly buffered high arctic lake to late-Holocene climatic change. Quaternary Research, 65:421–430.
- Michelutti, N., A.P. Wolfe, J.P. Briner and G.H. Miller, 2007. Climatically controlled chemical and biological development in Arctic lakes. Journal of Geophysical Research, 112:G03002.
- Michmerhuizen, C.M., R.G. Striegl and M.E. McDonald, 1996. Potential methane emission from north-temperate lakes following ice melt. Limnology and Oceanography, 41:985–991.
- Milot-Roy, V. and W.F. Vincent, 1994. Ultraviolet radiation effects on photosynthesis: the importance of near-surface thermoclines in a subarctic lake. Archiv für Hydrobiologie, 43:171–184.
- Moore, J.J., K.A. Huguen, G.H. Miller and J.T. Overpeck, 2001. Little Ice Age recorded in summer temperature reconstruction from varved sediments of Donard Lake, Baffin Island, Canada. Journal of Paleolimnology, 25:503–517.
- Morris, K., M.O. Jeffries and W.F. Weeks, 1995. Ice processes and growth history on Arctic and sub-Arctic lakes using ERS-1 SAR data. Polar Record 31:115–128.
- Mueller, D.R., W.F. Vincent and M.O. Jeffries, 2003. Break-up of the largest Arctic ice shelf and associated loss of an epishelf lake. Geophysical Research Letters, 30:2031.
- Mueller, D.R., L. Copland, A. Hamilton and D. Stern, 2008. Examining Arctic ice shelves prior to the 2008 breakup. EOS, Transactions, American Geophysical Union, 89:502–503.
- Mueller, D.R., P. Van Hove, D. Antoniadis, M.O. Jeffries and W.F. Vincent, 2009. High Arctic lakes as sentinel ecosystems: Cascading regime shifts in climate, ice cover, and mixing. Limnology and Oceanography, 54:2371–2385.
- Muir, D.C., X. Wang, F. Yang, T.A. Jackson, M. Evans, M. Douglas, G. Köck, R. Pienitz, J.P. Smol, W. Vincent and S. Lamoureux, 2009. Spatial trends and historical inputs of mercury and lead in eastern and northern Canada inferred from lake sediment cores. Environmental Science and Technology, 43:4802–4809.
- Nagarajan, B., M.K. Yau and P.H. Schuepp, 2004. The effects of small water bodies on the atmospheric heat and water budgets over the MacKenzie River Basin. Hydrological Processes, 18:913–938.
- Noble, R.B., 2009. Beating tough odds on top of the world. Canadian Mining Journal, 14–15.
- Nolan, M., G. Liston, P. Prokein, J. Brigham, V.L. Sharpton and R. Huntzinger, 2003. Analysis of lake ice dynamics and morphology on Lake El'gygytyn, NE Siberia, using synthetic aperture radar (SAR) and Landsat. Journal of Geophysical Research, 107/108:8162/D8162.
- Nozhevnikova, A.N., C. Holliger, A. Ammann and A.J.B. Zehnder, 1997. Methanogenesis in sediments from deep lakes at different temperatures (12–70°C). Water Science and Technology, 36:57–64.
- Nuttall, M., F. Berkes, B. Forbes, G. Kofinas, T. Vlassova and G. Wenzel, 2005. Hunting, herding, fishing, and gathering: Indigenous peoples and renewable resource use in the Arctic. Arctic Climate Impact Assessment, pp. 650–690, Cambridge University Press.
- Outridge, P.M., H. Sanei, G.A. Stern, P.B. Hamilton and F. Goodarzi, 2007. Evidence for control of mercury accumulation rates in Canadian High

- Arctic lake sediments by variations of aquatic primary productivity. *Environmental Science and Technology*, 41:5259–5265.
- Overland, J.E. and M.Y. Wang, 2005. The third Arctic climate pattern: 1930s and early 2000s. *Geophysical Research Letters*, 32:L23808.
- Overland, J.E., M. Wang and S. Salo, 2008. The recent Arctic warm period. *Tellus Series A*, 60:589–597.
- Pavelsky, T.M. and L.C. Smith, 2004. Spatial and temporal patterns in Arctic river ice breakup observed with MODIS and AVHRR time series. *Remote Sensing of Environment*, 93:328–338.
- Payette, S., A. Delwaide, M. Caccianiga and M. Beauchemin, 2004. Accelerated thawing of subarctic peatland permafrost over the last 50 years. *Geophysical Research Letters*, 31:L18208.
- Peeters, F., D. Straile, A. Lorke and D.M. Livingstone, 2007. Earlier onset of the spring phytoplankton bloom in lakes of the temperate zone in a warmer climate. *Global Change Biology*, 13:1898–1909.
- Perren, B.B., R.S. Bradley and P. Francus, 2003. Rapid lacustrine response to recent High Arctic warming: A diatom record from Sawtooth Lake, Ellesmere Island, Nunavut. *Arctic, Antarctic and Alpine Research*, 35:271–278.
- Peters, D.L. and T.D. Prowse, 2006. Generation of streamflow to seasonal high waters in a freshwater delta, northwestern Canada. *Hydrological Processes*, 20:4173–4196.
- Pfeffer, W.T., J.T. Harper and S. O'Neil, 2008. Kinematic constraints on glacier contributions to 21st-century sea-level rise. *Science*, 321:1340–1343.
- Phelps, A.R., K.M. Peterson and M.O. Jeffries, 1998. Methane efflux from high-latitude lakes during spring ice melt. *Journal of Geophysical Research-Atmospheres*, 103:29029–29036.
- Pienitz, R., É. Saulnier-Talbot, M.-A. Fallu, T. Laing, K. Ponader, K. Swadling and I.R. Walker, 2004. Long-term climate stability in the Québec-Labrador (Canada) region: Evidence from paleolimnological studies. Paper presented at the International Symposium on Climate Change in the Arctic, Reykjavik, Iceland, 9–12 November, 2004.
- Pienitz, R., P.T. Doran and S.F. Lamoureux, 2008. Origin and geomorphology of lakes in the polar regions. In: Vincent, W.F. and J. Laybourn-Parry (Eds.). *Polar Lakes and Rivers*, pp. 25–41, Oxford University Press.
- Pouliot, J., P.E. Galand, C. Lovejoy and W.F. Vincent, 2009. Vertical structure of archaeal communities and the distribution of ammonia monooxygenase A gene variants in two meromictic High Arctic lakes. *Environmental Microbiology*, 11:687–699.
- Prowse, T.D., 1990. Guidelines for river ice data collection programs. Working Group on River Ice Jams: Field Studies and Research Needs. National Hydrology Research Institute Science Report:1-36 pp. Environment Canada.
- Prowse, T.D., 2000. *River-Ice Ecology*. 74 pp. Environment Canada.
- Prowse, T.D., 2001a. River-ice ecology. I: Hydrologic, geomorphic, and water-quality aspects. *Journal of Cold Regions Engineering*, 15:1–16.
- Prowse, T.D., 2001b. River-ice ecology. II: Biological aspects. *Journal of Cold Regions Engineering*, 15:17–33.
- Prowse, T.D., 2005. River-ice hydrology. In: Anderson, M.G. (Ed.). *Encyclopedia of Hydrological Sciences*, pp. 2657–2677, John Wiley and Sons Ltd.
- Prowse, T.D., 2009. Preface Introduction: Hydrologic effects of a shrinking cryosphere. *Hydrological Processes*, 23:1–6.
- Prowse, T.D. and B.R. Bonsal, 2004. Historical trends in river-ice break-up: a review. *Nordic Hydrology*, 35:281–293.
- Prowse, T.D. and K. Brown, 2010. Hydro-ecological effects of changing Arctic river and lake ice covers: a review. *Hydrology Research*, 41:454–461.
- Prowse, T.D. and T. Carter, 2002. Significance of ice-induced storage to spring runoff: a case study of the Mackenzie River. *Hydrological Processes*, 16:779–788.
- Prowse, T.D. and J.M. Culp, 2008. Ice breakup: a neglected factor in river ecology. In: Beltaos, S. (Ed.). *River Ice Breakup*, pp. 349–375, Water Resources Publications, Highlands Ranch, Colorado, USA.
- Prowse, T.D. and N.C. Gridley, 1993. *Environmental Aspects of River Ice*. National Hydrology Research Institute Science Report. 5:155 pp. Environment Canada.
- Prowse, T.D., B.R. Bonsal and M.P. Lacroix, 2002a. Trends in river-ice breakup and related temperature controls. Paper presented at Ice in the Environment: the 16th IAHR International Symposium on Ice, pp. 64–71, Dunedin, New Zealand, 2–6 December 2002.
- Prowse, T.D., D. Peters, S. Beltaos, A. Pietroniro, L. Romolo, J. Töyrä and R. Leconte, 2002b. Restoring ice-jam floodwater to a drying delta ecosystem. *Water International*, 27:58–69.
- Prowse, T.D., F.J. Wrona and G. Power, 2004. Dams, reservoirs and flow regulation. www.ec.gc.ca/inre-nwri/default.asp?lang=En&n=0CD66675-1&offset=7&toc=show.
- Prowse, T.D., F.J. Wrona, J.D. Reist, J.J. Gibson, J.E. Hobbie, L.M.J. Lévesque and W.F. Vincent, 2006. Climate change effects on hydroecology of Arctic freshwater ecosystems. *Ambio*, 35:347–358.
- Prowse, T.D., B.R. Bonsal, C.R. Duguay and M.P. Lacroix, 2007a. River-ice break-up/freezing-up: A review of climatic drivers, historical trends and future predictions. *Annals of Glaciology*, 26:443–451.
- Prowse, T.D., B.R. Bonsal, C.R. Duguay, D.O. Hessen and V.S. Vuglinsky, 2007b. River and lake ice. In: *Global Outlook for Ice and Snow*, pp. 201–214, United Nations Environment Programme.
- Prowse, T.D., L. de Rham and Y. Dibike, 2008. Predicting lake and river ice: modelling of historical and future conditions. *WCRP/SCAR Climate and Cryosphere Newsletter*, 10:8–9.
- Prowse, T.D., C. Furgal, R. Chouinard, H. Melling, D. Milburn and S.L. Smith, 2009a. Implications of climate change for economic development in northern Canada: Energy, resource, and transportation sectors. *Ambio*, 38:272–281.
- Prowse, T.D., C. Furgal, F.J. Wrona and J.D. Reist, 2009b. Implications of climate change for northern Canada: freshwater, marine, and terrestrial ecosystems. *Ambio*, 38:282–289.
- Prowse, T.D., R. Shrestha, Y. Dibike and B. Bonsal, 2010. Changing spring air-temperature gradients along large northern rivers: Implications for severity of river-ice floods. *Geophysical Research Letters* 37:L19706.
- Quinlan, R., M.S.V. Douglas and J.P. Smol, 2005. Food web changes in arctic ecosystems related to climate warming. *Global Change Biology*, 11:1381–1386.
- Reist, J.D., F.J. Wrona, T.D. Prowse, M. Power, J.B. Dempson, R.J. Beamish, J.R. King, T.J. Carmichael and C.D. Sawatzky, 2006a. General effects of climate change on Arctic fishes and fish populations. *Ambio*, 35:370–380.
- Reist, J.D., F.J. Wrona, T.D. Prowse, M. Power, J.B. Dempson, J.R. King and R.J. Beamish, 2006b. An overview of effects of climate change on selected Arctic freshwater and anadromous fishes. *Ambio*, 35:381–387.
- Reist, J.D., F.J. Wrona, T.D. Prowse, J.B. Dempson, M. Power, G. Kock, T.J. Carmichael, C.D. Sawatzky, H. Lehtonen and R.F. Tallman, 2006c. Effects of climate change and UV radiation on fisheries for Arctic freshwater and anadromous species. *Ambio*, 35:402–410.
- Retamal, L., S. Bonilla and W.F. Vincent, 2008. Optical gradients and phytoplankton production in the Mackenzie River and the coastal Beaufort Sea. *Polar Biology*, 31:363–379.
- Rind, D., J. Perlwitz, P. Lonergan and J. Lerner, 2005. AO/NAO response to climate change: 2. Relative importance of low- and high-latitude temperature changes. *Journal of Geophysical Research*, 110:D12108.
- Robertson, D.M., R.H. Wynne and W.Y.B. Chang, 2000. Influence of El Niño on lake and ice cover in the Northern Hemisphere from 1900 to 1995. *Verhandlungen der Internationalen Vereinigung für Theoretische und Angewandte Limnologie*, 27:2784–2788.
- Rouse, W.R., C.M. Oswald, J. Binyamin, P.D. Blanken, W.M. Schertzer and C. Spence, 2003. Interannual and seasonal variability of the surface energy balance and temperature of central Great Slave Lake. *Journal of Hydrometeorology*, 4:720–730.
- Rouse, W.R., C.J. Oswald, J. Binyamin, C.R. Spence, W.M. Schertzer, P.D. Blanken, N. Bussières and C.R. Duguay, 2005. The role of northern lakes in a regional energy balance. *Journal of Hydrometeorology*, 6:291–305.
- Rouse, W.R., P.D. Blanken, C.R. Duguay, C.J. Oswald and W.M. Schertzer, 2007. Climate-Lake Interactions. In: Woo, M.-K. (Ed.). *Cold Region Atmospheric and Hydrologic Studies, The Mackenzie GEWEX Experience. 2: Hydrologic Processes*, pp. 139–160, Springer Verlag.
- Rudd, J.W.M. and R.D. Hamilton, 1978. Methane cycling in a eutrophic shield lake and its effects on whole lake metabolism. *Limnology and Oceanography*, 23:337–348.
- Rudd, J.W.M., R.D. Hamilton and N.E. Campbell, 1974. Measurement of microbial oxidation of methane in lake water. *Limnology and Oceanography*, 19:519–524.
- Rühland, K. and J.P. Smol, 2005. Diatom shifts as evidence for recent Subarctic warming in a remote tundra lake, NWT, Canada. *Palaeogeography Palaeoclimatology Palaeoecology*, 226:1–16.
- Rühland, K., A.M. Paterson and J.P. Smol, 2008. Hemispheric-scale patterns

- of climate-related shifts in planktonic diatoms from North American and European lakes. *Global Change Biology*, 14:2740–2754.
- Sagarin, R. and F. Micheli, 2001. Climate change in nontraditional data sets. *Science*, 294:811–811.
- Saloranta, T.M. and T. Andersen, 2007. MyLake – A multi-year lake simulation model code suitable for uncertainty and sensitivity analysis simulations. *Ecological Modelling*, 207:45–60.
- Saltveit, S.J., J.H. Halleraker, J.V. Arnekleiv and A. Harby, 2001. Field experiments on stranding in juvenile Atlantic salmon (*Salmo salar*) and brown trout (*Salmo trutta*) during rapid flow decreases caused by hydropowering. *Regulated Rivers—Research and Management*, 17:609–622.
- Samuelsson, P., E. Kuorzeneva and D. Mironov, 2010. The impact of lakes on the European climate as simulated by a regional climate model. *Boreal Environment Research*, 15:113–129.
- Schertzer, W.M., W.R. Rouse, P.D. Blanken and A.E. Walker, 2003. Over-lake meteorology and estimated bulk heat exchange of Great Slave Lake in 1998 and 1999. *Journal of Hydrometeorology*, 4:649–659.
- Schertzer, W.M., W.R. Rouse, P.D. Blanken, A.E. Walker, D. Lam and L. León, 2007. Interannual variability in heat and mass exchange and thermal components of Great Slave Lake. In: Woo, M.K. (Ed.). *Cold Region Atmospheric and Hydrologic Studies, The Mackenzie GEWEX Experience*, pp. 197–219, Springer Verlag.
- Scruton, D.A., C. Pennell, L.M.N. Ollerhead, K. Alfredsen, M. Stickler, A. Harby, M. Robertson, K.D. Clarke and L.J. LeDrew, 2008. A synopsis of ‘hydropowering’ studies on the response of juvenile Atlantic salmon to experimental flow alteration. *Hydrobiologia*, 609:263–275.
- Seidou, O., T. Ouara, L. Bilodeau, M. Hessami, A. St-Hilaire and P. Bruneau, 2006. Modeling ice growth on Canadian lakes using artificial neural networks. *Water Resources Research*, 42:W11407.
- Seidou, O., T. Ouara and L. Bilodeau, 2007. Reservoir storage loss due to grounded ice during winter operation. *Journal of Hydrology*, 335:15–24.
- Semkin, R.G., G. Mierle and R.J. Neureuther, 2005. Hydrochemistry and mercury cycling in a High Arctic watershed. *Science of the Total Environment*, 342:199–221.
- Serreze, M.C., J.E. Walsh, F.S. Chapin III, T. Osterkamp, M. Dyurgerov, V. Romanovsky, W.C. Oechel, J. Morison, T. Zhang and R.G. Barry, 2000. Observational evidence of recent change in the northern high-latitude environment. *Climatic Change*, 46:159–207.
- Sharma, S., S. Couturier and S.D. Côté, 2009. Impacts of climate change on the seasonal distribution of migratory caribou. *Global Change Biology*, 15:2549–2562.
- Smith, L.C., 2000. Trends in Russian Arctic river-ice formation and breakup, 1917 to 1994. *Physical Geography*, 21:46–56.
- Smith, S.V., R.S. Bradley and M.B. Abbott, 2004. A 300 year record of environmental change from Lake Tuborg, Ellesmere Island, Nunavut, Canada. *Journal of Paleolimnology*, 32:137–148.
- Smith, L.C., Y. Sheng, G.M. MacDonald and L.D. Hinzman, 2005. Disappearing Arctic lakes. *Science*, 308:1429.
- Smith, L.C., Y.W. Sheng and G.M. MacDonald, 2007. A first pan-Arctic assessment of the influence of glaciation, permafrost, topography and peatlands on northern hemisphere lake distribution. *Permafrost and Periglacial Processes*, 18:201–208.
- Smol, J.P. and M.S.V. Douglas, 2007a. From controversy to consensus: making the case for recent climate using lake sediments. *Frontiers in Ecology and the Environment*, 5:466–474.
- Smol, J.P. and M.S.V. Douglas, 2007b. Crossing the final ecological threshold in high Arctic ponds. *Proceedings of the National Academy of Sciences of the United States of America*, 104:12395–12397.
- Smol, J.P., A.P. Wolfe, H.J.B. Birks and 23 others, 2005. Climate-driven regime shifts in the biological communities of arctic lakes. *Proceedings of the National Academy of Sciences of the United States of America*, 102:4397–4402.
- Sokolov, B.L., 1986. Runoff formation role of aufeis. [in Russian]. *Vodnye Resursy* 1: 3–14.
- Sokolov, B.L., F.A. Lifshits and M.L. Markov, 1987. Aufeis of the Baikal-Amur Railway zone. [in Russian]. *Trudy GGI*, 314:22.
- Soldatova, I.I., 1993. Secular variations in river break-up dates and their relationship with climate variation. [in Russian]. *Meteorologia i gidrologia* 9:89–96.
- Solovieva, N., V.J. Jones, L. Nazarova, S.J. Brooks, H.J.B. Birks, J.A. Grytnes, P.G. Appleby, T. Kauppi, B. Kondratyuk, I. Renberg and V. Ponomarev, 2005. Palaeolimnological evidence for recent climatic change in lakes from the northern Urals, arctic Russia. *Journal of Paleolimnology*, 33:463–482.
- Sommer, U. (Ed.), 1989. *The role of competition for resources in phytoplankton succession*. 379 pp. Springer Verlag.
- Sorvari, S., A. Korhola and R. Thompson, 2002. Lake diatom response to recent Arctic warming in Finnish Lapland. *Global Change Biology*, 8:171–181.
- St. Jacques, J.M. and D.J. Sauchyn, 2009. Increasing winter baseflow and mean annual streamflow from possible permafrost thawing in the Northwest Territories, Canada. *Geophysical Research Letters*, 36:L01401.
- Stefan, H.G. and X. Fang, 1997. Simulated climate change effects on ice and snow covers on lakes in a temperate region. *Cold Regions Science and Technology*, 25:137–152.
- Stern, G.A., E. Braekvel, P.A. Helm, T.F. Bidleman, P.M. Outridge, W.L. Lockhart, R. McNeeley, B. Rosenberg, M.G. Ikononou, P. Hamilton, G.T. Tomy and P. Wilkinson, 2005. Modern and historical fluxes of halogenated organic contaminants to a lake in the Canadian arctic, as determined from annually laminated sediment cores. *Science of the Total Environment*, 342:223–243.
- Stewart, I.T., 2009. Changes in snowpack and snowmelt runoff for key mountain regions. *Hydrological Processes*, 23:78–94.
- Stickler, M., K. Alfredsen, D.A. Scruton, C. Pennell, A. Harby and F. Økland, 2007. Mid-winter activity and movement of Atlantic salmon parr during ice formation events in a Norwegian regulated river. *Hydrobiologia*, 582:81–89.
- Stickler, M., K.T. Alfredsen, T. Linnansaari and H.-P. Fjeldstad, 2010. The influence of dynamic ice formation on hydraulic heterogeneity in steep streams. *River Research and Applications*, 26:1187–1197.
- Straile, D., 2000. Meteorological forcing of plankton dynamics in a large and deep continental European lake. *Oecologia*, 122:44–50.
- Szeto, K.K., 2002. Moisture recycling over the Mackenzie basin. *Atmosphere-Ocean*, 40:181–197.
- Thompson, R., D. Price, N. Cameron, V. Jones, C. Bigler, P. Rosén, R.I. Hall, J. Catalan, J. Garcia, J. Weckström and A. Korhola, 2005. Quantitative calibration of remote mountain-lake sediments as climatic recorders of air temperature and ice-cover duration. *Arctic, Antarctic and Alpine Research*, 37:626–635.
- Tiljander, M., M. Saarnisto, A.K. Ojala and T. Saarinen, 2003. A 3000-year palaeoenvironmental record from annually laminated sediment of Lake Korttajärvi, central Finland. *Boreas*, 32:566–577.
- Todd, M.C. and A.W. Mackay, 2003. Large-scale climatic controls on Lake Baikal ice cover. *Journal of Climate*, 16:3186–3199.
- Tomkins, J.D., S.F. Lamoureux, D. Antoniades and W.F. Vincent, 2009. Sedimentary pellets as an ice-cover proxy in a High Arctic ice-covered lake. *Journal of Paleolimnology*, 41:225–242.
- Trenberth, K.E., 1990. Recent observed interdecadal climate changes in the Northern Hemisphere. *Bulletin of the American Meteorological Society*, 71:988–993.
- Uppala, S.M., P.W. Källberg, A.J. Simmons and 43 others, 2005. The ERA-40 re-analysis. *Quarterly Journal of the Royal Meteorological Society*, 131:2961–3012.
- Vallières, C., L. Retamal, P. Ramlal, C.L. Osburn and W.F. Vincent, 2008. Bacterial production and microbial food web structure in a large arctic river and the coastal Arctic Ocean. *Journal of Marine Systems*, 74:756–773.
- van Everdingen, R.O., 1990. Ground-water hydrology. In: Prowse, T.D. and C.S.L. Ommanney (Eds.). *Northern Hydrology, Canadian Perspectives*, pp. 77–101, Environment Canada.
- Veillette, J., D.R. Mueller, D. Antoniades and W.F. Vincent, 2008. Arctic epishelf lakes as sentinel ecosystems: Past, present and future. *Journal of Geophysical Research*, 113:G04014.
- Vincent, W.F. and J. Laybourn-Parry, 2008. *Polar Lakes and Rivers – Limnology of Arctic and Antarctic Aquatic Ecosystems*. 320 pp. Oxford University Press.
- Vincent, W.F., M. Rautio and R. Pienitz, 2007. Climate control of underwater UV exposure in polar and alpine aquatic ecosystems. In: Orbaek, J.B., R. Kallenborn, I. Tombre, E. Hegseth, A. Falk-Petersen and A.H. Hoel (Eds.). *Arctic Alpine Ecosystems and People in a Changing Environment*, pp. 227–249, Springer.
- Vincent, A.C., D.R. Mueller and W.F. Vincent, 2008a. Simulated heat storage

- in a perennially ice-covered high Arctic lake: Sensitivity to climate change. *Journal of Geophysical Research*, 113:C04036.
- Vincent, W.F., S. MacIntyre, R.H. Spigel and I. Laurion, 2008b. The physical limnology of high-latitude lakes. In: Vincent, W.F. and J. Laybourn-Parry (Eds.). *Polar Lakes and Rivers – Limnology of Arctic and Antarctic Aquatic Ecosystems*, pp. 65–80, Oxford University Press.
- Vincent, W.F., J.E. Hobbie and J. Laybourn-Parry, 2008c. Introduction to the limnology of high latitude lake and river ecosystems. In: Vincent, W.F. and J. Laybourn-Parry (Eds.). *Polar Lakes and Rivers – Limnology of Arctic and Antarctic Aquatic Ecosystems*, pp. 1–23, Oxford University Press.
- Vincent, W.F., L.G. Whyte, C. Lovejoy, C.W. Greer, I. Laurion, C.A. Suttle, J. Corbeil and D.R. Mueller, 2009. Arctic microbial ecosystems and impacts of extreme warming during the International Polar Year. *Polar Science*, 3:171–180.
- von de Wall, S.J., L.P. de Rham and T.D. Prowse, 2009. Open water and ice-induced extreme water levels on Canadian rivers. Paper presented at the 17th International Northern Research Basins Symposium and Workshop, pp. 337–347, Iqaluit - Pangnirtung - Kuujuaq, Canada, 12–18 August 2009.
- Vuglinskly, V.S. and T.P. Gronskaia, 2006. Changing of rivers and lakes ice regime within the Russian territory and their possible consequences for economy. [in Russian]. Modern problems of hydrometeorology, pp. 229–245, Asterion, St. Petersburg, Russia.
- Walker, A., A. Silis, J.R. Metcalf, M.R. Davey, R.D. Brown and B.E. Goodison, 2000. Snow cover and lake ice determination in the MAGS region using passive microwave satellite and conventional data. Paper presented at the Fifth Scientific Workshop for the Mackenzie GEWEX Study, pp. 39–41, Edmonton, Canada, 21–23 November 2000.
- Wallace, J.M., Y. Zhang and J.A. Renwick, 1995. Dynamic contribution to hemispheric mean temperature trends. *Science*, 270:780–783.
- Walsh, J.E., O. Anisimov, J.O.M. Hagen, T. Jakobsson, J. Oerlemans, T.D. Prowse, V. Romanovsky, N. Savelieva, M. Serreze, A. Shiklomanov, I. Shiklomanov and S. Solomon, 2005. Cryosphere and hydrology. In: *Arctic Climate Impact Assessment*, pp. 183–242, Cambridge University Press.
- Walter, K.M., S.A. Zimov, J.P. Chanton, D. Verbyla and F.S. Chapin III, 2006. Methane bubbling from Siberian thaw lakes as a positive feedback to climate warming. *Nature*, 443:71–75.
- Walter, K.M., M.E. Edwards, G. Grosse, S.A. Zimov and F.S. Chapin III, 2007a. Thermokarst lakes as a source of atmospheric CH₄ during the last deglaciation. *Science*, 318:633–636.
- Walter, K.M., L.C. Smith and F.S. Chapin III, 2007b. Methane bubbling from northern lakes: present and future contributions to the global methane budget. *Philosophical Transactions of the Royal Society A*, 365:1657–1676.
- Walter, K.M., J.P. Chanton, F.S. Chapin III, E.A.G. Schuur and S.A. Zimov, 2008a. Methane production and bubble emissions from arctic lakes: Isotopic implications for source pathways and ages. *Journal of Geophysical Research*, 113:G00A08.
- Walter, K.M., M. Engram, C.R. Duguay, M.O. Jeffries and F.S. Chapin III, 2008b. The potential use of synthetic aperture radar for estimating methane ebullition from Arctic lake. *Journal of the American Water Resources Association*, 44:305–315.
- Weber, F., D. Nixon and J. Hurley, 2003. Semi-automated classification of river ice types on the Peace River using RADARSAT-1 synthetic aperture radar (SAR) imagery. *Canadian Journal of Civil Engineering*, 30:11–27.
- Weyhenmeyer, G.A., 2008. Water chemical changes along a latitudinal gradient in relation to climate and atmospheric deposition. *Climatic Change*, 88:199–208.
- Weyhenmeyer, G.A., 2009a. Do warmer winters change variability patterns of physical and chemical lake conditions in Sweden? *Aquatic Ecology*, 43:653–659.
- Weyhenmeyer, G.A., 2009b. Increasing dissimilarity of water chemical compositions in a warmer climate. *Global Biogeochemical Cycles*, 23:GB2004.
- Weyhenmeyer, G.A., T. Blenckner and K. Pettersson, 1999. Changes of the plankton spring outburst related to the North Atlantic Oscillation. *Limnology and Oceanography*, 44:1788–1792.
- Weyhenmeyer, G.A., M. Meili and D.M. Livingstone, 2004. Nonlinear temperature response of lake ice breakup. *Geophysical Research Letters*, 31:L07203.
- Weyhenmeyer, G.A., M. Meili and D.M. Livingstone, 2005. Systematic differences in the trend toward earlier ice-out on Swedish lakes along a latitudinal temperature gradient. *Verhandlungen der Internationalen Vereinigung für Theoretische und Angewandte Limnologie*, 29:257–260.
- White, K.D. and H.J. Eames, 1999. CRREL ice jam data base. Report 99–2. 24 pp. US Army Corps of Engineers Cold Regions Research and Engineering Laboratory, Hanover, NH, USA.
- White, D., L. Hinzman, L. Alessa and 20 others, 2007. The arctic freshwater system: Changes and impacts. *Journal of Geophysical Research*, 112:G04S54.
- Williamson, C.E., D.P. Morris, M.L. Pace and A.G. Olson, 1999. Dissolved organic carbon and nutrients as regulators of lake ecosystems: Resurrection of a more integrated paradigm. *Limnology and Oceanography*, 44:795–803.
- Winder, M. and D.E. Schindler, 2004. Climatic effects on the phenology of lake processes. *Global Change Biology*, 10:1844–1856.
- Winder, M., J.E. Reuter and S.G. Schladow, 2009. Lake warming favours small-sized planktonic diatom species. *Proceedings of the Royal Society B*, 276:427–435.
- Wolfe, A.P. and I.R. Smith, 2004. Paleolimnology of the Canadian Arctic Archipelago. In: Pienitz, R., M.S.V. Douglas and J.P. Smol (Eds.). *Long-Term Environmental Change in Arctic and Antarctic Lakes*, pp. 241–268, Springer.
- Wolfe, B.B., R.I. Hall, W.M. Last, T.W.D. Edwards, M.C. English, T.L. Karst-Riddoch, A. Paterson and R. Palmi, 2006. Reconstruction of multi-century flood histories from Oxbow Lake sediments, Peace-Athabasca Delta, Canada. *Hydrological Processes*, 20:4131–4153.
- Woo, M.K. and R. Heron, 1989. Freeze-up and break-up of ice cover on small Arctic lakes. In: Mackay, W.C. (Ed.). *Northern Lakes and Rivers*, pp. 56–62, Boreal Institute for Northern Studies, University of Alberta.
- Wrona, F.J., T.D. Prowse, J.D. Reist, R. Beamish, J.J. Gibson, J. Hobbie, E. Jeppesen, J. King, G. Koeck, A. Korhola, L. Levesque, R. Macdonald, M. Power, V. Skvortsov and W. Vincent, 2005. Freshwater ecosystems and fisheries. In: *Arctic Climate Impact Assessment*, pp. 353–452, Cambridge University Press.
- Wrona, F.J., T.D. Prowse, J.D. Reist, J.E. Hobbie, L.M.J. Lévesque and W.F. Vincent, 2006. Climate change effects on aquatic biota, ecosystem structure and function. *Ambio*, 35:359–369.
- Yang, D.Q., Y.Y. Zhao, R. Armstrong, D. Robinson and M.J. Brodzik, 2007. Streamflow response to seasonal snow cover mass changes over large Siberian watersheds. *Journal of Geophysical Research*, 112:F02S22.
- Yang, D.Q., Y.Y. Zhao, R. Armstrong and D. Robinson, 2009. Yukon River streamflow response to seasonal snow cover changes. *Hydrological Processes*, 23:109–121.
- Yoo, J.C. and P. D'Odorico, 2002. Trends and fluctuations in the dates of ice break-up of lakes and rivers in Northern Europe: the effect of the North Atlantic Oscillation. *Journal of Hydrology*, 268:100–112.
- Yoshikawa, K., L.D. Hinzman and D.L. Kane, 2007. Spring and auferis (icing) hydrology in Brooks Range, Alaska. *Journal of Geophysical Research*, 112:G04S43.
- Zachrisson, G., 1989. Climate variation and ice conditions in the River Torneälven. Paper presented at the Conference on Climate and Water, pp. 353–364, Publications of the Academy of Finland.
- Zarnetske, J.P., M.N. Gooseff, W.B. Bowden, M.J. Greenwald, T.R. Brosten, J.H. Bradford and J.P. McNamara, 2008. Influence of morphology and permafrost dynamics on hyporheic exchange in arctic headwater streams under warming climate conditions. *Geophysical Research Letters*, 35:L02501.
- Zhang, X.B., K.D. Harvey, W.D. Hogg and T.R. Yuzik, 2001. Trends in Canadian streamflow. *Water Resources Research*, 37:987–998.
- Zhang, X.B., F.W. Zwiers, G.C. Hegerl, F.H. Lambert, N.P. Gillett, S. Solomon, P.A. Stott and T. Nozawa, 2007. Detection of human influence on twentieth-century precipitation trends. *Nature*, 448:461–465.
- Zhang, X.D., A. Sorteberg, J. Zhang, R. Gerdes and J.C. Comiso, 2008. Recent radical shifts of atmospheric circulations and rapid changes in Arctic climate system. *Geophysical Research Letters*, 35:L22701.
- Zimov, S.A., Y.V. Voropaev, S.P. Davidov, G.M. Zimova, A.E. Davydova, F.S. Chapin, III and M.C. Chapin, 2001. Flux of methane from North Siberian aquatic systems: Influence on atmospheric methane. In: Paepe, R. and V. Melnikov (Eds.). *Permafrost Response on Economic Development, Environmental Security and Natural Resources*, pp. 511–524, Kluwer Academic Publishers.

7. Mountain Glaciers and Ice Caps

COORDINATING LEAD AUTHOR: MARTIN SHARP

LEAD AUTHORS: MARIA ANANICHEVA, ANTHONY ARENDT, JON-OVE HAGEN, REGINE HOCK, EDWARD JOSBERGER, R. DAN MOORE, WILLIAM TAD PFEFFER, GABRIEL J. WOLKEN

CONTRIBUTING AUTHORS: HELGI BJÖRNSSON, CARL EGEDE BØGGILD, TOBIAS BOLCH, IGOR BUZIN, JOHN J. CLAGUE, JOHN GRAHAM COGLEY, JULIAN A. DOWDESWELL, MARK B. DYURGEROV, ANDREY GLAZOVSKY, HESTER JISKOOT, TÓMAS JÓHANNESSON, ALEXANDER KLEPIKOV, ALEXANDER KRENKE, MARK F. MEIER, BRIAN MENOUNOS, ALEXANDER MILNER, YAROSLAV MURAVYEV, MATT NOLAN, FINNUR PALSSON, VALENTINA RADIĆ, MATTIAS DE WOUL

Contents

Key Findings	2	7.6.2. Modeling mountain glacier and ice cap mass balance in the 21st century	30
Summary	2	7.6.3. Modeling ice dynamics and ice extent	31
7.1. Introduction	3	7.7. Impacts of changes in mountain glaciers and ice caps	33
7.1.1. Background	3	7.7.1. Impacts on sea level	33
7.1.2. Context: What did the Arctic Climate Impact Assessment report say about mountain glaciers and ice caps?	4	7.7.2. Impacts on the marine environment	34
7.1.3. Geographic setting	4	7.7.3. Impacts on water resources	36
7.1.4. Characteristics of Arctic mountain glaciers and ice caps ..	5	7.7.4. Glacier ecosystems	39
7.1.5. Significance and impacts of glacier changes	7	7.7.5. Geomorphological hazards	40
7.1.6. Challenges	8	7.7.6. Glacier-related tourism	41
7.2. Climate evolution in glacierized regions of the Arctic ..	8	7.8. New information expected from International Polar Year projects	42
7.2.1. Holocene climate	8	7.8.1. Alaska	42
7.2.2. Arctic ice cores: Holocene climate records from glacierized regions	9	7.8.2. Arctic Canada	42
7.2.3. Climate records for glacierized regions of the Arctic derived from instrumental observations and climate re-analysis	10	7.8.3. Iceland	43
7.3. Changes in glacier extent, volume and total mass	11	7.8.4. Svalbard	43
7.3.1. Arctic glacier changes during the Holocene	11	7.8.5. Russian Arctic and mountains	43
7.3.2. Arctic glacier changes in the 20th and 21st centuries ..	12	7.9. Synthesis of the current state of Arctic mountain glaciers and ice caps	44
7.3.3. Links between mass balance and climate	18	7.9.1. Mountain glacier and ice cap mass balance	44
7.4. Proxy indicators of surface mass balance	18	7.9.2. Ablation due to iceberg calving	45
7.4.1. Introduction	19	7.9.3. Observed trends in ice extent	46
7.4.2. Proxy indicators, data sources, and methods of measurement	19	7.9.4. Relationship to climate and circulation changes	46
7.5. Ice dynamics and iceberg calving	22	7.9.5. Projections of future change	47
7.5.1. Overview	23	7.9.6. Impacts	47
7.5.2. Measurement methods	24	7.10. Knowledge gaps and recommendations	47
7.5.3. Calving and surging glaciers in the Arctic	25	7.10.1. Key gaps in knowledge	48
7.5.4. Recent ice shelf break-up events	27	7.10.2. Basic observations	48
7.5.5. Iceberg characteristics and relationship to ice dynamics ..	28	7.10.3. Mass balance measurements, proxies, and modeling ..	48
7.5.6. Controls on calving fluxes	28	7.10.4. Ice dynamics and ablation by iceberg calving	49
7.5.7. State of theory and modeling	28	7.10.5. Impacts	49
7.5.8. Requirements for improved predictions of calving fluxes ..	29	Appendix 7.1 Glossary of glaciological terms	50
7.6. Projections of Arctic glacier changes	29	References	52
7.6.1. Downscaling climate model projections	29		

Key Findings

- Mountain glaciers and ice caps in the Arctic cover an area of around 402 000 km² and contain about 0.41 m sea-level equivalent of water.
- Over the past century, nearly all have retreated from maximum extents reached during the Little Ice Age, which ended in the late 19th century. This period of glacier retreat has been associated with an overall reduction in glacier mass during the period of record, which extends to more than 60 years in some cases. Surface mass balance measurements showed negative or nearly balanced conditions and generally showed no trend until the mid-1990s, but since then reveal significantly higher rates of mass loss in Alaska, the Canadian Arctic, and Iceland.
- The fraction of ablation that occurs through iceberg calving can be as much as 40% in regions where it has been measured, but it has not been measured over large areas of the Arctic. Estimation of calving fluxes is therefore a major source of uncertainty in estimates of current and future rates of mass loss from mountain glaciers and ice caps in the Arctic.
- Mass loss (surface mass balance plus calving) from Arctic glaciers probably exceeded 150 Gt/y in the past decade, when it was similar to mass loss from the Greenland Ice Sheet. This suggests that glacier and ice sheet change in the Arctic is probably now the dominant contributor to the eustatic (water mass) component of global sea level rise.
- Under the IPCC A1B emissions scenario, the total volume of Arctic glaciers is projected to decline by between 13% and 36% by 2100 (corresponding to an increase of 51 to 136 mm sea-level equivalent), depending on the choice of general circulation model. These projections are a lower bound since they do not include mass losses by iceberg calving. Regardless, mountain glaciers and ice caps will continue to influence global sea-level changes beyond the 21st century.
- In many parts of the Arctic, climate warming should cause glacier runoff to increase for a few decades or longer, but glacier area reduction will ultimately cause glacier runoff to decline. These changes in glacier runoff will have impacts on water supplies; water quality; hydroelectric power generation; flood hazards; freshwater, estuarine and coastal habitats; and ocean circulation patterns.
- Iceberg hazards to shipping and offshore activities related to exploration for and exploitation of offshore hydrocarbon and mineral resources may increase if changes in tidewater glacier dynamics result in more iceberg production and/or larger bergs, and reductions in sea-ice cover allow icebergs to become more mobile.

Summary

In addition to the Greenland Ice Sheet, the Arctic contains a diverse array of smaller glaciers ranging from small cirque glaciers to large ice caps with areas up to 20 000 km². Together, these glaciers cover an area of more than 400 000 km², over half the global area of mountain glaciers and ice caps. Their total volume is sufficient to raise global sea level by an average of about 0.41 m if they were to melt completely.

These glaciers exist in a range of different climatic regimes, from the maritime environments of southern Alaska, Iceland, western Scandinavia, and Svalbard, to the polar desert of the Canadian Arctic. Glaciers in all regions of the Arctic have decreased in area and mass as a result of the warming that has occurred since the 1920s (in two pulses – from the 1920s to the 1940s and since the mid-1980s). A new phase of accelerated mass loss began in the mid-1990s, and has been most marked in Alaska, the Canadian Arctic, and probably Greenland. Current rates of mass loss are estimated to be in the range 150 to 300 Gt/y; comparable to current mass loss rates from the Greenland Ice Sheet. This implies that the Arctic is now the largest regional source of glacier contributions to global sea-level rise.

Most of the current mass loss is probably attributable to a change in surface mass balance (the balance between annual mass addition, primarily by snowfall, and annual mass loss by surface melting and meltwater runoff). Iceberg calving is also a significant source of mass loss in areas such as coastal Alaska, Arctic Canada, Svalbard, and the Russian Arctic. However, neither the current rate of calving loss nor its temporal variability have been well quantified in many regions, so this is a significant source of uncertainty in estimates of the total rate of mass loss. It is, however, clear that the larger Arctic ice caps have similar variability in ice dynamics to that of the Greenland Ice Sheet. That is to say, areas of relatively slow glacier flow (which terminate mainly on land) are separated by faster-flowing outlet glaciers (which terminate mainly in the ocean). Several of these outlet glaciers exhibit surge-type behavior, while others have exhibited substantial velocity changes on seasonal and longer timescales. It is very likely that these changes in ice dynamics affect the rate of mass loss by calving both from individual glaciers and the total ice cover.

Projections of future rates of mass loss from mountain glaciers and ice caps in the Arctic focus primarily on projections of changes in the surface mass balance. Current models are not yet capable of making realistic forecasts of changes in losses by calving. Surface mass balance models are forced with downscaled output from climate models driven by forcing scenarios that make assumptions about the future rate of growth of atmospheric greenhouse gas concentrations. Thus, mass loss projections vary considerably, depending on the forcing scenario used and the climate model from which climate projections are derived. A new study in which a surface mass balance model is driven by output from ten general circulation models (GCMs) forced by the IPCC (Intergovernmental Panel on Climate Change) A1B emissions scenario yields estimates of total mass loss of between 51 and 136 mm sea-level equivalent (SLE) (or 13% to 36% of current glacier volume) by 2100. This implies that there will still be substantial glacier mass in the Arctic in 2100 and that Arctic mountain glaciers and ice caps will continue to influence global sea-level change well into the 22nd century.

As glaciers and ice caps shrink in a warming climate, runoff initially increases in response to higher rates of surface melting. Ultimately, however, runoff will decline as reductions in glacier area outweigh the effect of more rapid melting. This phase of declining runoff does not yet seem to have begun in most regions of the Arctic, but it may begin soon in the Russian Arctic mountains. In the Yukon River basin, Greenland, Iceland, and Norway, glacier runoff is an important resource for hydroelectric power generation, and the viability of hydroelectric projects may ultimately be compromised by runoff decreases associated with glacier shrinkage.

Changes in glacier runoff also result in changes in stream temperature, sediment load, and nutrient export (both magnitude and type) that can be expected to initiate changes in the ecology and productivity of downstream river, lake, and fjord environments. Increased rates of glacier melt may accelerate the release of a range of ‘legacy’ pollutants stored in firn (partially compacted snow that is the intermediate stage between snow and glacier ice) and glacier ice back into the environment. Increasing freshwater fluxes to fjords and other nearshore marine environments will alter the characteristics of surface water masses and drive changes in circulation. Circulation changes may also follow the retreat of tidewater glaciers onto land, particularly in regions of upwelling close to the termini of these glaciers. These changes can decrease the availability of feeding and resting habitats that are important for marine mammals and seabirds.

The number and size of icebergs produced is likely to change as tidewater glaciers retreat, ultimately reaching zero as their termini emerge onto land. Break-up of floating glacier tongues and ice shelves, a process that has accelerated in the past decade along the northern coast of Ellesmere Island, results in large tabular bergs, while accelerated flow of tidewater glaciers tends to result in accelerated production of small bergs unless flotation of the glacier terminus occurs, when large tabular bergs may be produced. Cessation of small berg production when tidewater termini retreat onto land can reduce the number of such bergs that become grounded in fjords, decreasing the availability of important resting habitat for seals. Circulating icebergs are a potential hazard for shipping, drilling platforms, and seafloor pipelines in the Arctic. Circulation patterns and longevity of bergs may change as the Arctic sea-ice cover declines. Thinner and less extensive sea ice is likely to result in greater berg mobility, while warmer surface waters may result in more rapid melting and disintegration of bergs. A knowledge of the size distributions of bergs produced and circulating in different regions is critical to evaluating the risk of bergs contacting the sea floor and damaging seafloor pipelines.

Glacier retreat will be associated with changes in the magnitude and frequency of a range of geomorphological hazards, most notably outburst floods from ice-marginal and moraine-dammed proglacial lakes, and mass movements from newly deglaciated valley walls. The degree of risk from such phenomena will, however, be highly variable, depending upon the nature of the deglaciated terrain, the size of local populations, and the amount of infrastructure present in individual regions.

Finally, it should be emphasized that the ability to monitor and predict changes in the Arctic’s mountain glaciers and ice caps is still quite limited. Basic inventory data for Arctic

glaciers are lacking. The number of glaciers on which mass balance is measured is small and declining, and the distribution of measurement sites is highly non-uniform. There are no measurement sites at all in some areas with large glacier areas (such as the Russian Arctic and the Yukon). There is no routine monitoring of mass losses by iceberg calving, and understanding of what controls calving rates is rudimentary. This severely constrains the ability to model calving losses into the future. Studies of the socio-economic impacts of Arctic glacier change are currently few and limited in scope, so most statements about such impacts are based solely on general principles. As such, they do not provide a strong basis for either the formulation or enactment of a policy response to Arctic glacier change. Some of the largest impacts of the ongoing changes in Arctic glaciers (such as global sea-level rise) will be felt in regions of the world that are very far from the Arctic. They may, however, still have social, political, and economic repercussions for Arctic nations – repercussions that need to be explored more thoroughly.

7.1. Introduction

- Mountain glaciers and ice caps cover an area of nearly 402 000 km² in the Arctic. Over half of this area is in western North America and the Canadian Arctic.
- The combined volume of these glaciers is sufficient to raise sea level by around 0.41 m if they all melted.
- Glacier types range from small cirque glaciers to large ice caps, with areas of up to 20 000 km². These ice caps are dynamically complex, and are drained in part by fast-flowing outlet glaciers that often reach the ocean and lose mass by calving icebergs.
- In many regions, a proportion of the glaciers exhibit ‘surge-type’ behavior, in which long periods of flow at relatively low speeds are punctuated by short-lived episodes of very rapid flow.
- Long-term changes in the extent, volume, and mass of these glaciers are driven by changes in climate and oceanographic conditions that alter their ‘mass balance’ – the annual balance between mass gains (due mainly to snowfall) and mass losses (due mainly to surface melting and runoff, and iceberg calving).
- Changes in the thermal structure and flow of glaciers can play an important role in how, and how rapidly, they respond to changing climate and oceanographic conditions.

7.1.1. Background

Glacier ice (including mountain glaciers, ice caps and the Greenland Ice Sheet) occupies about 2.16 million km² of the Arctic land surface. This chapter deals with all mountain glaciers and ice caps (hereafter referred to as glaciers), including those in Greenland that are not connected to the ice sheet. The Greenland Ice Sheet itself is addressed in Chapter 8. Mountain glaciers are ice bodies whose geometry and boundaries are controlled by bedrock topography, while ice caps are dome-shaped ice bodies that submerge the underlying bedrock topography. Table 7.1 presents the regional distribution of the

Table 7.1. The areas (rounded to three significant figures) and estimated volumes, in mm sea-level equivalent (SLE), of ice caps and glaciers in the Arctic compared to global values and the ice sheets in Greenland and Antarctica.

Region	Ice-covered area, km ²	Volume ^a , mm SLE	Source, area
Canadian Arctic	1 51 000	199 ± 30	Ommanney, 1970
Northwestern North America	91 800	71 ± 8	Berthier et al., 2010; ESRI, 2003
Russian Islands ^b	56 700	44 ± 8	Radić and Hock, 2010
Greenland ^c	48 600	44 ± 7	Weng, 1995
Svalbard	36 500	26 ± 2	Hagen et al., 1993
Iceland	11 000	12 ± 6	Björnsson and Pálsson, 2008
Scandinavia	3 100	6 ± 0	Østrem et al., 1973, 1988
Russian Arctic	2 900	4 ± 0	Radić and Hock, 2010
Total (Arctic)	401 600	410 ± 30	
Mountain glaciers and ice caps (global)	741 400	600 ± 70	Radić and Hock, 2010
Greenland Ice Sheet	1 755 600	7500	Bamber et al., 2001
Antarctic ice sheet	12 348 000	57 000	Fox and Cooper, 1994 (areas)
Antarctic ice shelves	1 555 000		Lythe et al., 2001 (volume)

^a Volumes of all mountain glaciers and ice caps are from Radić and Hock (2010); ^b Franz Josef Land (13 700 km²), Novaya Zemlya (23 600 km²), Severnaya Zemlya (19 400 km²); ^c Greenland excluding the ice sheet: only the glaciers physically disconnected from the ice sheet are considered here. Areas over 70 000 km² have been reported (Holtzschcher and Bauer, 1954; Weidick and Morris, 1998); however, these estimates have included some glaciers that are connected to the ice sheet but considered independent of the ice sheet in a dynamic sense or that were, by their morphology, discernible as units independent of the ice sheet. Nevertheless, the estimate by Weng (1995) is a minimum estimate because it is based on a 1:2 500 000 map, a scale too coarse to allow identification of many small glaciers.

area and volume of glacier ice in the Arctic. Here, the ice volume is given in units of mm sea-level equivalent (SLE), which is the volume of water (in m³) stored as glacier ice, divided by the surface area of the global ocean (in m²) multiplied by 1000.

7.1.2. Context: What did the Arctic Climate Impact Assessment report say about mountain glaciers and ice caps?

The SWIPA report is an update of knowledge on the state of the Arctic cryosphere relative to the Arctic Climate Impact Assessment (ACIA, 2005). This dealt with mountain glaciers, ice caps, and the Greenland Ice Sheet in a single section of chapter 6, '*Cryosphere and Hydrology*'. It gave a regional summary of glacier changes since around 1950 with an emphasis on measurements of surface mass balance and, for regions where mass balance measurements were lacking, changes in glacier area. Mass losses by iceberg calving were mentioned but not discussed in detail. The major ACIA contribution was a series of projections of changes in the surface mass balance of Arctic glaciers for the period until 2100. These mass balance projections were computed using regional seasonal sensitivity characteristics (a measure of the expected change in the annual surface mass balance due to prescribed changes in monthly mean air temperature and precipitation amounts) and projected changes in temperature and precipitation derived from a suite of five GCMs forced by the IPCC B2 emissions scenario. The mass balance projections were used to estimate the potential contributions of different regions of the Arctic to sea level rise over the 21st century. The ACIA report also commented on the potential impacts of changes in glaciers for other parts of the physical system,

ecosystems, and people, and gave an assessment of critical research needs that remains valid today.

7.1.3. Geographic setting

The glacierized areas (i.e. those presently overlain by glaciers) addressed in this chapter are shown in Figure 7.1. Most of the glaciers are located north of 60° N, but some more southerly glaciers, in Kamchatka, Alaska, and northwestern Canada are also included (Table 7.1). The total glacier-covered area is approximately 402 000 km², which is about 54% of all glaciers in the world excluding the large ice sheets (~741 400 km², Radić and Hock, 2010).

Arctic glaciers are irregularly distributed in space (Figure 7.1), and are located in a range of very different climatic regimes (Braithwaite, 2005). In southern Alaska, Iceland, western Scandinavia, and western Kamchatka, the climate is maritime with a relatively small annual temperature range and precipitation rates of a few metres per year, while in the Canadian High Arctic it is very dry, cold and continental, with short summers, a very large annual temperature range (greater than 50 °C), and annual precipitation that ranges from 0.1 to 0.7 m/y. Conditions on Svalbard and in the Russian Arctic islands fall between these two climatic extremes. In northwestern North America, most of the ice cover is in the mountain ranges adjacent to the Gulf of Alaska, while in Arctic Canada the most heavily glacierized regions are in the mountains on Devon and Ellesmere Islands, which are nourished in part by moisture from a large persistent polynya in northern Baffin Bay (the North Open Water).




Figure 7.1. Map of the Arctic showing the distribution of regions containing mountain glaciers and ice caps considered in this report and the major glacierized areas.

7.1.4. Characteristics of Arctic mountain glaciers and ice caps

7.1.4.1. Morphology

Arctic glaciers have a range of forms. Dome-shaped ice caps have lobes and outlet glaciers that drain ice away from the accumulation area, where annual snowfall exceeds annual surface melt, to lower-lying regions (ablation areas) where the reverse is true, and in some cases to tidewater margins where the ice reaches the ocean and icebergs are calved. Large ice caps are found in the Canadian Arctic, Iceland, Svalbard, the Russian Arctic islands, and in Greenland beyond the margins of the ice sheet (Figure 7.2). In other regions, large glaciers originate from icefields that fill basins within mountain ranges (e.g., in southern Alaska). Many regions, for example Svalbard, also have a large number of individual valley glaciers that occupy valleys and basins in the landscape.

Much of the Arctic ice mass is contained in relatively large ice caps with areas of up to 20 000 km², although there are large numbers of independent glaciers with areas ranging from 0.1 to several thousand km² (Dowdeswell and Hagen, 2004). The largest ice masses in the Arctic are found in Arctic Canada, and include the Agassiz Ice Cap (17 300 km²) and Prince of Wales Icefield (19 400 km²) on Ellesmere Island, the Devon Island Ice Cap (about 14 400 km²), and the Barnes and Penny Ice Caps (each almost 6000 km²) on Baffin Island. On Greenland, the largest independent ice cap is the ~9000 km² Flade Isblink in the northeast, while the more northerly Hans Tausen Ice Cap,

at 3975 km², is probably the best studied (Reeh et al., 2001). Austfonna on Nordaustlandet in eastern Svalbard (8120 km²) is the largest ice cap in the Eurasian Arctic (Dowdeswell, 1986; Hagen et al., 1993). The largest Russian ice cap is the Academy of Sciences Ice Cap (5575 km²) on Severnaya Zemlya (Dowdeswell et al., 2002), although the northern island of Novaya Zemlya has a larger ice-covered area with many outlet glaciers. In Iceland, Vatnajökull has an area of 8100 km² (Björnsson and Pálsson,



Figure 7.2. Small plateau ice caps on Axel Heiberg Island, Arctic Canada, with a larger ice cap in the distance. Note the clear contrast between the snow-covered accumulation area and the greyer ablation area, and the outlet glaciers draining into valleys leading away from the ice cap. Source: Martin Sharp, University of Alberta.

2008). Among the mountain glaciers (Figure 7.3), the largest is Bering Glacier in Alaska, with an area of 3630 km².

The larger Arctic ice caps and icefields (Figure 7.4) have complex dynamics involving a mix of fast- and slow-flowing elements that can vary in how they respond to climate changes and variability. Vestfonna on Nordaustlandet in eastern Svalbard is a good example, where four fast-flowing outlet glaciers are embedded within a largely slower-flowing ice cap of 2500 km² (Dowdeswell and Collin, 1990). Typical surface velocities may be less than 10 m/y close to the equilibrium-line altitude of valley and cirque glaciers that terminate on land. They can reach many hundreds of metres per year on major calving outlet glaciers, on which seasonal velocity variations can be large, with summer velocities up to an order of magnitude greater than winter velocities (Williamson et al., 2008). Interannual velocity variations can also be significant on such glaciers.

7.1.4.2. Thermal regime

Most glaciers in Iceland, Scandinavia, and central and southern Alaska are predominantly temperate (composed of ice at the pressure melting point). Elsewhere in the Arctic, glaciers tend




Figure 7.3. Gulkana Glacier in Alaska is a typical mountain glacier and a long-term mass balance monitoring site. Note the end moraines surrounding the glacier terminus that indicate that the glacier was more extensive and thicker in the past. Source: U.S. Geological Survey.



Figure 7.4. The Glacier Bay Icefield, Alaska. Outlet glaciers drain outward from a central accumulation area within the mountains. Source: Landsat imagery courtesy of NASA Goddard Space Flight Center and U.S. Geological Survey.

to have polythermal temperature regimes (composed of a mixture of ice at and below the pressure melting point), and their dynamics may be strongly affected by climate-driven changes in the thermal regime. In some parts of polythermal glaciers, the ice temperature at the glacier bed is below the melting point, implying that the glacier is frozen to its bed. In some smaller (cold) glaciers, all the ice is at temperatures below the melting point, except at the surface where the ice temperature may reach the melting point in summer. The thermal regime of glaciers is determined by the prevailing climatic conditions (snow accumulation and surface energy balance). Climatic change can alter the thermal regime of a glacier, and potentially also its dynamics, because ice deforms more rapidly at higher temperatures and glacier flow can be enhanced by the lubricating effect of meltwater at the glacier bed. Most cold-based and polythermal glaciers are found in dry regions with low accumulation rates. It takes a long time for a climate change signal to penetrate into such glaciers, and changes in the temperature regime are probably not very large on a 100-year timescale. However, in areas where penetration of surface meltwater into cold firn on the glacier surface increases, the release of latent heat when this meltwater refreezes can cause a more rapid change in the thermal regime.

Owing to the polythermal nature of many Arctic glaciers, the formation of superimposed ice by meltwater refreezing on the glacier surface and internal accumulation (where percolating meltwater freezes in cold snow and firn) can be important processes of mass accumulation. When these processes occur, the refrozen water has to be melted again to become meltwater runoff, complicating the measurement and modeling of the surface mass balance. Neglecting or inadequately accounting for these processes in mass balance measurements overestimates mass loss. Superimposed ice formation is important on many Arctic glaciers and is the dominant form of accumulation on some (Koerner, 1970).

Surge-type glacier behavior is common in many parts of the Arctic and can be a source of significant hazards. In a glacier surge, surface velocities increase by an order of magnitude or more and glacier fronts can advance many kilometres (sometimes more than 10 km) in a matter of years. When tidewater glaciers surge, iceberg production increases and can be an important process of mass loss from the glacier (Liestøl, 1973; Dowdeswell, 1989). While the occurrence of individual surges is not directly related to climate change, climate change may alter the frequency of surging (Dowdeswell et al., 1991; Eisen et al., 2001), or even cause glaciers to cease being of the surge type (Dowdeswell et al., 1995). Changes in the number of actively surging glaciers in a region that extend into tidewater can have a large short-term impact on the regional glacier mass balance through changes in the overall calving flux to the ocean.

7.1.4.3. Tidewater glaciers

Iceberg calving plays a major role in the overall mass balance of tidewater glaciers and Arctic ice caps that have significant tidewater margins (Dowdeswell et al., 1997, 2008; Dowdeswell and Hagen, 2004; Błaszczyk et al., 2009) (Figure 7.5). However, accurate calculation of the calving flux requires information that is frequently not available (e.g., ice thickness at the glacier terminus), and modeling of calving flux is challenging because



Figure 7.5. Time-lapse camera overlooking the calving terminus of the tidewater glacier, Kronebreen, in Svalbard. Kronebreen is a focus of study within the IPY GLACIODYN project. Source: Monica Sund, University Centre, Svalbard.

of the lack of a widely accepted calving law. Although individual ice caps may have multiple tidewater glacier outlets, the mass loss by calving is often dominated by one or two of these outlets (Krenke, 1982; Dowdeswell et al., 2002, 2008; Burgess et al., 2005; Williamson et al., 2008; Mair et al., 2009), but calving fluxes from individual glaciers can show large temporal variability.

Recent increases in calving flux from the Greenland Ice Sheet have been associated with acceleration, retreat, and thinning of major outlet glaciers (Howat et al., 2005; Rignot and Kanagaratnam, 2006). Similar changes are observed in Alaska and on some large Arctic ice caps, and may be caused by changes in glacier dynamics related to increased surface melting, penetration of meltwater to glacier beds, and subsequent lubrication of the ice-bed interface allowing increased flow by basal sliding. Other possible causes of calving flux increases include increased melt of the underwater part of terminal ice cliffs due to increasing ocean temperature (Holland et al., 2008), thermal transitions (from cold-based to warm-based) in polythermal glaciers, and break-up and removal of floating ice tongues that formerly restrained the flow of the glacier. Such dynamic changes may be larger and more rapid than those induced by changes in surface mass balance alone.

7.1.4.4. Response to climate change

Glaciers respond to climate change over very different timescales depending on their size, shape, and thermal regime. Among glaciers that terminate on land, smaller glaciers tend to respond more quickly, changing their shape, flow, and terminus position over years or decades. The hypsometry (area-altitude distribution) of a glacier plays an important controlling role in determining its response to changes in climate. In a given region, low-lying glaciers may shrink and retreat quickly at the same time as glaciers at higher elevations grow or maintain their size. Changes in the temperature and salinity of the ocean water adjacent to calving ice fronts can trigger rapid changes in the terminus position, flow velocity, and calving flux of tidewater glaciers, so that large tidewater glaciers may alter their form more rapidly than small glaciers that terminate on

land (Holland et al., 2008; Rignot et al., 2010; Straneo et al., 2010). Although Arctic glaciers show a variety of responses to changing climate, it is something to which they are all sensitive. It is worth noting that the surface mass balance of glaciers in the Arctic may be affected indirectly by changes in other components of the Arctic cryosphere, such as the regional snow cover and extent of sea ice, that affect the surface energy balance, atmospheric circulation, and availability of open water as a source of water vapor (e.g., Rennermalm et al., 2009).

7.1.5. Significance and impacts of glacier changes

According to recent estimates, glaciers contributed about 0.8 to 1 mm annually to global sea-level rise during the period 2001 to 2004. The upper limit of the estimates includes the contribution from glaciers surrounding the Greenland and Antarctic ice sheets (Kaser et al., 2006; Solomon et al., 2007). Meier et al. (2007) gave a slightly higher estimate of 1.1 mm for 2006. This is about one third of the total current sea-level rise, or about 60% of that component of the rise attributable to the addition of water mass to the oceans, as opposed to the thermal expansion of ocean waters. The remaining 40% of that component comes from the combined contribution of the Greenland and Antarctic ice sheets. Meier et al. (2007) predicted that a large contribution to sea-level rise over the period to 2100 will still come from glaciers and ice caps. As more than half of the world's glacier and ice cap area is found in the Arctic, it is very important to reduce the uncertainty in estimates of the current and future mass balance of the Arctic glaciers and ice caps.

It is also important to evaluate the impacts of ongoing and future changes in glacier extent and volume on regional water resources, water quality, and the incidence of glacier-related natural hazards. Glacier runoff is exploited as a source of hydroelectric power in Scandinavia, Iceland, Greenland, western Canada, and Alaska. Increasingly negative surface mass balance of the glaciers, and reductions in glacier area may have a direct impact on the water balance of basins used for hydroelectric power generation. Increased freshwater flux from glaciers to nearby fjords and oceans may have an impact on the marine ecosystem via freshening of ocean water and increased transport of nutrients and contaminants from land to sea. Freshening of ocean water may have an impact on fjord circulation and on global ocean thermohaline circulation. Changes in the frequency and magnitude of iceberg calving events may impact infrastructure development, marine transport, fisheries, and oil and gas exploration and production on Arctic continental shelves, where human activity is expected to increase significantly over the coming decades.

Changes in the extent and thickness of Arctic glaciers can destabilize the surrounding terrain and generate geomorphological hazards (rock slides, debris flows, ice avalanches, glacial mudflows, outburst floods), especially when combined with changes in the extent and thickness of permafrost on surrounding slopes. They also create a threat of floods (*jökulhlaups*) from ice-dammed and subglacial lakes, especially in volcanic areas such as Iceland, Alaska, and Kamchatka.

Glacier related tourism is important to some local economies, and shrinking or even disappearing glaciers may have a direct economic impact.

7.1.6. Challenges

The ACIA report (ACIA, 2005) stated that the most difficult task in a regional-scale assessment of glacier behavior is to generalize results from a few glaciers and ice caps to all ice masses in the Arctic. This statement is still valid today. Neither the remote sensing tools nor the glacier and ice sheet models currently available are well suited to studies of regional ice covers that comprise a multitude of glaciers of varying sizes in regions with complex surface topography.

Direct measurements of the mass balance of Arctic glaciers are limited to a small number of glaciers across the Arctic (50 in the 2000 to 2004 pentad); 31 of these were in Scandinavia, which contains only 3.5% of the total mountain glacier and ice cap area in the Arctic. In the past 35 years, the number of *in situ* glacier monitoring sites in the Canadian Arctic and Arctic Russia (regions which contain over 50% of the area of mountain glaciers and ice caps in the Arctic) has declined from 16 in the 1970 to 1975 period, to just six in the period 2000 to 2005, with no measurements in Arctic Russia since 1990 and only one set since 1980 (Dyurgerov and Meier, 2005). There is a pressing need for an updated regional-scale assessment of glacier and ice cap mass balance, the last assessment having been made in 2005. The uncertainties associated with such regional-scale assessments are large owing to the small number of *in situ* measurements and their uneven spatial distribution relative to the distribution of glacier ice.

In situ measurements are critical for quantifying regional mass balance, enhancing process understanding, and validating remote sensing techniques and model predictions. Given the limited number and distribution of such measurements, it is essential to improve and sustain remote sensing capabilities for monitoring ongoing changes in glacier extent, surface elevation and thickness, surface mass balance, ice dynamics, and iceberg production. Although there has been some progress on these issues, there is also a need for repeated, regional-scale mapping of parameters that provide simple indices of glacier mass balance (such as equilibrium-line altitude, glacier facies zones, and summer melt duration; see Section 7.4.2) to be used to evaluate year-to-year variability in climate effects on glacier health.

7.2. Climate evolution in glacierized regions of the Arctic

- While some Arctic glaciers have existed throughout the period since the end of the last glaciation, most disappeared during a warm period between 10 000 and 6000 years ago. Many of today's glaciers, therefore, formed in a cooler period after 5000 years ago.
- Although there were several warmer intervals within this cool period, the 20th century appears to have been the warmest century in the past 2000 years, with the warmest conditions occurring between the 1930s and early 1960s and since the mid-1980s.
- Across much of the Arctic, low winter precipitation means that most of the year-to-year variability in glacier mass balance arises from changes in summer temperature. In more maritime regions such as southern Alaska, Iceland, western Scandinavia and Svalbard, variability in winter precipitation can be an important influence on mass balance variability.

7.2.1. Holocene climate

Ice formed during the last glaciation is found in some ice caps in the Canadian Arctic (Koerner and Fisher, 2002; Zdanowicz et al., 2002) and Severnaya Zemlya (Kotlyakov et al., 1991). The absence of such ice in ice caps in Svalbard and other parts of the Russian Arctic is evidence for substantial retreat (or even disappearance) of glaciers and ice caps across much of the Arctic outside Greenland in the early Holocene (Koerner and Fisher, 2002). Therefore, the genesis of much of the present-day Arctic glacier cover may lie in the climate of the middle and late Holocene.

Many climate proxy records suggest that the warmest period of the Holocene in the Arctic was between 10 000 and 6000 years BP, after which the climate cooled, possibly because of a decrease in incident solar radiation at high latitudes due to changes in the Earth's orbital parameters (Koerner and Fisher, 1990; Vinther et al., 2009). Air temperature reconstructions based on ice-core oxygen isotope records from the Agassiz Ice Cap (Canadian Arctic) and Renland (eastern Greenland) suggest peak temperatures slightly in excess of 2 °C warmer than at present during this period (Vinther et al., 2009), which is often referred to as the Holocene Thermal Maximum. However, the exact timing of peak air temperatures during this period seems to have varied across the Arctic. In North America, it was later in the eastern Arctic than in the western Arctic, probably because the residual Laurentide Ice Sheet had a cooling effect on the climate in the east. During the Thermal Maximum, around 7500 years BP, summer temperatures were about 1.6 ± 0.8 °C warmer than in the 20th century (Kaufman et al., 2004). Records of summer melt and oxygen isotope ratios from ice cores in the Canadian and Russian Arctic indicate that cooling following the Thermal Maximum was underway by no later than 6000 years BP (Koerner and Fisher, 2002) (Figure 7.6).

A 2000-year, decadal-resolved, multi-proxy record of Arctic summer surface temperatures (which includes the temperature reconstructions from Agassiz Ice Cap and Renland) shows a cooling trend from 2000 to 100 years BP (Kaufman et al., 2009) (see Fisher, 2002, for an analysis of the reliability of multi-proxy temperature reconstructions). This trend (-0.22 °C/millennium) was probably driven by the orbitally-forced trend in summer insolation at high latitudes over the same period, but may have been amplified in some regions by feedbacks involving the progressive expansion of Arctic sea ice (England et al., 2008; Vare et al., 2009) and seasonal snow cover. The record also shows centennial-scale anomalies about the long-term trend, with the period 450 to 700 AD being cooler than the long-term trend and the period 900 to 1050 being warmer. The coldest period in the record occurred between 1600 and 1850, during the Little Ice Age (Kaufman et al., 2009). There is evidence that this cold period was associated with a persistently negative phase of the North Atlantic Oscillation (Trouet et al., 2009). Although the decline in orbitally-driven summer insolation continued throughout the 20th century, reconstructed Arctic summer temperatures rose sharply, reaching the highest values in the 2000-year record in the period after 1950. On the basis of this reconstruction and recent instrumental data, Kaufman et al. (2009) concluded that the decade 1999 to 2008 had the warmest summers in the 2000-year record (Kaufman et al., 2009).

Thousand years
Before Present (BP)




Figure 7.6. Holocene sections of ice cores from Greenland (GRIP, GISP2, Renland), Arctic Canada (Agassiz, Devon, Penny), and Severnaya Zemlya (Akademii Nauk) showing records of $\delta^{18}\text{O}$ (negative values) and summer melt (positive values), which are proxies for air temperature over the ice caps / ice sheet. Shaded sections suggest conditions warmer than those of today. Source: Koerner and Fisher (2002).

7.2.2. Arctic ice cores: Holocene climate records from glacierized regions

Ice cores from the larger Arctic ice caps yield records of past environmental conditions in glacierized regions that span the full Holocene. The longest records are from the Canadian Arctic, Mount Logan (Yukon), and Severnaya Zemlya (Koerner and Fisher, 1990, 2002; Kotlyakov et al., 1991; Fisher et al., 1995, 2008; Koerner, 1997; Zdanowicz et al., 2002; Kinnard et al., 2008). The melt layer record from the Agassiz Ice Cap and the oxygen isotope record from Severnaya Zemlya show a temperature maximum in the early Holocene, before 8000 BP, while oxygen isotope records from Arctic Canada typically show a later thermal maximum – as late as 5000 BP on Devon Island (Paterson et al., 1977). Melt layer records show a persistent cooling trend from about 8000 BP until the mid-19th century, after which there is renewed warming. Oxygen isotope records

also show cooling, but the timing of this is delayed until after about 5000 BP in some records (Koerner and Fisher, 2002). The melt records suggest maximum summer cooling from the Holocene Thermal Maximum of 2.0 to 2.5 °C, while the oxygen isotope records suggest cooling of 1.3 to 3.5 °C (Koerner and Fisher, 2002). Part of the early Holocene warming recorded in the ice core records must be due to the effects of surface lowering due to ice cap thinning, although this would have been partly offset by cooling induced by isostatic uplift of the land surface as the ice cover thinned and shrank (Koerner and Fisher, 2002; Vinther et al., 2009).

Oxygen isotope records from ice cores from smaller ice caps in Arctic Canada, northern Greenland, Svalbard, and the Russian Arctic islands show temporal variability but not the long-term cooling trend apparent in the records from the larger ice caps. This suggests that the small ice caps began to re-grow in the latter part of the Holocene after melting away during the

Thermal Maximum (Hammer et al., 2001; Landvik et al., 2001; Koerner and Fisher, 2002). The record from the upper 125 m of the ice core from Hans Tausen Iskappe in northern Greenland suggests a warm period between 900 and 1100 AD, and that the period 1700 to 1900 was the coldest in the past 2000 years. There was strong warming from the 1920s to the early 1960s (making the 20th century the warmest part of the record), but no clear trend in temperatures thereafter (Hammer et al., 2001). New oxygen isotope records from Austfonna and Lomonosovfonna in Svalbard span the past 600 to 800 years and show gradual cooling to a minimum in the 19th century, followed by rapid warming around 1900 that made the 20th century the warmest century in the past 600 years (Isaksson et al., 2003, 2005). A 275-year oxygen isotope record from Akademii Nauk Ice Cap on Severnaya Zemlya shows the coldest conditions around 1790, and then continuous warming until 1935. It also shows that the 20th century was the warmest period in this region (Fritzsche et al., 2005). A reconstruction of snow accumulation rates on Lomonosovfonna shows an increase of 25% in the late 1940s (Pohjola et al., 2002). A similar increase is recorded on Severnaya Zemlya after 1935 (Opel et al., 2009).

The oxygen isotope record from Mount Logan is unusual in that it appears to be a proxy for changes in the moisture source region for precipitation, rather than air temperature (Fisher et al., 2008). Major changes in moisture source region seem to be associated with switches between strong, frequent El Niño conditions (associated with meridional patterns of atmospheric flow and water vapor transport towards the Yukon) and strong, frequent La Niña conditions (associated with more zonal flow and moisture transport towards the Pacific Northwest). La Niña periods are associated with reduced precipitation (and snow accumulation) in the southern Yukon, while the reverse is true for El Niño periods. Periods of enhanced meridional flow seem to have occurred around 4200 BP and between 8000 and 7000 BP, while the modern El Niño Southern Oscillation regime seems to have been initiated after 4200 BP (Fisher et al., 2008).

Chemically-based melt indices from the Lomonosovfonna ice core show very high melt in the 12th century (Grinsted et al., 2006), as do melt layer records from the Canadian Arctic. This suggests a warm episode in medieval times in these parts of the Arctic. This warm episode was followed by a long period of reduced melt lasting to the mid- to late 19th century, after which melt increased sharply. For example, the melt layer record from Akademii Nauk Ice Cap shows maxima in the 1840s, 1880s, and from 1900 to 1970, after which melt layer content dropped sharply (Opel et al., 2009). However, the increase in melt was delayed until about 1925 in the new record from Prince of Wales Icefield, Ellesmere Island (Kinnard et al., 2008). The first principal component of seven Arctic melt layer records spanning the period 1551 to 1956 explains 34% of the variance in these records. It shows a strong increase in melt layers starting around 1830 and peaking in the mid-20th century (Kinnard et al., 2008) and has a similar form to a multi-proxy summer temperature reconstruction for the Arctic (Overpeck et al., 1997). Melt layer records from multiple sites on the Devon Island Ice Cap show an increase in ice fraction of over 50% after 1989 relative to the period 1963 to 1988 (Colgan and Sharp, 2008), consistent with a shift to increasingly negative surface mass balance after 1987 (Gardner and Sharp, 2007).

7.2.3. Climate records for glacierized regions of the Arctic derived from instrumental observations and climate re-analysis

Observational records of past surface air temperature from around 70 stations in the Arctic (north of 62° N) since 1875 show large multi-decadal fluctuations. Maxima in mean annual air temperatures occurred in the 1930s and 1940s and in the past two decades, with minima before 1920 and from about 1955 to 1985 (Polyakov et al., 2003). The same trends are apparent for the region 68° to 90° N in the 250-km smoothed air temperature dataset from the Goddard Institute for Space Studies. Mean summer 2-m air temperature anomalies in this dataset show a similar history to mean annual anomalies, but the range of summer anomalies is smaller than for the mean annual air temperature. In addition, there is a period of high mean summer air temperature in the 1950s that is not apparent in the record of mean annual air temperature (Figure 7.7).

Correlations between surface air temperature measured at coastal weather stations and the monthly North Atlantic Oscillation index are positive for a region that includes northern Scandinavia, Svalbard, and the Eurasian Arctic islands, and negative for a region that covers most of Greenland and the Canadian Arctic (Polyakov et al., 2003). Since the late 1990s, surface air temperature anomalies over the Arctic Ocean have become increasingly positive in autumn, especially over those regions where there has been a strong decrease in September sea-ice extent (Serreze et al., 2009). This trend may have resulted in longer melt seasons over glacierized regions of the Canadian and Eurasian Arctic.

In most regions of the Arctic, low winter precipitation means that interannual variability in annual glacier mass balance arises from variability in the summer balance, which is strongly controlled by summer air temperature. Gardner et al. (2009) found positive correlations between mean lower-troposphere summer air temperature from climate re-analyses and surface air temperature measured at the summit elevations




Figure 7.7. Five-year running means for mean annual and mean summer (June – August) 2-m air temperature anomalies (relative to the mean for 1951 to 1980) for the region 68° to 90° N from the Goddard Institute for Space Studies 250-km smoothed dataset.

of Arctic ice caps. Sharp and Wang (2009) reported similar correlations between lower tropospheric summer mean air temperature from climate re-analyses and melt season duration on Eurasian Arctic ice caps. For the period 1948 to 2008, NCEP/NCAR (U.S. National Weather Service National Centers for Environmental Prediction and the National Center for Atmospheric Research) Reanalysis (Kalnay et al., 1996) decadal mean 700 hPa air temperatures over glacierized regions of the Arctic in June to August were warmest in either the 1950s (Russian Arctic, northern Ellesmere and Axel Heiberg Islands) or the 2000s (Alaska, Iceland, Svalbard, and the rest of the Canadian Arctic). They were coldest in the 1990s in the Eurasian Arctic and the 1960s and 1970s over Iceland, Alaska, and the Canadian Arctic.

In the more maritime regions of the Arctic (such as Alaska, Iceland, Svalbard, and western Scandinavia), high variability in winter accumulation can also induce interannual variability in the annual mass balance. According to the NCEP/NCAR Reanalysis, decadal mean winter (September to May) precipitation anomalies were most negative in the 1950s over Alaska, the 1960s over Iceland, and the 1980s over Svalbard. They were most positive in the 2000s over Alaska and the 1950s over Iceland and Svalbard.

High summer precipitation keeps glacier surface albedo relatively high and reduces summer melt, while low summer precipitation has the opposite effect. In the Eurasian Arctic islands, decadal mean summer precipitation anomalies were typically positive from the 1950s through the 1970s and negative from the 1980s to 2000s. The opposite trend was observed in Iceland.

7.3. Changes in glacier extent, volume and total mass

- Following the early Holocene warm period, the cooler climate between 6000 years BP and the end of the Little Ice Age resulted in glacier growth and advances across the Arctic.
- In some cases, maximum glacier extents were reached as early as the mid-17th century, but in most regions glaciers were at or close to their maximum extents in the late 19th and/or early 20th centuries.
- Across the Arctic, glaciers began retreating and losing mass in the early 20th century. This trend continued through the mid-20th century, although glaciers in some regions experienced brief episodes of slower retreat, reduced mass loss, or even mass gain. Overall, there were substantial reductions in glacier area and mass across the entire Arctic over the 20th century.
- Mass loss has accelerated across most regions of the Arctic since the mid-1990s.
- In some regions, the timing and duration of episodes of relatively positive or negative mass balance were tied to major changes in atmospheric circulation related to phenomena such as the North Atlantic Oscillation (Iceland, western Scandinavia), the Pacific Decadal Oscillation (western Canada, southern Alaska), and the location and intensity of the summer circumpolar vortex (Arctic Canada).

7.3.1. Arctic glacier changes during the Holocene

Reconstructions of dated lateral and terminal moraine positions (and associated stratigraphy) are the primary source of information on glacier changes during the Holocene. In western North America, the Cordilleran ice sheet reached its maximum extent and thickness by 16 000 BP. Between 15 000 and 11 000 BP, climate conditions allowed some lobes of the ice sheet to advance (Menounos et al., 2009), and alpine glaciers also advanced in the southern and north-central ranges of the Cordillera, but by 11 000 BP glacier extent was comparable to that at present (Clague et al., 1982). Glacier extent reached a minimum between about 11 500 to 9000 BP, with temperatures 2 to 3 °C above present and generally drier conditions (Kaufman et al., 2004). Subsequently, periods of glacier advance occurred from 8600 to 8200 BP, 7400 to 6500 BP, 4400 to 4000 BP, 3500 to 2800 BP, and 1700 to 1300 BP (Menounos et al., 2009), and maximum Holocene extents were reached during the early 18th or mid-19th centuries AD.

A number of ice caps in Arctic Canada (Devon, Agassiz, Barnes, Penny) contain ice dating from the last glaciation (Paterson et al., 1977; Hooke and Clausen, 1982; Fisher et al., 1983, 1995, 1998; Zdanowicz et al., 2002) and must therefore have survived throughout the Holocene. During deglaciation, the margins of the last Innuitian ice sheet covering the Queen Elizabeth Islands reached the current margins of ice caps on Devon, Ellesmere, and Axel Heiberg Islands between 10 000 and 7500 ¹⁴C years BP (England et al., 2006). Many of the smaller ice caps and glaciers in this region disappeared during this period (Koerner and Fisher, 2002). Glaciers began to grow again after 1000 ¹⁴C years BP (Blake, 1981), reaching maximum extents in the late 19th or early 20th centuries. On Baffin Island, the Laurentide Ice Sheet retreated progressively throughout the Holocene to its current margin, that of the Barnes Ice Cap. Deglaciation was especially rapid around 7000 BP, when the ice cover in Foxe Basin collapsed (Briner et al., 2009). The early Holocene ice extent in this region is poorly constrained but glaciers began to advance again as early as 6000 BP, reaching extents similar to those of the Little Ice Age (the Holocene maximum for alpine glaciers on Baffin Island) by 3500 to 2500 BP (Briner et al., 2009). Small ice caps have been present in the northern interior of Baffin Island for 1600 to 2800 years, but they were absent for much of the middle Holocene. These ice caps started to expand after 1280 AD, and especially after 1450 (Anderson et al., 2008).

Most glaciers in Greenland were smaller during the early Holocene than at present and some areas that are currently occupied by mountain glaciers and ice caps may have become completely ice free in that period (Hammer et al., 2001). Neoglacial moraines have been reported (from western and southeastern Greenland), but in most regions historical advances were the most extensive after the early Holocene. In all areas apart from northern Greenland (where many ice margins are stationary), local glaciers are currently receding from their historical maximum extents (Kelly and Lowell, 2009).

Iceland was largely ice free during the early Holocene (8000 to 6000 BP), after which Neoglacial cooling began. Glacier extent increased between 4500 and 4000 BP, and again between 3000 and 2500 BP. The most extensive Holocene ice extent was

reached during the period 1250 to 1900 AD – probably in the latter part of that period between 1700 and 1850 (Geirsdóttir et al., 2009). However, some steep alpine glaciers reached their maximum extents earlier, probably around 2500 BP, when the present ice caps are also likely to have formed. A general glacier recession that began in the 1890s accelerated after 1930. Retreat slowed by the 1960s as a result of cooler summers beginning in the 1940s, and many steep glaciers were advancing in the 1970s. Renewed climate warming since 1985 has led to a new episode of retreat, and all major non-surging outlet glaciers have been retreating since 1995, at rates of up to 100 m/y. The southern outlets of Vatnajökull eroded down into soft sediments during the pre-1890 advance and have been especially susceptible to rapid retreat since then. The volume of Vatnajökull has decreased by about 300 km³ (10%) since 1890 (Björnsson and Pálsson, 2008).

In northern Scandinavia, retreat of the Scandinavian Ice Sheet during the Late Glacial and early Holocene was punctuated by numerous readvances in the period 11 200 to 8000 BP. Most glaciers disappeared completely at some point in the early to mid-Holocene, and ice cover is likely to have reached a minimum between 6600 and 6300 BP (Nesje, 2009). Subsequently, there was a period of renewed glacier growth during which there were numerous century- to millennium-long ‘Neoglacial’ events. Glaciers in northern Sweden were probably at their Little Ice Age maximum extent in the 17th and early 18th centuries (Karlén, 1988), while those in Norway reached their maxima in the mid-18th century (Winkler, 2003; Nesje, 2009), or even later in some parts of northern Norway (Bakke et al., 2005). Most Swedish glaciers reached an extent close to their Holocene maximum at the beginning of the 20th century (Holmlund, 1993). Since then, Scandinavian glaciers have generally retreated, particularly since the 1930s (Nesje, 2009). Increased snow accumulation caused some glaciers to advance in the 1990s (Dowdeswell et al., 1997).

In northeast Svalbard, many glaciers started to retreat after the Last Glacial Maximum by about 9500 BP (Blake, 1989). During this period of deglaciation, variations of the glaciers and ice caps in Svalbard were similar to those of glaciers in Scandinavia. However, the Younger Dryas advance was apparently small due to a very dry climate, and the Little Ice Age maximum extent was larger than the Younger Dryas advance (Mangerud and Landvik, 2007). In the early Holocene, glaciers were much smaller than at present and perhaps even completely absent. A period of glacier growth from 3000 to 2500 BP was followed by a warmer period with smaller glaciers (Svendsen and Mangerud, 1997). Dating of relict vegetation found under the cold-based Longyearbreen indicates that late Holocene glacier growth started about 1100 BP. This period of glacier growth culminated in the Little Ice Age maximum with the greatest Holocene glacier extent. Many ice-cored moraines were formed at this time, which may have been as recently as around 1900 (Humlum et al., 2005). Surging of Svalbard glaciers is common and the maximum extent of many glaciers may be a result of surge dynamics (Hagen et al., 1993). Since the Little Ice Age maximum, the glaciers have generally retreated in response to early 20th century warming (Lefauconnier and Hagen, 1991; Hagen et al., 2003a,b).

In the Russian Arctic, outlet glaciers in northwestern Novaya Zemlya retreated from the outer coast by the earliest

Holocene. Prior to about 9500 BP the terminus of the tidewater Shokalsky Glacier was over 1 km behind its present margin, allowing incursion of the sea (Zeeberg, 2001). A sediment core from Russkaya Gavan spans a period of 800 years and allows reconstruction of the recent history of Shokalsky Glacier. A noticeable advance around 1400 AD was followed by a major retreat by about 1600. Increased melting in the 1900s is suggested by an increase in sedimentation rates (Polyak et al., 2004). On Franz Josef Land, glaciers were less extensive than at present throughout the period 10 300 to 4400 ¹⁴C years BP, but re-expanded to their present margins by 2000 ¹⁴C years BP (Lubinski et al., 1999). A major advance occurred during the past 1000 years, with maxima around 1200, 1400, and in the mid-17th century. Glaciers were more extensive than now at the start of the 20th century; since then there has been widespread glacier retreat.

7.3.2. Arctic glacier changes in the 20th and 21st centuries

7.3.2.1. Methods for determining glacier mass balance

Mass balance is the change in mass of a glacier, quantified as the difference between mass gains (accumulation) and mass losses (ablation), over a specified time period. A summary of the processes that determine the mass balance of a glacier is provided in Appendix 7.1 (see also Box 7.1). Over the 20th and beginning of the 21st centuries, many new methods have been developed for measuring glacier mass balance. Each method provides information at unique spatial and temporal resolutions, and samples specific parameters to characterize glacier evolution over time. Important challenges for global mass balance inventories include the integration of these different datasets and quantification of the errors in each approach.

Long-term records of surface mass balance that form the basis of existing global datasets have been acquired from direct sampling of individual glaciers using glaciological methods (Østrem and Brugman, 1991; Cogley, 2005). In this approach, measurements of snow accumulation are acquired from snow probing or digging snow pits to measure snow depth and density (Figure 7.8). Glacier ablation is measured by determining the

Box 7.1. Units for mass balance measurements

Mass balance measurements have units of mass per unit time (see Appendix 7.1). It is also common to report the rate of change of mass per unit area, for example, kg/m² per year, which is numerically equivalent to the millimetres of water equivalent (w.e.) per year. In this report, mass balances are usually presented in units of gigatonnes per year (Gt/y) or metres of water equivalent per year (m w.e./y). Exceptions are those studies reporting cumulative mass balances, in which case they are not converted to a rate because it is not always clear what exact time period was used for the measurements, and those studies reporting volume changes, in which case they are not converted to a mass equivalent unless the density of the changing snow and ice volume is clearly stated.




Figure 7.8. Measuring snow accumulation in a snow pit.

vertical change in distance from the glacier surface to a marker, fixed within the reference frame of the moving ice mass, and by assuming an appropriate density for the snow, firn, or glacier ice that melted. Annual mass balance is defined as the difference between the annual accumulation and the annual ablation. Point measurements of this quantity are extrapolated to the entire glacier. Two processes, internal accumulation and the formation of superimposed ice, involve the refreezing of some fraction of the annual melt and alter surface mass balance by reducing the amount of meltwater runoff. However, not all surface mass balance programs measure these processes owing to the difficulty of doing so, resulting in overestimates of the rate of mass loss. Regardless, glaciological mass balance measurements generally provide the most accurate sampling of mass balance at a point, but are limited in spatial extent.

Developments in ground surveying and remote sensing technologies have resulted in many geodetic mass balance methods. These calculate a volume balance determined from repeat measurements of surface elevation and area, from which the mass balance is obtained by estimating the density of the changing ice volume. Elevations are determined using overlapping aircraft or satellite imagery to determine the 3-dimensional position of the surface through stereoscopy, ground mapping of the glacier surface elevation using theodolite or Global Positioning System (GPS) surveying, or airborne / satellite altimetry using radar or laser ranging instruments. Geodetic methods provide a broad regional sampling of glacier changes, but can have large errors due to uncertainties in the density of the volume lost, especially over short periods, non-representative sampling of fast- and slow-flowing sectors of ice caps, or biases in the distribution of surface-elevation change measurements relative to the distribution of rates of elevation change (e.g., in aircraft altimetry where measurements are typically made along a glacier centerline where rates of thickness change may be

larger than the glacier-wide mean; Berthier et al., 2010).

Recent advances in spaceborne geodesy provide gravimetric data to determine glacier mass variations via measurement of changes in Earth's gravity field. At present, this is achieved using the Gravity Recovery and Climate Experiment (GRACE) satellites that measure variations in Earth's gravitational potential. Corrections must be made to the satellite measurements to account for all non-glacier sources of mass variation, such as glacial isostatic adjustment and changes in terrestrial water, atmospheric, and ocean mass. Gravimetric methods circumvent the need for density corrections of measured volume changes, but are limited in spatial resolution (about 50 000 km²) and can only effectively sample broad regions undergoing significant change.

Measurements of glacier thickness are essential for estimating glacier volume and for computing mass losses by iceberg calving. They are also needed as input to models of the dynamic response of glaciers to climate forcing. They are usually obtained using the technique of radio echo sounding from either ground-based or airborne platforms (Dowdeswell and Evans, 2004). Airborne campaigns are typically required for measurements of the thickness of larger glaciers and ice caps, as well as for regional-scale studies (Dowdeswell et al., 2002, 2004).

Area/volume scaling (Bahr et al., 1997) is used to estimate glacier volume when glacier areas are known but direct measurements of volume are lacking. This method is based on the observed power-law relationship between a glacier's volume and area. Glacier surface areas measured at different times are used to estimate corresponding glacier volumes, from which changes in glacier volume can be determined. This method can have large errors when data are not available to constrain the scaling relationship and determine suitable scaling coefficients (Radić et al., 2008). Therefore, it is most appropriately applied to entire populations of glaciers rather than to individual ice masses.

Changes in proxy indicators are also used to approximate mass balance trends, and these approaches are summarized in Section 7.4. The distribution and length of glaciological and geodetic mass balance records in the Arctic region are highly variable, but the longest continuous records (from Scandinavia) extend back to the 1940s (Figure 7.9). Records from individual regions are discussed in the following sections.

7.3.2.2. Northwestern North America

Northwestern North America includes all glaciers of Alaska (United States) and Yukon Territory (Canada) and those glaciers in British Columbia and Alberta (Canada) that drain into the Alaska Panhandle or into the Arctic Ocean via the northern tributaries of the Mackenzie River.

During the 20th century most land-terminating glaciers in northwestern North America retreated extensively from their Little Ice Age maximum extent (Kaufman et al., 2004). Most of the recession occurred between 1900 and 1950 and from 1980 to present, with a period of slower recession, and in some cases advance, between 1950 and 1980. Since 1980, nearly all glaciers have been in a state of retreat. For example, in British Columbia, the extent of glaciers in the northern Coast and St. Elias mountains changed by $-7.7 \pm 2.9\%$ and $-7.9 \pm 2.6\%$,




Figure 7.9. Glacierized regions in the Arctic and the locations where mass balance measurements have been made. The length of time of the geodetic and glaciological mass balance records are also indicated. Source: AMAP.

respectively, over the period 1985 to 2005 (Bolch et al., 2010). Between 1958/1960 and 2006/2008, the total glacier area in the Yukon Territory decreased by $2541 \pm 189 \text{ km}^2$ (or 22% of the initial area of $11\,622 \text{ km}^2$) (Barrand and Sharp, 2010).

Regular glaciological mass balance measurements in Alaska began during the 1960s and trends generally agree with observed variations in glacier extent. Wolverine Glacier lost mass from 1966 to 1976 and gained mass from 1976 to 1988, while Gulkana Glacier lost mass at a constant rate from 1966 to 1973 and at an increasing rate from 1974 to 1985 (Josberger et al., 2007). After about 1988, both glaciers entered a period of accelerating mass loss (Figure 7.10).

Aircraft laser altimetry measurements showed that about 85% of 67 glaciers in northwestern North America had a mass balance of $-52 \pm 15 \text{ Gt/y}$ between 1950/1970 and the early 1990s (Arendt et al., 2002; Echelmeyer et al., 1996). A repeat sampling of 28 of these glaciers between the early 1990s and late 1990s / early 2000s indicated a doubling of the rate of mass loss ($-96 \pm 35 \text{ Gt/y}$). A recent analysis compared digital elevation models (DEMs) from the 1950s/1970s against those from the 2000s, and argued that estimates based on centerline aircraft altimetry overestimated the mass loss of Alaskan glaciers by 34% (Berthier et al., 2010). These new estimates suggest a mass loss rate of $-41.9 \pm 8.6 \text{ Gt/y}$ for the period 1962 to 2006.

Other geodetic measurements have been acquired through differencing of 1950s U.S. Geological Survey (USGS) and NASA's Shuttle Radar Topography Mission (SRTM) DEMs. Glacier mass balances in regions south of 60.5° N in southeastern Alaska and the Kenai Mountains were -15 ± 4.0

Gt/y (Larsen et al., 2007) and $-1.2 \pm 0.25 \text{ Gt/y}$ (VanLooy et al., 2006), respectively, during a 30- to 50-year period ending in 2000. Another study using the SRTM data found the glaciers of the northern Coast and St. Elias mountains had a mass balance of $-11.1 \pm 2.0 \text{ Gt/y}$ during the period 1985 to 2000 (Schiefer et al., 2007). Recent altimetry measurements for 2004 to 2008 suggest an acceleration of mass loss relative to the 1990s, especially for glaciers at low elevations (Lingle et al., 2008).

There are three estimates for the mass balance of glaciers surrounding the Gulf of Alaska based on data from GRACE: $-110 \pm 30 \text{ Gt/y}$ for the period 2002 to 2004 (Tamisiea et al., 2005); $-101 \pm 22 \text{ Gt/y}$ for the period 2002 to 2005 (Chen et al., 2006); and $-84 \pm 5 \text{ Gt/y}$ for the period 2003 to 2008 (Luthcke et al., 2008).

7.3.2.3. Canadian Arctic

The Canadian Arctic region includes the Queen Elizabeth Islands (including Ellesmere, Devon, and Axel Heiberg Islands), and Bylot and Baffin Islands. Glaciers cover an area of about $150\,000 \text{ km}^2$ in this region. Current and past glacier extents are known from aerial photography taken during the period 1956 to 1961 and from satellite imagery collected since the mid-1970s (and especially since 1999) (Sharp et al., 2003, in press; Dowdeswell et al., 2007; Wolken et al., 2008). Comparison of ice extents from around 1960 with trimline and end moraine positions visible on satellite imagery shows that there has been extensive ice retreat across the region from glacier maximum positions reached by the end of the Little Ice Age. The ice-

covered area on the Queen Elizabeth Islands decreased by 37% from a Little Ice Age maximum of 170 124 km² to about 107 735 km² in 1960, and all permanent ice was removed from most of the western islands (Dyke, 1978; Wolken et al., 2008). Further glacier retreat has occurred since 1960, with ice area reductions by 2000/2001 of 5.1% (253 km²) on Bylot Island (Dowdeswell et al., 2007) and 2.7% (2844 km²) on the Queen Elizabeth Islands (Sharp et al., 2003). The 14 400 km² Devon Island Ice Cap decreased in area by 338 ± 40 km² (2.4%) (Burgess and Sharp, 2004). The area of small plateau ice caps in interior northern Baffin Island decreased by 55% (from 150 km²) between 1958 and 2005 (Anderson et al., 2008), while the area of 264 glaciers on the Cumberland Peninsula in southeast Baffin Island decreased by about 294 km² (12.5%) between around 1920 and 2000 (Paul and Svoboda, 2009). In the latter study, proportional area reductions were greatest for the smallest glaciers, and the rate of area loss roughly doubled after 1975.

Glaciological mass balance measurements have been made in the Queen Elizabeth Islands since the late 1950s (Cogley et al., 1996; Koerner, 2005) (Figure 7.10), but there are no long-term records from Bylot or Baffin Islands, and no regular measurements since the mid-1980s (Hooke et al., 1987). In this region, variability in the annual mass balance arises almost entirely from variability in the summer balance (Koerner, 2005). The cumulative surface mass balance of all measured glaciers in the region has been negative over the measurement period (e.g., Devon Island Ice Cap -4.4 m w.e. from 1961 to 2007; White Glacier, Axel Heiberg Island -6.8 m w.e. from 1960 to 2007). Compared with the 1963 to 1987 period, the rate of mass loss accelerated significantly after 1987 (Gardner and Sharp, 2007). There have been a number of very negative mass balance years since 1997 (notably 1998, 2001, 2005, 2007, 2008, 2009) that suggest a further acceleration of mass loss since 1997. The

cumulative mass loss from the Devon Island Ice Cap from 1997 to 2007 exceeds that for the period 1963 to 1997. Consistent with this trend, geodetic measurements on the Barnes Ice Cap suggest a progressive increase in rates of thinning from 0.12 m/y (1970 to 1984), to 0.76 ± 0.35 m/y (1984 to 2006), and 1.0 ± 0.14 m/y (2004 to 2006) (Sneed et al., 2008).

Iceberg calving also contributes to mass loss from many of the larger ice caps (Burgess et al., 2005). Separate estimates of surface mass balance and iceberg calving fluxes are available for two large ice caps in Arctic Canada: the Devon Island Ice Cap and Prince of Wales Icefield. For the Devon Island Ice Cap, the estimates equate to an overall mean annual balance of either -2.3 Gt/y (1963 to 2000) or -5.2 ± 1.7 Gt/y (1980 to 2006), depending on whether the net surface balance estimates of Mair et al. (2005) (-1.8 ± 0.8 Gt/y) or Gardner and Sharp (2009) (-4.7 ± 1.7 Gt/y) are added to the Burgess et al. (2005) estimate of mass loss due to iceberg calving (-0.5 Gt/y). The surface mass balance of the Prince of Wales Icefield (1963 to 2003) appears to be within an error of zero, so the overall negative balance (-2.0 ± 0.5 Gt/y) is similar to the annual calving flux (1.9 ± 0.2 Gt/y) (Mair et al., 2009).

Repeat airborne laser altimetry flown over some of the larger ice caps in the region in 1995 and 2000 showed that most ice caps were thickening or maintaining a constant thickness at elevations above 1600 m, and thinning at lower elevations (Abdalati et al., 2004). Rates of thinning were greater on Baffin Island ice caps (>1 m/y) than in the Queen Elizabeth Islands (<0.5 m/y). Based on these data, Abdalati et al. (2004) suggested that the total mass balance of Arctic Canada in the period 1995 to 2000 was -22.9 Gt/y.

Thus, measurements of glacier extent, thickness, and surface mass balance are all consistent in showing progressive and possibly accelerating shrinkage of the Canadian Arctic land





Figure 7.10. Cumulative area-averaged mass balance for six Arctic glaciers: White Glacier (Axel Heiberg Island), Gulkana Glacier (Alaska), Storglaciären (Sweden), Midre Lovénbreen (Svalbard), Satujökull (Hofsjökull, Iceland), and Kozelsky (Kamchatka) over the period of record. All records show a negative cumulative balance (net thinning) over the period of record and more rapid thinning after about 1990 (although the precise timing of this varies between regions). Source: AMAP.



ice cover. Nonetheless, a precise and regionally comprehensive estimate of the magnitude of these changes and their implications for global sea level is not yet available.

7.3.2.4. Greenland (excluding Greenland Ice Sheet)

Glaciers occupy about one quarter of the peripheral area around the Greenland Ice Sheet (Thomsen and Weidick, 1992) (Figure 7.11). The glaciers of Disko Island (Qeqertarsuaq) and the Nuussuaq and Svartenhuk peninsulas, West Greenland, that covered an area of 3832 km² in 2001, lost between 16% and 21% of their area from the end of the Little Ice Age to 2001 (Citterio et al., 2009). There were no noticeable changes in the position of most calving glacier fronts between the late 19th century and the mid-1980s (Weidick, 1995). Between 1978 and 1991, major tidewater glacier termini along the northern coast of Kangerlussuaq and the southern part of Blosseville Kyst showed little change or a slight loss (0.1 to 0.5 km²) in the glacier tongue area (Dwyer, 1995).

Extreme fluctuations of the terminus of the surge-type tidewater glacier Sortebrae involved a retreat of about 1.5 km between 1933 and 1943, a surge advance of about 10 km by 1950, a retreat of 8 km between 1950 and 1981, followed by stagnation between 1981 and 1992, and a second surge advance of over 5 km between 1992 and 1994 (Jiskoot et al., 2001). Another example of surge-related terminus fluctuations is shown by a small land-based Scoresby Sund glacier, which retreated 0.5 km between 1987 and 2000, and advanced by 2.8 km between 2000 and 2007 (Jiskoot and Juhlin, 2009). Neighboring glaciers did not change their terminus positions significantly during the same period.

7.3.2.5. Iceland

Glacier terminus variations in Iceland have been monitored regularly since 1930. Most non-surge-type glaciers retreated rapidly from 1930 to 1960, but more slowly in the 1960s. Glaciers began to advance in the 1970s and rates of advance peaked in the mid-1980s. In the 1990s, glaciers began to retreat again and all monitored glaciers were retreating by 2000. Terminus fluctuations follow changes in mean summer temperature with a delay of only a few years (Sigurðsson et al., 2007).

Mass balance measurements were initiated on Hofsjökull in 1987/1988 (Figure 7.10; Satujökull), Vatnajökull in 1991, and Langjökull in 1996. Vatnajökull's balance was positive from 1991 to 1994 and near zero in 1994 to 1995, but it has been negative ever since, with a cumulative specific balance of about -9.2 m w.e. (84 Gt, or 2.7% of the ice cap mass) from 1994 to 2006 (Björnsson and Pálsson, 2008). In the 1990s, mass loss from Vatnajökull due to basal melting resulting from geothermal activity and volcanic eruptions averaged 0.55 Gt/y, about 4% of the total surface ablation in a year of zero surface balance. However, the Gjalp volcanic eruption in 1996 melted about 4.0 Gt of ice. The net balance of Langjökull has been negative since measurements began and the cumulative specific net balance from 1996 to 2006 was about -12.8 m w.e. (13.1 Gt, 7% of the ice cap mass) (Björnsson and Pálsson, 2008). The current period of negative mass balance reflects a combination of high summer temperatures and low winter snowfall.



Figure 7.11. Mountain glaciers and ice caps occupy much of the peripheral areas of Greenland that lie beyond the margins of the Greenland Ice Sheet. Source: Anthony Arendt, University of Alaska.

7.3.2.6. Scandinavia

After their Little Ice Age maximum, Scandinavian glaciers retreated slightly until the 1930s/1940s, when there was a period of more rapid retreat that lasted into the 1950s for maritime outlet glaciers and the 1970s for more slowly responding outlets in the interior. Increased winter precipitation between 1988/1989 and 1994/1995 triggered a readvance of some glaciers in western Norway and Sweden, but higher summer air temperatures after 2001 induced an episode of rapid glacier retreat (Andreassen et al., 2005; Nesje, 2005, 2009). The longest mass balance records from Scandinavia date to the late 1940s (e.g., Holmlund et al., 2005), but the number of measurements increased in the early 1960s. Since that time, glaciers in inland Scandinavia (for which net balance variability is due largely to variability in the summer balance) have had a cumulative negative mass balance (Figure 7.10), while maritime glaciers in western Norway and some others such as Storglaciären in Sweden (for which net balance variability is due largely to variability in the winter balance) have had a cumulative positive net balance (especially in the 1990s when winter precipitation was unusually high) (Nesje, 2009). Since 2001, however, the mass balance of Norwegian glaciers has become predominantly negative. The North Atlantic Oscillation has a strong influence on the variability of the mass balance of maritime glaciers in western Norway (Reichert et al., 2001).

7.3.2.7. Svalbard

Over the past century, there has been a general trend toward retreat and thinning of Svalbard glacier fronts (Dowdeswell, 1986), excluding those that have surged during the period of observation, and thickening of higher elevation regions (Bamber et al., 2004; Nuth et al., 2007, 2010; Kohler et al., 2007; Moholdt et al., 2010a,b). Mass balance has been measured on two Svalbard glaciers (Austre Brøggerbreen and Midre Lovénbreen) since 1967 and on two more (Kongsvegen and Hansbreen) since the late 1980s (Hagen et al., 2003b). Almost all annual net balances are negative, the most notable exceptions being in 1987 and 1991 when all the measured balances were positive. There is no significant long-term trend in any of the annual balance records. Large annual variations are driven mainly by variations in the summer ablation. The cumulative balances of Austre Brøggerbreen (1967 to 2007) and Midre

Lovénbreen (1968 to 2007) were -20.3 and -15.3 m w.e., respectively, while that of Hansbreen (1989 to 2007) was -6.2 m w.e. (WGMS, 2009). Kongsvegen had a much smaller negative annual balance and a cumulative balance of -1.6 m w.e. (1987 to 2007) (WGMS, 2009), indicating that larger glaciers with high-elevation accumulation areas are experiencing more favorable mass balance conditions than smaller, low-lying glaciers. This is also the case for Austfonna in northeastern Svalbard, which had a surface net balance of -0.05 m/y w.e. for the five-year period 2004 to 2008 (Moholdt et al., 2010a). Shallow ice cores from Austfonna also indicated a net surface mass balance close to zero for the period between the Chernobyl fallout in 1986 and 1999 (Pinglot et al., 1999).

Hagen et al. (2003b) used the hypsometry (area-altitude distribution) of the glaciers and curves of net balance versus altitude for 13 regions to estimate the surface balance of Svalbard glaciers over the period 1968 to 1998. They found it to be slightly negative (-0.5 ± 0.1 Gt/y), or a mean specific surface net balance of -0.014 ± 0.003 m w.e./y. Mass loss by iceberg calving was estimated to be -4.0 ± 1.0 Gt/y (Dowdeswell and Hagen, 2004), making the total net balance of the archipelago significantly more negative, in total -4.5 Gt/y, or -0.12 ± 0.03 m w.e./y. A more recent estimate of the Svalbard calving flux (2000 to 2006) is -6.8 ± 1.7 Gt/y (Błaszczyk et al., 2009).

Geodetic measurements suggest that the rate of volume loss from a number of glaciers, especially low-lying glaciers close to the west coast, has increased by up to a factor of four since the early 1960s (Kohler et al., 2007). This is consistent with summer temperatures recorded at Longyearbyen, which increased by 0.04 °C/y from 1967 to 2006 and 0.17 °C/y from 1997 to 2006 (Førland and Hanssen-Bauer, 2003). Nuth et al. (2010) compared satellite altimetry from ICESat (2003 to 2007) to older topographic maps and digital elevation models (1965 to 1990) and estimated the geodetic mass change over the past 40 years for Svalbard, excluding Austfonna and Kvitøya, to be -9.7 ± 0.6 Gt/y (surface mass balance of -0.36 ± 0.02 m w.e./y). When the Austfonna estimate is added, this gives an overall mass balance for Svalbard of nearly -13 Gt/y. Moholdt et al. (2010b) used repeat track ICESat laser altimetry to assess mass and volume changes of Svalbard glaciers from 2003 to 2008. During this period, most regions experienced thinning at low elevations and thickening at high elevations. The geodetic mass balance for all of Svalbard's glaciers (not taking into account the effects of advance and retreat of calving glacier termini) was estimated to be -4.3 ± 1.4 Gt/y. The largest mass losses were in western and southern Svalbard, while Austfonna and glaciers in northeastern Spitsbergen gained mass over the period. Thus, available estimates of Svalbard net mass balance range from -4.3 to -14 Gt/y, depending upon the period of measurement and which calving flux estimate is used.

7.3.2.8. Russian Arctic islands

The major glacierized regions in the Russian Arctic are in the archipelagos of Franz Josef Land, Severnaya Zemlya, and Novaya Zemlya. Between 1952 and 2001, the glacierized areas decreased by 2.7% on Franz Josef Land, 0.4% on Severnaya Zemlya, and 1.4% on Novaya Zemlya. The total area reduction was about 725 km² (-375 km² on Franz Josef Land, -284 km² on Novaya Zemlya, and -65 km² on Severnaya Zemlya) (Glazovsky and

Macheret, 2006). In Novaya Zemlya, net glacier recession has been greater on the west coast than on the east coast (Glazovsky, 2003). Using local area-volume scaling relationships, volume losses from the three archipelagos between 1952 and 2001 were estimated at -71 km³ (Franz Josef Land), -24 km³ (Severnaya Zemlya), and -150 km³ (Novaya Zemlya). Assuming the volume was lost as ice, this gives a mean annual mass loss of -4.5 Gt/y from the three archipelagos (Glazovsky and Macheret, 2006).

Limited measurements of the surface mass balance of Shokal'sky Glacier on Novaya Zemlya, supplemented by reconstructions based on regression analyses between winter temperature / accumulation and summer temperature / ablation, suggest predominantly negative balances between 1930 and the mid-1990s (Zeeberg and Forman, 2001). Direct measurements on Vavilov Ice Cap (Severnaya Zemlya) between 1974 and 1988 also showed a slightly negative surface balance (-0.03 m w.e./y) (Barkov et al., 1992).

7.3.2.9. Russian mountains

The USSR glacier inventory mapped the glaciers of northeastern Siberia from aerial photography. Glacier changes have been determined by comparison with 2002/2003 Landsat7 ETM+ imagery. The area of glaciers of the Suntar Khayata mountain range (Figure 7.12) decreased from 200 km² in 1945 to 162 km² in 2002/2003, while that of glaciers in the Chersky mountain range decreased from 156 km² in 1970 to 113 km² in 2002/2003 (Ananicheva et al., 2006). The area of the Byrranga glaciers on the Taymir Peninsula decreased from 30.5 km² in 1967 to 24.4 km² in 2003, a reduction of 20%. South- and east-facing glaciers had the largest areal reductions, consistent with greater warming trends and smaller influence of westerly-derived cyclones on the eastern side of the mountain range (Ananichava and Kapustin, 2010).

On the Koryak Upland, a peninsula between Kamchatka and Chukotka, 248 glaciers were mapped from maps and aerial photographs dating from the 1950s and using Landsat 7 ETM+ and ASTER data from 2003. Their combined area decreased by 66.5%, from 176.6 km² to 54.4 km², over the intervening period. Glaciers with a northeasterly aspect showed the largest proportional area reductions. These glacier area changes are the largest recorded in the Russian sub-Arctic and reflect a



Figure 7.12. Mountain glaciers in the Suntar Khayata Range of northeastern Siberia. Note the well-developed meltwater drainage systems on the glacier surfaces. Source: Maria Ananicheva, Russian Academy of Science.

response to a combination of climate warming and decreased snowfall from Pacific sources (Ananichava and Kapustin, 2010).

At the end of the 1950s, there were 143 glaciers in the Ural Mountains with a total area of 28.7 km² (Osipova, 2006). From 1958 to 2001, mass balance observations were carried out on two Polar Ural glaciers (IGAN Glacier, area 0.73 km², and Obruchev Glacier, area 0.35 km²). These records have been extended to cover the entire 20th century by correlation with local measurements of summer air temperature and winter precipitation. The resulting series show periods of negative balance between 1900 and 1920, in the late 1950s and 1960s, and since 1980. Positive balances occurred between 1920 and the mid-1950s (Kononov et al., 2005). From 1953 to 2000 (1981 for IGAN Glacier), the average area decrease rate of the four glaciers in the region (Obruchev, MGU, Chernov, IGAN) was 0.9% per year (Glazovsky et al., 2007).

7.3.2.10. Kamchatka

There are currently 448 glaciers in Kamchatka, with an area of about 874 km². The climate of Kamchatka is strongly influenced by intense storm activity from the Pacific Ocean, the thermal influence of the Sea of Okhotsk on the western side of the Peninsula, and the topography of the region. The mass balance of Kozelsky Glacier was positive from 1973 to 1978 and generally negative thereafter, with a cumulative mass balance of about -5 m w.e. over the period of record (1973 to 1997; Dyurgerov and Meier, 2005) (Figure 7.10).

7.3.2.11. Summary of regional changes

In general, glaciers across the Arctic began retreating and losing mass in the early 20th century. Area changes and mass loss continued through the mid-20th century, with some regions experiencing brief episodes of slower retreat, reduced mass loss, or even mass gain. The rate of mass loss increased during the past decade across most regions of the Arctic. This marks a change from the situation reported by Dowdeswell et al. (1997), who found that although most Arctic glaciers had experienced predominantly negative net surface mass balance over the previous few decades, there was no uniform trend in mass balance.

7.3.3. Links between mass balance and climate

Annual glacier mass balances often correlate over spatial scales as large as 1200 km (Cogley and Adams, 1998; Rasmussen, 2004) as a result of trends in climate that are consistent over broad regions. These trends often occur due to synoptic-scale teleconnections between the positioning of the polar jet stream, the phase of the El Niño Southern Oscillation (ENSO), and regional patterns in temperature and precipitation. The mass balance of glaciers in Alaska, western Canada, and the U.S. Pacific Northwest is strongly affected by a decadal ENSO-like phenomenon, otherwise known as the Pacific Decadal Oscillation (PDO), which is measured by variations in the sea-surface temperature of the Gulf of Alaska (Bitz and Battisti, 1999; Josberger et al., 2007). Mass balance measurements from Gulkana Glacier in interior Alaska, Wolverine Glacier in maritime Alaska, and South Cascade Glacier in coastal Washington State show the complex reaction of glacier mass balance to variations in the PDO that result in major changes

in the positioning of the North Pacific storm track and the distribution of winter precipitation. From 1966 to 1977, the PDO was in a strong cold phase and the net balance of the three glaciers was slightly negative. In 1977, the PDO switched into a strong warm phase, and the mass balance of South Cascade became very negative, a trend that continues to present. The mass balance of Gulkana and Wolverine Glaciers began to increase as the storm track was diverted toward Alaska. From 1987 to present, the PDO warm phase has weakened, and the net balance of all three glaciers has become uniformly negative.

Gardner and Sharp (2007) showed that accelerated glacier surface mass loss in the Canadian Arctic after 1987 was associated with increased July mean air temperature and a shift in the mean position of the center of the July circumpolar vortex from the western hemisphere to the eastern hemisphere. This allowed increased intrusion of warm air from continental North America into the Queen Elizabeth Islands in summer. July vortex types associated with warm temperatures and negative mass balance anomalies were also more common from 1948 to 1962, so predominantly negative surface mass balances may also have characterized the 1950s.

Occasional periods of positive balance on Novaya Zemlya (especially in the late 1940s and early 1950s) occurred when the North Atlantic Oscillation (NAO) was in a positive phase, sea-surface temperatures in the southern Barents Sea were anomalously warm, and winter precipitation was increased (Zeeberg and Forman, 2001). Negative surface balances occurred whenever summer temperatures rose more than 1 °C above the 1933 to 1991 mean, most notably from the early 1950s to the late 1960s. Positive NAO conditions also coincided with the period of positive mass balances in western Scandinavia in the early 1990s (Pohjola and Rogers, 1997).

7.4. Proxy indicators of surface mass balance

- The number of *in situ* measurements of the surface mass balance of glaciers in the Arctic is small, and the distribution of monitored glaciers is uneven. Therefore, it is difficult to estimate accurately the surface mass balance of the regional ice cover (the quantity that needs to be known to determine the contribution of Arctic glaciers to global sea level change) on the basis of these measurements alone.
- There is, therefore, considerable interest in using remote sensing methods to repeatedly measure regional-scale patterns in parameters that vary in ways that are well-correlated with surface mass balance in order to generate records that may reflect the temporal trends and variability in surface mass balance.
- Parameters of interest include the length of the summer melt season, the distribution of snow and ice facies across mountain glaciers and ice caps, the equilibrium-line altitude, the accumulation area ratio, the surface albedo, and the surface temperature. These can be measured using active microwave methods or passive monitoring in the visible and infrared parts of the electromagnetic spectrum. To date, such measurements have been made more widely on the large ice sheets than on mountain glaciers and ice caps, but this is changing with improvements in sensor resolution.

- Pan-Arctic mapping of summer melt season duration and the end-of-summer distribution of snow and ice facies has been possible for the 1999 to 2009 decade due to the availability of enhanced resolution data products from the Seawinds scatterometer on QuikSCAT. That satellite is no longer functional and there is as yet no new data series to replace the one it generated.

7.4.1. Introduction

Glaciological (*in situ*) measurements of the surface mass balance of Arctic glaciers and ice caps are limited to a small number of glaciers that are unevenly distributed across the Arctic and are biased toward small, land-terminating glaciers. For many of these glaciers, the time series of surface mass balance measurements are discontinuous, of short duration, and not recent. In some regions of the Arctic, *in situ* surface mass balance data are simply nonexistent. Such limitations are mainly due to the remoteness of the Arctic and the intense logistical demands associated with establishing and maintaining *in situ* surface mass balance observations. However, common practice has been to produce regional-scale estimates of surface mass balance based on interpolation of the small number of *in situ* observations. This results in large uncertainties where data are sparse, so that it is not clear whether these estimates truly represent regional surface mass balance trends over the Arctic. Because of these limitations, there is a pressing need to develop alternative methods for estimating trends in surface mass balance and to be able to apply them repeatedly over large areas in order to monitor changes in surface mass balance at regional scales.

Proxy indicators of surface mass balance are parameters or indices that are directly related to the surface mass balance process and that can be used to infer changes in surface mass balance. For example, variations in the abundance of melt layers in ice cores have been used for this purpose (e.g., Koerner and Fisher, 1990; Kinnard et al., 2008). Currently, regional-scale proxy indicators of annual surface mass balance are typically developed from satellite-derived remote sensing data. Some of these proxies provide an indication of the sign of the surface mass balance change between consecutive mass balance years (e.g., Wolken et al., 2009), while others may be useful in the development of methodologies for up-scaling *in situ* surface mass balance measurements to the regional-scale glacier cover (e.g., Wang et al., 2005) or for validating predictions from surface mass balance models.

7.4.2. Proxy indicators, data sources, and methods of measurement

7.4.2.1. Melt duration

Spatial and temporal variability in the surface mass balance of many Arctic glaciers is controlled by the variability in surface melt (Koerner, 2005; Gardner and Sharp, 2007). Surface melt characteristics (extent and duration) can provide valuable information about the melt process and can be detected at regional scales by satellite remote sensing. Because melt usually occurs in all regions of Arctic glaciers and ice caps every summer, melt extent provides little information about variability in the summer melt process on these ice masses.

Melt duration is a much better descriptor and is well correlated with the annual positive degree-day total (a parameter used to simulate snow and ice melt rates in temperature index melt and mass balance models) (Wang et al., 2005), and with summer mean temperatures and geopotential heights in the lower troposphere as derived from climate re-analyses (Wang et al., 2005, 2007; Sharp and Wang, 2009).

Microwave remote sensing is well suited for mapping melt duration on Arctic ice masses. Passive microwave remote sensing is commonly used for melt mapping on Greenland, but its coarse spatial resolution (≥ 25 km) precludes its use on the smaller Arctic glaciers and ice caps. Data from Ku- and C-band microwave scatterometers have been used successfully to map annual melt duration on ice caps and glaciers in the Arctic (Smith et al., 2003; Wang et al., 2005; Sharp and Wang, 2009; Sharp and Wolken, 2009, 2010; Wolken et al., 2009) (Figure 7.13). Annual melt duration is determined by calculating the number of days between the melt onset and freeze-up dates minus the duration of any intervening periods when melt was not detected. Wang et al. (2005) used time series of enhanced resolution data from the SeaWinds scatterometer aboard QuikSCAT (Early and Long, 2001; Long and Hicks, 2005) to determine melt onset and freeze-up dates and to determine annual melt season durations on ice caps in Arctic Canada (2000 to 2004). On these ice caps, annual mean melt duration varies with ice surface elevation ($r = -0.80$) and distance from Baffin Bay ($r = -0.44$) and is strongly linked to variations in geopotential height at the 500 hPa level. For the period 2000 to 2004, average melt duration for individual ice caps ranged from 26 days on the Agassiz Ice Cap to 62 days on the Manson Icefield. For the Queen Elizabeth Islands as a whole, the shortest melt season was 2002 and the longest was 2001.

In the Eurasian Arctic (Svalbard, Severnaya Zemlya, Novaya Zemlya), average melt duration (2000 to 2004) is well correlated with latitude, longitude, and elevation and is consistent with the steep climatic gradient across the region (i.e., warm and moist in the west to cool and dry with persistent sea ice in the east; Dowdeswell et al., 2002; Sharp and Wang, 2009). Average melt duration on Severnaya Zemlya (51 days) is significantly shorter than on Novaya Zemlya (75 days) and Svalbard (77 days). Data show that 2000 was the shortest melt season and 2001 the longest during the 2000 to 2004 period (Sharp and Wang, 2009). Variations in annual mean melt duration were strongly correlated with the mean (June and August) 850 hPa air temperature.

7.4.2.2. Snow and ice facies

Glacier surfaces are organized into zones on the basis of differences in the physical properties of surface and near-surface snow and ice (Benson, 1962). The differences between snow and ice facies are related to variations in the magnitude of summer melt, which are strongly correlated with elevation. Snow and ice facies on glaciers and ice caps in the Arctic include the following (from high to low elevation): dry snow facies – formed where no melt occurs and snow is converted to ice solely by compaction; percolation facies – formed where meltwater percolates into the snowpack and refreezes as lenses, layers and pipes, but the snowpack never reaches the melting point throughout the melt season; saturation facies – formed where




Figure 7.13. Mean annual melt duration on larger Arctic ice masses for the period 1999 to 2008 based on QuikSCAT scatterometer data. Source: Gabriel Wolken, Alaska Division of Geological and Geophysical Surveys.

the temperature of the entire snowpack reaches the melting point sometime during the melt season and wet snow refreezes at the end of the melt season; superimposed ice facies – formed in a transitional zone in the lowest part of the accumulation area where meltwater freezes directly onto the glacier ice surface; and glacier ice facies – exposed in the ablation zone in summer when summer melt removes the annual snow accumulation and exposes glacier ice at the surface (Figure 7.14). There is often a transitional zone between snow and ice facies in which a mixture of these facies can be found. The distribution of snow and ice facies can change annually, and not all facies are found on all ice masses in all years. Because the distribution of snow and ice facies is directly linked to the balance between the processes of accumulation and surface melt, it can provide valuable proxy information about spatial and temporal variations in the surface mass balance.

Snow and ice facies have been mapped at regional scales using optical and microwave remote sensing. Mapping with optical sensors has had limited success, largely due to the often subtle contrast between snow and ice facies and to the occurrence of fresh snow (which conceals the underlying facies) and cloud cover (which conceals the glacier) at the end of the ablation season (Østrem, 1975a; Nolin and Payne, 2007; Dowdeswell et al., 2007). Microwave radiation is unaffected by cloud cover, but

is sensitive to the surface and volumetric physical properties of snow and ice. Snow and ice facies on Arctic glaciers and ice caps have been linked to specific signatures acquired by active microwave sensors, and mapped on the glaciers Kongsvegen and Lovénbreen (Svalbard) using synthetic aperture radar (SAR; ERS-1/2) data (Engeset et al., 2002; König et al., 2002). Firn, superimposed ice, and glacier ice facies were identified




Figure 7.14. Snow and ice facies zones on a glacier or ice cap. Source: after Benson (1962).

in these studies, but the complicated nature of backscatter in the superimposed ice zone precluded the identification of the equilibrium line. Further work on Kongsvegen using *in situ* data and SAR concluded that the superimposed ice zone represents 35% of the glacier (Obleitner and Lehning, 2004). Langley et al. (2008) and Brandt et al. (2008) also investigated snow and ice facies on Kongsvegen by combining data from SAR and ground-penetrating radar (GPR) and concluded that SAR zones were in very good agreement with GPR-derived glacier facies. On Austfonna (Svalbard), Dunse et al. (2009) used GPR to determine the multi-year (2004 to 2007) snow and ice facies distribution and linked variability in facies over the study period to changes in surface mass balance.

Regional-scale mapping and monitoring of snow and ice facies have been performed using microwave scatterometer data. Wolken et al. (2009) used a classification of end-of-summer, enhanced resolution (2.225 km²) data from QuikSCAT (tuned using available field observations) to map the distribution of snow and ice facies in the Canadian High Arctic and its interannual variability (1999 to 2005) (Figure 7.15). Increases in summer air temperature and melt duration were associated with a decrease in the areas of the percolation and saturation zones, an increase in the area of the glacier ice zone, and an increase in the elevation of inter-facies boundaries.

7.4.2.3. Equilibrium-line altitude

The equilibrium line is the line connecting points on a glacier surface where annual accumulation equals annual ablation. Above the equilibrium line (the accumulation area) there is

a net gain in mass for a particular year, whereas below the equilibrium line (the ablation area) there is a net loss in mass. The equilibrium-line altitude (ELA) is the average altitude of the equilibrium line at the end of the ablation season in any balance year. The ELA is related to the surface mass balance because it rises and falls as the annual mass balance of the whole glacier becomes more or less negative (Østrem, 1975a; Hagen and Liestøl, 1990). It can be used to identify variability and trends in surface mass balance when monitored annually. The long-term ELA represents the average position of the ELA over many years. Change in the long-term ELA, generally linked to a change in glacier geometry, serves as an important indicator of regional climate change.

The ELA is most accurately determined using standard *in situ* glaciological techniques for measuring surface mass balance. Dyurgerov (2002), Dyurgerov and Meier (2005) and Dyurgerov et al. (2009) compiled all available time series (around 280) of *in situ* mass balance data and related variables, including ELA, for glaciers outside the two ice sheets. For the few glaciers in the Arctic where ELAs are determined through *in situ* measurements, ELA time series are characterized by a high degree of interannual variability. However, while these measurements are robust and invaluable to the glaciological community, they are also spatially restricted and limited in their ability to provide a meaningful measure of ELA variability on a regional scale.

Alternative methods have been developed for monitoring regional-scale changes in the annual ELA, the most effective of which involve the use of satellite microwave remote sensing. In Arctic Canada, regional-scale variability in the




Figure 7.15. Annual distribution of snow and ice facies at the end of the melt season on ice caps in the Canadian High Arctic (1999–2005) as derived from QuikSCAT scatterometer data. Source: Wolken et al. (2009).

ELA can be inferred from changes in the lower boundary of the superimposed ice zone, which is highly correlated with changes in surface mass balance measurements (Wolken et al., 2009). Scatterometer-derived changes in the annual average ELA for each ice cap show a generally coherent pattern of change during the study period (1999 to 2005), with the highest ELAs occurring in 2001, the year with the longest melt season.

7.4.2.4. Accumulation area ratio

The accumulation area ratio (AAR) is the ratio of the area of the accumulation area to the area of the entire glacier. Because the lower limit of the accumulation area is determined by the position of the equilibrium line, the AAR and the ELA are directly related. If a record of the AAR is combined with *in situ* surface mass balance data, then it is possible to produce quantitative estimates of changes in the surface mass balance with respect to changes in the AAR (Dyurgerov et al., 1996, 2009; Hock et al., 2007b). Quantification of regional-scale changes in surface mass balance from AAR changes in the Arctic is limited by the sparseness of *in situ* surface mass balance data for use in calibration. However, regional-scale changes in surface mass balance can be qualitatively assessed based on the relative changes in the AAR between regions. Annual AARs for ice caps in the Canadian High Arctic were determined from maps of the distribution of snow and ice facies derived from QuikSCAT scatterometer data for the period 1999 to 2005 (Wolken et al., 2009). Results from this study indicate considerable spatial and temporal variability in the annual AAR during this period. For the Queen Elizabeth Islands as a whole, the mean AAR was 0.75 over the period 1999 to 2005. The smallest mean AAR (0.50) occurred in 2001 and the largest (0.82) in 2004 (Wolken et al., 2009).

7.4.2.5. Albedo

The albedo (the fraction of incoming solar radiation reflected by a surface) of snow and ice is a function of snow/ice grain size, surface water content, solar incidence angle (Wiscombe and Warren, 1980), and snow impurities (Warren and Wiscombe, 1980), including black carbon from natural and industrial sources (McConnell et al., 2007; Forsstrom et al., 2009). On Arctic glaciers, solar radiation is usually the main source of energy for surface melt, and its magnitude and distribution are controlled in part by the glacier surface albedo. As a result, and because factors such as grain size and water content are coupled to surface melt rates, interannual variations in surface albedo and their spatial patterns over individual glaciers can serve as a proxy indicator of surface mass balance.

In situ observations of albedo can be scaled-up with satellite optical remote sensing measurements (Williams, 1987; Reijmer et al., 1999; Greuell and Knap, 2000; Nolin and Payne, 2007), producing data that can be used to identify reductions in albedo that provide an indication of melt onset (Hall et al., 1987; Bindshadler et al., 2001). De Ruyter de Wildt et al. (2002, 2003) used Advanced Very High Resolution Radiometer (AVHRR) data for Vatnajökull, Iceland to determine the evolution of the surface albedo over the melt season and estimate the potential absorbed radiation, which was shown to correlate well with the mean specific mass balance ($r = 0.87$ and 0.94 for different outlet glaciers). This methodology was further developed by

Greuell et al. (2007), who generated estimates of mass balance for the whole of Vatnajökull.

7.4.2.6. Land (glacier) surface temperature

Because winter precipitation is consistently low in the Arctic (excluding southern Alaska, Scandinavia, Iceland, and Kamchatka), variability in glacier mass balance is largely controlled by summer temperature. While precipitation events during summer can be important as summer snowfalls result in short-term increases in surface albedo, temperature tends to drive the ablation process and control variations in surface mass balance (Koerner, 2005; Gardner and Sharp, 2007). In the absence of systematic *in situ* temperature observations, which are available for only a few areas across the Arctic, satellite-borne thermal infrared sensors can be used to monitor clear-sky land surface temperature (LST) and surface melt at regional scales over the terrestrial cryosphere (Key and Haeffliger, 1992; Key et al., 1997; Stroeve and Steffen, 1998; Hall et al., 2004, 2006, 2008a,b). In the Eurasian Arctic, Sharp and Wang (2009) used Moderate-Resolution Imaging Spectroradiometer (MODIS) LST data in place of *in situ* near-surface air temperature data to tune melt detection algorithms applied to QuikSCAT scatterometer data. However, there has been little other use of LST data on Arctic glaciers and ice caps. This is probably because reliable satellite-derived LST data can only be obtained under cloud-free conditions and because there are errors and calibration inconsistencies associated with many of these data. Owing to the great potential in using LST as a proxy for regional-scale surface mass balance, there is a need for more *in situ* validation work over ice-covered regions in order to assess the accuracy of satellite-derived LST over Arctic glaciers and ice caps.

7.5. Ice dynamics and iceberg calving

- Iceberg calving from ocean-terminating glaciers can be an important process of mass loss. Rates of calving loss can change rapidly for reasons that are influenced, but not directly controlled, by climate. These changes can generate anomalously high rates of mass loss, but not anomalously high rates of mass gain.
- Possible controls on calving rates include changes in lubrication from seasonal meltwater input, changes in resistance to flow from thinning and flotation, loss of contact with a stabilizing moraine, and break-up of floating ice tongues, as well as from changes in upstream dynamics, including surging.
- A tidewater glacier cycle is recognized. It involves prolonged periods of slow (~1000 years) glacier advance into the ocean, alternating with shorter periods (around decades) of accelerated glacier flow and retreat.
- Although measurements of iceberg calving fluxes are now available for many regions of the Arctic, the ability to model the processes that determine these fluxes is rudimentary. There is currently no ability to predict how calving fluxes will evolve in the future.

- The character of a glacier terminus and the icebergs produced are linked. Small, hard-to-detect bergs are produced mainly by grounded termini and glaciers in rapid retreat, while large tabular bergs come from floating ice tongues and ice shelves.
- The largest remaining ice shelves in the Arctic fringe the northern coastline of Ellesmere Island. These entered a new phase of break-up after 2000. As a result, several fjords in the region are now free of a permanent ice cover for the first time in at least 3000 years.

7.5.1. Overview

Glaciers that terminate in the ocean or in lakes lose mass by iceberg calving as well as by melting and sublimation, and iceberg calving can be the dominant mass-loss term for many glaciers and ice caps in the Arctic. Rates of iceberg calving from marine-ending glaciers (referred to as ‘tidewater glaciers’ if their termini are grounded below sea level) are modulated by stress and flow conditions near the glacier’s terminus, which will vary as the glacier changes shape and volume in response to climate change. Rates of calving can also change in response to internally controlled processes that alter stresses and may be entirely independent of climate. In either case, glacier mass loss through calving may be sudden and rapid, and may be far greater in magnitude than losses due to climatically controlled mass balance. Rapid dynamic changes can cause anomalously rapid mass loss, but not anomalously rapid mass gain, because alterations in flow can force fast ablation (by moving ice either to lower and warmer elevations or into the ocean), while accumulation rates are limited by precipitation.

7.5.1.1. Hydrology and basal sliding

Glaciers that slide over their beds typically exhibit significantly larger velocities and fluxes than glaciers that flow by internal (ice) deformation alone. Sliding is facilitated by the presence of water and deformable sediments at the ice/bed interface, although the relationship between water input and sliding speed is highly non-linear. Warmer surface conditions that increase surface melting in summer will accelerate glacier flow, but there is no simple relationship between the amount of warming and the magnitude of the flow acceleration. Higher water fluxes through subglacial drainage systems may result in greater enlargement of individual drainage channels, lower subglacial water pressures, and less flow enhancement than is generated by smaller fluxes. Thus, it is by no means clear that climate warming will, in the long term, result in more rapid glacier flow. As on Greenland, however, supraglacial lakes often form on Arctic glaciers in summer (Figure 7.16), and may drain suddenly when water-pressure induced fracturing creates drainage connections between the glacier surface and the glacier bed (Boon and Sharp, 2003). These lake drainage events may result in short-lived accelerations of glacier flow. As yet, however, there is no general rule to link increased sliding speed with increased englacial or subglacial water input, and no validated, reliable numerical model for basal sliding exists (Fountain and Walder, 1998; Hooke, 1998; Marshall et al., 2002).



Figure 7.16. Supraglacial lakes forming on the surface of Columbia Glacier, Alaska, during the melt season. Source: W. Tad Pfeffer, Institute for Arctic and Alpine Research, University of Colorado

7.5.1.2. Glacier surges

Glacier surges are episodes of anomalously rapid motion (about 10 to 100 times ‘normal’ or non-surging speeds) that last for months to a few years and alternate with longer periods (decades to centuries) of normal, or quiescent, glacier behavior. Glacier velocities during the active phase of the surge cycle may reach 100 m per day and rates of terminus advance may approach 1 km per month. Glacier surges are not a direct response to climate forcing, but surging can alter a glacier’s sensitivity to climate, especially in the immediate post-surge phase when its accumulation area is anomalously depleted (Dowdeswell et al., 1995).

7.5.1.3. Calving and marine-ending outlet glacier instability

‘Marine-ending’ or ‘ocean-terminating’ glaciers reach the ocean shore with sufficient flux to maintain an ice tongue that is either grounded in water shallower than the tongue’s flotation depth or may be floating under polar conditions (subfreezing and, therefore, strong when in tension). Floating tongues can also form during periods of rapid terminus retreat. The term ‘tidewater glacier’ is often used interchangeably with these labels, although it was originally restricted to glaciers with grounded termini. Marine-ending glaciers can undergo a periodic growth/shrinkage instability with long (roughly centuries) periods of slower motion and slow advance

alternating with shorter periods (decades) of rapid (~ 5 to 10 km/y) motion, high calving flux, and rapid (~ 1 km/y) retreat (Meier and Post, 1987) (Figure 7.17). This is significant in that during rapid retreat a glacier can lose mass into the ocean far faster (by loss of its marine-grounded tongue and drawdown of its source basin by rapid flow) than is possible by direct surface mass balance forcing alone.

In its advancing phase, a tidewater terminus is stabilized in part by back stress against a moraine at its advancing margin. If it retreats from the moraine, a tidewater glacier in an advanced position can switch abruptly (within years) into an unstable phase of rapid flow and calving accompanied by thinning in its ocean-grounded reach that results in terminus retreat. Once initiated, rapid flow and retreat appear to be generally irreversible and continue until the glacier's terminus retreats inland to a point where the water depth provides no significant buoyancy force. The causes of unstable retreat are not completely understood, but involve high basal water pressures tied to the depth of the glacier bed below sea level, rapid sliding, vertical thinning, and positive feedback between thinning and rapid flow. The processes governing the size and rate of production of icebergs are extremely poorly known. Climate-induced thinning can play a critical role in initiating unstable retreat, but once initiated, unstable retreat appears to be modulated by channel geometry and englacial and basal hydrology and is essentially independent of climate and surface mass balance. Melting of the submarine faces of grounded tidewater glaciers can be rapid (Motyka et al., 2003) and can result in undercutting of the terminal ice cliff with consequences for iceberg production and terminus stability (Rignot et al., 2010; Straneo et al., 2010).

7.5.1.4. Lake-terminating glaciers

The total area of lake-terminating calving glaciers is much smaller than the area of marine-terminating glaciers, and the dynamics of their calving appear to be significantly different. Thinning rates on lake-calving glaciers are among the highest observed anywhere (e.g., -3.0 m/y basin-averaged thinning at Yakutat Glacier, Alaska) (Larsen et al., 2007).

7.5.1.5. Ice shelf / ice tongue break-up

Stable floating ice tongues (or ice shelves) are held in place by stabilizing stresses supplied by lateral attachments to valley walls or embayment margins (and, to a lesser degree, back stress from sea ice and confined iceberg fragments: *sikkusaq*), rather than by basal drag or back stress on the glacier terminus (Dowdeswell et al., 2000; Reeh et al., 1999). Submarine melt can be a significant source of mass loss from floating tongues (Mayer et al., 2000). Spreading and thinning of floating ice produces small tensile stresses, crevassing, and calving of icebergs. Under warming conditions, a floating ice tongue can be destabilized by (i) increased submarine melt, (ii) increased internal ice temperature, and (iii) percolation of surface meltwater into open crevasses and fractures. Loss of an ice shelf or floating tongue and the associated back stress on the feeding glacier(s) affect the force balance on the ice upstream from the grounding line and in general cause an acceleration of the grounded ice and increased ice discharge to the ocean. The loss of the floating tongue has no influence on sea level,

The Tidewater Glacier Cycle




Figure 7.17. Schematic diagram showing the typical advance-retreat cycle of a tidewater glacier. Source: after Meier and Post (1987).

but increased discharge from the grounded part of the glacier contributes to eustatic sea-level rise.

7.5.2. Measurement methods

Glacier dynamic changes are manifested principally in changes in speed, surface elevation, ice discharge, and iceberg calving. Consequently, surface observations to track moving features or measure surface altitude are critical to understanding the processes involved. Glacier velocity is determined from repeat measurements of the position of markers on the glacier surface made by optical survey (Harper et al., 2007), GPS (Howat et al., 2008), and by feature tracking using aerial photography (Krimmel, 2001) and ground-based photography (O'Neel et al., 2005). Velocities are also measured remotely by manual and automated feature tracking applied to a variety of visible satellite imagery (Scambos et al., 1992; Joughin, 2002; Dowdeswell and Benham, 2003) and by radar interferometry and speckle tracking (Joughin et al., 1999). Elevation changes are measured by photogrammetry, by repeat altimetry from airborne or spaceborne platforms (Arendt et al., 2002, 2006; Larsen et al., 2007; Howat et al., 2008), and to a lesser degree by ground-based GPS and optical surveys.

The terminus advance/retreat rate ($\partial x / \partial t$) is the difference between the calving rate (u_c) and the ice flow speed at the terminus (u_T): ($\partial x / \partial t = u_c - u_T$). Iceberg calving events are episodic and very short in duration, and the volume of individual icebergs is hard to determine from imagery. The calving rate is therefore difficult to measure directly, and it is typically calculated as $u_c = \partial x / \partial t + u_T$ (O'Neel et al., 2005), but this is a weak approach in predictive models where $\partial x / \partial t$ is often the variable being sought. New methods are being developed to use seismic records to identify individual calving events and estimate iceberg discharge (O'Neel and Pfeffer, 2007).

7.5.3. Calving and surging glaciers in the Arctic

Surging and marine calving glaciers are found throughout the Arctic, although there are currently none in Norway or Sweden. Table 7.2 summarizes recent estimates of mass loss by calving from major regions and/or major ice masses within the Arctic (but note that no estimates are available for some regions and ice masses).

7.5.3.1. Alaska and western Canada

The greatest concentrations of glacier area in Alaska and northwestern Canada lie along the coast of the Gulf of Alaska, where land-terminating glaciers on the interior side drain predominantly into the Matanuska, Copper, and Yukon Rivers, while seaward-facing glaciers drain into, or terminate in, the Gulf of Alaska.

7.5.3.1.1. Calving

A significant but undetermined fraction of the area of Gulf of Alaska glaciers is drained through 54 calving tidewater outlets. No estimates have been made of calving flux for the entire Gulf, but a 1982 study (Brown et al., 1982) compared geometry and calving

speed for 13 of the largest tidewater glaciers and found a total flux of 7.2 Gt/y draining from an aggregate basin area of 8138 km², estimated for various periods within the interval 1942 to 1979. No more recent or more complete assessment has been made.

In the past 200 years, the 54 tidewater glaciers terminating in the Gulf of Alaska all retreated from extended stable positions. Columbia Glacier was the last to start retreating and as of 2009 had retreated roughly two-thirds of the way up the 30-km long fjord in which it was grounded up to about 1982. The majority of Gulf of Alaska tidewater glaciers are now either stable in retreated positions or slowly advancing (e.g., Hubbard and Mears Glaciers). Columbia Glacier is undergoing the most rapid change, calving an average 3.3 Gt/y of ice (1982 to 2001), with a maximum annual calving flux of 6.6 Gt in 2001 (O'Neel et al., 2005), and thinning in the terminus region by 20 m/y. GRACE gravity measurements suggest that the Gulf of Alaska glaciers were losing mass at a rate of 84 ± 5 Gt/y in the period 2003 to 2007 (Luthcke et al., 2008). A study of the southeastern (panhandle) Gulf of Alaska sub-region (not including Columbia Glacier) found a loss of 16.7 ± 4.4 Gt/y from 14 580 km². Two-thirds of this was from calving glaciers, although the fraction of this volume loss that was attributable to calving (as opposed to surface melting) is unknown (Larsen et al., 2007).

Table 7.2. Estimated mass losses by iceberg calving of mountain glaciers and ice caps. Specific balances due to calving are derived by dividing the calving mass loss by the total area of the glacier.

	Period	Area, km ²	Calving loss, Gt/y	Specific balance, m/y w.e.	Source
Alaska					
Columbia Glacier	1982 – 2001	1000	3.3	-3.3	O’Neel et al., 2005
Canadian High Arctic					
Devon Ice Cap	1960 – 1999	14 000	0.53±0.12	-0.04	Burgess et al., 2005
Prince of Wales Icefield	1963 – 2003	19 300	1.9 ±0.02	-0.10±0.00	Mair et al., 2009
Agassiz Ice Cap	1999 – 2002	19 500	0.60±0.14	-0.03±0.01	Williamson et al., 2008
W Grant Ice Cap ^a	1999 – 2003	2 000	~0.23	~ -0.12	Williamson et al., 2008
Russian Arctic					
Academy of Sciences Ice Cap	1995	5 575	0.59	-0.10	Dowdeswell et al., 2002
Franz-Josef Land	1929 – 1959	13 700	2.1	-0.15	Govorukha, 1989
	1952 – 2001		4.3	-0.31	Glazovsky and Macheret, 2006
Novaya Zemlya	1930 – 1960	23 600	1.8	-0.08	Govorukha, 1989
	1952 – 2001		1.4	-0.06	Glazovsky and Macheret, 2006
Severnaya Zemlya	1929 – 1972	19 400	0.45	-0.02	Govorukha, 1989
	1952 – 2001		0.7	-0.04	Glazovsky and Macheret, 2006
Svalbard					
All glaciers	1968 – 1998	36 600	4±1	-0.1±0.0	Hagen et al., 2003b
	2000 – 2006	36 600	6.75±1.7	-0.18±0.05	Błaszczuk et al., 2009
Austfonna	^b	8 000	2.5±0.5	-0.31±0.06	Dowdeswell et al., 2008

^a Calving estimates only from Otto Glacier which is likely to represent the majority of the mass loss by calving from the ice cap; ^b a combination of various data sets from the period 1973 to 2001.

Here, and elsewhere, episodic discharges from individual glaciers can exceed the aggregate discharge from the rest of the region, making averages over time difficult to interpret or extrapolate.

7.5.3.1.2. Surging

Surging glaciers are abundant in the central Alaska Range (Denali massif), eastern Alaska Range, and throughout the St. Elias mountains, where ‘Alaskan-type’ surging was defined (Figure 7.18). Bering Glacier, in this region, is the largest glacier (and largest surging glacier) in Alaska (Shuchman and Josberger, 2010). Its last major surge took place in 1995 to 1996, although there was a small surge in 2009 to 2010. Bering Glacier terminates in a large proglacial lake at sea level, the size of which changes dramatically as the glacier advances and retreats. Some surging glaciers in the St. Elias Range terminate in the ocean, allowing surge behavior to influence calving discharge. No surging glaciers are known in the Chugach or Brooks Ranges.

7.5.3.2. Arctic Canada

7.5.3.2.1. Calving

There is no comprehensive summation of calving flux or inventory of calving glaciers for the Canadian Arctic Archipelago, but estimates of calving fluxes for some of the ice caps exist for mixed time periods in the interval 1960 to 2003, totaling 3.0 Gt/y (Devon Ice Cap, 0.5 Gt/y; Agassiz Ice Cap, 0.6 Gt/y; Otto Glacier (western Grant ice complex), 0.2 Gt/y; Prince of Wales Icefield, 1.9 Gt/y). As in Alaska, individual glaciers can dominate the regional flux estimates.

7.5.3.2.2. Surging

At least 51 surge-type glaciers have been identified in the Queen Elizabeth Islands (Copland et al., 2003). Of these, 15 were surging in 1959/1960 and/or 1999/2000. The largest recorded surge-type advances (4 to 7 km) were observed on Axel Heiberg Island and the Manson Icefield (Ellesmere Island). The active phase of the surge cycle of these glaciers may last more than a decade (Mueller, 1969; Copland et al., 2003), typical of ‘Svalbard-type’ surging (Mueller, 1969; Murray et al., 2003). Glacier velocities during the active phase of the surge cycle may range from several hundred metres to over 1 km per year. Because many of the known surge-type glaciers terminate in the ocean, surging may cause large short-term changes in the loss of mass to the oceans by iceberg calving. Little is known about the duration of the quiescent phase of the surge cycle in this region owing to the short period of observations.

7.5.3.3. Greenland (excluding the Greenland Ice Sheet)

Little is known about the history of area and volume changes of the roughly 48 600 km² of glaciers and ice caps that surround the Greenland Ice Sheet, or about their mass balance, calving discharge, or the fraction of their area drained through marine-terminating outlets. Mass balance estimates for these glaciers have been made (Dyurgerov and Meier, 2005) using correlated mass balance records from Svalbard and the Canadian Arctic



Figure 7.18. Hubbard Glacier, which drains into Russell Fjord in the Yakutat region of southern Alaska, is a surging tidewater glacier. Source: Anthony Arendt, University of Alaska.

Archipelago. Net losses from 1992 to 2002 are estimated to be about 18 Gt/y, but the fraction due to calving is completely unknown.

7.5.3.4. Iceland

In Iceland, 26 surge-type glaciers and 80 surge advances have been identified (Björnsson et al., 2003), and surges account for a significant fraction of the mass transported by major outlet glaciers of all the main ice caps. Surges affected 38% of the area of Vatnajökull in the 1990s, and accounted for about 25% of the mass transfer from the accumulation zone of the ice cap to the ablation zone (Björnsson and Pálsson, 2008). Calving losses are unknown but probably not significant.

7.5.3.5. Svalbard

Glacier geometry, flow velocity, and front position changes of Svalbard glaciers were determined from ASTER images acquired in 2000 to 2006 (Błaszczyk et al., 2009). A total of 163 grounded tidewater glaciers drain an area of around 21 200 km² (more than 60% of the total glacier area of Svalbard) through a combined calving terminus length of 860 km.

7.5.3.5.1. Calving

Mass loss due to calving from the whole archipelago was initially estimated to be about 4 Gt/y for the period 1968 to 1998 (Hagen et al., 2003b), but a more recent estimate for the period 2000 to 2006 is 5.0 to 8.4 Gt/y, with a mean value of 6.75 ± 1.7 Gt/y (Błaszczyk et al., 2009). The mean retreat rate ($\partial x / \partial t$) of the calving glaciers is about 30 m/y, and terminus retreat ($\dot{M}_t$) accounts for about 30% (~ 2.1 Gt/y) of the total calving flux from the archipelago. Calving constitutes about 20% of the overall mass loss from Svalbard glaciers (Błaszczyk et al., 2009).

Dowdeswell et al. (2008) estimated the calving flux from Austfonna to be 2.5 ± 0.5 Gt/y from an aggregate terminus length of about 230 km. This represents 30% to 40% of the annual ablation from this ice cap. Terminus retreat reduced the ice cap area by about 10 km²/y during the period 1991 to 2001 and accounted for about 50% of the calving loss.

7.5.3.5.2. Surging

Surge-type glaciers are very common in Svalbard and comprise a range of glacier types from small land-terminating cirque glaciers to large calving outlets. Although the overall fraction of surge-type glaciers is unknown, estimates range from 13% to 90% (Liestøl, 1969; Dowdeswell et al., 1991; Lefauconnier and Hagen, 1991; Hamilton and Dowdeswell, 1996; Jiskoot et al., 1998). Surging of marine-grounded outlets can interact with calving dynamics. The 1250-km² Hinlopenbreen calved about 2 km³ of icebergs in a single year during a surge (Liestøl, 1973). Bråsvellbreen (1100 km²) advanced up to 20 km along its 30-km marine-grounded margin during a surge in 1936 to 1938 (Schytt, 1969). In the inner part of Storfjorden, east Spitsbergen, Negribreen advanced about 12 km in less than a year (about 35 m/d) along a 15-km long section of its front during a surge in 1935 to 1936 (Liestøl, 1969). Recently, the tidewater glacier Nathorstbreen advanced about 7.6 km or about 20 m/d from September 2008 to September 2009 (Sund and Eiken, 2010).

7.5.3.6. Russian Arctic islands

7.5.3.6.1. Calving

Govorukha (1989) estimated calving fluxes of 1.8 Gt/y from Novaya Zemlya (1930 to 1960), 0.45 Gt/y from Severnaya Zemlya (1929 to 1972), and 2.1 Gt/y from Franz Josef Land during the period 1929 to 1959 (a total of 4.35 Gt/y). Using measurements of terminus ice thickness derived by radio echo sounding, ice surface velocities at glacier termini derived by radar interferometry, and measurements of terminus length and terminus advance/retreat, Glazovsky and Macheret (2006) estimated calving fluxes from the Russian Arctic islands to be 6.4 Gt/y for the period 1952 to 2001 (Novaya Zemlya = 1.4 Gt/y; Severnaya Zemlya = 0.7 Gt/y; Franz Josef Land = 4.3 Gt/y). Losses due to terminus retreat were estimated to be about 1.35 Gt/y, or roughly 21% of the total calving flux. It is not possible to determine the significance of the difference between the two calving flux estimates, so it should not be taken to imply a temporal trend in calving fluxes.

7.5.3.6.2. Surging

Surge-type glaciers are rare in the Russian Arctic Archipelago (Dowdeswell and Williams, 1997). None are known to exist in Franz Josef Land, while until recently only three had been identified in Novaya Zemlya and two in Severnaya Zemlya. However, a new analysis based on high-resolution satellite imagery identified 32 potential surge-type glaciers on Novaya Zemlya, representing 18% of the total glacier area (Grant et al., 2009). These glaciers are generally relatively long (median length 18.5 km), large (median area 106.8 km²) outlet glaciers that terminate in water. They occupy large, complex catchment areas that may be receiving increased precipitation from the Barents Sea.

7.5.4. Recent ice shelf break-up events

Most of the largest floating ice shelves in the Arctic, fringing the northern coast of Ellesmere Island, are not predominantly glacier-fed, but form mainly by basal accretion of sea ice and surface accumulation of precipitation (Jeffries, 1992). They

developed around 5500 to 3000 years BP (England et al., 2008) and have lost over 90% of their area during the 20th century, with only four major ice shelves now remaining. Much of the area loss occurred in the 1950s (Koenig et al., 1952) and 1960s (Hattersley-Smith, 1963, 1967). A new phase of disintegration began in 2000, with renewed fracturing of the Ward Hunt Ice Shelf (Mueller et al., 2003) and continued in 2005 with the abrupt loss of almost all of the Ayles Ice Shelf and major calving from the Petersen Ice Shelf (Copland et al., 2007). In summer 2008, the total ice shelf area in Arctic Canada decreased further (by 23% relative to 2007; Mueller et al., 2008) due to the loss of the entire Markham Ice Shelf and 60% of the area of the Serson Ice Shelf. As a result, several fjords on the northern coast of Ellesmere Island are now ice-free for the first time in 3000 to 5500 years (England et al., 2008). In 2010, large new fractures in the Ward Hunt Ice Shelf were first detected in Radarsat-2 images from 7 and 14 August. A MODIS image from 18 August shows that break-up of the eastern part of the ice shelf was underway (Figure 7.19), and some 65 to 70 km² of the shelf had been lost by the end of August. Meanwhile, fragments of the ice islands that calved from the Ayles, Serson, Peterson, Ward Hunt and Markham ice shelves in 2005 and 2008 have drifted into Canada Basin and the Sverdrup and Queen Elizabeth Islands and are beginning to enter the Northwest Passage via Barrow Strait.

Causes of ice shelf break-up appear to include rising summer air temperature and the loss of semi-permanent landfast sea ice along the northern coast of Ellesmere Island, although strong southerly winds seem to play an important role in individual break-up events. Ice shelf break-up events produce large ‘ice islands’ which may become a hazard to shipping and offshore resource exploration if they drift westward into the Beaufort Sea. They can also result in the drainage of epishelf lakes and the loss of their unique ecosystems (Veillette et al., 2008).

As with floating ice tongues, the loss of ice shelves does not directly influence sea-level rise. In the case of the Ellesmere ice shelves, because most of them do not interact with terrestrial glaciers, there is no indirect effect on sea level.

The Matusevich Ice Shelf in Severnaya Zemlya, the only major ice shelf in the Eurasian Arctic, has also undergone periodic calving events during roughly the past 70 years (Williams and Dowdeswell, 2001).




Figure 7.19. MODIS image from 18 August 2010 showing the Ward Hunt Ice Shelf, northern Ellesmere Island, and the extensive fracturing that had developed in the ice shelf to the east and south of Ward Hunt Island. Source: Canadian Ice Service.

7.5.5. Iceberg characteristics and relationship to ice dynamics

There are certain relationships between iceberg characteristics (size, number, morphological type) and parent glacier type and behavior. These relationships can be broadly described as follows (Dowdeswell, 1989; Dowdeswell et al., 1992):

- The largest tabular icebergs (large horizontal dimension relative to depth) are calved from floating glacier tongues and ice shelves. Horizontal sizes reach hundreds of metres to kilometres. The number of individual icebergs calved each year is usually small.
- Fast-flowing tidewater glaciers that are grounded have high rates of discharge, but often produce icebergs of relatively small size (tens to hundreds of metres) and irregular shape that tend to break up quickly into still smaller bergs and bergy bits (Dowdeswell and Forsberg, 1992) (Figure 7.20). Slower-flowing glaciers calve fewer icebergs, but their sizes may be larger than those of icebergs calved from more active glaciers.
- Surging glaciers and tidewater glaciers in rapid retreat tend to produce a very large number of small icebergs (10 to 50 m in length) with irregular shapes (Schytt, 1969). If such glaciers start to float, however, the mode of calving may change to one in which episodic flow-perpendicular rift formation and propagation result in the release of a few very large icebergs (Walter et al., 2010).

The systematic classification of iceberg types made by Dowdeswell for glaciers of Spitsbergen can be applied to all sources of icebergs in the Arctic. It is supported by descriptions of icebergs made at different times near Spitsbergen, Franz Josef Land, and Novaya Zemlya (Sandford, 1955; Kubyshkin et al., 2009), and by observations in the northern Barents Sea in 2003 to 2007. For example, tidewater outlet glaciers in Russkaya Gavan Bay and Inostrantsev Bay in northern Novaya Zemlya have strong fracturing of the front and produce a moderate quantity of small- and medium-sized icebergs of irregular shape (Buzin and Glazovsky, 2005). Floating margins on some of the larger ice caps of Franz Josef Land produce large tabular icebergs (Dowdeswell et al., 1994; Zubakin et al., 2007).



Figure 7.20. Small iceberg off the coast of Franz Josef Land. Note the debris-rich layers within the iceberg. Source: Photo courtesy of Arctic-shelf laboratory, AARI.

7.5.6. Controls on calving fluxes

Although the detailed physics of iceberg calving are poorly understood, certain controlling factors can be identified. The tensile strength of ice is strongly dependent on temperature, and temperate ice (ice at its pressure melting point, where water and ice exist in thermal equilibrium) has essentially no tensile strength (Schulson, 1999). Along-flow extension or compression of ice influences the opening or closing of transverse crevasses, but no clear relationship between calving rate and along-flow strain rate has been demonstrated observationally on meaningful timescales (Alley et al., 2008). A statistical relationship between water depth at grounded glacier termini and calving rate has been demonstrated (Brown et al., 1982), but this relationship is purely empirical and possibly applicable only to calving margins near steady-state. Sea ice, floating brash ice, and iceberg debris can exert substantial restraining forces (or back stresses) that are transmitted to the fjord walls and inhibit calving (Amundson et al., 2010). The presence or absence of a moraine shoal at the terminus providing resistive back stress against extension of ice in the direction of flow has a strong influence on calving rate (Meier and Post, 1987; Fischer and Powell, 1998; Nick et al., 2007). However, it is unclear whether the detachment of a glacier terminus from its terminal moraine is a cause or a consequence of thinning and retreat.

7.5.7. State of theory and modeling

A number of attempts have been made to formulate calving models, but there is still no universal theoretical framework that can explain the full suite of available observations. Using data from twelve Alaskan glaciers, Brown et al. (1982) proposed an empirical linear relationship between the calving rate and the water depth at the terminus. However, the correlation is not broadly applicable because there is no obvious physical control that can explain any depth dependency of the calving rate (Benn et al., 2007). A drawback to such empirical models is that they are often based on data from glaciers that are either in or near a steady-state (Van der Veen, 1996). Indeed, based on observations at Columbia Glacier in Alaska, Meier and Post (1987) suggested that a linear calving relationship might not be valid during periods of rapid advance or retreat. Various approaches to a mechanically based process model of calving have been pursued since the mid-1960s, based on several different lines of analysis. These include, most notably, an elastic bending beam model developed by Reeh (1968), analyses of crevasse penetration with and without water (Nye, 1957; Weertman, 1973), and analyses based on linear elastic fracture mechanics (Van der Veen, 1998a,b). Other observations and analyses include work by Holdsworth (1969) and Hughes (1992).

Based on observations from Columbia Glacier, Van der Veen (1996) proposed a flotation model, wherein the terminus of the glacier retreats to the position where the ice thickness exceeds the flotation thickness by some threshold value, H_0 . On Columbia Glacier, H_0 was determined to be about 50 m. Vieli et al. (2001) pointed out that for smaller glaciers (water depths below 150 m and flow velocities less than 200 m/y), frontal cliff heights do not usually exceed 50 m, so the height above flotation will be much less than was suggested for Columbia

Glacier. As a result, they proposed a modified flotation criterion, with the minimum height above flotation, H_0 , replaced by a fraction, q , of the flotation thickness at the terminus. Benn et al. (2007) noted that one significant weakness of flotation models is that they do not allow floating termini to form, thus limiting their use to certain types of calving margins. As a result, they proposed a new criterion based on a simple model of crevasse formation, in which the calving margin is located where crevasse depth is equal to the glacier surface height above sea level, and the determination of the calving rate is reduced to determining ice thickness, velocity distribution, and changes in thickness and velocity through time.

Hanson and Hooke (2000) treated calving as a multivariate problem, using water depth, longitudinal strain rate, and ice temperature as the primary factors controlling the calving rate. Nick and Oerlemans (2006) compared the water depth and flotation models using synthetic simplified glacier geometries and found the latter to be superior, but they failed to simulate a full cycle of glacier length variations when the glacier terminates in very deep water. Nick et al. (2007) elaborated on their model by including a simple sediment transport scheme in the ice flow model and concluded that sedimentation at the glacier front needs to be included for the glacier to advance into deepening water.

Most calving models presented to date are either wholly empirical or based on mechanics. Other englacial processes, including glacial hydraulics, have not been incorporated, although there is evidence that water flow along cracks may play an important role in the calving process (O'Neel and Pfeffer, 2007).

No validated, broadly applicable, and robust calving model exists at this point. The calving relationships and models proposed so far have been tailored and applied to specific glaciers and data sets, and the proposed models tend to require data that are not readily available on regional scales. Larger models, either focused glacier/ice sheet models or comprehensive coupled GCMs, tend to include calving only in an extremely simplistic fashion (e.g., specifying a fixed calving boundary location) or do not treat calving at all. Hence, there is a pressing need for robust calving formulations of intermediate complexity that are capable of being applied in a wide variety of settings and for regional-scale mass change predictions. There is also a need for the basic data required to constrain models based on such a formulation.

7.5.8. Requirements for improved predictions of calving fluxes

Because calving can deplete terrestrial ice reservoirs very rapidly, calving dynamics are a key element in understanding and predicting the mass balance and sea level rise contributions of all glaciers, ice caps, and ice sheets with calving margins. Knowledge of present-day calving rates is extremely limited owing to a lack of fundamental observations. Since changes in flow dynamics and calving are not controlled directly by externally observed variables (such as climate), robust predictions depend on an understanding of glacier physics that is still lacking and on observations that can be difficult to make. The most fundamental observations needed to better constrain potential calving losses are (i) more complete

observations of calving rate and marine-ending terminus changes, and (ii) radio echo sounding of ice thicknesses and basal topography to identify marine-grounded outlets and the marine-grounded fractions of glacier and ice cap areas. Without these measurements, the potential for dynamically forced calving losses cannot be constrained let alone predicted.

7.6. Projections of Arctic glacier changes

- Most attempts to simulate the response of Arctic glaciers to future climate change involve evaluation of the response of the surface mass balance to prescribed changes in climate (usually air temperature and precipitation); simulations generally do not include changes in glacier dynamics or mass loss by iceberg calving. Climate change can be imposed as either step changes from an initial state or as transient changes over some period of time derived from climate models.
- Projections for individual glaciers throughout the Arctic show substantial mass loss or even disappearance of smaller glaciers by the end of the 21st century in response to imposed temperature and precipitation scenarios.
- Very few studies have attempted to model the response of Arctic glaciers on larger scales. A new simulation of the surface mass balance of the global population of mountain glaciers and ice caps to 2100 uses a temperature index mass balance model driven by downscaled output from ten GCMs, all forced by the IPCC A1B emissions scenario. For Arctic glaciers, projected volume loss due to surface mass balance ranges between 0.051 to 0.136 m sea-level equivalent, or 13% to 36% of their current volume by 2100 depending on the choice of GCM. Most models suggest that the largest mass losses are from glaciers in Alaska and Arctic Canada.

7.6.1. Downscaling climate model projections

General circulation models (Solomon et al., 2007) driven by standardized IPCC emissions scenarios (B1, A2, A1B; see Chapter 3) generally predict that warming and precipitation increases in the Arctic beyond 2030 will be larger than the global mean (Chapman and Walsh, 2007; Kattsov et al., 2007). Only part of the projected increases in precipitation will lead to increases in snow accumulation because the fraction of precipitation falling as rain will increase with the projected air temperature increases.

Direct use of data from GCMs for glacier mass balance projections is not currently feasible, owing to the generally large biases in model data on regional scales. Individual glaciers are typically much smaller than climate model grid boxes, and often occupy complex terrain that is only coarsely resolved in the model's underlying topography. Mass balance modeling is particularly sensitive to biases and offsets in air temperature, which controls the energy available for melt and the snow-rain ratio of precipitation (and thus controls both ablation and accumulation). Hence, some form of downscaling is required to transfer global-scale climate information to local glacier scales prior to making glacier mass balance projections.

Statistical downscaling is often used, whereby statistical relationships are established between meteorological

quantities determined at the GCM and the local scales. This can be done using either field observations or other suitable meteorological data such as data from climate re-analyses. Radić and Hock (2006) applied ‘local scaling’ to correct for the biases in climate model air temperature and precipitation for projecting the mass balance of Storglaciären until 2100. Downscaled temperature series were produced from GCMs and regional climate models (RCMs) by shifting the series by the averaged monthly differences between climate model and local-scale data (here ERA-40 re-analysis data) over a baseline period for which both GCM and local-scale data were available. Hence, the average seasonal cycle from ERA-40 was used as a reference by which seasonal cycles from the climate model could be ‘corrected’. The results highlight the importance of including seasonally varying biases in the downscaling instead of assuming a constant bias throughout the year. Precipitation was scaled by the ratio of precipitation in the reference data set (here ERA-40) summed over the baseline period and the corresponding climate model precipitation sum. A drawback of statistical downscaling is the inherent assumption that the statistical relationships established over a baseline period will continue to hold in future climates.

An alternative approach to statistical downscaling is to use changes in GCM variables between a defined time slice in a GCM simulation of future climate and a baseline period corresponding to a period for which local climate data are available. These changes are then used to perturb the observed local climate data to drive a mass balance model and project future mass balance changes (e.g., Schneeberger et al., 2003). The changes in climate variables are often simply linearly interpolated between time slices to allow for transient simulations. Due to generally large interannual variability, however, projected climate variable changes can be sensitive to the choice of baseline period. This is especially true when large fluctuations occur around the baseline period or when the climate variable shows a trend during this period (Aðalgeirsdóttir et al., 2006).

Zhang et al. (2007a) used a dynamical downscaling approach, employing the high resolution regional model Polar MM5 driven by global atmospheric re-analysis to obtain temperature and precipitation data on a 10-km resolution grid to force a glacier mass balance model. The results of mass balance simulations using dynamically downscaled data and simulations based on observed temperature and precipitation data were in reasonably good agreement when calibration was used to minimize systematic biases in the MM5 downscaling.

7.6.2. Modeling mountain glacier and ice cap mass balance in the 21st century

While numerous studies have projected the response of individual glaciers to climate change, very few studies have attempted to project the response of Arctic glaciers on a regional scale. Zhang et al. (2007b) used dynamically downscaled daily maximum and minimum air temperatures and precipitation driven by the IPCC A1B emissions scenario of the CCSM3 climate model to force a temperature-index mass balance model for Hubbard Glacier (2460 km²) and Bering Glacier (3630 km²) in Alaska for the period 2010 to 2100. Both glaciers are projected to have increased accumulation, particularly

on the upper reaches of the glaciers, and increased ablation, particularly on the lower parts. The modeled mass balance of Bering Glacier is projected to become more negative on average (−2.0 m w.e./y compared to −1.3 m w.e./y during the 1994 to 2004 baseline period) and the modeled mass balance of Hubbard Glacier, which was positive during the baseline period, is projected to decrease slightly (to 0.3 m w.e./y from 0.4 m w.e./y).

Hock et al. (2007a) modeled cumulative mass balance changes of the 3 km² Storglaciären in Sweden until 2100 in response to model-projected regional temperature changes. They predicted total changes ranging from −81 to −121 m w.e., depending on the choice of the mass balance model. A fully distributed energy balance melt model produced a greater mass balance response than simpler temperature-index models. Projections based on the IPCC B2 emissions scenario showed a 50% to 90% decrease in ice volume by 2100 (Radić and Hock, 2006) (Figure 7.21). The volume change projections vary by 40% of the initial ice volume for six different GCM inputs to the mass balance model, and by 10% depending on the details of the mass balance model used. This is in agreement with the conclusion of Oerlemans et al. (2005) that the uncertainties due to a simple representation of glacier processes are less than those associated with the output from GCMs.

Huss et al. (2008) modeled the complete disappearance of the 4.4 km² Laika Glacier in Arctic Canada by 2100 in response to temperature and precipitation trends derived from a climate model forced by the IPCC A1B emissions scenario. Bassford et al. (2006) modeled complete wastage of Pioneer Ice Cap (~200 km²) and Vavilov Ice Cap (~1770 km²) on Severnaya Zemlya within about 370 and about 1080 years, respectively, by imposing a linear change in temperature and precipitation over the period 1990 to 2100 based on the IPCC IS92a ‘business-as-usual’ scenario, after which the climate was held constant. Although these ice caps have quite low static sensitivities of mass balance to changes in temperature and precipitation, they are nonetheless highly sensitive to long-term climate change owing to their hypsometry and location on relatively flat beds close to sea level.

Ananicheva and Krenke (2007) modeled mass changes of 17 glacier regions in northeastern Siberia and Kamchatka (1040 km²) for the period 2040 to 2069 using climate projections from the ECHAM4 GCM driven by the IPCC A2 emissions scenario. The equilibrium-line altitude (ELA) on these glaciers is predicted to rise by 230 m in the northern parts and 500 m in the southern parts of northeastern Siberia. The upward shift is largest in Kamchatka. Based on known correlations between the ELA and the elevation of the glacier terminus, only 22% and 31% of the glacier areas are predicted to remain in northeastern Siberia and Kamchatka, respectively, in 2070 (Ananichava et al., 2010).

On larger regional or global scales, mass changes have been projected using either an ‘indirect’ approach based on mass balance sensitivity, defined as the change in mass balance caused by an instantaneous change in a climatic variable such as air temperature or precipitation, or a ‘direct’ approach based on transient mass balance modeling. The indirect approach involves computation of sensitivities, often for each month individually (‘seasonal sensitivity characteristic’; Oerlemans and Reichert, 2000), which are used to calculate the change in




Figure 7.21. Volume projections for Storglaciären, Sweden, in the 21st century derived from six general circulation models (GCMs). Source: Radić and Hock (2006).

surface mass balance for given anomalies of temperature and precipitation. Mass balance sensitivities are determined for individual glaciers by energy balance or temperature-index modeling. Mass balance sensitivities to temperature computed on a 1° by 1° grid exhibit large spatial variations across the Arctic, with the largest sensitivities in Iceland, southern Greenland, and coastal Alaska, and the smallest sensitivities in Arctic Canada and northern Greenland (Hock et al., 2009; Figure 7.22).

Applying a regression-based temperature index model to 42 glaciers located north of 60° N, de Woul and Hock (2005) found that the mass balance sensitivity to a hypothetical temperature increase of $+1$ K ranged from -0.2 to -2.0 m/y. Sensitivity of the mass balance to a 10% increase in precipitation ranged from $< +0.1$ to $+0.4$ m/y. This offset the effect of a $+1$ K temperature increase by about 20% on average. Maritime glaciers had considerably higher mass balance sensitivities

than continental glaciers. Results were extrapolated to the entire Arctic by assuming area-weighted means of sensitivity to be representative for different Arctic regions. The estimated total contribution to sea level from Arctic glaciers (including the Greenland Ice Sheet) in response to a $+1$ K warming was about $+0.6$ mm/y. This compares to an estimate of $+0.53$ mm/y derived using a sensitivity approach that suggested about equal contributions from the Greenland Ice Sheet and the Arctic glaciers (Oerlemans et al., 2005).

Radić and Hock (2011) computed global mass balance and volume changes for more than 120 000 mountain glaciers and roughly 2600 ice caps around the world until 2100 using an elevation-dependent temperature-index mass balance model driven by output from ten GCMs forced by the IPCC A1B emissions scenario. Future volume changes were up-scaled to all glaciers using a regionally differentiated approach. For the Arctic glaciers (including those in Greenland surrounding the ice sheet), the projected volume loss due to melt (ablation by calving is not included) ranges from 51 to 136 mm sea-level equivalent (SLE) (i.e., 13% to 36% reduction in their current volume by 2100) depending on the choice of GCM (Figure 7.23). The multi-model mean is 88 ± 28 mm SLE, or $22\% \pm 7\%$ volume reduction where the uncertainty range is ± 1 standard deviation. Multi-model mean volume reductions by 2100 (relative to initial volumes) vary considerably among regions, with the smallest values in Greenland ($8\% \pm 5\%$) and the largest values in Svalbard ($54\% \pm 15\%$); however, the spread among models for most regions is large (Figure 7.23). Most models show the largest sea level contributions coming from the Canadian Arctic and Alaska (including the Yukon), followed by the Russian Arctic and Svalbard. Contributions from Arctic Canada show a very large range from less than 10 mm SLE contribution to the largest projected contribution for any of seven Arctic regions, indicating a large spread in the projected temperature and precipitation fields among the GCMs for this region (Figure 7.24).

7.6.3. Modeling ice dynamics and ice extent

Glacier size and geometry will change as a glacier responds to climate change. Hence, projections of glacier mass balance on timescales longer than a few decades need to take into account feedbacks between the mass balance and the changing glacier surface elevation.




Figure 7.22. Modeled mass balance sensitivity, that is, the change in specific mass balance owing to a 1 K uniform warming. Source: Hock et al. (2009).




Figure 7.23. Projected volume and corresponding sea level equivalent of the volume change for 2001 to 2100 of all mountain glaciers and ice caps for seven regions and the entire Arctic derived from temperature and precipitation scenarios from ten general circulation models (GCMs). Source: data from Radić and Hock (2011). Note that mass loss by calving is not included and the ice sheet in Greenland is not considered in the Greenland estimate.

Ice flow models have been used to simulate area and thickness changes of individual glaciers (e.g., Schneeberger et al., 2003; Aðalgeirsdóttir et al., 2006). However, the detailed input data required to run such models are often not available. As a result, the effects of area changes are either simply neglected (e.g., Oerlemans et al., 2005; Zhang et al., 2007b) or approximated by scaling methods based on a functional relationship between glacier volume and glacier area (e.g., Radić and Hock, 2006). The total glacier volume is adjusted annually according to the volume changes computed from a climate-driven mass balance model. Annual area changes are then computed by inverting the volume-area relationship. Based on modeling of eleven glaciers, Schneeberger et al. (2003) showed that volume loss is overestimated by about 20% in a 100-year simulation if changes in glacier geometry are not included in the projections.

Detailed ice dynamic modeling is currently not possible on

a regional scale due to a lack of the required data to run models for the vast majority of glaciers. Raper et al. (2000) developed a geometrical approach, in which the width, thickness, and length of a glacier are reduced as its volume and area decline. When applied statistically to the global population of glaciers and individually to ice caps, this approach shows that the reduction in glacier area strongly reduces ablation during the 21st century (Raper and Braithwaite, 2006). The reduction is about 45% under the IPCC A1B emissions scenario using output from two different GCMs.

A large number of glaciers in the Arctic terminate in the ocean and, therefore, lose mass through iceberg calving in addition to surface melting. Studies on a few Arctic marine-terminating ice caps (Dowdeswell et al., 2002, 2008; Burgess et al., 2005; Mair et al., 2009) indicate that calving may account for roughly 30% to 40% of total mass loss. However, model-




Figure 7.24. Projections of fractional volume change and sea-level equivalent of the volume change by 2100 for seven regions that include all Arctic glaciers. Projections are based on temperature and precipitation modeled by ten general circulation models (GCMs). Source: Radić and Hock (2011).

based projections on regional scales neglect this effect. The current state-of-the-art in modeling does not allow meaningful projections of calving losses. However, calving rates are likely to increase as surface melting increases (Oerlemans et al., 2005).

7.7. Impacts of changes in mountain glaciers and ice caps

- The recent acceleration of mass loss from mountain glaciers and ice caps in the Arctic is such that, together with the Greenland Ice Sheet, they are likely to account for more than 60% of the current glacier wastage contribution to global sea level rise.
- Glacier wastage is likely to increase inputs of freshwater, sediment, and some nutrients to Arctic coastal waters, with potential impacts on water mass circulation, biological productivity, and ecosystem structure in affected fjord and nearshore marine environments.
- Retreat of tidewater glaciers onto land may be removing important feeding habitats that exist for seabirds and marine mammals in regions of upwelling in front of tidewater glacier termini and reducing the occurrence of grounded bergy bits that are used by seals for resting.
- Icebergs are a hazard to shipping and offshore platforms in the Arctic. The number and size distribution of bergs produced may change as tidewater glaciers retreat (e.g., more large bergs if floating ice tongues and ice shelves break up; more smaller bergs if calving from fast-flowing outlets increases). The way they circulate in Arctic waters is likely to change if sea-ice cover continues to decrease and surface water temperatures rise as a result. Bergs may become more mobile in summer as the restraining effect of sea ice declines, but disintegrate more rapidly in warmer surface waters.
- As climate warms, glacier runoff initially tends to increase due to higher melt rates, but ultimately declines as glacier

area shrinks. In most regions of the Arctic, the phase of declining runoff does not yet seem to have begun, but it may begin soon in the Russian Arctic mountains.

- Changes in glacier runoff will ultimately impact the viability of hydroelectric power operations in the Arctic. They will also be associated with changes in stream temperature, sediment load, and nutrient content that will initiate changes in the ecology of downstream river and lake environments.
- As rates of mass loss increase, ‘legacy pollutants’ stored in firn and glacier ice will be released back into the environment.
- As glaciers retreat, there are likely to be changes in the magnitude and frequency of a range of geomorphological hazards, including mass movements from deglaciated valley walls and outburst floods from ice-marginal and proglacial (moraine-dammed) lakes.

7.7.1. Impacts on sea level

In the most recent decade for which mass balance data were available for all regions (1996 to 2006), Dyurgerov and Meier (2005) reported that Arctic glaciers collectively lost mass at a rate of 165 Gt/y (0.45 mm/y sea-level equivalent; SLE). The dataset compiled by Cogley (2009a) yields a loss rate of 180 Gt/y (0.5 mm/y SLE) for the decade 1995 to 2005, and a loss rate of as much as 282 Gt/y (0.75 mm/y SLE) for the 2000 to 2005 pentad (see Section 7.9 for a more extended discussion). For comparison, Rignot et al. (2008) calculated a mass loss from Greenland of 267 Gt/y (0.71 mm/y SLE) for 2007. These results suggest that, together, Arctic glaciers and the Greenland Ice Sheet may account for more than 60% of the current glacier wastage contribution to global sea level rise (2.1 mm/y; Cazenave et al., 2009).

The acceleration of mass loss from Arctic glaciers and ice caps for the period 1985 to 2003 calculated using data from Dyurgerov and Meier (2005) is $-7.3 \text{ km}^3/\text{y}^2$ ice equivalent, or 6.5 Gt/y^2 (0.02 mm/y² SLE) (Figure 7.25). Note that at this rate




Figure 7.25. Rate of volume loss from Arctic glaciers and ice caps, derived from Dyurgerov and Meier, (2005). Source: AMAP.

of acceleration the estimated reservoir of mountain glacier and ice cap sea-level equivalent of 0.41 m (Radić and Hock, 2010) is being drawn down by only about 0.2% per year. While the current trend cannot be reliably extrapolated any significant distance into the future, depleting the reservoir is unlikely to result in a decline in annual total balance for at least the next several decades.

Analysis of the Cogley (2009a) dataset yields an estimate of mass losses from the glaciers surrounding the Greenland Ice Sheet of about 35 to 45 Gt/y for the 2000 to 2005 pentad. Some methods used to assess the mass balance of the Greenland Ice Sheet, such as most GRACE gravimetric observations, account for these losses, while other methods, such as satellite altimetric and mass flux observations, do not. It is therefore important, when combining mass loss estimates from this chapter with those in Chapter 8 on the Greenland Ice Sheet, to identify which glaciers are included in each particular method to avoid double counting.

7.7.2. Impacts on the marine environment

7.7.2.1. Freshwater and associated chemical fluxes

Glacier runoff is projected to increase in many parts of the Arctic for a period of decades or longer before declining (see also Section 7.7.3). This increased freshwater flux will influence conditions in coastal and marine waters. In fjords, freshwater discharge in summer produces a stable surface layer with low salinity (e.g., Svendsen et al., 2002), an effect that would be intensified with accelerated glacier melt. In the Gulf of Alaska, the majority (78%) of freshwater discharge occurs via a large number of smaller rivers and streams rather than a small number of point sources (Neal et al., 2010), producing baroclinic transport along the coast that is modified by wind stress (Royer, 1982). This along-coast transport is a major source of freshwater to the Bering Sea shelf and the Arctic Ocean (Weingartner et al., 2005). Runoff from glaciers and icefields contributes about half of the freshwater discharge to the Gulf of Alaska, with 10% currently from wastage (Neal et

al., 2010). Because the magnitude of baroclinic transport varies with freshwater flux, future changes in glacier runoff volume and timing will have significant implications for the strength of the Alaska Coastal Current, associated marine ecosystems, and economically valuable fisheries.

In addition to changes in freshwater flux, changes in material export may influence coastal and marine ecosystems. Hood and Scott (2008) monitored three streams in southeastern Alaska and found that decreasing glacier cover was associated with decreased phosphorus export and increased export of nitrogen and dissolved organic matter, although with a decrease in the more labile forms of organic matter. Nitrogen export increases in the early stages of vegetation succession on deglaciated forelands due to the establishment of nitrogen-fixing species such as alder, but is likely to decrease with the later establishment of other species such as conifers.

Increased glacier melt may be associated with increased sediment loads, which would increase turbidity in coastal waters. Increased turbidity would reduce the penetration of solar radiation, including harmful UV-B radiation, with implications for primary production and ecosystem functioning (Hanelt et al., 2001; Erga et al., 2005).

7.7.2.2. Seabird and marine mammal habitat

Tidewater glacier fronts are known to be ‘hot spots’ for seabirds and marine mammals in many Arctic areas. In Svalbard, a strong preference for these habitats has been identified for ringed seals (*Phoca hispida*) and beluga (*Delphinapterus leucas*) during summer and autumn (Lydersen et al., 2001; Freitas et al., 2008). Individuals of both species spend significant amounts of their time in proximity to tidewater glacier fronts, and their diving behavior in these areas suggests that they are feeding in these locations, which are known to be areas of high productivity. Enhanced production in these areas is probably due to freshwater outflows that drive upwelling of deep water close to glacier fronts, bringing nutrients to the surface and stimulating phytoplankton blooms and zooplankton growth. In addition, the cold-water outflows from the glaciers may stun or kill invertebrates, thus attracting predators such as polar cod (*Boreogadus saida*) and capelin (*Mallotus villosus*) that are an important part of the diet of beluga and ringed seal (Dahl et al., 2000; Labansen et al., 2007), as well as a variety of seabirds and other marine mammals. In addition, ringed seals, bearded seals (*Erignathus barbatus*), and other pinnipeds use bergy bits as resting platforms. Retreat of tidewater glacier fronts onto land would decrease the availability of this preferred habitat at a time when decreases in late summer sea-ice extent are making the other preferred summer feeding habitats of Arctic pinnipeds less available. In addition, changes during glacier retreat in the lability of organic matter and the amount and types of nutrients that are delivered from land to the marine environment in meltwater runoff may reduce the productivity of these environments and their attractiveness to marine mammals and seabirds.

7.7.2.3. Iceberg production and drift

In some Arctic and sub-Arctic offshore areas, icebergs present a significant danger for marine operations including shipping

and commercial fisheries, geological exploration surveys, and production of hydrocarbons from sea surface structures such as oil rigs (Figure 7.26). The Grand Banks of Newfoundland, the Labrador Sea, offshore of West Greenland, Davis Strait, and the Barents Sea are typical examples of such areas. Damage to or even destruction of a stationary platform or its communication lines by an iceberg will result in enormous economic losses and possibly significant environmental damage. Both iceberg plan form and keel depth are important quantities to measure in this context (Woodworth-Lynas et al., 1991). Non-stationary platforms and other floating structures (e.g., floating production, storage, and offloading systems), capable of leaving their operation localities, will limit economic losses owing to interruption of hydrocarbon production for the period of shutdown due to iceberg threat.

The general direction of the drift of icebergs near the Labrador coast and the Grand Banks of Newfoundland coincides with the direction of a strong Labrador Current. Iceberg trajectories and the most dangerous drift directions are known. Over the past few decades, Canada has gained significant experience in minimizing iceberg threats and has introduced a complex system of operational practices known as the Iceberg Management System.

Currents in the Barents Sea carry icebergs from the north to the southwest (Johannessen et al., 1999; Dmitriev and Nesterov, 2007). Some may enter the central and southern regions of the area, threatening navigation and operations in the *Shtokman* gas-condensate field. An analysis of atmospheric conditions at the time of the southernmost spreading of icebergs (e.g., 1881, 1929, 1989, and 2003) has revealed that all cases were characterized by prolonged periods (three to five months) of winds from the north (Buzin et al., 2008). Under such conditions, large numbers of icebergs concentrated near Spitsbergen and Franz Josef Land (their source) are exported southward. In some years (1989, 2003), icebergs reached the *Shtokman* gas-condensate field area and in particularly extreme cases (1881, 1929) reached the coast of northern Norway

and the Kola Peninsula. Sightings of an anomalously large concentration of icebergs and bergy bits (around 100 pieces) in the *Shtokman* gas-condensate field area in May 2003 (Naumov et al., 2003) significantly influenced the design concept for the production complex. The boundary of iceberg drift in the Barents Sea has been displaced to the south over the past 60 years (Zubakin et al., 2006; Buzin et al., 2008), probably related to climate warming and a corresponding increase in the production of icebergs (Figure 7.27). The tendency for the ice edge in the Barents Sea to be displaced toward the north in summer during the past 10 to 15 years (Divine and Dick, 2006) may result in earlier and easier release of icebergs stuck in the straits of Franz Josef Land. Consequently, a larger number of icebergs may be in free drift and represent a threat to shipping and platforms. However, the life expectancy of the icebergs also may be reduced in a warmer climate (Weeks and Campbell, 1973).

The iceberg discharge from the Greenland Ice Sheet is known to have increased by more than 40% from 1995 to 2005 (Rignot and Kanagaratnam, 2006). This has not, however, increased iceberg numbers on the Grand Banks or in the Labrador Sea. The number of icebergs reaching the Grand Banks has actually decreased, probably owing to increased surface water temperatures in the region and decreased ice cover (which protects icebergs from the dynamic impact of ocean waves) (McClintock et al., 2007). However, potential iceberg damage to sea-floor engineering structures is a function of iceberg keel depth as well as iceberg number. Icebergs with keel depths greater than 500 m have been observed in the Scoresby Sund fjord system of East Greenland, but few other systematic measurements of the keel depth of Arctic icebergs exist (Dowdeswell et al., 1992). The occurrence of recent plow marks on the sea floor, produced where drifting icebergs go aground, is evidence of this natural hazard, although many plow marks on Arctic continental shelves are not produced by modern icebergs (Dowdeswell et al., 1993; Syvitski et al., 2001).



Figure 7.26. Large iceberg (100 m length, 30 m width, and 15 m height above sea surface) drifting in the Barents Sea to the southwest of Franz Josef Land on 30 May 2009. Source: Andrey Masanov, Arctic and Antarctic Research Institute, Russian Federation.




Figure 7.27. Multiyear variability of the southern limit of icebergs in the Barents Sea for the period 1928 to 2008. Source: Buzin et al. (2008).

7.7.3. Impacts on water resources

7.7.3.1. Glacier runoff

Streamflow in glacier-fed streams tends to peak later in the summer and to continue to exhibit diurnal fluctuations later in the melt season than streamflow in nival (snowmelt-dominated) streams (Church, 1974). However, the contrast between nival and proglacial regimes can be obscured by the weather patterns dominating the particular melt season, particularly when melt begins later than normal (Marsh and Woo, 1981). Research in temperate areas and in the Arctic indicates that detectable glacier melt contributions to streamflow occur in catchments with more than about 5% glacier cover, while contributions to summer flow are detectable even in catchments with as little as 2% glacier cover (e.g., Marsh and Woo, 1981; Stahl and Moore, 2006). Based on these criteria, glaciers are an important water resource throughout much of the Arctic.

Over annual or longer timescales, the influence of glaciers on streamflow can be assessed through the catchment water balance, which can be expressed as follows:

$$[1] \quad Q = P - E - f_g B + GW_{net} - \Delta S$$

where Q is streamflow, P is precipitation, E is evapotranspiration (including sublimation), f_g is the fractional glacier area within the catchment, B is the net mass balance for the glaciers, GW_{net} is the net flux of groundwater across the catchment boundaries, and ΔS represents changes in storage of seasonal snow, subsurface water, and surface water. All terms in [1] are typically expressed as a depth of water averaged over the catchment area. Negative net mass balance (glacier loss) augments streamflow relative to a basin lacking glacier cover. This contribution to streamflow ($f_g B$) is commonly referred to as ‘wastage runoff’.

Table 7.3 highlights the contributions of glacier wastage (negative mass balance) to mean annual streamflow over recent decades, based on published water balance calculations and hydrological modeling. The significance of glacier melt contributions to streamflow tends to be greater than average in years with low precipitation and warm summers. At De Geerdalen, Svalbard, for example, glacier wastage contributed up to 20% of annual runoff, roughly double the average, in a year when annual precipitation was 40% below average (Killingtveit et al., 2003).

Assuming no further climate change, glaciers currently experiencing negative mass balance would recede until they

achieved a hypsometry for which $B = 0$, as long as the ELA is below the top of the glacier. If the ELA lies above the maximum elevation of the glacier, the glacier would ultimately disappear. Under this assumption of constant climate, average annual runoff would ultimately decrease by an amount equal to the current contribution due to glacier wastage. Decreases in runoff would be particularly severe in years with low precipitation. Flowers et al. (2005) simulated the future evolution of Vatnajökull, Iceland, assuming a continuation of the 1961 to 1990 climatology, and found that glacier runoff would decrease by about 20% after 200 years.

Climatic warming will result in a longer melt period and more intense melt, particularly as firn cover is depleted, exposing lower-albedo glacier ice to solar radiation. As a consequence, glacier runoff will increase with the onset of a warming trend. However, increased melt is accompanied by glacier thinning and retreat, and at some point the decrease in glacier area will cause glacier runoff to decrease. While this conceptual model is widely recognized (e.g., Jansson et al., 2005; Moore et al., 2009), the timescales associated with the transition from increasing to decreasing flow are uncertain. Available studies focused on southern Alaska, northeastern British Columbia, and southwestern Yukon have reported positive trends in streamflow for glacier-fed rivers, suggesting that the glaciers in those regions are still in the initial phase of their response to warming (Fleming and Clarke, 2003; Brabets and Walvoord, 2009).

Runoff from glaciers in the temperate and sub-Arctic regions of Russia was calculated from the USSR Glacier Inventory for the period 1966 to 1980 based on the assumption that glacier systems are in equilibrium with climate. The total glacier runoff over the period 1966 to 1980 was estimated to be no more than 3 Gt (Ananicheva and Krenke, 2007). To project future changes in glacier runoff in Russia, the morphology and regime of glacier systems were adjusted on the basis of predicted changes in ELA under a climate-warming scenario derived from the ECHAM4 GCM driven by the IPCC A2 emissions scenario. Despite a significant reduction of the glacierized area, the glacier runoff from southeastern Siberia and the Sredinny Range (Kamchatka) was predicted to increase through the 21st century owing to increased ablation. Glaciers in the Kronotsky Range (Kamchatka) were predicted to almost disappear, resulting in a sharp reduction in glacier-melt runoff (Ananicheva and Krenke, 2007).

Transient responses of glacier geometry and runoff to climate warming have been simulated for Hofsjökull and

Table 7.3. Runoff contributions associated with glacier wastage.

Catchment	Location	Period	Catchment area, km ²	Glacier coverage, %	Wastage contribution to streamflow, %	Q , kg/m ²	Source
Zackenberg	Northeast Greenland	1997 – 2005	512	20	63	428	Mernild et al., 2008a
Mittivakkat	Ammassalik Island, Greenland	1993 – 2004	14.2	78	23	1970	Mernild et al., 2008b
Bayelva	Svalbard	1990 – 2001	30.9	55	23	1050	Killingtveit et al., 2003
De Geerdalen	Svalbard	1990 – 2001	34.4	17	9	539	Killingtveit et al., 2003
Endalen	Svalbard	1990 – 2001	28.8	20	19	545	Killingtveit et al., 2003

Vatnajökull, Iceland (Flowers et al., 2005; Aðalgeirsdóttir et al., 2006), and the results are consistent with the conceptual model presented above. Figure 7.28 illustrates that, as the rate of warming increases, the interval with maximum glacier runoff for Hofsjökull moves forward in time and the increase in runoff is greater. For simulations involving a warming-related increase in precipitation, the effect is to increase the magnitude of runoff increase and delay the timing of peak runoff. Flowers et al. (2005) also reported that changes in the surface topography of the ice cap would cause shifts in the hydrological divides, effectively redistributing outflow among the outlet glaciers.

Climate warming and glacier response will modify seasonal patterns of runoff in addition to changing annual totals. Jónsdóttir (2008) simulated runoff in Iceland for climate projections based on the IPCC A2 and B2 emissions scenarios and projections of glacier geometry using a dynamic glacier model (Aðalgeirsdóttir et al., 2006; Jóhannesson et al., 2006). For the period 2071 to 2100, glacier-melt contributions to streamflow are projected to increase in all seasons, while runoff from unglacierized areas increases from October to April and decreases from May to September, jointly producing a significant shift in the seasonal pattern of runoff in partially glacier-fed catchments.

The highest peak flows in proglacial streams are often associated with outburst floods (Ng et al., 2007), in which water stored on, under, or within the glacier is released suddenly, for example, by the rapid growth of a meltwater channel (e.g., Mernild et al., 2008a). There is some evidence that subglacially derived outburst events are more extreme in warmer summers when there is greater meltwater generation (Skidmore and Sharp, 1999), suggesting that flood risk in glacier-fed Arctic catchments may increase as a result of climate warming. When outburst floods are derived from ice-dammed marginal lakes, thinning of the ice dams due to increased melting may result in floods that occur earlier in the melt season and are smaller and more frequent than they are at present. Lakes will fill sooner and more rapidly than in the past and the accumulated lake water may breach the ice dam more easily than before. Earlier onset of lake drainage may allow multiple filling/drainage cycles during a melt season, especially because melt seasons will be longer in a warmer climate.

7.7.3.2. Water quality

Climate warming will influence proglacial water quality as well as streamflow. Increasing meltwater runoff in the initial phases of warming should tend to moderate diurnal increases in stream temperature. However, as glaciers retreat, the length of stream exposed to solar radiation and other heat inputs will increase, potentially counteracting the effect of increased flow. In addition, the emergence of proglacial lakes can increase warming. Milner et al. (2008) found that maximum stream temperatures at Wolf Point Creek, which drains into Glacier Bay, Alaska, were 2 °C in 1977, roughly 30 years after the creek emerged due to glacier retreat. From 1996 onward, maximum temperatures have consistently exceeded 15 °C, at least in part due to the increase in size of the upstream lake, which initially formed in the 1970s. Once glaciers reach the stage of declining flow, there should be a trend to increasing stream temperature. At that point, the main factor mitigating this increase would be development of




Figure 7.28. Simulated variations in glacier runoff from Hofsjökull, Iceland, under four climate scenarios. Source: Aðalgeirsdóttir et al. (2006).

riparian forests where they do not currently exist, which would increase stream shading and enhance bank stability, resulting in a narrower, deeper stream. Both effects would tend to reduce stream warming, but would be relevant only in sub-Arctic and temperate areas such as the Gulf of Alaska.

Focusing on temperate regions, Moore et al. (2009) concluded that the onset of negative mass balance and glacier retreat would be likely to result in an initial increase in suspended sediment concentrations in proglacial streams, followed by a longer-term decrease. This long-term projection is consistent with studies that show that glacier-fed streams in the Arctic typically yield orders of magnitude more sediment than those without glacier contributions (e.g., Hasholt and Mernild, 2008). However, temporal changes in sediment concentration could vary substantially among basins due to site-specific factors, particularly the emergence of proglacial lakes, which trap sediment and thus reduce downstream transport (Hasholt et al., 2008). Future patterns of suspended sediment concentration would also be complicated in cases where glaciers shift from being cold-based or polythermal to temperate, as well as by thawing of permafrost, which could influence the erosion of stream channel beds and banks (McNamara and Kane, 2009).

Glacier retreat may be accompanied by changes in streamwater chemistry. Glacial forefields are subject to different weathering and nutrient cycling processes than those that dominate in subglacial environments, particularly as soils and vegetation develop (Anderson, 2007; Hood and Scott, 2008). Available studies, not all from Arctic areas, suggest that concentrations of nutrients and dissolved organic carbon should increase as glaciers retreat, although the forms of some nutrients and organic matter might change, possibly influencing their availability to aquatic organisms (Lafrenière and Sharp, 2005; Filippelli et al., 2006; Hood and Scott, 2008). In southeastern Alaska, decreasing basin glacier cover was found to be associated with higher concentrations of soluble reactive phosphorus and higher proportions of bioavailable (labile)

dissolved organic carbon (Hood and Berner, 2009; Hood et al., 2009). Fluvial transport of dissolved organic carbon could be influenced by changes in suspended sediment concentration, because high turbidity reduces photodegradation of dissolved organic carbon in streamwater.

7.7.3.3. Water resources and hydroelectric power generation

Most studies suggest that Arctic glaciers are currently in the initial phase of their response to warming, in which runoff increases, and that glacier runoff should continue to increase over the next few decades or so, providing an increase in water availability. However, some Russian results indicate that some areas (especially those where the glaciers are predominantly small) are likely to experience flow decreases over the next few decades as a result of glacier retreat (Ananicheva and Krenke, 2007). These contrasting behaviors could either reflect fundamental differences among glaciers in the timescale of response to warming, or suggest that glaciers are currently at different stages of their response. Further site-specific assessments are clearly warranted.

Glacier runoff is significant for hydroelectric power generation in the upper Yukon basin (at Whitehorse, Yukon, Canada), Iceland, Greenland, and in many river systems in Norway. A trend to increasing flows would also tend to increase the hydroelectric power resource. In Iceland, Jónsdóttir (2008) projected a substantial increase in hydroelectric power potential for the period 2071 to 2100, but a substantial decrease over the following century as the glaciers disappeared under the IPCC A2 and B2 emissions scenarios employed.

Reservoir operations could be influenced not only by the effects of changes in streamflow, but also by changes in sediment transport and stream temperature. Increased sediment transport would reduce the operational lifetime of a reservoir by infilling, while suspended sediment concentration and inflow temperature together would influence mixing processes and temperature profiles, in turn influencing habitat conditions for aquatic organisms as well as the temperature of water downstream.

7.7.3.4. Aquatic ecosystems

Glacier-fed rivers typically support a distinctive flora and fauna determined by physicochemical conditions, including the dominant influences of water temperature and channel stability (Milner and Petts, 1994; Milner et al., 2001). While bedload and suspended sediment transport typically peak during maximum glacial melt in summer (Østrem, 1975b), lower water levels during spring and autumn result in greater water clarity and channel stability, creating ‘windows of opportunity’ when algal and macroinvertebrate productivity is higher. Some of the largest runs of salmon in south-central Alaska occur in glacially influenced systems (Dorava and Milner, 2000) as glacial runoff enhances summer flow relative to rainfall- or snowmelt-dominated catchments, facilitating the migration of salmon from the ocean to their spawning grounds in tributary streams via the main channel corridor.

Since increases in glacial runoff will enhance summer flow and increase the duration of meltwater runoff, they will

probably also facilitate the migration of adult salmon to their spawning grounds. Increased glacial runoff will also increase the amount of available spawning habitat and would potentially enhance winter baseflow through recharge of groundwater during the summer (Smith et al., 2001; Brown et al., 2003). The survival of young salmonids during the winter is significantly correlated with the amount of winter discharge or winter groundwater inputs (Fleming, 2005). Any changes in water source contributions that enhance winter flow should be beneficial to salmonid populations and mitigate the effect of overwintering mortality on salmonids.

In the phase of declining glacier runoff, bedload and suspended sediment transport will potentially decrease in the long term as glacial and paraglacial erosion (erosion by non-glacial processes of previously deposited glacial and fluvioglacial sediments) decrease and the stream’s transport capacity decreases (Fleming and Clarke, 2005). In addition, newly formed proglacial lakes trap sediment, reducing sediment loads downstream. Fleming (2005) emphasized the potentially favorable effects of glaciers and lakes in combination on salmonid habitat: glaciers maintain late summer flow while lakes reduce sediment transport. Reduced bedload transport could allow streams to become more stable, and thus narrower and deeper. The projected reduction in suspended sediment load with ongoing glacier retreat should allow greater light penetration into the water column and increase algal productivity, particularly during certain periods of the year. The effect of increased light would be augmented by an increase in nutrient concentrations as vegetation and soils develop following glacier retreat. However, the effects of decreased turbidity on ecosystem productivity need to be considered in the context of possible decreases in late summer streamflow and increasing late summer water temperature.

There is clear evidence of a strong relationship between catchment glacierization and macroinvertebrate taxon richness in glacially influenced streams. In a stream fed by a receding glacier in southeastern Alaska, Milner et al. (2008) found that the benthic macroinvertebrate community supported only five taxa when 70% of the catchment was glacierized but 24 taxa after the glacier had disappeared two decades later. Füreder (2007) found similar trends in alpine streams with differing degrees of glacierization. This evidence suggests that changes in glacial runoff and fluvial sediment transport due to glacier shrinkage may cause an increase in the diversity of the benthic macroinvertebrate community. An increase in algal productivity will potentially enhance macroinvertebrate abundance. With a change in benthic community structure, dominant species traits will reflect a reduction in glacial contribution to flow. Macroinvertebrate body size will become larger and life cycles longer, with the benthic community dominated by habitat generalists with less omnivory and flattened forms (Ilg and Castella, 2006; Füreder, 2007). The fauna would also be less cold-adapted with reduced mobility of the adults. Enhanced abundance and increased body size will favor food availability for fish. Although an overall increase in taxonomic richness and abundance in benthic macroinvertebrate communities is predicted with decreased glacial inputs, some cold-specialist benthic species will be lost, including some endemic species. Some species will not adapt rapidly enough to survive

the anticipated rate of deglaciation in future decades (Hari et al., 2006).

The effect of shrinking glaciers on fish populations in glacially influenced rivers will depend upon whether the system is an alpine or a more lowland system. However, over time reduced glacial input into these rivers will reduce summer flow and may influence salmon migration upstream. Lower flow will also reduce the amount of habitat available adjacent to the main glacier-fed channel, including side channels and side sloughs. Side channels and sloughs are sustained by meltwaters of the main channel (Richardson and Milner, 2005). For many river systems in northerly regions, winter is a critical period when overwintering mortality for salmonids can be high if they are unable to migrate to suitable refugia, such as side channels. Water temperature is a critical variable influencing fish distribution and each species has an optimum range for different life stages. Matulla et al. (2007) predicted that the ranges of alpine stream salmonids (e.g., brown trout *Salmo trutta* and grayling *Thymallus thymallus*) would contract upstream due to changes in water temperature regimes under climate change scenarios in which the cold water input from glacial runoff decreases. Projected changes in water temperature in cold rivers can also favor non-indigenous species that have wider thermal tolerance and can out-compete indigenous taxa at higher water temperature (Ficke et al., 2007). In the Rocky Mountains, cutthroat trout (*Oncorhynchus clarkii*) have been displaced by non-indigenous brook trout (*Salvelinus fontinalis*) and brown trout that are more efficient at securing food resources at higher temperatures (Hauer et al., 1997). However, in streams that are currently colder than is optimal for salmonid growth, some degree of warming might increase salmonid production.

Large-scale glacial recession creates new habitat that can potentially be colonized by organisms including fish. The creation of new stream habitat due to glacial recession has been extensive along the coasts of southeastern and south-central Alaska due both to climate change and changing local environmental conditions (Milner et al., 2008). Although many of the recently formed streams are relatively short, the creation of new salmonid habitat is significant at a time when human activity threatens salmonid stocks in other parts of the Pacific Northwest region of North America (Nehlsen et al., 1991). Pink salmon (*Oncorhynchus gorbuscha*) can establish substantial populations from a small colonizing population of spawners within a few generations, and other species (including non-anadromous fish such as sticklebacks) colonize rapidly (Milner et al., 2008). As migrant salmon die soon after spawning, rotting of their carcasses results in a significant input of nutrients and organic matter to affected catchments, and this can promote productivity in other parts of the ecosystem.

7.7.3.5. Contaminant release from melting glaciers

Many contaminants originating from lower latitudes are carried to the Arctic by long-range atmospheric transport and stored in the firn and ice of glaciers and ice caps (Chapter 11, Section 11.3). These contaminants include sulfate and nitrate, which have increased the acidity of snow and ice above pre-industrial levels (Koerner and Fisher, 1982), metals such as lead (Zheng et al., 2003), persistent organic pollutants such as PCBs (polychlorinated biphenyls), DDT and other organochlorine

pesticides (Gregor and Gummer, 1989; Hermanson et al., 2005), as well as radionuclides associated with the Chernobyl reactor failure in 1986 and with nuclear testing dating back to 1961 to 1962 (Pinglot et al., 1999). Stored contaminants may be released back into the environment by glacier melt and the process can be accelerated if melt rates increase over time (Blais et al., 2001).

Contaminants stored in seasonal snow away from glaciers interact with soil and aquifer materials prior to their discharge to receiving waterbodies such as lakes and streams. During these interactions, a proportion of the contaminants (especially persistent organic pollutants) released via melting will be retained through sorption onto organic matter and cation exchange on clay particles in the soil. In contrast, glacier meltwater has much less interaction with organic matter and clays in soils before leaving the glacier, leading to less retention and higher rates of contaminant export to lakes and rivers downstream, as has been found in the Canadian Rockies (Blais et al., 2001; Lafrenière et al., 2006).

All the contaminants stored in glaciers would eventually be discharged in meltwater runoff regardless of climate change, but there would be significant lag times associated with the flow of ice from the accumulation to ablation zones. Climate warming accelerates melting of snow, firn, and ice, potentially releasing stored contaminants to receiving waters in a more concentrated pulse. However, thus far there has been no research in the Arctic directly addressing this impact.

7.7.4. Glacier ecosystems

Distinctive microbial ecosystems are found on and under glaciers (Hodson et al., 2008). On the glacier surface, the supraglacial ecosystem exists in the snowpack, supraglacial streams, melt pools, and cryoconites (water-filled holes on glacier surfaces that contain dust and microbial communities). It comprises a diverse array of bacteria, algae, fungi, viruses, rotifers, and tardigrades. *In situ* rates of primary production and respiration on glacier ice surfaces in summer are comparable to those encountered in soils in warmer and more nutrient-rich regions. Measurements of net production suggest that glacier ice surfaces may be largely autotrophic systems (Anesio et al., 2009), unlike most lakes and rivers, which tend to be heterotrophic systems.

At the glacier bed, a subglacial ecosystem is found in basal ice, subglacial sediments, meltwaters, and volcanic subglacial lakes (Gaidos et al., 2004, 2009; Hodson et al., 2008). It includes a mixture of aerobic and anaerobic (chemoautotrophic and heterotrophic) bacteria and probably also fungi and viruses (D'Elia et al., 2008). These microorganisms have metabolisms based on the oxidation of organic carbon, sulfide, sulfur, or hydrogen, and they use oxygen, nitrate, sulfate, iron(III), manganese(IV), or carbon as terminal electron acceptors. They play a critical role in subglacial chemical weathering (Tranter et al., 2002, 2005) and in controlling the biogeochemistry, nutrient loading, and properties of dissolved organic matter in glacial runoff (Hodson et al., 2008; Gaidos et al., 2009). They may also be involved in the production of greenhouse gases (carbon dioxide and methane), with possible feedbacks to the climate system if these gases are stored in basal ice or subglacial sediments and released to the atmosphere during deglaciation (Sharp et al., 1999; Skidmore et al., 2000; Wadham et al., 2008; Boyd et al., 2010).

The impact of climate change on these ecosystems is likely to be complicated as there will be a number of competing influences (Hodson et al., 2008). In the long term, changes in global glacier area will limit their geographical extent, and total deglaciation would be likely to eradicate these ecosystems completely. In the shorter term, increased surface melt would probably enhance supraglacial ecosystem productivity. As end-of-summer snowline elevations rise, the extent of supraglacial stream and meltwater habitats will increase at the expense of snowpack habitats. Higher ice melt rates may swamp these systems with water, continually redistributing them across the glacier surface. Increased melting of glacier ice may increase the rate of release of glacially entombed microorganisms into the supraglacial environment. This may increase the transfer of carbon, nutrients, and biota into downstream (subglacial and proglacial) aquatic environments. Increased water fluxes would be likely to increase the oxygenation of glacier beds in summer, favoring aerobic over anaerobic bacterial processes. They might also result in more rapid transit of meltwater through the subglacial ecosystem, especially as glaciers shrink, reducing the efficiency of utilization of supplies of nutrients and organic matter by subglacial microbial communities. Alternatively, increased delivery of carbon and nutrients could stimulate microbial activity, and create anoxic conditions at glacier beds in winter when surface water inputs cease.

Paradoxically, however, negative surface mass balances and glacier thinning have resulted in cooling and net freezing at the beds of some Arctic glaciers (Dowdeswell et al., 1995; Hodgkins et al., 1999; Glasser and Hambrey, 2001). Such changes would lead to isolation and cryostasis (the reversible cryopreservation of live organisms) of the subglacial ecosystem. Whether this might ultimately eliminate the subglacial ecosystem from individual glaciers or drive it deeper into unfrozen subglacial sediments is currently unknown. Elimination of the ecosystem would substantially alter the biogeochemistry of glacial runoff, with potential implications for downstream ecosystems (Hodson et al., 2004, 2005).

7.7.5. Geomorphological hazards

Glacier changes, particularly glacier retreat, can produce a range of hazards involving slope instability, increased proglacial fluvial sediment transport, and changes in water flow, particularly outburst floods. To augment the available research conducted in the Arctic, the review below draws heavily on work outside the Arctic. However, the general principles should apply throughout the Arctic region as broadly defined in this chapter.

7.7.5.1. Slope instability

Glacier down-wasting and retreat appear to be partly responsible for destabilizing adjacent terrain, leading to landslides, debris flows, rock avalanches and falls, and some catastrophic rock-slope failures in high mountains (Evans and Clague, 1994; Holm et al., 2004). Many marginally stable slopes that were buttressed by glacier ice during the Little Ice Age failed after they became deglaciated in the 20th century. A factor that has possibly contributed to such failures is steepening of rock slopes by cirque and valley glaciers during the Little Ice Age. These effects are most pronounced in mountain ranges with the largest ice cover; because it is there that ice losses in the

20th century have been greatest. An extreme example is Glacier Bay, which until the end of the 18th century was covered by glacier ice. Since then, Glacier Bay has become deglaciated, with the loss of over 1000 km² of ice in 200 years. The amount of ice lost is so great that the uplift of the land due to isostatic rebound is measurable (Larsen et al., 2005).

7.7.5.2. Outburst floods from moraine- and ice-dammed lakes

Lakes dammed by moraines and glaciers in high mountains have drained suddenly to produce floods orders of magnitude larger than normal nival or rainfall floods (Costa and Schuster, 1988; Clague and Evans, 1994). Lakes dammed by Neoglacial end and lateral moraines are susceptible to failure because they are steep-sided and consist of loose, poorly sorted sediment that in some cases is ice-rich (Clague and Evans, 2000). Irreversible rapid incision of a moraine dam may be caused by a large overflow triggered by an ice or snow avalanche or rockfall. Other failure mechanisms include earthquakes, slow melt of ice within the moraine, and slow removal of fine-grained sediment from the moraine by groundwater flow (piping). As climate warms, lakes impounded by glaciers may drain suddenly and unexpectedly following a long period of stability due to progressive wastage of the glacier dam and the formation of subglacial, supraglacial, or ice-marginal channels. Drainage may be initiated by hydrostatic lifting of that part of the base of the glacier facing the lake. Lakes may also form during glacier surges; they drain, often catastrophically, soon after they form.

Most outburst floods display an exponential increase in discharge, followed by a gradual or abrupt decrease to background levels as the water supply is exhausted (Clarke, 2003; Ng et al., 2007). Peak discharges are controlled by lake volume, dam height and width, the material properties of the dam, failure mechanism, and downstream topography and sediment availability. Floods from glacier-dammed lakes tend to have lower peak discharges than those from moraine-dammed lakes of similar size because enlargement of tunnels within ice is a slower process than overtopping and incision of sediment dams.

Floods resulting from failures of natural dams may transform into debris flows as they travel down steep valleys. Such flows can only form and be sustained on slopes greater than 10 to 15 degrees and only where there is an abundant supply of sediment in the valley below the dam. Entrainment of sediment and woody plant debris by floodwaters may cause peak discharge to increase down valley, which has important implications for hazard appraisal.

Outburst floods from lakes dammed by moraines and glaciers commonly alter river floodplains tens of kilometres from the flood source. The floodwaters erode, transport, and deposit huge amounts of sediment. They commonly broaden floodplains, destroy pre-flood channels, and create a new multi-channel, braided to anastomosing (channels that repeatedly branch and reconnect) plan form. The changes can persist for decades after the flood, although rivers quickly reestablish their pre-flood grades by incising the flood deposits.

Climate is an important determinant of the stability of moraine and glacier dams (O'Connor and Costa, 1993; Evans and Clague, 1994). Most moraine-dammed lakes formed

during the past century as glaciers retreated from bulky end moraines constructed during the Little Ice Age. The lake dams soon began to fail as climate warmed. With continued warming and glacier retreat, the supply of moraine-dammed lakes that are susceptible to failure will be exhausted, and the threat they pose will diminish. Glacier-dammed lakes have typically gone through a period of cyclic or sporadic outburst activity, lasting up to several decades, since climate began to warm in the late 19th century. The outburst floods from any one lake ended when the glacier dam weakened to the point that it could no longer trap water behind it. However, with continued glacier retreat, the locus of outburst activity may, in some cases, shift up-glacier to sites where new lakes develop in areas that are becoming deglaciated. Landslide damming is less clearly linked to climate.

7.7.5.3. Erosion and sedimentation

Fluctuations of glacier margins on timescales of decades and centuries can remobilize glacial sediment. During glacier advance, initial incision due to increased competence of meltwater streams is quickly followed by deposition as sediment supply increases (Maizels, 1979). Sediment stored within and beneath glaciers is delivered at an increasing rate to fluvial systems as glaciers advance (Karlén, 1976; Maizels, 1979; Leonard, 1986, 1997; Karlén and Matthews, 1992; Lamoureux, 2000). Similarly, subglacial erosion increases during glacier advance, and meltwater may carry more sediment into river valleys than at times when glaciers are more restricted. Sediment delivery to streams in the Coast Mountains of British Columbia, for example, increased during the Little Ice Age, and the streams responded by filling in their channels and braiding over distances up to tens of kilometres down valley from glaciers (Church, 1983; Gottesfeld and Johnson-Gottesfeld, 1990). Glacier retreat typically exposes large areas of unstable, unvegetated sediment that is easily entrained by meltwater (Church, 1983; Desloges and Church, 1987; Gottesfeld and Johnson-Gottesfeld, 1990; Brooks, 1994; Ashmore and Church 2001; Clague et al., 2003).

7.7.5.4. Glacier-volcano interactions and related hazards

Glaciers are found in regions of active volcanism in Alaska, Iceland, and Kamchatka, where high seismic and volcanic activity can generate significant glacier-related hazards. Consequences of volcanic activity include glacier burial by ash falls, melt-induced formation of craters and lakes on glaciers, significant mass loss by subglacial melting during subglacial eruptions, and accelerated glacier flow. Several volcanogenic *jökulhlaups* (outburst floods from glaciers) have been documented in Iceland (Russell et al., 2006).

Lahars (fluidized volcanic debris flows produced when hot pyroclastic material falls onto glaciers) can be extremely destructive owing to their high density and low viscosity while in motion, and their tendency to over-consolidate (stiffen) upon halting. Lahars are especially destructive because their mode of origin allows large volumes of material to be activated quickly, and because the topographic relief of the volcano provides abundant potential energy. In Kamchatka, lahars have caused significant damage to infrastructure and the environment. For example, the 2001 eruption of Shiveluch Volcano produced lahars which

traveled about 20 km and damaged the road to Ust-Kamchatsk. The 2005 eruption of Kluchevskaya Volcano created lahars that carried blocks 3 to 4 m in size a distance of over 30 km.

It is unclear from the available literature how glacier-volcano interactions and the associated hazards will be influenced by future changes in climate and resulting changes in glaciers and ice caps. However, there is some evidence that volcanic activity may increase as ice thins (Tuffen, 2010).

7.7.5.5. Glacier surges

Surging glaciers are found in Alaska, the Yukon Territory, Arctic Canada, Greenland, Iceland, Svalbard, and Novaya Zemlya. Those in Novaya Zemlya tend to terminate in water (Grant et al., 2009), and surges of these glaciers are a potential danger to local populations and infrastructure. Some surging glaciers in Alaska, such as the Black Rapids Glacier, are a potential hazard to the Trans-Alaska (oil) Pipeline (Heinrichs et al., 1995). Surge behavior has been documented for 26 glaciers in Iceland (Björnsson et al., 2003). Surges of these glaciers are associated with an increase in proglacial stream turbidity, but not discharge. The geographical variability of surge behavior, coupled with the incomplete understanding of glacier surge mechanisms, makes it difficult to predict whether climate change will alter the frequency of surging or the impact of the phenomenon on human society.

7.7.6. Glacier-related tourism

More than 1.5 million tourists currently visit the Arctic each year, up from one million in the early 1990s. Longer and warmer summers keep Arctic seas free of ice floes, so cruise ships can visit places that were once inaccessible. The annual number of visitors to Svalbard has surged by 33% in the period 2002 to 2006 to about 80 000 (Naik, 2007). At the beginning of the 21st century, tourism has clearly become a major engine of growth for the Alaskan economy. According to the Alaska Tourism Satellite Account (Anon, 2004), travel and tourism's economic contribution in Alaska reached USD 1.6 billion in 2002. This amount – representing sales net of related imports into the state – contributed 5.6% to Alaska Gross State Product (GSP). This includes the direct and indirect effects of all travel and tourism expenditure, but not induced (multiplier) effects. Travel and tourism's core industry – that is, only the direct impact of end-providers of goods and services to travelers – generated USD 856 million in local value added in 2002: 3.0% of Alaska's GSP. Using the core industry definition, travel and tourism was the third largest private sector employer – fourth overall – in the State, with 26 158 direct full-time-equivalent jobs (9.1% of Alaska's total employment) in 2002. Travel and tourism-generated jobs provided USD 579 million in core labor income (benefits and salaries) to Alaska. Adding public sector employment, travel and tourism's economic contribution to employment reached 39 420 full-time-equivalent jobs. Those jobs provided Alaskan workers with USD 1.15 billion in income. Glacier-related tourism is an important part of the economy in several regions of the Arctic, especially in Alaska. Every year hundreds of thousands of people visit coastal Alaska to see the glaciers. Melting of the glaciers in the warming Arctic may be a threat to this sector of the economy.

7.8. New information expected from International Polar Year projects

- Eleven projects focusing on the behavior of Arctic mountain glaciers and ice caps were initiated during the International Polar Year (IPY). They contributed to several IPY projects including GLACIODYN and ‘State and Fate of the Cryosphere’.
- New regional surveys of glacier changes, which contribute to the IPY program ‘State and Fate of the Arctic Cryosphere’, have been conducted in Alaska, the Yukon, Labrador, Iceland, the Russian Arctic Islands, and northeastern Siberia. Surveys in Alaska and Iceland involve new mapping of glacier surface topography with LIDAR and laser altimetry. Satellite laser altimeter data from ICESat have also been used extensively in these surveys. The Yukon surveys reveal a 22% reduction in glacier area since the 1957/1958 International Geophysical Year.
- GLACIODYN projects focus on understanding and modeling the role of changing ice dynamics in the response to climate change of polythermal and calving tidewater glaciers. Target glaciers for this work are Columbia and McCall Glaciers in Alaska, Belcher Glacier on Devon Island, Canada, and Austfonna and Vestfonna in Nordaustlandet, Svalbard.
- A Russian IPY project has focused on the formation, dynamics, and decay of icebergs in the western sector of the Russian Arctic, a topic of particular interest given the increasing amount of shipping and offshore resource exploration activity in the region.

7.8.1. Alaska

Three U.S. IPY projects will contribute to knowledge of Arctic glacier changes and mechanisms of change. As part of IPY-37 GLACIODYN, there is a continuation of the 30-year record of observations on the retreat of Columbia Glacier, Alaska, which at present is the largest single Alaskan contributor to sea level change (at 3.3 Gt/y from 1982 to 2001, and 6.6 Gt/y around 2001). The ongoing work at Columbia Glacier includes re-analysis and archival of the 145-mission, 30-year sequence of aerial photography of the glacier (the longest and most detailed record of its kind ever acquired), a continuation of this aerial photogrammetric record, and a variety of additional measurements and analyses including photogrammetric feature-tracking, terrestrial time-lapse photogrammetry, airborne radar, GPS surveying, seismic observations of calving, and meteorological monitoring. Collaborative work on Svalbard with Polish colleagues is included in this project. The results will add to knowledge of the physics of calving and tidewater glaciers, and improve the ability to predict future marine-terminating glacier behavior, not only on Arctic glaciers and ice caps, but on marine-terminating glaciers everywhere, including the outlet glaciers of Greenland and Antarctica. Work under this funding is in progress and research supported in part by this funding is presented by O’Neel and Pfeffer (2007).

A second GLACIODYN project aims to investigate the mass balance and ice dynamics of polythermal land-terminating

glaciers using McCall Glacier in Arctic Alaska as the primary field site. During the IPY, ice cores to bedrock were extracted at three locations. One complete core and selected parts of the other two cores have been returned for analyses designed to elucidate past climate conditions in the region and establish a history of pollutant deposition. Thermistor strings were installed to bedrock in the drill holes as part of a study of internal accumulation within the glacier and its effects on the glacier’s mass balance and thermal regime. A program of stream hydrology measurements was initiated both at the glacier terminus and in the river that drains from the region to the Arctic Ocean (these rivers have never previously been gauged and glaciers currently contribute roughly 90% of their discharge). A full 3D higher-order ice flow model of the glacier is being run using high-resolution bedrock and surface maps. To help understand how representative the McCall Glacier measurements are of a broader region, a new LIDAR digital elevation model covering about 500 glaciers in the eastern Brooks Range was created based on surveys conducted in 2008. It will be used to measure changes in glacier volume in the region.

As part of IPY-105 ‘State and Fate of the Cryosphere’, glacier mass loss across Alaska is assessed using airborne laser altimetry along glacier centerline profiles. Repeat profiles are compared to previous mass change estimates to address the primary question of continued acceleration of glacial wastage.

7.8.2. Arctic Canada

Two Canadian IPY projects will contribute new knowledge about the glaciers in Arctic Canada. One component of the project ‘Variability and Change in the Canadian Cryosphere’ (a contribution to IPY-105 ‘State and Fate of the Cryosphere’) involves producing a multi-temporal glacier inventory and mapping changes in the extent of glaciers in the Yukon and Labrador since the International Geophysical Year (1958/1959) from aerial photography and satellite imagery. Initial results suggest a reduction of 22% in Yukon glacier area over that period (Barrand and Sharp, 2010) and a 25% reduction in the extent of Labrador glaciers between 2003 and 2007. A second goal of the project is to undertake annual mapping of melt extent, melt duration, melt onset and freeze-up dates, and the end-of-summer distribution of snow and ice facies on all large glaciers and ice caps in the Arctic (including Greenland) using enhanced resolution data from the SeaWinds scatterometer on QuikSCAT. The records extend over ten years, to the end of the 2009 melt season, and will provide new insight into the evolution of summer climate over the ice-covered areas of the Arctic land mass.

A second project is a Canadian contribution to IPY-37 GLACIODYN, which aims to investigate the role of ice dynamics in the response of Arctic glaciers and ice caps to global warming, and improve the ability to predict future changes and their impact on global sea level and fluxes of freshwater to the ocean. The Canadian contribution to GLACIODYN focuses on the Belcher Glacier in the northeastern sector of the Devon Island Ice Cap, Nunavut. This is the fastest flowing outlet from the ice cap and a major source of icebergs. The project involves an intensive field and remote sensing study of the hydrology and dynamics of the glacier linked to the development and

validation of a state-of-the-art, high-order coupled model of ice flow dynamics and glacier hydrology. The model will be used to test hypotheses about the effects of climate warming on meltwater inputs to Arctic outlet glaciers and their impact on ice flow, and to perform simulations of the response of the Belcher Glacier to recent and projected future climate change.

7.8.3. Iceland

A major Icelandic IPY project involves mapping the surface topography of Icelandic ice caps using LIDAR. The results will be used to correct digital photogrammetric maps from the 1990s, allowing an analysis of surface elevation changes of the ice caps over the past one to two decades. The LIDAR mapping is a collaboration between the Icelandic Meteorological Office and the Institute of Earth Sciences of the University of Iceland and is funded by RANNIS (the Icelandic Centre for Research), Landsvirkjun (the National Power Company of Iceland), the Icelandic Public Road Administration, the Reykjavík Energy Environmental and Energy Research Fund, and the National Land Survey of Iceland.

High-resolution LIDAR digital terrain models (DTMs) of most of Hofsjökull, Langjökull, Eiríksjökull, and Snæfellsjökull have been made from surveys conducted during the 2007/2008 IPY. DTMs of Mýrdalsjökull, Eyjafjallajökull, Hofsjökull, and southeastern Vatnajökull were completed in 2010. Mapping will be continued in 2011 to 2013 to produce DTMs of the southern, western, and northern drainage basins of the Vatnajökull ice cap.

The new LIDAR DTMs of proglacial areas and nunataks (isolated peaks protruding through the surface of the ice caps) will be used as a reference for re-analysis of the digital photogrammetric maps of glacier ablation areas in the 1990s, which should reduce systematic bias in these maps. This will make it possible to compare the photogrammetric maps with the LIDAR DTMs and quantify volume changes of the Icelandic ice caps during the past 10 to 20 years.

It is important that the glaciers are accurately mapped now when rapid changes are occurring in response to a warming climate. Accurate DTMs make it possible to pursue various lines of glaciological research, but they also have considerable economic value for the assessment and monitoring of water resources for hydroelectric power generation. Potential uses of the DTMs include modeling of surface mass balance and ice flow, mapping the boundaries of surface and subglacial watersheds, mapping subglacial water flow pathways, and quantifying rates of glacier change and their impact on global sea level. The DTMs are also important for investigations of glacier surges and isostatic uplift due to reductions in ice mass.

7.8.4. Svalbard

During the IPY, two international project consortia worked on glaciology in Svalbard: the IPY Kinnvika project and GLACIODYN. Both studied mass balance and dynamics with a focus on large ice caps. The glaciological part of the Kinnvika project focused on Vestfonna (2500 km²) and involved studies of accumulation rates, ablation rates, ice temperatures, and ice geometry and measured ice velocity fields. Fixed mass balance stations and automatic weather stations were established across the ice cap. Shallow cores were taken to find the average point

mass balance over a few decades. The data provide input to and validation of modeling and remote sensing studies.

The Norwegian part of GLACIODYN focused on Austfonna in Nordaustlandet and on Kongsvegen / Kronebreen in northwestern Spitsbergen. GLACIODYN monitored the current status of more than a dozen Arctic ice caps and glaciers with the aim of predicting the future fate of these terrestrial Arctic ice systems. The Austfonna investigations focused on (i) direct surface mass balance measurements; (ii) elevation and volume changes using satellite data, airborne laser profiles, and ground-based GPS measurements; (iii) dynamics of surge, calving and subglacial processes; and (iv) modeling of mass balance and dynamics. Five years of net surface mass balance studies on Austfonna show a slightly negative average balance (-0.1 m w.e./y), but with large interannual variations both in snow accumulation and total ablation. The calving is important (-0.30 m w.e./y) and represents 30% to 40% of the total ablation, similar to values observed on other Arctic ice caps. However, the elevation change measurements on Austfonna show a thickening in the interior of about 0.5 m/y and an increasing thinning closer to the coast of 1 to 2 m/y. A total of 230 km, or about 70%, of the ice cap margin is a calving front, at which all the ice is grounded. The calving front has been retreating at an average rate of 50 m/y since 1990 (Dowdeswell et al., 2008). There seems to be a large dynamic instability, as the measured mass flux is much less than the flux that would be expected given the observed surface mass balance.

On Spitsbergen, a Russian IPY project has used surface radio echo sounding surveys and the analysis of available multi-temporal cartographic, aerial, and satellite-derived data to determine changes in the surface elevation, thickness, ice volume, and internal structure of Fridtjovbreen resulting from a surge event in the 1990s.

7.8.5. Russian Arctic and mountains

The Russian National Program and Implementation Plan for the IPY 2007/2008 includes three projects relevant to glaciers in the Russian Arctic. The project 'Current state of glaciers and ice caps in the Eurasian Arctic' is a Russian contribution to GLACIODYN. The main goal of the project is to study the area changes, mass balance, hydrothermal state, and potential instability of glaciers and ice caps in the Russian Arctic islands and Svalbard. The main fieldwork programs in 2007 and 2008 included airborne and surface radio echo sounding surveys of ice thickness and bedrock and surface topography of ice caps and glaciers, which have been supported by the analysis of spaceborne remote sensing data. On the basis of radio echo sounding surveys of glaciers on Franz Josef Land and Novaya Zemlya and satellite altimetry data, characteristic heights and thicknesses of glacier fronts producing icebergs have been determined, including Glacier No. 1 and the Moscow Ice Cap on Hall Island, the northern part of the glacier complex on George Land (Franz Josef Land), and the glaciers in the Inostrantsev Bay area, Novaya Zemlya. New criteria for the estimation of iceberg hazards from the glaciers of Novaya Zemlya and Franz Josef Land were developed. Franz Josef Land has the greatest potential for regular formation of large icebergs (with thicknesses of up to 150 to 200 m and extents of more than 1 to 2 km) (Kubyshekin et al., 2009).

A second project, 'Formation, dynamics and decay of icebergs in the western sector of the Russian Arctic', aimed to collect new data on the formation, distribution, and properties of icebergs in the Barents and Kara Seas and to estimate the current state of outlet glacier fronts in the Russian Arctic archipelagos. During a cruise of R/V *Mikhail Somov* in September 2007, iceberg-producing glaciers on Franz Josef Land, Novaya Zemlya, and some other islands were surveyed. The survey included a wide range of iceberg studies, following their life history from calving to melting and disintegration. The study continued the survey of 2003, when an abnormally large group of icebergs (over 40, the largest of which was over 400 m long and weighed about 3 million tonnes) was discovered in the northeastern part of the Barents Sea, in the vicinity of the *Shtokman* gas-condensate field. The unusual ice conditions allowed R/V *Mikhail Somov* to circumnavigate Franz Josef Land. Helicopter radio echo sounding and aerial photography of glaciers on Prince George Land, Salisbury Island, Luigi and Champ Islands, Hall Island, and Wilczek Land allowed determination of ice thickness in potential iceberg-producing areas. Photogrammetry was used to reconstruct the geometry of glacier fronts and the above-water parts of icebergs. On some glaciers and icebergs, the vertical distribution of ice temperature (down to 20 m depth) and energy balance components of the upper 3 m layer were measured. Observations were made on the surface and in the ice (down to 3 m depth). On some glaciers, markers were installed for measurement of glacier flow. Glaciological studies were supplemented with oceanographic temperature and salinity profiling in the Franz Josef Land straits. Several groups of large tabular icebergs (more than 1 million tonnes) were found not far from their calving areas (Elena Guld Bay on Wilczek Land; the straits between Salisbury, Luigi, and Champ Islands; Geographers' Bay on Prince George Land). The majority of large icebergs were already drifting. Under favorable meteorological conditions, some may drift to the Barents Sea through the deep straits. A similar survey was undertaken of the glaciers of the northern end of the Northern Island of Novaya Zemlya (Buzin et al., 2008). This survey was repeated in autumn 2008.

The project 'Climatic factors in the contemporary evolution of North-Eastern Siberia glaciation' is another Russian contribution to GLACIODYN. This project continued studies of climate–glacier interactions in the poorly explored northeastern Siberia region. This region is of special interest because its climate is influenced both by Atlantic and Pacific air masses. It includes a part of the Northern Hemisphere where climate change (weakening of the Siberian High and warming in recent years) and cryospheric change have been detected. Meteorological parameters were measured along a transect from Magadan to Oymyakon, and in the northern massif of Suntar-Khayata. A study has been completed of glacier change in the region based on modern satellite images and data from the USSR Glacier Inventory. Infrared, visual, and aerial photo surveys were conducted for the Suntar-Khayata glaciers in order to update the Glacier Inventory (Ananichava and Kapustin, 2010).

7.9. Synthesis of the current state of Arctic mountain glaciers and ice caps

- Mass balance assessments based on field measurements and geodetic surveys indicate a marked increase in the rate of mass loss from Arctic glaciers (especially those in Alaska, the Canadian Arctic, and Greenland) since the mid-1990s. From 1961 to 2004, the mean rate of loss was in the range -91 to -141 Gt/y, but pentadal estimates for the period since 1995 range from -170 to -280 Gt/y.
- The recent increase in mass loss coincides with increases in summer air temperature and reductions in glacier area.
- Recent rates of mass loss are comparable to those from the Greenland Ice Sheet, emphasizing the importance of the Arctic as a whole as a first-order control on the rate of global sea level rise.
- Iceberg calving is an important component of mass loss in Alaska, Arctic Canada, the Russian Arctic, and Svalbard (where it accounts for about 32% of the net mass loss). Individual tidewater glaciers can discharge very large amounts of ice into the ocean (e.g., Columbia Glacier discharged 6.6 Gt/y in 2001). However, temporal changes in this mass loss term are not well known and are not included in projections of future mass and volume change.
- Model-based projections suggest a 13% to 36% reduction in Arctic glacier volume by 2100 due to changes in surface mass balance alone. While some individual glaciers will disappear during this period (and others have already done so), mountain glaciers and ice caps in the Arctic will continue to influence change in global sea level well beyond 2100.
- Meltwater runoff from Arctic glaciers is expected to increase for a few decades at least, but will eventually decrease as the influence on melt production of decreasing glacier area becomes more significant than that of increasing melt rate.

7.9.1. Mountain glacier and ice cap mass balance

Two global mass balance datasets, one based on glaciological mass balance measurements (DM05) (Dyurgerov and Meier, 2005) and the other a combination of both glaciological and geodetic measurements (C09) (Cogley, 2009a), are sub-setted to determine a pan-Arctic glacier mass balance. DM05 is a weighted arithmetic mean of single-glacier time series within a set of climatically homogeneous regions, based on data from the World Glacier Monitoring Service (WGMS, which collects standardized observations of change in the mass, volume, area, and length of glaciers worldwide; www.wgms.ch), individual published sources and, in some cases, unpublished measurements. Each time series is weighted by the area of its glacier, and then extrapolated to the climatic region based on estimates of the total glacierized area in each region. Nearly all the glaciological measurements in DM05 are derived from land-terminating glaciers (with larger glaciers underrepresented). C09 uses a nearly identical glaciological dataset to DM05, but also includes geodetic datasets that sample several tidewater glaciers. For the annual glaciological dataset,

C09 uses a spatial interpolation algorithm that fits a polynomial in geographical coordinates (centered successively on each cell of a 1° by 1° grid) to the complete (glaciological plus geodetic) set of single-glacier balances. The measured mass balances are inverse-distance weighted to the center of the grid cell, and the resulting estimate is multiplied by the total glacierized area within that cell. Estimates are averaged over five-year (pentadal) time periods. For the geodetic measurements, which usually span several years, the time-averaged mass balance during the entire period is assumed to represent the annual balances within that period. Interannual variations in the geodetic balances are accounted for by calculating a standard deviation that is a function of the warmest month's air temperature in a given year, interpolated to the glacier equilibrium line. The temperatures used are climatological means from the NCEP/NCAR Reanalysis.

While all the mass balance measurements included in the DM05 and C09 datasets are total mass balances (surface mass balance plus iceberg calving), very few are from calving glaciers. Circumstantial evidence presented by Cogley (2009a) suggests that calving glaciers may currently have more negative mass balances than land-terminating glaciers. If so, underrepresentation of calving glaciers in these datasets may result in underestimation of rates of mass loss in both global mass balance assessments. As yet, it is not understood why rates of mass loss from calving glaciers might be higher than those from land-terminating glaciers and it is not possible to properly quantify the magnitude of the bias in global mass balance assessments that arises from underrepresentation of calving glaciers in the datasets on which these assessments are based. Equally, it is not yet possible to predict how the rate of mass loss by iceberg calving will evolve under different climate change scenarios.

Both estimates derived from measurements (DM05 and C09) show that mass balances were predominantly negative during the period of record, with large interannual variability (Figure 7.29). During the period 1961 to 2004, the average mass balance of Arctic glaciers was -91 Gt/y using the DM05 data and -138.4 Gt/y using the C09 data. Estimates from DM05, based only on glaciological measurements, are more positive than the C09 estimates, possibly because they underrepresent calving glaciers. A third global mass balance estimate, derived from a surface mass balance model driven by climate station data (Hock et al., 2009), suggests that the surface mass balance of Arctic glaciers was -141 ± 65 Gt/y during the period 1961 to 2004 (Figure 7.29). Mass balances were significantly more negative in the period 1995 to 2005 (of the order of -170 to -280 Gt/y according to the C09 dataset). These recent rates of mass loss are comparable in magnitude to recent estimates of mass loss from the Greenland Ice Sheet (see Chapter 8). When the mass loss rates from Arctic mountain glaciers and ice caps are combined with those from the Greenland Ice Sheet, it becomes clear that wastage of glacier ice in the Arctic is a first-order control on the rate of global sea level rise.

The regional contributions that comprise the pan-Arctic mass balance estimate derived using the combined geodetic-glaciological method (C09) are shown in Figure 7.30. This figure also shows the pentadal mean summer (June to August) 700 hPa air temperature for each region from the NCEP/NCAR Reanalysis. The time series of estimated contributions from regions with observed records (such as southern Alaska, the




Figure 7.29. Annual mass balance (Dyurgerov and Meier, 2005) and pentadal mass balance (from data compiled by Cogley, 2009a) of Arctic glaciers as outlined in Figure 7.9. Annual estimates are extrapolated from glaciological measurements. Pentadal estimates are derived from a combination of geodetic and glaciological data. The grey box is an estimate from mass balance modeling (Hock et al., 2009) marking the error bounds around the mean estimate. Source: AMAP.

Canadian Arctic, Scandinavia, and Iceland) are inversely related to regional summer air temperature variations. However, the time series for some regions with fewer observations (such as the Russian Arctic) are not consistent with local climate fluctuations. In these regions, the reconstructed mass balance records may be overly influenced by regional interpolation from areas with more mass balance data and different temperature histories. In general, the degree of confidence in the regional mass balance reconstructions decreases as the amount of smoothing of observed data required to generate them increases. This suggests that records from such regions need to be treated with caution and that deriving more reliable records for such regions should be a high priority.

Estimates of regional mass balance based on local measurements also illustrate the relative contribution of each region to rising sea level (Figure 7.31) over specific intervals of time. All areas with regional syntheses show mass losses during their periods of measurement, with Alaska and the Canadian Arctic being the dominant contributors to rising sea level. It is important to note that these estimates for different regions are not directly comparable owing to the differences in measurement periods.

7.9.2. Ablation due to iceberg calving

The relative proportions of ablation due to calving and surface mass balance are not well known, but available data suggest that calving plays an important role in the mass balance of glaciers in Alaska, the Canadian Arctic, Svalbard, and the Russian Arctic. There are 54 tidewater glaciers in northwestern North America, some of which are continuing their rapid retreat that commenced about 200 years ago. Among these, Columbia Glacier is undergoing the most rapid retreat exceeding 1 km/y since 2000, discharging an average of 3.3 Gt/y of calved ice during the period 1982 to 2001, with 6.6 Gt/y calved ice in 2001 (O'Neel et al., 2005). In Svalbard, calving losses accounted for about 32% of the overall glacier ablation (Błaszczuk et al., 2009). In Arctic Canada, Svalbard, and Severnaya Zemlya, calving comprises a significant fraction of the total ablation from several large ice caps including Devon Ice Cap and Prince of Wales Icefield, Austfonna, and Academy of Sciences Ice Cap




Figure 7.30. Estimates of pentadal mean annual specific mass balance for glacierized regions of the Arctic derived using the combined geodetic-glaciological dataset of Cogley (2009a) and the pentadal mean of annual anomalies in summer (June – August) air temperature at a geopotential height of 700 hPa over each region from the NCEP/NCAR Reanalysis. Temperature data are not plotted for the Greenland Periphery and Continental Arctic regions due to the non-contiguity of these regions. Source: Dan Moore, University of British Columbia.

(Dowdeswell et al., 2002, 2008; Burgess et al., 2005; Williamson et al., 2008). However, ongoing monitoring of calving fluxes is almost non-existent and, as a result, the magnitude of temporal variability and the existence and sign of any trend in calving fluxes are essentially unknown.

7.9.3. Observed trends in ice extent

Observed changes in ice extent over the past half-century are consistent with changes in mass. In nearly all regions, mass losses occurred coincidentally with decreases in glacier area. Although a small number of glaciers have advanced during this time, nearly all of these are tidewater or surge-type glaciers. The area evolution of tidewater and surge-type glaciers depends more on dynamic cycles than on direct climatic forcing, although it may be influenced by regional climate patterns.

7.9.4. Relationship to climate and circulation changes

Arctic air temperatures have increased during the past half-century (Hinzman et al., 2005), which probably explains much of the increase in rates of mass loss observed on Arctic glaciers. Increases in summer air temperature explain the accelerated losses from glaciers in northwestern North America (Arendt et al., 2009) and Arctic Canada (Gardner and Sharp, 2007), but uncertainties remain large due to the difficulties in modeling dynamic losses owing to calving.

In general, changes in synoptic-scale atmospheric circulation patterns, resulting from variations in sea-surface temperature, polar jet stream position, and other factors, correlate well with Arctic glacier mass balance time series. In northwestern North




Figure 7.31. Estimates of the mass balance of Arctic glacier regions for which regional assessments have been conducted. The vertical extent of each box describes the range of uncertainty in the mass balance estimates (uncertainty estimates are not available for Iceland or the Canadian or Russian Arctic). Glaciological estimates relate only to the surface mass balance. Source: Anthony Arendt, University of Alaska, and W. Tad Pfeffer, INSTAAR, University of Colorado.

¹Björnsson and Pálsson (2008): data from two ice caps comprising 81% of the ice-covered area of Iceland; ²Hagen et al. (2003a): surface mass balance component, Hagen et al. (2003b) calving component; ³Nuth et al. (2010): date ranges are 1965/90 to 2003/07; ⁴Abdalati et al. (2004); ⁵Arendt et al. (2002); ⁶Tamisiea et al. (2005); ⁷Chen et al. (2006); ⁸Luthcke et al. (2008); ⁹Glazovsky and Macheret (2006); ¹⁰Berthier et al. (2010).

America, two well-documented ‘regime shifts’ occurred in 1977 and 1989, during which temperatures abruptly shifted to more positive values and storm tracks changed direction. These shifts are evident in the mass balance time series of glaciers in Alaska (Bitz and Battisti, 1999; Josberger et al., 2007). In the Canadian Arctic, accelerated surface mass loss after 1987 was associated with changes in the position of the July circumpolar vortex. In the Russian Arctic, mass balance changes have been linked to sea-surface temperature variations in the Barents Sea.

7.9.5. Projections of future change

Modeling studies indicate that many individual glaciers may disappear by the end of the 21st century if air temperatures in the Arctic continue to rise as projected in the scenarios used by the suite of climate models employed in the Fourth Assessment of the IPCC (Solomon et al., 2007). The total volume of Arctic glaciers is projected to decline substantially by 2100. Projected reductions are of the order of 13% to 36% of current glacier volume. However, these projections vary greatly from model to model, are sensitive to the choice of climate scenario, and generally do not include mass losses by iceberg calving, which is known to be an important mode of ablation. Nonetheless, it is clear that glaciers in the Arctic are likely to continue to influence changes in global sea level well beyond the end of the 21st century.

7.9.6. Impacts

In many parts of the Arctic, climate warming should cause glacier runoff to increase for a few decades or longer, but glacier retreat will ultimately cause glacier runoff to decline. Runoff decline may already have started in some regions where most glaciers are small.

Changes in glacier runoff will influence freshwater habitat, water supply, hydroelectric power generation, flood

and avalanche hazard, estuarine and coastal habitat, and patterns of ocean circulation. Glacier retreat may result in the destabilization and failure of valley-side slopes. Outburst floods from moraine-dammed lakes are likely to decrease in frequency as glaciers retreat further from moraines formed during the Little Ice Age. The frequency and magnitude of outbursts from existing glacier-dammed lakes may also change as ice dams are thinned by ice melting. However, new lakes may form further up-glacier as glacier margins recede down valley-side slopes and melt rates increase.

7.10. Knowledge gaps and recommendations

- The major gaps in knowledge that limit the ability to quantify current rates of glacier wastage in the Arctic and predict future trends are (i) the lack of a complete glacier inventory for the Arctic (including information about glacier location, area, surface topography, and ice thickness); (ii) the limited number of *in situ* mass balance measurements, the strong spatial bias in the distribution of available measurements, and the complete lack of measurements from areas such as the Russian Arctic; and (iii) the lack of ongoing monitoring programs for the iceberg calving component of mass balance, and limited knowledge of the major controls on calving fluxes.
- A coordinated effort to fill these knowledge gaps is needed in order to predict more reliably the current and future contribution of Arctic glaciers to global sea level change and better assess how glacier change will affect regional water resources.

7.10.1. Key gaps in knowledge

Despite progress since the Arctic Climate Impact Assessment (ACIA, 2005), major gaps remain in knowledge about Arctic glaciers and ice caps. The keys gaps are as follows:

1. There is a severe lack of basic information about glaciers in the Arctic. Knowledge gaps include the geographical distribution, total area and size distribution of glaciers in some regions, the distribution of area with elevation (hypsometry), and glacier thicknesses and, therefore, volume (Figure 7.32).
2. Glaciological mass balance measurements are limited to a small number of Arctic glaciers (50 in the 2000 to 2004 pentad, of which 30 were in Scandinavia), with larger glaciers and calving glaciers underrepresented. There have been no mass balance measurements conducted in Arctic Russia since 1990, and all but one measurement series from that region ended before 1980. In Arctic Canada, the number of measurement sites peaked at 13 in the early 1970s and is now only five. Given that the uncertainties associated with estimates of regional mass balance increase substantially as the number of local measurements decreases, there is a pressing need to continue (and expand) *in situ* monitoring programs and to develop alternative well-validated methods for assessing regional-scale glacier mass changes, including remote sensing observations (although a problem with these is the lack of temporal and methodological continuity between sensors and satellite missions) and numerical modeling.
3. Observations, process understanding, and modeling capabilities related to ablation by calving are severely limited, introducing large uncertainties into current and future mass balance estimates.




Figure 7.32. (a) Ratio between the area of Extended World Glacier Inventory (WGI-XF) glaciers (Cogley, 2009b), A_{WGI-XF} , and regional glacier area, A_{region} , for the nine glacierized regions that have incomplete glacier inventories. (b) Missing area in WGI-XF as a fraction of missing global glacierized area. While 'a' shows the degree of completeness of each regional inventory, 'b' indicates how much the different regions contribute to the global missing area. South America I refers to Bolivia, Ecuador, and Peru, while South America II refers to Argentina and Chile. Source: after Radić and Hock (2010).

7.10.2. Basic observations

Basic information about the geometry and distribution of glaciers is required to assess and model current and future mass changes and contributions of Arctic glaciers to changes in sea level, but this information is currently incomplete for the Arctic. As it is unlikely that direct volume measurements on regional scales will become available in the near future, volume estimates will continue to rely on volume-area scaling techniques. Nonetheless, more direct volume measurements, for example by airborne radio echo sounding, are required to validate scaling techniques.

Completion of high-quality Arctic-wide inventories of glacier areas and size distributions from recent optical satellite imagery is also essential to improve Arctic glacier mass balance assessments. It is important to have regional inventories based on glacier regions; regions should not be bisected by political borders.

There is need for an accurate pan-Arctic inventory of surge-type glaciers and a better understanding of surge recurrence intervals, to provide better estimates of the drawdown of ice by these unusual glaciers. The fraction of mountain glacier and ice cap area drained by marine outlets, and the size and discharge of the marine outlets (including the temporal variability in discharge), must be known if present-day estimates and future forecasts of mass loss by iceberg calving are to be improved.

7.10.3. Mass balance measurements, proxies, and modeling

Most of the uncertainties associated with mass balance estimates arise from the limited number of *in situ* observations. Because the number and distribution of *in situ* observations are unlikely to increase in the short term, there is a need to use remote sensing data to monitor ongoing changes in glacier geometry, surface mass balance, dynamics, and iceberg production. In particular, the potential for estimating mass change of Arctic ice caps using satellite gravimetry (GRACE) and repeat-track altimetry data from the Geoscience Laser Altimeter System on ICESat and its successor needs to be explored more fully. The successful launch in April 2010 of the European Space Agency's CryoSat-2 satellite will create opportunities for monitoring changes in the thickness of the larger ice masses in the Arctic.

Most indices of glacier change at regional scales can only be derived from remote sensing sources, so it is important to continue to develop and maintain long and continuous time series of remote sensing data. The development of regional-scale indicators of mass balance is currently limited by the low spatial resolution of much readily available remote sensing data. This seriously impedes the ability to map the properties of smaller ice bodies containing a significant fraction of the total glacier mass, resolve local features, and properly interpret and validate interpretations using sub-pixel *in situ* data. This is particularly the case with mapping melt duration and identifying the limits of snow and ice facies (especially the superimposed ice zone) from active microwave data that are freely available at the pan-Arctic scale. The accuracy of the results of facies mapping affects the accuracy of secondary indices (e.g., equilibrium-line altitude and accumulation area ratio) derived from facies maps. The ability to monitor regional-scale mass balance proxies at high spatial and temporal resolution is dependent on the

availability of microwave scatterometer data and enhanced resolution products (e.g., QuikSCAT SIR). It is crucial for the construction of long-term records that these data sources be replaced following the recent demise of QuikSCAT.

Uncertainties in nearly all mass balance methods are poorly quantified and rarely reported, although the latter problem is abating steadily. Often it is not clear whether reported mass balances include internal accumulation or calving, both of which can be major components of the mass balance; this makes direct comparison of different measurements problematic. The effects of internal accumulation and superimposed ice formation on glaciological mass balance measurements need to be quantified and these processes need to be included in mass balance modeling. Rigorous identification of sources and magnitudes of error is necessary through intercomparison of methods. Methods for combining mass balance datasets derived from different sampling techniques and representing different time periods and regions need to be expanded and improved to deliver firmer estimates of mass balance and contributions to sea level rise for all Arctic ice masses. The number of glaciologists with expertise in mass balance compilation and integration is also declining and a new generation of glaciologists with these skills must be trained soon.

Given the limited number of *in situ* observations, modeling will continue to play an important and growing role in the assessment of ongoing change in surface mass balance as well as in the projection of future changes. Regional-scale modeling remains a challenge because of the difficulties involved in downscaling climate re-analysis data and climate model results to the complex topography and the heterogeneous climatic conditions of mountain glacier and ice cap environments. These problems are exacerbated by the limited availability of ground measurements made on glaciers to validate the results of downscaling. Projections of future mass balance are also challenging owing to the magnitude of the uncertainty in climate projections for the Arctic that results both from the choice of forcing scenarios used to drive the climate models and large inter-model differences in climate response to the same forcing scenario.

7.10.4. Ice dynamics and ablation by iceberg calving

Although, with the possible exception of internal accumulation (but see Reeh et al., 2005 and Reeh, 2008 for recent progress), processes related to surface mass balance are relatively well understood, there is a severe gap in understanding and modeling of mass loss by calving. Glaciers that terminate in water can have dynamic instabilities that result in rapid mass losses. However, for glacier calving and glacier-marine interactions, there is a lack of both the physical understanding of critical processes and the observations necessary to validate the mathematical representation of these processes. There is also a lack of direct measurements of calving flux and its variability, and of the roles that glacier-marine interactions, bathymetry, ocean temperature, and terminus geometry and dynamics play in determining rates and patterns of glacier retreat and advance. Another area where understanding is limited involves the relationships between summer melt, the development of meltwater drainage systems on, in, and under glaciers, the delivery of water to glacier beds, and the subsequent effects on glacier sliding.

Such information would provide constraints on estimates of total dynamic mass losses and would improve modeling results. There appear to be fundamental differences between calving from tidewater glaciers that terminate in the ocean and calving from those that terminate in freshwater, but these remain poorly understood. Ablation by calving has generally been neglected in predictions of future mass balances. Hence, there is an urgent need to incorporate suitable parameterizations in Arctic-wide mass balance modeling. Since approaches developed for modeling individual glaciers are not yet suitable for application at regional scales due to the paucity of constraining observational data and the largely unresolved nature and complexity of the processes involved, there is a need to explore simpler empirical parameterizations. Given that iceberg keel plowing of sea-floor sediments is a major hazard to underwater engineering structures, there is very little knowledge of the size-frequency distribution of iceberg keel depths or the sources of large icebergs.

7.10.5. Impacts


There is a general understanding that climate warming should cause an initial increase in glacier runoff, followed by a decreasing trend. However, the magnitude of peak runoff and the timing of the shift from increasing to decreasing runoff are not known for most watersheds. Indeed, it is possible that some glaciers are currently in the phase of declining runoff, although the total stored ice volume is large enough that an Arctic-wide decline in loss will not occur in the near future. This knowledge gap is particularly critical because changes in glacier runoff control many other impacts, including those on water quality, stream channel dynamics, and circulation in estuaries and coastal waters. There is a need for further simulations of the transient response of glacier geometry and runoff, and their application to a range of drainage basins and climate scenarios, to understand better the sensitivity of runoff changes to climate forcing and its regional variability.

There is a reasonable consensus regarding the direction of stream temperature response to changing glacier runoff and glacier retreat. However, the magnitudes are uncertain. There is less certainty regarding the changes in biogeochemistry and sediment yields. Further process-based research and model development are required to address these gaps. Without predictions of these water quality responses to future climate-glacier change it is not possible to make reasonable projections of the impacts on aquatic ecosystems.

Finally, the impact of climate change on the magnitude and frequency of glacier hazards needs to be understood with a considerably greater degree of confidence to be useful.

Appendix 7.1 Glossary of glaciological terms

Definitions largely follow those proposed by Cogley et al. (2011).



Components of the mass balance of a glacier. The arrows have arbitrary widths and do not indicate physical pathways of mass transfer. Source: after Cogley et al. (2011).

Accumulation area ratio

The *accumulation area ratio* (AAR), often expressed as a percentage, is the ratio of the area of the accumulation area to the area of the glacier. The AAR is bounded between 0.0 and 1.0 and its value often correlates well with the surface mass balance. The likelihood that mass balance will be positive increases as the AAR approaches 1.0.

Calving

Calving involves the breaking off of discrete pieces of ice from a glacier terminus into a lake or marine waters, producing icebergs. Calving of outlet glaciers is responsible for roughly half of the mass loss of the Greenland Ice Sheet (see Chapter 8), and can account for a significant part of the mass lost from glaciers in the Arctic.

Calving flux

Calving flux is the *mass flux by calving from a glacier terminus*, with dimension mass per unit time [M/T]. The calving flux can be determined from ice thickness and velocity measurements close to the terminus and the change in ice mass due to terminus advance or retreat.

Equilibrium line

The equilibrium line is defined by the set of points on the surface of the glacier where the surface mass balance is zero at the end of the melt season. The equilibrium line separates the *accumulation area* (where the annual mass balance is positive) from the *ablation area* (where the annual mass balance

is negative). It coincides with the snowline (defined as the set of points on a glacier forming the lower boundary of the snow-covered area) only if all mass exchange occurs at the surface of the glacier and there is no superimposed ice. Where superimposed ice forms, the equilibrium line marks the lower limit of superimposed ice formation and occurs at a lower elevation than the snowline.

Equilibrium-line altitude

The spatially averaged altitude of the *equilibrium line* is known as the equilibrium-line altitude (ELA). The ELA is generally determined by fitting a curve to data representing *surface mass balance* as a function of altitude, although it may also be defined by direct visual observation. The ELA often correlates well with the surface mass balance.

Glacier surge

A glacier surge represents anomalously fast glacier motion (10 to 100 times non-surging speeds) sustained for a period of months to years. Surges commonly alternate with slower motion lasting for periods of years to centuries during which the glacier thickens in its upper reaches and thins in its lower reaches. Surging transfers most of the accumulated reservoir of ice from high on the glacier to its lowest reaches, and often extends the glacier terminus by significant distances (kilometres). Surges recur at fairly consistent, glacier-specific intervals. Surge-type glaciers may end on land or in the ocean and are clustered geographically for reasons that are not well understood. Surges seem to be related to changes in the subglacial hydrological regime and not primarily to climatic fluctuations. They are

controlled in some cases by thermal processes ('Svalbard-type surging', characterized by long quiescent periods) and in other cases by hydraulic processes ('Alaskan-type surging' characterized by shorter quiescent periods and higher velocities relative to Svalbard-type surges). While the processes involved in surging are understood in broad terms, many details of their behavior remain elusive (Raymond, 1987).

Internal accumulation

Internal accumulation is the refreezing of surface meltwater (or freezing of rain) that is in transit through the glacier that otherwise would have left the glacier as runoff. Water that freezes within the current year's snowpack is not counted as internal accumulation. Internal accumulation may be regarded as simply redistributing mass within the glacier. On many Arctic glaciers, internal accumulation is a major component in the mass balance and failure to account for it results in a measurement bias towards overestimation of mass loss. Typically, internal accumulation is not detected by traditional surface mass balance measurements.

Mass balance

The mass balance is the change in the mass of a glacier or ice body over a stated span of time, often expressed as a rate. Mass gain (accumulation) mainly occurs by snowfall. On some glaciers deposition of hoar, gain of blowing and drifting snow, avalanching, and basal freeze-on (usually beneath floating ice) are significant processes of accumulation. The glacier loses mass (ablation) mainly by melting and iceberg calving. On some glaciers, sublimation, evaporation, loss of blowing and drifting snow, and ice avalanching are significant processes of ablation. In some cases, a fraction of the meltwater produced (plus rainfall) can refreeze, either within snow or firn (see *internal accumulation*) or on the ice surface (see *superimposed ice*), and does not contribute to mass loss from the glacier. These processes are summarized in Figure 7.8. There are several ways to measure mass balance; these are described in Section 7.3.2.1.

The principal mass balance components are surface accumulation (C_{sfc} , usually mostly snowfall and superimposed ice formation), surface ablation (A_{sfc} , usually mostly melt), internal accumulation C_i , internal ablation A_i , basal accumulation C_b , and basal ablation A_b , and (for ocean- or lake-terminating glaciers) iceberg calving D , so the glacier-wide mass balance $\dot{M}$ expressed as a rate is given by:

$$\dot{M} = \dot{C}_{sfc} + \dot{A}_{sfc} + \dot{C}_i + \dot{A}_i + \dot{C}_b + \dot{A}_b + \dot{D}$$

All terms have the dimension mass per unit time, [M/T]. Surface accumulation and ablation tend to be major components on most land-terminating Arctic glaciers. Internal accumulation is also important on the Greenland Ice Sheet and many polythermal/cold glaciers. Basal ablation can be a dominant component of the mass balance of floating tongues of marine-terminating glaciers, while basal accumulation and internal ablation are generally negligible.

The sum $C_{sfc} + A_{sfc}$ defines the **surface mass balance**, B_{sfc} or SMB, the latter symbol often being used in ice sheet studies. In estimates of ice sheet mass balance, the term has often

been extended to include internal accumulation. In addition to snowfall and superimposed ice, surface accumulation also includes deposition of hoar, freezing rain, solid precipitation in forms other than snow (e.g., hail), and snow transported by wind or avalanches.

Mass balance units

The principal dimension for mass balance is mass per unit time [M/T]. Ice sheet balances are often expressed in Gt/y (1 Gt = 10^{12} kg). However, the mass balance, especially of smaller ice bodies, is usually treated as a rate of change of mass per unit area, in which case it is referred to as *specific mass balance* and its dimension becomes [M/L²/T], for example, kg/m²/y, which is numerically identical to the millimetre water equivalent, mm w.e./y. While mass units (e.g., kg or Gt) are useful for hydrological or sea level calculations, specific units (e.g., kg/m², mm w.e.) are needed for comparisons of glaciers of different sizes, for example, when investigating glacier-climate interactions. Mass balances, in particular for larger ice bodies, are often expressed in **sea level equivalent** (SLE), which is the change in mean global sea level that would result if glacier mass were added or removed from the ocean. SLE in mm/y is often simply obtained by

$$SLE = \frac{0.001 \dot{M} A_{glacier}}{\rho_w A_{ocean}}$$

where the glacier mass change $\dot{M}$ is in kg/m²/y and the areas of the glacier ($A_{glacier}$) and the ocean (A_{ocean}) are in m²; ρ_w is the density of freshwater (1000 kg/m³).

Superimposed ice

Ice accumulated on top of glacier ice by the refreezing of rain or meltwater produced during the current mass balance year is known as superimposed ice. It is different from internal accumulation, which represents refreezing within firn below the summer surface formed at the end of the summer in the previous mass balance year. Measurement of superimposed ice accumulation requires special attention in conventional mass balance programs.

Tidewater glacier

A tidewater glacier terminates in the sea, with its terminus either floating or grounded below sea level. Tidewater glaciers can undergo a periodic growth/shrinkage instability with long periods (centuries) of slower motion and slow advance alternating with shorter periods (decades) of rapid motion, high calving flux, and rapid (~1 km/y) retreat (Meier and Post, 1987).

Termed *tidewater instability*, this cyclic behavior has been documented most extensively in Alaska (Post, 1975), although it has been observed in many other regions, and the present retreat of certain Greenland Ice Sheet outlet glaciers appears to operate in a nearly identical fashion (Howat et al., 2005). During rapid retreat, a glacier can thin far faster (by loss of the marine-grounded tongue plus drawdown of an upstream basin by rapid flow) than can be accomplished by surface mass

balance alone. In its advancing phase, a tidewater terminus is stabilized by back-stress against a push moraine at its advancing margin. A tidewater glacier in an advanced position can switch abruptly (~years) to an unstable phase of thinning in its ocean-grounded reach, fast flow, and rapid calving which results in terminus retreat. Once initiated, fast flow and retreat can continue until the glacier's terminus retreats to a point where the glacier bed rises above sea level.

The causes of unstable retreat are not completely understood, but involve high basal water pressures tied to the depth of the glacier bed below sea level, rapid sliding, vertical thinning, and positive feedback between thinning and fast flow. The processes governing the size and rate of production of icebergs are extremely poorly known. Climate-induced thinning can play a critical role in initiating unstable retreat, but once initiated, unstable retreat is modulated by channel geometry and englacial and basal hydrology and is essentially independent of climate and surface mass balance.

References

- Abdalati, W., W. Krabill, E. Frederick, S. Manizade, C. Martin, J. Sonntag, R. Swift, R. Thomas, J. Yungel and R. Koerner, 2004. Elevation changes of ice caps in the Canadian Arctic Archipelago. *Journal of Geophysical Research-Earth Surface*, 109:F04007.
- ACIA, 2004. Impacts of a Warming Arctic. Arctic Climate Impact Assessment. pp. 140. Cambridge University Press.
- ACIA, 2005. Arctic Climate Impact Assessment. pp. 1024. Cambridge University Press.
- Aðalgeirsdóttir, G., T. Johannesson, H. Björnsson, F. Pálsson and O. Sigurðsson, 2006. Response of Hofsjökull and southern Vatnajökull, Iceland, to climate change. *Journal of Geophysical Research-Earth Surface*, 111:F03001.
- Alley, R.B., H.J. Horgan, I. Joughin, K.M. Cuffey, T.K. Dupont, B.R. Parizek, S. Anandakrishnan and J. Bassis, 2008. A simple law for ice-shelf calving. *Science*, 322:1344–1344.
- Amundson, J.M., M. Fahnestock, M. Truffer, J. Brown, M.P. Lüthi and R.J. Motyka, 2010. Ice mélange dynamics and implications for terminus stability, Jakobshavn Isbræ Greenland. *Journal of Geophysical Research-Earth Surface*, 115:F01005.
- Ananicheva, M.D. and G. Kapustin, 2010. Change of glacier state in mountain regions of the Russian sub-arctic: assessment by satellite imagery and aerial photography in the USSR glacier inventory [in Russian; English summary on last page]. Russian contribution into the IPY. 2007–2008. Vol.3 Cryosphere, pp. 19–26.
- Ananicheva, M.D. and A.N. Krenke, 2007. Glaciation and snow cover in North Eurasia in immediate future. In: Kotlyakov, V.M. (Ed.). *Glaciation in North Eurasia in the Recent Past and Immediate Future*, pp. 277–293, Nauka, Moscow.
- Ananicheva, M.D., G.A. Kapustin and M.M. Koreysha, 2006. Glacier changes in the Suntar-Khayata mountains and Chersky Range from the glacier inventory of the USSR and satellite images 2001–2003. *Data of Glaciological Studies*, 101:163–169.
- Ananicheva, M.D., A.N. Krenke, and R.G. Barry, 2010. The Northeast Asia mountain glaciers in the near future by AOGCM scenarios. *The Cryosphere*, 4:435–445.
- Anderson, S.P., 2007. Biogeochemistry of glacial landscape systems. *Annual Review of Earth and Planetary Sciences*, 35:375–399.
- Anderson, R.K., G.H. Miller, J.P. Briner, N.A. Lifton and S.B. DeVogel, 2008. A millennial perspective on Arctic warming from C-14 in quartz and plants emerging from beneath ice caps. *Geophysical Research Letters*, 35:L01502.
- Andreassen, L.M., H. Elvehøy, B. Kjølmoen, R.V. Engeset and N. Haakensen, 2005. Glacier mass-balance and length variation in Norway. *Annals of Glaciology*, 42:317–325.
- Anesio, A.M., A.J. Hodson, A. Fritz, R. Psenner and B. Sattler, 2009. High microbial activity on glaciers: importance to the global carbon cycle. *Global Change Biology*, 15:955–960.
- Anon, 2004. The Alaska Tourism Satellite Account. A comprehensive analysis of the economic contribution of travel and tourism. 24 pp. Global Insight,
- Arendt, A.A., K.A. Echelmeyer, W.D. Harrison, C.S. Lingle and V.B. Valentine, 2002. Rapid wastage of Alaska glaciers and their contribution to rising sea level. *Science*, 297:382–386.
- Arendt, A., K. Echelmeyer, W. Harrison, C. Lingle, S. Zirnheld, V. Valentine, B. Ritchie and M. Druckenmiller, 2006. Updated estimates of glacier volume changes in the western Chugach Mountains, Alaska, and a comparison of regional extrapolation methods. *Journal of Geophysical Research-Earth Surface*, 111:F03019.
- Arendt, A., J. Walsh and W. Harrison, 2009. Changes of glaciers and climate in northwestern North America during the late twentieth century. *Journal of Climate*, 22:4117–4134.
- Ashmore, P. and M. Church, 2001. The impact of climate change on rivers and river processes in Canada. *Geological Survey of Canada Bulletin*, 555:58.
- Bahr, D.B., M.F. Meier and S.D. Peckham, 1997. The physical basis of glacier volume-area scaling. *Journal of Geophysical Research-Solid Earth*, 102:20355–20362.
- Bakke, J., S.O. Dahl, Ø. Paasche, R. Løvlie and A. Nesje, 2005. Glacier fluctuations, equilibrium-line altitudes and palaeoclimate in Lyngen, northern Norway, during the Lateglacial and Holocene. *The Holocene*, 15:518–540.
- Bamber, J.L., S. Ekholm and W.B. Krabill, 2001. A new, high-resolution digital elevation model of Greenland fully validated with airborne laser altimeter data. *Journal of Geophysical Research-Solid Earth*, 106:6733–6745.
- Bamber, J., W. Krabill, V. Raper and J. Dowdeswell, 2004. Anomalous recent growth of part of a large Arctic ice cap: Austfonna, Svalbard. *Geophysical Research Letters*, 31:L12402.
- Barkov, N.I., D.Y. Bolshiyakov, O.A. Gvozdk, O.L. Klementyev, V.M. Makeyev, I.G. Maksimenko, V.Y. Potapenko and K.R.I. Yuna, 1992. New data on structure and development of Vavilov Glacier on Severnaya Zemlya [in Russian]. *Data of Glaciological Studies*, 75:35–41.
- Barrand, N.E. and M.J. Sharp, 2010. Sustained rapid shrinkage of Yukon glaciers since the 1957–1958 International Geophysical Year. *Geophysical Research Letters*, 37:L07501.
- Bassford, R.P., M.J. Siegert and J.A. Dowdeswell, 2006. Quantifying the mass balance of ice caps on Severnaya Zemlya, Russian High Arctic. III: Sensitivity of ice caps in Severnaya Zemlya to future climate change. *Arctic, Antarctic and Alpine Research*, 38:21–33.
- Benn, D.I., C.R. Warren and R.H. Mottram, 2007. Calving processes and the dynamics of calving glaciers. *Earth-Science Reviews*, 82:143–179.
- Benson, C.S., 1962. Stratigraphic studies in the snow and firn of Greenland ice sheet. CRREL (SIPRE) Research Report, 70, 93 pp.
- Berthier, E., E. Schiefer, G.K.C. Clarke, B. Menounos and F. Rémy, 2010. Contribution of Alaskan glaciers to sea-level rise derived from satellite imagery. *Nature Geoscience*, 3:92–95.
- Bindschadler, R., J. Dowdeswell, D. Hall and J.G. Winther, 2001. Glaciological applications with Landsat-7 imagery: early assessments. *Remote Sensing of Environment*, 78:163–179.
- Bitz, C.M. and D.S. Battisti, 1999. Interannual to decadal variability in climate and the glacier mass balance in Washington, western Canada, and Alaska. *Journal of Climate*, 12:3181–3196.
- Björnsson, H. and F. Pálsson, 2008. Icelandic glaciers. *Jökull*, 58:365–386.
- Björnsson, H., F. Pálsson, O. Sigurðsson and G.E. Flowers, 2003. Surges of glaciers in Iceland. *Annals of Glaciology*, 36:82–90.
- Blais, J.M., D.W. Schindler, D.C.G. Muir, M. Sharp, D. Donald, M. Lafrenière, E. Braekeveld and W.M.J. Strachan, 2001. Melting glaciers: A major source of persistent organochlorines to subalpine Bow Lake in Banff National Park, Canada. *Ambio*, 30:410–415.
- Blake, W., 1981. Neoglacial fluctuations of glaciers, southeastern Ellesmere Island, Canadian Arctic Archipelago. *Geografiska Annaler Series a-Physical Geography*, 63:201–218.
- Blake, W.J., 1989. Radiocarbon dating by accelerator mass spectrometry: A contribution to the chronology of Holocene events in Nordaustlandet, Svalbard. *Geografiska Annaler* 71A:51–74.
- Błaszczak, M., J.A. Jania and J.O. Hagen, 2009. Tidewater glaciers of Svalbard: Recent changes and estimates of calving fluxes. *Polish Polar Research*, 30:85–142.
- Bolch, T., B. Menounos and R. Wheate, 2010. Landsat-based inventory of glaciers in western Canada, 1985–2005. *Remote Sensing of Environment*, 114:127–137.

- Boon, S. and M. Sharp, 2003. The role of hydrologically-driven ice fracture in drainage system evolution on an Arctic glacier. *Geophysical Research Letters*, 30:1916.
- Boyd, E.S., M. Skidmore, A.C. Mitchell, C. Bakermans and J.W. Peters, 2010. Methanogenesis in subglacial sediments. *Environmental Microbiology Reports* 2:685-692.
- Brabets, T.P. and M.A. Walvoord, 2009. Trends in streamflow in the Yukon River Basin from 1944 to 2005 and the influence of the Pacific Decadal Oscillation. *Journal of Hydrology*, 371:108-119.
- Braithwaite, R.J., 2005. Mass-balance characteristics of arctic glaciers. *Annals of Glaciology*, 42:225-229.
- Brandt, O., J. Kohler and M. Luthje, 2008. Spatial mapping of multi-year superimposed ice on the glacier Kongsvegen, Svalbard. *Journal of Glaciology*, 54:73-80.
- Briner, J.P., P.T. Davis and G.H. Miller, 2009. Latest Pleistocene and Holocene glaciation of Baffin Island, Arctic Canada: key patterns and chronologies. *Quaternary Science Reviews*, 28:2075-2087.
- Brooks, G.R., 1994. The fluvial reworking of late Pleistocene drift, Squamish River drainage basin, southwest British Columbia. *Géographie physique et Quaternaire*, 48:51-68.
- Brown, C.S., M.F. Meier and A. Post, 1982. Calving speed of Alaska tidewater glaciers, with application to Columbia Glacier. USGS Professional Paper, 1258-C, 20 pp.
- Brown, L.E., D.M. Hannah and A.M. Milner, 2003. Alpine stream habitat classification: An alternative approach incorporating the role of dynamic water source contributions. *Arctic, Antarctic and Alpine Research*, 35:313-322.
- Burgess, D.O. and M.J. Sharp, 2004. Recent changes in areal extent of the Devon Ice Cap, Nunavut, Canada. *Arctic, Antarctic and Alpine Research*, 36:261-271.
- Burgess, D.O., M.J. Sharp, D.W.F. Mair, J.A. Dowdeswell and T.J. Benham, 2005. Flow dynamics and iceberg calving rates of Devon Ice Cap, Nunavut, Canada. *Journal of Glaciology*, 51:219-230.
- Buzin, I.V. and A.F. Glazovsky, 2005. Icebergs of Shokalsky glacier, Novaya Zemlya. *Data of Glaciological Studies*, 99:39-44.
- Buzin, I.V., A.F. Glazovsky, Y.P. Gudoshnikov, A.I. Danilov, N.Y. Dmitiev, G.K. Zubakin, N.V. Kubyshkin, A.K. Naumov, A.V. Nesterov, A.A. Skutin, E.A. Skutina and S.I. Shibakin, 2008. Icebergs and glaciers of the Barents Sea. Results of the most recent research. Part. I. Main producing glaciers, their propagation and morphometric properties. [in Russian with English summary]. *Problems of the Arctic and Antarctic*, 78:66-80.
- Cazenave, A., K. Dominh, S. Guinehut, E. Berthier, W. Llovel, G. Ramillien, M. Ablain and G. Larnicol, 2009. Sea level budget over 2003-2008: A reevaluation from GRACE space gravimetry, satellite altimetry and Argo. *Global and Planetary Change*, 65:83-88.
- Chapman, W.L. and J.E. Walsh, 2007. Simulations of Arctic temperature and pressure by global coupled models. *Journal of Climate*, 20:609-632.
- Chen, J.L., C.R. Wilson and B.D. Tapley, 2006. Satellite gravity measurements confirm accelerated melting of Greenland ice sheet. *Science*, 313:1958-1960.
- Church, M., 1974. Hydrology and permafrost with reference to North America. – Paper presented at Proceedings of Workshop Seminar 1974, Permafrost Hydrology, pp. 7-20. Canadian National Committee for the International Hydrological Decade, Ottawa
- Church, M., 1983. Pattern of instability in a wandering gravel bed channel. In: Collinson, J.D. and J. Lewin (Eds.). *Modern and Ancient Fluvial Systems*, pp. 169-180, International Association of Sedimentologists Special Publication,
- Citterio, M., F. Paul, A.P. Ahlstrom, H.F. Jepsen and A. Weidick, 2009. Remote sensing of glacier change in West Greenland: accounting for the occurrence of surge-type glaciers. *Annals of Glaciology*, 50:70-80.
- Clague, J.J. and S.G. Evans, 1994. Formation and failure of natural dams in the Canadian Cordillera. *Geological Survey of Canada, Bulletin* 464.
- Clague, J.J. and S.G. Evans, 2000. A review of catastrophic drainage of moraine-dammed lakes in British Columbia. *Quaternary Science Reviews*, 19:1763-1783.
- Clague, J., J.R. Harper, R.J. Hebda and D.E. Howes, 1982. Late Quaternary sea levels and crustal movements, coastal British Columbia. *Canadian Journal of Earth Sciences*, 19:597-618.
- Clague, J.J., R.J.W. Turner and A.V. Reyes, 2003. Record of recent river channel instability, Cheakamus Valley, British Columbia. *Geomorphology*, 53:317-332.
- Clarke, G.K.C., 2003. Hydraulics of subglacial outburst floods: new insights from the Spring-Hutter formulation. *Journal of Glaciology*, 49:299-313.
- Cogley, J.G., 2005. Mass and energy balances of glaciers and ice sheets. In: Anderson, M.G. (Ed.). *Encyclopedia of Hydrological Sciences*, pp. 2555-2573, Wiley.
- Cogley, J.G., 2009a. Geodetic and direct mass-balance measurements: comparison and joint analysis. *Annals of Glaciology*, 50:96-100.
- Cogley, J.G., 2009b. A more complete version of the World Glacier Inventory. *Annals of Glaciology*, 50:32-38.
- Cogley, J.G. and W.P. Adams, 1998. Mass balance of glaciers other than the ice sheets. *Journal of Glaciology*, 44:315-325.
- Cogley, J.G., W.P. Adams, M.A. Ecclestone, F. JungRothenhausler and C.S.L. Ommanney, 1996. Mass balance of White Glacier, Axel Heiberg island, NWT, Canada, 1960-91. *Journal of Glaciology*, 42:548-563.
- Cogley, J.G., R. Hock, L.A. Rasmussen, A.A. Arendt, A. Bauder, R.J. Braithwaite, P. Jansson, G. Kaser, M. Moller, L. Nicholson and M. Zemp, 2011. Glossary of Glacier Mass Balance and Related Terms. IHPVII Technical Documents in Hydrology No. 86, IACS Contribution No. 2, UNESCO-IHP.
- Colgan, W. and M. Sharp, 2008. Combined oceanic and atmospheric influences on net accumulation on Devon Ice Cap, Nunavut, Canada. *Journal of Glaciology*, 54:28-40.
- Copland, L., D.R. Mueller and L. Weir, 2007. Rapid loss of the Ayles ice shelf, Ellesmere Island, Canada. *Geophysical Research Letters*, 34:L21501.
- Copland, L., M.J. Sharp and J.A. Dowdeswell, 2003. The distribution and flow characteristics of surge-type glaciers in the Canadian High Arctic. *Annals of Glaciology*, 36:73-81.
- Costa, J.E. and R.L. Schuster, 1988. The formation and failure of natural dams. *Geological Society of America Bulletin*, 100:1054-1068.
- D'Elia, T., R. Veerapaneni and S.O. Rogers, 2008. Isolation of microbes from Lake Vostok accretion ice. *Applied and Environmental Microbiology*, 74:4962-4065.
- Dahl, T.M., C. Lydersen, K.M. Kovacs, S. Falk-Petersen, J. Sargent, I. Gjertz and B. Gulliksen, 2000. Fatty acid composition of the blubber in white whales (*Delphinapterus leucas*). *Polar Biology*, 23:401-409.
- De Ruyter de Wildt, M.S. and J. Oerlemans, 2003. Satellite retrieval of mass balance: comparing SAR images with albedo images and in situ mass-balance observations. *Journal of Glaciology*, 49:437-448.
- De Ruyter de Wildt, M.S., J. Oerlemans and H. Björnsson, 2002. A method for monitoring glacier mass balance using satellite albedo measurements: application to Vatnajökull, Iceland. *Journal of Glaciology*, 48:267-278.
- de Woul, M. and R. Hock, 2005. Static mass-balance sensitivity of Arctic glaciers and ice caps using a degree-day approach. *Annals of Glaciology*, 42:217-224.
- Desloges, J.R. and M. Church, 1987. Channel and floodplain facies in a wandering gravel-bed river. In: Ethridge, F.G. and R.M. Flores (Eds.). *Recent Developments in Fluvial Sedimentology*, pp. 99-109.
- Divine, D.V. and C. Dick, 2006. Historical variability of sea ice edge position in the Nordic Seas. *Journal of Geophysical Research-Oceans*, 111:C01001.
- Dmitriev, N.Y. and A.V. Nesterov, 2007. Iceberg drift in the Barents Sea according to observation data and simulation results. – Paper presented at The 17th International Offshore and Polar Engineering Conference (ISOPE-2007), pp. 633-638. The International Society of Offshore and Polar Engineers, Lisbon, Portugal, July 1-6, 2007.
- Dorava, J.M. and A.M. Milner, 2000. Role of lake regulation on glacier-fed rivers in enhancing salmon productivity: the Cook Inlet watershed, south-central Alaska, USA. *Hydrological Processes*, 14:3149-3159.
- Dowdeswell, J.A., 1986. Remote sensing of ice cap outlet glacier fluctuations on Nordaustlandet, Svalbard. *Polar Research*, 4:25-32.
- Dowdeswell, J.A., 1989. On the nature of Svalbard icebergs. *Journal of Glaciology*, 35:224-234.
- Dowdeswell, J.A. and T.J. Benham, 2003. A surge of Perseibreen, Svalbard, examined using aerial photographs and ASTER high-resolution satellite imagery. *Polar Research*, 22:373-383.
- Dowdeswell, J.A. and R. L. Collin, 1990. Fast-flowing outlet glaciers on Svalbard ice caps. *Geology*, 18:778-781.
- Dowdeswell, J.A. and S. Evans, 2004. Investigations of the form and flow of ice sheets and glaciers using radio-echo sounding. *Reports on Progress in Physics*, 67:1821-1861.

- Dowdeswell, J.A. and C.F. Forsberg, 1992. The size and frequency of icebergs and bergy bits from tidewater glaciers in Kongsfjorden, northwest Spitsbergen. *Polar Research*, 11:81-91.
- Dowdeswell, J.A. and J.-O. Hagen, 2004. Arctic ice caps and glaciers. In: Bamber, J.L. and A.J. Payne (Eds.). *Mass Balance of the Cryosphere: Observations and Modelling of Contemporary and Future Changes*, pp. 527- 557, Cambridge University Press.
- Dowdeswell, J.A. and M. Williams, 1997. Surge-type glaciers in the Russian High Arctic identified from digital satellite imagery. *Journal of Glaciology*, 43:489-494.
- Dowdeswell, J.A., G.S. Hamilton and J.O. Hagen, 1991. The duration of the active phase on surge-type glaciers - contrasts between Svalbard and other regions. *Journal of Glaciology*, 37:388-400.
- Dowdeswell, J.A., R.J. Whittington and R. Hodgkins, 1992. The sizes, frequencies, and freeboards of East Greenland icebergs observed using ship radar and sextant. *Journal of Geophysical Research-Oceans*, 97:3515-3528.
- Dowdeswell, J.A., H. Villinger, R. J. Whittington and P. Marienfeld, 1993. Iceberg scouring in Scoresby Sund and on the East Greenland continental shelf. *Marine Geology*, 111:37-53.
- Dowdeswell, J.A., M.R. Gorman, A.F. Glazovsky and Y.Y. Macheret, 1994. Evidence for floating ice shelves in Franz Josef Land, Russian High Arctic. *Arctic and Alpine Research*, 26:86-92.
- Dowdeswell, J.A., R. Hodgkins, A.M. Nuttall, J.-O. Hagen and G.S. Hamilton, 1995. Mass balance change as a control on the frequency and occurrence of glacier surges in Svalbard, Norwegian High Arctic. *Geophysical Research Letters*, 22:2909-2912.
- Dowdeswell, J.A., J.O. Hagen, H. Björnsson, A.F. Glazovsky, W.D. Harrison, P. Holmlund, J. Jania, R.M. Koerner, B. Lefauconnier, C.S.L. Ommanney and R.H. Thomas, 1997. The mass balance of circum-Arctic glaciers and recent climate change. *Quaternary Research*, 48:1-14.
- Dowdeswell, J.A., R.J. Whittington, A. E. Jennings, J.T. Andrews, A. Mackensen and P. Marienfeld, 2000. An origin for laminated glacialine sediments through sea-ice build-up and suppressed iceberg rafting. *Sedimentology*, 47:557-576.
- Dowdeswell, J.A., R.P. Bassford, M.R. Gorman, M. Williams, A.F. Glazovsky, Y.Y. Macheret, A.P. Shepherd, Y.V. Vasilenko, L.M. Savatuyguin, H.W. Hubberten and H. Miller, 2002. Form and flow of the Academy of Sciences Ice Cap, Severnaya Zemlya, Russian High Arctic. *Journal of Geophysical Research-Solid Earth*, 107:2076.
- Dowdeswell, J.A., T.J. Benham, M.R. Gorman, D. Burgess and M.J. Sharp, 2004. Form and flow of the Devon Island Ice Cap, Canadian Arctic. *Journal of Geophysical Research-Earth Surface*, 109:F02002.
- Dowdeswell, E.K., J.A. Dowdeswell and F. Cawkwell, 2007. On the glaciers of Bylot Island, Nunavut, Arctic Canada. *Arctic, Antarctic and Alpine Research*, 39:402-411.
- Dowdeswell, J.A., T.J. Benham, T. Strozzi and J.O. Hagen, 2008. Iceberg calving flux and mass balance of the Austfonna ice cap on Nordaustlandet, Svalbard. *Journal of Geophysical Research-Earth Surface*, 113:F03022.
- Dunse, T., T.V. Schuler, J.O. Hagen, T. Eiken, O. Brandt and K.A. Hogda, 2009. Recent fluctuations in the extent of the firn area of Austfonna, Svalbard, inferred from GPR. *Annals of Glaciology*, 50:155-162.
- Dwyer, J.L., 1995. Mapping tide-water glacier dynamics in east Greenland using LANDSAT data. *Journal of Glaciology*, 41:584-595.
- Dyke, A.S., 1978. Indications of neoglaciation on Somerset Island, District of Franklin. *Scientific and Technical Notes, Current Research, Part B. Geological Survey of Canada*, 78-1B:215-217.
- Dyrgerov, M.B., 2002. Glacier mass balance and regime: data of measurements and analysis. *Occasional Paper 55*, 268 pp. Institute of Arctic and Alpine Research, University of Colorado, Boulder.
- Dyrgerov, M.B. and M.F. Meier, 2005. Glaciers and the changing earth system: a 2004 snapshot. *Occasional Paper 58*, 118 pp. Institute of Arctic and Alpine Research, University of Colorado, Boulder.
- Dyrgerov, M., V.N. Uvarov and T.E. Kostjashkina, 1996. Mass balance and runoff of Tuyuksu glacier and the north slope of the Zailiyskiy Alatau Range, Tien Shan. *Zeitschrift für Gletscherkunde und Glazialgeologie*, 32:41-54.
- Dyrgerov, M., M.F. Meier and D.B. Bahr, 2009. A new index of glacier area change: a tool for glacier monitoring. *Journal of Glaciology*, 55:710-716.
- Early, D.S. and D.G. Long, 2001. Image reconstruction and enhanced resolution imaging from irregular samples. *Ieee Transactions on Geoscience and Remote Sensing*, 39:291-302.
- Echelmeyer, K.A., W.D. Harrison, C.F. Larsen, J. Sapiano, J.E. Mitchell, J. DeMallie, B. Rabus, G. Aðalgeirsdóttir and L. Sombardier, 1996. Airborne surface profiling of glaciers: A case-study in Alaska. *Journal of Glaciology*, 42:538-547.
- Eisen, O., W.D. Harrison and C.F. Raymond, 2001. The surges of Variegated Glacier, Alaska, USA, and their connection to climate and mass balance. *Journal of Glaciology*, 47:351-358.
- Engeset, R.V., J. Kohler, K. Melvold and B. Lunden, 2002. Change detection and monitoring of glacier mass balance and facies using ERS SAR winter images over Svalbard. *International Journal of Remote Sensing*, 23:2023-2050.
- England, J., N. Atkinson, J. Bednarski, A.S. Dyke, D.A. Hodgson and C.O. Cofaigh, 2006. The Innuitian Ice Sheet: configuration, dynamics and chronology. *Quaternary Science Reviews*, 25:689-703.
- England, J.H., T.R. Lakanen, D.S. Lemmen, J.M. Bednarski, T.G. Stewart and D.J.A. Evans, 2008. A millennial-scale record of Arctic Ocean sea ice variability and the demise of the Ellesmere Island ice shelves. *Geophysical Research Letters*, 35:L19502.
- Erga, S.R., K. Aursland, O. Frette, B. Hamre, J.K. Lotsberg, J.J. Stamnes, J. Aure, F. Rey and K. Stamnes, 2005. UV transmission in Norwegian marine waters: controlling factors and possible effects on primary production and vertical distribution of phytoplankton. *Marine Ecology Progress Series*, 305:79-100.
- ESRI, 2003. *Digital Chart of the World: for use with ARC/INFO software*. 4 laser optical disks. 220 pp. Environmental Systems Research Institute, USA.
- Evans, S.G. and J.J. Clague, 1994. Recent climatic change and catastrophic geomorphic processes in mountain environments. *Geomorphology*, 10:107-128.
- Ficke, A.D., C.A. Myrick and L.J. Hansen, 2007. Potential impacts of global climate change on freshwater fisheries. *Reviews in Fish Biology and Fisheries*, 17:581-613.
- Filippelli, G.M., C. Souch, B. Menounos, S. Slater-Atwater, A.J.T. Jull and O. Slaymaker, 2006. Alpine lake sediment records of the impact of glaciation and climate change on the biogeochemical cycling of soil nutrients. *Quaternary Research*, 66:158-166.
- Fischer, M.P. and R.D. Powell, 1998. A simple model for the influence of push-moraine banks on the calving and stability of glacial tidewater termini. *Journal of Glaciology*, 44:31-41.
- Fisher, D.A., 2002. High-resolution multiproxy climatic records from icecores, tree-rings, corals and documentary sources using eigenvector techniques and maps: assessment of recovered signal and errors. *The Holocene*, 12:401-419.
- Fisher, D.A., R.M. Koerner, W.S.B. Paterson, W. Dansgaard, N. Gundestrup and N. Reeh, 1983. Effect of wind scouring on climatic records from ice-core oxygen-isotope profiles. *Nature*, 301:205-209.
- Fisher, D.A., R.M. Koerner and N. Reeh, 1995. Holocene climatic records from Agassiz Ice Cap, Ellesmere Island, NWT, Canada. *The Holocene*, 5:19-24.
- Fisher, D.A., R.M. Koerner, J.C. Bourgeois, G. Zielinski, C. Wake, C.U. Hammer, H.B. Clausen, N. Gundestrup, S. Johnsen, K. Goto-Azuma, T. Hondoh, E. Blake and M. Gerasimoff, 1998. Penny ice cap cores, Baffin Island, Canada, and the Wisconsin Foxe Dome connection: Two states of Hudson Bay ice cover. *Science*, 279:692-695.
- Fisher, D., E. Osterberg, A. Dyke, D. Dahl-Jensen, M. Demuth, C. Zdanowicz, J. Bourgeois, R.M. Koerner, P. Mayewski, C. Wake, K. Kreutz, E. Steig, J. Zheng, K. Yalcin, K. Goto-Azuma, B. Luckman and S. Rupper, 2008. The Mt Logan Holocene-late Wisconsinan isotope record: tropical Pacific-Yukon connections. *The Holocene*, 18:667-677.
- Fleming, S.W., 2005. Comparative analysis of glacial and nival streamflow regimes with implications for lotic habitat quantity and fish species richness. *River Research and Applications*, 21:363-379.
- Fleming, S.W. and G.K.C. Clarke, 2003. Glacial control of water resource and related environmental responses to climatic warming, empirical analysis using historical streamflow data from northwestern Canada. *Canadian Water Resources Journal* 28:69-86.
- Fleming, S.W. and G.K.C. Clarke, 2005. Attenuation of high-frequency interannual streamflow variability by watershed glacial cover. *ASCE-Journal of Hydraulic Engineering*, 131:615-618.
- Flowers, G.E., S.J. Marshall, H. Björnsson and G.K.C. Clarke, 2005. Sensitivity of Vatnajökull ice cap hydrology and dynamics to climate warming over the next 2 centuries. *Journal of Geophysical Research-Earth Surface*, 110:F02011.

- Førland, E.J. and I. Hanssen-Bauer, 2003. Past and future climate variations in the Norwegian Arctic: overview and novel analyses. *Polar Research*, 22:113–124.
- Forsström, S., J. Strom, C.A. Pedersen, E. Isaksson and S. Gerland, 2009. Elemental carbon distribution in Svalbard snow. *Journal of Geophysical Research-Atmospheres*, 114:8.
- Fountain, A.G. and J.S. Walder, 1998. Water flow through temperate glaciers. *Reviews of Geophysics*, 36:299–328.
- Fox, A.J. and A.P.R. Cooper, 1994. Measured properties of the Antarctic Ice Sheet derived from the SCAR Antarctic digital database. *Polar Record*, 30:201–206.
- Freitas, C., K.M. Kovacs, R.A. Ims, M.A. Fedak and C. Lydersen, 2008. Ringed seal post-moulting movement tactics and habitat selection. *Oecologia*, 155:193–204.
- Fritzsche, D., R. Schütt, H. Meyer, H. Miller, F. Wilhelms, T. Opel and L.M. Savatugin, 2005. A 275 year ice-core record from Akademii Nauk ice cap, Severnaya Zemlya, Russian Arctic. *Annals of Glaciology*, 42:361–366.
- Füreder, L., 2007. Life at the edge: Habitat condition and bottom fauna of Alpine running waters. *International Review of Hydrobiology*, 92:491–513.
- Gaidos, E., B. Lanoil, T. Thorsteinsson, A. Graham, M. Skidmore, S.K. Han, T. Rust and B. Popp, 2004. A viable microbial community in a subglacial volcanic crater lake, Iceland. *Astrobiology*, 4:327–344.
- Gaidos, E., V. Marteinsson, T. Thorsteinsson, T. Jóhannesson, A.R. Runarsson, A. Stefansson, B. Glazer, B. Lanoil, M. Skidmore, S. Han, M. Miller, A. Rusch and W. Foo, 2009. An oligarchic microbial assemblage in the anoxic bottom waters of a volcanic subglacial lake. *Isme Journal*, 3:486–497.
- Gardner, A.S. and M. Sharp, 2007. Influence of the arctic circumpolar vortex on the mass balance of Canadian High Arctic glaciers. *Journal of Climate*, 20:4586–4598.
- Gardner, A.S. and M. Sharp, 2009. Sensitivity of net mass-balance estimates to near-surface temperature lapse rates when employing the degree-day method to estimate glacier melt. *Annals of Glaciology*, 50:80–86.
- Gardner, A.S., M.J. Sharp, R.M. Koerner, C. Labine, S. Boon, S.J. Marshall, D.O. Burgess and D. Lewis, 2009. Near-surface temperature lapse rates over Arctic glaciers and their implications for temperature downscaling. *Journal of Climate*, 22:4281–4298.
- Geirsdóttir, A., G.H. Miller, Y. Axford and S. Olafsdóttir, 2009. Holocene and latest Pleistocene climate and glacier fluctuations in Iceland. *Quaternary Science Reviews*, 28:2107–2118.
- Glasser, N.F. and M.J. Hambrey, 2001. Styles of sedimentation beneath Svalbard valley glaciers under changing dynamic and thermal regimes. *Journal of the Geological Society*, 158:697–707.
- Glazovsky, A.F., 2003. Glacier dynamics. In: Bobylev, L.P., K.Y. Kondratyev and O.M. Johannessen (Eds.). *Arctic Environmental Variability in the Context of Global Change*, pp. 251–270, Praxis Publishing Ltd.
- Glazovsky, A. and Y. Macheret, 2006. Eurasian Arctic. In: Kotlyakov, V.M. (Ed.). *Glaciation in north and central Eurasia in present time*. [in Russian with English summary], pp. 97–114 and 438–445, Nauka, Moscow.
- Glazovsky, A.F., G.A. Nosenko and D.G. Tsvetkov, 2007. Glaciers of Urals. Current and future state. *Data of Glaciological Studies* 98:207–214.
- Gottesfeld, A.S. and L.M. Johnson-Gottesfeld, 1990. Floodplain dynamics of a wandering river, dendrochronology of the Morice River, British Columbia, Canada. *Geomorphology*, 3:159–179.
- Govorukha, L.S., 1989. Modern glaciation of the Soviet Arctic. 256 pp. *Gidrometeoizdat / Hydrometeoizdat*, Leningrad.
- Grant, K.L., C.R. Stokes and I.S. Evans, 2009. Identification and characteristics of surge-type glaciers on Novaya Zemlya, Russian Arctic. *Journal of Glaciology*, 55:960–972.
- Gregor, D.J. and W.D. Gummer, 1989. Evidence of atmospheric transport and deposition of organochlorine pesticides and polychlorinated biphenyls in Canadian Arctic snow. *Environmental Science & Technology*, 23:561–565.
- Greuell, W. and W.H. Knap, 2000. Remote sensing of the albedo and detection of the slush line on the Greenland ice sheet. *Journal of Geophysical Research-Atmospheres*, 105:15567–15576.
- Greuell, W., J. Kohler, F. Obleitner, P. Glowacki, K. Melvold, E. Bernsen and J. Oerlemans, 2007. Assessment of interannual variations in the surface mass balance of 18 Svalbard glaciers from the Moderate Resolution Imaging Spectroradiometer/Terra albedo product. *Journal of Geophysical Research-Atmospheres*, 112:D07105.
- Grinsted, A., J.C. Moore, V. Pohjola, T. Martma and E. Isaksson, 2006. Svalbard summer melting, continentality, and sea ice extent from the Lomonosovfonna ice core. *Journal of Geophysical Research-Atmospheres*, 111:D07110.
- Hagen, J.O. and O. Liestøl, 1990. Long-term glacier mass-balance investigations in Svalbard, 1950–88. *Annals of Glaciology*, 14:102–106.
- Hagen, J.O., O. Liestøl, E. Roland and T. Jørgensen, 1993. *Glacier Atlas of Svalbard and Jan Mayen*. Norsk Polarinstitutt Meddelelser 129, 160 pp.
- Hagen, J.O., J. Kohler, K. Melvold and J.G. Winther, 2003a. Glaciers in Svalbard: mass balance, runoff and fresh water flux. *Polar Research* 22:145–159.
- Hagen, J.O., K. Melvold, F. Pinglot and J.A. Dowdeswell, 2003b. On the net mass balance of the glaciers and ice caps in Svalbard, Norwegian Arctic. *Arctic Antarctic and Alpine Research*, 35:264–270.
- Hall, D.K., J.P. Ormsby, R.A. Bindschadler and H. Siddalingaiah, 1987. Characterization of snow and ice reflectance zones on glaciers using Landsat thematic mapper data. *Annals of Glaciology*, 9:104–108.
- Hall, D.K., R.S. Williams, K. Steffen and J.Y.L. Chien, 2004. Analysis of summer 2002 melt extent on the Greenland ice sheet using MODIS and SSM/I data. Paper presented at IEEE International Symposium on Geoscience and Remote Sensing (IGARSS), pp. 3029–3032. Anchorage, Alaska, September 20–24 2004.
- Hall, D.K., R.S. Williams, K.A. Casey, N.E. DiGirolamo and Z. Wan, 2006. Satellite-derived, melt-season surface temperature of the Greenland Ice Sheet (2000–2005) and its relationship to mass balance. *Geophysical Research Letters*, 33:L11501.
- Hall, D.K., J.E. Box, K.A. Casey, S.J. Hook, C.A. Shuman and K. Steffen, 2008a. Comparison of satellite-derived and in-situ observations of ice and snow surface temperatures over Greenland. *Remote Sensing of Environment*, 112:3739–3749.
- Hall, D.K., R.S. Williams, S.B. Luthcke and N.E. DiGirolamo, 2008b. Greenland ice sheet surface temperature, melt and mass loss: 2000–06. *Journal of Glaciology*, 54:81–93.
- Hamilton, G.S. and J.A. Dowdeswell, 1996. Controls on glacier surging in Svalbard. *Journal of Glaciology*, 42:157–168.
- Hammer, C.U., S.J. Johnsen, H.B. Clausen, D. Dahl-Jensen, N. Gundestrup and J.-P. Steffensen, 2001. The palaeoclimatic record from a 345m long ice core from the Hans Tausen Iskappe. *Meddelelser om Grønland, Geoscience* 39:87–95.
- Hanelt, D., H. Tug, K. Bischof, C. Gross, H. Lippert, T. Sawall and C. Wiencke, 2001. Light regime in an Arctic fiord: a study related to stratospheric ozone depletion as a basis for determination of UV effects on algal growth. *Marine Biology*, 138:649–658.
- Hanson, B. and R.L. Hooke, 2000. Glacier calving: a numerical model of forces in the calving-speed/water-depth relation. *Journal of Glaciology*, 46:188–196.
- Hari, R.E., D.M. Livingstone, R. Siber, P. Burkhardt-Holm and H. Guttinger, 2006. Consequences of climatic change for water temperature and brown trout populations in Alpine rivers and streams. *Global Change Biology*, 12:10–26.
- Harper, J.T., N.F. Humphrey, W.T. Pfeffer and B. Lazar, 2007. Two modes of accelerated glacier sliding related to water. *Geophysical Research Letters*, 34:L12503.
- Hasholt, B. and S.H. Mernild, 2008. Hydrology, sediment transport and water resources of Ammassalik Island, SE Greenland. *Geografisk Tidsskrift-Danish Journal of Geography*, 108:73–95.
- Hasholt, B., J. Kruger and L. Skjerna, 2008. Landscape and sediment processes in a proglacial valley, the Mittivakkat Glacier area, Southeast Greenland. *Geografisk Tidsskrift-Danish Journal of Geography*, 108:97–110.
- Hattersley-Smith, G., 1963. The Ward Hunt Ice Shelf: recent changes in the ice front. *Journal of Glaciology*, 4:415–424.
- Hattersley-Smith, G., 1967. Note on ice shelves off the north coast of Ellesmere Island. *Arctic Circular*, 17:13–14.
- Hauer, F.R., J.S. Baron, D.H. Campbell, K.D. Fausch, S.W. Hostetler, G.H. Leavesley, P.R. Leavitt, D.M. McKnight and J.A. Stanford, 1997. Assessment of climate change and freshwater ecosystems of the Rocky Mountains, USA and Canada. *Hydrological Processes*, 11:903–924.
- Heinrichs, T., I. Mayo, D. Trabant and R. March, 1995. Observations of the surge-type Black Rapids Glacier, Alaska, during a quiescent period,

- 1970–92. US Geological Survey, Earth Science Information Center, Open-File Report, 94-512, 131 pp.
- Hermanson, M.H., E.H. Isaksson, C. Teixeira, D.C.G. Muir, K.M. Compther, Y.F. Li, I. Igarashi and K. Kamiyama, 2005. Current-use and legacy pesticide history in the Austfonna ice cap, Svalbard, Norway. *Environmental Science & Technology*, 39:8163–8169.
- Hinzman, L.D. and 34 others, 2005. Evidence and implications of recent climate change in northern Alaska and other arctic regions. *Climatic Change*, 72:251–298.
- Hock, R., V. Radić and M. de Woul, 2007a. Climate sensitivity of Storglaciären - An inter-comparison of mass balance models using ERA-40 reanalysis and regional climate model data. *Annals of Glaciology*, 46:342–348.
- Hock, R., D. Kootstra and C. Reijmer, 2007b. Deriving glacier mass balance from accumulation area ratio on Storglaciären, Sweden. *IAHS Publication*, 318:163–170.
- Hock, R., M. de Woul, V. Radić and M. Dyurgerov, 2009. Mountain glaciers and ice caps around Antarctica make a large sea-level rise contribution. *Geophysical Research Letters*, 36:L07501.
- Hodgkins, R., J.O. Hagen and S.E. Hamran, 1999. 20th century mass balance and thermal regime change at Scott Turnerbreen, Svalbard. *Annals of Glaciology*, 28:216–220.
- Hodson, A., P. Murnford and D. Lister, 2004. Suspended sediment and phosphorus in proglacial rivers: bioavailability and potential impacts upon the P status of ice-marginal receiving waters. *Hydrological Processes*, 18:2409–2422.
- Hodson, A.J., P.N. Mumford, J. Kohler and P.M. Wynn, 2005. The High Arctic glacial ecosystem: new insights from nutrient budgets. *Biogeochemistry*, 72:233–256.
- Hodson, A., A.M. Anesio, M. Tranter, A. Fountain, M. Osborn, J. Priscu, J. Laybourn-Parry and B. Sattler, 2008. Glacial ecosystems. *Ecological Monographs*, 78:41–67.
- Holdsworth, G., 1969. Flexure of a floating ice tongue. *Journal of Glaciology*, 8:385–397.
- Holland, D.M., R.H. Thomas, B. De Young, M.H. Ribergaard and B. Lyberth, 2008. Acceleration of Jakobshavn Isbræ triggered by warm subsurface ocean waters. *Nature Geoscience*, 1:659–664.
- Holm, K., M. Bovis and M. Jakob, 2004. The landslide response of alpine basins to post-Little Ice Age glacial thinning and retreat in southwestern British Columbia. *Geomorphology*, 57:201–216.
- Holmlund, P., 1993. Surveys of post-Little Ice Age glacier fluctuations in northern Sweden. *Zeitschrift für Gletscherkunde und Glazialgeologie* 29:1–13.
- Holmlund, P., P. Jansson and R. Pettersson, 2005. A re-analysis of the 58 year mass-balance record of Storglaciären, Sweden. *Annals of Glaciology*, 42:389–394.
- Holtzschner, J.-J. and A. Bauer, 1954. Contributions à la connaissance de l'Indlandsis du Groenland. *IAHS Publication* 39:244–296.
- Hood, E. and L. Berner, 2009. Effects of changing glacial coverage on the physical and biogeochemical properties of coastal streams in southeastern Alaska. *Journal of Geophysical Research-Biogeosciences*, 114:G03001.
- Hood, E. and D. Scott, 2008. Riverine organic matter and nutrients in southeast Alaska affected by glacial coverage. *Nature Geoscience*, 1:583–587.
- Hood, E., J. Fellman, R.G.M. Spencer, P.J. Hernes, R. Edwards, D. D'Amore and D. Scott, 2009. Glaciers as a source of ancient and labile organic matter to the marine environment. *Nature*, 462:1044–1047.
- Hooke, R.L., 1998. Principles of Glacier Mechanics. pp. 248. Prentice-Hall.
- Hooke, R.L. and H.B. Clausen, 1982. Wisconsin and holocene delta-18-O variations, Barnes Ice Cap, Canada. *Geological Society of America Bulletin*, 93:784–789.
- Hooke, R.L., G.W. Johnson, K.A. Brugger, B. Hanson and G. Holdsworth, 1987. Changes in mass balance, velocity, and surface profile along a flow line on Barnes Ice Cap, 1970–1984. *Canadian Journal of Earth Sciences*, 24:1550–1561.
- Howat, I.M., I. Joughin, S. Tulaczyk and S. Gogineni, 2005. Rapid retreat and acceleration of Helheim Glacier, east Greenland. *Geophysical Research Letters*, 32:L22502.
- Howat, I.M., I. Joughin, M. Fahnestock, B.E. Smith and T.A. Scambos, 2008. Synchronous retreat and acceleration of southeast Greenland outlet glaciers 2000–06: ice dynamics and coupling to climate. *Journal of Glaciology*, 54:646–660.
- Hughes, T.J., 1992. Theoretical calving rates from glaciers along ice walls grounded in water of variable depths. *Journal of Glaciology*, 38:282–294.
- Humlum, O., B. Elberling, A. Hormes, K. Fjorðheim, O.H. Hansen and J. Heinemeier, 2005. Late-Holocene glacier growth in Svalbard, documented by subglacial relict vegetation and living soil microbes. *The Holocene*, 15:396–407.
- Huss, M., R. Stöckli, G. Kappenberger and H. Blatter, 2008. Temporal and spatial changes of Laika Glacier, Canadian Arctic, since 1959, inferred from satellite remote sensing and mass-balance modelling. *Journal of Glaciology*, 54:857–866.
- Ilg, C. and E. Castella, 2006. Patterns of macroinvertebrate traits along three glacial stream continuums. *Freshwater Biology*, 51:840–853.
- Isaksson, E., D. Divine, J. Kohler, T. Martma, V. Pohjola, H. Motoyama and O. Watanabe, 2005. Climate oscillations as recorded in Svalbard ice core delta O-18 records between AD 1200 and 1997. *Geografiska Annaler Series a-Physical Geography*, 87A:203–214.
- Isaksson, E., M. Hermanson, H.C. Sheila, M. Igarashi, K. Kamiyama, J. Moore, H. Motoyama, D. Muir, V. Pohjola, R. Vaikmäe, R.S.W. van de Wal and O. Watanabe, 2003. Ice cores from Svalbard - useful archives of past climate and pollution history. *Physics and Chemistry of the Earth*, 28:1217–1228.
- Jansson, P., G. Rosqvist and T. Schneider, 2005. Glacier fluctuations, suspended sediment flux and glacio-lacustrine sediments. *Geografiska Annaler Series a-Physical Geography*, 87A:37–50.
- Jeffries, M.O., 1992. Arctic ice shelves and ice islands: Origin, growth and disintegration, physical characteristics, structural-stratigraphic variability, and dynamics. *Reviews of Geophysics*, 30:245–267.
- Jiskoot, H. and D.T. Juhlin, 2009. Surge of a small East Greenland glacier, 2001–2007, suggests Svalbard-type surge mechanism. *Journal of Glaciology*, 55:567–570.
- Jiskoot, H., P. Boyle and T. Murray, 1998. The incidence of glacier surging in Svalbard: Evidence from multivariate statistics. *Computers & Geosciences*, 24:387–399.
- Jiskoot, H., A.K. Pedersen and T. Murray, 2001. Multi-model photogrammetric analysis of the 1990s surge of Sortebræ, East Greenland. *Journal of Glaciology*, 47:677–687.
- Johannessen, K., S. Loiset and P. Strass, 1999. Simulation of Iceberg Drift. – Paper presented at The 15th International Conference on Port and Ocean Engineering Under Arctic Conditions, (POAC-99), pp. 97–105. Espoo, Finland, August 23–27 1999.
- Jóhannesson, T., G. Aðalgeirsdóttir, A. Ahlström, L.M. Andreassen, H. Björnsson, M. de Woul, H. Elvehøy, G.E. Flowers, S. Guðmundsson, R. Hock, P. Holmlund, F. Pálsson, V. Radić, Ö. Sigurðsson and T. Thorsteinsson, 2006. The impact of climate change on glaciers and glacial runoff in the Nordic countries. Paper presented at The European Conference on Impacts of Climate Change on Renewable Energy Sources, pp. 30. CE-2, Hydrological Service, National Energy Authority, Reykjavik, Iceland, May 31 – June 2.
- Jónsdóttir, J.F., 2008. A runoff map based on numerically simulated precipitation and a projection of future runoff in Iceland. *Hydrological Sciences Journal-Journal Des Sciences Hydrologiques*, 53:100–111.
- Josberger, E.G., W.R. Bidlake, R.S. March and B.W. Kennedy, 2007. Glacier mass balance fluctuations in the Pacific Northwest and Alaska, USA. *Annals of Glaciology*, 46:291–296.
- Joughin, I., 2002. Ice-sheet velocity mapping: a combined interferometric and speckle-tracking approach. *Annals of Glaciology*, 34:195–201.
- Joughin, I., L. Gray, R. Bindshadler, S. Price, D. Morse, C. Hulbe, K. Mattar and C. Werner, 1999. Tributaries of West Antarctic Ice streams revealed by RADARSAT interferometry. *Science*, 286:283–286.
- Kalnay, E., M. Kanamitsu, R. Kistler, W. Collins, D. Deaven, L. Gandin, M. Iredell, S. Saha, G. White, J. Woollen, Y. Zhu, M. Chelliah, W. Ebisuzaki, W. Higgins, J. Janowiak, K.C. Mo, C. Ropelewski, J. Wang, A. Leetmaa, R. Reynolds, R. Jenne and D. Joseph, 1996. The NCEP/NCAR 40-year reanalysis project. *Bulletin of the American Meteorological Society*, 77:437–471.
- Karlén, W., 1976. Lacustrine sediments and tree limit variations as indicators of Holocene climatic fluctuations in Lapland, northern Sweden. *Geografiska Annaler Series a-Physical Geography*, 58:1–34.
- Karlén, W., 1988. Scandinavian glacial and climatic fluctuations during the Holocene. *Quaternary Science Reviews*, 7:199–209.
- Karlén, W. and J.A. Matthews, 1992. Reconstructing Holocene glacier variations from glacial lake sediments: studies from Nordvestlandet and Jostedalbreen-Jotunheimen, southern Norway. *Geografiska Annaler* 74:327–348.

- Kaser, G., J.G. Cogley, M.B. Dyurgerov, M.F. Meier and A. Ohmura, 2006. Mass balance of glaciers and ice caps: Consensus estimates for 1961-2004. *Geophysical Research Letters*, 33:L19501.
- Kattsov, V.M., J.E. Walsh, W.L. Chapman, V.A. Govorkova, T.V. Pavlova and X.D. Zhang, 2007. Simulation and projection of arctic freshwater budget components by the IPCC AR4 global climate models. *Journal of Hydrometeorology*, 8:571-589.
- Kaufman, D.S. and 28 others, 2004. Holocene thermal maximum in the western Arctic (0-180 degrees W). *Quaternary Science Reviews*, 23:529-560.
- Kaufman, D.S., D.P. Schneider, N.P. McKay, C.M. Ammann, R.S. Bradley, K.R. Briffa, G.H. Miller, B.L. Otto-Bliesner, J.T. Overpeck, B.M. Vinther and M. Arctic Lakes 2k Project, 2009. Recent warming reverses long-term Arctic cooling. *Science*, 325:1236-1239.
- Kelly, M.A. and T.V. Lowell, 2009. Fluctuations of local glaciers in Greenland during latest Pleistocene and Holocene time. *Quaternary Science Reviews*, 28:2088-2106.
- Key, J. and M. Haeffliger, 1992. Arctic ice surface temperature retrieval from AVHRR thermal channels. *Journal of Geophysical Research-Atmospheres*, 97:5885-5893.
- Key, J.R., J.B. Collins, C. Fowler and R.S. Stone, 1997. High-latitude surface temperature estimates from thermal satellite data. *Remote Sensing of Environment*, 61:302-309.
- Killingtveit, Å., L.E. Pettersson and K. Sand, 2003. Water balance investigations in Svalbard. *Polar Research*, 22:161-174.
- Kinnard, C., R.M. Koerner, C.M. Zdanowicz, D.A. Fisher, J. Zheng, M.J. Sharp, L. Nicholson and B. Lauriol, 2008. Stratigraphic analysis of an ice core from the Prince of Wales Icefield, Ellesmere Island, Arctic Canada, using digital image analysis: High-resolution density, past summer warmth reconstruction, and melt effect on ice core solid conductivity. *Journal of Geophysical Research-Atmospheres*, 113:D24120.
- Koenig, L.S., K.R. Greenaway, M. Dunbar and G. Hattersley-Smith, 1952. Arctic ice islands. *Arctic* 5:67-103.
- Koerner, R.M., 1970. Some observations on superimposition of ice on the Devon Island Ice Cap, N. W.T., Canada. *Geografiska Annaler*, 52A:57-67.
- Koerner, R.M., 1997. Some comments on climatic reconstructions from ice cores drilled in areas of high melt. *Journal of Glaciology*, 43:90-97.
- Koerner, R.M., 2005. Mass balance of glaciers in the Queen Elizabeth Islands, Nunavut, Canada. *Annals of Glaciology*, 42:417-423.
- Koerner, R.M. and D.A. Fisher, 1982. Acid snow in the Canadian High Arctic. *Nature*, 295:137-140.
- Koerner, R.M. and D.A. Fisher, 1990. A record of Holocene summer climate from a Canadian High-Arctic ice core. *Nature*, 343:630-631.
- Koerner, R.M. and D.A. Fisher, 2002. Ice-core evidence for widespread Arctic glacier retreat in the Last Interglacial and the early Holocene. *Annals of Glaciology*, 35:19-24.
- Kohler, J., T.D. James, T. Murray, C. Nuth, O. Brandt, N.E. Barrand, H.F. Aas and A. Luckman, 2007. Acceleration in thinning rate on western Svalbard glaciers. *Geophysical Research Letters*, 34:L18502.
- König, M., J. Wadham, J.-G. Winther, J. Kohler and A.-M. Nuttall, 2002. Detection of superimposed ice on the glaciers Kongsvegen and Midre Lovénbreen, Svalbard, using SAR satellite imagery. *Annals of Glaciology*, 34:335-342.
- Kononov, Y.M., M.D. Ananicheva and I.C. Willis, 2005. High-resolution reconstruction of Polar Ural glacier mass balance for the last millennium. *Annals of Glaciology*, 42:163-170.
- Kotlyakov, V.M., V.I. Nikolaev, I.M. Korotkov and O.L. Klementyev, 1991. Climate-stratigraphy of Severnaya Zemlya ice domes in the Holocene. In: Khudyakov, G.I. (Ed.). *Stratigraphy and Correlation of Quaternary deposits of Asia and Pacific region*, pp. 100-112, Nauka, Moscow.
- Krenke, A.N., 1982. Mass exchange of glacier systems over the USSR territory [in Russian with English summary]. *Hydrometeoizdat*, 5:1-93-101.
- Krimmel, R.M., 2001. Photogrammetric data set, 1957- 2000, and bathymetric measurements for Columbia Glacier, Alaska. U.S. Geological Survey Water Resources Investigation Report, 01-4089, 49 pp. U.S. Geological Survey,
- Results of airborne and direct studies during the IPY 2007/08. Paper presented at The 19th International Offshore and Polar Engineering Conference (ISOPE-2009), pp. 539-543. Osaka, Japan, June 21-26, 2009.
- Labansen, A.L., C. Lydersen, T. Haug and K.M. Kovacs, 2007. Spring diet of ringed seals (*Phoca hispida*) from northwestern Spitsbergen, Norway. *ICES Journal of Marine Science*, 64:1246-1256.
- Lafrenière, M.J. and M.J. Sharp, 2005. A comparison of solute fluxes and sources from glacial and non-glacial catchments over contrasting melt seasons. *Hydrological Processes*, 19:2991-3012.
- Lafrenière, M.J., J.M. Blais, M.J. Sharp and D.W. Schindler, 2006. Organochlorine pesticide and polychlorinated biphenyl concentrations in snow, snowmelt, and runoff at Bow Lake, Alberta. *Environmental Science & Technology*, 40:4909-4915.
- Lamoureux, S., 2000. Five centuries of interannual sediment yield and rainfall-induced erosion in the Canadian High Arctic recorded in lacustrine varves. *Water Resources Research*, 36:309-318.
- Landvik, J.Y., A. Weidick and A. Hansen, 2001. The glacial history of the Hans Tausen Iskappe and the last glaciation of Peary Land, North Greenland. *Meddelelser om Grønland, Geoscience* 39:27-44.
- Langley, K., S.E. Hamran, K.A. Hogda, R. Storvold, O. Brandt, J. Kohler and J.O. Hagen, 2008. From glacier facies to SAR backscatter zones via GPR. *IEEE Transactions on Geoscience and Remote Sensing*, 46:2506-2516.
- Larsen, C.F., R.J. Motyka, J.T. Freymueller, K.A. Echelmeyer and E.R. Ivins, 2005. Rapid viscoelastic uplift in southeast Alaska caused by post-Little Ice Age glacial retreat. *Earth and Planetary Science Letters*, 237:548-560.
- Larsen, C.F., R.J. Motyka, A.A. Arendt, K.A. Echelmeyer and P.E. Geissler, 2007. Glacier changes in southeast Alaska and northwest British Columbia and contribution to sea level rise. *Journal of Geophysical Research-Earth Surface*, 112:F01007.
- Lefauconnier, B. and J.O. Hagen, 1991. Surging and calving glaciers in eastern Svalbard. *Norsk Polarinstitut Meddelelser*, 116, 130 pp.
- Leonard, E.M., 1986. Varve studies at Hector Lake, Alberta, Canada, and the relationship between glacial activity and sedimentation. *Quaternary Research*, 25:199-214.
- Leonard, E.M., 1997. The relationship between glacial activity and sediment production: Evidence from a 4450-year varve record of neoglaciation in Hector Lake, Alberta, Canada. *Journal of Paleolimnology*, 17:319-330.
- Liestøl, O., 1969. Glacier surges in west Spitsbergen. *Canadian Journal of Earth Sciences*, 6:895-897.
- Liestøl, O., 1973. Glaciological work in 1971. *Aarbok Norsk Polarinstitut* pp. 67- 76, Norsk Polarinstitut.
- Lingle, C.S., A.A. Arendt, W.D. Harrison, K.A. Echelmeyer and C.F. Larsen, 2008. Is glacier wastage continuing to accelerate in NW North America? *EOS Transactions of the American Geophysical Union*, 90, Fall Meeting Supplement:C22A-05.
- Long, D.G. and B.R. Hicks, 2005. Standard Brigham Young University QuikSCAT/SeaWinds land/ice image products. Brigham Young University, Microwave Environmental Remote Sensing Technical Report MERS 05-04 and Electrical and Computer Engineering Department Report TR-L130-05.04, 30 pp.
- Lubinski, D.J., S.L. Forman and G.H. Miller, 1999. Holocene glacier and climate fluctuations on Franz Josef Land, Arctic Russia, 80°N. *Quaternary Science Reviews*, 18:85-108.
- Luthcke, S.B., A.A. Arendt, D.D. Rowlands, J.J. McCarthy and C.F. Larsen, 2008. Recent glacier mass changes in the Gulf of Alaska region from GRACE mascon solutions. *Journal of Glaciology*, 54:767-777.
- Lydersen, C., A.R. Martin, K.M. Kovacs and I. Gjertz, 2001. Summer and autumn movements of white whales *Delphinapterus leucas* in Svalbard, Norway. *Marine Ecology Progress Series*, 219:265-274.
- Lythe, M.B., D.G. Vaughan and B. Consortium, 2001. BEDMAP: A new ice thickness and subglacial topographic model of Antarctica. *Journal of Geophysical Research-Solid Earth*, 106:11335-11351.
- Mair, D., D. Burgess and M. Sharp, 2005. Thirty-seven year mass balance of Devon Ice Cap, Nunavut, Canada, determined by shallow ice coring and melt modeling. *Journal of Geophysical Research-Earth Surface*, 110:F01011.
- Mair, D., D. Burgess, M. Sharp, J.A. Dowdeswell, T. Benham, S. Marshall and F. Cawkwell, 2009. Mass balance of the Prince of Wales Icefield, Ellesmere Island, Nunavut, Canada. *Journal of Geophysical Research-Earth Surface*, 114:F02011.

- Maizels, J.K., 1979. Proglacial aggradation and changes in braided channel patterns during a period of glacier advance: An Alpine example. *Geografiska Annaler* 61:87–101.
- Mangerud, J. and J.Y. Landvik, 2007. Younger Dryas cirque glaciers in western Spitsbergen: smaller than during the Little Ice Age. *Boreas*, 36:278–285.
- Marsh, P. and M.K. Woo, 1981. Snowmelt, glacier melt, and high arctic streamflow regimes. *Canadian Journal of Earth Sciences*, 18:1380–1384.
- Marshall, S.J., T.S. James and G.K.C. Clarke, 2002. North American Ice Sheet reconstructions at the Last Glacial Maximum. *Quaternary Science Reviews*, 21:175–192.
- Matulla, C., S. Schmutz, A. Melcher, T. Gerersdorfer and P. Haas, 2007. Assessing the impact of a downscaled climate change simulation on the fish fauna in an Inner-Alpine River. *International Journal of Biometeorology*, 52:127–137.
- Mayer, C., N. Reeh, F. Jung-Rothenhausler, P. Huybrechts and H. Oerter, 2000. The subglacial cavity and implied dynamics under Nioghalverdsfjorden Glacier, NE Greenland. *Geophysical Research Letters*, 27:2289–2292.
- McClintock, J., R. McKenna and C. Woodworth-Lynas, 2007. Grand Banks Iceberg Management. Report prepared for PERD/CHC, National Research Council Canada, Ottawa, ON. Report prepared by AMEC Earth & Environmental, St. John's, NL, R.F. McKenna & Associates, Wakefield, QC, and PETRA International Ltd., Cupids, NL. PERD/CHC Report, 20–84, 92 pp.
- McConnell, J.R., R. Edwards, G.L. Kok, M.G. Flanner, C.S. Zender, E.S. Saltzman, J.R. Banta, D.R. Pasteris, M.M. Carter and J.D.W. Kahl, 2007. 20th-century industrial black carbon emissions altered arctic climate forcing. *Science*, 317:1381–1384.
- McNamara, J.P. and D.L. Kane, 2009. The impact of a shrinking cryosphere on the form of arctic alluvial channels. *Hydrological Processes*, 23:159–168.
- Meier, M.F. and A. Post, 1987. Fast tidewater glaciers. *Journal of Geophysical Research-Solid Earth and Planets*, 92:9051–9058.
- Meier, M.F., M.B. Dyurgerov, U.K. Rick, S. O'Neel, W.T. Pfeffer, R.S. Anderson, S.P. Anderson and A.F. Glazovsky, 2007. Glaciers dominate Eustatic sea-level rise in the 21st century. *Science*, 317:1064–1067.
- Menounos, B., G. Osborn, J.J. Clague and B.H. Luckman, 2009. Latest Pleistocene and Holocene glacier fluctuations in western Canada. *Quaternary Science Reviews*, 28:2049–2074.
- Mernild, S.H., B. Hasholt and G.E. Liston, 2008a. Climatic control on river discharge simulations, Zackenberg River drainage basin, northeast Greenland. *Hydrological Processes*, 22:1932–1948.
- Mernild, S.H., D.L. Kane, B.U. Hansen, B.H. Jakobsen, B. Hasholt and N.T. Knudsen, 2008b. Climate, glacier mass balance and runoff (1993–2005) for the Mittivakkat Glacier catchment, Ammassalik Island, SE Greenland, and in a long term perspective (1898–1993). *Hydrology Research*, 39:239–256.
- Milner, A.M. and G.E. Petts, 1994. Glacial rivers - physical habitat and ecology. *Freshwater Biology*, 32:295–307.
- Milner, A.M., J.E. Brittain, E. Castella and G.E. Petts, 2001. Trends of macroinvertebrate community structure in glacier-fed rivers in relation to environmental conditions: a synthesis. *Freshwater Biology*, 46:1833–1847.
- Milner, A.M., A.L. Robertson, K.A. Monaghan, A.J. Veal and E.A. Flory, 2008. Colonization and development of an Alaskan stream community over 28 years. *Frontiers in Ecology and the Environment*, 6:413–419.
- Moholdt, G., J.O. Hagen, T. Eiken and T.V. Schuler, 2010a. Geometric changes and mass balance of the Austfonna ice cap, Svalbard. *The Cryosphere*, 4:21–34.
- Moholdt, G., C. Nuth, J.-O. Hagen and J. Kohler, 2010b. Recent elevation changes of Svalbard glaciers derived from ICESat laser altimetry. *Remote Sensing of Environment*, 114:2756–2767.
- Moore, R.D., S.W. Fleming, B. Menounos, R. Wheate, A. Fountain, K. Stahl, K. Holm and M. Jakob, 2009. Glacier change in western North America: influences on hydrology, geomorphic hazards and water quality. *Hydrological Processes*, 23:42–61.
- Motyka, R., L. Hunter, K. Echelmeyer and C. Connor, 2003. Submarine melting at the terminus of a tidewater glacier, Leconte Glacier, Alaska, USA. *Annals of Glaciology*, 36:57–65.
- Mueller, F., 1969. Was the Good Friday Glacier on Axel Heiberg Island surging? *Canadian Journal of Earth Sciences*, 6:891–894.
- Mueller, D.R., W.F. Vincent and M.O. Jeffries, 2003. Break-up of the largest Arctic ice shelf and associated loss of an epishelf lake. *Geophysical Research Letters*, 30:2031.
- Mueller, D.R., L. Copland, A. Hamilton and D. Stern, 2008. Examining Arctic ice shelves prior to the 2008 breakup. *EOS, Transactions of the American Geophysical Union* 89:502–503.
- Murray, T., T. Strozzi, A. Luckman, H. Jiskoot and P. Christakos, 2003. Is there a single surge mechanism? Contrasts in dynamics between glacier surges in Svalbard and other regions. *Journal of Geophysical Research-Solid Earth*, 108:2237.
- Naik, G., 2007. Arctic becomes tourism hot spot, but is that cool? *The Wall Street Journal*: A1. September 24.
- Naumov, A.K., G.K. Zubakin, Y.P. Gudoshnikov, I.V. Buzin and A.A. Skutin, 2003. Glaciers and icebergs in the region of Shtokmanovskoe gas condensate deposit. [in Russian with English summary]. Paper presented at Proceedings of RAO-03, pp. 337–342. St.Petersburg, Russia, 16–19 September.
- Neal, E.G., E. Hood and K. Smikrud, 2010. Contribution of glacier runoff to freshwater discharge into the Gulf of Alaska. *Geophysical Research Letters*, 37:L06404.
- Nehlsen, W., J.E. Williams and J.A. Lichatowich, 1991. Pacific salmon at the crossroads: stocks at risk from California, Oregon, Idaho and Washington. *Fisheries*, 16:4–21.
- Nesje, A., 2005. Briksdalsbreen in western Norway: AD 1900–2004 frontal fluctuations as a combined effect of variations in winter precipitation and summer temperature. *The Holocene*, 15:1245–1252.
- Nesje, A., 2009. Latest Pleistocene and Holocene alpine glacier fluctuations in Scandinavia. *Quaternary Science Reviews*, 28:2119–2136.
- Ng, F., S. Liu, B. Mavlyudov and Y. Wang, 2007. Climatic control on the peak discharge of glacier outburst floods. *Geophysical Research Letters*, 34:L21503.
- Nick, F.M. and J. Oerlemans, 2006. Dynamics of tidewater glaciers: comparison of three models. *Journal of Glaciology*, 52:183–190.
- Nick, F.M., C.J. van der Veen and J. Oerlemans, 2007. Controls on advance of tidewater glaciers: Results from numerical modeling applied to Columbia Glacier. *Journal of Geophysical Research-Earth Surface*, 112:F03S24.
- Nolin, A.W. and M.C. Payne, 2007. Classification of glacier zones in western Greenland using albedo and surface roughness from the Multi-angle Imaging SpectroRadiometer (MISR). *Remote Sensing of Environment*, 107:264–275.
- Nuth, C., J. Kohler, H.F. Aas, O. Brandt and J.O. Hagen, 2007. Glacier geometry and elevation changes on Svalbard (1936–90). *Annals of Glaciology*, 46:106–116.
- Nuth, C., G. Moholdt, J. Kohler, J.O. Hagen and A. Kääb, 2010. Svalbard glacier elevation changes and contribution to sea level rise. *Journal of Geophysical Research-Earth Surface*, 115:F01008.
- Nye, J.F., 1957. The distribution of stress and velocity in glaciers and ice sheets. *Proceedings of the Royal Society of London, Series A*, 239:113–133.
- O'Connor, J.E. and J.E. Costa, 1993. Geologic and hydrologic hazards in glacierized basins in North America resulting from 19th and 20th century global warming. *Natural Hazards* 8:121–140.
- O'Neel, S. and W.T. Pfeffer, 2007. Source mechanics for monochromatic icequakes produced during icebergs calving at Columbia Glacier, AK. *Geophysical Research Letters*, 34:L22502.
- O'Neel, S., W.T. Pfeffer, R. Krimmel and M. Meier, 2005. Evolving force balance at Columbia Glacier, Alaska, during its rapid retreat. *Journal of Geophysical Research-Earth Surface*, 110:F03012.
- Obleitner, F. and M. Lehning, 2004. Measurement and simulation of snow and superimposed ice at the Kongsvegen glacier, Svalbard (Spitzbergen). *Journal of Geophysical Research-Atmospheres*, 109:D04106.
- Oerlemans, J. and B.K. Reichert, 2000. Relating glacier mass balance to meteorological data by using a seasonal sensitivity characteristic. *Journal of Glaciology*, 46:1–6.
- Oerlemans, J., R.P. Bassford, W. Chapman, J.A. Dowdeswell, A.F. Glazovsky, J.O. Hagen, K. Melvold, M.D. de Wildt and R.S.W. van de Wal, 2005. Estimating the contribution of Arctic glaciers to sea-level change in the next 100 years. *Annals of Glaciology*, 42:230–236.
- Ommanney, C.S.L., 1970. The Canadian glacier inventory. Paper presented at Glaciers, Proceedings of Workshop Seminar, pp. 23–30. Canadian National Committee, the International Hydrological Decade, Ottawa.

- Opel, T., D. Fritzsche, H. Meyer, R. Schutt, K. Weiler, U. Ruth, F. Wilhelms and H. Fischer, 2009. 115 year ice-core data from Akademii Nauk ice cap, Severnaya Zemlya: high-resolution record of Eurasian Arctic climate change. *Journal of Glaciology*, 55:21–31.
- Osipova, G.B., 2006. General state of mountain glaciers. In: Kotlyakov, V.M. (Ed.). *Glaciation in North and Central Eurasia at Present Time*, pp. 115–126, Nauka, Moscow.
- Østrem, G., 1975a. ERTS data in glaciology - An effort to monitor glacier mass balance from satellite imagery. *Journal of Glaciology*, 15:403–415.
- Østrem, G., 1975b. Sediment transport in glacial meltwater streams. *Glaciofluvial and Glaciolacustrine Sedimentation. SEPM Special Publication*, 23:101–122.
- Østrem, G. and M.M. Brugman, 1991. Glacier mass-balance measurements: a manual for field and office work. *NHRI Science Report 4*, 224 pp.
- Østrem, G., K.D. Selvig and K. Tandberg, 1988. *Atlas over breer i Sør-Norge. Meddelelser fra Hydrologisk Avdeling 61*, 248 pp. Norges Vassdrags-og Energiverk, Oslo.
- Østrem, G., N. Haakensen and O. Melander, 1973. *Atlas over breer i Nord-Skandinavia. Meddelelser fra Hydrologisk Avdeling 22*, 315 pp. Norges Vassdrags-og Energiverk, Oslo and Stockholm.
- Overpeck, J., K. Hughen, D. Hardy, R. Bradley, R. Case, M. Douglas, B. Finney, K. Gajewski, G. Jacoby, A. Jennings, S. Lamoureux, A. Lasca, G. MacDonald, J. Moore, M. Retelle, S. Smith, A. Wolfe and G. Zielinski, 1997. Arctic environmental change of the last four centuries. *Science*, 278:1251–1256.
- Paterson, W.S.B., R.M. Koerner, D. Fisher, S.J. Johnsen, H.B. Clausen, W. Dansgaard, P. Bucher and H. Oeschger, 1977. An oxygen-isotope climatic record from Devon Island Ice Cap, Arctic Canada. *Nature*, 266:508–511.
- Paul, F. and F. Svoboda, 2009. A new glacier inventory on southern Baffin Island, Canada, from ASTER data: II. Data analysis, glacier change and applications. *Annals of Glaciology*, 50:22–31.
- Pinglot, J.F., M. Pourchet, B. Lefauconnier, J.O. Hagen, E. Isaksson, R. Vaikmae and K. Kamiyama, 1999. Accumulation in Svalbard glaciers deduced from ice cores with nuclear tests and Chernobyl reference layers. *Polar Research*, 18:315–321.
- Pohjola, V.A. and J.C. Rogers, 1997. Atmospheric circulation and variations in Scandinavian glacier mass balance. *Quaternary Research*, 47:29–36.
- Pohjola, V.A., T.A. Martma, H.A.J. Meijer, J.C. Moore, E. Isaksson, R. Vaikmae and R.S.W. Van de Wal, 2002. Reconstruction of three centuries of annual accumulation rates based on the record of stable isotopes of water from Lomonosovfonna, Svalbard. *Annals of Glaciology*, 35:57–62.
- Polyakov, I.V., R.V. Bekryaev, G.V. Alekseev, U.S. Bhatt, R.L. Colony, M.A. Johnson, A.P. Maskhtas and D. Walsh, 2003. Variability and trends of air temperature and pressure in the maritime Arctic, 1875–2000. *Journal of Climate*, 16:2067–2077.
- Polyak, L., I. Murdmaa and E. Ivanova, 2004. A high-resolution, 800-year glaciomarine record from Russkaya Gavan', a Novaya Zemlya Fjord, Eastern Barents Sea. *The Holocene*, 14:628–634.
- Post, A., 1975. Preliminary hydrography and historic terminal changes of Columbia Glacier, Alaska. *Hydrological Investigations Atlas*, HA-559, 3 pp. U.S. Geological Survey, Tacoma, Washington.
- Radić, V. and R. Hock, 2006. Modeling future glacier mass balance and volume changes using ERA-40 reanalysis and climate models: A sensitivity study at Storglaciären, Sweden. *Journal of Geophysical Research-Earth Surface*, 111:F03003.
- Radić, V. and R. Hock, 2010. Regional and global volumes of glaciers derived from statistical upscaling of glacier inventory data. *Journal of Geophysical Research-Earth Surface*, 115:F01010.
- Radić, V. and R. Hock, 2011. Regional differentiated contribution of mountain glaciers and ice caps to future sea-level rise. *Nature Geoscience*, 4:91–94.
- Radić, V., R. Hock and J. Oerlemans, 2008. Analysis of scaling methods in deriving future volume evolutions of valley glaciers. *Journal of Glaciology*, 54:601–612.
- Raper, S.C.B. and R.J. Braithwaite, 2006. Low sea level rise projections from mountain glaciers and icecaps under global warming. *Nature*, 439:311–313.
- Raper, S.C.B., O. Brown and R.J. Braithwaite, 2000. A geometric glacier model for sea-level change calculations. *Journal of Glaciology*, 46:357–368.
- Rasmussen, L.A., 2004. Altitude variation of glacier mass balance in Scandinavia. *Geophysical Research Letters*, 31:L13401.
- Raymond, C.F., 1987. How do glaciers surge? A review. *Journal of Geophysical Research-Solid Earth and Planets*, 92:9121–9134.
- Reeh, N., 1968. On the calving of ice from floating glaciers and ice shelves. *Journal of Glaciology*, 7:215–232.
- Reeh, N., 2008. A non-steady-state firn-densification model for the percolation zone of a glacier. *Journal of Geophysical Research*, 113:F03023.
- Reeh, N., C. Mayer, H. Miller, H.H. Thomsen and A. Weidick, 1999. Present and past climate control on fjord glaciations in Greenland: implications for IRD-deposition in the sea. *Geophysical Research Letters*, 26:1039–1042.
- Reeh, N., O.B. Olesen, H.H. Thomsen, W. Starzer and C.E. Bøggild, 2001. Mass balance parameterisation for Hans Tausen Iskappe, Peary Land, North Greenland. *Meddelelser om Grønland, Geosciences*, 39:57–69.
- Reeh, N., D.A. Fisher, R.M. Koerner and H.B. Clausen, 2005. An empirical firn densification model comprising ice lenses. *Annals of Glaciology*, 42:101–106.
- Reichert, B.K., L. Bengtsson and J. Oerlemans, 2001. Midlatitude forcing mechanisms for glacier mass balance investigated using general circulation models. *Journal of Climate*, 14:3767–3784.
- Reijmer, C.H., W.H. Knap and J. Oerlemans, 1999. The surface albedo of the Vatnajökull ice cap, Iceland: A comparison between satellite-derived and ground-based measurements. *Boundary-Layer Meteorology*, 92:125–144.
- Rennermalm, A.K., L.C. Smith, J.C. Stroeve and V.W. Chu, 2009. Does sea ice influence Greenland ice sheet surface-melt? *Environmental Research Letters*, 4:1–6.
- Richardson, J.C. and A.M. Milner, 2005. Rivers of Pacific Canada and Alaska. In: Benke, A. and B. Cushing (Eds.). *Rivers of North America*, pp. 735–775, Academic Press.
- Rignot, E. and P. Kanagaratnam, 2006. Changes in the velocity structure of the Greenland ice sheet. *Science*, 311:986–990.
- Rignot, E., J.E. Box, E. Burgess and E. Hanna, 2008. Mass balance of the Greenland ice sheet from 1958 to 2007. *Geophysical Research Letters*, 35:L20502.
- Rignot, E., M. Koppes and I. Velicogna, 2010. Rapid submarine melting of the calving faces of West Greenland glaciers. *Nature Geoscience*, 3:187–191.
- Royer, T.C., 1982. Coastal fresh water discharge in the northeast Pacific. *Journal of Geophysical Research-Oceans and Atmospheres*, 87:2017–2021.
- Russell, A.J., M.J. Roberts, H. Fay, P.M. Marren, N.J. Cassidy, F.S. Tweed and T. Harris, 2006. Icelandic jökullhlaup impacts: Implications for ice-sheet hydrology, sediment transfer and geomorphology. *Geomorphology*, 75:33–64.
- Sandford, K.S., 1955. Tabular icebergs between Spitsbergen and Franz-Josef Land. *Geographical Journal*, 121:164–170.
- Scambos, T.A., M.J. Dutkiewicz, J.C. Wilson and R.A. Bindshadler, 1992. Application of image cross-correlation to the measurement of glacier velocity using satellite image data. *Remote Sensing of Environment*, 42:177–186.
- Schiefer, E., B. Menounos and R. Wheate, 2007. Recent volume loss of British Columbian glaciers, Canada. *Geophysical Research Letters*, 34:L16503.
- Schneeberger, C., H. Blatter, A. Abe-Ouchi and M. Wild, 2003. Modelling changes in the mass balance of glaciers of the northern hemisphere for a transient 2 x CO₂ scenario. *Journal of Hydrology*, 282:145–163.
- Schulson, E.M., 1999. The structure and mechanical behavior of ice. *JOM-Journal of the Minerals Metals & Materials Society*, 51:21–27.
- Schytt, V., 1969. Glacier surge in eastern Svalbard. *Canadian Journal of Earth Sciences* 6:875–882.
- Serreze, M.C., A.P. Barrett, J.C. Stroeve, D.N. Kindig and M.M. Holland, 2009. The emergence of surface-based Arctic amplification. *The Cryosphere*, 3:11–19.
- Sharp, M. and L.B. Wang, 2009. A five-year record of summer melt on Eurasian Arctic ice caps. *Journal of Climate*, 22:133–145.
- Sharp, M. and G. Wolken, 2009. Glaciers outside Greenland. *Bulletin of the American Meteorological Society, State of the Climate in 2008*:107–108.
- Sharp, M. and G. Wolken, 2010. Glaciers outside Greenland. *Bulletin of the American Meteorological Society, State of the Climate 2009*:91–94–97.
- Sharp, M., J. Parkes, B. Cragg, I.J. Fairchild, H. Lamb and M. Tranter, 1999. Widespread bacterial populations at glacier beds and their relationship

- to rock weathering and carbon cycling. *Geology*, 27:107–110.
- Sharp, M.J., L. Copland, K. Filbert, D. Burgess and S. Williamson, 2003. Recent changes in the extent and volume of Canadian Arctic glaciers. Paper presented at Snow Watch 2002 Workshop and Assessing Global Glacier Retreat, Glaciological Data Report, pp. 73–75. NSIDC/WDC for Glaciology, Boulder, Colorado.
- Sharp, M., D.O. Burgess, F. Cawkwell, L. Copland, J.A. Davis, E.K. Dowdeswell, J.A. Dowdeswell, A.S. Gardner, D. Mair, L. Wang, S.N. Williamson, G.J. Wolken and F. Wyatt, 2011, in press. Recent glacier changes in the Canadian Arctic. In: Kargel, J.S., M.P. Bishop, A. Kääb, B.H. Raup and G. Leonard (Eds.). *Global Land Ice Measurements from Space: Satellite Multispectral Imaging of Glaciers*, pp. 20 pp, Praxis-Singer,
- Shuchman, R.A. and E.G. Josberger (Eds.), 2010. *Bering Glacier: Interdisciplinary Studies of Earth's Largest Temperate Surging Glacier*. 384 pp.
- Sigurðsson, O., T. Jónsson and T. Jóhannesson, 2007. Relations between glacier termini variations and summer temperature in Iceland since 1930. *Annals of Glaciology*, 46:170–176.
- Skidmore, M.L. and M.J. Sharp, 1999. Drainage system behaviour of a High-Arctic polythermal glacier. *Annals of Glaciology*, 28:209–215.
- Skidmore, M.L., J.M. Foght and M.J. Sharp, 2000. Microbial life beneath a high Arctic glacier. *Applied and Environmental Microbiology*, 66:3214–3220.
- Smith, B.P.G., D.M. Hannah, A.M. Gurnell and G.E. Petts, 2001. A hydrogeomorphological context for ecological research on alpine glacial rivers. *Freshwater Biology*, 46:1579–1596.
- Smith, L.C., Y.W. Sheng, R.R. Forster, K. Steffen, K.E. Frey and D.E. Alsdorf, 2003. Melting of small Arctic ice caps observed from ERS scatterometer time series. *Geophysical Research Letters*, 30:2034.
- Sneed, W.A., R.L. Hooke and G.S. Hamilton, 2008. Thinning of the south dome of Barnes Ice Cap, Arctic Canada, over the past two decades. *Geology*, 36:71–74.
- Solomon, S., D. Qin, M. Manning, Z. Chen, M. Marquis, K.B. Averyt, M. Tignor and H.L. Miller (Eds.), 2007. *Climate Change 2007. The Physical Science Basis. Contribution of Working Group I to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change*. 996 pp. Cambridge University Press.
- Stahl, K. and R.D. Moore, 2006. Influence of watershed glacier coverage on summer streamflow in British Columbia, Canada. *Water Resources Research*, 42:W06201.
- Straneo, F., G.S. Hamilton, D.A. Sutherland, L.A. Stearns, F. Davidson, M.O. Hammill, G.B. Stenson and A. Rosing-Asvid, 2010. Rapid circulation of warm subtropical waters in a major glacial fjord in East Greenland. *Nature Geoscience*, 3:182–186.
- Stroeve, J. and K. Steffen, 1998. Variability of AVHRR-derived clear-sky surface temperature over the Greenland ice sheet. *Journal of Applied Meteorology*, 37:23–31.
- Sund, M. and T. Eiken, 2010. Recent surges on Blomstrandbreen, Comfortlessbreen and Nathorstbreen, Svalbard. *Journal of Glaciology*, 56:182–184.
- Svendsen, J.I. and J. Mangerud, 1997. Holocene glacial and climatic variations on Spitsbergen, Svalbard. *The Holocene*, 7:45–57.
- Svendsen, H., A. Beszczynska-Moller, J.O. Hagen, B. Lefauconnier, V. Tverberg, S. Gerland, J.B. Orbaek, K. Bischof, C. Papucci, M. Zajackowski, R. Azzolini, O. Bruland, C. Wiencke, J.G. Winther and W. Dallmann, 2002. The physical environment of Kongsfjorden-Krossfjorden, an Arctic fjord system in Svalbard. *Polar Research*, 21:133–166.
- Syvitski, J.P.M., A.B. Stein, J.T. Andrews and J.D. Milliman, 2001. Icebergs and the sea floor of the East Greenland (Kangerlussuaq) continental margin. *Arctic, Antarctic and Alpine Research*, 33:52–61.
- Tamisiea, M.E., E.W. Leuliette, J.L. Davis and J.X. Mitrovica, 2005. Constraining hydrological and cryospheric mass flux in southeastern Alaska using space-based gravity measurements. *Geophysical Research Letters*, 32:L20501.
- Thomsen, T. and A. Weidick, 1992. Climate change impact on northern water resources in Greenland. Paper presented at the 9th International Northern Research Basins Symposium, pp. 749–781. Government of Canada, Yukon & Northwest Territories.
- Tranter, M., M.J. Sharp, H.R. Lamb, G.H. Brown, B.P. Hubbard and I.C. Willis, 2002. Geochemical weathering at the bed of Haut Glacier d'Arolla, Switzerland - a new model. *Hydrological Processes*, 16:959–993.
- Tranter, M., M. Skidmore and J. Wadham, 2005. Hydrological controls on microbial communities in subglacial environments. *Hydrological Processes*, 19:995–998.
- Trouet, V., J. Esper, N.E. Graham, A. Baker, J.D. Scourse and D.C. Frank, 2009. Persistent positive North Atlantic Oscillation mode dominated the Medieval climate anomaly. *Science*, 324:78–80.
- Tuffen, H., 2010. How will melting of ice affect volcanic hazards in the twenty first century. *Philosophical Transactions of the Royal Society A*, 368:2535–2558.
- Van der Veen, C.J., 1996. Tidewater calving. *Journal of Glaciology*, 42:375–385.
- Van der Veen, C.J., 1998a. Fracture mechanics approach to the penetration of surface crevasses on glaciers. *Cold Regions Science and Technology*, 27:31–47.
- Van der Veen, C.J., 1998b. Fracture mechanics approach to the penetration of bottom crevasses on glaciers. *Cold Regions Science and Technology*, 27:213–223.
- VanLooy, J., R. Forster and A. Ford, 2006. Accelerating thinning of Kenai Peninsula glaciers, Alaska. *Geophysical Research Letters*, 33:L21307.
- Vare, L.L., G. Massé, T.R. Gregory, C.W. Smart and S.T. Belt, 2009. Sea ice variations in the central Canadian Arctic Archipelago during the Holocene. *Quaternary Science Reviews*, 28:1354–1366.
- Veillette, J., D.R. Mueller, D. Antoniadis and W.F. Vincent, 2008. Arctic epishelf lakes as sentinel ecosystems: Past, present and future. *Journal of Geophysical Research-Biogeosciences*, 113:G04014.
- Viel, A., M. Funk and H. Blatter, 2001. Flow dynamics of tidewater glaciers: a numerical modelling approach. *Journal of Glaciology*, 47:595–606.
- Vinther, B.M., S.L. Buchardt, H.B. Clausen, D. Dahl-Jensen, S.J. Johnsen, D.A. Fisher, R.M. Koerner, D. Raynaud, V. Lipenkov, K.K. Andersen, T. Blunier, S.O. Rasmussen, J.P. Steffensen and A.M. Svensson, 2009. Holocene thinning of the Greenland ice sheet. *Nature*, 461:385–388.
- Wadham, J.L., M. Tranter, S. Tulaczyk and M. Sharp, 2008. Subglacial methanogenesis: A potential climatic amplifier? *Global Biogeochemical Cycles*, 22:GB2021.
- Walter, F., S. O'Neil, D. McNamara, W.T. Pfeffer, J.N. Bassis and H.A. Fricker, 2010. Iceberg calving during transition from grounded to floating ice: Columbia Glacier, Alaska. *Geophysical Research Letters*, 37:L15501.
- Wang, L., M.J. Sharp, B. Rivard, S. Marshall and D. Burgess, 2005. Melt season duration on Canadian Arctic ice caps, 2000–2004. *Geophysical Research Letters*, 32:L19502.
- Wang, L., M. Sharp, B. Rivard and K. Steffen, 2007. Melt season duration and ice layer formation on the Greenland ice sheet, 2000–2004. *Journal of Geophysical Research-Earth Surface*, 112:F04013.
- Warren, S.G. and W.J. Wiscombe, 1980. A model for the spectral albedo of snow. II: snow containing atmospheric aerosols. *Journal of the Atmospheric Sciences*, 37:2734–2745.
- Weeks, W.F. and W.J. Campbell, 1973. Icebergs as a freshwater source: An appraisal. *Journal of Glaciology*, 12:207–233.
- Weertman, J., 1973. Can a water-filled crevasse reach the bottom surface of a glacier? Paper presented at the Symposium on the Hydrology of Glaciers, pp. 139–145. Union Geodesique et Geophysique Internationale. Association Internationale d'Hydrologie Scientifique. Commission de Neiges et Glaces, Cambridge, September 7–13, 1969.
- Weidick, A., 1995. *Greenland. Satellite Image Atlas of Glaciers of the World*, USGS Professional Paper. 1386-C, 153 pp.
- Weidick, A. and E. Morris, 1998. Local glaciers surrounding the continental ice sheets. Paper presented at Into the second century of world glacier monitoring - prospects and strategies, pp. 197–205. UNESCO, Paris.
- Weingartner, T.J., S.L. Danielson and T.C. Royer, 2005. Freshwater variability and predictability in the Alaska Coastal Current. *Deep-Sea Research Part II-Topical Studies in Oceanography*, 52:169–191.
- Weng, W.L., 1995. The area of Greenland and ice cap, Letter to the editor. *Arctic*, 48:206–206.
- WGMS, 2009. *Glacier Mass Balance Bulletin (2006–2007)*. Glacier Mass Balance Bulletin, 10, 108 pp. World Glacier Monitoring Service, Zürich.
- Williams, R.S., 1987. Satellite remote sensing of the Vatnajökull, Iceland. *Annals of Glaciology*, 9:127–165.
- Williams, M. and J.A. Dowdeswell, 2001. Historical fluctuations of the Matusevich Ice Shelf, Severnaya Zemlya, Russian High Arctic. *Arctic, Antarctic and Alpine Research*, 33:211–222.
- Williamson, S., M. Sharp, J. Dowdeswell and T. Benham, 2008. Iceberg calving rates from northern Ellesmere Island ice caps, Canadian Arctic,

- 1999-2003. *Journal of Glaciology*, 54:391-400.
- Winkler, S., 2003. A new interpretation of the date of the 'Little Ice Age' glacier maximum at Svartisen and Okstindan, northern Norway. *The Holocene*, 13:83-95.
- Wiscombe, W.J. and S.G. Warren, 1980. A model for the spectral albedo of snow, I: Pure snow. *Journal of the Atmospheric Sciences*, 37:2712-2733.
- Wolken, G.J., J.H. England and A.S. Dyke, 2008. Changes in late-Neoglacial perennial snow/ice extent and equilibrium-line altitudes in the Queen Elizabeth Islands, Arctic Canada. *The Holocene*, 18:615-627.
- Wolken, G.J., M. Sharp and L.B. Wang, 2009. Snow and ice facies variability and ice layer formation on Canadian Arctic ice caps, 1999-2005. *Journal of Geophysical Research-Earth Surface*, 114:F03011.
- Woodworth-Lynas, C.M.T., H.W. Josenhans, J.V. Barrie, C.F.M. Lewis and D.R. Parrott, 1991. The physical processes of seabed disturbance during iceberg grounding and scouring. *Continental Shelf Research*, 11:939-951.
- Zdanowicz, C.M., D.A. Fisher, I. Clark and D. Lacelle, 2002. An ice-marginal delta O-18 record from Barnes Ice Cap, Baffin Island, Canada. *Annals of Glaciology*, 35:145-149.
- Zeeberg, J., 2001. Climate and glacial history of the Novaya Zemlya Archipelago, Russian Arctic, with notes on the region's history of exploration. pp. 174. Rosenberg Publishers, Amsterdam.
- Zeeberg, J. and S.L. Forman, 2001. Changes in glacier extent on north Novaya Zemlya in the twentieth century. *The Holocene*, 11:161-175.
- Zhang, J., U.S. Bhatt, W.V. Tangborn and C.S. Lingle, 2007a. Climate downscaling for estimating glacier mass balances in northwestern North America: Validation with a USGS benchmark glacier. *Geophysical Research Letters*, 34:L21505.
- Zhang, J., U.S. Bhatt, W.V. Tangborn and C.S. Lingle, 2007b. Response of glaciers in northwestern North America to future climate change: an atmosphere/glacier hierarchical modeling approach. *Annals of Glaciology*, 46:283-290.
- Zheng, J., C. Zdanowicz, D. Fisher, G. Hall and J. Vaive, 2003. A new 155-year record of Pb pollution from Devon Ice Cap, Canada. *Journal de Physique IV France*, 107:1405-1408.
- Zubakin, G.K., A.K. Naumov and E.A. Skutina, 2006. Spreading and morphometric peculiarities of icebergs in the Barents Sea. Paper presented at The 18th IAHR International Symposium on Ice, pp. 79-87.
- Zubakin, G.K., Y.P. Gudoshnikov, A.K. Naumov, A.F. Glazovsky, N.V. Kubyshkin, I.V. Buzin, V.V. Borodulin and E.A. Skutina, 2007. Results of investigation of icebergs, glaciers and their frontal zones in the North-Eastern part of the Barents Sea. In: Yue, Q.J. (Ed.). *Recent Development of Offshore Engineering in Cold Regions*, pp. 548-564, POAC-07.

8. The Greenland Ice Sheet in a Changing Climate

COORDINATING LEAD AUTHOR: DORTHE DAHL-JENSEN

LEAD AUTHORS: JONATHAN BAMBER, CARL EGEDE BØGGILD, MICHAEL VAN DEN BROEKE, ERIK BUCH, JENS HESSELBERG CHRISTENSEN, KLAUS DETHLOFF, MARK FAHNESTOCK, SHAWN MARSHALL, MINIK ROSING, KONRAD STEFFEN, ROBERT THOMAS, MARTIN TRUFFER, CORNELIS VAN DER VEEN

Contents

Key Findings	2	8.5. Socio-economic and cultural aspects of changes in the Greenland Ice Sheet	53
Summary	2	8.5.1. History of change and contemporary socio-economic and cultural trends	53
8.1. Introduction	3	8.5.2. Implications of changes	54
8.1.1. Evolution of the Greenland Ice Sheet	3	8.5.3. Influences	54
8.1.2. History of the Greenland Ice Sheet	4	8.5.4. The Ilulissat case	54
8.1.3. Evolution of the Greenland Ice Sheet in the future	5	8.5.5. Conclusions	56
8.2. The Greenland Ice Sheet today	6	8.6. Major knowledge gaps and recommendations	56
8.2.1. Overview of the Greenland Ice Sheet	6	8.6.1. Introduction	56
8.2.2. Surface mass balance	11	8.6.2. Gaps in knowledge of surface mass balance	58
8.2.3. Ice discharge	19	8.6.3. Gaps in knowledge of net balance or components thereof	58
8.2.4. Total mass balance	23	8.6.4. Gaps in knowledge of ice dynamics	58
8.2.5. Summary and outlook	26	8.6.5. Gaps in knowledge of ice sheet and climate modeling ..	59
8.3. Predictions and sensitivity	29	8.6.6. Perspectives	59
8.3.1. Aspects of modeling climate change for Greenland ...	30	References	60
8.3.2. Modeling Greenland Ice Sheet dynamics	34		
8.3.3. Future climate and ice sheet scenarios: Response of the Greenland Ice Sheet to a warmer climate	40		
8.3.4. Summary and outlook	46		
8.4. Impacts caused by changes in the Greenland Ice Sheet	47		
8.4.1. Ocean circulation	47		
8.4.2. The marine environment and marine ecosystems ...	52		

Key Findings

- At present, Greenland is warming at more than twice the global average due to the polar amplification at high Arctic latitudes. Annual Arctic temperatures are projected to be 2.8 to 7.8 °C higher in 2100.
- Mass balance estimates reveal that the Greenland Ice Sheet is losing ice at an increasing rate. The mass loss has increased from 50 (± 50) Gt/y in 1995–2000 to 205 (± 50) Gt/y in 2005–2006.
- A slight increment of accumulated mass is more than counterbalanced by the increased loss of mass by melting and ice discharge to the ocean. Runoff and ice discharge have both increased, each with more than 100 Gt of mass lost each year since 1990.
- The discharge occurs mainly through an increase in the velocity of the fast-flowing glaciers that terminate on ocean water in the fjords. Many fast-flowing glaciers have increased their velocity – some as much as doubling their velocity – and the glaciers reacting are observed further and further northward along the west coast of Greenland with global warming.
- The increased velocity from the fast-flowing glaciers appears to be related to warming of the ocean water.
- The present loss of mass (205 Gt/y) from the Greenland Ice Sheet if unchanged will cause a 5 cm global mean sea level rise by 2100. Models predict further loss of mass and increased discharge with the ongoing warming and 10 to 19 cm of eustatic sea level rise from Greenland Ice Sheet can be expected by 2100. However, the models still suffer from a very incomplete understanding of atmosphere-ocean-ice interactions. The maximum projected loss of mass from the Greenland Ice Sheet by 2100 is believed to result in a 40 cm eustatic sea level rise.
- Since 2003, the global contribution to sea level rise from the ice sheets and glaciers has increased from 50% to 75–85%. In the Arctic, mass loss from the Greenland Ice Sheet is very likely to exceed the contributions from the Arctic mountain glaciers and ice caps and from thermal expansion of the sea water during the next century.
- The increased meltwater runoff and iceberg discharge are reducing the salinity and density of the recipient marine surface water. These changes result in stronger gradients between the fresh surface water and the underlying saline water, as a result boosting circulation and increasing the transport of nutrients, which has a strong impact on the primary production of the affected marine areas.
- Planned hydroelectric power plants rely solely on runoff from the Greenland Ice Sheet and retreat of the ice sheet needs to be understood to be able to construct reliable and economic hydropower plants.
- Retreat of the Greenland Ice Sheet will open areas for mining, but will result in longer walking distances for hunters.
- Tourism in relation to the accelerating and retreating ice streams, especially at the UNESCO World Heritage site at Ilulissat Ice Fjord, is increasing and plays an important role in witnessing climate change first-hand.

Summary

The Greenland Ice Sheet is a massive ice cap nearly 3000 m thick. It is the largest body of freshwater ice in the Northern Hemisphere. There are 2.93 million km³ of ice locked up in the Greenland Ice Sheet. Ice is lost from the ice sheet either at the surface, where it is melted, or from the edge, where it breaks off as chunks of solid ice. Measured rates of both types of loss from the Greenland Ice Sheet have increased.

Most ice comes off the Greenland Ice Sheet in a series of fast-flowing glaciers that discharge to the ocean through fjords along the west coast of Greenland. Studies show that these have increased their rate of flow – some doubled their speed between 1995 and 2000. The trigger for these changes is thought to be warming of the ocean water that is in contact with the outflowing end of these glaciers. One well-known glacier, the one terminating in the Ilulissat Ice Fjord (Kangia in Greenlandic), which drains ice from around 7% of the entire ice sheet, has doubled its flow rate and the ice front has retreated by 15 km in the past eight years. These changes are dramatic and the glacier has become a popular tourist destination. Estimates of the amount of ice leaving the Greenland Ice Sheet as solid icebergs have risen from a pre-1990 value of 300 gigatonnes per year (Gt/y) to 400 Gt/y in 2005.

Results published in 2007 indicated that the area of the Greenland Ice Sheet's surface that experiences some melting each year had been steadily increasing since satellite observations began. The area of surface melting is not a direct measure of the volume of water being lost from the ice sheet (called 'runoff'), but both the area and the number of days of surface melting are strongly related to the amount of ice lost.

To calculate the net loss of mass from the Greenland Ice Sheet, losses by melt and discharge are offset against mass gains caused by snow falling onto the ice sheet's surface. The elevation of the Greenland Ice Sheet at its centre, measured from satellites, has risen slightly recently – probably reflecting an increase in snowfall – but this increase is more than outweighed by the increase in loss of ice due to melting and ice discharge.

When mass budgets were first calculated for the Greenland Ice Sheet in the 1960s, the ice sheet appeared to be in balance. Those early measurements were very uncertain, but they showed similar amounts of ice being added and lost each year. The latest measurements tell a very different story, with large net losses of ice every year. The net loss of ice has increased from an average estimate of 50 (± 50) Gt/y from 1995–2000 to 200 (± 50) Gt/y from 2004–2008. The current rate of loss (~200 Gt/y) represents enough water to supply more than one billion city-dwellers.

8.1. Introduction

- The Greenland Ice Sheet is the second largest body of ice on Earth and its mass is equivalent to a global mean sea level rise of about 7.5 m.
- During the last million years, sea level has ranged from being over 100 m lower than at present during glacial periods to up to 20 m higher during interglacial periods.
- The warming during the past decade in the Arctic is more than twice the global average.
- Annual temperatures over the Arctic (i.e., all areas north of 60° N) are projected to be 2.8 to 7.8 °C higher in 2100 and the mass loss from the Greenland Ice Sheet is projected to increase significantly.

8.1.1. Evolution of the Greenland Ice Sheet

The Greenland Ice Sheet (Figure 8.1) is the largest body of ice in the Northern Hemisphere and, globally, is dwarfed only by the Antarctic Ice Sheet. The entire mass of the Greenland Ice Sheet has a volume of 2.93 million km³ of ice, equivalent to a global mean sea level rise of 7.5 m (Table 8.1).

This section presents recent scientific results, focusing specifically on the impacts of contemporary changes in the Greenland Ice Sheet. Although many reports on climate change have addressed impacts resulting from the evolution of the ice sheet, none provide a thorough and up-to-date assessment of the importance of the Greenland Ice Sheet in a changing climate. The importance of the ice sheet as a component of the Arctic cryosphere and the enormous amount of new observations and data provide the background for a better understanding of the evolution of the Greenland Ice Sheet and its potential impacts.




Figure 8.1. The high latitudes of the Northern Hemisphere are covered with ice and snow. The high reflectance (albedo) of the white areas reduces the absorbance of incoming solar energy. As the white areas diminish in a warming climate more solar energy will be absorbed by the ice-free ocean and land surfaces. Source: Earth View image.

Table 8.1. Total volume of the ice bodies on Earth and the equivalent global sea level change if the ice bodies were to melt completely.

	Volume, million km ³	Equivalent sea-level rise, m	Source
Antarctic Ice Sheet	25.4	57	Lythe et al., 2001
Greenland Ice Sheet	2.93	7.5	Bamber et al., 2001
All remaining glaciers and ice caps	0.051 – 0.133	0.15 – 0.37	Lemke et al., 2007

The high latitudes of the Northern Hemisphere are the regions that have experienced the strongest changes in climate since the 1951–1980 reference period (Figure 8.2). While the global annual temperature anomaly for 2009 in relation to the 1951–1980 reference period is 0.7 °C, the anomaly over Greenland is 1.5 °C, which is twice the global value. Average surface temperature changes observed in the Arctic are greater than those observed on average over the Antarctic Ice Sheet.

The trend of strongly enhanced changes in surface





Figure 8.2. Mean surface temperature changes between 2009 and the reference period 1951–1980: (a) map averaged over 1200 km, (b) zonal means of the data shown on the main map. Source: data.giss.nasa.gov/gistemp.

temperature in the high northern latitudes is not only an issue in terms of the changes observed to date but is also a cause for concern in relation to the predicted increase in future temperatures. The IPCC A1B emissions scenario is projected to result in annual temperatures over the Arctic (i.e., all areas north of 60° N) 2.8 to 7.8 °C higher in 2100 than they were during the 1951–1980 reference period, with winters warming at a greater rate than summers (Meehl et al., 2007). A temperature increase of this magnitude is serious and would be the largest that the Greenland Ice Sheet would have experienced since the previous interglacial period, the Eemian, 130 000 to 115 000 BP (North Greenland Ice Core Project members, 2004).

8.1.2. History of the Greenland Ice Sheet

The global climate has changed enormously over time; there have been periods with glaciations and periods with no ice on Earth. While the Northern Hemisphere experienced ephemeral glaciations from 38 to 4 Myr BP, the onset of extensive


glaciations did not occur until 3.3 Myr BP (Lunt et al., 2008).

Over the past three million years, the Greenland Ice Sheet is believed to have waxed and waned in accordance with glacial and interglacial periods consistent with orbital timescale variations in benthic $^{18}\text{O}/^{16}\text{O}$ ratios (Weidick, 1993; Lisiecki and Raymo, 2005; Weidick and Bennike, 2007) (Figure 8.3). Glacial deposits (i.e., moraines) 20 to 50 km from the present shoreline of Greenland can be used to reconstruct the Greenland Ice Sheet in earlier climatic periods. While the maximum extent of the ice sheet during glacial periods can be observed through studies of moraines and marine sediment cores, the degree to which the Greenland Ice Sheet retreated in earlier warmer periods is not clear.


Observations by Imbrie et al. (1984) indicate that sea level has been higher than at present several times during the past 400 000 years. 130 000 to 115 000 years ago during the Eemian climatic period (MIS5) sea level was 5 to 8 m above present (Kopp et al., 2009; Rohling et al., 2009) and 400 000 years ago

Reconstructions of sea level


Temperature forcing, °C



Global sea level, m




Ice volume, million km³



Reconstructions of the Greenland Ice Sheet

Last Interglacial Period 120 000 years BP



Last Glacial Maximum
20 000 years BP

Present




Figure 8.3. The volume and area of the Greenland Ice Sheet have changed as the climate has evolved through glacial and interglacial periods. The reconstructed temperatures, based on the Vostok ice core data (a), are compared with reconstructed sea level changes (b) over the past 400 000 years. The volume and area of the ice sheet for the past 200 000 years are shown in (c). Snapshots, 120 000 years ago, of the modeled Greenland Ice Sheet from the Last Interglacial Period, 130 000 to 115 000 BP (d-e), show the very reduced volume during the previous warm period. During the cold Last Glacial Maximum, 20 000 BP, the ice sheet volume increased and model simulations (f) estimate that the added volume of the ice sheet was equivalent to a reduced average global sea level lowering of 2.9 m. For comparison, the model simulation of the present Greenland Ice Sheet is shown in (g). Source: (a, b, c, f, g) Huybrechts (2002); (d) Otto-Bliesner et al. (2006); (e) Cuffey and Marshall (2000).

during the warm interglacial (MIS20) the highest stand is reconstructed at 20 m above present (Alley et al., 2010).

The 5 to 8 m of additional sea level during the previous interglacial period, the Eemian (MIS5), is of particular relevance for the future evolution of the ice sheet (Stirling et al., 1998; Lambeck et al., 2002; Kopp et al., 2009). The average air temperature is believed to have been 5 °C warmer than during the 1951–1980 reference period and to have remained so for several thousand years (North Greenland Ice Core Project members, 2004). The reaction of the Greenland Ice Sheet during the Eemian can to some degree be seen as an analogue to the evolution of the ice sheet in future warming scenarios.

Model reconstructions of the ice sheet during the Eemian show very reduced ice volumes (Figure 8.3), especially in southern Greenland (Létréguilly et al., 1991; Cuffey and Marshall, 2000; Otto-Bliesner et al., 2006), predicting a sea level contribution of 1 to 5 m from the Greenland Ice Sheet. Findings of Eemian ice in several Greenland ice cores and the presence of older ice at the base of the southern Greenland ice core drill site, DYE 3 (North Greenland Ice Core Project members, 2004; Willerslev et al., 2007; de Vernal and Hillaire-Marcel, 2008) support volume changes equivalent to a 1 to 3 m rise in sea level.

During the last glacial maximum, 25 000 to 14 000 BP, annual temperatures over Greenland are believed to have been 25 °C colder than at present (Cuffey et al., 1994; Cuffey and Clow, 1997; Dahl-Jensen et al., 1998), sea level to have been 120 m lower than at present (Lambeck et al., 2002), and the volume of the Greenland Ice Sheet to have been 140% higher than at present (Huybrechts, 2002; Lambeck et al., 2002), corresponding to a global average sea level lowering contribution of 3 m (Fleming and Lambeck, 2004).

Throughout the last glacial period, the climate was very unstable with 25 rapid climate changes, termed ‘interstadials’ or ‘Dansgaard-Oeschger events’. The North Atlantic region and the Greenland Ice Sheet experienced rapid temperature increases of 10 to 15 °C occurring over a few decades (North Greenland Ice Core Project members, 2004; Landais et al., 2005; Steffensen et al., 2008) together with sea level increases of 5 to 20 m (Siddall et al., 2003). The rapid changes are believed to have been connected to enormous surges of ice into the ocean, especially from the Laurentide Ice Sheet over North America and changing strength of the ocean circulation in the Atlantic Ocean (Flückiger et al., 2006). After the abrupt warmings during the Dansgaard-Oeschger events, surface temperatures gradually cooled over the subsequent 1000 to 5000 years, before the next rapid warming occurred. The contribution of the Greenland Ice Sheet to sea level during these rapid warming events is not known. Ice core data show that glacial accumulation over the central parts of the Greenland Ice Sheet was less than 50% of the present accumulation, showing a strong correlation between surface temperature and precipitation (Cuffey and Clow, 1997; Johnsen et al., 2001). The 25 rapid climate changes were also followed by strong changes in precipitation rates, apparent from changing annual layer thicknesses in the ice cores (Alley et al., 1993; Andersen et al., 2006a; Svensson et al., 2006).

After the glacial period, the climate warmed into the present interglacial period, the Holocene, and the coastal regions around Greenland experienced an isostatic uplift of up to 100 m in response to the retreating ice (Létréguilly et al., 1991; Weidick, 1993; Huybrechts, 2002).

The onset of the Holocene brought the climate directly into a warm period named the ‘Climatic Optimum’ 5000 to 8000 years ago with Greenland temperatures 2 °C warmer than in the 1951–1980 reference period (Dahl-Jensen et al., 1998). The onset of the present interglacial period with abrupt warming changed the shape and volume of the Greenland Ice Sheet. The modeled volume changes of the ice sheet entering the warm Holocene climatic period differ depending on the modeled extent of the ice sheet during the last glacial maximum, the mass balance applied, and the evolution of the temperature in the ice (Létréguilly et al., 1991; Huybrechts, 1996; Marshall and Cuffey, 2000; Clarke and Marshall, 2002; Vinther et al., 2009). Investigations in the region around the Jakobshavn Isbræ glacier on the west coast of Greenland show that 5000 to 8000 years ago the margin had retreated 10 km further east than at present (Weidick et al., 1990; Weidick and Bennike, 2007).

Following the Climatic Optimum, surface temperature gradually cooled until The Little Ice Age (occurring between 1500 and 1800) with temperatures 1 °C colder than during the 1951–1980 reference period (Dahl-Jensen et al., 1998). Temperatures then increased and the years around 1940 were about 1 °C warmer than in the reference period. In general, temperature change during the present Holocene climate (the past 12 000 years) has been moderate and of the order of 1 to 2 °C, compared to changes of the order of 10 to 20 °C during the last glacial period. The warming of 1.5 °C over the past decades is of the same order as other warming events recorded during the Holocene interglacial period. Due to the relatively small temperature changes recorded during the Holocene the variability in the proxy paleo-data leading to temperature and precipitation records is of the same order as the changes themselves (Bales et al., 2001, 2009; Mosley-Thompson et al., 2001; Andersen et al., 2006a; Vinther et al., 2010). The relation between temperature change and change in mass balance during the Holocene is not well established and is further complicated by regional patterns. Decadal-scale trends over the past century are also complicated by the large degree of natural variability (Chylek et al., 2006).

8.1.3. Evolution of the Greenland Ice Sheet in the future

Experience from modeling the past evolution of the Greenland Ice Sheet indicates the need for improvements in order to accurately model the evolution of the ice sheet in a changing climate. Not enough is known about many fundamental parameters, such as ice sheet mass balance, basal processes, and ice-ocean interactions. Observations are made difficult by the vast extent of the ice sheet and the inaccessibility of the ice sheet base and submerged front.

This inadequate knowledge of processes is affecting the ability to predict the evolution of ice sheets and led the Intergovernmental Panel on Climate Change (IPCC) to conclude that:

Taken together, the ice sheets of Greenland and Antarctica are very likely shrinking, with Greenland contributing about $0.2 \pm 0.1 \text{ mm yr}^{-1}$ and Antarctica contributing $0.2 \pm 0.35 \text{ mm yr}^{-1}$ to sea level rise over the period 1993 to 2003. There is evidence of accelerated loss through 2005. Thickening of high-altitude, cold regions of Greenland and East Antarctica, perhaps from

coastal regions of Greenland and West Antarctica in response to increased ice outflow and increased Greenland surface melting. (Lemke et al., 2007:376).

Since the latest IPCC assessment was published in 2007 (IPCC, 2007), several other compilations have raised concern about the evolution of the big ice masses in response to global warming (Rignot et al., 2008; Steffen et al., 2008; Velicogna, 2009).

There is consensus from observations that the mass loss from the Greenland Ice Sheet has accelerated since 2000. While the contribution from the ice sheet is currently 10–20% of the observed global sea level rise of 3 mm/y, the Greenland Ice Sheet is believed to be capable of reacting more strongly to the warming over the next 100 years with a mass loss that could increase sea level by several tens of centimetres (Rignot et al., 2008; Steffen et al., 2008).

8.2. The Greenland Ice Sheet today

8.2.1. Overview of the Greenland Ice Sheet

- The Greenland Ice Sheet presents a major orographic barrier to Arctic weather systems.
- Long-term temperature records from coastal stations show a warming over Greenland since 1950. Since 1985 in West Greenland, the warming has primarily been driven by higher winter temperatures.
- The basal hydrological system plays an important role in the flow of the Greenland Ice Sheet and is also affected by increasing amounts of surface water drained to the base.

8.2.1.1. Arctic climate and large-scale synoptic observations

Greenland is the largest island in the world with a surface area of 2.2 million km², stretching 2600 km from 59.8 to 83.6° N, where – for several months of the year – it is either polar night or continuous daylight. Over 80% of Greenland is covered by a dome of inland ice (Figure 8.4) rising along an average gradient of about 1% from sea level in various regions to over 3300 m along the central spine.

Greenland plays a pivotal role in determining the climate of the Northern Hemisphere because of its size, location, elevation gradient, and mass of water stored in the ice sheet. During summer, Greenland is ideal for monitoring changes in meridional energy transport into the Arctic because it is located in the predominant direction of cyclone flow. Greenland's extreme North Atlantic location and the ice-filled ocean that surrounds it are the principal factors influencing the climate. The northern branch of the Gulf Stream, known as the North Atlantic Current, runs northward along the Norwegian coast into the Arctic Ocean, mixes with cold polar water and returns southward along the east coast of Greenland. Nearly all the water that leaves the Arctic Ocean passes through Fram Strait (Figure 8.4) via the East Greenland Current, eventually wrapping around Cape Farewell and continuing northward along the west coast of Greenland for several hundred kilometres. A similar, counterclockwise gyre is active along the coast of West Greenland with warm water moving northward




Figure 8.4. Greenland Ice Sheet elevation map and location of WMO climate stations along the coast and Greenland Climate Network (GC-Net) automatic weather stations (blue) in the ice sheet interior and the climate stations from the Geological Survey of Denmark and Greenland (red). Source: Konrad Steffen, CIRES, University of Colorado.

until it meets colder polar water flowing through Kennedy Channel. The resultant cold current flows southward along northeastern Canada.

Wind in the lower troposphere is forced to flow along the coasts of Greenland because of the height and size of the ice sheet. As a result, Greenland is an important participant in the exchange of air mass between the southern and northern latitudes of the Northern Hemisphere. Northerly and southerly air flow are about evenly distributed during summer. However, the predominant flow during winter is northerly due to high pressure in the colder regions to the west or northwest. Airflow in the free atmosphere at the 500 hPa level plays a key role in the Greenland climate because it governs the North Atlantic storm track. Generally, airflow at 500 hPa is from the southwest during winter and from the west during summer.

A typical North Atlantic cyclone develops as a wave in the polar front and propagates along the front. Therefore, winter cyclones generally travel along the east coast of the United States tracking along the edge of the Gulf Stream heading northeast. The cyclones often pass south of Greenland continuing toward Iceland and into the Norwegian Sea. However, they can also track more to the north through Davis Strait and into Baffin Bay. Occasionally, a cyclone will split near the southern tip of Greenland producing separate lows that track along both

coasts. During summer, lows tend to be less intense but are frequently more northerly and, therefore, often influence summer conditions in western Greenland.

Passing cyclones are generally accompanied by strong winds. However, during periods with no cyclone activity, the wind regimes are determined by local conditions, which usually relate to katabatic flow on the Greenland Ice Sheet, and sea breezes during summer or land breezes during winter near the coasts. Whether the high velocity katabatic winds on the ice sheet propagate down the fjords to the coastal areas largely depends on the temperature of the air mass as it reaches the head of the fjords. If the katabatic air mass is warmer than the air in the fjord due to adiabatic warming it will not be able to replace the air near the top of the fjord where it will be experienced as a warm ‘foehn wind’. As a result, it will ride above the colder and denser surface air mass. If the katabatic flow is colder than the air in the fjord, it will replace the local air mass and probably travel all the way to the coast where it will be experienced as an icy downhill wind.

Climatic conditions in the fjords in the absence of cyclonic or katabatic influences are usually characterized by sea breezes during summer and weak land breezes during winter due to ocean-land temperature differences. The winds associated with passing cyclones are, generally, very strong and heavily influenced by local topography and direction of the wind relative to the coast. Winds blowing directly toward the coast will often lead to precipitation due to orographic lifting. This scenario can often lead to very strong barrier winds, which blow clockwise relative to the land mass. Strong winds can cause re-deposition of snow accumulation and even wind-generated mass loss to the sea. Another special feature of the Greenland wind regime is that of very rapid change from calm to gale force conditions. These situations often develop as a result of cold Canadian air reaching the eastern coast of Greenland via the ice sheet behind a cyclone tracking to the northeast. The ice sheet topography determines the direction of the cold outflow from the ice sheet, focusing the wind into the low-lying coastal regions. The Greenlandic term for such an event is *pitoraq* (*pitera*q in East Greenland) which is closely related to the word for ‘being attacked’. *Pitera*qs are most common during autumn and winter. Wind speeds typically reach 50 to 80 m/s. On 6 February 1970, the community Tasiilaq, also known as Ammassalik and the most populous community in East Greenland, was hit by a very strong *pitera*q causing severe damage. Since the beginning of the 1970s, special *pitera*q warnings have been issued by the Danish Meteorological Institute.

Surface air temperature in Greenland during summer is dominated by radiation effects as the sunlight returns to the Arctic. As a result, the mean temperature in July in the northernmost part of the country is only about 2 °C colder than in the southernmost part. However, temperatures at the coast are strongly influenced by the ocean and sea-ice variability; inland temperatures in ice-free regions can, therefore, be 5 °C warmer than at the coast. The proximity of the ice sheet does not seem to cool neighboring areas because the air flow off the ice during summer is usually warmer than the low lying local air mass due to adiabatic warming.

The latitudinal temperature gradient is much greater during winter than during summer with average sea level February

air temperatures in the north of -36 °C and in the south of -4 °C. Variability is also much greater without the moderating influences of the open ocean in the north and the melting ice sheet. Katabatic storms often raise winter temperatures above freezing via the combined effects of adiabatic warming and mixing of the inversion layer, particularly in the southern regions, where winter temperatures in the fjords can reach 10 °C (Cappelen, 2003).

Analysis of the long-term temperature record (1840 to 2001) from coastal stations in Greenland (Vinther et al., 2006, 2010) puts the more recent observations from satellites and weather stations on the Greenland Ice Sheet into a broader context (Box, 2002). The warmest decades in the long-term Greenland temperature record (1840 to 2000) are the 1930s and 1940s. Generally, the west coast experienced warming from 1873 to 1930 followed by cooling until 1988. There has been a warming trend since 1985 of 2 to 4 °C in West Greenland, primarily driven by winter temperature anomalies. The current warm period, beginning in 1988, is not unprecedented because the record warm decades occurred during the 1930s and 1940s.

The recent warmth occurred in spite of a persistently positive North Atlantic Oscillation (NAO) since around 1970. The NAO has a significant influence on the coastal temperature record particularly in the western and southern regions of Greenland during winter. The spectra of the temperature records display peak power at 3.7 years which Box (2002) attributed to the NAO, which has a spectral peak at ~4.0 years. The positive trend in coastal temperatures in southwestern Greenland appears to be responsible for the ice-sheet thinning observed in the region (Ohmura et al., 1999).

Volcanism has a significant cooling effect on temperatures in southern and western Greenland with a peak lag of 5 to 10 months following major eruptions (Box, 2002). The warming trend in Greenland since the early 1990s, in spite of major volcanic eruptions in 1982 and 1991, stands in contrast to the warmth of the 1930s and 1940s during a period of anomalously low volcanic activity (Overland et al., 2004).

Meteorological station records and regional climate model output were combined to develop a continuous 168-year (1840 to 2007) spatial reconstruction of monthly, seasonal, and annual mean Greenland Ice Sheet near-surface air temperatures (Box et al., 2009). Box and co-workers found that volcanic cooling episodes were concentrated in winter and along the western ice sheet slope, that inter-decadal warming trends coincided with an absence of major volcanic eruptions, and that 2003 was the only year in the 168-year series with a warm anomaly that exceeded three standard deviations from the 1951–1980 base period. The magnitude of the annual whole ice sheet 1919–1932 warming trend is 33% greater than the 1994–2007 warming. Box et al. (2009) also found that the recent warming was stronger along western Greenland in autumn and southern Greenland in winter. Spring trends marked the 1920s warming onset while autumn leads the 1994–2007 warming.

The climate on the Greenland Ice Sheet has been studied intensively in an effort to quantify the surface mass balance and to estimate its contribution to global sea level. However, *in situ* observations are limited due to the large area and remoteness of the ice sheet. The notable exception is the climate record from the Greenland Climate Network (GC-Net) of automatic weather stations, operating since 1995 and distributed across the

ice sheet (Figure 8.4). Scientists are, therefore, forced to rely on remotely sensed observations and estimations from downscaled general circulation models (GCMs) or high-resolution regional climate models (RCMs). However, systematic biases in the models relative to the *in situ* record illustrate that the climate of the ice sheet is more or less decoupled from the coastal regions where most of the direct observations that feed the models are made. Nevertheless, a consensus picture of change due to a warming climate since 1995 is emerging.

8.2.1.2. Climate observations

The Danish Meteorological Institute (DMI) data are the most comprehensive meteorological records available for Greenland's coastal region and have been homogenized, most notably the original observations have been checked and the data compared with time series of related climatic elements for the same stations, with the specific purpose of studying long-term climatological trends (Cappelen et al., 2001).

Monthly air temperature records from eight DMI synoptic stations at the coast of Greenland (located mainly in the southwest but including Tasiilaq in the southeast) show a pronounced warming since the early 1990s. The warming follows an overall trend of regional cooling between 1958 and 1992, concentrated in the winters of the 1960s to 1980s (Hanna and Cappelen, 2003). Summer trends for the 7-station DMI

average (i.e., excluding Kangerlussuaq because of its relatively short record) indicate a significant warming for 1961 to 2006 of 0.9 °C.

For the DMI station average, 2003 had the warmest summer (i.e., June to August) on record, with a mean temperature of 8.1 °C at 3.3 standard deviations above the most recent climatological 'normal' period (1971–2000) mean. The second warmest summer occurred in 2005 (7.6 °C) at 2.5 standard deviations above the 1971–2000 mean. 2005 was more than 0.5 °C warmer than the third warmest summer, 2006 (7.07 °C) which was closely followed by 2001 (7.02 °C), 1965 (7.00 °C), and 2004 (6.97 °C) (Hanna et al., 2008).

The record for the GC-Net automatic weather station 'Swiss Camp' (1170 m above sea level in 1991 and since then decreasing 0.32 m annually; Stober and Hepperle, 2006; Figure 8.4) (Steffen and Box, 2001) was used to gauge temperature changes on the western flank of the Greenland Ice Sheet, where extensive seasonal melt and relatively high runoff from this relatively low elevation zone contribute a large proportion of the total runoff (Hanna et al., 2005; Box et al., 2006). This record, by far the longest GC-Net series, spans 19 years (1991 to 2009), and its interannual variability is significantly correlated with that of the mean of the seven DMI coastal stations (detrended series $r = 0.65$, $p < 0.01$; Figure 8.5).

Similar to the positive (7-station mean) DMI temperature




Figure 8.5. (a) Summer (June–July–August) mean temperature at Greenland climate stations for the period 1958 to 2006 (for locations see Figure 8.4). (b) Greenland summer mean temperature from the mean of seven DMI stations (see Figure 8.4, except Kangerlussuaq) compared with the northern-hemisphere summer mean temperature, with five-year running means of both series. Note some early years in Greenland / Northern Hemisphere antiphase (e.g., 1965, 1971, 1983), as highlighted by the disparate running means, but the post-Pinatubo (1992 onward) period shows better agreement in terms of interannual variability, correlation, and strong upward trends. Source: Hanna et al. (2008).

trend, Swiss Camp summer mean temperature increased significantly by 2.4 °C from 1991 to 2008, or 2.2 °C for the period 1993 to 2008, excluding the global cooling effect of the Mount Pinatubo eruption in 1992. The three summers of 2003/2004/2005 were almost equally record warm (mean temperatures 0.3, 0.3, and 0.2 °C, respectively) at Swiss Camp, alongside 1995 (0.5 °C) and the record year 2007 (1.2 °C). The latter season has been previously noted for its relatively high modeled runoff compared with most other years between 1958 and 2003 (Hanna et al., 2005). The latest data from the Swiss Camp GC-Net record show a continued warming with another record mean summer temperature of 1.2 °C in 2007; 0.7 °C above the previous maximum in 1995.

A reprocessed and updated near-surface air temperature series for Summit (1987–2005, 3205 m above sea level) (Shuman et al., 2001) shows a slight overall -0.3 °C cooling in summer, in contrast to all the other Greenland temperature records (all from much lower elevations and generally around the ice sheet margin; Figure 8.5). This new Summit series is a re-analyzed composite, primarily of University of Wisconsin and ongoing GC-Net automatic weather station data, supported by SSM/I (Special Sensor Microwave / Imager) brightness temperature data (Shuman et al., 1996, 2001). There is a highly significant correlation between individual years' fluctuations in the detrended DMI and the Summit series (Figure 8.5).

Three hypothesized possible causes for the cooling trend observed at Summit compared to the warming trend along the coast are: (i) continued relative suppression of more regional climatic change by thermal inertia of the huge central Greenland ice mass as noted for Arctic Ocean sea ice (Serreze and Francis, 2006); (ii) a differential response of the high elevation zones of the Greenland Ice Sheet in accordance with the well-known lower tropospheric warming / higher atmospheric cooling response to increased greenhouse gases (Stott et al., 2006), which has been demonstrated specifically for Greenland in a recent analysis of radiosonde data spanning the period 1964 to 2006 (Box and Cohen, 2006); and/or (iii) regional changes in wind, cloud cover, or radiation patterns over the Greenland Ice Sheet.

This observed pattern (coastal, i.e., marginal, warming combined with little change or slight cooling in the high interior) is opposite to the output of simulations from Atmosphere-Ocean General Circulation Models (AOGCMs). In all high-resolution temperature changes studied in the present century, Huybrechts et al., (2004) and Gregory and Huybrechts (2006) found that modeled summer warming is actually greatest over the interior of Greenland and least along the coast.

High-resolution (5 km × 5 km) surface air temperature (SAT) data were bilinearly interpolated from the 0.5° resolution 40-year European Centre for Medium-Range Weather Forecasts (ECMWF) Re-Analysis (ERA-40) and corrected for ECMWF terrain errors using empirically derived ice sheet surface lapse rates, as explained by Hanna et al. (2005). These SAT data provide corroborating evidence for anomalously (3 °C) high summer temperatures around the Greenland margins during recent warm summers with a noted high melt, which occurred most widely within the southern and western marginal ablation zones of the ice sheet.

The accumulation zone of the Greenland Ice Sheet (above 2000 m elevation) apparently had cold summer anomalies in

2003 and 2006. This is in contrast to warm anomalies in more outlying areas but in line with the Summit temperature results discussed previously. Summer temperatures both in Greenland and across the Northern Hemisphere exhibit strongly rising trends since the early 1990s, although the earliest part of this period (1992–1993) characterizes the general temperature recovery following the cooling after the 1991 Mount Pinatubo volcanic eruption (Robock and Mao, 1995).

Observations and models both indicate the occurrence of recent high snow accumulation events in the winter of 2004/2005, concentrated in western Greenland (Nghiem et al., 2007), and winter–spring 2002/2003 in southeastern Greenland (Krabill et al., 2004; Hanna et al., 2006). Huybrechts et al. (2004) hypothesized that such events may become more frequent in Greenland as storm tracks intensify or shift position with climate change.

8.2.1.3. Surface and basal properties and processes

Surface melting in the ablation zone (Figure 8.6) is highly sensitive to changes in surface albedo. Melting of ice in the ablation zone exposes a surface layer of dust that was originally deposited with snowfall high on the ice sheet. Dust in snow and on ice reduces the solar reflection (albedo) and, thus, increases surface melt further. Surface albedo decreased dramatically at Swiss Camp during 1993 to 2008 and this led to increased surface melt and ablation at Swiss Camp (Figure 8.7).

Basal melt and meltwater exert a strong influence on ice flow (Fahnestock et al., 2001). The limited knowledge of basal melt is derived from models and sparse observations of bed properties. A basal melt rate of 0.1 m/y over a substantial area requires a regional geothermal heat flux of 970 MW/m², which is 17 times higher than the continental background of 56.5 MW/m² (Sclater et al., 1980). This does not account for heat conducted through the ice. For most of the ice sheet, the heat conducted through the ice is close to the background geothermal heat flux. It can be lower in low-accumulation regions because the thermal gradient in the basal ice is lower. The volume of meltwater being produced in the areas of high basal melt is of the order of 1 km³/y. This water and warm basal ice are responsible for the onset of rapid ice flow in the large ice stream that drains the north side of the summit dome in Greenland (Fahnestock et al., 2001). Strong melt also occurs due to deformation heat under the fast-flowing ice streams thereby further increasing their flow. Melt rates of metres per day are observed where the base of the ice streams is in contact with the ocean (Rignot et al., 2010).

Basal flow can transport ice at velocities exceeding rates of internal deformation (i.e., from hundreds to more than 10 000 m annually) and glacier surges, tidewater glacier flow, and ice stream motion are governed by basal flow dynamics (Clarke, 1987). Glaciers and ice sheets that are susceptible to basal flow can move quickly and erratically, making them intrinsically less predictable than those governed by internal deformation. They are more sensitive to climate change because of their high rates of ice turnover which gives them a shorter response time to climate (or ice margin) perturbations. In addition, they may be directly responsive to increased amounts of surface meltwater production associated with climate




Figure 8.6. The ice cover in Greenland and Antarctica has two components – thick, grounded, inland ice that rests on a more or less solid bed, and thinner floating ice shelves and glacier tongues. An ice sheet is actually a giant glacier, and like most glaciers is nourished by the continual accumulation of snow on its surface. As successive layers of snow build up, the layers beneath are gradually compressed into solid ice. Snow input is balanced by glacial outflow, so the height of the ice sheet stays approximately constant through time. The ice is driven by gravity to slide and to flow downhill from the highest points of the interior to the coast. There it either melts or is carried away as icebergs that eventually melt, thus returning the water to the ocean from where it came. Outflow from the inland ice is organized into a series of drainage basins separated by ice divides that concentrate the flow of ice into either narrow mountain bounded outlet glaciers or fast-moving ice streams surrounded by slow-moving ice rather than rock walls. In Antarctica, much of this flowing ice has reached the coast and has spread over the surface of the ocean to form ice shelves that are floating on the sea but are attached to ice on land. There are ice shelves along more than half of Antarctica's coast, but very few in Greenland. Sources: UNEP Maps and Graphs; Konrad Steffen, CIRES, University of Colorado.




Figure 8.7. Interannual variability of monthly mean albedo at Swiss Camp (1993 to 2008). Note the decrease in surface reflectivity (albedo) for the summer months (June–August) with values as low as 0.4 in 2007 and 2008. Increase in summer air temperature at this elevation enhances snow and ice melt as well as reducing albedo. Hence, less solar radiation is reflected and this further increases surface melt (positive albedo feedback). Source: Konrad Steffen, CIRES, University of Colorado.

warming. This latter process is crucial for predicting dynamic feedbacks to the expanding ablation area, longer melt season, and higher rates of surface meltwater production that are predicted for most ice masses.

Although basal meltwater is most likely to be the primary source of subglacial water, models have shown that supraglacial streams with discharges of over $0.15 \text{ m}^3/\text{s}$ can penetrate down through 300 m of ice to reach bedrock, via self-propagation of water-filled crevasses (Arnold and Sharp, 2002). There are several possible subglacial hydrological configurations: ice-walled conduits, bedrock conduits, water film, linked cavities, soft sediment channels, porous sediment sheets, and ordinary aquifers (Mair et al., 2001; Flowers and Clarke, 2002).

Modern interest in water flow through glaciers originated in a pair of theoretical papers published in 1972. In one, Shreve (1972) discussed the influence of ice pressure on the direction of water flow through and under glaciers, while Röthlisberger (1972) presented a theoretical model for calculating water pressures in subglacial conduits in the other. Through a combination of these theoretical considerations and field observations, Röthlisberger concluded that the englacial drainage system probably comprises an arborescent network of passages. The millimetre-sized fingertip tributaries of this network join downward into ever larger conduits.

Locally, moulins provide large direct connections between the glacier surface and the bed. Beneath a valley glacier, the

subglacial drainage is likely to occur as a tortuous system of linked cavities transected by a few relatively large and comparatively straight conduits. The average flow direction in the combined system is controlled by a combination of ice overburden pressure and bed topography, and, generally, is not normal to contours of equal elevation on the bed.

Luthje et al. (2006) studied the summer evolution of supraglacial lakes on the Greenland ice margin using a one-dimensional model to calculate the surface ablation for a bare ice surface and beneath supraglacial lakes for 30 days in the summers of 1999 and 2001. The surface ablation beneath the lake was enhanced by 110–170% for the two years 1999 and 2001 compared with the ablation for bare ice. Within the region of the ice sheet where supraglacial lakes presently occur, the area covered by supraglacial lakes was found to be more or less independent of the summer melt rate but controlled by topography. Luthje and co-workers predicted that, inside the ablation region, the area covered by supraglacial lakes will remain constant even in a warmer climate.

Although theoretical studies usually assume that subglacial conduits are semicircular in cross section, there are reasons to believe that this ideal is rarely realized in nature. Much of the progress in subglacial hydrology has been theoretical, as experimental techniques for studying the englacial hydraulic system are few and, as yet, not fully exploited and observational evidence is difficult to obtain. How directly and permanently do these effects influence ice dynamics? It is not clear at this time. The process is well known in valley glaciers where surface meltwater that reaches the bed in the summer melt season induces seasonal or episodic speed-ups (Iken and Bindshadler, 1986). Speed-ups have also been observed in response to large rainfall events (e.g., O’Neel et al., 2005).

8.2.1.4. Summary

Is the climate in Greenland changing? Coastal records since 1840 show the warmest decades to be the 1930s and 1940s and a warming trend since 1988 of 2 to 4 °C in West Greenland, mainly during the winter months. Recent, short-term temperature records on the ice sheet in West Greenland (Swiss Camp) show a 2.2 °C warming in summer since 1991 with the highest air temperatures in 2007. Air temperatures at the top of the Greenland Ice Sheet (Summit) revealed a slight cooling of -0.3 °C between 1987 and 2005. Decadal-scale trends over the past century, however, are complicated by the large degree of natural variability (Chylek et al, 2006). The observation period for the recent climate warming over Greenland is short.

8.2.2. Surface mass balance

- The surface mass balance of the Greenland Ice Sheet has decreased since 1990. The mean of three model reconstructions of the surface mass balance show a 40% decrease from 350 Gt/y (1970–2000) to 200 Gt/y in 2007.
- The runoff has increased significantly due to higher temperatures, increasing ablation zone area and a longer melt season.
- These trends in surface mass balance have been linked to a global warming trend that exceeds the local natural variability in climate.

8.2.2.1. Introduction

The total mass balance of the Greenland Ice Sheet (Section 8.2.4) determines its overall state of health and is the sum of two terms: the surface mass balance (SMB), discussed here, and solid ice discharge from marine terminating glaciers, discussed in Section 8.2.3. The SMB is the net mass added or removed from the surface of an ice sheet by a range of processes. The aim of this section is to introduce the factors that control SMB, and how they respond to climate change. This is achieved by reviewing recent estimates of the components that make up the SMB, discussing the degree of consistency in these components, both from observations and modeling, and considering areas of uncertainty requiring further development.

The annual SMB is defined as the sum of mass fluxes to and from the ice sheet surface, integrated over a year and over the area of the ice sheet. Mathematically, this is expressed as:

$$\text{SMB} = P + \text{TMT} - R - Q$$

where P is total precipitation, comprising the solid fraction (snow, hail, freezing rain) as well as the liquid fraction (rain); TMT is turbulent moisture transport, representing the net effect of surface evaporation, sublimation/deposition and snowdrift sublimation; R is runoff, representing the net effect of condensation, melt, refreezing and retention; and Q is the snowdrift blown off the ice sheet integrated along the entire margin. All fluxes are in Gt/y and integrated over the area of the ice sheet. Snowdrift plumes being blown into the ocean have been occasionally observed, but Q is believed to impact SMB significantly only locally and is not further considered here (Box et al., 2006). The accumulation zone is the region where $\text{SMB} > 0$ and the ablation zone is the region where $\text{SMB} < 0$. The equilibrium-line altitude (ELA) is the elevation where $\text{SMB} = 0$. It is important to note, however, that precipitation takes place in the ablation zone and runoff can take place in the lower part of the accumulation zone. Above the ELA, however, accumulation (via snowfall) exceeds ablation (via runoff) and below the ELA the opposite is true. For an ice sheet as a whole to be in a state of balance, SMB must match the solid ice flux crossing the grounding line and flowing into the ocean. For the Greenland Ice Sheet, this was roughly the case prior to the 1990s but there has since been a marked increase both in solid ice flux (Rignot and Kanagaratnam, 2006) and runoff (e.g., Hanna et al., 2008; Ettema et al., 2009). Accumulation includes all processes by which mass is added to the ice sheet, which, in this case is almost entirely through precipitation in the form of snowfall. The accumulation rate is what is typically measured with *in situ* observations from snow pits or shallow ice cores in the high elevation zones of the ice sheet where there is basically no runoff. It is usually expressed as a water equivalent (w.e.) thickness change per unit area per unit time. Ablation includes all process by which mass is lost from the ice sheet. This section, however, only considers ablation via surface melting (called runoff). The other major component of ablation due to solid ice discharge into the ocean is dealt with in Section 8.2.3. The ablation rate is identical and has the same units but is a measure of net mass loss at the surface rather than mass gain. Ablation rates can be measured during the summer melt season using, for example, stakes drilled into the ice surface.

These observations of surface accumulation/ablation rate are equivalent to the local SMB.

There are a number of approaches for estimating SMB. The first, and the only tractable approach until quite recently, involves the interpolation of *in situ* observations of point SMB (accumulation/ablation) estimates from snowpits, ice cores, stake measurements and automatic weather stations to estimate accumulation rates (Figure 8.8). The data were combined with simplified models of runoff, R , to determine SMB (Ohmura and Reeh, 1991; Reeh, 1991; Ohmura et al., 1999; Bales et al., 2001; Steffen and Box, 2001). The more recent interpolations to determine accumulation rates also included a formal assessment of the error associated with field data and their interpolation (Cogley, 2004; Bales et al., 2009) as discussed in Section 8.2.2.2.

Commonly, runoff has been estimated using an empirical model of melt, M (see Section 8.2.2.3), combined with simplified assumptions about refreezing, RF , calibrated using stake measurements (Reeh, 1991; Braithwaite et al., 1992; Braithwaite, 1995). The differences in the estimations of runoff from the different models are of the order 25% (Table 8.2). The individual components contributing to runoff (M and RF) vary by far more than this. Thus, the agreement in R is largely based on compensating differences. The different runoff models have very different sensitivities to forcing and, as a consequence, the ability to predict the true response of SMB to a future change in climate also contains significant uncertainties (Bougamont et al., 2007).

Recently, alternative approaches for estimating SMB have been developed, especially following the release of a high-quality, consistent ~50 year global climatology produced by ECMWF. The data set is known as ERA-40 (i.e., ECMWF Re-Analysis covering the ~40 year period 1957–2002). ERA-

40 is a hind-cast generated using the ECMWF atmospheric forecast model driven by surface and satellite meteorological observations (Uppala et al., 2005). ERA-40 produces 6-hourly and daily fields of key atmospheric parameters at 1.125° resolution, which equates to a grid cell size of ~125 km in latitude. This resolution is too coarse to be used unadjusted for SMB calculation as the ablation zone, for example, is mostly less than a single grid cell in width. As a result, various approaches, commonly termed downscaling, have been used to interpolate ERA-40 to higher resolution. The simplest approach has been to downscale surface air temperature using seasonally adjusted lapse rates and high-resolution surface topography as well as a simple interpolation of precipitation (Hanna et al., 2002, 2005) (Table 8.2 and Figure 8.9).

Another approach is to use an atmospheric RCM as a physically-based ‘interpolator’ of the reanalysis data. Generally, an RCM is run at high resolution for a limited area and forced at its boundaries by climate data from a coarser-resolution GCM. To date, three RCMs have been used to produce a high-resolution time series of the Greenland Ice Sheet SMB (Box et al., 2004, 2006; Fettweis, 2007; Ettema et al., 2009) although others are under development.

It is interesting to note how SMB responds to changes in climate. Increased near-surface air temperatures bring about increased moisture and, therefore, precipitation. Simulations with coupled atmosphere-ocean GCMs suggest a 5%/K sensitivity of P to surface air temperature (Gregory and Huybrechts, 2006). This value can be combined with SMB ‘climate sensitivities’ (especially to changes in temperature and precipitation) estimated from an energy balance model that suggests that the area-averaged SMB sensitivity, CT , to temperature is -49 mm/K and to precipitation, CP , 3.8 mm/% (Oerlemans et al., 2005). Using the sensitivity of precipitation




Figure 8.8. Net accumulation (snowfall minus turbulent moisture transport) from three recent estimates. Figures a and b are from observations, while c is from a regional climate model. Sources: (a) Bales et al. (2001, 2009); (b) Cogley (2004); (c) MAR (Fettweis, 2007).

Table 8.2. Estimates of the SMB components in Gt/y for Greenland from satellite (Mote, 2003) and modeling studies for the range of time periods specified. The regional climate models, PMM5, RACMO2/GR and MAR are discussed in Section 8.2.2.2. The sum of RF and R does not necessarily equal M, depending on how rain is treated.

Model	Period	Area $\times 10^7$ km ²	P	TMT	Rain	M	R	RF	SMB
MAR ^a	1958–2007	1.701	575	-5	20	532	282	250	264
PMM5 ^b	1958–2006	1.691	555	-63	16	228	213	48	326
Hanna ^c	1958–2007	1.678	559	-35	26	313	261	77	264
RACMO2/GR ^d	1958–2007	1.69	743	-26	46	404	248	199	469
Mote ^e	1988–1999	1.648	591	-69	23		255		239
Reeh ^f	1990s	1.707	552 ^g				279		273

P: Precipitation, comprising the solid fraction (snow, hail, freezing rain) as well as the liquid fraction (rain); TMT: Turbulent Moisture Transport, comprising surface evaporation, sublimation/deposition and snowdrift sublimation; Rain: liquid fraction of precipitation; M: total volume of Meltwater; R: Runoff, comprising the liquid water fraction from melt and rain that leaves the firn/ice column; RF: Re-Freezing; SMB: Surface Mass Balance.

^a Modèle Atmosphérique Régional (Fettweis, 2007); ^b Polar Mesoscale Model version 5 (Box et al., 2004); ^c Hanna et al. (2002, 2005); ^d Ettema et al. (2009); ^e Mote (2003); ^f Reeh et al. (1999); ^g Reeh and co-workers (1999) did not estimate the individual terms in accumulation and the tabulated value represents, therefore, P-TMT-Rain.

to temperature, given above, makes it possible to express CP with respect to temperature, which gives $CP = 19$ mm/K. Thus the increase in runoff greatly outweighs the increase in accumulation (49 vs 19) for a fixed temperature change. Assuming the area of the ice sheet to be 1.7 million km² then the increased mass loss from the ice sheet is 47 Gt/K, excluding any dynamic response. Thus, simulations of future SMB for various greenhouse gas emissions scenarios generally predict a decreasing SMB (Gregory and Huybrechts, 2006). Most importantly, this is what has been observed to have taken place over the past 15 years, since the temperature increase over Greenland started (Hanna et al., 2008).

8.2.2.2. Accumulation

8.2.2.2.1. Observations

Shallow ice cores and snowpit measurements have been collected and used to determine accumulation rates, going back to the 1920s (Ohmura and Reeh, 1991). In this compilation, 251 measurements of accumulation rate were used to derive a map of precipitation for the whole of Greenland. Since the 1990s, the Program for Arctic Regional Climate Assessment (PARCA), a NASA-funded, multi-decadal, coordinated project, has been supplementing these records and collecting many other types of data with the aim of improving estimates of




Figure 8.9. Time series of surface mass balance components from four different models: (a) melt, (b) accumulation, (c) runoff, (d) SMB. Note that the y-axis scales are not the same for each plot. Source: Jonathan Bamber, University of Bristol.

a wide range of key parameters for the ice sheet (Abdalati, 2001). Among the measurements taken were over 100 shallow ice core estimates of accumulation. These were combined with a subset of the historical records to produce the most comprehensive observation-based map of accumulation across the ice sheet to date. The estimated mean error for this compilation was 24% with regional variations of 15–30% (Bales et al., 2001). This compilation has recently been updated with a number of new cores and coastal station data (Figure 8.10) (Bales et al., 2009). The recent update resulted in regional changes, compared with the earlier study, of as much as $\pm 50\%$, suggesting that uncertainties in accumulation rates were significantly underestimated in previous studies: a conclusion that is corroborated by the substantial differences in modeled accumulation shown in Figure 8.9.

The average accumulation rate of 300 kg/m^2 over the ice sheet agrees well with an earlier estimate obtained from different sources and covering a different time period (Ohmura and Reeh, 1991), and with a further estimate using a different interpolation approach (Cogley, 2004). Although there is agreement between the average values of the estimated accumulation, examination of the spatial distribution demonstrates marked and significant differences (Figure 8.8).




Figure 8.10. Locations of ice cores (red symbols) and coastal meteorological station (yellow symbols) data used to reconstruct accumulation rates over the ice sheet. Source: Bales et al. (2009).

An error analysis of *in situ* snowpit and ice core data suggested an uncertainty of 7.7% in the averaged 30-year mean. This is in agreement with the error estimate from the most recent study (Bales et al., 2009). It does not, however, reflect the interannual and spatial uncertainties which are very much greater (Bales et al., 2009). Uncertainties in the spatial pattern can have a significant impact on modeled estimates of ablation due to the influence of snowfall on surface albedo and refreezing (see discussion in Section 8.2.2.3). In addition, rain is a small but important term of the accumulation rate. Although its volume is low ($\sim 4\%$ of total precipitation), its impact can be important because upon refreezing it raises the heat content of the snowpack, and in doing so increases total melt and runoff volume. The increased percentage of precipitation falling as rain in a warming climate will have a stronger influence on runoff and, hence, SMB.

8.2.2.2.2. Regional climate models

One big advance in assessing the SMB of the Greenland Ice Sheet, its temporal evolution and the relative importance of different components and their sensitivity to climate has been the development of RCMs. The first high-resolution RCM for Greenland was based on a modified version of the fifth generation mesoscale model known as PMM5 (Polar MM5; Box et al., 2004). This model ran at 24 km resolution and was calibrated using *in situ* data to correct for biases in melt energy and water vapor fluxes (Box et al., 2004). It was run, initially, for the period 1957 to 2004 forced by ERA-40 data (Box et al., 2006) (see Table 8.2 and Figure 8.9).

More recently, a 25 km resolution RCM was developed by Gallée and Schayes (1994) and applied to the Greenland Ice Sheet by Fettweis (2007) for the period 1958 to 2006. Unlike PMM5, the MAR (Modèle Atmosphérique Régional) has not been calibrated or corrected using *in situ* data. Comparison of modeled water vapor fluxes from MAR with automatic weather station data suggests that TMT is underestimated in MAR (Fettweis, 2007). Precipitation and runoff, however, are broadly comparable with other estimates from modeling and observations. The individual terms that comprise the runoff (M and RF) are both much greater than, for example, those of Hanna et al. (2008) (Table 8.2, Figure 8.9).

The third, a 50-year RCM reconstruction driven by ERA-40 data, is known as RACMO-2/GR. This is an adapted version of the ECMWF regional forecast model and was initially developed to run over Antarctica (van de Berg et al., 2006). More recently it has been coupled to a snow metamorphism and melt model (Bougamont et al., 2005) and run at 11 km resolution over a domain covering the whole of Greenland (Ettema et al., 2009). Like MAR, it was not calibrated using any *in situ* observations. The total accumulation from the RACMO-2/GR RCM is 7–24%, higher than the estimates from the other RCMs (Figure 8.9c). The greatest differences between the accumulation estimates from the RCMs are found in the wet southeast of Greenland where precipitation is estimated to exceed 4 m w.e./y locally. This unusually high value is consistent with a single ice core obtained from this region (Ettema et al., 2009).

It should be noted that RCMs are the only approach where all the components of SMB can be separated. *In situ* data provide the net SMB: that is, precipitation minus TMT terms

and runoff. Also, measuring melt volume and refreezing, in the field, is challenging (Bøggild et al., 2005). The models suggest that TMT is generally negative, indicating net sublimation/evaporation, with a magnitude of about 10% of P, except in MAR, where it is an order of magnitude smaller.

8.2.2.3. Ablation

8.2.2.3.1. Observations

Direct observations of ablation rates around the margins of the Greenland Ice Sheet are sparse both in space and time (Figure 8.11). Ablation has been measured using stakes at a number of sites in Greenland (Braithwaite et al., 1992) and, more recently, a technique has been developed for making automated measurements (Bøggild et al., 2004a). However, the spatial coverage is far from representative. One of the more comprehensive and uninterrupted *in situ* data sets has been collected since 1990 by Utrecht University along a 150-km transect near Kangerlussuaq, central western Greenland, known as the K-transect (Greuell et al., 2001; van de Wal et al., 2005). Stake measurements of mass balance have been collected at eight sites along the K-transect since 1990 and automatic weather station data are available since 1997 at one site and since 2003 at two further sites.

This represents the longest existing continuous record of *in situ* mass balance and ablation data for the Greenland Ice Sheet, but how representative the data are of other parts of the ablation zone is uncertain. This region of the ablation zone is, generally, smoother and less rugged compared with areas to the north and south. Small-scale topography affects the microclimate and therefore local ablation variability. A modeled time series used to assess the spatial autocorrelation of SMB showed little autocorrelation in the ablation zone in the southeast, a negative correlation in the northeast, and a strong positive correlation along the western margins suggesting that ablation depends on local conditions (as would be expected) as well as larger-scale climate forcing (Box et al., 2006). For example, in northeastern Greenland at the Storstrømmen glacier at 77° N, the observed large spatial variability in ablation is mainly controlled by the katabatic windfield producing a highly uneven winter snow cover distribution and higher melt rates locally at convex surface undulations.

Although the *in situ* data cannot be used to provide direct estimates of ice-sheet integrated ablation or the individual ablation components, they can be used to validate and calibrate satellite and model-based estimates. The spatial coverage of the quite sparse observational points, however, is currently not adequate to provide representative sampling to validate and calibrate satellite and model-based estimates of ablation.

The runoff component of the ablation has also been estimated using calibrated satellite observations of passive microwave melt extent and duration (Mote, 2003) and satellite-derived albedo data (Greuell and Oerlemans, 2005). Both approaches rely on an empirically derived relationship between melt duration or albedo and runoff. Estimating runoff from routinely acquired satellite observations is a promising technique but is empirically based and it remains to be shown whether the relationships derived are robust under current and future (changing) climate conditions. Recent results have




Figure 8.11. Location of ice sheet ablation measurements up to 2004. Source: Bøggild et al. (2004b).

shown, for example, that for areas in Antarctica where melt occurs, passive microwave-derived values underestimate SMB (Magand et al., 2008).

In addition to estimating runoff, passive microwave data have also been used to measure the area of the Greenland Ice Sheet subject to surface melt (Abdalati and Steffen, 2001; Mote, 2007). Results indicate that the melt area has been steadily increasing since satellite observations began (Figure 8.12). Although this is not a direct measure of runoff (because it does not estimate the volume of melt or refreezing) there is a good correlation between melt area, number of melt days, and runoff (Mote, 2003).

In this approach, the satellite-based melt duration data are used as a proxy for surface air temperature. Although this method has some merit, the development of a consistent, homogeneous temperature data set derived from ERA-40 and extending back to 1958, provides a longer time series with roughly the same correlation with runoff (Hanna et al., 2002, 2005). Its advantage, however, is that it represents a direct observation of changing surface properties as opposed to a model reconstruction and can, therefore, be used to corroborate the estimates derived from re-analysis data. In addition, it provides observational evidence for changes in the length of the melt season and its onset date (Figure 8.12).




Figure 8.12. (a) Departure of the 2008 melt frequency from the mean melt frequency for 1973–2008, and (b) departure of the date of melt onset in 2008 from the mean date of melt onset for 1973–2008. Elevation contours are shown in grey, and black indicates land area. Source: Mote (2007); T.L. Mote, pers. comm.

8.2.2.3.2. Runoff modeling

The first reasonable, quantitative attempts to model runoff from the Greenland Ice Sheet used a positive degree day (PDD) approach (Reeh, 1991). Here, the melt volume is related to the number of days where the near surface air temperature (usually taken at 2 m above the surface) exceeds 0 °C, and by how much. Melt volume is calculated by multiplying the positive temperature by a degree day factor (typically ~ 8 mm/°C per day for ice). This approach has been, and still is, used extensively for modeling the present-day runoff and SMB of the Greenland Ice Sheet (Braithwaite, 1995; Abdalati et al., 2001; Mote, 2003; Hanna et al., 2006; Rignot and Kanagaratnam, 2006) as well as its response in the future (Huybrechts et al., 2002, 2004).

The compelling advantage of the PDD approach is that it relies on a single, smoothly varying and easily interpolated parameter, i.e., near surface air temperature. Climatological maps of this parameter have been produced from a combination of coastal station and inland automatic weather station data (e.g., Ohmura, 1987) and more recently downscaled from ERA-40 (Hanna et al., 2002, 2005). The weakness of the approach is that it relies on an empirically based relationship, calibrated using a limited range of data for present-day conditions only. As a result, it is unclear how well a PDD model can predict melt in the future (Bougamont et al., 2007). For example, a PDD model has no sensitivity to changes in cloud cover or type unless they impact near-surface air temperature. Modifications to the approach have been suggested to incorporate more of the physical processes involved (Pellicciotti et al., 2005) but remain, fundamentally, empirical.

A more physically rigorous approach is to calculate the energy balance at the surface and, from this, the quantity of energy available for melting. Most recently, energy balance

models have been used to estimate melt volume over Greenland by downscaling meteorological hindcast data such as ERA-40 (Box et al., 2004, 2006; Fettweis et al., 2005). Generally, these types of model incorporate all the key processes that affect melt but, as a result, require a large number of meteorological inputs that may not be constrained particularly well. For example, to estimate the turbulent, sensible and latent heat fluxes, requires prescribing a surface roughness as well as atmospheric stability corrections. It also requires near-surface humidity and the vertical wind profile in the boundary layer, all of which may not be particularly well known.

The single most important surface property for controlling runoff in the energy balance, however, is surface albedo, α . This can be estimated by the model based on snow age and/or density (Greuell and Konzelmann, 1994; Konzelmann et al., 1994) or prescribed from satellite observations (Stroeve, 2001). Model-based estimates, however, are generally only reliable for snow. Ice in the ablation zone can have an albedo of 0.4 or less (see Figure 8.7), which is substantially less than that of snow. Ice albedo depends on aerosol content and this is highly spatially heterogeneous. The advantage of an energy balance model compared to a PDD approach is that it incorporates the physical processes responsible for melt explicitly and should, therefore, respond appropriately to changing climate forcing. To do this, however, requires the ‘correct’ forcing. For long integrations (e.g., multi-centennial) such input data typically do not exist or may not be reliable enough to justify the use of a more complex and more ‘data hungry’ energy balance model. Thus, although an energy balance model may provide a more physical representation of the processes, it will not always be the best tool to use.

Preconditioning of the snowpack and the firn is very important for subsequent melt and runoff. In the SMB time

series of Hanna et al. (2005), high runoff years (except 2003) are generally synchronous with low precipitation / accumulation and vice versa. More accumulation results in a higher albedo for a longer time, which, in turn, reduces absorbed energy available for melt; the available surface energy needs to melt any snow first before ice can melt in the ablation region. Also, higher volumes of meltwater are retained in the thicker snowpack, which tends to reduce net runoff. Thus, accurate reconstruction of the timing, pattern and volume of accumulation is important for reliable estimation of runoff.

Another important consideration in modeling runoff is refreezing of meltwater within the snowpack. A variety of approaches exist from the simplest, using a fixed fraction of the annual accumulation (Reeh, 1991) to full snow metamorphism models (Bougamont et al., 2005; Mernild et al., 2006; Fettweis, 2007). The latter contain explicit terms for the metamorphism of the snowpack as meltwater percolates into it but can, in general, be driven only by an energy balance model because they require the energy balance of the snowpack to be calculated, which is not possible using a simpler PDD approach. A study of three relatively simple refreezing schemes for the Greenland Ice Sheet found that they accounted for about 20% of the total melt production, produced similar estimates, and had reasonably similar sensitivities to changing climate (Janssens and Huybrechts, 2000).

More recent analyses incorporating these simple approaches as well as snow metamorphism models reached a different conclusion, however, and found that the different models produced different volumes of refreezing and had different sensitivities (Bougamont et al., 2007; Wright et al., 2007). The MAR RCM, for instance, estimates that refreezing is about 50% of the total melt production (Table 8.2). These studies suggest that further work on understanding and modeling refreezing is required. They also indicate that modeling refreezing remains a significant uncertainty in present-day and future estimates of SMB. A major hurdle for improving refreezing estimates is both the difficulty in obtaining reliable *in situ* validation data (Bøggild, 2000) and the difficulty of incorporating preferential water flow deep into the snowpack with the models, which is known to take place (Bøggild, 2000). Instead of refreezing in the cold snow, water channels into vertical flow fingers followed by horizontal conduits and eventually results in runoff (Bøggild, 2000).

8.2.2.4. Differences and trends in measured and modeled SMB

The average SMB for the four reconstructions (RACMO2/GR, MAR, PMM5, Hanna; see Table 8.2) covering the past 50 years is 354 Gt/y with a range of 206 Gt between the lowest and highest estimates. This range is 58% of the mean value and provides some measure of the uncertainty in the SMB. This compares with a mean estimate of precipitation of 599 Gt/y. Thus, roughly half the precipitation is lost as runoff during this period, although estimates vary substantially (Table 8.2). It should be noted that runoff is not equal to the total volume of meltwater, M , because a proportion of this percolates into the underlying snowpack and refreezes. Considerable uncertainty exists in estimating this refreezing term, RF (see Section 8.2.2.4).

Table 8.2 summarizes some recent estimates of Greenland SMB, derived from a variety of methods. It is important to

note that the values presented in Table 8.2 are not entirely independent. The models labeled Mote and PMM5 derived accumulation rates from almost identical downscaling approaches. Hanna, MAR, RACMO2/GR and PMM5 all use the same source: ECMWF climate re-analysis (known as ERA-40) and operational analysis data as the input for their downscaling approach. Thus, biases in ERA-40 may affect all of these estimates in similar ways.

Estimates of SMB from downscaling of ERA-40 data agree reasonably well when averaged over several years but there are substantial differences in spatial patterns, individual components of SMB, and interannual variability. Figure 8.9 compares the components of SMB from several different approaches: A simple downscaling of ERA-40 derived by Hanna et al. (2005) and the RCMs, MAR (Fettweis, 2007), RACMO2/GR (Ettema et al., 2009) and PMM5 (Box et al., 2006). It is not surprising that the trends are in agreement and that there is reasonable correlation between minima and maxima as this is largely constrained by the common forcing used in the simulations (i.e., ERA-40). There are, however, substantial departures in absolute values. For 2003, for example, the Fettweis (2007) SMB anomaly is about 180 Gt less than Hanna and PMM5, while RACMO2/GR is consistently even higher due to its higher estimate of accumulation (Figure 8.9d). These differences are about as large as the SMB for that year.

The difference between the estimates is thus larger than the loss of mass from the ice sheet over the past decade (Section 8.2.5).

In addition, the refreezing component, RF, is highly uncertain. The range for RF between the four time series that use ERA-40 data as input is from 39 to 238 Gt/y: a difference that is 58% of the mean SMB. Refreezing is, therefore, an important, yet poorly known, component of SMB, which has received relatively little attention compared with other terms, partly due to the difficulty in making direct measurements of its magnitude. Although the fundamental physical processes that influence SMB are, in the main, relatively well understood, Table 8.2 and Figure 8.9 clearly show that much uncertainty still remains in constraining it.

Figure 8.13 summarizes the main trend in SMB over the past 50 years. Hanna et al. (2008) estimated a statistically significant




Figure 8.13. Mean SMB of the three reconstructions (MAR, PMM5, Hanna) shown in Figure 8.9. The data have been smoothed over a running 5-year period to reduce interannual variation. Source: Jonathan Bamber, University of Bristol.

positive trend in precipitation from 1958 to 2006 of 84 Gt/y, equivalent to 1.7 Gt/y². Runoff, however, has increased at a greater rate, particularly since the early 1990s (Figure 8.9) resulting in a net reduction in SMB during this time (Figure 8.13) as expected in a warming climate. The modest increase in precipitation is supported by *in situ* measurements from an ice core in North East Greenland (Figure 8.14), which show an increase since about 1990 once interannual variability is reduced by smoothing. However, observational data from one site is not enough owing to climate variability and significant noise in the data (Fisher, 1985; Andersen et al., 2006b). There are, however, few studies extending to the most recent years and the data illustrate the need for many and long records before changes in accumulation can be statistically verified. The interannual variability in precipitation from the RCMs is around 20% and, as can be seen in Figure 8.9, means that short-term signals over, for example, the past decade are strongly influenced by this variability.

The SMB has a 50-year mean average value of 354 Gt/y. During the 1960s and early 1970s, SMB was 10–20% below the 50-year mean. Since the mid-1990s, however, SMB has decreased steadily to its lowest value over the entire reconstructed period, such that the most recent years are more than 100 Gt below the 50-year mean and 200 Gt below the value in the mid-1990s. This is the most striking trend in the time series and has been linked to a global, rather than regional, warming trend that exceeds the background natural variability (Hanna et al., 2008). This is an important conclusion, which suggests that the trend is likely to continue into the future. Also, crucially, the increased melt during this period has warmed the surviving snowpack at lower elevations by some 5 to 10 °C, priming it for even greater losses in the near future (van den Broeke et al., 2009).

8.2.2.5. Summary and recommendations

The mean SMB, based on the four ~50-year records, is 354 Gt/y with a range between estimates that is 54% of the mean, providing

a qualitative indication of the uncertainty in the SMB. This is of the order of magnitude of the standard deviation of the interannual variability, which ranges from 62 Gt/y for PMM5 to 124 Gt/y for MAR. Since the mid-1990s, runoff has increased significantly with only a modest change in accumulation, resulting in a reduction in the SMB of around ~200 Gt over the past 13 years (Figure 8.13). This trend in SMB appears to be a response to global climate change and above the level expected due to natural variability (Hanna et al., 2008). It should be noted, however, that the gradient of the trend is dependent on the epoch, due to the large interannual variability discussed above. Also of note, is that 2007 had the lowest SMB of any year in the 50-year time series. Significant differences exist between the various estimates of the components of the SMB derived from numerical modeling and downscaling of climate re-analysis data. These differences can be as large as the actual SMB estimate for a given year and the standard deviation of the differences is of the order of 92 Gt. This is of the same order of magnitude as the inferred increase in mass loss due to changes in ice dynamics over the past decade (Rignot and Kanagaratnam, 2006). The differences suggest that mass budget calculations (where the solid ice flux is subtracted from the SMB to estimate the overall net mass balance of the ice sheet) may have been seriously hindered by uncertainties in the SMB in the past. The most recent mass budget calculation, however, showed good agreement with results from independent satellite observations, giving confidence that progress is being made in constraining the components of mass loss from the ice sheet (van den Broeke et al., 2009). Nonetheless, resolving and explaining the cause of the large differences between reconstructions remains an important goal in improving the ability to model past, and predict future, changes in SMB.

To achieve this goal will require a concerted effort to collect more targeted *in situ* SMB data, especially from the percolation and ablation zone, with which to calibrate and validate the models. Improvements in process understanding and modeling of key processes such as refreezing, blowing snow and subgrid-scale effects will also be valuable.




Figure 8.14. Results from a shallow ice core drilled at NEEM (77.5° N, 51° W) in 2007. The black curves represent annual values of accumulation (a) and stable water isotopes δ¹⁸O (b) while the red curves represent 20-year sliding mean values for the period 1750 to 2003. The accumulation rates are determined from detailed δ¹⁸O identification of annual layers based on 2.5 cm samples and a measured density record. Source: courtesy of the NEEM project.

8.2.3. Ice discharge

- Accelerating ice discharge from outlet glaciers since 1995–2002 is widespread and has gradually moved further northward along the west coast of Greenland with global warming.
- The ice discharge has increased from the pre-1990 value of 300 Gt/y to 400 Gt/y in 2005.
- The acceleration of fast-flowing marine terminating glaciers coincides with terminus retreat.
- The increase of glacier velocities is believed to be related to warming ocean water and the basal melt under the floating tongues can be several metres per day.

The Greenland Ice Sheet loses mass by melting as well as by discharge of ice into the ocean. The discharge comprises calving of icebergs as well as submarine melting. This section addresses the mechanisms of fast ice flow leading to transport of ice from the inland to the margin and the mechanisms of iceberg calving and submarine melting.

The margin of the Greenland Ice Sheet is characterized by spatially variable flow; areas of slow flow are separated by fast-flowing outlet glaciers and ice streams (Figure 8.15; Weidick, 1995; Rignot and Kanagaratnam, 2006). Parts of the ice are in direct contact with the surrounding ocean. In southern Greenland, ice-ocean contact is restricted to fast-flowing outlet glaciers that are topographically constrained by fjords, which often extend subglacially into the present-day ice sheet. The slower flowing ice usually terminates on dry land inland from the coast. However, in southwestern Greenland ice marginal lakes are quite common, and ice can be lost there by freshwater calving (Warren, 1991). The role of calving into ice marginal lakes has not been investigated extensively. It is likely to become increasingly important as the Greenland Ice Sheet retreats into the bedrock depression created by its own weight. In the north, along a significant section of the ice margin, both slowly and rapidly flowing ice is in direct contact with the ocean.

Around the Greenland Ice Sheet, the highest rates of ice discharge and the highest variability of discharge are observed at ocean-terminating outlet glaciers (Figure 8.15). The major mass loss mechanism for these glaciers is calving into the ocean (Reeh, 1968, 1994) and melting from ocean water (Rignot, 1996; Rignot et al., 1997). Rignot and Steffen (2008) showed that the floating ice shelf in front of Petermann Glacier, in northwestern Greenland, experiences massive bottom melting that removes 80% of its ice before calving into the Arctic Ocean. Commonly, estimates of ice discharge into the ocean implicitly include mechanical calving as well as melting by the ocean, since the ice contributes to sea level as soon as it crosses the grounding line and begins to float. Many of the outlet glaciers with high discharge rates flow through deep and narrow fjords. The largest and best studied of these is Jakobshavn Isbræ on the west coast of Greenland, for which the mechanisms of fast flow have been examined in detail (Iken et al., 1993; Funk et al., 1994; Lüthi et al., 2002, 2003). The findings are summarized here to illustrate the mechanism of fast outlet glacier flow.

Jakobshavn Isbræ is characterized by a deep subglacial trough that extends to 1500 m below sea level about 50 km inland from the current ice front (Clarke and Echelmeyer, 1996). This fjord (i.e., the trough) is relatively narrow (~5 km) but channels the ice from a drainage area that comprises




Figure 8.15. Velocity mosaic of the Greenland Ice Sheet derived from radar satellite data. The mosaic shows how the slow-flowing inland ice transitions into the fast-moving outlet glaciers, and the large variability of flow along the margin. White ice sheet areas are lacking radar satellite data. Source: Ian Joughin, University of Washington and Mark Fahnestock, University of New Hampshire, unpubl. (2008).

about 6.5% of the Greenland Ice Sheet (Bindshadler, 1984; Echelmeyer et al., 1991). Ice flow in such a channel is inherently complicated. The various commonly-used ice flow models that are simplified by approximations based on shallow ice (i.e., where ice thickness is much less than horizontal extent) are not adequate to fully describe the flow in this type of channel. Such models include the Shallow Ice Approximation (SIA, Hutter, 1983), and the Shallow Shelf Approximation (SSA, MacAyeal and Thomas, 1982), which can also be applied to shallow ice streams with low basal drag (MacAyeal, 1989). Instead, a fully 3-D thermo-mechanical treatment of ice flow, without approximation of the stress terms in the momentum balance, is necessary (Hutter, 1983) to describe outlet glaciers whose depths are comparable to their widths. No such model has yet been applied to either the Greenland or Antarctic ice sheets or even to an entire drainage basin of one of these ice sheets. (The hierarchy of ice flow models is discussed in Section 8.3.2.)

The relatively steep and very thick ice of Jakobshavn Isbræ creates high driving stresses that are balanced by high basal drag, particularly at the flanks of the subglacial trough (Lüthi et al., 2003; Truffer and Echelmeyer, 2003). The high driving stress influences the stress field far into the surrounding ice sheet. Using a numerical model, Lüthi et al. (2003) found differences to sheet flow at lateral distances from the ice stream of seven times the ice sheet thickness. The high stresses lead to high deformation rates, because they are combined with soft ice at depth, due to a temperate layer and lower viscosity Wisconsinian ice (Funk et al., 1994; Lüthi et al., 2002; Truffer and Echelmeyer, 2003).

The presence of this temperate ice adds an additional modeling challenge, because it introduces a free boundary: the cold-temperate surface (Hutter, 1982) and it requires the treatment of waterflow in the temperate layer (Aschwanden and Blatter, 2009). Also, the existence of a temperate basal layer implies water at the bed and a certain amount of basal motion. This is a boundary layer process that needs to be parameterized through a ‘sliding law’. The most commonly used sliding laws (see also Section 8.3.2) relate the basal motion to the basal shear stress and the subglacial water pressure; the latter is generally unknown but thought to be relatively high, that is, comparable to the ice overburden pressure.

This type of sliding law has well-known limitations, which are due to spatially and temporally variable parameters and to the limited knowledge of spatial and temporal variability of basal water pressure, which is an important variable (e.g., Iken and Truffer, 1997). The present inability to predict the nature and the amount of basal motion under large changes

in geometry, water supply, and stresses is a major limitation to credibly predictive models of outlet glaciers.

Reeh (1994) used mass balance considerations to estimate a total ice discharge into the ocean of 316 Gt/y. This is higher than a subsequent estimate of 170 to 270 Gt/y, which is based on calving rate estimates from parameters such as ice thickness at the front and water depth (Biggs, 1999). Both estimates applied for some time before the 1990s. Reeh's (1994) estimate is very close to one by Rignot and Kanagaratnam (2006) for 1995, which was derived from measurements of ice surface velocity and thickness at flux gates, as well as an estimate of surface ablation downstream from these gates. Rignot and Kanagaratnam (2006) also estimated discharge for 2000 and 2005, which showed a progressive increase in discharge within just a few years (Figure 8.16). The various estimates are summarized in Table 8.3. It is clear that ice calving into the ocean is a significant ice loss mechanism for the Greenland Ice Sheet, and that it can be highly variable (Bamber et al., 2007).




Figure 8.16. Flow acceleration (in m/y) at a selection of outlet glaciers. Cross profiles of velocity (a-d and i-l) were used for ice discharge calculations. e-h show along-flow velocity profiles. Note that acceleration is accompanied by glacier retreat. Source: Rignot and Kanagaratnam (2006).

Table 8.3. Calving flux estimates for the Greenland Ice Sheet.

Calving flux estimates, Gt/y	pre-1990	1995	2000	2005
Reeh (1994) ^a	316			
Biggs (1999) ^b	170–270			
Rignot and Kanagaratnam (2006) ^c		321	354	421

^aEstimate is based on mass balance considerations; ^bestimate based on empirical calving rate relationships derived in Greenland and elsewhere; ^cestimate derived from measurements of surface velocity and ice thickness at flux gates and a correction for surface ablation downstream of these gates. The measurements have been converted to Gt/y assuming a density of 900 kg/m³.

Ice calving is a major factor accounting for the recent negative mass balance of the Greenland Ice Sheet.

The variability of ice discharge is confirmed by observations of individual outlet glaciers, which have shown dramatic changes in recent years. In the period 2002 to 2007, Jakobshavn Isbræ went through a period of thinning, retreat by loss of its floating tongue, and acceleration to twice its former speed (Thomas et al., 2003; Joughin et al., 2004, 2008c; Podlech and Weidick, 2004; Luckman and Murray, 2005). There is no evidence of similar increases in discharge in the 20th century at Jakobshavn Isbræ (Weidick and Bennike, 2007), but old moraines and glacier trim lines do indicate that the glacier has lost its floating tongue at least once since the Little Ice Age (15th to 19th centuries), while it was retreating to a position that remained stable for the next 50 years (Csatho et al., 2008). Large changes have also been observed at two big glaciers on Greenland's east coast: Kangerdlugssuaq Glacier and Helheim Glacier (Howat et al., 2005, 2007; Luckman et al., 2006; Stearns and Hamilton, 2007).

Rignot and Kanagaratnam (2006) showed that the acceleration of ice discharge is widespread. Between 1995 and 2000 many of the outlet glaciers south of 66° N accelerated, often doubling their discharge. This pattern spread to 70° N by 2005, and appears to have been related to regional warming. The detailed pattern is complicated, however. For example, Howat et al. (2007) reported that the Helheim and Kangerdlugssuaq glaciers decreased their discharge again to near former levels in 2006. This was partially due to a slow-down connected with a re-advance of the terminus, and partly due to thinning, so that at similar ice velocity less volume can be discharged. Other glaciers, such as Jakobshavn Isbræ, have maintained their high rates of ice discharge (Dietrich et al., 2007; Amundson et al., 2008; Joughin et al., 2008c).

The out-of-balance flux of ice into the ocean from many of the outlet glaciers in southern Greenland has led to large thinning of near-margin ice (Pritchard et al., 2009, Figure 8.17). This thinning is affecting large parts of the drainage basins (Stearns and Hamilton, 2007; Joughin et al., 2008c). For Jakobshavn Isbræ, the thinning is closely related to increased ice flow that can be accounted for by an inland-propagating change in ice surface slope (Joughin et al., 2008c).

Coincident with ice-flow acceleration is a widespread retreat of outlet glacier terminus positions (e.g., Figure 8.18). Moon and Joughin (2008) recorded terminus positions of 203 outlet glaciers and concluded that retreat accelerated during 2000 to 2006 compared to 1992 to 2000. Again, the detailed picture is




Figure 8.17. Thinning rates across the Greenland Ice Sheet from ICESat repeat laser measurements. Elevation changes over time intervals larger than 365 days in the period 2003 to 2007. The thinning is concentrated at the margin of the ice sheet. (Part of Figure 2, Pritchard et al., 2009).

more complicated and Moon and Joughin suggested that there is a close relationship between air temperature and ice front advance / retreat, without suggesting that there is a cause and effect relationship between the two.

The observed acceleration of outlet glaciers coincides with an increase in teleseismically discovered glacial earthquakes (Ekström et al., 2003, 2006). The earthquakes occur seasonally and are strongly related to the occurrence of large calving events (Joughin et al., 2008b). Ekström et al. (2003) and Tsai and Ekström (2007) attributed the seismicity to large slip events on outlet glaciers. Recent ice displacement measurements do not confirm this hypothesis (Amundson et al., 2008; Nettles et al., 2008), and the former authors favor a model in which the glacial earthquakes are generated by the scraping of large overturning icebergs. Only a few seismic studies have been carried out on the ice and they point to a rich variety of seismic sources, many of which are presently not well understood (Rial et al., 2009).

Various hypotheses have been proposed for the causes of the speed-up of outlet glaciers. Thomas (2004) and Johnson




Figure 8.18. Changes in terminus position at Jakobshavn Isbræ (see Figure 8.35). Photo: Henning Thing.

et al. (2004) presented a model of Jakobshavn Isbræ in which the floating tongue provides resistance (i.e., backstress) to ice flow. The loss of the floating tongue then leads to ice flow acceleration. This model is also invoked by Joughin et al. (2008c) who observed a striking correlation between the speed of Jakobshavn Isbræ and the seasonally varying position of the calving front. Howat et al. (2005) used a force balance method to show how the loss of grounded ice near the terminus of Helheim Glacier leads to flow acceleration. The recently observed increases in ice discharge were always coincident with the loss of a floating tongue. But once the process is initiated, a pattern of fast flow, thinning and retreat can become established. This is a common observation at temperate tidewater glaciers, which only rarely develop floating tongues (Meier and Post, 1987). The idea of rapid tidewater glacier retreat is directly linked to that of a reverse bed slope, that is, the glacier bed deepens in the up-glacier direction. Nick et al. (2009) suggested that, in the case of Helheim Glacier, the phase of accelerated flow may be relatively short-lived, but it remains to be seen how universally applicable this model is.

While the exact form of a calving law remains unknown (e.g., Benn et al., 2007), it is clear from observations that a retreat into deeper water will lead to higher rates of calving, thinning, and further retreat. Vieli et al. (2001) and Schoof (2007) showed that no stable terminus position can exist on a reverse bedrock slope. This holds in advance as well as in retreat. The glacier acceleration that accompanies retreat can then be due to the effect of thinning, as suggested by Meier and Post (1987) and used by Pfeffer (2007).

Thinning influences glacier velocity in several ways. First, spatially-uniform thinning leads to a reduction in driving stress and thus in horizontal velocity. Second, thinner ice leads to a reduction in effective stress (ice overburden minus basal water pressure). This is because the basal water pressure has to exceed a level that is given by sea level for subglacial drainage to occur. As a tidewater glacier thins, basal water pressure cannot decrease due to this set downstream level, causing an overall drop in effective pressure. The reduction of effective pressure, as the lower part of the glacier approaches floatation, is expected to lead to higher rates of basal motion in any reasonable sliding law. Finally, enhanced thinning near the

terminus leads to increases in surface slope and hence driving stress and ice velocity.

Pfeffer (2007) derived a stability index for tidewater glaciers by considering the first and second of the three effects, which have opposite effects on ice flow. Pfeffer showed that an ice thickness above a certain threshold:

$$h_{th} = C \cdot \rho_w / \rho_i h_w$$

is stable against thinning in that thinning leads to a reduction in ice flow, whereas an ice thickness below that threshold reacts to thinning by ice acceleration. Here, h_w is the depth of the water and ρ_w and ρ_i are the densities of ocean water and glacier ice, respectively. C is a constant that depends on the choice of the ice flow law and the sliding law. Pfeffer (2007) suggested that $C = 4/3$, given flow parameters in the literature.

The analyses by Vieli et al. (2001), Pfeffer (2007) and Schoof (2007) all apply to flowline models and do not consider the embedding of an outlet glacier in its surrounding ice sheet. This could be an important factor contributing to the stability of outlet glaciers. As an outlet glacier retreats and thins, the surface slope increases in a lateral direction (i.e., toward the ice sheet), and more convergent flow should be expected, which could stabilize the glacier and delay further thinning and retreat (Howat et al., 2007).

Measurements from outside the fast-flowing ice in West Greenland have also indicated a seasonality in ice flow (Lüthi et al., 2002; Zwally et al., 2002b; Joughin et al., 2008b; van de Wal et al., 2008). This seasonality is related to the seasonality of surface melt and was attributed to meltwater reaching the base of the ice (Zwally et al., 2002b). Das et al. (2008) observed the draining of a supraglacial lake to the bed and a corresponding local speed-up of the ice sheet. They concluded that the integrated effect of multiple lake drainages could explain some of the observed acceleration of the ice sheet. However, for several reasons, it is unlikely that increased melt directly leads to the observed speed-up of outlet glaciers.

First, the ice-stream acceleration was first observed near the termini of these glaciers and then propagated inland (Joughin et al., 2004; Howat et al., 2007). Second, at least in the case of the main channel of Jakobshavn Isbræ, there is no observed distinct seasonal reaction to the large variability of meltwater supply. Rather, the seasonality of ice flow is closely related to the position of the glacier terminus, which varies seasonally, but with a distinctly different phase than the meltwater production (Joughin et al., 2008c). Third, van de Wal et al. (2008) did find a large seasonal velocity signal that correlates well with meltwater production, but does not translate into a correlation between annual velocities and melt. In fact, the mean annual velocity of the ice sheet has a negative correlation with melt. This has also been reported for mountain glaciers (e.g., Truffer et al., 2005) and is presumably due to the theoretically expected increase in effectiveness of water drainage as discharge increases.

Reeh et al. (2001) and Joughin et al. (2008c) observed a correlation between sea-ice cover and the stability of glacier fronts. While it is perhaps difficult to imagine a sea-ice cover that provides substantial resistance to glacier flow, it is possible that icebergs held together by sea ice inhibit calving, which then leads to glacier advance because ice is not lost at the terminus (Joughin et al., 2008c). This can then have an influence on ice velocities by the increased resistance due to lateral shear, and

perhaps by decreased effective pressures near the grounding line due to ice thickening. In practice, it is often difficult to tell whether the influence of sea ice is direct, or whether the sea ice reacts to the same forcing as the outlet glaciers, for example, warmer ocean water.

That all large observed changes in ice-stream flow initially occurred near the ocean and then propagated inland, points to the importance of understanding ice-ocean interactions. Holland et al. (2008) reported that the acceleration of Jakobshavn Isbræ is temporally coincident with a pulse of deep warm ocean water that was observed along the west coast of Greenland. Typical fjord circulation patterns that bring in warm saline water at depth and return colder and fresher water at the surface could bring this pulse to the glacier front and contribute to the very high melting rates that were reported on Jakobshavn Isbræ before the disintegration of its floating tongue (Thomas et al., 2003). Straneo et al. (2010) and Rignot et al. (2010) also pointed to the importance of warm water incursions for regulating glacial flow. Howat et al. (2008) noted a correlation between sea surface temperature and outlet glacier acceleration and retreat in southeastern Greenland. Murray et al. (2010) observed simultaneous acceleration and deceleration of many southeastern glaciers and proposed that increased ice and freshwater discharge led to a strengthening of a fresh coastal current that kept warm ocean water from entering glacial fjords, thus providing a negative and self-regulating feedback between ice discharge and melting by ocean water. Ocean conditions can also favor the formation of a strong melange (mix of sea ice and icebergs) that can inhibit calving and lead to a strong seasonality in terminus position (Amundson et al., 2010). The length of the winter season determines the amount of time a grounded terminus is exposed to calving. This provides a link between seasonality and longer term glacier behavior.

In a different setting, Motyka et al. (2003) showed that melting of submerged ice at a tidewater glacier front could account for about half of the total ice flux into the ocean. The important factors for melting were the temperature of the deep fjord water and the strength of the fjord circulation. Motyka et al. (2003) hypothesized that the buoyant freshwater emerging at the glacier's base plays an important role in the fjord water circulation. This provides an interesting physical link between atmospheric temperatures, surface melt, and fjord circulation.

The fast flow of Jakobshavn Isbræ and other outlet glaciers can be explained as a consequence of subglacial topography. This is not, however, necessarily the case for all outlet glaciers. One that stands out in particular is the northeastern Greenland ice stream (Fahnestock et al., 1993; Figure 8.15), which extends far into the ice sheet (Joughin et al., 2000). The fast flow of this ice stream might be controlled by geothermal heat. Fahnestock et al. (2001) used the spacing of deep radar layers to derive the geothermal heat flux under this ice stream and discovered unusually high melt rates.

Some of Greenland's glaciers also show surge-type behavior: long periods of quiescent flow interrupted by short periods of very rapid flow (Meier and Post, 1969). Glacier surges are a non-equilibrium phenomenon that is believed to be due to a positive feedback between basal water storage and basal motion (Kamb et al., 1985; Harrison and Post, 2003) that can

last several months. Slower surges at polythermal glaciers might also be thermally controlled (Clarke et al., 1984). In Greenland, surging has been reported for the northeastern ice stream Storstrømmen (Reeh et al., 1994) and several glaciers in central East Greenland (Murray et al., 2002; Jiskoot et al., 2003). A short surge-like flow acceleration was also seen at Ryder Glacier (Joughin et al., 1996). It is important to remember the temporary nature of such changes in ice discharge. The mechanisms (and perhaps duration) are quite different from outlet glacier changes.

8.2.4. Total mass balance

- The Greenland Ice Sheet is losing mass at an accelerating rate.
- The present (2005/06) loss of mass is 205 Gt/y corresponding to a 0.5 mm/y global average rise in sea level.
- Satellite and airborne observation in general reveal a slight increase in elevation in the regions above 2000 m and a strong decrease in elevation in the regions below 2000 m with very dominating regional patterns.

8.2.4.1. Total net balance of the Greenland Ice Sheet

The total mass balance of an ice sheet is the sum of the surface mass balance and ice discharge. It is the net result of the mass changes due to the addition and loss processes discussed in the previous sections. Owing to the seasonal nature of these processes, the mass of an ice sheet varies throughout the year, between years, and over many years as longer-term trends in climate become established. There are strong spatial gradients in mass balance that must be taken into account to determine variations in the total mass of the ice sheet.

For the Greenland Ice Sheet, which is subject to substantial surface melt and the resulting runoff of meltwater, mass exchange through the year has a large seasonal component at lower elevations caused by winter accumulation giving way to summer surface melt. These changes around the ice sheet margins are accompanied in outlet glaciers by changes in ice flow and iceberg production that may be linked in part to summer warming. At high latitudes and high elevations in the interior of the Greenland Ice Sheet, the relatively low input of snow and relatively small loss of snow to sublimation and wind transport lead to smaller amplitude annual variations in mass.

The time it takes for significant changes in accumulation or rates of ice loss around the margins of the Greenland Ice Sheet to impact on the ice flow in the bulk of the ice sheet interior determines the response of the ice sheet to forcings on ice-age time scales. Changes in the flow of the Greenland Ice Sheet over millennia are driven by slowly changing temperature profiles and ice characteristics. The rate of these changes is controlled by thermal diffusion, slow flow of ice downward and outward as new snow is added to the ice sheet surface, and the slow evolution of the shape of the ice sheet as changing accumulation and melt patterns add and remove mass.

Prior to recent measurements of changes in the rates of outlet glacier flow and melt in Greenland, the ice sheet appeared to be roughly in balance. The mass turnover in the Greenland Ice Sheet was estimated at 500 Gt/y by Benson (1962) with about half the mass added through snowfall each year lost by

surface melt and subsequent runoff, and the other half returned to the ocean through outlet glacier discharge leading to iceberg calving. But, as discussed in Sections 8.2.2 and 8.2.3, recent observations show quite large and rapid changes in surface melting and ice discharge. At the same time, different analyses of the total mass balance show the Greenland Ice Sheet overall to have lost mass since the early 1990s.

8.2.4.2. Techniques employed to observe or estimate total mass balance

Current techniques for estimating or measuring total mass balance include: (i) the mass budget approach, comparing total net snow accumulation with losses by ice discharge and meltwater runoff; (ii) repeated altimetry, to estimate volume changes; and (iii) tracking temporal changes in gravity, to infer mass changes.

The first two provide estimates of mass balance for regions included within survey boundaries, whereas the third provides an estimate for large regions with less distinct boundaries. All three techniques can be applied to the Greenland Ice Sheet as a whole, within limitations specific to each technique.

8.2.4.2.1. Mass budget approach

Changes in the Greenland Ice Sheet mass can be inferred from the difference between estimates of accumulation (i.e., snowfall) and mass loss through ablation (i.e., melt and subsequent runoff and sublimation) or ice discharge and calving. Each of these quantities involves a number of variables. Generally, snow accumulation is estimated from annual layering in ice cores, sometimes with interpolation between core sites using satellite microwave measurements or shallow radar sounding (e.g., Rotschky et al., 2004), or from atmospheric modeling (e.g., Box et al., 2004). Ice discharge is the product of ice flow velocity and ice thickness, with velocities measured *in situ* or remotely, preferably near the grounding line where velocity is almost depth independent. Ice thickness is measured by airborne radar, seismically, or from measured surface elevations assuming hydrostatic equilibrium for floating ice near grounding lines. Generally, meltwater runoff (large near the Greenland coast but small or zero elsewhere) is from model estimates calibrated against surface observations where available (e.g., Box et al., 2004; Hanna et al., 2005). Rignot and Kanagaratnam (2006) applied the mass balance approach around Greenland.

Mass budget calculations involve the often small difference of two large numbers, and small errors in either mass loss or gain terms can result in large errors in estimated total mass balance. These errors are difficult to assess for the Greenland Ice Sheet because of high temporal and spatial variability (see Section 8.2.2). Although broad interferometric SAR (InSAR) coverage and progressively improving estimates of grounding line ice thickness have substantially improved ice discharge estimates, incomplete data coverage and uncertainty regarding velocity–depth relationships and meltwater runoff limit accuracy of total discharge estimates. The mass budget uncertainty for the Greenland Ice Sheet is a result of all these factors.

Moreover, accumulation estimates are based on data from the past few decades, and there are indications that snowfall in Greenland may be increasing with time (e.g., Hanna et al., 2005). Similarly, it is becoming clear that glacier velocities can

change substantially over quite short time periods (see Section 8.2.3). Both of these would add to estimated mass budget errors.

Thomas et al. (2000) gave a regional estimate for the mass budget for central Greenland above 2000 m elevation, using discharge velocities from repeat GPS measurements made at stake markers 30 to 40 km apart along a traverse at 2000 to 3000 m elevations, ice thickness from radar sounding, and snow accumulation rates from shallow ice cores. Results show that between the mid-1970s and mid-1990s, central Greenland was in overall mass balance, but with regions of thickening, particularly in the southwest, and of thinning, particularly in the southeast.

A more complete picture, including near-coastal regions and individual drainage basins, comes from balancing net SMB (Section 8.2.2) against ice discharge rates derived from SAR-derived ice velocities and ice thicknesses from radar or surface elevations near grounding lines, where the ice is floating (Rignot and Kanagaratnam, 2006). SMB for this work was derived from SMB anomalies calculated from Hanna et al. (2005) scaled and applied to modulate a surface accumulation pattern from shallow ice cores combined with ECMWF (re) analyses (Section 8.2.2).

Results show significant mass loss since the mid-1990s from most drainage basins, with very large losses after 2000 from Jakobshavn Isbræ, Kangerdlugssuaq Glacier and Helheim Glacier and from nearly all glaciers along the east coast south of Helheim (Joughin et al., 2004; Rignot and Kanagaratnam, 2006; Luckman et al., 2006; Howat et al., 2007, 2008). Velocity time series for these glaciers show up to a 100% increase after 2000, consistent with their negative mass balance.

8.2.4.2.2. Repeat altimetry

Rates of surface elevation change ($\delta S/\delta t$) reveal changes in ice sheet mass after correction for changes in depth / density profiles and bedrock elevation, or for hydrostatic equilibrium if the ice is floating. Satellite radar altimetry (SRALT) data have been widely used (e.g., Davis et al., 2000; Johannessen et al., 2005; Zwally et al., 2005), together with laser altimetry from airplanes (Krabill et al., 2000), and from NASA's ICESat (Zwally et al., 2002a; Thomas et al., 2006). Modeled corrections for isostatic changes in bedrock elevation (e.g., Peltier, 2004) are small (i.e., a few mm/y) but with errors comparable to the correction. Those for near-surface snow density changes (Arthern and Ingham, 1998; Li and Zwally, 2004; Helsen et al., 2008) are larger (i.e., a few cm/y) and also uncertain.

SRALT data provide the longest time series, with the first measurements in 1978. Resulting estimates of $\delta S/\delta t$ can be misleading, however, because derived elevations refer to the radar reflection horizon. The depth of this horizon below the actual ice sheet surface is affected by near-surface characteristics, such as snow wetness. Consequently, changes in these characteristics can affect SRALT-derived estimates of $\delta S/\delta t$ (Thomas et al., 2008), particularly in Greenland where the area affected by summer melting has increased substantially since the early 1990s. In addition, because of the broad radar beam, SRALT data are unreliable over the sloping and undulating surfaces near the coast, where rates of elevation change are greatest (e.g., Brenner et al., 2007).

Airborne Topographic Mapper (ATM) and satellite (ICESat) laser altimeters provide data that are easier to validate and

interpret because footprints are small (i.e., about 1 m for airborne laser, and 60 m for ICESat) and there is negligible laser penetration into the ice. However, clouds limit data acquisition, and accuracy is affected by atmospheric conditions and particularly by laser pointing errors. Moreover, existing laser data are comparatively sparse, being limited by practical limitations on the number of ATM surveys and the ICESat orbit separation of up to 40 km in southern Greenland.

ATM elevation estimates are accurate to ~10 cm along survey tracks (Krabill et al., 2002) with similar errors estimated for ICESat surveys, but increasing over steeper slopes (Brenner et al., 2007). Because there are large gaps both in ICESat and airborne coverage, $\delta S/\delta t$ values are generally supplemented by degree-day estimates of anomalous melting (Krabill et al., 2000, 2004). This increases overall errors and probably underestimates total losses, because it does not take into full account the dynamic thinning of outlet glaciers.

In summary, $\delta S/\delta t$ errors cannot be quantified precisely for SRALT data, because of the broad radar beam and time-variable penetration. For laser data the difficulty in quantification comes because of sparse coverage. If the SRALT limitations are real, they are difficult, if not impossible, to resolve. Laser limitations result primarily from poor coverage, and can be resolved by increasing coverage to include all regions of rapid change around the Greenland coast. All altimetry mass balance estimates include additional uncertainties due to changes in the density profile of near-surface snow and (small) rates of basal uplift. If elevation changes are caused by recent changes in snowfall, the appropriate density (ρ) may be as low as 300 kg/m³; for long-term changes, it may be as high as 900 kg/m³. This is of most concern for small rates of surface elevation change, where the safest assumption is that density $\rho = 600 \pm 300$ kg/m³, implying a $\pm 50\%$ mass balance uncertainty. Slobbe et al. (2009) used this conservatively large range for the entire ice sheet for an ICESat-only analysis, finding results consistent with other laser analyses.

Large and rapid changes, commonly found near the coast, are almost certainly caused by changes in melt rates or glacier dynamics, and the appropriate density of the lost or added volume approaches that of pure ice ($\rho \sim 900$ kg/m³). Moreover, densification rates are sensitive to snow accumulation rates, temperature, and wetness, with warm conditions favoring more rapid densification (Arthern and Wingham, 1998; Li and Zwally, 2004; Helsen et al., 2008). Thus, the recent Greenland warming probably caused ice sheet surface lowering simply from this effect alone. Finally, the rate of basal uplift is inferred from models and has uncertain errors.

An early estimate of surface elevation change in southern Greenland using SRALT showed either little change or that much of the variability could be attributed to decadal changes in accumulation rates as measured in ice cores (Davis et al., 2000; McConnell et al., 2000). Other estimates of the Greenland Ice Sheet volume change from SRALT altimetry (Johannessen et al., 2005; Zwally et al., 2005) show thickening at higher elevations, particularly in the south, comparatively modest thinning nearer the coast, and a small positive mass balance overall.

However, as previously discussed, time-variable radar penetration and ‘blurring’ of near-coastal results by the wide radar beam make these results suspect (Thomas et al., 2008). Estimates derived by comparing ATM surveys 1993/1994 and

1998/1999 (Krabill et al., 2000) show substantial thinning near the coast and an overall mass loss of about 55 Gt/y between surveys. Comparison of elevations from these surveys with later values from ICESat at locations where flight tracks crossed ICESat orbits show that mass losses have increased to about 80 Gt/y between 1998/1999 and 2004 (Thomas et al., 2006). These laser-based estimates probably represent lower bounds because the sparse coverage ‘misses’ outlet glaciers that are thinning dynamically. Annual thinning rates of tens of metres on outlet glaciers in southeastern Greenland are shown clearly from repeat stereo satellite coverage (Howat et al., 2007, 2008; Stearns and Hamilton, 2007).

8.2.4.2.3. Temporal variations in Earth’s gravity field

Of all the techniques that are used to monitor the changing mass of the Greenland Ice Sheet, only gravity measurements are directly sensitive to changes in that mass; all other techniques convert changes in other quantities, such as melt, ice flux or surface elevation change, into changes in mass. Since 2002, the GRACE (Gravity Recovery and Climate Experiment) mission, joint between NASA and Deutsche Forschungsgemeinschaft für Luft und Raumfahrt (DLR), has measured Earth’s gravity field and its temporal variability. GRACE comprises two satellites, following each other in the same orbit 200 km apart, that carefully monitor the distance between themselves (Tapley et al., 2004a,b).

As the first satellite approaches a more massive object on the surface, it accelerates away from the trailing satellite, which then accelerates as it approaches the same object, closing the increased distance between the two orbiters. A detailed record of the changes in this inter-satellite distance over time provides a direct indication of changes in mass at the Earth’s surface. Other accelerations are monitored with on-board accelerometers. GRACE has produced time series of these small changes in gravitational acceleration that start in 2002 and still continue (Tapley et al., 2004a,b). The spatial scale of the changes in gravity that GRACE can detect is determined by the height of the orbit, the spacing of the two satellites, and the accuracy with which the range rate between the two satellites can be determined.

After removing the effects of other loading, high latitude data, like those for Greenland, contain information on temporal changes in the mass distribution of the ice sheet and the underlying bedrock. Because of its high altitude, GRACE makes coarse-resolution measurements of the gravity field and its changes with time and the resulting mass balance estimates are also at coarse resolution – hundreds of kilometres. Despite this limitation, this technique has the advantage of covering the entire Greenland Ice Sheet, which is extremely difficult using other techniques. GRACE estimates include mass changes on the small ice caps and isolated glaciers that surround the Greenland Ice Sheet, regions not included in mass balance estimates from other techniques.

There are two different analysis schemes for GRACE data that have been applied to determining changes in the mass of the Greenland Ice Sheet. The first uses products derived by the GRACE mission that represent the global gravity field, expressed as a spherical harmonic expansion to a high order, differencing fields from each 30-day period to detect changes in

ice sheet mass over time (Velicogna and Wahr, 2005, 2006; Chen et al., 2006). This technique requires convolving the harmonic expansion of the global gravity field with a filter representing either part or all of the Greenland Ice Sheet to isolate the changes in gravity that are due to changing ice mass. The gravity fields produced by the GRACE team have been updated since the time of publication of these papers; results may change with this revised input data. Ramillien et al. (2006) used a similar technique, but began with a different input dataset, which is a version of the Earth's geoid (i.e., another representation of the gravity field) derived for 10-day periods by a group at Centre National d'Etudes Spatiales (CNES). Slobbe et al. (2009) used a common analysis scheme on gravity fields produced by four different centers, and reported a significant range of resulting net balance rates.

Corrections applied in these analyses include compensation for changes in global patterns of water storage on land, ocean mass, and atmospheric mass. In addition, a correction must be made for longer-term changes in crustal mass distribution due to glacial isostatic adjustment (GIA) (crustal uplift that is a continued response to past deglaciation, or post-glacial rebound). Each of these analyses uses different input data sets and modeling strategies to make the corrections. Chen et al. (2006) used an optimized filtering technique to fit mass change time series on a $1^\circ \times 1^\circ$ grid with high resolution aided by use of knowledge about where changes were occurring (i.e., in outlets near the ice margin identified by Rignot and Kanagaratnam, 2006). Ramillien et al. (2006) discussed the impacts of errors from each of these corrections. Barletta et al. (2008) conducted an extensive analysis of the impact of different factors on the GIA corrections to GRACE estimates in Greenland and Antarctica. They did make a somewhat simplified estimate of the rate of mass loss in Greenland from GRACE data to illustrate these impacts. This result is not included in Figure 8.19 or Table 8.4, but is similar to the others in the table.

Wu et al. (2010) have presented a different analysis also based on the glacial isostatic adjustment and the redistribution of ice and water masses. It is suggested that the GIA correction is large and negative (-0.72 ± 0.006 mm/y) resulting in a mass loss of 104 Gt annually during the period 2003 to 2008 from the Greenland Ice Sheet; this mass loss is smaller than those published by other authors.

The second type of GRACE analysis scheme uses the range rate measurements between the two satellites directly, modeling the local changes in mass required to produce the observed changes in these rates during different overpasses of Greenland (Luthcke et al., 2006). This work also makes corrections for GIA using published paleo ice sheet reconstructions, but not the smaller effects from atmospheric and oceanic mass variations.

Error sources can include measurement uncertainty, leakage of gravity change signal both from regions surrounding the Greenland Ice Sheet, and for some analyses, globally, and causes of gravity changes other than ice sheet changes. Of these, the most serious are the gravity changes associated with vertical bedrock motion (i.e., GIA). These are inferred from models of deglaciation history and its impact on vertical crustal motion, primarily post-glacial crustal uplift; the errors are also modeled and remain highly uncertain. Results from all gravity-based analyses show mass loss over their periods of observation, with rates ranging from -100 Gt/y to more than -200 Gt/y. The wide

spread in results requires further investigation, but several studies using different analysis techniques show continued and accelerated change over the GRACE time period.

8.2.4.3. Synthesis and state-of-the-art

The results for each of the techniques are shown in Figure 8.19, plotted as boxes that encompass the length of the measurement period along the time axis, and the published range of the mass change rate over that interval. Data used for Figure 8.19 are summarized in Table 8.4.

With the exception of measurements from SRALT, estimates of the Greenland Ice Sheet total mass balance discussed here are negative, and are becoming more negative with time, with the caveat that many of these records are relatively short. The trend and timing are largely consistent with increased ice discharge from outlet glaciers around the edge of the Greenland Ice Sheet. Where these measurements do not agree within published errors, the sources of the discrepancies may be attributable to shortcomings in spatial sampling, complex sets of corrections, and input data that continue to evolve as satellite missions mature; limitations in measurement techniques are better characterized, and surface conditions on the Greenland Ice Sheet respond to a changing climate.

The complexity of measuring or estimating total balance has led to the development and exploitation of a number of measurement strategies. With respect to the Greenland Ice Sheet, these strategies have been developed and are maturing into a system that will one day be capable of tracking well constrained and internally consistent mass changes on a sub-annual basis. The extension of present measurement time series, combined with follow-on instruments and new airborne and satellite campaigns (e.g., Cryosat II), will help solve problems associated with limited coverage, slope and surface change induced error, and disparities in analysis of common data sets.

This represents a rapid evolution in capability that is presently matched by the rapid evolution of the Greenland Ice Sheet mass itself. One lesson that may be taken from the present state of knowledge is that multiple approaches and observations of mass input and mass loss processes have been required to make the progress that has been made to date.

8.2.5. Summary and outlook

Compared with processes that take place at the base of the ice sheet, those that influence SMB are relatively well understood and considerably easier to observe. Despite this, published reconstructions of the individual components that make up SMB differ significantly. The differences can be as large as the inferred increase in mass loss due to changes in ice dynamics over the past decade. The uncertainties in SMB arise, largely, as a result of the paucity of relevant, spatially extensive *in situ* observations. To reduce uncertainties to a level useful for mass budget calculations and reliable SMB predictions will require a concerted effort to collect more targeted *in situ* data, especially from the percolation and ablation zone. Improvements in process understanding and modeling of key processes such as refreezing, blowing snow and sub-grid scale effects will also be needed. Although there are differences between reconstructions, they all indicate a negative trend over the past ~15 years. This is largely due to an increase in runoff since about 1995, resulting

Net balance, Gt/y




Figure 8.19. Results from the Recent Large Area Total Balance Measurements discussed in the text, placed into common units and displayed versus the time intervals of the observations. The heights of the boxes cover the published error bars or ranges in mass change rate over those intervals. Source: Mark Fahnestock, University of New Hampshire. See Table 8.4 for details.

in a marked reduction in SMB since then. Also of note is that 2007 had the lowest SMB of any year over the 50-year record for which reliable estimates exist.

Much of the ice loss from the Greenland Ice Sheet occurs by ice discharge into the surrounding ocean. This has been estimated at 50% of the mass loss on average over the past ~50 years, but recently large variability in the flow of many large outlet glaciers has been documented. The temporal variability of Greenland's ice mass balance has a large contribution from variability of flow in its outlet glaciers. Observations during the past decade have shown that ice discharge can increase by a factor of two within a few years and, in some cases at least, that this can also be reversed. These changes are coincident with observations of warming in the ocean and atmosphere, as well as the disappearance of near-coastal sea ice. While the general mechanisms of fast flow are reasonably well understood, the necessary tools for predicting future behavior have not been developed. This is primarily due to a lack of understanding of the ice-ocean coupling and the role of surface water in determining the rates of ice flow.

The total mass balance of the ice sheet (i.e., the sum of SMB and ice discharge) was exceptionally difficult to determine prior to the development of the present suite of observational and analysis techniques. While it is clear from the spread of published results that estimation remains a challenge for

these techniques, it is important to note that nearly all the approaches show very similar trends, indicating clearly that the Greenland Ice Sheet is losing significant mass, and has been doing so at an accelerating rate over the past ten years. This conclusion is supported by all approaches sensitive to the ice margins: (i) the change in ice discharge from outlet glaciers combined with increasingly negative SMB; (ii) surface lowering in outlet glaciers measured directly by laser altimeters; and (iii) the reduction in the mass of the ice sheet measured by the GRACE satellite gravity mission. This reduction of mass is consistent with what would be expected to happen in a warming Arctic and the diverse, independent suite of approaches used to document this change in total mass balance provides confidence in the result.

The challenge of more accurately determining the present and future rate of mass change of the Greenland Ice Sheet, by reducing the uncertainties inherent in the different approaches, will require improvements in measurements, more consistent and complete observational time series, better analysis schemes, and an improved understanding of the physical processes involved in recent rapid changes.

This chapter has attempted to show the state-of-the-art with respect to observations and understanding of present-day, and recent past, behavior of the Greenland Ice Sheet. It is clear that, although the state-of-the-art has greatly advanced over the past

Table 8.4. Rate of total mass change in the Greenland Ice Sheet.

Source	Technique	Time period	Rate of total mass change, GT/y	Range (or stated error), $\pm$ Gt/y	Notes
Radar Altimetry					Satellite radar altimetry is affected by surface slope near ice margins and changes in penetration
Zwally et al., 2005	SRALT (ERS 1-2) + limited ATM	1992 – 2002 (10.5 y)	11	± 3	
Johannessen et al., 2005	SRALT (ERS 1-2) low elevations sparsely sampled	1992 – 2003 (11 y)	30	± 3	Densities of 0.9, 0.5, 0.4, 0.3, 0.3 Gt/km ³ assumed to convert area-weighted height change in elevation intervals (<1.5, 1.5–2, 2–2.5, 2.5–3, >3 km) into mass
Laser Altimetry					
Krabill et al., 2004	ATM (airborne laser altimetry)	1993/4 – 1998/9	-55	± 3	
		1997 – 2003	-73	± 11	
Thomas et al., 2006	ATM	1993/4 – 1998/9	-4 to -50		High end of range likely due to limited coverage at low elevations
	ATM/ICESat	1998/9 – 2004	-57 to -105		High end of range likely due to limited coverage at low elevations
Slobbe et al., 2009	ICESat (GLAS)	2003/2 – 2007/4	-139 $\pm$ 68		Used large density range (± 300 kg/m ³) for error bounds
Mass Budget					
Rignot and Kanagaratnam, 2006	InSAR (ice motion) 1996 + balance anomaly estimate (Hanna et al., 2005)	1996	-83	± 28	
	InSAR (ice motion) 2000 balance anomaly estimate (Hanna et al., 2005)	2000	-127	± 28	
	InSAR (ice motion) 2005 + balance anomaly estimate (Hanna et al., 2005) (extrapolated)	2005	-205	± 38	
van den Broeke et al., 2009	Mass budget validated with data from GRACE.	2003–2008	-237	± 20	
Satellite Gravity (GRACE)					
Luthcke et al., 2006	GRACE MASCON – (change in gravitational acceleration on each orbital pass fit to forward model of mass history of local basins)	July 2003 – July 2005	-101	± 16	Gain of 54 GT/y above 2000 m and loss of 155 GT/y below 2000 m
Chen et al., 2006	GRACE – averaging filter applied to monthly spherical harmonic gravity field product	April 2002 – Nov 2005	-219	± 21	
Velicogna and Wahr, 2006	GRACE – averaging filter applied to monthly spherical harmonic gravity field product	April 2002 – April 2006	-227	± 33	
Velicogna, 2009	Monthly measurements of time-variable gravity from the GRACE.	April 2002 – February 2009	-230	± 33	
Ramillien et al., 2006	GRACE – averaging filter applied to 10-day gravity solutions	July 2002 – March 2005	-118	± 14	
Wouters et al., 2008	GRACE EOF decomposition of monthly spherical harmonics iteratively fit with forward model of mass change of basins (based initially on R&K and iterated)	February 2003 – January 2008	-179	± 25	

Source	Technique	Time period	Rate of total mass change, GT/y	Range (or stated error), $\pm$ Gt/y	Notes
		July 2003 – July 2005	-121	± 27	Same period as Luthcke et al. (2006) Similar elevation dependence seen
		January 2006 – January 2008	-204	± 25	
Slobbe et al., 2009	GRACE using products from CNES (Centre National d'Etudes Spatiales), CSR (Center for Space Research, University of Texas-Austin), DEOS (Delft Institute of Earth Observation and Space Systems, Delft University of Technology, Delft), and GFZ (GeoForschungsZentrum, Helmholtz-Zentrum Potsdam)	July 2002 – June 2007	-128 to -218		Range in net balance is range of results using gravity products from four different centers, rather than estimated error
Baur et al., 2009	Analysing time-variable GRACE gravity fields	August 2002 – July 2008	-177	± 12	Value is the average derived from monthly gravity field models provided by CSR, GFZ and JPL, with individual contributions of 242 ± 14 km ³ /y, 194 ± 24 km ³ /y and 96 ± 23 km ³ /y, respectively

decade or so, major gaps and challenges remain. During this period, unpredicted and striking variability in ice dynamics has been detected from satellite observations as well as a marked decrease in SMB coincident with a decreasing trend in total mass balance. Serious limitations in the ability to model and monitor these processes, however, are also apparent from the disparity between published results.

Progress will need to come from many sources, including:

- Improving acquisition of more comprehensive and complete time series suitable for ice velocity determination, including seasonal variability. This will be predominantly from satellite and airborne remote sensing.
- Acquisition of improved measurements of surface elevation change by satellite and aircraft.
- Better measurement of ice thickness in rapidly flowing glaciers for improved ice discharge estimation.
- Improvements in analysis strategies and measurement capabilities for all processes which determine SMB.
- More, and better, *in situ* measurements of refreezing and ablation.
- Better understanding of links between outlet glaciers, surface melt, and marine conditions.
- Perhaps, most importantly of all, the need to ensure that the time series of observations is secure into the future, and extended back in time with the aid of historic and paleo-proxy data.

8.3. Predictions and sensitivity

- The Greenland Ice Sheet is likely to lose mass at an accelerating rate in the 21st century in response to ongoing warming.
- Increases in snow accumulation in central Greenland may partially offset the increased melting and runoff from the ice sheet periphery, but are unlikely to compensate for the effects of higher temperatures, which increase the area of

the ablation zone as well as the duration and intensity of the summer melt season.

- Between 5 and 10 cm of global sea level rise can be expected by 2100 as a result of declining SMB. Adding estimates of increasing ice discharge means a total ice mass loss of 10 to 19 cm can be expected by 2100.
- Greenland Ice Sheet retreat is projected to accelerate beyond 2100 under most IPCC emissions scenarios, as the regional climate continues to warm and the dynamical feedbacks associated with surface lowering become more important over time scales of several centuries.
- A regional warming of 3 to 4.5 °C (equivalent to a global warming of 2 to 3 °C) would move the Greenland Ice Sheet into a state of negative SMB, which would cause large-scale ice sheet collapse if maintained for several centuries to millennia.

The Greenland Ice Sheet response to climate change is too complex to be predicted through simple theory or analytical equations. SMB depends on the interaction of weather systems with the ice sheet orographic influences and surface energy balance. Spatial and temporal patterns of ice sheet evolution therefore feed back onto the meteorological fields over the ice sheet. The regional- and synoptic-scale weather patterns that affect the ice sheet are also evolving as part of global-scale climate change and accompanying shifts in sea ice, ocean conditions, the hydrological cycle, and atmospheric dynamics. These systems are all interlinked and the interactions can be described only by numerical weather or climate models (Box 8.1).

Similarly, the evolution of the ice sheet depends on the climate fields that dictate SMB (see Section 8.2.2), on the oceanic influences that affect the rates of iceberg calving and basal melting at the ice-ocean interface, and on the dynamic ice sheet processes that govern the flux of ice to the ice sheet margin. Numerical models have been developed to describe

Box 8.1. Numerical models of the oceans, atmosphere and ice sheets

Numerical models of the oceans, atmosphere, and ice sheets take similar approaches to simulating the large-scale evolution of each system. All are based on the principles of mass, momentum, and energy conservation, with these conservation equations governing mass and energy transfer within or between these systems. The models disassemble the oceans, atmosphere, and ice sheets into 3-D grid-cell networks and solve the governing equations to predict the system state in each grid cell. Neighboring cells interact to simulate the fluxes of water, air, ice, energy, and climatically active variables such as salt and water vapor.

The whole system is driven by boundary conditions such as global topography and bathymetry, the Earth's rate of rotation, and temporal and spatial patterns of solar input. The resulting fluid motions and energy exchanges provide a representation of the climate system. Integrating the system forward in time, system interactions can give internal weather/climate variability or can simulate climate system response to a change in boundary conditions, for example, increases in solar activity or greenhouse gas concentrations.

The resolution of the simulation is determined by the size of the 3-D grid cells used to discretize the oceans, atmosphere, and ice sheets. Although computational limitations are continually receding, simulating climate dynamics still taxes the world's most advanced computational facilities. This places limits on the available simulation capabilities. For century-scale climate change scenarios, typical grid resolutions are 1° latitude-longitude for the oceans, 2° to 3° for the atmosphere, and 0.2° (~20 km) for ice sheets.

the ice sheet. However, some processes are poorly understood and unresolved in the models, particularly those associated with basal sliding of ice over the bedrock. Furthermore, SMB and ocean-ice interactions need to be prescribed to simulate ice sheet response to climate change. Although efforts to couple ice sheet, atmosphere, and ocean models to describe the co-evolution of these systems are still in early stages, this is the best available route for physically-based forecasts of how the Greenland Ice Sheet will change in the coming decades and centuries.

8.3.1. Aspects of modeling climate change for Greenland

The IPCC AR4 models incorporate many improvements compared to their predecessors, but there are still shortcomings (see Stroeve et al., 2007; as well as Chapter 2). While some studies suggest anthropogenic forcing may favor a positive Northern Annular Mode (NAM), there is evidence that climate models underestimate NAM-like variability (e.g., Stenchikov et al., 2006). Maslanik et al. (2007) analyzed three types of atmospheric circulation pattern that appear most significant in terms of Arctic Basin winds and ice transport. The 'light ice' phases of these patterns include decreased mean sea level pressure (SLP) in the North Atlantic (an 'NAO-like' pattern resembling the positive phase of the NAO), a low pressure cell within the Arctic Basin (a 'central Arctic' pattern), and a dipole pattern of high pressure over the Canadian Arctic paired with low pressure

over the Siberian Arctic. Winds and ice transport patterns that favor reduced ice cover in the western and central Arctic have continued since the late 1980s, but the Arctic Oscillation (AO) index is not a reliable indicator of these patterns.

Atmospheric modeling over complex terrain is a great challenge. The major reason for this is the difficulty represented by the topographical relief. If not properly resolved, the atmospheric circulation will not, for an otherwise perfect model, be able to depict the real local circulation patterns. This, in turn, will lead to systematic deficiencies in the models' ability to capture regional / local climatological features.

The most obvious example is that of topographically lifted precipitation that causes enhanced precipitation on the upstream slopes of a mountain, while producing less precipitation on the lee side downstream. Only when the appropriate mountain ridges are captured by the resolution, will the precipitation patterns be accurately simulated. The importance of this effect at larger scales is not well understood.

High resolution is offered by regional climate models (RCMs) (see Chapter 2). Results from RCMs are sensitive to the choice of integration domain, the horizontal and vertical resolution and parameterizations, and all contribute to the uncertainties of RCM simulations. There is no exact choice of domain any more than there is for resolution or parameterization, which means that domain must be treated as yet another element contributing to the uncertainty of RCM simulations. RCM simulations are also sensitive to lateral boundary conditions and to the surface conditions prescribed. The climate scenario projections come from interpolated atmosphere-ocean general circulation model (AOGCM) simulations and contribute to the overall uncertainties of RCM simulations and projections. The RCM results can vary depending on the AOGCMs used, in terms of large-scale atmospheric circulation patterns and their teleconnections. RCM results are often based on only one specific AOGCM and are for just one selected scenario. A multi-model ensemble approach could increase the confidence of future projections of extreme climate. Accurate simulation of surface mass accumulation over the ice sheets requires a spatial resolution which is currently not available from AOGCM simulations. Therefore high-resolution RCMs (i.e., PMM5 and MAR) have been run for shorter time slices driven by AOGCM boundary conditions and combined with an ice sheet mass balance model as described by Gregory and Huybrechts (2006) and Fettweis et al. (2008), see also Chapter 2.2.

One of the remaining challenges is that sequential modeling (i.e., climate modeling followed by ice sheet modeling) lacks any possible feedback between the climate and ice sheet. Thus, a poor climate model performance over the ice sheet will result in a possibly erroneous climate change signal over the ice sheet as well. This in turn will possibly result in an erroneous estimate of the change in SMB, even if the ice sheet model is excellent. A consistent development and coupling of models of atmospheric processes with ice sheet models is therefore in demand (see also Chapter 2).

According to the recent IPCC AR4 GCM studies, the Arctic is projected to be generally warmer and wetter (Kattsov et al., 2007). Using an RCM, Rinke and Dethloff (2008) projected future changes over the Arctic by the end of the 21st century according to the IPCC A1B emissions scenario. The results showed distinct regional patterns. Over the Arctic Ocean

these are mainly associated with sea-ice retreat and over land are mainly associated with surface characteristics, such as orography, and the agreement with the large-scale temperature and precipitation projections within the driving GCM is striking. Regional detail is evident along the North Atlantic storm track and, during summer, close to orographic obstacles. This is attributed to the higher resolution of the RCM.

Modeling sea ice in a realistic manner is still a great challenge, particularly with respect to the minimum ice extent at the end of summer. Dorn et al. (2007, 2008, 2009) investigated modified descriptions of ice growth, snow and ice albedo, and snow cover on ice used in the coupled regional atmosphere-ocean-ice model HIRHAM-NAOSIM. A series of sensitivity experiments were performed in order to assess the need for more sophisticated parameterizations of these processes in coupled regional and global models. These showed that the simulation of Arctic summer sea ice is very sensitive to the parameterization of snow and ice albedo as well as to the treatment of ice growth. The parameterization of the snow cover fraction on ice plays an important role in the onset of summer ice melt. This has a crucial impact on summer ice decay when more sophisticated schemes for ice growth and ice albedo are used. The work by Dorn and co-workers illustrates that when using a harmonized combination of more sophisticated parameterizations, simulation of the summer minimum in ice extent can be considerably improved due to the more realistic representation of interactions between the atmosphere and sea ice influencing Greenland and the Arctic as a whole.

Current understanding of model limitations as briefly described here, suggest that as a necessity for achieving improved simulations of the climate over Greenland, model development efforts should be directed towards the following:

- Use of an accurate ice sheet topographic dataset
- Accurate albedo parameterization
- More realistic surface layer model, including thermal conductivity for snow/firn
- Accurate planetary boundary layer momentum exchange.

These recommendations would improve the simulation of regional effects of Greenland's climate due to finer-resolved orography and land-sea contrasts, better-resolved non-linear interactions between the large-scale and mesoscales, better simulation of hydrodynamic instabilities and synoptic cyclones, and better description of hydrological and precipitation processes. Better representation of the northward development of the storm track, and invasion of the Arctic Basin by cyclonic systems from the lee of Greenland, which varies greatly with the NAO, would have a major influence on the Arctic sea-ice movement and melting in a coupled regional climate system. At higher resolution, the air-sea interaction changes, the air-sea heat flux is enhanced and localized in the lee of Greenland, and the wind stress increases.

8.3.1.2. Model limitations and challenges

In order to capture even the large-scale snow accumulation rates, it is essential for the atmospheric models to include a good representation of the mountains around the Greenland Ice Sheet. The detailed deposition of moisture in the mountains as well as over the ablation zone of the ice sheet will influence

the amount of moisture transported further into the interior of the ice sheet. It is also of great importance to use an accurate elevation model for the ice sheet itself. Box and Rinke (2003) looked at how the ice sheet topography used in the standard version of the HIRHAM regional climate model compared to a more recent digital elevation model (e.g., Bamber et al., 2001), and found substantial differences. They considered these to be responsible for several degrees of systematic temperature bias, particularly in the ablation zone.

Figure 8.20 illustrates how the topography of Greenland is depicted with increasing resolution (based on Bamber et al., 2001). At the coarsest grid resolution (~150 km), which is typical for most advanced state-of-the-art GCMs, the resolution does not allow for discrimination between the outermost part of the ice sheet and the coastal mountains. This basically implies that the atmosphere 'sees' all of Greenland as one big lump of ice. Increasing the grid resolution to 25 km improves the situation, but the gradients over the ice margins are not resolved even at this scale. Typically, the incremental rise in topography within the ablation zone is 300 to 500 m for a 25 km grid, which is potentially in conflict with the formulation of the vertical structure of the atmospheric model and clearly introduces systematic surface temperature




Figure 8.20. (a) Topography of Greenland, with the ice sheet extent indicated by the black contour, (b) elevation as seen by models along a W-E transect (indicated in 'a') at GCM scale (black line) (~150 km), high-resolution GCM scale (green line) (~75 km), high-resolution RCM (blue line) (~25 km), and very high-resolution (red line) (~5 km). Source: Courtesy of Philippe Lucas-Picher, Danish Meteorological Institute.

errors that may exceed 3 °C. At a grid resolution of 12 km, this feature is almost resolved. But it is not until a resolution of about 5 km is applied that the surface temperature error no longer introduces serious inconsistencies, in cases where the modeled temperature field is used without any adjustment.

At present, it is still speculative as to whether a grid resolution of 5 km will also improve the precipitation climatology. Figure 8.21, however, compares the precipitation patterns from three simulations with the RCM HIRHAM with increasing resolution (Stendel et al., 2008; Philippe Lucas-Picher, Danish Meteorological Institute, pers. comm. 2008). The three HIRHAM realizations have a grid distance of ~80 km, 25 km and 5 km, respectively. The large-scale patterns are similar, but whether the precipitation is falling in the coastal margins, in the ablation zone or even in the accumulation zone does not appear to be resolved unless using a fine grid resolution.

In order to provide realistic driving conditions for an ice sheet model, a necessary requirement for the atmospheric model must, therefore, be that it resolves the features that are of most relevance in controlling the mass balance of the ice sheet. If this cannot be provided directly, additional adjustments to the data are necessary. This, in turn, raises questions about internal consistency of the energy and water cycle balances.

Representing the detailed regional conditions of Greenland in a climate model is also affected by the ability of the model to simulate realistically the energy and moisture cycles in the surrounding seas. Clearly, part of the moisture supply for the precipitation systems influencing the ice sheet originates from the regional seas surrounding Greenland. Because the oceanic circulation around Greenland is complex and poorly resolved by coarse-resolution coupled climate models, it is not surprising that detailed sea-ice conditions are often poorly represented.

At best, only large-scale sea-ice conditions can be depicted. Stendel et al. (2008) gave an example of a climate change downscaling experiment, where the driving GCM does have a relatively good representation of present-day sea-ice conditions, both with respect to seasonal variability and to interannual variability. However, details are still not matching observed

conditions to a level providing confidence that the changes are indeed a result of a realistic timing of changes in circulation and moisture support.

When ice sheet models are forced with atmospheric model output from GCMs, it is always an issue as to how realistic the simulated sea-ice temperatures and sea-surface temperatures actually are.

The IPCC concluded in its Fourth Assessment Report (IPCC, 2007) that mean temperature within the Arctic is likely to increase at a greater rate than mean global temperature, confirming results from previous IPCC assessments and the Arctic Climate Impact Assessment (ACIA, 2005). For the IPCC A1B emissions scenario, the annual mean Arctic temperature increase by the end of the 21st century is projected to be about twice that of the global mean increase (5 to 7 °C vs 2.5 to 3.5 °C) (IPCC, 2007; Christensen et al., 2007). Figure 8.22 shows an extract from an evaluation of 21 model simulations of global change under the A1B emissions scenario (Christensen et al., 2007), highlighting three models, the NCAR PCM, GFDL CM2.0, and MPI ECHAM5 as well as the 21-model mean. It is clear that the three individual models qualitatively show the same climate change response, but that the magnitude of the change differs by several degrees with the PCM model showing the lowest and the ECHAM5 model the highest degree of warming, while the GFDL CM2.0 model is close to the ensemble mean.

It is interesting to note, however, that the projected climate signals are to some degree caused by quite different mechanisms. Figure 8.23 shows an extract of an analysis of the performance of 14 model simulations for the period 1958 to 2000 (Walsh et al., 2008). Again, the ensemble mean behavior is shown with the same three individual models. A common feature for most of the models, reflected by the ensemble mean, is a clear cold bias in the Barents Sea due to a tendency to simulate too much sea ice, with the MPI model a clear exception. The implication is that only the MPI model simulates sea-ice coverage in this region reasonably well. At the same time, the greatest warming by the end of the study period is simulated exactly over this region in the ensemble mean as well as by the individual models.




Figure 8.21. Resolution dependency of simulated winter precipitation over Greenland. (a) RCM resolution (~80 km), (b) RCM resolution (~25 km), (c) RCM very high resolution (~5 km). Source: Courtesy of Philippe Lucas-Picher, Danish Meteorological Institute.




Figure 8.22. Maps of composite (based on 21 models) and three individual model-simulated annual mean temperature changes (2080–2099 vs 1980–1999) for the IPCC A1B SRES scenario. Source: IPCC (2007).

In the NCAR and GFDL models, this partly reflects the bias in present-day sea-ice conditions, while this apparently cannot be the case in the MPI model because the present-day sea ice appears to be captured with some realism. It should also be noted that, in general, the greatest warming occurs in the area with too much ice (strong cold bias) under current conditions, and in the NCAR model in particular, even though here winter data are compared with the annual mean.

This section has shown that, to varying extents, results at the regional scale are clearly subject to systematic errors in present-day simulations. Using an ensemble of models masks this deficiency. The role of the ocean as a driver of the climate in the Arctic is obvious, and there should be concern about interpreting a climate change signal, when most of the signal is apparently due to systematic error in simulating present-day conditions.

As the models discussed above have indicated, maps of warming must be carefully analyzed and, without further analysis, data cannot be used in a region with non-linear feedbacks such as the presence and absence of sea ice. Thus, it is also likely that the simulated warming and precipitation change signals are strongly influenced by these systematic errors, not only in the vicinity of the imperfections themselves, but also further away due to non-linear interactions in the atmospheric and oceanic circulations.




Figure 8.23. Ensemble mean temperature (based on 14 models) and three individual model temperature biases for winter (1958–2000). Source: Walsh et al. (2008).

8.3.2. Modeling Greenland Ice Sheet dynamics

8.3.2.1. Objectives of numerical ice sheet modeling

The future evolution of the Greenland Ice Sheet depends on the extent of climate change over the ice sheet, in particular the specific impacts on SMB as well as past climate forcing. As discussed in Sections 8.2.3 and 8.2.4, overall ice sheet mass balance depends strongly on the rate of ice discharge. In particular, dynamical mass loss is governed by the flux of ice to the ablation area. This includes terrestrial margins, where ice is removed through melting and runoff, and marine margins, where ice loss occurs through iceberg calving and melting of ice that is in contact with the ocean. High ice velocities lead to greater transport of ice to the ice sheet margins and higher rates of mass loss through each of these processes.

Ice sheet dynamics are difficult to predict or extrapolate from present-day observations because ice sheet velocities do not remain constant on decadal and century timescales. There are unanswered questions as to how ice flux will respond to changes in ice sheet geometry, oceanic boundary conditions, and surface meltwater reaching the bed. All of these changes are expected in the coming decades and centuries.

Numerical ice sheet models have been designed to describe first order ice sheet physics and to provide prognostic solutions for ice sheet evolution in response to such changes. Numerical models are required because the flow and deformation of ice at a particular point depends on a complex array of physical parameters, including ice sheet thickness, surface and bed slopes, ice temperature (which influences the deformation of the ice), ice fabric, valley walls, regional ice flow, and basal friction which is a function of bed geology, basal ice temperature, and subglacial hydrological conditions. By simulating these processes and features of the ice sheet system, physically-based estimates of ice flow and deformation and thus ice sheet response to climate change are possible.

8.3.2.2. The physical basis of ice sheet models

Detailed descriptions of ice sheet physics are provided by van der Veen (1999) and Paterson (1994). Box 8.2 provides a simplified overview of the theoretical basis of ice sheet models. The ice sheet is discretized into a 3-D array of grid cells and the equations that govern ice thickness, velocity, and temperature evolution are solved in each grid cell. Atmospheric and oceanic forcing of the ice sheet are introduced as boundary conditions.

The Greenland Ice Sheet is still adjusting to the last cycle of glaciation and deglaciation, particularly with respect to ice temperature at depth, where most of the ice deformation occurs. Simulations of future evolution of the ice sheet therefore require a ‘spin up’ simulation that takes Greenland through one or more glacial cycles (Huybrechts et al., 1991; Letréguilly et al., 1991). The climate forcing for these simulations is taken from Greenland ice core records. Climate forecasts are then imposed for studies of future ice sheet changes, generally as perturbations from present-day climatology.

When considering longer time scales, adjustment of the Earth’s crust to ice loading and unloading must be included in the model as this represents a potentially important

Box 8.2. Theoretical basis of ice sheet models

Three-dimensional models applied to the Greenland Ice Sheet to date all make use of the shallow-ice approximation, in which the gravitational driving stress is locally balanced by drag at the glacier base (Nye, 1957; Hutter, 1983). The gravitational driving stress is $\tau_d(z) = \rho g(hS - z) \nabla hS$, where ρ is the ice density, g is gravitational acceleration, hS is the glacier surface elevation, and ∇hS is the surface slope. At the glacier bed, $\tau_d(hb) = \rho gH \nabla hS$, for ice thickness H . Glen’s flow law relates ice deformation rates to the stress field in the ice. In the shallow-ice approximation, the ice velocity (u) associated with vertical shear deformation (d), i.e., ud , follows $ud \propto \nabla hS^n H^{n+1}$, where $n = 3$ is the exponent in Glen’s flow law.

Ice deformation rates are sensitive to ice temperature, with the effective viscosity of ice varying by a factor of about 1000 over the range of temperatures found in the Greenland Ice Sheet (Marshall, 2005). Ice sheet models therefore simulate the 3-D ice thermodynamics – advection and diffusion of energy and strain heating due to ice deformation – to model the temperature distribution in the ice sheet.

In addition to internal deformation, ice can flow via basal motion where the bed is at the pressure-melting point, through some combination of subglacial sediment deformation and decoupled sliding over the bed. Basal flow rates, u_b , often exceed the ice motion associated with deformation by one or several orders of magnitude. The vertically-averaged velocity, $\bar{u}$, is calculated from the sum of these two contributions: $\bar{u} = \bar{u}_d + u_b$. Large-scale basal flow generally requires a layer of pressurized subglacial meltwater at the bed. Models make some allowance for basal flow, usually through a local sliding ‘law’ relating basal flow rates to gravitational shear stress at the bed. There is little knowledge of subglacial hydrological conditions, and the physical processes that determine basal water pressure are not yet modeled or parameterized in ice sheet models. For this reason, sliding rates and the spatial-temporal variability in basal flow are highly uncertain in current models.

Given an estimate of the vertically-averaged ice velocity, the equation for conservation of mass describes the rate of change of ice thickness at each point on the ice sheet:

$$\frac{\partial H}{\partial t} = -\nabla \cdot (\bar{u} H) + b$$

The first term on the right describes the divergence of the ice flux and b is the local mass balance rate (accumulation minus ablation; basal melting can be included in this term but is, generally, negligible compared to surface accumulation and ablation). This is usually considered over one year, that is, expressed as metres per year of ice-equivalent gain or loss of mass. Given measurements or climate model predictions of b , this equation can be integrated forward to simulate the evolution of ice thickness at all locations on the ice sheet. This is the basis of ice sheet modeling.

feedback through the coupling between SMB and surface elevation (e.g., Oerlemans, 1980). Different models have been adopted for estimating isostatic adjustment, with for example, Marshall et al. (2000) assuming a local, damped return to

isostatic equilibrium, while Le Meur and Huybrechts (1998) incorporated a self-gravitating spherical visco-elastic Earth model.

For whole-ice sheet simulations over one or more glacial cycles the horizontal grid spacing is typically 20 km or more, with some 30 layers in the vertical (e.g., Huybrechts, 2002). Grid sizes of 5 to 10 km are tractable, but each time the grid is reduced by a factor of two the computational demand increases by an order of magnitude. There are also theoretical and pragmatic limits to resolution. The shallow-ice approximation that is used in most whole-ice sheet models is based on an assumption that horizontal grid dimensions are greater than the ice thickness. Further, available bedrock maps for the ice sheet, derived from airborne radar surveys, are currently available only at 5-km resolution. Issues associated with model resolution are discussed below.

Parameterization of SMB is a key parameterization in the models. Most ice sheet modeling efforts to date prescribe the SMB from monthly or annual surface air temperatures and precipitation rates. These can be based on observed (present-day) meteorological patterns or meteorological fields downscaled from a climate model. In general, the SMB fields simulated by climate models are not accurate enough for coupled ice sheet-climate modeling, in part because GCMs are too coarse to adequately resolve the ice sheet ablation areas (see Section 8.3.1). This makes it difficult to estimate ablation through a direct surface energy balance, so degree-day methods, driven solely by temperature fields, are generally adopted for melt and runoff modeling, following Reeh (1991) and Huybrechts et al. (1991).

Interest in decadal-scale ice sheet changes and the development of improved regional-scale meteorological models (e.g., Box et al., 2006) should soon permit direct estimates of SMB from meteorological models for future predictions, rather than parameterizations based on temperature and precipitation fields. This is desirable because such models are more physically-based and can capture the spatial variability in climate fields as ice sheet geometry and surface properties change; parameterizations tuned to present-day conditions become less reliable as both the climate and the ice sheet depart from their present-day state. This is discussed in more depth in Sections 8.2.2, 8.3.1, and 8.3.3.

8.3.2.3. Modeling of the Greenland Ice Sheet

To date, Greenland Ice Sheet simulations are all based on the shallow-ice approximation and the physics described in Box 8.2 (Huybrechts et al., 1991, 2004; Letréguilly et al., 1991; Greve, 1997, 2000; Ritz et al., 1997; Huybrechts and de Wolde, 1999; Marshall and Cuffey, 2000; Tarasov and Peltier, 2002; Gregory and Huybrechts, 2006). Basal flow is typically assumed to be active wherever the basal ice is at the pressure-melting point and is prescribed as a function of the gravitational driving stress.

Figure 8.24 gives an example of modeled and observed topography for the Greenland Ice Sheet on a 5-km grid. Present-day ice sheet area and volume can be simulated to within a few percent, but there are often systematic regional biases in modeled ice thickness (Figure 8.24c). The Northeast Greenland Ice Stream (see Figures 8.15 and 8.16) is present in

the model (Figure 8.25b), but the modeled flow rates in the ice stream are too slow, contributing to the ice thickness anomaly in this region. The ice margin position is poorly simulated in northern Greenland, leading to thickness anomalies of several hundred metres. The model is anomalously thin in southern-central Greenland, for reasons that are unclear. It may be related to a bias in the climate forcing or modeled rates of basal flow that are excessive, driving a thinner, lower-sloping ice dome.

The velocity field over the whole ice sheet indicates high flow rates on the ice sheet flanks and areas of concentrated ice flux where they are expected (Figure 8.16). These regions correspond




Figure 8.24. Model reconstructions of the present-day Greenland Ice Sheet on a 5-km grid: (a) observed and (b) modeled ice sheet surface topography. (c) Modeled minus observed ice sheet thickness. Source: Unpublished results, based on the Greenland Ice Sheet model described by Marshall and Cuffey (2000).

to major topographic channels and drainage outlets, which are resolved in this simulation. However, the model fails to capture the high rates of discharge in major outlet glaciers such as Jakobshavn Isbræ and Helheim Glacier; simulated velocities in some of these systems are an order of magnitude too low. This is most likely to be related to inadequate resolution of the fjord geometry, discussed further below.

Basal flow in this model is parameterized as a function of gravitational driving stress and is enabled wherever the ice sheet bed is at the pressure-melting point. Figure 8.25 plots modeled present-day basal ice temperatures and ice sheet velocities, including contributions from basal flow in warm-based sectors of the ice sheet. Few data are available to validate or test these predictions from the model.

Deep borehole data confirm that central and eastern Greenland are generally cold-based, due to the relatively thin ice that drapes the underlying mountains and the advection of cold ice to the bed along the ice divide. On the ice sheet flanks, deformational heating warms the ice to produce large areas that are at the melting point. In the major topographic channels, this can produce a thick temperate ice layer which has a low effective viscosity, introducing a positive feedback




Figure 8.25. Model reconstructions of the present-day Greenland Ice Sheet (a) basal ice temperatures below the pressure-melting point, and (b) surface ice velocity. Source: Unpublished results, based on the Greenland Ice Sheet model described by Marshall and Cuffey (2000).

that accelerates deformation and ice flow in these channels.

These models have limitations, elaborated below, but they also capture many large-scale features of the ice sheet dynamics in Greenland. Bearing the model limitations in mind Figure 8.26 illustrates the modeled response time of the Greenland Ice Sheet to simple warming scenarios. A regional warming of 2 to 8 °C is introduced as a linearly increasing temperature perturbation over the period 2000 to 2100, relative to late 20th century baseline temperature fields over the Greenland Ice Sheet as compiled by Ohmura (1987). The temperature anomaly is held constant from 2100 to 3000. Figure 8.27 plots ice sheet configurations at 3000 for the 4 and 8 °C scenarios.

Most of the ice volume loss in these scenarios comes from southwestern Greenland, with the ice dome in southern Greenland collapsing under sufficient warming. This result has been well established in the modeling by Huybrechts and others, as illustrated in Figure 8.28 from Alley et al. (2005). These results correspond to three different scenarios of future atmospheric carbon dioxide (CO_2), with values in excess of 750 ppm inducing summer warming of more than 5 °C in Greenland, sufficient to excite collapse of Greenland's southern dome on a timescale of several centuries.

These results reflect the plausible impact of atmospheric warming on increased melt and drawdown of the Greenland Ice Sheet. There is an accelerating ice loss in late stages of the retreat, when the interior of the Greenland Ice Sheet falls below the equilibrium line altitude. Due to simplified fast-flow and ice-marginal physics in the model, as well as one-way climate forcings (i.e., missing climatic feedbacks of ice sheet retreat), the time-scale of modeled Greenland Ice Sheet retreat in Figures 8.26, 8.27 and 8.28 is uncertain. Many of the missing feedbacks and processes give a systematic bias towards underprediction of ice sheet sensitivity to climate warming; it is expected that Greenland Ice Sheet retreat will proceed more quickly than forecast for a given warming scenario. However, how quickly this could transpire is not well-constrained, because no models with the requisite physics are available to assess this. This is picked up again in Section 8.3.3. The next section addresses several of the outstanding challenges for the current ice sheet models.




Figure 8.26. Modeled Greenland Ice Sheet volume response to different climate warming scenarios. Warming scenarios are introduced as a linear temperature perturbation from 2000 to 2100, with warming held constant at that level (2, 4, 6, or 8 °C) from 2100 to 3000. Source: Unpublished model results from Shawn Marshall, University of Calgary. For illustrative purposes only; not intended as a forecast for the ice sheet.




Figure 8.27. Modeled Greenland Ice Sheet surface topography in 3000 AD for (a) the 4 °C and (b) 8 °C warming scenarios of Figure 8.26. Source: Shawn Marshall, University of Calgary.




Figure 8.28. Greenland Ice Sheet simulations for 3000 to 5000 AD under different greenhouse gas scenarios: (a) surface elevation, (b) surface temperature change, and (c) sea level change. Source: Alley et al. (2005).

8.3.2.4. Modeling challenges

The modeling studies cited above have a general skill in simulating Greenland Ice Sheet dynamics, but some features and processes are difficult to capture. These include ice sheet-ocean interactions, ice stream dynamics, basal flow processes (sliding and sediment deformation at the glacier bed), and coupling of ice marginal dynamics and inland ice dynamics. These features are critical to questions of ice sheet sensitivity and response time to climate change.

The IPCC AR4 summarizes this well: *Dynamical processes related to iceflow not included in current models but suggested by recent observations could increase the vulnerability of the ice sheets to warming, increasing future sea level rise. Understanding of these processes is limited and there is no consensus on their magnitude.* (IPCC, 2007:17).

An expanded discussion of shortcomings of existing ice sheet models was provided by van der Veen and ISMASS (2007). Shortcomings with existing Greenland Ice Sheet models

fall into three categories: those related to physical processes; those associated with spatial resolution; and uncertainties in specification of boundary conditions, including ice-ocean and ice-atmosphere interactions. These issues are elaborated in the following sections, ranked according to a subjective judgment of their relative importance to modeling Greenland Ice Sheet ice dynamics. These processes and considerations have different levels of importance in different parts of the ice sheet, and in some cases the process is not understood well enough to assess how important it will prove to Greenland Ice Sheet response to climate change.

8.3.2.4.1. Uncertainties associated with physical processes

Basal flow and hydrology

The extent and physical controls of glacier motion due to basal flow remain poorly known and difficult to quantify (Clarke, 2005). This is true across a wide spectrum of ice masses, including mountain glaciers, outlet glaciers in Greenland and other polar icefields, and Antarctic ice streams. Basal flow is generally the main mechanism for fast flow (except for enhanced creep rates in deep fjords), so must be well quantified to provide a realistic model of ice sheet dynamics.

Elaborate theories have been constructed to describe the sliding of ice over variously shaped obstacles and glacier beds with different roughness characteristics, but it is unclear whether the models are relevant to large-scale basal flow. The models describe salient physical processes in the subglacial environment, including regelation and stress enhanced softening of glacier ice, which allow it to flow around basal obstacles, and the free slip of basal ice over air- and water-filled cavities in the lee of bedrock obstacles. While these processes are likely to contribute to integrated basal slip over large areas of the glacier bed, at least for hard beds (i.e., bedrock rather than deformable till), the governing physics operate at scales of centimetres to metres. Basal motion at scales of tens of metres to tens of kilometres, as observed in Antarctic ice streams and ice marginal regions of Greenland (Joughin et al., 2008a), is more relevant to overall ice flux.

Furthermore, motion associated with regelation and stress-softening around bedrock obstacles increases non-linearly with shear stress (Paterson, 1994:157), whereas basal flow in many settings (e.g., Antarctic ice streams) is associated with low values of gravitational driving stress: thin, low-sloping ice with subglacial water pressures near flotation, implying low values of basal shear stress over large regions (Bindschadler et al., 2000). Summer speed-ups in valley and outlet glaciers and the ice marginal region of the Greenland Ice Sheet provide another illustration of this. These speed-ups are associated with negligible change in surface geometry (i.e., gravitational driving stress), but are instead driven by reductions in basal friction due to the influx of surface meltwater to the bed (e.g., Iken and Bindschadler, 1986; Copland et al., 2003; Das et al., 2008; Joughin et al., 2008a).

The mechanics of large-scale basal motion therefore appear to be governed by the extent of the glacier bed that experiences ice-bed decoupling due to high subglacial water pressures. High water pressure promotes basal flow by effectively floating the glacier above the bed, reducing basal traction. This applies both

to basal sliding and subglacial sediment deformation, although the rheological properties and supply of basal sediments also need to be considered for the latter.

The need to understand hydrological influences on basal flow and to incorporate these processes into models is pressing, considering recent evidence that surface meltwater can drain to the bed through hundreds of metres of cold ice in marginal areas of the Greenland Ice Sheet (Zwally et al., 2002b; Das et al., 2008) and smaller-scale polar icefields (Boon and Sharp, 2003). Similar to the long-standing observations from mountain glaciers, this influx of meltwater is capable of triggering transient speed-ups, increasing the discharge of ice (Zwally et al., 2002b; Joughin et al., 2008a). This presents a direct mechanism by which climate change can influence ice dynamics. Coupled with trends of increasing spatial extent and intensity of the melt season in Greenland (Tedesco, 2007), accelerated summertime flow is expected in future decades in the marginal zones of the Greenland Ice Sheet.

The magnitude of the speed-up and the extent to which ice sheet drawdown will propagate inland are less clear. Joughin et al. (2008a) presented observations over a 300-km wide region in southwestern Greenland which indicate that summer speed-ups of the major outlet glaciers, including Jakobshavn Isbræ, contribute only a few percent to the total annual discharge. Speed-ups on the slow-moving ice sheet flank (i.e., away from the major outlet glaciers) are relatively greater, increasing annual discharge by as much as 25%, but this region does not account for much of the total dynamic discharge of the Greenland Ice Sheet. Therefore, this mechanism represents a pathway for ice sheet response to climate forcing, but one which may be relatively stable (i.e., non-catastrophic).

These influences on ice dynamics are generally absent in the large-scale models that predict Greenland Ice Sheet response to climate change. Physically-based models of ice sheet hydrology are needed to simulate these processes. In a flowline model of the western flank of the Greenland Ice Sheet, Parizek and Alley (2004) simulated the supraglacial hydrology and englacial drainage to the bed, assuming that surface drainage induces speed-ups as seen by Zwally et al. (2002b). Extrapolating their results to the whole ice sheet, their most conservative scenarios gave 12% to 38% more volume loss from the Greenland Ice Sheet over the next several centuries due to surface-meltwater induced lubrication, with the effect increasing with warming. Parizek and Alley (2004) also suggested that the effect could be much higher, with the upper range of their modeling giving a tripling of the ice volume loss in Greenland, relative to models that exclude surface meltwater effects.

These models assume that basal flow is proportional to water supply at the bed, but subglacial water storage and basal water pressures are what really matter for ice-bed coupling and basal flow. The physics that governs the relationship between subglacial water pressure, bed geology, bed roughness, and basal traction still needs to be elucidated and parameterized in a way that is physically valid and testable in models.

A subglacial hydrological model is also required to provide a realistic estimate of spatial and temporal variations in basal water pressure. These have begun to be developed and coupled with models of glacier dynamics (Arnold and Sharp, 2002; Flowers and Clarke, 2002; Johnson and Fastook, 2002; Flowers et al., 2005; Marshall et al., 2005), but subglacial hydrological

conditions are notoriously difficult to observe, so models are difficult to test and constrain at large scales. To date, most models of subglacial hydrology treat the subglacial water system as a distributed water sheet, with water fluxes driven by hydraulic potential gradients. Conduit physics and the nuances of regime shifts between distributed and channelized drainage systems need to be better understood and included in the models in order to capture spatio-temporal patterns of basal water pressure and their influence on glacier dynamics. This has yet to be attempted in Greenland.

High-order stresses (horizontal stress coupling)

The shallow-ice approximation estimates ice motion as a function of the local gravitational driving stress, with the explicit assumption that non-local effects are negligible. This is known to be a poor approximation in certain parts of the ice sheet, such as the ice divide, ice streams, ice shelves, and ice sheet margins. In these settings, higher-order stress terms such as horizontal shear stress and longitudinal stress gradients, sometimes known as non-local stress coupling effects, become important to ice deformation. For instance, horizontal shear stresses at ice stream margins and next to valley walls play an important role in holding back ice flow, while longitudinal strains (stretching) represent the primary mode of ice deformation in ice shelves and floating ice tongues.

Longitudinal stress coupling also provides a mechanism for the transmission of ice-marginal forcings to the interior of the ice sheet. Current thinning of Jakobshavn Isbræ is accompanied by rapid retreat of the calving terminus (Sohn et al., 1998; Joughin et al., 2004). Joughin et al. (2004) proposed that the velocity increase resulted from development of large rifts in the floating tongue, followed soon thereafter by complete collapse of this tongue. Associated reductions in buttressing would allow increased discharge from the grounded portion of the glacier (Thomas, 2004). On the other hand, Pfeffer (2007) proposed that thinning could have decreased the height above buoyancy, thereby reducing the effective basal water pressure. This, in turn, would lead to greater sliding speeds, especially if the ice thickness approached flotation. To adequately incorporate these processes into numerical models and to test the validity of these competing hypotheses, it is necessary to incorporate stress transmission across the grounding line.

Models of glacier dynamics with higher-order stresses have become more common in studies of valley glaciers as well as regional ice sheet applications (Albrecht et al., 2000; Schneeberger et al., 2001; Pattyn, 2002, 2003; Saito et al., 2003). These advances are relatively new, and have yet to be applied to whole-ice sheet simulations in Greenland. Higher-order models such as that of Payne et al. (2004) and Price et al. (2008) demonstrate the importance of longitudinal stress coupling for accurate simulation of ice sheet response to perturbations at the ice sheet margin, that is, inland propagation of changes due to ice-marginal thinning or acceleration.

Iceberg calving

Ice sheet grounding lines, floating ice tongues, and iceberg calving processes are poorly represented in current glaciological models. Existing models generally determine the position of the calving terminus (i.e., marine ice front) by either prescribing an

ice limit based on a maximum water depth (e.g., the continental shelf break), or by freely simulating floating ice tongue advance based on a simple parameterization of iceberg calving, typically prescribing calving rates to be proportional to water depth. Zweck and Huybrechts (2005) examined several different treatments of calving in large-scale models; all are simple parameterizations that do not describe the actual process(es) and should be considered to be statistical-empirical models that aim to capture the bulk loss of ice through this mechanism.

The physical controls of iceberg calving are not well understood and may not be deterministic. Iceberg calving requires fractures to initiate and propagate at the ice front. The process has been well-observed, but the environmental controls of calving rates are difficult to isolate; ocean and air temperature, surface meltwater, sea-ice conditions, and tidal flexure at the ice front may all have an influence on calving, but there is no simple relationship. Sohn et al. (1998) observed an increase in calving rate following the onset of spring melting and found a strong correlation between surface melting on the Greenland Ice Sheet, the melting of fjord ice, and the rapid increase in calving rate during summer. Their observations are insufficient, however, to resolve conclusively whether the presence of abundant surface meltwater enhances the ability of surface crevasses to penetrate the ice thickness, or whether the break-up of confining fjord ice reduces the restraining force acting on the calving front.

Recent evidence indicates the likely role of regional ocean warming in destabilizing the floating ice tongue of Jakobshavn Isbræ (Holland et al., 2008). This is also consistent with tidewater-style retreat of Helheim Glacier on the southeast coast of Greenland (Nick et al., 2009). Ocean-ice sheet coupling is lacking in the current models, but clearly needs to be embraced for predictive models of ice sheet response to climate warming.

8.3.2.4.2. Uncertainties associated with model resolution

Whole-ice sheet models for Greenland now operate at scales of 5 to 20 km, but scale problems still arise because of the small spatial scale of most of the outlet glaciers where drainage to the sea is concentrated. For example, Jakobshavn Isbræ, which drains mass from 7% of the total area of the Greenland Ice Sheet, is less than 10 km wide over its entire ~100 km length (Echelmeyer et al., 1991). This glacier overlies a narrow (6 to 10 km) and deep (~1500 m below the surrounding basal landscape) subglacial trough (Clarke and Echelmeyer, 1996; Gogineni et al., 2006; Lohofener et al., 2006) that cannot be resolved with a horizontal grid spacing of 10 km or more. This limits the capacity of models to simulate the enhanced creep and high rates of flow that are observed in Jakobshavn Isbræ and other major outlet glaciers that drain the Greenland Ice Sheet.

At the same time, detailed and accurate bed topography upstream of the grounding line or calving front is needed to assess the possible irreversibility of terminus retreat for Greenland's major outlet glaciers. Howat et al. (2007) suggested that the rapid retreat of the Helheim Glacier terminus occurred as the calving front retreated into deeper water and continued until reaching a reversed bed slope, similar to the behavior of tidewater glaciers (Nick et al., 2009).

Even if spatial resolution is improved sufficiently to capture

small-scale basal topography, narrow channels no more than a few kilometres wide and up to 1500 m deep challenge the assumptions in the shallow-ice approximation. As noted by Clarke and Echelmeyer (1996), these bedrock troughs are similar to valley walls in that the near-vertical faces produce lateral drag that partially opposes the driving stress – horizontal shear stresses become important in taking up the gravitational driving stress. Also, an overlying temperate layer of fast-moving ice is embedded within more slowly moving ice, which may provide additional resistance, similar to the situation on West Antarctic ice streams. As a start, an effective shape factor could be introduced (Clarke and Echelmeyer, 1996) to account for the additional flow resistance, but no rigorous tests have been conducted to evaluate the applicability of this approach.

Additional uncertainty is introduced by the well-known (if rarely discussed) sensitivity of modeled ice margin dynamics to grid resolution (Abe-Ouchi and Blatter, 1993). With a fixed grid and a free boundary, the standard treatment in continental ice sheet models, the advance and retreat of the ice sheet margin proceed by discrete ‘jumps’ to adjacent grid cells. This process is sensitive to grid resolution because the flux of ice into a neighboring cell is a function of the local surface slope. This sensitivity combines with mass balance elevation feedbacks to make ice margins more mobile under higher resolution; it is simpler for the ice sheet to advance as grid size $\Delta x \rightarrow 0$. Strategies involving adaptive grids (e.g., Price et al., 2008) or sub-grid tracking of the ice sheet margin are needed to give convergent behavior that is insensitive to model resolution.

8.3.2.4.3. Uncertainties associated with boundary conditions

Geothermal heat flux

Pronounced subglacial topography with a very deep basal valley such as that of Jakobshavn Isbræ intensifies the local geothermal heat flux by as much as 100% (van der Veen et al., 2007), potentially introducing an important feedback between subglacial topography and fast flow. On a broader scale, significant variations in crustal thickness have been inferred from airborne gravity, with the thinnest crust underlying the Northeast Greenland Ice Stream and other major drainage routes (Braun et al., 2007). Where the crust is relatively thin, geothermal heat flow may be expected to be greater than the continental average (Leftwich et al., 2007). High geothermal heat flux in northern Greenland is also believed to play a role in providing the temperate, lubricated bed that enables fast flow in this ice stream (Fahnestock et al., 2001). The extent to which spatial variations in heat supplied to the glacier base affect the regional flow regime remains to be resolved (Greve, 2005). This could explain discrepancies in areas where basal meltwater has been detected but where models incorrectly predict the basal ice to be frozen to the bed.

Climatic forcing

Ice sheet models require distributed (spatially-resolved) atmospheric fields to provide SMB fields. To examine climate change scenarios, temporal evolution of atmospheric conditions needs to be characterized. This appears as a boundary condition in ice sheet models, and is prescribed simplistically in most ice

sheet model experiments. Uncertainties in spatial-temporal climate evolution may well dominate uncertainties in ice dynamics modeling for prediction of Greenland Ice Sheet response to climate change. This is discussed in more detail in Section 8.3.3. Still striving to present a correct present-day mass balance, the challenge of reproducing past and future mass balances is large.

In addition to atmospheric fields, ocean and sea-ice conditions directly impact on marine outlet glaciers (e.g., Holland et al., 2008; Section 8.2.3). Marine influences are parameterized through the ocean heat flux that is prescribed as a basal boundary condition for floating ice; this is generally held fixed in current models, for example, a uniform flux of 2 W/m^2 . Plus, ocean conditions can be incorporated in calving parameterizations, but this has rarely been done, in part because of unclear mechanistic links. Except for a small number of regional studies, ocean and ice sheet models are largely uncoupled and ocean variability is not considered in ice sheet modeling. Challenges in ice sheet modeling are revisited in the summary comments of Section 8.3.4, where the main sources of uncertainty for predicting Greenland Ice Sheet sensitivity to climate change are discussed.

8.3.3. Future climate and ice sheet scenarios: Response of the Greenland Ice Sheet to a warmer climate

8.3.3.1. Objectives of coupled ice sheet-climate modeling

Ice sheet models, as described in Section 8.3.2, can investigate the ice-dynamical response to idealized climate change scenarios, such as a uniform cooling or warming. However, patterns of change in climate fields (e.g., temperature, precipitation, radiation, winds) will not be uniform, as used in the models, over the area and elevation range of the Greenland Ice Sheet. Realistic climate forcing is required to provide more detail on ice sheet evolution in the coming decades and centuries. Ice sheet evolution over long timescales also introduces a number of feedbacks that need to be captured in future climate forecasts, such as changing elevation and albedo fields over the ice sheet. Coupled ice sheet-climate models are needed to capture these feedbacks.

The next section describes the coupling approaches adopted in ice sheet-climate modeling. Model predictions of Greenland Ice Sheet response to future warming are then summarized, followed by a discussion of some of the limitations of current models and priorities for future development.

8.3.3.2. Coupling approaches

8.3.3.2.1. One-way and two-way coupling

One-way and two-way approaches have both been adopted for coupling atmospheric climate and ice sheet models. In one-way coupling, output from the climate model provides input for the ice sheet model (e.g., SMB fields), but the ice sheet model output does not force the climate model. This allows existing climate change scenarios (e.g., the ensemble of IPCC climate model forecasts) to be applied to ice sheet simulations. To

increase realism of the exchange, relationships between surface elevation, latitude, and surface conditions have been prescribed to allow climate forcings to change as the ice sheet surface evolves (Huybrechts et al., 1991). This includes elevation-temperature (lapse rate) feedbacks, precipitation rates that increase with increasing temperatures, roughly in accord with a Clausius-Clapeyron relationship, and a modification of local precipitation rates as a function of local surface slope (Ritz et al., 1997).

In two-way coupling, climate model output forces the ice sheet model, while output from the ice sheet model (e.g., ice topography, albedo fields) serves as input to the climate model. Two-way coupling is desirable as the simulation more realistically represents the physical system and the climate feedbacks associated with temporal evolution of the ice sheet. However, as two-way coupling is more challenging than one-way coupling and there are, generally, discrepancies of resolution between climate and ice sheet models, most ice sheet modeling experiments to date have used one-way coupling.

The model results in Figures 8.25, 8.26, 8.27, and 8.28 are examples of ice sheet simulations with one-way climate forcing. SMB is estimated from temperature and precipitation fields, using a degree-day methodology to estimate surface melt and the fraction of precipitation to fall as snow (Reeh, 1991). Present-day precipitation and temperature fields are taken as the baseline and temporal variability is prescribed as a perturbation based on ice core reconstructions, climate model forecasts, or simple scenarios (e.g., a step warming of 2 or 4 °C). Many Greenland Ice Sheet modeling studies have adopted this approach (Huybrechts et al., 1991, 2004; Ritz et al., 1997; Huybrechts and de Wolde, 1999; Greve, 2000; Alley et al., 2005; Gregory and Huybrechts, 2006).

While several parameterized ice-climate feedbacks are included in these numerical experiments, the one-way approach may omit key physical processes that affect the circulation of the atmosphere and ocean, which in turn would modify temperature and accumulation patterns on the ice sheet. A small number of groups have begun to interactively couple ice sheet models with climate models of varying degrees of complexity and resolution. Huybrechts et al. (2002), Fichefet et al. (2003), and Driesschaert et al. (2007) forced an ice sheet model with an AOGCM and examined how Greenland Ice Sheet retreat may affect oceanic circulation in the coming decades. These studies use one-way ice-sheet forcing from the atmospheric model. Other studies focus on ice sheet-atmosphere feedbacks (Gregory et al., 2004; Toniazzo et al., 2004), while a small number of studies explore fully-coupled ice sheet and AOGCMs (Ridley et al., 2005; Mikolajewicz et al., 2007b; Vizcaíno et al., 2008).

A number of climate-system and ice sheet feedbacks identified in coupled model studies are discussed in Section 8.3.3.3. Specific predictions of Greenland Ice Sheet retreat and sea-level rise in response to climate change are summarized in Section 8.3.3.4.

8.3.3.2.2. Climate downscaling

The experiments described above require atmospheric fields to be downscaled to the ice sheet model grid for mass balance modeling. This is due to the mismatch that exists between even high-resolution AOGCMs running at 1.25° (~150 km) grid resolution and ice sheet models (10 to 20 km). Grid

downscaling is thus required and commonly takes the form of a simple interpolation.

This step requires a good understanding of altitude-SMB relationships in different climate regions of the ice sheet. Constant and spatially-uniform temperature lapse rates (linear temperature decreases with elevation) are usually used to downscale temperatures, often with different summer and annual lapse rates (Huybrechts et al., 1991). This does not account for the effects of inversions, katabatic-wind induced cooling at low elevations on the ice sheet, or surface energy balance effects that govern near-surface (vs free-air) temperatures, so a uniform lapse rate is a simplification. Precipitation is more difficult to downscale, as it can vary over small spatial scales, particularly in association with orographic forcing of precipitation at the ice sheet margin. Most modeling studies to date are based on perturbations to the present-day spatial pattern of precipitation in Greenland.

Under interactive coupling, the influence of significant changes in ice sheet topography and boundary conditions are better accounted for. For example, processes such as orographic precipitation and the energy balance influence of increasing areas of open water and ice-free land can be included as feedbacks in the model, rather than an assumption that present-day climate patterns will hold.

Because of the uncertainty associated with interpolation of meteorological fields, the downscaled climate is typically parameterized into positive-degree-day (PDD) input in order to simulate snow/ice melt; a full surface energy balance is not generally attempted. PDD approaches have proven reasonable for melt modeling in Greenland, but downscaling or interpolation of temperature or PDD fields does not ensure conservation of energy between the applied surface climatology and the climate model. There is a similar concern for downscaled precipitation fields. Conservation of mass with respect to larger-scale climate model precipitation and moisture fields is not straightforward and is often disregarded. Conservation of energy and mass warrant serious attention, particularly in two-way coupling experiments where there is a possibility of cumulative biases leading to ‘drift’ in transient simulations.

8.3.3.2.3. Mass balance estimation in coupled models

For the reasons outlined above, most Greenland Ice Sheet modeling studies to date estimate SMB from degree-day calculations as a function of climate (i.e., temperature and precipitation) perturbations. As was discussed in detail in Section 8.2.2, SMB fields have also been simulated directly from climate model re-analyses (Hanna et al., 2002, 2005, 2008), remote sensing studies (Mote, 2003), and regional climate modeling (Box et al., 2006; Fettweis et al., 2007, 2008). Like the reconstructions by Hanna and co-workers, regional climate models make use of re-analyzed climatology to provide the boundary conditions for atmospheric simulations. The main difference is the nature of accumulation and melt modeling in the two approaches; Hanna and co-workers use a degree-day approach, while regional climate models distribute precipitation based on atmospheric dynamics and estimate melt from a surface energy balance.

Table 8.2 gives a summary of simulated SMB terms from the historical period for several of these efforts. These studies

provide detailed estimates of Greenland Ice Sheet mass balance through the second half of the 20th century, but future forecasts cannot be carried out with re-analyzed climatology. RCMs offer a potential solution to this, as they can be trained/calibrated on the historical period and forced by global-model fields for future simulations. This has yet to be attempted for Greenland.

Regional climate models have the inherent capacity to represent the physical processes of how snowfall and melt relate to the local and regional surface characteristics and energy budgets, and these models are likely to form the basis for the next generation of Greenland Ice Sheet predictions. However, climate models exhibit systematic biases, for example, land surface temperature too high or too low, in response to biases in model surface energy budget. These errors have been attributed largely to cloud-radiation bias, such as too much or too little downward longwave radiation. Terrain biases are another typical source of systematic bias, commonly arising from inaccurate representation of the terrain or from the need to smooth the surface topography at the ‘steep’ ice sheet margin to avoid atmospheric dynamical instabilities, for example, gravity waves. Through comparison with *in situ* observations, calibration procedures can be developed and uncertainties can be quantified (e.g., Box et al., 2004, 2006). However, a careful assessment of the stationarity of model biases is needed before these models can be applied with confidence to future forecasts.

8.3.3.2.4. Ice sheet-ocean coupling

Regional-scale coastal and sub-ice shelf oceanographic models are also needed to improve ice-climate coupling, something that has been explored on a regional scale in Antarctica, but has not been considered in Greenland. Other than an influence of global sea level on calving rates, ice-ocean feedbacks have not been examined on the scale of the whole ice sheet; ocean temperatures and heat fluxes, sea-ice conditions, and other potential controls of iceberg calving and melting at the ice-ocean interface are invariant in current models. This point is discussed further in Section 8.3.4.

8.3.3.3. Feedbacks in coupled models

Simulations with two-way coupling of the ice-ocean-atmosphere system reveal positive and negative feedbacks on ice sheet retreat in a warmer world. Huybrechts et al. (2002) and Fichet et

al. (2003) examined the coupled response of a 3-D thermo-mechanical model of the Greenland Ice Sheet and an AOGCM to future climate warming (IPCC B2 emissions scenario, mid-range greenhouse gas forcing). Simulated ice sheet melt is put into the ocean circulation model. Modeled melt rates are modest in the 21st century (global sea level rise of 4 cm in response to a warming of 4.5 °C over Greenland), but Fichet et al. (2003) concluded that the freshwater addition to the ocean from ice sheet melt would contribute to a weakened Atlantic Meridional Overturning Circulation (AMOC) by the end of the 21st century; a feedback that lowers temperatures over East Greenland and partly counteracts warming in this region.

In a subsequent study, Driesschaert et al. (2007) concluded that Greenland Ice Sheet melting only significantly impacts on the AMOC in the 21st century under severe future warming scenarios. This is echoed in the results of Mikolajewicz et al. (2007b) and Vizcaíno et al. (2008), who used a coarse-resolution AOGCM interactively coupled with an ice-sheet model at 80-km resolution to explore millennial-scale future climate and ice sheet changes in Greenland. They also predicted that a weakened AMOC will reduce the degree of warming over southern Greenland (Figure 8.29), buffering Greenland Ice Sheet melt. However, changes in the hydrological cycle of the North Atlantic region are the main reason for this; Greenland Ice Sheet runoff is about 10% of the total freshwater forcing of the system (Mikolajewicz et al., 2007b).

Vizcaíno et al. (2008) predicted that a doubling or tripling of atmospheric CO₂ would result in 2 to 5 °C of summer warming in Greenland, with greater warming in northern Greenland (Figure 8.29). Simulations with 4 × CO₂ trigger a shutdown in North Atlantic deepwater formation, which creates a dramatic reversal in the projections and a cooling of up to 3 °C in southern Greenland.

Atmospheric feedbacks in response to Greenland meltback have been examined extensively through the productive collaboration of Philippe Huybrechts, Jonathan Gregory, and colleagues, using Huybrechts’ ice sheet model and the Hadley Centre AOGCM. Toniazzi et al. (2004) examined the effect of removing the Greenland Ice Sheet on regional atmospheric circulation and climate. A lower (or absent) ice sheet reduces the persistent anticyclonic flow over the ice sheet, particularly in winter months, causing a net increase in precipitation in eastern and northern Greenland. Low elevation, reduced albedo, and




Figure 8.29. Modeled changes in summer temperature over Greenland as a result of 2×, 3× and 4× pre-industrial carbon dioxide concentration scenarios. These snapshots correspond to the period 2900–3000 AD and include ice-dynamical feedbacks. Source: Vizcaíno et al. (2008).

the development of vegetation (e.g., boreal forest) cause greatly intensified summer warming and seasonal melting. No perennial snow is predicted. This prevents the ice sheet from re-growing in today's climate; it is an artifact of the Pleistocene, preserved by its own elevation and regional cooling influence.

Ridley et al. (2005) examined two-way coupling for a $4 \times \text{CO}_2$ climate. In this analysis, the ice sheet model output forces the climate model through changes in ice topography, surface albedo, and freshwater runoff. Ridley et al. (2005) concluded that long-term trends are primarily sensitive to topographic feedbacks (i.e., elevation-temperature effects) that are reasonably well captured in the one-way forcing parameterizations of, for example, Huybrechts et al. (1991). There are some additional feedback effects that appear to slow down ice loss. Warming of the ice-free region at the ice sheet margin, which intensifies under climate warming (and with ice sheet retreat) generates a convective circulation that cycles warm air to the interior of the ice sheet, while enhancing the intensity of katabatic return flows at the surface. This cools the lower elevations, reducing melt rates at the ice margin and helping to preserve the ice there.

Ice dynamics introduce another negative feedback in the models during early stages of the ice sheet retreat. As described by Huybrechts and de Wolde (1999) and Ridley et al. (2005), higher ablation at the margins and increased snowfall at high elevations combine to give greater balance gradients and steeper ice sheet slopes. This produces an increased ice flux which buffers drawdown at the ice sheet margin, maintaining thicker ice and reducing the elevation-temperature feedbacks. This reduces the initial rate of ice sheet retreat, although it is not sustainable as drawdown in the interior regions eventually causes an expansion of the ablation area, with elevation and albedo feedbacks that hasten ice sheet retreat.

8.3.3.4. Predicted Greenland Ice Sheet response to warming

Bearing in mind the missing ice-dynamical processes and ice sheet-climate coupling challenges, a number of insights are available from simulations to date. It is clear that the Greenland Ice Sheet is very sensitive to climate warming. In steady-state, a regional warming of more than 3°C is likely to be sufficient to precipitate ice sheet retreat in southern Greenland (Huybrechts et al., 1991; Alley et al., 2005). This is illustrated in Figure 8.28; the southern dome retreats by 3000 AD in these simulations at CO_2 levels between 550 and 750 ppm, which correspond to a summer warming of 4 to 5°C in Greenland.

Based on an ensemble of models, including high-resolution ($\sim 1^\circ$) climate model representations of temperature and precipitation patterns over the ice sheet, Gregory and Huybrechts (2006) concluded that an average annual regional warming of 4.5°C would push the Greenland Ice Sheet into a negative SMB. The threshold temperature is higher than in earlier studies (e.g., 2.7°C in Huybrechts et al., 1991; 3°C in Gregory et al., 2004), in part because summer warming over Greenland, ΔT_s , is forecast to be less than the mean annual warming, ΔT_A : Gregory and Huybrechts (2006) reported an average value $\Delta T_s / \Delta T_A = 0.81$. Summer temperature is the critical parameter for Greenland's mass balance, as this is the main driver of annual surface melt and runoff.

A warming of 4.5°C in Greenland corresponds to an average global warming of 3.1°C in the ensemble of models explored by Gregory and Huybrechts (2006). The relationship is plotted in Figure 8.30, along with estimates of rates of sea level rise due to SMB losses as a function of mean annual warming. There is an average polar amplification factor of ~ 1.5 over Greenland, less than the average value for the Arctic. Part of the moderate polar amplification factor here may be due to the cooling influence of weakened deepwater formation in the Nordic Seas that is predicted by many AOGCMs in the coming decades (see for example Figure 8.29). This is addressed in more detail in Section 8.4.1.

The critical warming value of 4 to 5°C for Greenland to go into a state of negative SMB is often quoted as a threshold for 'irreversible' ice sheet decline. Dynamical ice losses would place the Greenland Ice Sheet into a negative total mass balance well before this SMB threshold was met – this threshold appears to have been reached in the 1990s and 2000s with a regional warming of close to 1°C (Section 8.2.4). However, the temperature threshold for SMB to become negative is considered to be terminal because ice sheet thinning would provide a positive feedback to ice sheet decay. If this proceeds too far, ice sheet drawdown would make it difficult to reverse the decline, even with temperature stabilization. However, the timescale for such a decline is long – many centuries to millennia – so it is difficult to judge irreversibility on this timescale.

Charbit et al. (2008) argued that 3000 Gt of cumulative CO_2 emissions could lead past this threshold for an irreversible Greenland Ice Sheet retreat, such that anthropogenic activity in the 21st century could commit the world to several centuries of sea level rise. Ridley et al. (2010) examined this question through coupled modeling with climate restored to its pre-industrial state for several different Greenland Ice Sheet configurations. They argued for a potential two-stage destabilization of the ice sheet in Greenland, with reductions to 80–90% of the current ice sheet volume inducing ice loss in southern Greenland and an irreversible sea level rise of about 1.3 m over several centuries. If the ice sheet retreats further before climate is stabilized (i.e., under greater or sustained




Figure 8.30. Rates of sea level rise as a function of mean global temperature change and the temperature change over Greenland for future climate simulations in the ensemble of AOGCMs examined by Gregory and Huybrechts (2006). Source: Gregory and Huybrechts (2006).

warming), such that the ice sheet falls below half of its current volume, Ridley et al. (2010) predicted an irreversible sea level rise of about 5 m.

Such a decline is consistent with reconstructions of a reduced Greenland Ice Sheet in the last interglacial period (Cuffey and Marshall, 2000), in response to orbitally induced spring and summer warming at high northern latitudes. Other ice sheet modeling studies predict a less severe ice sheet decline at this time (Huybrechts et al., 1991), due to different assumptions about the ice core isotope–temperature relationship. Miller et al. (2006) and Otto-Bliesner et al. (2006) estimated a summer warming of about 5 °C near Greenland at the peak of the Eemian warming. Ice sheet models predict an almost complete collapse of the ice sheet if warming of this magnitude persists for several thousand years, but the modeled retreat takes several millennia – changes over the first few centuries are modest.

For future warming, the extent of modeled Greenland Ice Sheet retreat by 2100 is primarily a function of the change in SMB, hence the climate scenario. Ice dynamics plays only a minor role over this time scale in the current models, for two main reasons: elevation-induced SMB and ice-dynamic feedbacks are minor over a one-century timescale, and ice dynamics models lack a direct connection with climate (e.g., ocean or surface-meltwater forcing). The latter is consistent with ice-sheet model simulations of the past century; there is little to no interannual variability in modeled ice dynamics. This is partly because ice dynamics in the current generation of ice sheet models is sensitive only to local gravitational driving stress (see Section 8.3.2), which changes slowly.

Table 8.5 provides a summary of future sea-level rise forecasts from model studies of Greenland Ice Sheet response to climate change. These studies are difficult to compare directly because they make different assumptions about future climate change, the climate downscaling strategy and SMB models differ in each study, and results are not always documented for 2100. These results all include ice sheet dynamical feedbacks.

Under CO₂ stabilization at concentrations of 2× pre-industrial, equivalent to the IPCC IS92a climate change scenario, Huybrechts and de Wolde (1999) simulated a contribution to sea level rise from the Greenland Ice Sheet

of 3.9 cm by 2100. Equivalent simulations for 4× and 8× pre-industrial CO₂ concentrations give ice sheet retreat equivalent to 10.6 and 20.8 cm of sea level rise. Using a more sophisticated climate treatment with the IS92a scenario, Huybrechts et al. (2004) estimated an average 21st century rate of sea level rise of 0.45 to 0.49 mm/y from an ensemble of climate models: a net sea level rise of 4.5 to 4.9 cm by 2100 (Figure 8.31). The range of model estimates for 2100 from Huybrechts et al. (2004) is 2 to 7 cm; these estimates are all for the IS92a emissions scenario, so this represents the variation in climate models. Alley et al. (2005) gave a similar estimate for 2100, 5 ± 4 cm, for a fuller range of emissions scenarios.

Greenland Ice Sheet retreat has also been studied by van de Wal and Oerlemans (1997), with a simpler (2-D, vertically-integrated) ice sheet model but using an energy balance model to calculate surface melt. They estimated 10.4 cm of sea level rise from Greenland between 1990 and 2100 due to changes in SMB under the IS92a scenario. Depending on assumptions about basal sliding and the initial state of the ice sheet, van de Wal and Oerlemans (1997) estimated a range from 5 to 16 cm of sea level rise. In a follow-up study, van de Wal et al. (2001) examined the impact of different emissions scenarios and reported a similar range of sea-level rise forecasts, from 6 to 14 cm by 2100. Sea level rise accelerates as the century progresses. The reference scenario, IS92a (10.4 cm), corresponds with 4.1 cm of sea level rise by 2070. With climate fields derived from an AOGCM for a similar scenario (2 × CO₂), van de Wal et al. (2001) estimated only 1.3 cm of sea level rise by 2070, which can be extrapolated to 3.3 cm by 2100. Increased snow accumulation in the AOGCM explains the lower total in this study, compared to the energy balance model results driven by the IS92a reference scenario.

The analysis by Gregory and Huybrechts (2006) is the most detailed examination to date of the expected future contributions to sea level rise from warming-driven changes in SMB. Figure 8.32 plots the phase space of simulated sea level rise as a function of change in temperature and precipitation. Decadal changes in temperature and precipitation from a suite of AOGCM simulations for the 21st century indicate projected temperature increases of up to 8 °C and precipitation

Table 8.5. Model projections of future sea level rise (SLR) associated with Greenland Ice Sheet retreat. Results are from ice sheet modeling studies with one-way climate forcing introduced as a perturbation to present-day temperature and precipitation fields, unless noted otherwise.

Year	SLR, cm	Source	Climate treatment
2100	4.8	Huybrechts et al., 1991	Warming anomaly increasing to +4.2 °C by 2100
2100	3.9	Huybrechts and de Wolde, 1999	Radiative forcing for stabilization at 2 × CO ₂
2100	4.0	Huybrechts et al., 2002	IPCC SRESB2 scenario, single AOGCM
2100	2-7	Huybrechts et al., 2004	IPCC IS92a emissions scenario, ensemble of AOGCMs
2100	1-9	Alley et al., 2005	Range of AOGCM future climate scenarios
2100	10.4	van de Wal and Oerlemans, 1997	IS92a radiative forcing, energy balance model
2100	6-14	van de Wal et al., 2001	As above but a range of IS92 radiative forcings
2070	1.3	van de Wal et al., 2001	2 × CO ₂ , AOGCM forcing of energy balance model
3000	88-317	Huybrechts and de Wolde, 1999	Radiative forcing, stabilization at 2× and 4 × CO ₂
3000	72-240	Greve, 2000	Temperature anomalies of +3 and +6 °C
3000	25	Vizcaíno et al., 2008	2 × CO ₂ , fully coupled ice model and AOGCM
2600	98	Vizcaíno et al., 2010	2 × CO ₂ , fully coupled ice model and AOGCM




Figure 8.31. Modeled sea level rise from Greenland Ice Sheet retreat, 1860 to 2100, driven by modeled high-resolution (1.125°) temperature and precipitation patterns over Greenland, with temporal climate perturbations from the Hadley Centre AOGCM. The different lines denote different treatments of climate. Source: Huybrechts et al. (2004).

increases of up to 50%. The net effect on SMB is negative in the models; higher melt rates beat increases in accumulation. The corresponding rate of sea level rise due to declining SMB ranges from 0 to 2 mm/y for warmings of 0 to 8°C . Examining Greenland Ice Sheet sensitivity to changes in temperature and precipitation, along with an ensemble of AOGCM forecasts for

the full spectrum of IPCC AR4 emissions scenarios, Meehl et al. (2007) reported a Greenland Ice Sheet contribution to global sea level of 1 to 12 cm by 2100.

Based on this collection of model studies, the direct SMB effect of expected warming in Greenland is likely to be a sea level rise of 5 to 10 cm by 2100, corresponding to 200 to 400 Gt/y loss of mass in average over the period to 2100. Within the range of anticipated climate change, ice volume losses in excess of 1 m of sea-level equivalent from the Greenland Ice Sheet require several centuries in all published modeling studies to date. The complete demise of the ice sheet requires 3000 years or more under most future climate change scenarios. The most severe climate warming simulated by Greve (2000), that is, 12°C over Greenland, precipitates a full collapse (and a 7 m sea level rise) in 1000 years. Predictions by Greve (2000) for more moderate warming scenarios of 3 and 6°C give a sea level rise of 0.72 m and 2.4 m after 1000 years. Contributions by 2100 are about 5% of this. Huybrechts and de Wolde (1999) found a similar rate of extreme ice sheet retreat in their most severe climate change scenario, $8 \times \text{CO}_2$, with an average rate of sea level rise of 60 cm per century and about 80% of the Greenland Ice Sheet melting within 1000 years under these conditions. Rates of ice loss increase non-linearly with time in these simulations, as elevation-climate feedbacks strengthen.

While the forecasts are reasonably well bounded for this century, models have a conservative bias for ice sheet response to climate change, due to missing processes in the glaciological models (see Section 8.3.2) and a number of missing climatic feedbacks. There is no sensitivity to changing conditions at the ocean interface in current models, that is, no capacity for outlet glacier acceleration.

Pfeffer et al. (2008) probed this by considering an extreme case where all of the marine-based outlet glaciers of the Greenland Ice Sheet double their discharge to the ocean. By taking the cross-sectional area of all marine outlet glaciers and




Figure 8.32. Modeled rates of sea level change as a function of changes in temperature and precipitation over Greenland based on a suite of AOGCM simulations for the 21st century. The rate of sea level rise is indicated by the colour, while the contour lines denote the standard deviation in an ensemble of AOGCM forecasts. The points indicate the results of decadal temperature and precipitation shifts in future simulations from the ensemble of models. Source: Gregory and Huybrechts (2006).

assuming a constant ice thickness at these flux gates, Pfeffer et al. (2008) calculated that a two-fold increase in outlet glacier velocity would contribute 9.3 cm to sea level rise by 2100. This is an extreme case: all of the outlet glaciers would need to double their velocity immediately and remain at this higher rate of flow for the rest of the century, without significant thinning. This, therefore, provides a plausible upper bound on ice dynamical discharge in Greenland.

Pfeffer et al. (2008) added this term to the sea level rise associated with SMB losses to give an upper bound for Greenland mass loss. However, the Greenland Ice Sheet's 'baseline state' and current estimates of future sea level rise from Greenland (e.g., Huybrechts and de Wolde, 1999; Greve, 2000; Gregory et al., 2004; Huybrechts et al., 2004) include contributions from dynamical ice losses (i.e., iceberg calving). Current models have negligible 21st century variability in this term and muted sensitivity to climatic forcing, relative to recent observations, but there is still a background level of ablation from this mechanism. Hence, it might be appropriate to consider only the extra iceberg discharge associated with a two-fold speed-up of marine outlet glaciers in placing an upper bound on Greenland's contribution to sea level rise. Using the fluxes calculated by Pfeffer et al. (2008), this gives 4.7 cm of sea level rise by 2100. If this is based, instead, on the estimated baseline ice discharge from Greenland in the early 1990s, 350 km³/y (Table 8.3), the additional discharge from a doubling of the ice flux would give a 21st century sea level contribution of 8.8 cm. This can be added to the expected SMB-driven losses of up to 10 cm to give an upper bound of 19 cm of sea level rise from the Greenland Ice Sheet by 2100 corresponding to an average mass loss of 800 Gt/y in the period to 2100. This is not a true upper bound. The value could be higher, if climate change during this century is more severe than expected in Greenland, or as a result of additional climate feedbacks that are lacking in the current models.

8.3.4. Summary and outlook

The complexities of climate and ice sheet models are such that much work is still needed to refine model physics, improve model resolution, and assimilate observational data to better constrain and test simulations of the meteorology, mass balance, and dynamics of the Greenland Ice Sheet. Great strides have been made in coupling of ice sheet and climate models in recent years. RCMs now offer the possibility of grid-matching and a full surface energy balance calculation, to help reduce uncertainties associated with climate downscaling and some of the simplistic assumptions in current parameterizations of SMB.

A number of climate forcings and ice sheet-climate processes are still missing in current models, particularly at the ice-ocean interface. This is pressing in light of evidence that oceanic forcing is responsible for some of the recent, rapid changes in the Greenland Ice Sheet mass balance and ice dynamics (Holland et al., 2008). Most fast-flow processes in ice sheets are not well represented in current models, and potential climatic excitation of fast flow, through either the ocean or atmosphere, has not been explored. This means that the parameter space for Greenland Ice Sheet response to climate change is not fully explored; models cannot give reliable bounds on this.

The kinematic approach of Pfeffer et al. (2008) probably

offers the best available upper bound on the ice-dynamical contributions to mass balance losses in Greenland. For a proper dynamical simulation of these effects, the ice-dynamical processes discussed in detail in Section 8.2.3 need to be captured by predictive models. This is important to improved estimation of the total ice sheet mass balance, given the potential for large-scale climate forcing of ice-dynamical ablation mechanisms. At present, ice sheet models are not sensitive to surface meltwater production or to ocean and sea-ice conditions, all of which have begun to change rapidly in the Arctic.

Further development of AOGCMs and regional equivalents is also needed. Little besides what has been reviewed here has been done to couple climate and ice dynamical models. Thus, more coupling experiments represent an obvious area of future work, particularly with respect to regional patterns of climate downscaling and atmospheric/mass balance feedbacks of changing ice sheet geometry.

Other climatic feedbacks on ice sheet mass balance are not fully explored, such as the impact of decreasing ice sheet albedo as the ablation zone of the ice sheet expands spatially and seasonally. Degree-day melt models typically use two melt factors, one for snow and one for ice, rather than the continuum of behavior that is evident in nature. The positive feedbacks of a wetter, lower-albedo snow surface may not be being captured in present model forecasts. More physically-based melt models (e.g., from energy balance calculations on high-resolution grids) will provide improved estimates of the threshold temperature at which the Greenland Ice Sheet switches into a state of negative SMB.

These limitations make it difficult to project the extent of sea level rise that can be expected from the Greenland Ice Sheet in this century and beyond. Current models suggest 5 to 10 cm by 2100, but conservative biases in the models mean that it may be in excess of this. If climate warming excites systematic, widespread acceleration of the outlet glaciers in Greenland, the ice sheet could contribute as much as 19 cm to global sea level rise this century. Extreme warming scenarios (e.g., 10 °C) are needed to extract more ice than this from Greenland by 2100, although long-term ice sheet losses may result from instabilities that are triggered in the coming decades.

The models are still in early stages of coupling and several key processes and feedbacks are absent or poorly parameterized, which compromises the ability of the models to simulate interannual variability in ice velocities (hence, ice discharge to the oceans), as well as some potentially important aspects of ice sheet sensitivity to climate forcing. Some of the key processes that need to be better understood and included in the models include:

- subglacial processes governing basal flow
- effects of surface meltwater on basal flow
- numerical representation of ice stream and outlet glacier dynamics
- oceanic influences on ice flow and ice-marginal ablation
- surface energy balance feedbacks as the ice sheet wanes (e.g., declining albedo).

These missing processes introduce a likely conservative bias in model studies to date, such that they may systematically underestimate Greenland Ice Sheet sensitivity to climate change. Recent observations and simplified (e.g., conceptual)

model studies indicate that increased ice discharge associated with a warmer climate could effectively double the ice sheet sensitivity to climate change, with ice dynamics contributing 5 to 9 cm to sea level rise by 2100. This is on top of the SMB-driven ice sheet losses of 5 to 10 cm, giving a total contribution to sea level rise of 10 to 19 cm.

8.4. Impacts caused by changes in the Greenland Ice Sheet

- The mass loss from the Greenland Ice Sheet will increase and cause a rise in sea level that will impact globally, especially the vast population living close to the coast.
- The increasing freshwater input to the fjords and ocean surrounding Greenland will change salinity and impact on the marine food web and thereby the fisheries.
- Freshwater input to the ocean will affect the thermohaline ocean circulation. But as the component from the Greenland Ice Sheet is less than 10% of the total freshwater input the effect of the increased melt is assumed to be small.

8.4.1. Ocean circulation

Freshwater from the Greenland Ice Sheet melt as well as iceberg calving into the sea have various effects on the waters of the Arctic region (i.e., Arctic Ocean with continental shelves, Nordic Seas, and Labrador Sea) as well as the World Ocean. The Greenland Ice Sheet runoff dilutes the marine surface water and reduces its salinity and density, thereby impacting global sea level rise and two types of ocean circulation: thermohaline circulation and estuarine circulation. All are important for the marine climate of the Arctic region although they are affected in different ways.

8.4.1.1. Sea level change

8.4.1.1.1. Global sea level change

The Greenland Ice Sheet represents, if entirely melted, a global average eustatic sea level rise of about 7 m. In a warmer climate with more precipitation, accumulation, ablation and ice discharge will increase but model studies suggest that the net balance of these factors will be toward a diminishing ice sheet (Gregory and Huybrechts, 2006). Depending on the future temperature evolution, the potential disappearance of the Greenland Ice Sheet or its transformation to a much reduced inland ice cap, will take of the order of millennia (Gregory et al., 2004).

The contribution to global sea level rise from the Greenland Ice Sheet has increased during the past decades (Cazenave et al., 2008) and global sea level has been observed to rise at a faster rate than projected by Meehl et al. (2007). Motivated by this apparent under-estimation of sea level rise from dynamical modeling, Rahmstorf (2007) suggested an alternative semi-empirical approach where a statistical model is fitted to historical time series of global sea level and temperature. By then driving the statistical model with temperature scenarios Rahmstorf obtained total global sea level changes of 0.5 to 1.4 m for the end of the 21st century; larger than by Meehl et al. (2007). This work has, however, been criticized by several authors (Holgate et al., 2007; Schmith et al., 2007; Rahmstorf,

2008; von Storch et al., 2008). An improved semi-empirical model by Grinsted et al. (2010) estimated the likely sea level rise to be in the range 0.7 to 1.6 m at the end of the 21st century.

8.4.1.1.2. Regional sea level change

The increased release of freshwater from the Greenland Ice Sheet will, together with the expected increase in net precipitation over the North Atlantic area, cause changes in the salinity and temperature distribution (Curry et al., 2003), which, through a dynamic response, will cause regional changes in sea surface height. This dynamic response can be either thermohaline in nature, such as weakening of the AMOC, or an adjustment of gyre circulations due to changes in the density distribution. Moving mass from the ice sheet to the ocean causes changes in the gravity field (Mitrovica et al., 2001; Milne et al., 2009). This has remained unnoticed to date, but causes noticeable regional differences in sea level rise. Diminishing the Greenland Ice Sheet is expected to produce the largest sea level increase in the South Atlantic and the North Pacific and a decrease in the North Atlantic and around Greenland. This does not take vertical isostatic land lift into account, which takes place on a longer time scale.

A quantitative assessment of the effect of freshwater release from the Greenland Ice Sheet does not exist at present. Landerer et al. (2007) analyzed a standard IPCC scenario run (i.e., without melting from the Greenland Ice Sheet) and discovered regional signals, most prominent a sea level increase of 0.3 m in the Arctic Ocean and a minor increase (i.e., up to 0.1 m) along the Greenland coast. In the center of the subpolar gyre, Landerer et al. (2007) found a decrease of the order of 0.1 m, which could be due either to changed density distribution or to changed wind forcing, or both.

8.4.1.2. North Atlantic circulation – deep convection and climate impact

Through thermohaline ventilation, the Arctic region is a significant source to the North Atlantic Deep Water as part of the global thermohaline circulation. Therefore, increased runoff from Greenland has the potential to affect the circulation of the Arctic region and the global ocean.

Off Greenland (Figure 8.33), the East Greenland Current flows southward along the shelf towards the Atlantic (Hofort et al., 2008). Together with the outflow through the Canadian Arctic Archipelago, this comprises a low-salinity surface outflow from the Arctic (Melling et al., 2008). The inflow, to compensate for the estuarine outflow, consists of warm and saline Atlantic water concentrated to the eastern part of the North Atlantic and which cannot be distinguished from the direct wind- and thermohaline-driven surface inflow to the Nordic Seas (Hansen and Østerhus, 2000). This inflow enters the Arctic in three distinct branches: a branch to the west of Iceland, a branch between Iceland and the Faroe Islands, and a branch between the Faroe Islands and Shetland (Østerhus et al., 2005; Hansen et al., 2008).

Through heat loss to the atmosphere, the inflow is cooled as it flows northward, and this increases its density. Brine rejection from freezing of seawater also has this effect whereas freshwater input decreases density. The overall effect is to separate the inflow into an upper low-density water mass and a sub-surface high-

density water mass that is then returned to the North Atlantic.

The low-density water mass is returned as surface outflow in the East Greenland Current and through the Canadian Arctic Archipelago, which also carries most of the Bering Strait inflow of Pacific water to the Arctic Ocean (Rudels, 1989). The high-density water mass returns to the North Atlantic through several current branches, termed ‘overflows’ (Saunders, 2001), and passes through a number of deep channels across the Greenland-Scotland Ridge.

In terms of volume transport, the overflows export roughly twice as much water to the North Atlantic as the surface outflows of the East Greenland Current and the Canadian Arctic Archipelago. The formation of overflow water by thermohaline ventilation involves two steps: density increase and sinking. For the density to increase substantially the water has to be in contact with the atmosphere and this occurs by heat loss in the western part of the Nordic Seas and in the Barents Sea (Simonsen and Haugan, 1996). The sinking may occur through open ocean convection (Marshall and Schott, 1999) in the Greenland Sea and Iceland Sea, but this is only one of the mechanisms (Hansen and Østerhus, 2000) and convection in the Greenland Sea is not likely to be the main source of overflow water (Eldevik et al., 2009).

The overflow water is cold, much of it at temperatures below 0 °C, and is relatively saline compared to other cold water masses in the ocean. Thus, it is one of the densest water masses found anywhere in the World Ocean but, immediately after

crossing the Greenland-Scotland Ridge, it mixes strongly with, and so entrains, ambient upper ocean water masses (Dickson and Brown, 1994; Østerhus et al., 2008). The resulting water mass is warmer and less dense, but also has a larger volume transport. Most of this water flows into the Labrador Sea where it contributes to the North Atlantic Deep Water together with the Labrador Sea Water formed locally by convection (Lazier, 1980; Yashayaev et al., 2008). North Atlantic Deep Water is thus from three sources: overflow water, Atlantic water entrained into the overflows, and Labrador Sea Water. Formation rates for some of these are debated (Haine et al., 2008), but there seems to be general agreement that they are of similar magnitudes.

North Atlantic Deep Water is carried south by the deep branch of the AMOC and is the main deep water source of the World Ocean, complemented by Antarctic Bottom Water formed by dense outflows from the Antarctic shelf regions. The AMOC is associated with heat transport on inter-hemispheric scales toward the ventilation areas where heat is released to the atmosphere. This transport of heat by the ocean is modest compared to the atmospheric heat transport (Trenberth and Caron, 2001) and its importance for climate has been challenged (Seager et al., 2002).

However, convincing evidence suggests that, through climate interactions, this ocean transport indeed plays a disproportionate role for fundamentals of the global climate (Rhines and Häkkinen, 2003; Rhines et al., 2008). This also finds support from tailored ‘what if’ climate model experiments,




Figure 8.33. Ocean currents in the North Atlantic. Source: Danish Meteorological Institute.

where artificial shutdown of the North Atlantic Deep Water production has been shown to strongly cool the regional climate of the Nordic Seas and Barents Sea but with cooling evident over the entire Northern Hemisphere (e.g., Vellinga and Wood, 2002; Sutton and Hodson, 2005). Apparently, this has occurred in other climatic periods, for example, during the deglaciation period where reduced thermohaline ventilation was likely to have been triggered by increased extreme freshwater supply from the melting glaciers to the ventilation areas (Tarasov and Peltier, 2005). Changes in the AMOC also have indirect impacts on the global climate. The formation of deep water and its subsequent spreading is crucial for maintaining not only the density but also the chemical structure and the biological conditions characterizing the World Ocean (Schmittner, 2005) with feedbacks also on atmospheric chemistry and climate.

A number of confounding factors, however, make quantifying the impacts of increasing runoff from the Greenland Ice Sheet difficult. First, runoff is not the only freshwater source in the Arctic region. In the present-day climate, total Greenland Ice Sheet runoff (0.018 Sverdrup¹; Dickson et al., 2007) is almost an order of magnitude smaller than the estimated freshwater (including sea ice) transport southward through Fram Strait (0.15 Sv; Carmack et al., 2008), which flows through the areas into which the Greenland Ice Sheet runoff is released. It is also much smaller than the freshwater component of the Canadian Arctic Archipelago outflow (Carmack et al., 2008).

Various changes in the freshwater cycle of high latitude lands and oceans have been reported for the period since the 1950s (Peterson et al., 2006). Changes have been widespread and perhaps dramatic in the case of the Great Salinity Anomaly of the 1970s but, by attribution, anomalous glacial melt has played a minor role, contributing only about 5% to the observed ocean freshwater storage in the North Atlantic and Arctic region. In the future, the Greenland Ice Sheet runoff may well, in relative terms, increase more rapidly than the other sources but even in the most extreme case, the projected peak rate of melting estimated from a coupled climate-ice sheet model (0.06 Sv; Ridley et al., 2005) remains considerably smaller than the contribution from other sources today (Dickson et al., 2007). In idealized anthropogenic climate change simulations, absolute changes in atmospheric moisture transport are also found to exceed changes in runoff (Mikolajewicz et al., 2007a; Vizcaíno et al., 2008), which tends to downplay the isolated role of the Greenland Ice Sheet runoff on ocean circulation.

Second, the effects of increased freshwater supply depend on other factors. The intensity of the estuarine circulation is determined mainly by the rate of mixing between freshwater and seawater thus depending primarily on stratification and winds (Stigebrandt, 2000). For the thermohaline ventilation, the amount of freshwater that can reach an area of deep ventilation is a crucial factor. Most of the Greenland Ice Sheet runoff should be able to reach the ventilation areas in the Labrador Sea, but only runoff from the east coast of Greenland, north of Denmark Strait, can directly affect the offshore regions of the Nordic Seas where overflow waters are produced.

In the present-day climate, even this runoff seems to affect these areas only weakly because most of it is carried south through Denmark Strait by the East Greenland Current

(Dickson et al., 2007; Holfort et al., 2008), depending on the wind conditions over the East Greenland Current (Stigebrandt, 2000), which may well change. Although part of the runoff from the ice sheet may initially bypass areas of ventilation, it is recirculated in the sub-polar North Atlantic and will, on decadal scales, dilute the entire sub-polar North Atlantic and spread to the Nordic Seas (Curry et al., 2003; Curry and Mauritzen, 2005; Peterson et al., 2006). The recent freshening has indeed been traced into the deep overflows from the Nordic Seas (Dickson et al., 2002).

In anthropogenic climate change projections, the effect on the AMOC of increased freshwater supply to the ventilation areas in response to an intensified atmospheric hydrological cycle (Cubasch et al., 2001) may also be partly or completely compensated for by increased salinity of the Atlantic inflow. With enhanced evaporation at low latitudes, the source waters in the sub-tropical North Atlantic are becoming more saline (Curry et al., 2003) and this effect has been shown to stabilize the AMOC (Latif et al., 2000). The pathways of subtropical waters toward the ventilation areas, however, are dependent on the circulation of the subpolar gyre (Hátún et al., 2005), which again depends on Labrador Sea convection (Häkkinen and Rhines, 2004). No such direct compensation, however, will be in effect considering an increased Greenland Ice Sheet runoff resulting from a negative mass balance of the ice sheet, or anomalous freshwater outflow from the Arctic Ocean due to retreating Arctic sea-ice cover.

Although these freshwater fluxes will certainly add to AMOC weakening under anthropogenic climate change, this effect, including changes due to intensification of the hydrological cycle, will possibly be masked by the direct effects of atmospheric warming on the AMOC. In a comparison of 11 different climate models, Gregory et al. (2005) found weakening of the AMOC in idealized global warming experiments to be induced mainly by changes in surface heat flux and to a lesser extent by changes in freshwater fluxes.

In the IPCC AR4, Working Group 1 reviewed the status of climate model projections for the AMOC and found it ‘very likely’ that the strength of the AMOC will decrease in the 21st century (Meehl et al., 2007). The working group did not expect the AMOC weakening to lead to cooling over Europe and considered an abrupt transition during the course of the 21st century to be ‘very unlikely’. However, none of the model studies above take the effects of ice sheets into account.

Very few studies exist where GCMs have been coupled to dynamic ice sheet models (Fichefet et al., 2003; Ridley et al., 2005; Winguth et al., 2005; Mikolajewicz et al., 2007a,b; Vizcaíno et al., 2008). It may also be argued that only in the recent study by Mikolajewicz et al. (2007a) was the coupling complete. This model alone features a realistic climate, allowing reasonable simulation of ice sheets. Nevertheless, the models yield similar meltwater input rates and most, although not all, reveal only a moderate effect of enhanced Greenland Ice Sheet runoff on the AMOC. Thus, it would be premature to conclude on the effects of the Greenland Ice Sheet runoff on the thermohaline circulation on the basis of these few studies.

Whereas fully coupled models will be required to convincingly project future melt rates of the Greenland Ice Sheet and project future global sea level rise, the freshwater impact on the AMOC by other and probably more dominating sources

¹ A Sverdrup = 1 Sv = 10⁶ m³/s.

may be studied independently. This understanding is crucial for assessing the stability of the AMOC under anthropogenic climate change where a large spread in projected weakening for the 21st century among available models (Gregory et al., 2005) indicates a significant model uncertainty. In particular, differences in the projected changes in the hydrological cycle explain differences in the projections of the AMOC (Cubasch et al., 2001; Vellinga et al., 2008). This is one of the key questions to be addressed in the FP7-funded research project THOR (ThermoHaline Overturning - at Risk?) initiated in 2008.

It has been debated whether the projected AMOC decrease has already been initiated. Bryden et al. (2005) suggested that the meridional overturning circulation decreased by 30% between 1950 and 2000 at 24 °N in the Atlantic Ocean with most of the decrease being due to declining overflows. This supports the suggestion of a similar, but smaller, decrease in the overflow transport through the Faroe Bank Channel (Hansen et al., 2001).

Direct measurements have demonstrated a high stability of this flow between 1995 and 2005 (Hansen and Østerhus, 2007) and Olsen et al. (2008) found no weakening of either this overflow branch or the total overflow transport from 1948 to 2005 in a study combining measurements with an ocean model. Concerns have also been raised about the methodology of the Bryden et al. (2005) study (Baehr et al., 2007; Cunningham et al., 2007; Wunsch, 2008).

Conversely, there is evidence in the Labrador Sea of a weakened convection since the mid-1990s, but the formation rate of Labrador Sea Water exhibits large variability (Haine et al., 2008) and attribution of this weakening to anthropogenic causes would be premature and, on the present observational basis (Peterson et al., 2006), it seems unlikely that enhanced Greenland Ice Sheet runoff has played a prominent role.

8.4.1.3. Sea ice

Sea-ice formation depends on the stability of the surface layer of the ocean. Changes to the surface layer incurred by increased meltwater runoff from the Greenland Ice Sheet in a warmer climate could therefore potentially influence sea-ice production.

8.4.1.3.1. Freshwater flux

An increased freshwater flux may lead to increased stability of the upper ocean, which could precondition greater sea-ice production. On the other hand, ice cover of the marginal seas around Greenland has reduced during the present global warming period (satellite data from the period 1978 to 2008). The total effect of higher annual mean air temperatures and increased freshwater flux is not well predicted.

In the Greenland Sea, the role of local sea-ice production and advection was shown to potentially precondition the ocean for deep convection (Visbeck et al., 1995; Toudal and Coon, 2001). Brine rejection during sea-ice formation destabilizes the ocean and advection of the ice out of the area removes excess freshwater. After a period of ice formation and advection, the density gradient will be eroded and further cooling can generate deeper convection. With sufficient cooling, this mechanism can remove excess freshwater from the surface of the Greenland Sea and counteract an increased freshwater flux from Greenland in relation to deep water formation. However, as the mechanism

is reliant on subsequent cooling during winter, it is not clear if it will prevail in a warmer climate.

Few examples of coupled global climate model predictions of the response of sea ice to an increased freshwater flux from the Greenland Ice Sheet have been published. Fichefet et al. (2003) showed indications of a possible feedback mechanism where a breakdown of the thermohaline circulation leads to a significant cooling over eastern Greenland and northern North Atlantic waters, amplified by the sea-ice albedo feedback related to an expansion of the sea-ice cover in the Greenland-Iceland-Norwegian seas. The cooling subsequently reduces the freshwater flux from Greenland.

Feedback of less ice on the state of ice shelves

The reduced summer ice cover at the Arctic Ocean margins (e.g., Greenland Sea and Barents Sea) exposes the coastline of these regions to the influence of ocean swells. This may cause increased coastal erosion but may also directly influence the stability of floating glaciers, such as Storstrømmen and 79-fjorden, in northeastern Greenland.

Reeh et al. (2001) studied the interaction between sea ice and glacier, in the case of the floating tongue of the 79-fjorden glacier, northeastern Greenland (79°30' N, 22° W). The authors used information from glaciological and geological studies, expedition reports, aerial photographs and satellite imagery to document the position of the glacier front and fast-ice conditions on millennial to decadal time scales. The study indicates that stability of the floating glacier margin is dependent on the presence of a protecting fast-ice cover in front of the glacier. In periods with a permanent fast-ice cover, no iceberg calving occurs, but after fast-ice break-up the glacier responds with a large ice discharge activity, whereby several years worth of accumulated glacier ice flux suddenly breaks away.

Climate-induced changes in sea-ice conditions in the Arctic Ocean with seasonal break-up of the nearshore fast ice could lead to the disintegration of floating glaciers. The present dominant mass loss by bottom melting would then be largely overtaken by grounding line calving of icebergs and the local influx of freshwater from north Greenland glaciers to the sea would be reduced and local iceberg production would increase.

8.4.1.4. Greenland coastal currents, including fjords, circulation and stratification

The ocean currents around Greenland are part of the cyclonic sub-polar gyre circulation of the North Atlantic and the Arctic region (Figure 8.33). The surface waters in southeastern and western Greenland are dominated by two very different water masses: warm and saline Irminger Water, a side branch of the North Atlantic Current, and cold and low-saline Polar Water originating from the Arctic Ocean.

These water masses meet in the northern Irminger Basin and in the Denmark Strait. The main branch of the Irminger Current turns west toward East Greenland where it meets the Polar Water, which is transported southward along East Greenland within the East Greenland Current. The strength of these two currents determines the hydrographic conditions around southeastern and West Greenland. The two water masses flow side by side forming large meanders at the front where intensive mixing takes place. Polar Water is found at the surface on the continental

shelf whereas Irminger Water is found over the continental slope and partly below the Polar Water on the deeper parts of the continental shelf. As they round Cape Farewell the Irminger Water subducts under the Polar Water.

Adjacent to the coast, the surface water is modified by runoff from Greenland whereby the stratification in the water column increases. During summer, this forms a freshwater baroclinic jet, named the East Greenland Coastal Current, which is only a few tens of kilometres wide but with maximum velocities exceeding 1 m/s (Bacon et al., 2002; Wilkinson and Bacon, 2005). The runoff originates from melting of the Greenland Ice Sheet as well as from precipitation. Kiilsholm et al. (2003) showed that by far the greatest value (i.e., precipitation minus evaporation) over Greenland is found in southeastern Greenland, which could be the main driver behind the East Greenland Coastal Current. If so, the presence of significant, baroclinic coastal currents is limited to southwestern Greenland waters, but this is still an open question, especially due to the lack of observations in northeastern Greenland waters.

The classic time series of temperature and salinity on top of Fylla Bank describes the observed hydrographic conditions off West Greenland. For the temperature curve, the most striking feature is the three cold periods centered around 1970, the early 1980s and the 1990s; all three related to atmospheric forcing (Buch et al., 2004). The cooling in the late 1960s was associated with a large pulse of freshwater that left the Arctic Ocean through Fram Strait and moved rapidly southward in the East Greenland Current and later northward in the West Greenland Current, and it was easily recognized in the Fylla Bank salinity. This event has been labeled the ‘Great Salinity Anomaly’ (GSA) (Dickson et al., 1988; Belkin et al., 1998), and Curry and Mauritzen (2005) estimated the freshwater flux to be about 0.07 Sv. This value is in agreement with model simulations preformed by Haak et al. (2003) and Olsen and Schmidt (2007).

Interestingly, the freshwater anomaly associated with the GSA is similar to the expected freshwater anomaly due to the forecast maximum melting of the Greenland Ice Sheet. In other words, the natural variability observed today in freshwater fluxes is similar to the expected additional contribution from the Greenland Ice Sheet. However, events similar to the GSA are expected in the future and more importantly, as noted by Vizcaíno et al. (2008), the atmospheric moisture transport is expected to increase by one order of magnitude more than the freshwater increase due to melting of the Greenland Ice Sheet.

In a future climate with increased runoff due to increased precipitation and melting of the Greenland Ice Sheet, the East Greenland Coastal Current would be expected to increase. In a study of climate changes in Greenland waters and surrounding seas, high-resolution regional models were applied to calculate a scenario of the climate for the period 1950 to 2050 (Stendel et al., 2007; Kliem et al., 2007). The regional models were used to downscale a global AOGCM.

The ocean model was forced by the GCM simulation at the lateral boundaries and by a regional climate atmospheric simulation at the surface. Runoff was not included due to melting of the ice sheet directly in the simulations. However, an indirect effect was included by restoring the surface salinity toward the surface salinity of the GCM. Still, Vizcaíno et al. (2008) found that the increase in freshwater flux from the

Greenland Ice Sheet is one order of magnitude smaller than the increase in the atmospheric moisture transport under anthropogenic greenhouse gas forcing.

The slight increase in temperature is due to a general atmospheric warming and not caused by the retreat of sea ice, as it is rarely present at Fylla Bank. Moreover, the simulations show a clear freshening at Fylla Bank that is most likely to be a result of the increased hydrological cycle. Note that the major salinity fluctuations are due to major GSA-like events. These natural variations are an order of magnitude higher than the general freshening.

8.4.1.4.1. Fjords

Deep fjords are characteristic elements of the Greenland coastline. They constitute a key element of the land-ocean interface as they connect the ice sheet to shelf waters around Greenland. In addition to tide, runoff and local winds are the main driving forces acting on the upper water masses in a fjord system (Svendsen et al., 2002). Frequently, there is a large climate gradient from the inner parts of the fjords to the outer parts. Also, meltwater from the Greenland Ice Sheet or rivers that drain into the inner parts of the fjords also causes a strong salinity gradient along the fjord axis. Typically, meltwater discharge takes place over a few months when temperatures exceed 0 °C and the discharge often occurs in pulses (Hasholt et al., 2008).

Where a glacier meets ocean water, mass is not just lost by the visually spectacular calving mechanisms. At ice shelves and floating tongues it is known from mass conservation considerations that sub-ice melting can occur at rates exceeding 10 m/y (Rignot and Jacobs, 2002; Rignot and Steffen, 2008). Also, Motyka et al. (2003) proposed a model of freshwater-driven fjord convection that brings in warm saline bottom water and transports cold fresh surface water out of the fjord. Recent observations of high water temperatures (3 to 10 °C) in the immediate vicinity of tidewater glaciers (Motyka and Truffer, 2007; Ritchie et al., 2008; Rysgaard et al., 2008) indicate that the ocean water around Greenland has a large heat content and a corresponding melting potential. Changes in the ocean have been observed to coincide with glacier changes in this system and elsewhere in Greenland (e.g., Howat et al., 2008; Holland et al., 2008).

Numerical simulations of the hydrographic conditions under a warmer climate scenario exist from a northeastern Greenland fjord (Young Sund, 74° N) that is connected to the Greenland Ice Sheet via river runoff. However, no large floating glaciers are present in the fjord system. In a warmer climate, the runoff from land would increase and this would locally change the circulation and influence the biological production (Rysgaard et al., 2003; Bendtsen et al., 2007). The sensitivity of Young Sund to changing runoff shows that in the case of no runoff, the mixed layer thickness is about 9 to 11 m during the summer period due to a weak pycnocline in the upper part of the water column (Figure 8.34).

At a runoff corresponding to only 50% of the normal runoff, the halocline is quickly established, and the mixed layer is about 0.7 to 1.6 m deeper in July and August than under present-day conditions where the mixed layer depth is about 4.0 to 5.2 m in July and August. At a runoff two times greater than in the




Figure 8.34. Model solutions from a sensitivity study of the relation between the mixed layer depth in the central part of Young Sound and the freshwater discharge (Qf) where the present-day discharge (corresponding to 1.0) is scaled between 0 and 8. Source: adapted from Bendtsen et al. (2007).

reference case, the mixed layer becomes 0.3 to 1.1 m shallower during the summer season than in the reference case, and in the extreme case when runoff is 8 times greater, mixed layer depth decreases to about 2.2 to 3.7 m during the summer season.

These sensitivity studies show the importance of the runoff for controlling the depth of the mixed layer. Without a runoff, the mixed layer is controlled solely by wind-induced mixing and buoyancy fluxes at the surface. Even at a moderate runoff of only 50% of the present level, a freshwater controlled mixed layer is established quite early by the end of June, and is only slightly deeper than in the reference case. At the other extreme, when runoff is large, the mixed layer depth is controlled by the strength of the surface forcing on the system, that is, wind and air temperature. Thus, the case with no runoff puts an upper limit on the mixed layer depth of about 11 m in the fjord during the summer season, and, correspondingly when runoff is 8 times the current level this puts a lower limit on the mixed layer depth of about 2 m.

In a future warmer climate scenario, the runoff period might increase significantly, and this would prolong the period in which surface conditions are controlled by freshwater discharge. However, this would not be expected to decrease the mixed layer depth significantly because the balance between runoff and atmospheric forcing is established within a few weeks.

Whereas mixed layer depth would change little due to increased freshwater runoff, it may alter significantly the transport of saltwater into the fjord from the Greenland Sea due to increased estuarine circulation. Hence, in a future climate scenario primary production is expected to increase due to a combination of increased nutrient import to the fjord and improved light availability as a result of reduced sea ice (Rysgaard et al., 1999, 2003; Bendtsen et al., 2007).

8.4.1.5. Summary

Melting of the Greenland Ice Sheet will affect the physical marine environment on different scales, ranging from local scales to global scales. The most visible effect, which is also the one that attracts most attention in public debate, is the rising water level of the world ocean. The latest assessment from the IPCC (2007) predicts the water level to rise between 0.18 and 0.59 m by 2100. This forecast has been questioned by several scientists, however, because recent data show that global warming seems to accelerate the melting of the Greenland Ice Sheet, which will lead to an increased rise in sea level. Estimates are still rather uncertain but recent studies project a sea level rise of 0.5 to 1.6 m by 2100.

More locally, the most visible effect of the melting ice sheet on the marine environment may be the changes in salinity conditions especially in the Greenland fjords and coastal waters. These may result in stronger gradients between the relatively low-saline surface water and the more saline water below; stronger gradients will have a great impact on primary production.

Although the increased runoff of meltwater from Greenland will reach the areas of deep water formation in the North Atlantic (i.e., the Greenland Sea and Labrador Sea), the freshwater volume from the Greenland Ice Sheet is around one order of magnitude less than that from other freshwater sources (i.e., the Arctic Ocean), and so it seems to be of minor importance to changes in the global thermohaline circulation although this has not yet been fully proven.

8.4.2. The marine environment and marine ecosystems

Almost no research has focused on the effects of increased melting of the Greenland Ice Sheet on marine ecology. Present knowledge on the impact on marine ecology due to climate change in the Arctic region is mainly related to the melting or reduction of sea ice although increased meltwater production will also influence the marine food web especially in the fjords.

8.4.2.1. Primary and secondary production

Overall, predictions of how the marine food web will respond to climate change are challenging due to the non-linear nature of ecosystems. Changes in the phytoplankton influence the copepods that, in turn, influence the phytoplankton through changes in grazing pressure. The same is true for the relationship between copepods and their predators, as well as for relationships further up the food chain. Thus, more research is needed before the essential details of the effects of climate change on marine organisms at the base of the food web can be understood and reliable predictions of ecosystem changes can be made.

In summary, climate-mediated changes of the Greenland Ice Sheet and subsequent changes in physical properties of the marine environment may have large consequences for the succession, composition and production at the base of Arctic marine food web. These changes will propagate up the food web and ultimately affect populations of fish, birds and marine mammals with major consequences for the structure, productivity and exploitation potential of the Greenland marine ecosystem.

8.4.2.2. Important economic species

Greenland waters are important fishing grounds, especially for the Northern shrimp (*Pandalus borealis*) and Greenland halibut (*Reinhardtius hippoglossoides*) fisheries that are essential to the economy of Greenland (Buch et al., 2004). Northern shrimp, currently the most important marine resource in Greenland, accounts for more than 70% of the total fisheries revenue. Catches have gradually increased to around 150 000 t/y (Kingsley, 2007), with 90–95% harvested off West Greenland. Northern shrimp in West and East Greenland waters are considered separate stocks.

Greenland fish stock composition and stock size is believed to change as an effect of climate change but there are, however, pending research projects to further study and quantify such changes. The effect of increased melting of the Greenland Ice Sheet, however, is believed to be of minor importance compared to the effects of increasing temperature especially on the offshore fishing grounds.

8.4.2.3. Marine apex predators in Greenland

Currently, there are only a few predictions of the direct effects of the melting of the Greenland Ice Sheet on marine apex predators. However, this large-scale event will have cascading effects on the primary productivity and associated species in the marine ecosystem; thus, many indirect effects can be expected.

8.4.2.4. Summary

Generally, climate change has immediate effects on the physical environment of the ocean and in Greenland waters these effects are increased by a strong inflow of freshwater from the melting Greenland Ice Sheet. These changes may have large consequences for succession, composition and production at the base of the Arctic marine food web. The changes will propagate to levels higher up the food web and will ultimately affect populations of fish, birds and marine mammals with major consequences for the structure, productivity and exploitation potential of the Greenland marine ecosystem.

To date, there has been almost no research on the effect of the melting Greenland Ice Sheet on marine ecology; therefore much of the present knowledge on the effects of climate change is related to the melting and reduction of sea ice. Research is therefore needed to quantify how the higher trophic levels of the food chain will be affected by changes in the physical marine environment around Greenland as a result of the increased melting of the Greenland Ice Sheet. To be able to make proper and scientifically based plans and decisions for the future, such research is extremely important to the Greenland society since its economy is highly dependent on the surrounding ocean.

8.5. Socio-economic and cultural aspects of changes in the Greenland Ice Sheet

- Impacts of climate change cannot be studied in isolation from other environmental and social and cultural changes.
- Until now, the observed effects of changes in the Greenland Ice Sheet due to global warming have caused only minor

impacts on society. The most marked change observed by the Greenland population has been the retreat of Jakobshavn Isbræ. This has caused an increase in tourism and has increased international attention on Greenland as an icon of global climate change.

- Planned hydroelectric power plants rely solely on runoff from the Greenland Ice Sheet and retreat of the ice sheet. To be economically viable they need to be based on reliable projections of the future evolution of the ice sheet.
- Retreat of the Greenland Ice Sheet will open areas for mining but will also result in longer walking distance in relation to hunting.

This chapter evaluates the possibility for projecting socio-economic and cultural impacts on Greenland society caused directly or indirectly by changes in the Greenland Ice Sheet. The chapter describes the modern Greenland society from a historical and contemporary perspective and introduces a number of specific cases that illustrate the propensity for change in a society that is derived from the Inuit culture; a culture that has survived over a millennium of climate change and external cultural influences.

It is essential to emphasize that impacts of climate change cannot be studied in isolation from other environmental and social and cultural changes. History shows that Arctic societies, like Greenland, have always changed and have always demonstrated a great ability to adapt to change. The implications of climate change have been the strengthening of ongoing socio-economic changes, and have contributed to outlining possible development paths. On the other hand, socio-economic and cultural changes have been reflecting a more or less pragmatic approach both to changes in the environment (including climate change) and the political reality.

8.5.1. History of change and contemporary socio-economic and cultural trends

The shift from an economy based on marine mammals to one based on fisheries has had profound consequences on society, first of all through the sedentarization process. The shift from a cod- to a shrimp-based economy furthermore consolidated an already ongoing process of concentration and centralization, but did not totally restructure the organization of the communities. The present-day diversification both of renewable resource exploitation and the economy in general may contribute to a partial reversal of the former concentration policy by making some of the settlements located near new resources and new economic opportunities (e.g., tourism) a potentially more active part of the economy (Rasmussen and Hamilton, 2001; Hamilton et al., 2003).

Although Greenland has considerable raw material deposits, commercial exploitation has been limited by adverse natural conditions and difficult logistics. Cryolite, coal, copper, marble, zinc, lead and silver as well as gold, olivine, and rubies have all been mined – and the latter three recently extracted. International interest in exploration for minerals and hydrocarbons is increasing and some deposits may prove of economic interest in the future not least because of increasing accessibility due to changes in the Greenland Ice Sheet.

Hydroelectric power is a new potential resource, not for

energy export but for domestic consumption and for energy intensive activities such as aluminum production. It is important to note that hydroelectric power is based entirely on water basins supplied by meltwater from the Greenland Ice Sheet.

8.5.2. Implications of changes

The new expectations for large-scale mineral and energy resource production as well as the dependence on fisheries and hunting activities are influenced by changes in climate and associated changes in the Greenland Ice Sheet and sea-ice conditions. Renewable resources are affected through their interactions with the environment, while non-renewable resources are affected by changes in accessibility and transportation.

The smaller settlements will experience the immediate effects of these changes because renewable resources are still of significance to them and because access to resources and to settlements will be altered by changes in accessibility, abundance and geographic distribution of these resources, as well as by changes in their economic importance (Poppel, 2007). Tourism has become an alternative source of income for many local communities, enabling a positive interaction between new economic opportunities and traditional activities that are less affected by change than exploitation.

At a longer perspective, Greenland's economy is shifting toward increased dependency on non-renewable resources and in so doing will be highly affected by the ongoing changes, including those affecting access to resources and transportation. The decisive force will be the population's ability to adapt to the changes and to continue to improve the level of education (Hamilton and Seyfrit, 1993; Paldam, 1994; Rasmussen, 1997, 1998, 2002; Winther, 1999, 2001; Zelarney and Ciarlo, 2000; Duhaime et al., 2001; Hansen, 2003; Nellemann and Vistnes, 2003).

8.5.3. Influences

8.5.3.1. Accessibility and impact on communities

Changing ice conditions, both on land and at sea, are important factors influencing everyday life in most communities in Greenland, mostly by determining the accessibility of the water bodies. Access to the sea, and sea transport to and within Greenland, are determinant factors for hunting, fishing, exchange of goods and tourism, which is becoming increasingly important for many communities.

Hunting terrestrial mammals is contributing both to subsistence and informal economic activities of many Greenlanders (Dahl, 2000; Poppel and Kruse, 2009). Muskox (*Ovibos moschatus*) and caribou / wild reindeer (*Rangifer tarandus*) are hunted by licensed commercial hunters and by sports hunters in the autumn, when as much as a fifth of the population goes hunting. Changes in the position of the Greenland Ice Sheet margin may affect hunting activities by changing the routes of rivers draining meltwater from the ice, and in conjunction with rising temperatures may affect the migration patterns of the game. In cold weather, the animals move toward the coast, where they become more accessible to hunters, while in warmer weather, the animals move toward cooler conditions closer to the ice margin in order to reduce insect harassment. As a result, the walking distance of the hunters to the animals becomes increasingly difficult to cope

with, first while searching for the animals, and then especially when the meat is carried on the shoulders back to the boats anchored along the coast.

8.5.3.2. Possible consequences for new activities

Reduction of glaciers, ice sheet and sea ice in and around Greenland will increase accessibility to new areas with the potential for commercial exploitation of minerals and energy resources. A significant side effect to the retreat of the ice sheet margin will be the increased volume of meltwater that can be harnessed for producing hydroelectricity. This potential is already included in the new economic strategies for Greenland. Over the past 50 years, the hydroelectric power perspectives in Greenland have been mapped and evaluated as a potential contribution to the development of the national economy. The hydroelectric power exploitation has already emerged in the form of three hydropower plants: A 30 MW plant near Nuuk, a 1.2 MW plant in Tasiilaq, East Greenland, and a 7.2 MW plant near Qaqortoq, South Greenland. A 15 MW hydropower plant near Sisimiut, West Greenland, is under construction and will become operational in 2010.

Several other hydropower plants are in the planning process, now aiming at providing power to new economic activities connected to energy intensive large-scale raw material processing. The first project is the supply of energy to an aluminum production plant currently planned at Maniitsoq, West Greenland. Even though Greenland does not have the ore resources needed for aluminum production, import of ore (i.e., bauxite) from Australia or South America to Greenland could be a viable economic activity given the access to large and continuing amounts of meltwater from the Greenland Ice Sheet and the derived hydroelectricity.

A key question, however, is the stability of the water supply to the new power plants as the ice sheet margin retreats due to melting. Increased amounts of silt and sand in the meltwater may fill dammed lakes and affect the viability of the dams, eventually requiring additional reconstruction in order to maintain the water flow needed. Or worse, the bedrock topography exposed by the retreating ice may cause new meltwater drainage patterns, leading to a partial or complete drying out of the water supply to the hydropower plants (Anon, 1994; Udvalget om socioøkonomiske virkninger af olie- og gasudvinding samt mineralindustri, 1997; Rasmussen, 1997, 2005; Keddeman, 1998; Storey and Hamilton, 2003).

8.5.4. The Ilulissat case

The Jakobshavn Isbræ (i.e., the Ilulissat Glacier) at the head of the Ilulissat ice fjord is one of the world's fastest moving glaciers producing more than 10% of the total discharge of icebergs from the ice sheet (Figure 8.35). During the culmination of the last Ice Age 21 000 years ago, an ice sheet that reached out onto the margin of the continental shelf covered the present-day ice-free land bordering the Greenland Ice Sheet.

After the end of the Ice Age, the melt-back of the ice started about 11 700 years ago and, during a warm climatic period 8000 years ago, the ice rapidly regressed causing the glacier front to retreat inland to a position more than 50 km east of the present grounding line. With the onset of the Little Ice Age, the glacier front again advanced, and in 1851, a maximum extension was recorded in the middle of the ice fjord close to the former Inuit settlement Qajaa. Following this advance, the ice front stabilized

and a slow regression prevailed until the front suddenly collapsed in 2002/2003 causing the floating ice tongue to withdraw more than 15 km eastward in just a few years. This rapid withdrawal ceased in 2007, when the ice front reached the grounding line.

8.5.4.1. Inuit settlements, cultural changes and role of the Ilulissat ice fjord

The glacier and the ice fjord have had an immense impact on the population of the region during the history of human occupation. The glacier produces a large amount of nutrient-rich meltwater that facilitates the primary production in the fjord. The constant input of nutrients thus forms the basis for a rich fauna in the fjord, which has provided excellent hunting and fishing conditions for people inhabiting Disko Bay through the ages. Prehistoric hunting areas and settlements were established and abandoned as the location of the glacier front changed. In this way, the Ilulissat area illustrates the interplay between an ever-changing glacier environment and the development of human occupation.

Many archaeological findings testify to the long history of settlement in the Ilulissat ice fjord region, where hunting and fishing have always been the basis for life. The Saqqaq people reached West Greenland from Alaska 4500 years ago and settled in the Ilulissat area where they lived for 1500 years before they disappeared. West Greenland was then uninhabited until a new wave of paleo-eskimo settlers, the Dorset people, arrived 2800 years ago. They occupied the region for 800 years before they disappeared leaving the Ilulissat region and Greenland uninhabited for the next 1000 years. By 1200 AD, people of the Thule culture settled in the region and established two flourishing communities, Sermermiut and Qajaa, along the ice fjord. These settlements are among the largest prehistoric Inuit

settlements discovered in Greenland and, together with the dense pattern of smaller settlements in the area, indicate that the living resources around the ice fjord were rich, stable and plentiful over long periods of time (Grønnow and Meldgaard, 1988).

8.5.4.2. The Ilulissat ice fjord and present-day socio-economic effects

In 1741, the Danish colony of Jakobshavn (today Ilulissat) was established and this led to the depopulation of the rich Sermermiut settlement around 1850. Today, Ilulissat is the third-largest town in Greenland with a population of more than 4000. Half of Greenland's coastal fisheries are now centered here and the town is also home to one of the country's largest fish-processing factories. Greenland halibut are plentiful throughout the fjord system and are subject to fishing based on a quota system. Long-line fishing for Greenland halibut from the sea ice in the Ice Fjord has been an important part of the fishing tradition through centuries and it is still taking place.

The abundance of resources and the adaptability of the traditional culture to the changing conditions of the glacier and winter sea ice have been crucial to the prosperity of the social and economic life of the region. Although the remarkable present changes in the ice will constitute new challenges to economic and social activities in the region, the conditions may now be different, less predictable and more challenging than before: Icebergs are smaller and the immense discharge by the glacier in combination with a rise in sea temperature, has caused a considerable reduction in sea-ice cover during winter.

This may imply profound changes for the production of nutrients – the basis for biological life in the region – and may lead to smaller stocks of Greenland halibut and northern shrimp. These species are fundamental, not only to human harvesting,




Figure 8.35. Location of Jakobshavn Isbræ and adjacent region. Place names: Ilulissat (town of Ilulissat; formerly named Jakobshavn); Kangia (the ice fjord proper, white because of tightly packed floating glacial ice and stranded icebergs); Sermeq Kujalleq (Jakobshavn Isbræ; also known as Ilulissat Glacier). Copyright by Geological Survey of Denmark and Greenland (GEUS).

but also to the seals and whales that form a significant part of the daily food supply for humans and dogs. Also, the distribution of seabird species may be affected. Other species may enter the region offering new and potentially prosperous options for economic activities. Such challenges will be met as before.

The adaptations of today are, however, far more complicated. Modern and economically viable harvest of renewable resources is highly industrialized, and to establish new production will be costly, requiring national initiatives as well as international involvement and regulations applied to managing, accessibility and rights. The local capacity for adaptation will be met by implications of today's global interaction. Changes in sea-ice cover, especially a reduction in winter sea-ice extent and thickness will inevitably alter marine transport conditions. Reduced sea ice may offer new transportation routes and prolonged navigation seasons, but will also increase marine access to natural resources and, accordingly, the potential for disturbance and for more efficient fisheries. Although the changes in sea ice may lead to significant changes in the socio-economic life of the region, it is still premature to state the nature of these socio-economic changes. The unpredictability of climate change and its local implications make planning, decision-making and management even more challenging. In spite of its richness, Arctic nature is vulnerable and poor management may lead to serious and irretrievable damage.

8.5.4.3. **The Ilulissat ice fjord and its impact on science, politics and tourism**

The Ilulissat ice fjord and its glacier is one of the world's best-studied glaciers with the longest observational record. The ice fjord has attracted many scientists through the centuries, the first being H.J. Rink who studied and described the glacier and the Greenland Ice Sheet in the mid-19th century. The studies were instrumental in formulating the important theory of the Quaternary glaciations. Today, the ice fjord is still the subject of detailed international research because of its exceptional manifestation of changes.

The Ilulissat ice fjord was nominated a UNESCO World Heritage site in 2004. The World Heritage List uses the name 'Ilulissat Icefjord' for the entire world heritage site, which includes land areas, the glacier front and parts of the Greenland Ice Sheet adjacent to the ice fjord, recognizing the uniqueness of the area and the extensive interplay between nature and culture.

By entering this prestigious list, tourism has virtually exploded in the ice fjord region. This has made Ilulissat Greenland's leading tourist town and the area now hosts more than 50% of the total number of tourists visiting Greenland. Thus, the ice fjord is by far the main attraction and cruise ships arrive in increasing numbers during the summer to let their passengers visit the fjord.

It is not just tourists that are congregating in the area. The Ilulissat ice fjord has also attracted a large number of politicians from around the world who wish to experience firsthand the global climate change as witnessed here. The ice fjord has now entered political discussions in a way that has never been seen for any part of Greenland before (Mikkelsen and Ingerslev, 2002).

8.5.5. **Conclusions**

Both local and global effects of the ongoing changes in Earth's climate will inevitably affect Greenland and its population. This chapter has attempted to assess the extent to which changes in the Greenland Ice Sheet will be a major factor in shaping the future society of Greenland. The response of Greenland society to past changes in climate has also been reported and has compared these changes to the effects of societal dynamics. The history of the Thule culture, which gradually transformed into the present-day society in Greenland, has been one of constant adaptation to changes in climate and increased interaction with European culture.

Until now, the observed effects of changes in the Greenland Ice Sheet due to global warming have caused only minor impacts on society. The most marked change observed by the Greenland population has been the retreat of Jakobshavn Isbræ. This has caused an increase in tourism and has increased international attention on Greenland as an icon of global climate change.

In the coming years, changes in drainage patterns around the Greenland Ice Sheet may affect coastal waters and thereby cause changes in the distribution of marine fish stocks and game species. Future changes in drainage patterns may also be a major concern for large infrastructure investments with decadal to centennial life spans, such as hydroelectric power plants and transmission lines, roads, airports and seaports. This chapter has not considered effects from changes in permafrost, although these may have considerable economic implications; the issue of permafrost is considered as separate from that of the ice sheet. Based on the historic observations and the strong drive for change in Greenland society today, it is likely that the consequences of changes in the Greenland Ice Sheet will be minor compared to socio-economic, cultural and demographic influences generated within the Greenlandic and international societies.

8.6. **Major knowledge gaps and recommendations**

8.6.1. **Introduction**

New research results from the Greenland Ice Sheet often lead to the identification of new gaps in knowledge, although they may become more specific over time (see Table 8.6). For example, research projects initiated under the International Polar Year 2007/2008 should eventually lead to the identification of new gaps in knowledge or to changes in the existing gaps in knowledge.

8.6.1.1. **Assessment of the impacts**

Earlier assessments identified some of the major gaps that are currently being addressed. The Arctic Climate Impact Assessment (ACIA, 2005) focused on improving projections of future changes and identified several major gaps in knowledge that are also valid for the Greenland Ice Sheet:

- a need to improve understanding of albedo changes and feedback mechanisms
- the need for studies of outlet glacier dynamics with an emphasis on their potential for triggering persistent and rapid thinning
- a need for improving ice dynamic models for determining

the long-term response of the ice sheet to past climate change

- a need for improving parameterization and verification of internal accumulation models
- a need to improve understanding of the relationships between climate change, meltwater penetration to the bed, and changes in iceberg production.

Uncertainty in scenarios concerning how glaciers, ice caps and ice sheets contribute to sea level rise over decadal to centennial time scales needs to be reduced. This requires an assessment of the Greenland Ice Sheet and its stability and vulnerability to climate change, including sudden and potentially irreversible climate change. The Climate and Cryosphere Project (CliC), established in March 2000 to stimulate, support, and coordinate research into the processes by which the cryosphere interacts with the rest of the climate system, recommends that an insight is needed into the highly non-linear links between the various components of the cryosphere and their likelihood for producing significant global change. CliC recommends that the long-term ice sheet monitoring system is improved in order to make realistic representations (modeled as well as observational) of spatial and temporal variability in the surface mass budget in areas sensitive

to sea level change (Climate and Cryosphere Project, 2007).

The IPCC's Fourth Assessment Report (IPCC, 2007) stated that realistic scenarios of the Greenland Ice Sheet SMB require a resolution exceeding that of the current AOGCMs used for long-term climate experiments. Present climate models do not generally include a representation of the refreezing of surface meltwater. All models predict an increase in snow accumulation, but there is much uncertainty in its size. In projections for Greenland, an increase in ablation is important but uncertain, being particularly sensitive to temperature change around the margins. The main uncertainty is the degree to which outlet glaciers having a marine terminus respond to climate change. Further accelerations in ice flow, of the kind recently observed in some Greenland outlet glaciers (and in West Antarctic ice streams), could increase the ice sheet loss of mass substantially, but quantitative projections cannot be made with confidence.

8.6.1.2. Summary of earlier assessments

The research needs presented in the ACIA, CliC and IPCC assessments of the Greenland Ice Sheet vary in their degree of detail, but all focus on the importance of making more precise scenarios and filling gaps in knowledge. There is a common

Table 8.6. Major gaps in knowledge and recommendations.

Major gaps in knowledge	Recommendations
Large variability between presently used SMB models	Targeted in situ SMB data with which to calibrate/validate models
Incomplete understanding of SMB processes	Systematic studies focused on improvement in process understanding
Large spatial variability in SMB at the ice sheet margin	Better sub-grid scale quantification of the key processes; refreezing, albedo and blowing snow
Large error in determination of surface annual accumulation	Improved determination of snow densification
Discrepancy in estimating the mass change from satellite gravity measurements	Establish a community wide recognition on which processing method provides the most reliable method for tracing mass changes
Incomplete estimate of the mass loss from marine terminating outlets	More systematic mapping of ice thicknesses from outlet glaciers
Incomplete determination of the annual cycle in SMB from satellites	Sampling sufficiently frequent to capture the annual cycle in accumulation, melt and iceflow
Lack of ice discharge determination from ice streams and narrow outlets	Development of high resolution sampling methods from satellites to capture basin scale changes
Large seasonal as well as interannual variability in marginal ice fluxes	Improved theoretical understanding of the basal hydrology and its impact on ice flow
Basic understanding of coupling between ocean and marine based fronts	Theoretical understanding of the calving and basal melting at marine margins where changes occur
Lack of thickness determination around highly dynamic outlets	Develop methods to retrieve ice thicknesses at heavily crevassed margins
Incomplete understanding of flow properties deepest in the ice sheet	Determination and validation of the thickness of the basal temperate layer as well as deep ice temperatures
Incomplete cryospheric representation and determination in climate models	Validate climate models more systematic with observations of surface climate and mass balance of the ice sheet
Lack of full coupling between surface dynamics and the atmosphere	More accurate incorporation of surface albedo and snow microphysics in climate models
Major dynamical features like ice streams lack representation in ice sheet scale models	Better model resolution as well as process understanding leading to well parameterized models
Several-fold changes in velocity variations at marine based outlet glaciers	More complete determination of process leading to improved parameterizations of basal and marginal (ocean) linked process

agreement, that improved understanding of processes is needed in order to determine meltwater runoff more precisely. Also, the rapid increase in ice discharge from the outlet glaciers observed over the past decade calls for a better understanding of processes as well as a better formulation of theory before models quantifying the observed increase in ice flux can be developed. The three assessments all call for better monitoring capabilities and a more precise determination of present state of balance in the Greenland Ice Sheet before more reliable scenarios can be made.

8.6.2. Gaps in knowledge of surface mass balance

Significant differences exist between different estimates of the components of the SMB derived from numerical modeling and downscaling of climate re-analysis data. For example, there are important differences in distribution and total accumulation in the ‘wet’ southeastern Greenland. The differences between model estimates can be as large as the net SMB for a given year and the standard deviation of the differences is of the order of 100 Gt. Although values for total runoff may agree between models, the individual terms included in the calculations of total runoff vary much more widely, particularly when comparing melt and refreezing. Total differences are of the same order of magnitude as the inferred increase in mass loss due to changes in ice dynamics over the past decade (Rignot and Kanagaratnam, 2006). The differences suggest that mass budget calculations are seriously hindered by uncertainties in SMB.

Direct observations of increasing surface elevation in the regions above 2000 m are not confirmed by direct observed accumulation changes due to very high variability in the records. RCM reconstructions of precipitation do not predict increased values.

Uncertainties in SMB originate from a range of sources related both to lack of *in situ* data and incomplete process understanding. To reduce uncertainties to a level useful for mass budget calculations and reliable predictions will require concerted effort. Especially, (i) to collect more targeted *in situ* data to calibrate and validate models, (ii) to improve process understanding, and (iii) to model key processes such as refreezing, surface albedo, blowing snow and sub-grid scale effects. Sub-grid scale effects are particularly significant in coastal regions due to higher surface relief, which makes ablation observation uncertainties difficult to incorporate into SMB model validation. The most important parameters for controlling runoff in SMB modeling, however, are surface albedo and meltwater refreezing.

8.6.3. Gaps in knowledge of net balance or components thereof

At present, the best estimate of the mass of the Greenland Ice Sheet is probably provided by GRACE (see Section 8.2.4.2.3). However, different processing methods result in different results. One method of averaging the total mass of the Greenland Ice Sheet over 30-day periods and calculating seasonal loss (Velicogna and Wahr, 2006) provides a mass loss of 211 Gt/y, while another uses different processing algorithms for analyzing the distance between the two satellites (Luthcke et al., 2006); this second approach provides a divergent mass loss of 154 Gt for 2007 (Witze, 2008). Such discrepancies reflect

ongoing discussion on which method is most valid for detecting mass changes in the Greenland Ice Sheet using GRACE and the newer publications seem to have a better agreement of results.

Measuring volume change by altimetric methods such as laser (IceSat) or by radar (CryoSat) provides another tool for detecting changes in mass balance. However, connecting volume change to mass changes requires insight into densification processes of the surface snow and firn, which also has a strong seasonal dependence when the surface temperature reaches the melting point. Moreover, it remains difficult to produce a measuring accuracy any better than a few tens of centimetres, and this also renders it impossible to capture the seasonality of the parameters.

Satellite radar techniques measuring ice displacements and ice fluxes near calving glacier fronts are unique in providing a means for detecting iceberg production when the ice thickness is known. However, the lack of measured ice thicknesses from all outlet glaciers and the difficulty of measuring ice movement in the interior of the Greenland Ice Sheet constrain this technique.

The various techniques used to estimate the state of balance of the Greenland Ice Sheet differ in their methodology for detecting changes in specific components of the system; which means that they do not return results that are mutually compatible. Closing the gaps between the results for different techniques will make an important contribution toward a more consistent understanding of change in the ice sheet. Filling these gaps in knowledge will require common or compatible temporal and spatial sampling as well as an understanding of the annual cycles in mass balance, including its most important parameters: Accumulation, melt, runoff, and ice flow. Temporal sampling will need to be frequent enough to capture the annual cycle, or designed to mitigate the effect of interannual variations in this cycle on annual estimates.

Spatial sampling capturing variation at a drainage-basin scale would allow for a more direct comparison of changes in discharge and measures of ice sheet mass or volume. Improved sampling of surface height with new satellite missions may provide altimetric determinations that more faithfully reflect the impact of annual cycles on surface height. However, in order to secure significant progress in understanding densification processes, observation and modeling of the surface snow are also required.

8.6.4. Gaps in knowledge of ice dynamics

A better understanding of basal boundary conditions (i.e., sliding laws) is needed. This involves a more precise understanding of the mechanisms of basal motion in order to derive good parameterization, which accounts for seasonal and longer-term variability. An improved understanding of basal boundary conditions is inherently linked to an understanding of subglacial hydrology, which is assumed to drive the present speed-up of calving outlets. For instance, subglacial hydrology and the complex connection between surface hydrology (supraglacial lake drainage) and the bed are integral to basal flow, which can dominate ice flux near the margin. Modeling the ice sheet hydrology, however, is still in an early stage of development and has not yet been coupled with ice dynamics.

Concerning the ice-ocean interface, gaps in knowledge are mainly related to the assessment of melting rates under floating glacier tongues, where the ocean and heat circulation in combination with freshwater from melting ice drive the circulation and impact on the calving front (Motyka et al., 2003).

Generally, iceberg calving and basal melting at marine margins are difficult to measure and to simulate, and these processes are absent or overly simplified in current ice sheet models.

Observational gaps mainly relate to determining ice thickness at heavily crevassed outlet glaciers, due to difficulties retrieving radar signals in these regions. Also, ice temperatures and, in particular, thickness of the basal temperate layer are not well known, which in combination with ice fabric (Lüthi et al., 2002) show a strong dependence on ice deformation rates and hence dynamics of the outlets.

8.6.5. Gaps in knowledge of ice sheet and climate modeling

Models of meteorological processes, ice sheet mass balance, and ice sheet dynamics are constantly improving, but there are still many uncertainties associated with simulating the Greenland Ice Sheet and its likely response to climate change.

8.6.5.1. Climate models

Many climate models do not resolve the steep topography of the Greenland Ice Sheet margins very well, limiting model skill in simulating orographic precipitation and ice sheet ablation in this zone. High-resolution meteorological models such as PMM5 (e.g., Box et al., 2006) overcome this problem, but there are still outstanding issues with regard to temperature biases, simulation of mass balance processes such as sublimation and boundary layer winds, and the large-scale boundary conditions for regional climate modeling in future climate-change scenarios.

The dominant precipitation and ablation processes can also be event-driven in Greenland (i.e., resulting from a small number of extreme synoptic weather events), and these processes are well captured in simulations that are forced by historical (i.e., re-analyzed) climatology but do not necessarily arise in climate model simulations strong in predictions of the mean state; and they do not always represent the full range of weather variability.

Probably the most important boundary conditions for climate model simulations of the Greenland Ice Sheet are the surface properties (i.e., the physical representation of snow in the models). The inherent instability of snow crystals on the ground, the ever changing meteorological conditions, and the feedback between snow and atmosphere via snow albedo makes the snow-atmosphere coupling an important and highly dynamic one. New progress in snow physics theory and parameterizations needs to be incorporated into climate models.

8.6.5.2. Glaciological models

Ice sheet models now operate at resolutions of 5 to 20 km for the Greenland Ice Sheet, representing the overall ice sheet geometry quite well but still not capturing details of ice margin positions or some of the major fjords and outlet glaciers. This means that it is still difficult to compare model simulations with geological reconstructions of recent (i.e., 20th century) ice sheet changes. In addition, it is difficult to compare modeled ice discharge with observations, with the more distributed (i.e., less channelized) ice flux in the model. Major ice dynamical features such as the glaciers at Ilulissat and Storstrømmen (also known

as the Northeast Greenland Ice Stream) are known to account for a large percentage of ice discharge from the Greenland Ice Sheet, but these features are generally absent in ice sheet models. This is partly an issue of model resolution and partly an issue of complex dynamical processes that are presently too poorly understood to be well parameterized in models.

Ice sheet models are presently insensitive to ocean forcing, in contrast with recent observations of significant (several-fold) velocity variations in marine-based outlet glaciers, most likely to have been triggered by ice-ocean interactions and thinning at the grounding line. Models still cannot simulate this interannual flow variability, so it is unclear whether they are able to provide a credible estimate of the response time of ice sheet change to atmospheric or oceanic forcing.

8.6.6. Perspectives

During the 20th century, the mass discharge from the Greenland Ice Sheet was almost equally divided between meltwater runoff and iceberg discharge (Reeh, 1994) – making the two terms equally important. The magnitude of the present-day balance is uncertain due to lack of coherence between the different estimates relying on different methods. Closing the gaps between the results is a prerequisite for reliable estimates of the present balance. Furthermore, a firm knowledge about the present balance is needed in order to generate reliable future scenarios.

Making specific recommendations on research needs to close the gaps in knowledge requires detailed insight into the problems. However, detailed insight is still lacking for many of the major knowledge gaps, such as the processes underlying increased ice discharge and meltwater refreezing. Instead of reducing uncertainty about changes in the mass balance of the Greenland Ice Sheet, the new observational methods from space have revealed to the research community the incomplete understanding of the fundamental dynamics of calving glaciers. This lack of understanding may explain why gaps in earlier assessments are still unresolved in the present-day assessment of the Greenland Ice Sheet. Closing such gaps in knowledge, where there is a lack of fundamental understanding of the processes, demands the development of theory and methodology to validate the theory against field measurements.

Most changes appear in the marginal regions of the Greenland Ice Sheet where data coverage is most scarce due to logistical access constraints. Moreover, thin ice in these regions, combined with a complex terrain, results in highly variable ice dynamics, melt rates, and accumulation patterns. This calls for high spatial resolution modeling in combination with enough *in situ* measurements to capture adequate detail and to gain sufficient understanding of the present thinning process.

New satellites have triggered a quantum leap in surface observations of the Greenland Ice Sheet. However, *in situ* measurements are still progressing at a slow pace due to resource-demanding fieldwork. The development of new, and less labor-intensive, measuring techniques could potentially advance the process understanding over larger areas. A combined effort in advancing process theory, field methods and coverage as well as modeling efforts could facilitate major advances in understanding the present balance of the Greenland Ice Sheet and, hence, help create less uncertain future scenarios.

References

- Abdalati, W., 2001. Special section: Mass balance of the Greenland ice sheet (PARCA). *Journal of Geophysical Research-Atmospheres*, 106:33689–33689.
- Abdalati, W. and K. Steffen, 2001. Greenland ice sheet melt extent: 1979–1999. *Journal of Geophysical Research-Atmospheres*, 106:33983–33988.
- Abdalati, W., W. Krabill, E. Frederick, S. Manizade, C. Martin, J. Sonntag, R. Swift, R. Thomas, W. Wright and J. Yungel, 2001. Outlet glacier and margin elevation changes: Near-coastal thinning of the Greenland ice sheet. *Journal of Geophysical Research-Atmospheres*, 106:33729–33741.
- Abe-Ouchi, A. and H. Blatter, 1993. On the initiation of ice sheets. *Annals of Glaciology*, 18:203–207.
- ACIA, 2005. Arctic Climate Impact Assessment. 1042 pp. Cambridge University Press.
- Albrecht, O., P. Jansson and H. Blatter, 2000. Modelling glacier response to measured mass-balance forcing. *Annals of Glaciology*, 31:91–96.
- Alley, R.B., D.A. Meese, C.A. Shuman, A.J. Gow, K.C. Taylor, P.M. Grootes, J.W.C. White, M. Ram, E.D. Waddington, P.A. Mayewski and G.A. Zielinski, 1993. Abrupt increase in Greenland snow accumulation at the end of the Younger Dryas event. *Nature*, 362:527–529.
- Alley, R.B., P.U. Clark, P. Huybrechts and I. Joughin, 2005. Ice-sheet and sea-level changes. *Science*, 310:456–460.
- Alley, R.B., J.T. Andrews, J. Brigham-Grette, G.K.C. Clarke, K.M. Cuffey, J.J. Fitzpatrick, S. Funder, S.J. Marshall, G.H. Miller, J.X. Mitrovica, D.R. Muhs, B.L. Otto-Bliesner, L. Polyak and J.W.C. White, 2010. History of the Greenland Ice Sheet: Paleoclimatic insights. *Quaternary Science Reviews*, 29:1728–1756.
- Amundson, J.M., M. Truffer, M.P. Lüthi, M. Fahnestock, M. West and R.J. Motyka, 2008. Glacier, fjord, and seismic response to recent large calving events, Jakobshavn Isbræ, Greenland. *Geophysical Research Letters*, 35:L22501.
- Amundson, J.M., M. Fahnestock, M. Truffer, J. Brown, M.P. Lüthi and R.J. Motyka, 2010. Ice mélange dynamics and implications for terminus stability, Jakobshavn Isbræ, Greenland. *Journal of Geophysical Research*, 115:F01005.
- Andersen, K.K., P.D. Ditlevsen, S.O. Rasmussen, H.B. Clausen, B.M. Vinther, S.J. Johnsen and J.P. Steffensen, 2006a. Retrieving a common accumulation record from Greenland ice cores for the past 1800 years. *Journal of Geophysical Research-Atmospheres*, 111:D15106.
- Andersen, K.K., A. Svensson, S.J. Johnsen, S.O. Rasmussen, M. Bigler, R. Rothlisberger, U. Ruth, M.L. Siggaard-Andersen, J.P. Steffensen, D. Dahl-Jensen, B.M. Vinther and H.B. Clausen, 2006b. The Greenland Ice Core Chronology 2005, 15–42 ka. Part 1: constructing the time scale. *Quaternary Science Reviews*, 25:3246–3257.
- Anon, 1994. Environmental information for outer continental shelf oil and gas decisions in Alaska. National Research Council, Washington, D.C.
- Arnold, N. and M. Sharp, 2002. Flow variability in the Scandinavian ice sheet: modelling the coupling between ice sheet flow and hydrology. *Quaternary Science Reviews*, 21:485–502.
- Arthern, R.J. and D.J. Wingham, 1998. The natural fluctuations of firn densification and their effect on the geodetic determination of ice sheet mass balance. *Climatic Change*, 40:605–624.
- Aschwanden, A. and H. Blatter, 2009. Mathematical modeling and numerical simulation of polythermal glaciers. *Journal of Geophysical Research-Earth Surface*, 114:F01027.
- Bacon, S., G. Reverdin, I.G. Rigor and H.M. Snaith, 2002. A freshwater jet on the east Greenland shelf. *Journal of Geophysical Research-Oceans*, 107:3068–3084.
- Baehr, J., H. Haak, S. Alderson, S.A. Cunningham, J.H. Jungclauss and J. Marotzke, 2007. Timely detection of changes in the meridional overturning circulation at 26°N in the Atlantic. *Journal of Climate*, 20:5827–5841.
- Bales, R.C., J.R. McConnell, E. Mosley-Thompson and B. Csatho, 2001. Accumulation over the Greenland ice sheet from historical and recent records. *Journal of Geophysical Research-Atmospheres*, 106:33813–33825.
- Bales, R.C., Q.H. Guo, D.Y. Shen, J.R. McConnell, G.M. Du, J.F. Burkhart, V.B. Spikes, E. Hanna and J. Cappelen, 2009. Annual accumulation for Greenland updated using ice core data developed during 2000–2006 and analysis of daily coastal meteorological data. *Journal of Geophysical Research-Atmospheres*, 114:D06116.
- Bamber, J.L., S. Ekholm and W.B. Krabill, 2001. A new, high-resolution digital elevation model of Greenland fully validated with airborne laser altimeter data. *Journal of Geophysical Research-Solid Earth*, 106:6733–6745.
- Bamber, J.L., R.B. Alley and I. Joughin, 2007. Rapid response of modern day ice sheets to external forcing. *Earth and Planetary Science Letters*, 257:1–13.
- Barletta, V.R., R. Sabadini and A. Bordon, 2008. Isolating the PGR signal in the GRACE data: impact on mass balance estimates in Antarctica and Greenland. *Geophysical Journal International*, 172:18–30.
- Belkin, I.M., S. Levitus, J. Antonov and S.A. Malmberg, 1998. Great salinity anomalies in the North Atlantic. *Progress in Oceanography*, 41:1–68.
- Bendtsen, J., K.E. Gustafsson, S. Rysgaard and T. Vang, 2007. Physical conditions, dynamics and model simulations during the ice-free period of the Young Sound/Tyrolerfjord system. In: Rysgaard, S. and R.N. Glud (Eds.). *Carbon cycling in Arctic marine ecosystems: Case study Young Sound*, pp. 46–59, Meddelelser om Grønland, Bioscience, Copenhagen.
- Benn, D.I., C.R. Warren and R.H. Mottram, 2007. Calving processes and the dynamics of calving glaciers. *Earth-Science Reviews*, 82:143–179.
- Benson, C.S., 1962. Stratigraphic studies in the snow and firn of the Greenland Ice Sheet: Snow, Ice, and Permafrost Research Establishment (SIPRE). Research Report. 70:1–93 pp. U.S. Army Cold Regions Research and Engineering Laboratory (CRREL).
- Biggs, G.R., 1999. An estimate of the flux of iceberg calving from Greenland. Arctic, Antarctic, and Alpine Research, 31:174–178.
- Bindschadler, R.A., 1984. Jakobshavn Glacier drainage basin: a balance assessment. *Journal of Geophysical Research-Oceans*, 89:2066–2072.
- Bindschadler, R.A., X. Chen and P. Vornberger, 2000. The onset area of Ice Stream D, West Antarctica. *Journal of Glaciology*, 46:95–101.
- Bøggild, C.E., 2000. Preferential flow and melt water retention in cold snow packs in West-Greenland. *Nordic Hydrology*, 31:287–300.
- Bøggild, C.E., O.B. Olesen, A.P. Ahlstrøm and P. Jørgensen, 2004a. Automatic glacier ablation measurements using pressure transducers. *Journal of Glaciology*, 50:303–304.
- Bøggild, C.E., C. Mayer, S. Podlech, A. Taurisano and S. Nielsen, 2004b. Towards an assessment of the balance state of the Greenland Ice Sheet. *Geological Survey of Denmark and Greenland Bulletin*, 4:81–84.
- Bøggild, C.E., R. Forsberg and N. Reeh, 2005. Meltwater retention in a transect across the Greenland ice sheet. *Annals of Glaciology*, 40:169–173.
- Boon, S. and M. Sharp, 2003. The role of hydrologically-driven ice fracture in drainage system evolution on an Arctic glacier. *Geophysical Research Letters*, 30:L01916.
- Bougamont, M., J.L. Bamber and W. Greuell, 2005. A surface mass balance model for the Greenland ice sheet. *Journal of Geophysical Research-Earth Surface*, 110:F04018.
- Bougamont, M., J.L. Bamber, J.K. Ridley, R.M. Gladstone, W. Greuell, E. Hanna, A.J. Payne and I. Rutt, 2007. Impact of model physics on estimating the surface mass balance of the Greenland ice sheet. *Geophysical Research Letters*, 34:L17501.
- Box, J.E., 2002. Survey of Greenland instrumental temperature records: 1873–2001. *International Journal of Climatology*, 22:1829–1847.
- Box, J.E. and A.E. Cohen, 2006. Upper-air temperatures around Greenland: 1964–2005. *Geophysical Research Letters*, 33:L12706.
- Box, J.E. and A. Rinke, 2003. Evaluation of Greenland ice sheet surface climate in the HIRHAM regional climate model using automatic weather station data. *Journal of Climate*, 16:1302–1319.
- Box, J.E., D.H. Bromwich and L.S. Bai, 2004. Greenland ice sheet surface mass balance 1991–2000: Application of Polar MM5 mesoscale model and in situ data. *Journal of Geophysical Research-Atmospheres*, 109:D16105.
- Box, J.E., D.H. Bromwich, B.A. Veenhuis, L.S. Bai, J.C. Stroeve, J.C. Rogers, K. Steffen, T. Haran and S.H. Wang, 2006. Greenland ice sheet surface mass balance variability (1988–2004) from calibrated polar MM5 output. *Journal of Climate*, 19:2783–2800.
- Box, J.E., L. Yang, D.H. Bromwich and L.S. Bai, 2009. Greenland Ice Sheet surface air temperature variability: 1840–2007. *Journal of Climate*, 22:4029–4049.
- Braithwaite, R.J., 1995. Positive degree-day factors for ablation on the Greenland Ice Sheet studied by energy-balance modeling. *Journal of Glaciology*, 41:153–160.

- Braithwaite, R.J., O.B. Olesen and H.H. Thomsen, 1992. Calculated variations of annual ice ablation at the margin of the Greenland Ice Sheet, West Greenland, 1961–90. *Journal of Glaciology*, 38:266–272.
- Braun, A., H.R. Kim, B. Csatho and R.R.B. von Frese, 2007. Gravity-inferred crustal thickness of Greenland. *Earth and Planetary Science Letters*, 262:138–158.
- Brenner, A.C., J.R. DiMarzio and H.J. Zwally, 2007. Precision and accuracy of satellite radar and laser altimeter data over the continental ice sheets. *IEEE Transactions on Geoscience and Remote Sensing*, 45:321–331.
- Bryden, H.L., H.R. Longworth and S.A. Cunningham, 2005. Slowing of the Atlantic meridional overturning circulation at 25° N. *Nature*, 438:655–657.
- Buch, E., S.A. Pedersen and M.H. Ribergaard, 2004. Ecosystem variability in West Greenland waters. *Journal of Northwest Atlantic Fishery Science*, 34:13–28.
- Cappelen, J., 2003. World weather records 1991–2000: Denmark, the Faroe Islands and Greenland. Technical Report 03-34: pp. Danish Meteorological Institute, Copenhagen.
- Cappelen, J., B.V. Jørgensen, E.V. Laursen, L.S. Stannius and R.S. Thomsen, 2001. The observed climate of Greenland 1958–99 with climatological normals 1961–90. Technical Report. 00-18. Danish Meteorological Institute, Copenhagen.
- Carmack, E., F. McLaughlin, M. Yamamoto-Kawai, M. Itoh, K. Shimada, R. Krishfield and A. Proshutinsky, 2008. Freshwater storage in the Northern Ocean and the special role of the Beaufort Gyre. In: Dickson, R.R., J. Meincke and P. Rhines (Eds.). *Arctic-Subarctic Ocean Fluxes. Defining the Role of Northern Seas in Climate*, pp. 145–169, Springer Verlag.
- Cazenave, A., A. Lombard and W. Llovel, 2008. Present-day sea level rise: A synthesis. *Comptes Rendus Geoscience*, 340:761–770.
- Charbit, S., D. Paillard and G. Ramstein, 2008. Amount of CO₂ emissions irreversibly leading to the total melting of Greenland. *Geophysical Research Letters*, 35:L12503.
- Chen, J.L., C.R. Wilson and B.D. Tapley, 2006. Satellite gravity measurements confirm accelerated melting of Greenland ice sheet. *Science*, 313:1958–1960.
- Christensen, J.H., B. Hewitson, A. Busuioac and 14 others, 2007. Regional Climate Projections. In: Solomon, S., D. Qin, M. Manning, Z. Chen, M. Marquis, K.B. Averyt, M. Tignor and H.L. Miller (Eds.). *Climate Change 2007. The Physical Science Basis. Contribution of Working Group I to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change*, pp. 847–940, Cambridge University Press.
- Chylek, P., M.K. Dubey and G. Lesins, 2006. Greenland warming of 1920–1930 and 1995–2005. *Geophysical Research Letters*, 33:L11707.
- Clarke, G.K.C., 1987. Fast glacier flow: ice streams, surging and tidewater glaciers. *Journal of Geophysical Research-Solid Earth and Planets*, 92:8835–8841.
- Clarke, G.K.C., 2005. Subglacial processes. *Annual Review of Earth and Planetary Sciences*, 33:247–276.
- Clarke, T.S. and K. Echelmeyer, 1996. Seismic-reflection evidence for a deep subglacial trough beneath Jakobshavn Isbrae, West Greenland. *Journal of Glaciology*, 42:219–232.
- Clarke, G.K.C. and S.J. Marshall, 2002. Isotopic balance of the Greenland Ice Sheet: modelled concentrations of water isotopes from 30,000 BP to present. *Quaternary Science Reviews*, 21:419–430.
- Clarke, G.K.C., S.G. Collins and D.E. Thompson, 1984. Flow, thermal structure, and subglacial conditions of a surge-type glacier. *Canadian Journal of Earth Sciences*, 21:232–240.
- Climate and Cryosphere Project, 2007. CliC Implementation Strategy Document. WCRP Informal Report No. 126. WMO/TD 1301.
- Cogley, J.G., 2004. Greenland accumulation: An error model. *Journal of Geophysical Research-Atmospheres*, 109:D18101.
- Copland, L., M.J. Sharp and P.W. Nienow, 2003. Links between short-term velocity variations and the subglacial hydrology of a predominantly cold polythermal glacier. *Journal of Glaciology*, 49:337–348.
- Csatho, B., T. Schenk, C.J. van der Veen and W.B. Krabill, 2008. Intermittent thinning of Jakobshavn Isbrø, West Greenland, since the Little Ice Age. *Journal of Glaciology*, 54:131–144.
- Cubasch, U., G.A. Meehl, G.J. Boer, R.J. Stouffer, M. Dix, A. Noda, C.A. Senior, S.C.B. Raper and K.S. Yap, 2001. Projections of future climate change. In: Houghton, J.T., Y. Ding, D.J. Griggs, M. Noguer, P. van der Linden, X. Dai, K. Maskell and C.I. Johnson (Eds.). *Climate Change 2001: The scientific basis. Contribution of Working Group I to the Third Assessment Report of the Intergovernmental Panel on Climate Change*, pp. 525–582, Cambridge University Press.
- Cuffey, K.M. and G.D. Clow, 1997. Temperature, accumulation, and ice sheet elevation in central Greenland through the last deglacial transition. *Journal of Geophysical Research-Oceans*, 102:26383–26396.
- Cuffey, K.M. and S.J. Marshall, 2000. Substantial contribution to sea-level rise during the last interglacial from the Greenland ice sheet. *Nature*, 404:591–594.
- Cuffey, K.M., R.B. Alley, P.M. Grootes, J.M. Bolzan and S. Anandakrishnan, 1994. Calibration of the $\delta^{18}\text{O}$ isotopic paleothermometer for central Greenland, using borehole temperatures. *Journal of Glaciology*, 40:341–349.
- Cunningham, S.A., T. Kanzow, D. Rayner, M.O. Baringer, W.E. Johns, J. Marotzke, H.R. Longworth, E.M. Grant, J.J.M. Hirschi, L.M. Beal, C.S. Meinen and H.L. Bryden, 2007. Temporal variability of the Atlantic meridional overturning circulation at 26.5° N. *Science*, 317:935–938.
- Curry, R. and C. Mauritzen, 2005. Dilution of the northern North Atlantic Ocean in recent decades. *Science*, 308:1772–1774.
- Curry, R., B. Dickson and I. Yashayaev, 2003. A change in the freshwater balance of the Atlantic Ocean over the past four decades. *Nature*, 426:826–829.
- Dahl, J., 2000. *Saqqaq: an Inuit hunting community in the modern world*. 336 pp. University of Toronto Press.
- Dahl-Jensen, D., K. Mosegaard, N. Gundestrup, G.D. Clow, S.J. Johnsen, A.W. Hansen and N. Balling, 1998. Past temperatures directly from the Greenland Ice Sheet. *Science*, 282:268–271.
- Das, S.B., I. Joughin, M.D. Behn, I.M. Howat, M.A. King, D. Lizarralde and M.P. Bhatia, 2008. Fracture propagation to the base of the Greenland Ice Sheet during supraglacial lake drainage. *Science*, 320:778–781.
- Davis, C.H., C.A. Kluever, B.J. Haines, C. Perez and Y.T. Yoon, 2000. Improved elevation-change measurement of the southern Greenland ice sheet from satellite radar altimetry. *IEEE Transactions on Geoscience and Remote Sensing*, 38:1367–1378.
- de Vernal, A. and C. Hillaire-Marcel, 2008. Natural variability of Greenland climate, vegetation, and ice volume during the past million years. *Science*, 320:1622–1625.
- Dickson, R.R. and J. Brown, 1994. The production of North Atlantic Deep Water: Sources, rates, and pathways. *Journal of Geophysical Research-Oceans*, 99:12319–12341.
- Dickson, R.R., J. Meincke, S.A. Malmberg and A.J. Lee, 1988. The great salinity anomaly in the northern North Atlantic 1968–1982. *Progress in Oceanography*, 20:103–151.
- Dickson, B., I. Yashayaev, J. Meincke, B. Turrell, S. Dye and J. Holford, 2002. Rapid freshening of the deep North Atlantic Ocean over the past four decades. *Nature*, 416:832–837.
- Dickson, R., B. Rudels, S. Dye, M. Karcher, J. Meincke and I. Yashayaev, 2007. Current estimates of freshwater flux through Arctic and subarctic seas. *Progress in Oceanography*, 73:210–230.
- Dietrich, R., H.G. Maas, M. Baessler, A. Ruelke, A. Richter, E. Schwalbe and P. Westfeld, 2007. Jakobshavn Isbrae, West Greenland: Flow velocities and tidal interaction of the front area from 2004 field observations. *Journal of Geophysical Research-Earth Surface*, 112:F03S21.
- Dorn, W., K. Dethloff, A. Rinke, S. Frickenhaus, R. Gerdes, M. Karcher and F. Kauker, 2007. Sensitivities and uncertainties in a coupled regional atmosphere-ocean-ice model with respect to the simulation of Arctic sea ice. *Journal of Geophysical Research-Atmospheres*, 112:D10118.
- Dorn, W., K. Dethloff, A. Rinke and M. Kurgansky, 2008. The recent decline of the Arctic summer sea-ice cover in the context of internal climate variability. *Open Atmospheric Science Journal*, 2:91–100.
- Dorn, W., K. Dethloff and A. Rinke, 2009. Improved simulation of feedbacks between atmosphere and sea ice over the Arctic Ocean in a coupled regional climate model. *Ocean Modelling*, 29:103–114.
- Driesschaert, E., T. Fichefet, H. Goosse, P. Huybrechts, I. Janssens, A. Mouchet, G. Munhoven, V. Brovkin and S.L. Weber, 2007. Modeling the influence of Greenland ice sheet melting on the Atlantic meridional overturning circulation during the next millennia. *Geophysical Research Letters*, 34:L10707.
- Duhaime, G., A. Morin, H. Myers and D. St-Pierre, 2001. Inuit business ownership - Canadian experiences, Greenland challenges. In: Winther, G. (Ed.). *Participatory Ownership and Management in Greenland and other Circumpolar Regions*, pp. 105–116, Inussuk - Arctic Research Journal, Nuuk, Greenland.

- Echelmeyer, K., T.S. Clarke and W.D. Harrison, 1991. Surficial glaciology of Jakobshavn Isbræ, West Greenland: Part I. Surface morphology. *Journal of Glaciology*, 37:368–382.
- Ekström, G., M. Nettles and G.A. Abers, 2003. Glacial earthquakes. *Science*, 302:622–624.
- Ekström, G., M. Nettles and V.C. Tsai, 2006. Seasonality and increasing frequency of Greenland glacial earthquakes. *Science*, 311:1756–1758.
- Eldevik, T., J.E.Ø. Nilsen, D. Iovino, K.A. Olsson, A.B. Sandø and H. Drange, 2009. Observed sources and variability of Nordic seas overflow. *Nature Geoscience*, 2:405–409.
- Ettema, J., M.R. van den Broeke, E. van Meijgaard, W.J. van de Berg, J.L. Bamber, J.E. Box and R.C. Bales, 2009. Higher surface mass balance of the Greenland ice sheet revealed by high-resolution climate modeling. *Geophysical Research Letters*, 36:L12501.
- Fahnestock, M., R. Bindshadler, R. Kwok and K. Jezek, 1993. Greenland ice sheet surface properties and ice dynamics from ERS-1 SAR imagery. *Science*, 262:1530–1534.
- Fahnestock, M., W. Abdalati, I. Joughin, J. Brozena and P. Gogineni, 2001. High geothermal heat flow, basal melt, and the origin of rapid ice flow in central Greenland. *Science*, 294:2338–2342.
- Fettweis, X., 2007. Reconstruction of the 1979–2006 Greenland ice sheet surface mass balance using the regional climate model MAR. *The Cryosphere*, 1:21–40.
- Fettweis, X., H. Gallée, F. Lefebvre and J.P. van Ypersele, 2005. Greenland surface mass balance simulated by a regional climate model and comparison with satellite-derived data in 1990–1991. *Climate Dynamics*, 24:623–640.
- Fettweis, X., J.P. van Ypersele, H. Gallée, F. Lefebvre and W. Lefebvre, 2007. The 1979–2005 Greenland ice sheet melt extent from passive microwave data using an improved version of the melt retrieval XPRG algorithm. *Geophysical Research Letters*, 34:L05502.
- Fettweis, X., E. Hanna, H. Gallée, P. Huybrechts and M. Erpicum, 2008. Estimation of the Greenland ice sheet surface mass balance for the 20th and 21st centuries. *The Cryosphere*, 2:117–129.
- Fichefet, T., C. Poncin, H. Goosse, P. Huybrechts, I. Janssens and H. Le Treut, 2003. Implications of changes in freshwater flux from the Greenland ice sheet for the climate of the 21st century. *Geophysical Research Letters*, 30:1911.
- Fisher, D.A., N. Reeh and H.B. Clausen, 1985. Stratigraphic noise in time series derived from ice cores. *Annals of Glaciology* 7:76–83.
- Fleming, K. and K. Lambeck, 2004. Constraints on the Greenland Ice Sheet since the Last Glacial Maximum from sea-level observations and glacial-rebound models. *Quaternary Science Reviews*, 23:1053–1077.
- Flowers, G.E. and G.K.C. Clarke, 2002. A multicomponent coupled model of glacier hydrology - 1. Theory and synthetic examples. *Journal of Geophysical Research-Solid Earth*, 107:2287.
- Flowers, G.E., S.J. Marshall, H. Björnsson and G.K.C. Clarke, 2005. Sensitivity of Vatnajökull ice cap hydrology and dynamics to climate warming over the next 2 centuries. *Journal of Geophysical Research-Earth Surface*, 110:F02011.
- Flückiger, J., R. Knutti and J.W.C. White, 2006. Oceanic processes as potential trigger and amplifying mechanisms for Heinrich events. *Paleoceanography*, 21:PA2014.
- Funk, M., K. Echelmeyer and A. Iken, 1994. Mechanisms of fast flow in Jakobshavn Isbræ, Greenland: Part II. Modeling of englacial temperatures. *Journal of Glaciology*, 40:569–585.
- Gallée, H. and G. Schayes, 1994. Development of a 3-dimensional meso-gamma primitive equation model - katabatic winds simulation in the area of Terra-Nova Bay, Antarctica. *Monthly Weather Review*, 122:671–685.
- Gogineni, S., J. Paden, A. Torrey, C. Allen, P. Kanagaratnam, D. Braaten and K. Jezek, 2006. Synthetic Aperture Radar imaging of ice-bed interface. EOS, Transactions, American Geophysical Union, 87:Abstract C14B-06.
- Gregory, J.M. and P. Huybrechts, 2006. Ice-sheet contributions to future sea-level change. *Philosophical Transactions of the Royal Society A-Mathematical Physical and Engineering Sciences*, 364:1709–1731.
- Gregory, J.M., H.T. Banks, P.A. Stott, J.A. Lowe and M.D. Palmer, 2004. Simulated and observed decadal variability in ocean heat content. *Geophysical Research Letters*, 31:L15312.
- Gregory, J.M., K.W. Dixon, R.J. Stouffer and 15 others, 2005. A model intercomparison of changes in the Atlantic thermohaline circulation in response to increasing atmospheric CO₂-concentration. *Geophysical Research Letters*, 32:L12703.
- Greuell, W. and T. Konzmann, 1994. Numerical modeling of the energy-balance and the englacial temperature of the Greenland Ice-Sheet - Calculations for the ETH-Camp location (West Greenland, 1155m asl). *Global and Planetary Change*, 9:91–114.
- Greuell, W. and J. Oerlemans, 2005. Assessment of the surface mass balance along the K-transect (Greenland ice sheet) from satellite-derived albedos. *Annals of Glaciology*, 42:107–117.
- Greuell, W., B. Denby, R.S.W. van de Wal and J. Oerlemans, 2001. 10 years of mass-balance measurements along a transect near Kangerlussuaq, central West Greenland. *Journal of Glaciology*, 47:157–158.
- Greve, R., 1997. Application of a polythermal three-dimensional ice sheet model to the Greenland Ice Sheet: Response to steady-state and transient climate scenarios. *Journal of Climate*, 10:901–918.
- Greve, R., 2000. On the response of the Greenland ice sheet to greenhouse climate change. *Climatic Change*, 46:289–303.
- Greve, R., 2005. Relation of measured basal temperatures and the spatial distribution of the geothermal heat flux for the Greenland ice sheet. *Annals of Glaciology*, 42:424–432.
- Grinsted, A., J.C. Moore and S. Jevrejeva, 2010. Reconstructing sea level from paleo and projected temperatures 200 to 2100 AD. *Climate Dynamics*, 34:461–472.
- Grønnow, B. and M. Meldgaard, 1988. Boplads i dybfrost – Fra Christianshåb Museums udgravninger på Vestgrønlands ældste boplads. [in Danish]. In: *Naturens Verden*, 409–440.
- Haak, H., J. Jungclaus, U. Mikolajewicz and M. Latif, 2003. Formation and propagation of great salinity anomalies. *Geophysical Research Letters*, 30:1473.
- Haine, T., C. Böning, P. Brandt, J. Fischer, A. Funk, D. Kieke, E. Kvaleberg, M. Rhein and M. Visbeck, 2008. North Atlantic Deep Water formation in the Labrador Sea, recirculation through the subpolar gyre, and discharge to the subtropics. In: Dickson, R.R., J. Meincke and P. Rhines (Eds.). *Arctic-Subarctic Ocean Fluxes. Defining the Role of Northern Seas in Climate*, pp. 653–701, Springer Verlag.
- Häkkinen, S. and P.B. Rhines, 2004. Decline of subpolar North Atlantic circulation during the 1990s. *Science*, 304:555–559.
- Hamilton, L.C. and C.L. Seyfrit, 1993. Town-village contrasts in Alaskan youth aspirations. *Arctic*, 46:255–263.
- Hamilton, L.C., B.C. Brown and R.O. Rasmussen, 2003. West Greenland's cod-to-shrimp transition: Local dimensions of climatic change. *Arctic*, 56:271–282.
- Hanna, E. and J. Cappelen, 2003. Recent cooling in coastal southern Greenland and relation with the North Atlantic Oscillation. *Geophysical Research Letters*, 30:1132.
- Hanna, E., P. Huybrechts and T.L. Mote, 2002. Surface mass balance of the Greenland ice sheet from climate-analysis data and accumulation/runoff models. *Annals of Glaciology*, 35:67–72.
- Hanna, E., P. Huybrechts, I. Janssens, J. Cappelen, K. Steffen and A. Stephens, 2005. Runoff and mass balance of the Greenland ice sheet: 1958–2003. *Journal of Geophysical Research-Atmospheres*, 110:D13108.
- Hanna, E., J. McConnell, S. Das, J. Cappelen and A. Stephens, 2006. Observed and modeled Greenland ice sheet snow accumulation, 1958–2003, and links with regional climate forcing. *Journal of Climate*, 19:344–358.
- Hanna, E., P. Huybrechts, K. Steffen, J. Cappelen, R. Huff, C. Shuman, T. Irvine-Fynn, S. Wise and M. Griffiths, 2008. Increased runoff from melt from the Greenland Ice Sheet: A response to global warming. *Journal of Climate*, 21:331–341.
- Hansen, K.G., 2003. IT-sektoren i et magtperspektiv. [in Danish]. In: Winther, G. (Ed.). *Demokrati og magt i Grønland*, pp. 162–194. Universitetsforlaget, Aarhus, Denmark.
- Hansen, B. and S. Østerhus, 2000. North Atlantic-Nordic Seas exchanges. *Progress in Oceanography*, 45:109–208.
- Hansen, B. and S. Østerhus, 2007. Faroe Bank Channel overflow 1995–2005. *Progress in Oceanography*, 55:817–856.
- Hansen, B., W.R. Turrell and S. Østerhus, 2001. Decreasing overflow from the Nordic seas into the Atlantic Ocean through the Faroe Bank channel since 1950. *Nature*, 411:927–930.
- Hansen, B., S. Østerhus, B. Turrell, S. Jönsson, H. Valdimarsson, H. Hátún and S.M. Olsen, 2008. The inflow of Atlantic water, heat, and salt to the Nordic Seas across the Greenland-Scotland Ridge. In: Dickson, R.R., J.

- Meincke and P. Rhines (Eds.). Arctic-Subarctic Ocean Fluxes. Defining the Role of Northern Seas in Climate, pp. 15–43, Springer Verlag.
- Harrison, W.D. and A.S. Post, 2003. How much do we really know about glacier surging? *Annals of Glaciology*, 36:1–6.
- Hasholt, B., S.H. Mernild, C. Sigsgaard, B. Elberling, D. Petersen, B.H. Jakobsen, B.U. Hansen, J. Hinkler and H. Sogaard, 2008. Hydrology and transport of sediment and solutes at Zackenberg. In: Meltofte, H., T.R. Christensen, B. Elberling, M.C. Forchhammer and M. Rasch (Eds.). High-Arctic Ecosystem Dynamics in a Changing Climate: Ten years of monitoring and research at Zackenberg Research Station, Northeast Greenland, pp. 111–149, Academic Press.
- Hátún, H., A.B. Sandø, H. Drange, B. Hansen and H. Valdimarsson, 2005. Influence of the Atlantic subpolar gyre on the thermohaline circulation. *Science*, 309:1841–1844.
- Helsen, M.M., M.R. van den Broeke, R.S.W. van de Wal, W.J. van de Berg, E. van Meijgaard, C.H. Davis, Y.H. Li and I. Goodwin, 2008. Elevation changes in Antarctica mainly determined by accumulation variability. *Science*, 320:1626–1629.
- Holfort, J., E. Hansen, S. Østerhus, S. Dye, S. Jonsson, J. Meincke, J. Mortensen and M. Meredith, 2008. Freshwater fluxes east of Greenland. In: Dickson, R.R., J. Meincke and P. Rhines (Eds.). Arctic-Subarctic Ocean Fluxes. Defining the Role of Northern Seas in Climate, pp. 263–287, Springer Verlag.
- Holgate, S., S. Jevrejeva, P. Woodworth and S. Brewer, 2007. Comment on "A semi-empirical approach to projecting future sea-level rise". *Science*, 317:1866.
- Holland, D.M., R.H. Thomas, B. De Young, M.H. Ribergaard and B. Lyberth, 2008. Acceleration of Jakobshavn Isbræ triggered by warm subsurface ocean waters. *Nature Geoscience*, 1:659–664.
- Howat, I.M., I. Joughin, S. Tulaczyk and S. Gogineni, 2005. Rapid retreat and acceleration of Helheim Glacier, east Greenland. *Geophysical Research Letters*, 32:L22502.
- Howat, I.M., I. Joughin and T.A. Scambos, 2007. Rapid changes in ice discharge from Greenland outlet glaciers. *Science*, 315:1559–1561.
- Howat, I.M., B.E. Smith, I. Joughin and T.A. Scambos, 2008. Rates of southeast Greenland ice volume loss from combined ICESat and ASTER observations. *Geophysical Research Letters*, 35:L17505.
- Hutter, K., 1982. A mathematical model of polythermal glaciers and ice sheets. *Geophysical and Astrophysical Fluid Dynamics*, 21:201–224.
- Hutter, K., 1983. Theoretical Glaciology; Material Science of Ice and the Mechanics of Glaciers and Ice Sheets. First edition. D. Reidel.
- Huybrechts, P., 1996. Basal temperature conditions of the Greenland ice sheet during the glacial cycles. *Annals of Glaciology*, 23:226–236.
- Huybrechts, P., 2002. Sea-level changes at the LGM from ice-dynamic reconstructions of the Greenland and Antarctic ice sheets during the glacial cycles. *Quaternary Science Reviews*, 21:203–231.
- Huybrechts, P. and J. de Wolde, 1999. The dynamic response of the Greenland and Antarctic ice sheets to multiple-century climatic warming. *Journal of Climate*, 12:2169–2188.
- Huybrechts, P., A. Letrégouilly and N. Reeh, 1991. The Greenland Ice Sheet and greenhouse warming. *Global and Planetary Change*, 89:399–412.
- Huybrechts, P., I. Janssens, C. Pocin and T. Fichet, 2002. The response of the Greenland ice sheet to climate changes in the 21st century by interactive coupling of an AOGCM with a thermomechanical ice-sheet model. *Annals of Glaciology*, 35:409–415.
- Huybrechts, P., J. Gregory, I. Janssens and M. Wild, 2004. Modelling Antarctic and Greenland volume changes during the 20th and 21st centuries forced by GCM time slice integrations. *Global and Planetary Change*, 42:83–105.
- Iken, A. and R.A. Bindshadler, 1986. Combined measurements of subglacial water pressures and surface velocity of the Findelengletscher, Switzerland. Conclusions about drainage systems and sliding mechanism. *Journal of Glaciology*, 32:101–119.
- Iken, A. and M. Truffer, 1997. The relationship between subglacial water pressure and velocity of Findelengletscher, Switzerland, during its advance and retreat. *Journal of Glaciology*, 43:328–338.
- Iken, A., K. Echelmeyer, W. Harrison and M. Funk, 1993. Mechanisms of fast flow in Jakobshavns Isbræ, West Greenland: Part I. Measurements of temperature and water level in deep boreholes. *Journal of Glaciology*, 39:15–25.
- Imbrie, J., J.D. Hays, D.G. Martinson, A. McIntyre, A.C. Mix, J.J. Morley, N.G. Pisias, W.L. Prell and N.J. Shackleton, 1984. The orbital theory of Pleistocene climate: support from a revised chronology of the marine $\delta^{18}\text{O}$ record. Paper presented at Milankovitch and Climate: Understanding the Response to Astronomical Forcing, 269 pp., Palisades, NY, 30 November–4 December, 1982.
- IPCC, 2007. Summary for Policymakers. In: Solomon, S., D. Qin, M. Manning, Z. Chen, M. Marquis, K.B. Averyt, M. Tignor and H.L. Miller (Eds.). Climate Change 2007: The physical science basis. Contribution of Working Group I to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change, pp. 1–21, Cambridge University Press.
- Janssens, I. and P. Huybrechts, 2000. The treatment of meltwater retention in mass-balance parameterizations of the Greenland ice sheet. *Annals of Glaciology*, 31:133–140.
- Jiskoot, H., T. Murray and A. Luckman, 2003. Surge potential and drainage-basin characteristics in East Greenland. *Annals of Glaciology*, 36:142–148.
- Johannessen, O.M., K. Khvorostovsky, M.W. Miles and L.P. Bobylev, 2005. Recent ice-sheet growth in the interior of Greenland. *Science*, 310:1013–1016.
- Johnsen, S.J., D. Dahl-Jensen, N. Gundestrup, J.P. Steffensen, H.B. Clausen, H. Miller, V. Masson-Delmotte, A.E. Sveinbjornsdottir and J. White, 2001. Oxygen isotope and palaeotemperature records from six Greenland ice-core stations: Camp Century, Dye-3, GRIP, GISP2, Renland and NorthGRIP. *Journal of Quaternary Science*, 16:299–307.
- Johnson, J. and J.L. Fastook, 2002. Northern Hemisphere glaciation and its sensitivity to basal melt water. *Quaternary International*, 95–6:65–74.
- Johnson, J.V., P.R. Prescott and T.J. Hughes, 2004. Ice dynamics preceding catastrophic disintegration of the floating part of Jakobshavn Isbræ, Greenland. *Journal of Glaciology*, 50:492–504.
- Joughin, I., S. Tulaczyk, M. Fahnestock and R. Kwok, 1996. A mini-surge on the Ryder Glacier, Greenland, observed by satellite radar interferometry. *Science*, 274:228–230.
- Joughin, I.R., M.A. Fahnestock and J.L. Bamber, 2000. Ice flow in the northeast Greenland ice stream. *Annals of Glaciology*, 31:141–146.
- Joughin, I., W. Abdalati and M. Fahnestock, 2004. Large fluctuations in speed on Greenland's Jakobshavn Isbræ glacier. *Nature*, 432:608–610.
- Joughin, I., S.B. Das, M.A. King, B.E. Smith, I.M. Howat and T. Moon, 2008a. Seasonal speedup along the western flank of the Greenland Ice Sheet. *Science*, 320:781–783.
- Joughin, I., I. Howat, R.B. Alley, G. Ekström, M. Fahnestock, T. Moon, M. Nettles, M. Truffer and V.C. Tsai, 2008b. Ice-front variation and tidewater behavior on Helheim and Kangerdlugssuaq Glaciers, Greenland. *Journal of Geophysical Research-Earth Surface*, 113:F01004.
- Joughin, I., I.M. Howat, M. Fahnestock, B. Smith, W. Krabill, R.B. Alley, H. Stern and M. Truffer, 2008c. Continued evolution of Jakobshavn Isbræ following its rapid speedup. *Journal of Geophysical Research-Earth Surface*, 113:F04006.
- Kamb, B., C.F. Raymond, W.D. Harrison, H. Engelhardt, K.A. Echelmeyer, N. Humphrey, M.M. Brugman and T. Pfeffer, 1985. Glacier surge mechanism: 1982–1983 surge of Variegated Glacier, Alaska. *Science*, 227:469–479.
- Kattsov, V.M., J.E. Walsh, W.L. Chapman, V.A. Govorkova, T.V. Pavlova and X.D. Zhang, 2007. Simulation and projection of arctic freshwater budget components by the IPCC AR4 global climate models. *Journal of Hydrometeorology*, 8:571–589.
- Keddeman, W., 1998. Of NETS and ASSETS. Effects and impacts of employment-intensive programmes - A review of ILO experience. Development Policies Department. International Labour Office. Geneva.
- Kiilsholm, S., J.H. Christensen, K. Dethloff and A. Rinke, 2003. Net accumulation of the Greenland ice sheet: High resolution modeling of climate changes. *Geophysical Research Letters*, 30:1485.
- Kingsley, M.C.S., 2007. The Fishery for Northern Shrimp (*Pandalus borealis*) off West Greenland, 1970–2007. NAFO SCR Doc. 07/69:42 pp. Northwest Atlantic Fisheries Organization, Canada.
- Kliem, N., M.H. Ribergaard, M. Stendel and J.H. Christensen, 2007. Regional climate change for Greenland and surrounding seas. Part II: Ocean. DMI Climate Centre Report. 07-04:26 pp. Danish Meteorological Institute.
- Konzelmann, T., R.S.W. van de Wal, W. Greuell, R. Bintanja, E.A.C. Henneken and A. Abe-Ouchi, 1994. Parameterization of global and longwave incoming radiation for the Greenland Ice Sheet. *Global and*

- Planetary Change, 9:143–164.
- Kopp, R.E., F.J. Simons, J.X. Mitrovica, A.C. Maloof and M. Oppenheimer, 2009. Probabilistic assessment of sea level during the last interglacial stage. *Nature*, 462:863–867.
- Krabill, W., W. Abdalati, E. Frederick, S. Manizade, C. Martin, J. Sonntag, R. Swift, R. Thomas, W. Wright and J. Yungel, 2000. Greenland ice sheet: High-elevation balance and peripheral thinning. *Science*, 289:428–430.
- Krabill, W.B., W. Abdalati, E.B. Frederick, S.S. Manizade, C.F. Martin, J.G. Sonntag, R.N. Swift, R.H. Thomas and J.G. Yungel, 2002. Aircraft laser altimetry measurement of elevation changes of the Greenland ice sheet: technique and accuracy assessment. *Journal of Geodynamics*, 34:357–376.
- Krabill, W., E. Hanna, P. Huybrechts, W. Abdalati, J. Cappelen, B. Csatho, E. Frederick, S. Manizade, C. Martin, J. Sonntag, R. Swift, R. Thomas and J. Yungel, 2004. Greenland Ice Sheet: Increased coastal thinning. *Geophysical Research Letters*, 31:L24402.
- Lambeck, K., T.M. Esat and E.K. Potter, 2002. Links between climate and sea levels for the past three million years. *Nature*, 419:199–206.
- Landais, A., J. Jouzel, V. Masson-Delmotte and N. Caillon, 2005. Large temperature variations over rapid climatic events in Greenland: a method based on air isotopic measurements. *Comptes Rendus Geoscience*, 337:947–956.
- Landerer, F.W., J.H. Jungclauss and J. Marotzke, 2007. Regional dynamic and steric sea level change in response to the IPCC-A1B scenario. *Journal of Physical Oceanography*, 37:296–312.
- Latif, M., E. Roeckner, U. Mikolajewicz and R. Voss, 2000. Tropical stabilization of the thermohaline circulation in a greenhouse warming simulation. *Journal of Climate*, 13:1809–1813.
- Lazier, J.R.N., 1980. Oceanographic conditions at Ocean Weather Station Bravo, 1964–1974. *Atmosphere-Ocean*, 18:227–238.
- Le Meur, E. and P. Huybrechts, 1998. Present-day uplift patterns over Greenland from a coupled ice-sheet/visco-elastic bedrock model. *Geophysical Research Letters*, 25:3951–3954.
- Leftwich, T.E., K. van der Veen, R.R. von Frese and B. Csatho, 2007. Crustal geothermal controls on ice sheet dynamics of Greenland. *American Geophysical Union, Fall Meeting 2007: Abstract C41C-06*.
- Lemke, P., J. Ren, R.B. Alley, I. Allison, J. Carrasco, G. Flato, Y. Fujii, G. Kaser, P. Mote, R.H. Thomas and T. Zhang, 2007. Observations: Changes in snow, ice and frozen ground. In: Solomon, S., D. Qin, M. Manning, Z. Chen, M. Marquis, K.B. Averyt, M. Tignor and H.L. Miller (Eds.). *Climate Change 2007: The Physical Science Basis. Contribution of Working Group I to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change*, pp. 337–383, Cambridge University Press.
- Létréguilly, A., N. Reeh and P. Huybrechts, 1991. The Greenland ice sheet through the last glacial-interglacial cycle. *Global and Planetary Change*, 90:385–394.
- Li, J. and H.J. Zwally, 2004. Modeling the density variation in the shallow firn layer. *Annals of Glaciology*, 38:309–313.
- Lisiecki, L.E. and M.E. Raymo, 2005. A Pliocene-Pleistocene stack of 57 globally distributed benthic $\delta^{18}O$ records. *Paleoceanography*, 20:PA1003.
- Lohofener, A., C. Veeramacheni, S. Raghunandan, V. Ramasami, J. Paden, T. Akins, P. Kanagaratnam and P. Gogineni, 2006. Radar sounding of Jakobshavn and other outlet glaciers. EOS, Transactions, American Geophysical Union, Fall Meeting Supplement. 87:Abstract C41A-0318.
- Luckman, A. and T. Murray, 2005. Seasonal variation in velocity before retreat of Jakobshavn Isbræ, Greenland. *Geophysical Research Letters*, 32:L08501.
- Luckman, A., T. Murray, R. de Lange and E. Hanna, 2006. Rapid and synchronous ice-dynamic changes in East Greenland. *Geophysical Research Letters*, 33:L03503.
- Lunt, D.J., G.L. Foster, A.M. Haywood and E.J. Stone, 2008. Late Pliocene Greenland glaciation controlled by a decline in atmospheric CO_2 levels. *Nature*, 454:1102–1105.
- Luthcke, S.B., H.J. Zwally, W. Abdalati, D.D. Rowlands, R.D. Ray, R.S. Nerem, F.G. Lemoine, J.J. McCarthy and D.S. Chinn, 2006. Recent Greenland ice mass loss by drainage system from satellite gravity observations. *Science*, 314:1286–1289.
- Lüthi, M., M. Funk, A. Iken, S. Gogineni and M. Truffer, 2002. Mechanisms of fast flow in Jakobshavn Isbræ, West Greenland: Part III. Measurements of ice deformation, temperature and cross-borehole conductivity in boreholes to the bedrock. *Journal of Glaciology*, 48:369–385.
- Lüthi, M.P., M. Funk and A. Iken, 2003. Indication of active overthrust faulting along the Holocene-Wisconsin transition in the marginal zone of Jakobshavn Isbræ. *Journal of Geophysical Research-Solid Earth*, 108:2543.
- Luthje, M., L.T. Pedersen, N. Reeh and W. Greuell, 2006. Modelling the evolution of supraglacial lakes on the West Greenland ice-sheet margin. *Journal of Glaciology*, 52:608–618.
- Lythe, M.B., D.G. Vaughan and the BEDMAP Consortium, 2001. BEDMAP: A new ice thickness and subglacial topographic model of Antarctica. *Journal of Geophysical Research B*, 106:11335–11351.
- Macayeal, D.R., 1989. Large-scale ice flow over a viscous basal sediment: Theory and application to Ice Stream B, Antarctica. *Journal of Geophysical Research-Solid Earth and Planets*, 94:4071–4087.
- MacAyeal, D.R. and H. Thomas, 1982. Numerical modelling of ice shelf motion. *Journal of Glaciology*, 3:189–194.
- Magand, O., G. Picard, L. Brucker, M. Fily and C. Genthon, 2008. Snow melting bias in microwave mapping of Antarctic snow accumulation. *The Cryosphere*, 2:109–115.
- Mair, D., P. Nienow, I. Willis and M. Sharp, 2001. Spatial patterns of glacier motion during a high-velocity event: Haut Glacier d'Arolla, Switzerland. *Journal of Glaciology*, 47:9–20.
- Marshall, S.J., 2005. Recent advances in understanding ice sheet dynamics. *Earth and Planetary Science Letters*, 240:191–204.
- Marshall, S.J. and K.M. Cuffey, 2000. Peregrinations of the Greenland Ice Sheet divide in the last glacial cycle: implications for central Greenland ice cores. *Earth and Planetary Science Letters*, 179:73–90.
- Marshall, J. and F. Schott, 1999. Open-ocean convection: Observations, theory, and models. *Reviews of Geophysics*, 37:1–64.
- Marshall, S.J., L. Tarasov, G.K.C. Clarke and W.R. Peltier, 2000. Glaciological reconstruction of the Laurentide Ice Sheet: physical processes and modelling challenges. *Canadian Journal of Earth Sciences*, 37:769–793.
- Marshall, S.J., H. Björnsson, G.E. Flowers and G.K.C. Clarke, 2005. Simulation of Vatnajökull ice cap dynamics. *Journal of Geophysical Research-Earth Surface*, 110:F03009.
- Maslanik, J., S. Drobot, C. Fowler, W. Emery and R. Barry, 2007. On the Arctic climate paradox and the continuing role of atmospheric circulation in affecting sea ice conditions. *Geophysical Research Letters*, 34:L03711.
- McConnell, J.R., R.J. Arthern, E. Mosley-Thompson, C.H. Davis, R.C. Bales, R. Thomas, J.F. Burkhart and J.D. Kyne, 2000. Changes in Greenland ice sheet elevation attributed primarily to snow accumulation variability. *Nature*, 406:877–879.
- Meehl, G.A., T.F. Stocker, W.D. Collins, P. Friedlingstein, A.T. Gaye, J.M. Gregory, A. Kitoh, R. Knutti, J.M. Murphy, A. Noda, S.C.B. Raper, I.G. Watterson, A.J. Weaver and Z.-C. Zhao, 2007. Global Climate Projections. In: Solomon, S., D. Qin, M. Manning, Z. Chen, A. Marquis, K.B. Averyt, M. Tignor and H.L. Miller (Eds.). *Climate Change 2007: The Physical Science Basis. Contribution of Working Group I to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change*, pp. 747–845, Cambridge University Press.
- Meier, M.F. and A. Post, 1969. What are glacier surges? *Canadian Journal of Earth Sciences*, 6:63–77.
- Meier, M.F. and A. Post, 1987. Fast tidewater glaciers. *Journal of Geophysical Research-Solid Earth and Planets*, 92:9051–9058.
- Melling, H., T.A. Agnew, K.K. Falkner, D.A. Greenberg, C.M. Lee, A. Münchow, B. Petrie, S.J. Prinsenberg, R.M. Samelson and R.A. Woodgate, 2008. Freshwater fluxes via Pacific and Arctic outflows across the Canadian Polar Shelf. In: Dickson, R.R., J. Meincke and P. Rhines (Eds.). *Arctic-Subarctic Ocean Fluxes. Defining the Role of Northern Seas in Climate*, pp. 193–247, Springer Verlag.
- Mernild, S.H., G.E. Liston, B. Hasholt and N.T. Knudsen, 2006. Snow distribution and melt modeling for Mittivakkat Glacier, Ammassalik Island, southeast Greenland. *Journal of Hydrometeorology*, 7:808–824.
- Mikkelsen, N. and T. Ingerslev, 2002. Ilulissat Icefjord. <http://whc.unesco.org/en/list/1149/documents/> Accessed: 6 October 2010.
- Mikolajewicz, U., M. Gröger, E. Maier-Reimer, G. Schurgers, M. Vizcaino and A.M.E. Winguth, 2007a. Long-term effects of anthropogenic CO_2 emissions simulated with a complex earth system model. *Climate Dynamics*, 28:599–631.
- Mikolajewicz, U., M. Vizcaino, J. Jungclauss and G. Schurgers, 2007b. Effect of ice sheet interactions in anthropogenic climate change simulations. *Geophysical Research Letters*, 34:L18706.

- Miller, G., P. Anderson, O. Bennike and 22 others, 2006. Last interglacial Arctic warmth confirms polar amplification of climate change. *Quaternary Science Reviews*, 25:1383–1400.
- Milne, G.A., W.R. Gehrels, C.W. Hughes and M.E. Tamisiea, 2009. Identifying the causes of sea-level change. *Nature Geoscience*, 2:471–478.
- Mitrovica, J.X., M.E. Tamisiea, J.L. Davis and G.A. Milne, 2001. Recent mass balance of polar ice sheets inferred from patterns of global sea-level change. *Nature*, 409:1026–1029.
- Moon, T. and I. Joughin, 2008. Changes in ice front position on Greenland's outlet glaciers from 1992 to 2007. *Journal of Geophysical Research-Earth Surface*, 113:F02022.
- Mosley-Thompson, E., J.R. McConnell, R.C. Bales, P.N. Lin, K. Steffen, L.G. Thompson, R. Edwards and D. Bathke, 2001. Local to regional-scale variability of annual net accumulation on the Greenland ice sheet from PARCA cores. *Journal of Geophysical Research-Atmospheres*, 106:33839–33851.
- Mote, T.L., 2003. Estimation of runoff rates, mass balance, and elevation changes on the Greenland ice sheet from passive microwave observations. *Journal of Geophysical Research-Atmospheres*, 108:4056.
- Mote, T.L., 2007. Greenland surface melt trends 1973–2007: Evidence of a large increase in 2007. *Geophysical Research Letters*, 34:L22507.
- Motyka, R.J. and M. Truffer, 2007. Hubbard Glacier, Alaska: 2002 closure and outburst of Russell Fjord and postflood conditions at Gilbert Point. *Journal of Geophysical Research-Earth Surface*, 112:F02004.
- Motyka, R.J., L. Hunter, K.A. Echelmeyer and C. Connor, 2003. Submarine melting at the terminus of a temperate tidewater glacier, LeConte Glacier, Alaska, USA. *Annals of Glaciology*, 36:57–65.
- Murray, T., T. Strozzi, A. Luckman, H. Pritchard and H. Jiskoot, 2002. Ice dynamics during a surge of Sortebrø, East Greenland. *Annals of Glaciology*, 34:323–329.
- Murray, T., K. Scharer, T.D. James, S.R. Dye, E. Hanna, A.D. Booth, N. Selmes, A. Luckman, A.L.C. Hughes, S. Cook and P. Huybrechts, 2010. Ocean-regulation hypothesis for glacier dynamics in south-east Greenland and implications for ice-sheet mass changes. *Journal of Geophysical Research*, 115:F03026.
- Nellemann, C. and I. Vistnes, 2003. Large-scale environmental dynamics - assessing processes and impacts. In: Rasmussen, R.O. and N. Koroleva (Eds.). *Social and Environmental Impacts in the North*, pp. 3–6, Kluwer Academic Publishers.
- Nettles, M., T.B. Larsen, P. Elósegui, A.P. Ahlstrøm, J.L. Davis, J. de Juan, G. Ekström, R. Forsberg, G.S. Hamilton, S.A. Khan, M.L. Andersen, L.A. Stearns and L. Stenseng, 2008. Short-time-scale variations in flow speed observed at Helheim Glacier, East Greenland. *Geophysical Research Abstracts*, 10:EGU2008-A-05663.
- Nghiem, S.V., I.G. Rigor, D.K. Perovich, P. Clemente-Colon, J.W. Weatherly and G. Neumann, 2007. Rapid reduction of Arctic perennial sea ice. *Geophysical Research Letters*, 34:L19504.
- Nick, F.M., A. Vieli, I.M. Howat and I. Joughin, 2009. Large-scale changes in Greenland outlet glacier dynamics triggered at the terminus. *Nature Geoscience*, 2:110–114.
- North Greenland Ice Core Project members, 2004. High-resolution record of Northern Hemisphere climate extending into the last interglacial period. *Nature*, 431:147–151.
- Nye, J.F., 1957. The distribution of stress and velocity in glaciers and ice sheets. *Proceedings of the Royal Society of London Series A-Mathematical and Physical Sciences*, 239:113–133.
- O'Neel, S., W.T. Pfeffer, R. Krimmel and M. Meier, 2005. Evolving force balance at Columbia Glacier, Alaska, during its rapid retreat. *Journal of Geophysical Research-Earth Surface*, 110:F03012.
- Oerlemans, J., 1980. Model experiments on the 100,000-yr glacial cycle. *Nature*, 287:430–432.
- Oerlemans, J., R.P. Bassford, W. Chapman, J.A. Dowdeswell, A.F. Glazovsky, J.O. Hagen, K. Melvold, M.D. de Wildt and R.S.W. van de Wal, 2005. Estimating the contribution of Arctic glaciers to sea-level change in the next 100 years. *Annals of Glaciology*, 42:230–236.
- Ohmura, A., 1987. New temperature distribution maps for Greenland. *Zeitschrift für Gletscherkunde und Glazialgeologie*, 23:1–45.
- Ohmura, A. and N. Reeh, 1991. New precipitation and accumulation maps for Greenland. *Journal of Glaciology*, 37:140–148.
- Ohmura, A., P. Calanca, M. Wild and M. Anklin, 1999. Precipitation, accumulation and mass balance of the Greenland ice sheet. *Zeitschrift für Gletscherkunde und Glazialgeologie*, 35:1–19.
- Olsen, S.M. and T. Schmith, 2007. North Atlantic-Arctic Mediterranean exchanges in an ensemble hindcast experiment. *Journal of Geophysical Research-Oceans*, 112:C04010.
- Olsen, S.M., B. Hansen, D. Quadfasel and S. Østerhus, 2008. Observed and modelled stability of overflow across the Greenland-Scotland ridge. *Nature*, 455:519–522.
- Østerhus, S., W.R. Turrell, S. Jónsson and B. Hansen, 2005. Measured volume, heat, and salt fluxes from the Atlantic to the Arctic Mediterranean. *Geophysical Research Letters*, 32:L07603.
- Østerhus, S., T. Sherwin, D. Quadfasel and B. Hansen, 2008. The overflow transport east of Iceland. In: Dickson, R.R., J. Meincke and P. Rhines (Eds.). *Arctic-Subarctic Ocean Fluxes*, pp. 427–441, Springer Verlag.
- Otto-Bliesner, B.L., S.J. Marshall, J.T. Overpeck, G.H. Miller, A. Hu and CAPE Last Interglacial Project Members, 2006. Simulating arctic climate warmth and icefield retreat in the last interglaciation. *Science*, 311:1751–1753.
- Overland, J.E., M.C. Spillane and N.N. Soreide, 2004. Integrated analysis of physical and biological Pan-Arctic change. *Climatic Change*, 63:291–322.
- Paldam, M., 1994. Grønlands økonomiske udvikling - hvad skal der til for at lukke gabet? [in Danish]. 208 pp. University of Aarhus, Denmark.
- Parizek, B.R. and R.B. Alley, 2004. Implications of increased Greenland surface melt under global-warming scenarios: ice-sheet simulations. *Quaternary Science Reviews*, 23:1013–1027.
- Paterson, W.S.B., 1994. *The Physics of Glaciers*. 3rd edition. 481 pp. Reed Educational and Professional Publishing Ltd.
- Pattyn, F., 2002. Transient glacier response with a higher-order numerical ice-flow model. *Journal of Glaciology*, 48:467–477.
- Pattyn, F., 2003. A new three-dimensional higher-order thermomechanical ice sheet model: Basic sensitivity, ice stream development, and ice flow across subglacial lakes. *Journal of Geophysical Research-Solid Earth*, 108:2382.
- Payne, A.J., A. Vieli, A.P. Shepherd, D.J. Wingham and E. Rignot, 2004. Recent dramatic thinning of largest West Antarctic ice stream triggered by oceans. *Geophysical Research Letters*, 31:L23401.
- Pellicciotti, F., B. Brock, U. Strasser, P. Burlando, M. Funk and J. Corripio, 2005. An enhanced temperature-index glacier melt model including the shortwave radiation balance: development and testing for Haut Glacier d'Arolla, Switzerland. *Journal of Glaciology*, 51:573–587.
- Peltier, W.R., 2004. Global glacial isostasy and the surface of the ice-age earth: The ice-5G (VM2) model and grace. *Annual Review of Earth and Planetary Sciences*, 32:111–149.
- Peterson, B.J., J. McClelland, R. Curry, R.M. Holmes, J.E. Walsh and K. Agaard, 2006. Trajectory shifts in the Arctic and subarctic freshwater cycle. *Science*, 313:1061–1066.
- Pfeffer, W.T., 2007. A simple mechanism for irreversible tidewater glacier retreat. *Journal of Geophysical Research-Earth Surface*, 112:F03S25.
- Pfeffer, W.T., J.T. Harper and S. O'Neel, 2008. Kinematic constraints on glacier contributions to 21st-century sea-level rise. *Science*, 321:1340–1343.
- Podlech, S. and A. Weidick, 2004. Catastrophic break-up of the front of Jakobshavn Isbrae, West Greenland, 2002/03. Correspondence. *Journal of Glaciology*, 50:153–154.
- Poppel, B., 2007. Nogle forskelle mellem levevilkår i byer og bygder - og input til en diskussion om bygdernes fremtid. [in Danish] [Some differences between living conditions in towns and settlements - and input to the discussion about the future of the settlements]. *Samfundsøkonomen*, 1:19–24.
- Poppel, B. and J. Kruse, 2009. The importance of a mixed cash- and harvest herding based economy to living in the Arctic - an analysis based on Survey of Living Conditions in the Arctic (SLiCA). In: Møller, V. and D. Huscka (Eds.). *Quality of Life in the New Millennium: Advances in Quality-of-Life Studies, Theory and Research*, pp. 27–42, Springer Verlag.
- Price, S.F., A.J. Payne, G.A. Catania and T.A. Neumann, 2008. Seasonal acceleration of inland ice via longitudinal coupling to marginal ice. *Journal of Glaciology*, 54:213–219.
- Pritchard, H.D., R.J. Arthern, D.G. Vaughan and L.A. Edwards, 2009. Extensive dynamic thinning on the margins of the Greenland and Antarctic ice sheets. *Nature*, 461:971–975.
- Rahmstorf, S., 2007. A semi-empirical approach to projecting future sea-

- level rise. *Science*, 315:368–370.
- Rahmstorf, S., 2008. Response to comments on “A semi-empirical approach to projecting future sea-level rise”. *Science*, 317:1866d.
- Ramillien, G., A. Lombard, A. Cazenave, E.R. Ivins, M. Llubes, F. Remy and R. Biancale, 2006. Interannual variations of the mass balance of the Antarctica and Greenland ice sheets from GRACE. *Global and Planetary Change*, 53:198–208.
- Rasmussen, R.O., 1997. Arctic communities in transition. Experiences from North America and Greenland with Home Rule for Indigenous Peoples resource management. Nenets Autonomous Okrug, Naryan Mar, Russia.
- Rasmussen, R.O., 1998. Settlement structure, resource management, and sustainable development - Mega projects vs. local participation in Greenland. Paper presented at Sustainable Development in the North: Local Initiatives vs Megaprojects, pp. 47–87, Presses de l'Université Laval, Aguanish, Québec.
- Rasmussen, R.O., 2002. Food consumption patterns and local markets in the Arctic. In: Duhaime, G. (Ed.). *Sustainable Food Security in the Arctic: State of Knowledge*, pp. 117–144, CCI Press and GÉTIC.
- Rasmussen, R.O., 2005. Analyse af fangererhvervet i Grønland. [in Danish]. 158 pp. Grønlands Hjemmestyre, Direktoratet for Fangst og Fiskeri, Nuuk, Greenland.
- Rasmussen, R.O. and L.C. Hamilton, 2001. The Development of Fisheries in Greenland, with focus on Paamiut/Frederikshåb and Sisimiut/Holsteinsborg. NORS Research Report. 53:53 pp. Roskilde.
- Reeh, N., 1968. On the calving of ice from floating glaciers and ice shelves. *Journal of Glaciology*, 7:215–232.
- Reeh, N., 1991. Parameterization of melt rate and surface temperature on the Greenland ice sheet. *Polarforschung*, 59:113–128.
- Reeh, N., 1994. Calving from Greenland glaciers: Observations, balance estimates of calving rates, calving laws. Paper presented at Workshop on the Calving Rate of West Greenland Glaciers in Response to Climate Change, pp. 85–102, Danish Polar Center.
- Reeh, N., C.E. Bøggild and H. Oerter, 1994. Surge of Storstrømmen, a large outlet glacier from the inland ice of north-east Greenland. *Grønlands Geologiske Undersøgelse, Rapport*. 162:201–209. Grønlands Geologiske Undersøgelse, Copenhagen.
- Reeh, N., C. Mayer, H. Miller, H.H. Thomsen and A. Weidick, 1999. Present and past climate control on fjord glaciations in Greenland: Implications for IRD-deposition in the sea. *Geophysical Research Letters*, 26:1039–1042.
- Reeh, N., H.H. Thomsen, A.K. Higgins and A. Weidick, 2001. Sea ice and the stability of north and northeast Greenland floating glaciers. *Annals of Glaciology*, 33:474–480.
- Rhines, P.B. and S. Häkkinen, 2003. Is the oceanic heat transport in the North Atlantic irrelevant to the climate in Europe? *ASOF Newsletter*, 1:13–17.
- Rhines, P.B., S. Häkkinen and S.A. Josey, 2008. Is oceanic heat transport significant in the climate system? In: Dickson, R.R., J. Meincke and P. Rhines (Eds.). *Arctic-Subarctic Ocean Fluxes. Defining the Role of Northern Seas in Climate*, pp. 87–109, Springer Verlag.
- Rial, J.A., C. Tang and K. Steffen, 2009. Glacial rumblings from Jakobshavn ice stream, Greenland. *Journal of Glaciology*, 55:389–399.
- Ridley, J.K., P. Huybrechts, J.M. Gregory and J.A. Lowe, 2005. Elimination of the Greenland ice sheet in a high CO₂ climate. *Journal of Climate*, 18:3409–3427.
- Ridley, J., J. Gregory, P. Huybrechts and J. Lowe, 2010. Thresholds for irreversible decline of the Greenland ice sheet. *Climate Dynamics*, 35:1049–1057.
- Rignot, E., 1996. Tidal motion, ice velocity and melt rate of Petermann Gletscher, Greenland, measured from radar interferometry. *Journal of Glaciology*, 42:476–485.
- Rignot, E. and S.S. Jacobs, 2002. Rapid bottom melting widespread near Antarctic ice sheet grounding lines. *Science*, 296:2020–2023.
- Rignot, E. and P. Kanagaratnam, 2006. Changes in the velocity structure of the Greenland ice sheet. *Science*, 311:986–990.
- Rignot, E. and K. Steffen, 2008. Channelized bottom melting and stability of floating ice shelves. *Geophysical Research Letters*, 35:L02503.
- Rignot, E.J., S.P. Gogineni, W.B. Krabill and S. Ekholm, 1997. North and northeast Greenland ice discharge from satellite radar interferometry. *Science*, 276:934–937.
- Rignot, E., J.E. Box, E. Burgess and E. Hanna, 2008. Mass balance of the Greenland ice sheet from 1958 to 2007. *Geophysical Research Letters*, 35:L20502.
- Rignot, E., M. Koppes and I. Velicogna, 2010. Rapid submarine melting of the calving faces of West Greenland glaciers. *Nature Geoscience*, 3:187–191.
- Rinke, A. and K. Dethloff, 2008. Simulated circum-Arctic climate changes by the end of the 21st century. *Global and Planetary Change*, 62:173–186.
- Ritchie, J.B., C.S. Lingle, R.J. Motyka and M. Truffer, 2008. Seasonal fluctuations in the advance of a tidewater glacier and potential causes: Hubbard Glacier, Alaska, USA. *Journal of Glaciology*, 54:401–411.
- Ritz, C., A. Fabre and A. Letréguilly, 1997. Sensitivity of a Greenland ice sheet model to ice flow and ablation parameters: Consequences for the evolution through the last climatic cycle. *Climate Dynamics*, 13:11–24.
- Robock, A. and J.P. Mao, 1995. The volcanic signal in surface temperature observations. *Journal of Climate*, 8:1086–1103.
- Rohling, E.J., K. Grant, M. Bolshaw, A.P. Roberts, M. Siddall, C. Hemleben and M. Kucera, 2009. Antarctic temperature and global sea level closely coupled over the past five glacial cycles. *Nature Geoscience*, 2:500–504.
- Röthlisberger, H., 1972. Water pressure in intra- and subglacial channels. *Journal of Glaciology*, 11:177–203.
- Rotschky, G., O. Eisen, F. Wilhelms, U. Nixdorf and H. Oerter, 2004. Spatial distribution of surface mass balance on Amundsenisen plateau, Antarctica, derived from ice-penetrating radar studies. *Annals of Glaciology*, 39:265–270.
- Rudels, B., 1989. The formation of Polar Surface Water, the ice export and the exchanges through the Fram Strait. *Progress in Oceanography*, 22:205–248.
- Rysgaard, S., T.G. Nielsen and B.W. Hansen, 1999. Seasonal variation in nutrients, pelagic primary production and grazing in a high-Arctic coastal marine ecosystem, Young Sound, Northeast Greenland. *Marine Ecology Progress Series*, 179:13–25.
- Rysgaard, S., T. Vang, M. Stjernholm, B. Rasmussen, A. Windelin and S. Kiilsholm, 2003. Physical conditions, carbon transport, and climate change impacts in a northeast Greenland fjord. *Arctic, Antarctic and Alpine Research*, 35:301–312.
- Rysgaard, S., R.N. Glud, M.K. Sej, M.E. Blicher and H.J. Stahl, 2008. Denitrification activity and oxygen dynamics in Arctic sea ice. *Polar Biology*, 31:527–537.
- Saito, F., A. Abe-Ouchi and H. Blatter, 2003. Effects of first-order stress gradients in an ice sheet evaluated by a three-dimensional thermomechanical coupled model. *Annals of Glaciology*, 37:166–172.
- Saunders, P.M., 2001. The dense northern overflows. In: Siedler, G., J. Church and J. Gould (Eds.). *Ocean Circulation and Climate: Observing and Modelling the Global Ocean*, pp. 401–417, Academic Press.
- Schmith, T., S. Johansen and P. Thejll, 2007. Comment on “A semi-empirical approach to projecting future sea-level rise”. *Science*, 317:1866.
- Schmittner, A., 2005. Decline of the marine ecosystem caused by a reduction in the Atlantic overturning circulation. *Nature*, 434:628–633.
- Schneeberger, C., O. Albrecht, H. Blatter, M. Wild and R. Hock, 2001. Modelling the response of glaciers to a doubling in atmospheric CO₂: a case study of Storglaciaren, northern Sweden. *Climate Dynamics*, 17:825–834.
- Schoof, C., 2007. Ice sheet grounding line dynamics: Steady states, stability, and hysteresis. *Journal of Geophysical Research-Earth Surface*, 112:F03S28.
- Sclater, J.G., C. Jaupart and D. Galson, 1980. The heat flow through oceanic and continental crust and the heat loss of the Earth. *Reviews of Geophysics*, 18:269–311.
- Seager, R., D.S. Battisti, J. Yin, N. Gordon, N. Naik, A.C. Clement and M.A. Cane, 2002. Is the Gulf Stream responsible for Europe's mild winters? *Quarterly Journal of the Royal Meteorological Society*, 128:2563–2586.
- Serreze, M.C. and J.A. Francis, 2006. The arctic amplification debate. *Climatic Change*, 76:241–264.
- Shreve, R.L., 1972. Movement of water in glaciers. *Journal of Glaciology*, 11:205–214.
- Shuman, C.A., M.A. Fahnestock, R.A. Bindschadler, R.B. Alley and C.R. Stearns, 1996. Composite temperature record from the Greenland summit, 1987–1994: Synthesis of multiple automatic weather station records and SSM/I brightness temperatures. *Journal of Climate*, 9:1421–1428.
- Shuman, C.A., D.H. Bromwich, J. Kipfstuhl and M. Schwager, 2001.

- Multiyear accumulation and temperature history near the North Greenland Ice Core Project site, north central Greenland. *Journal of Geophysical Research-Atmospheres*, 106:33853–33866.
- Siddall, M., E.J. Rohling, A. Almogi-Labin, C. Hemleben, D. Meischner, I. Schmelzer and D.A. Smeed, 2003. Sea-level fluctuations during the last glacial cycle. *Nature*, 423:853–858.
- Simonsen, K. and P.M. Haugan, 1996. Heat budgets of the Arctic Mediterranean and sea surface heat flux parameterizations for the Nordic Seas. *Journal of Geophysical Research-Oceans*, 101:6553–6576.
- Slobbe, D.C., P. Ditmar and R.C. Lindenbergh, 2009. Estimating the rates of mass change, ice volume change and snow volume change in Greenland from ICESat and GRACE data. *Geophysical Journal International*, 176:95–106.
- Sohn, H.G., K.C. Jezek and C.J. van der Veen, 1998. Jakobshavn Glacier, West Greenland: 30 years of spaceborne observations. *Geophysical Research Letters*, 25:2699–2702.
- Stearns, L.A. and G.S. Hamilton, 2007. Rapid volume loss from two East Greenland outlet glaciers quantified using repeat stereo satellite imagery. *Geophysical Research Letters*, 34:L05503.
- Steffen, K. and J. Box, 2001. Surface climatology of the Greenland ice sheet: Greenland climate network 1995–1999. *Journal of Geophysical Research-Atmospheres*, 106:33951–33964.
- Steffen, K., P.U. Clark, J.G. Cogley, D. Holland, S. Marshall, E. Rignot and R. Thomas, 2008. Rapid changes in glaciers and ice sheets and their impacts on sea level. *Abrupt Climate Change. A Report by the U.S. Climate Change Science Program and the Subcommittee on Global Change Research*, pp. 60–142, U.S. Climate Change Science Program and the Subcommittee on Global Change Research, Washington, D.C.
- Steffensen, J.P., K.K. Andersen, M. Bigler, H.B. Clausen, D. Dahl-Jensen, H. Fischer, K. Goto-Azuma, M. Hansson, S.J. Johnsen, J. Jouzel, V. Masson-Delmotte, T. Popp, S.O. Rasmussen, R. Rothlisberger, U. Ruth, B. Stauffer, M.L. Siggaard-Andersen, A.E. Sveinbjörnsdóttir, A. Svensson and J.W.C. White, 2008. High-resolution Greenland Ice Core data show abrupt climate change happens in few years. *Science*, 321:680–684.
- Stenchikov, G., K. Hamilton, R.J. Stouffer, A. Robock, V. Ramaswamy, B. Santer and H.F. Graf, 2006. Arctic Oscillation response to volcanic eruptions in the IPCC AR4 climate models. *Journal of Geophysical Research-Atmospheres*, 111:D07107.
- Stendel, M., J.H. Christensen, G. Aalgeirsdóttir, N. Kliem and M. Drews, 2007. Regional climate change for Greenland and surrounding seas. Part I: Atmosphere and land surface DMI Climate Centre Report. 07-02:26 pp. Danish Meteorological Institute, Copenhagen, Denmark.
- Stendel, M., J.H. Christensen and D. Petersen, 2008. Arctic climate and climate change with a focus on Greenland. In: Meltofte, H., T.R. Christensen, B. Elberling, M.C. Forchhammer and M. Rasch (Eds.). *High Arctic Ecosystem Dynamics in a Changing Climate. Ten years of monitoring and research at Zackenberg Research station, Northeast Greenland*, pp. 13–43, Academic Press.
- Stigebrandt, A., 2000. Oceanic freshwater fluxes in the climate system. In: Lewis, E.L., E.P. Jones, P. Lemke, T.P. Prowse and P. Wadhams (Eds.). *The Freshwater Budget of the Arctic Ocean*, pp. 1–20, Kluwer Academic Publishers.
- Stirling, C.H., T.M. Esat, K. Lambeck and M.T. McCulloch, 1998. Timing and duration of the Last Interglacial: evidence for a restricted interval of widespread coral reef growth. *Earth and Planetary Science Letters*, 160:745–762.
- Stober, M. and J. Hepperle, 2006. Changes in ice elevation and ice flow-velocity in the Swiss Camp area (West Greenland) between 1991 and 2006. *Polarforschung*, 76:109–118.
- Storey, K. and L.C. Hamilton, 2003. Planning for the impacts of megaprojects. In: Rasmussen, R.O. and N.E. Koroleva (Eds.). *Social and Environmental Impacts in the North*, 544 pp, Kluwer Academic Publishers.
- Stott, P.A., J.A. Kettleborough and M.R. Allen, 2006. Uncertainty in continental-scale temperature predictions. *Geophysical Research Letters*, 33:L02708.
- Straneo, F., G.S. Hamilton, D.A. Sutherland, L.A. Stearns, F. Davidson, M.O. Hammill, G.B. Stenson and A. Rosing-Asvid, 2010. Rapid circulation of warm subtropical waters in a major glacial fjord in East Greenland. *Nature Geoscience*, 3:182–186.
- Stroeve, J., 2001. Assessment of Greenland albedo variability from the advanced very high resolution radiometer Polar Pathfinder data set. *Journal of Geophysical Research-Atmospheres*, 106:33989–34006.
- Stroeve, J., M.M. Holland, W. Meier, T. Scambos and M. Serreze, 2007. Arctic sea ice decline: Faster than forecast. *Geophysical Research Letters*, 34:L09501.
- Sutton, R.T. and D.L.R. Hodson, 2005. Atlantic Ocean forcing of North American and European summer climate. *Science*, 309:115–118.
- Svendsen, H., A. Beszczynska-Møller, J.O. Hagen, B. Lefauconnier, V. Tverberg, S. Gerland, J.B. Ørbæk, K. Bischof, C. Papucci, M. Zajaczkowski, R. Azzolini, O. Bruland, C. Wiencke, J.G. Winther and W. Dallmann, 2002. The physical environment of Kongsfjorden-Krossfjorden, an Arctic fjord system in Svalbard. *Polar Research*, 21:133–166.
- Svensson, A., K.K. Andersen, M. Bigler, H.B. Clausen, D. Dahl-Jensen, S.M. Davies, S.J. Johnsen, R. Muscheler, S.O. Rasmussen, R. Rothlisberger, J.P. Steffensen and B.M. Vinther, 2006. The Greenland Ice Core Chronology 2005, 15–42 ka. Part 2: comparison to other records. *Quaternary Science Reviews*, 25:3258–3267.
- Tapley, B.D., S. Bettadpur, J.C. Ries, P.F. Thompson and M.M. Watkins, 2004a. GRACE measurements of mass variability in the Earth system. *Science*, 305:503–505.
- Tapley, B.D., S. Bettadpur, M. Watkins and C. Reigber, 2004b. The gravity recovery and climate experiment: Mission overview and early results. *Geophysical Research Letters*, 31:L09607.
- Tarasov, L. and W.R. Peltier, 2002. Greenland glacial history and local geodynamic consequences. *Geophysical Journal International*, 150:198–229.
- Tarasov, L. and W.R. Peltier, 2005. Arctic freshwater forcing of the Younger Dryas cold reversal. *Nature*, 435:662–665.
- Tedesco, M., 2007. Snowmelt detection over the Greenland ice sheet from SSM/I brightness temperature daily variations. *Geophysical Research Letters*, 34:L02504.
- Thomas, R.H., 2004. Force-perturbation analysis of recent thinning and acceleration of Jakobshavn Isbrae, Greenland. *Journal of Glaciology*, 50:57–66.
- Thomas, R., T. Akins, B. Csatho, M. Fahnestock, P. Gogineni, C. Kim and J. Sonntag, 2000. Mass balance of the Greenland ice sheet at high elevations. *Science*, 289:426–428.
- Thomas, R.H., W. Abdalati, E. Frederick, W.B. Krabill, S. Manizade and K. Steffen, 2003. Investigation of surface melting and dynamic thinning on Jakobshavn Isbrae, Greenland. *Journal of Glaciology*, 49:231–239.
- Thomas, R., E. Frederick, W. Krabill, S. Manizade and C. Martin, 2006. Progressive increase in ice loss from Greenland. *Geophysical Research Letters*, 33:L10503.
- Thomas, R., C. Davis, E. Frederick, W. Krabill, Y.H. Li, S. Manizade and C. Martin, 2008. A comparison of Greenland ice-sheet volume changes derived from altimetry measurements. *Journal of Glaciology*, 54:203–212.
- Toniazzi, T., J.M. Gregory and P. Huybrechts, 2004. Climatic impact of a Greenland deglaciation and its possible irreversibility. *Journal of Climate*, 17:21–33.
- Toudal, L. and D. Coon, 2001. Interannual variability of the sea-ice-induced salt flux in the Greenland Sea. *Annals of Glaciology*, 33:385–390.
- Trenberth, K.E. and J.M. Caron, 2001. Estimates of meridional atmosphere and ocean heat transports. *Journal of Climate*, 14:3433–3443.
- Truffer, M. and K.A. Echelmeyer, 2003. Of isbrae and ice streams. *Annals of Glaciology*, 36:66–72.
- Truffer, M., W.D. Harrison and R.S. March, 2005. Record negative glacier balances and low velocities during the 2004 heatwave in Alaska, USA: implications for the interpretation of observations by Zwally and others in Greenland. Correspondence. *Journal of Glaciology*, 51:663–664.
- Tsai, V.C. and G. Ekström, 2007. Analysis of glacial earthquakes. *Journal of Geophysical Research-Earth Surface*, 112:F03S22.
- Udvalget om Socioøkonomiske Virkninger af Olie- og Gasudvinding samt Mineralindustri, 1997. Rapport om de Socioøkonomiske virkninger af råstofudvinding: En indledende kortlægning og forslag til videre arbejde. [in Danish]. www.kamikposten.dk/default.aspx?udvalgt=1997102800&folder=hvaderneningen&prog=da&tag=alleartikler.
- Uppala, S.M., P.W. Kallberg, A.J. Simmons and 43 others, 2005. The ERA-40 re-analysis. *Quarterly Journal of the Royal Meteorological Society*, 131:2961–3012.
- van de Berg, W.J., M.R. van den Broeke, C.H. Reijmer and E. van Meijgaard,

2006. Reassessment of the Antarctic surface mass balance using calibrated output of a regional atmospheric climate model. *Journal of Geophysical Research-Atmospheres*, 111:D11104.
- van de Wal, R.S.W. and J. Oerlemans, 1997. Modelling the short-term response of the Greenland ice-sheet to global warming. *Climate Dynamics*, 13:733-744.
- van de Wal, R.S.W., M. Wild and J. De Wolde, 2001. Short-term volume changes of the Greenland ice sheet in response to doubled CO₂ conditions. *Tellus Series B-Chemical and Physical Meteorology*, 53:94-102.
- van de Wal, R.S.W., W. Greuell, M.R. van den Broeke, C.H. Reijmer and J. Oerlemans, 2005. Surface mass-balance observations and automatic weather station data along a transect near Kangerlussuaq, West Greenland. *Annals of Glaciology*, 42:311-316.
- van de Wal, R.S.W., W. Boot, M.R. van den Broeke, C. Smeets, C.H. Reijmer, J.J.A. Donker and J. Oerlemans, 2008. Large and rapid melt-induced velocity changes in the ablation zone of the Greenland Ice Sheet. *Science*, 321:111-113.
- van den Broeke, M., J. Bamber, J. Ettema, E. Rignot, E. Schrama, W.J. van de Berg, E. van Meijgaard, I. Velicogna and B. Wouters, 2009. Partitioning recent Greenland mass loss. *Science*, 326:984-986.
- van der Veen, C.J., 1999. *Fundamentals of Glacier Dynamics*. 462 pp. A.A. Balkema, Rotterdam.
- van der Veen, C.J. and ISMASS, 2007. A need for more realistic ice-sheet models. 27 pp. SCAR Report.
- van der Veen, C.J., T. Leftwich, R. von Frese, B.M. Csatho and J. Li, 2007. Subglacial topography and geothermal heat flux: Potential interactions with drainage of the Greenland ice sheet. *Geophysical Research Letters*, 34:L12501.
- Velicogna, I., 2009. Increasing rates of ice mass loss from the Greenland and Antarctic ice sheets revealed by GRACE. *Geophysical Research Letters*, 36:L19503.
- Velicogna, I. and J. Wahr, 2005. Greenland mass balance from GRACE. *Geophysical Research Letters*, 32:L18505.
- Velicogna, I. and J. Wahr, 2006. Acceleration of Greenland ice mass loss in spring 2004. *Nature*, 443:329-331.
- Vellinga, M. and R.A. Wood, 2002. Global climatic impacts of a collapse of the Atlantic thermohaline circulation. *Climatic Change*, 54:251-267.
- Vellinga, M., B. Dickson and R. Curry, 2008. The changing view on how freshwater impacts the Atlantic meridional overturning circulation. In: Dickson, R.R., J. Meincke and P. Rhines (Eds.). *Arctic-Subarctic Ocean Fluxes. Defining the Role of Northern Seas in Climate*, pp. 289-313, Springer Verlag.
- Viel, A., M. Funk and H. Blatter, 2001. Flow dynamics of tidewater glaciers: a numerical modelling approach. *Journal of Glaciology*, 47:595-606.
- Vinther, B.M., K.K. Andersen, P.D. Jones, K.R. Briffa and J. Cappelén, 2006. Extending Greenland temperature records into the late eighteenth century. *Journal of Geophysical Research-Atmospheres*, 111:D11105.
- Vinther, B.M., S.L. Buchardt, H.B. Clausen, D. Dahl-Jensen, S.J. Johnsen, D.A. Fisher, R.M. Koerner, D. Raynaud, V. Lipenkov, K.K. Andersen, T. Blunier, S.O. Rasmussen, J.P. Steffensen and A.M. Svensson, 2009. Holocene thinning of the Greenland ice sheet. *Nature*, 461:385-388.
- Vinther, B.M., P.D. Jones, K.R. Briffa, H.B. Clausen, K.K. Andersen, D. Dahl-Jensen and S.J. Johnsen, 2010. Climatic signals in multiple highly resolved stable isotope records from Greenland. *Quaternary Science Reviews*, 29:522-538.
- Visbeck, M., J. Fischer and F. Schott, 1995. Preconditioning the Greenland Sea for deep convection: Ice formation and drift. *Journal of Geophysical Research-Oceans*, 100:18489-18502.
- Vizcaíno, M., U. Mikolajewicz, M. Groger, E. Maier-Reimer, G. Schurgers and A.M.E. Winguth, 2008. Long-term ice sheet-climate interactions under anthropogenic greenhouse forcing simulated with a complex Earth System Model. *Climate Dynamics*, 31:665-690.
- Vizcaíno, M., U. Mikolajewicz, J. Jungclauss and G. Schurgers, 2010. Climate modification by future ice sheet changes and consequences for ice sheet mass balance. *Climate Dynamics*, 34:301-324.
- von Storch, H., E. Zorita and J.F. González-Rouco, 2008. Relationship between global mean sea-level and global mean temperature in a climate simulation of the past millennium. *Ocean Dynamics*, 58:227-236.
- Walsh, J.E., W.L. Chapman, V. Romanovsky, J.H. Christensen and M. Stendel, 2008. Global climate model performance over Alaska and Greenland. *Journal of Climate*, 21:6156-6174.
- Warren, C.R., 1991. Terminal environment, topographic control and fluctuations of West Greenland glaciers. *Boreas*, 20:1-15.
- Weidick, A., 1993. Neoglacial change of ice cover and the related response of the Earth's crust in West Greenland. *Grønlands Geologiske Undersøgelser*, 159:121-126.
- Weidick, A., 1995. Greenland (with a section on Landsat images of Greenland by R.S. Williams, Jr. & J.G. Ferrigno). *Satellite image atlas of glaciers of the world*. U.S. Geological Survey Professional Paper, 1386-C:1-141.
- Weidick, A. and O. Bennike, 2007. Quaternary glaciation history and glaciology of Jakobshavn Isbrae and the Disko Bugt region, West Greenland: A review. *Geological Survey of Denmark and Greenland Bulletin*:1-13.
- Weidick, A., H. Oerter, N. Reeh, H.H. Thomsen and L. Thorning, 1990. The recession of the Inland Ice margin during the Holocene climatic optimum in the Jakobshavn Isfjord area of West Greenland. *Global and Planetary Change*, 82:389-399.
- Wilkinson, D. and S. Bacon, 2005. The spatial and temporal variability of the East Greenland Coastal Current from historic data. *Geophysical Research Letters*, 32:L24618.
- Willerslev, E., E. Cappellini, W. Boomsma and 27 others, 2007. Ancient biomolecules from deep ice cores reveal a forested Southern Greenland. *Science*, 317:111-114.
- Winguth, A., U. Mikolajewicz, M. Gröger, E. Maier-Reimer, G. Schurgers and M. Vizcaíno, 2005. Centennial-scale interactions between the carbon cycle and anthropogenic climate change using a dynamic Earth system model. *Geophysical Research Letters*, 32:L23714.
- Winther, G., 1999. The affinity between ownership mechanisms and social coordination mechanisms in Greenland. In: Petersen, H. and B. Poppel (Eds.). *Dependency, Autonomy, Sustainability in the Arctic*. Part II., pp. 61-70, Ashgate Publishing Company.
- Winther, G., 2001. Participatory ownership and management in Greenland and other circumpolar regions. *Proceedings from a Network Seminar in Ilulissat*. INUSSUK Arctic Research Journal, Part 1:7-22.
- Witze, A., 2008. Climate change: Losing Greenland. *Nature*, 452:798-802.
- Wouters, B., D. Chambers and E.J.O. Schrama, 2008. GRACE observes small-scale mass loss in Greenland. *Geophysical Research Letters*, 35:L20501.
- Wright, A.P., J.L. Wadham, M.J. Siegert, A. Luckman, J. Kohler and A.M. Nuttall, 2007. Modeling the refreezing of meltwater as superimposed ice on a high Arctic glacier: A comparison of approaches. *Journal of Geophysical Research-Earth Surface*, 112:F04016.
- Wu, X., M.B. Heflin, H. Schotman, B.L.A. Vermeersen, D. Dong, R.S. Gross, E.R. Ivins, M. A.W. and S.E. Owen, 2010. Simultaneous estimation of global present-day water transport and glacial isostatic adjustment. *Nature Geoscience*, 13:642-646.
- Wunsch, C., 2008. Mass and volume transport variability in an eddy-filled ocean. *Nature Geoscience*, 1:165-168.
- Yashayaev, I., N.P. Holliday, M. Bersch and H.M. van Aken, 2008. The history of the Labrador Sea Water: Production, spreading, transformation and loss. In: Dickson, R.R., J. Meincke and P. Rhines (Eds.). *Arctic-Subarctic Ocean Fluxes. Defining the Role of Northern Seas in Climate*, pp. 569-612, Springer Verlag.
- Zelarney, P.T. and J.A. Ciarlo, 2000. Defining and describing frontier areas in the United States: An update letter to the field. 22. www.wiche.edu/MentalHealth/Frontier/letter22.asp.
- Zwally, H.J., B. Schutz, W. Abdalati, J. Abshire, C. Bentley, A. Brenner, J. Bufton, J. Dezio, D. Hancock, D. Harding, T. Herring, B. Minster, K. Quinn, S. Palm, J. Spinhrine and R. Thomas, 2002a. ICESat's laser measurements of polar ice, atmosphere, ocean, and land. *Journal of Geodynamics*, 34:405-445.
- Zwally, H.J., W. Abdalati, T. Herring, K. Larson, J. Saba and K. Steffen, 2002b. Surface melt-induced acceleration of Greenland ice-sheet flow. *Science*, 297:218-222.
- Zwally, H.J., M.B. Giovinetto, J. Li, H.G. Cornejo, M.A. Beckley, A.C. Brenner, J.L. Saba and D.H. Yi, 2005. Mass changes of the Greenland and Antarctic ice sheets and shelves and contributions to sea-level rise: 1992-2002. *Journal of Glaciology*, 51:509-527.
- Zweck, C. and P. Huybrechts, 2005. Modeling of the northern hemisphere ice sheets during the last glacial cycle and glaciological sensitivity. *Journal of Geophysical Research-Atmospheres*, 110:D07103.

9. Sea Ice

COORDINATING LEAD AUTHORS: WALTER N. MEIER, SEBASTIAN GERLAND, MATS A. GRANSKOG, JEFFREY R. KEY

SECTION 9.1

LEAD AUTHORS: WALTER N. MEIER, CHRISTIAN HAAS

CONTRIBUTING AUTHORS: DAVID BARBER, CECILIA BITZ, HAJO EICKEN, SEBASTIAN GERLAND, MARIKA HOLLAND, JUN INOUE, FRANK KAUKER, TAKASHI KIKUCHI, RON KWOK, SEYMOUR LAXON, RONALD LINDSAY, ANDY MAHONEY, JAMES MASLANIK, MARCEL NICOLAUS, JAMES OVERLAND, LEIF T. PEDERSEN, IGOR POLYAKOV, SIMON PRINSENBERG, KOJI SHIMADA, VASILY SMOLYANITSKY, MATTHEW STURM, TIMO VIHMA, STEPHEN G. WARREN, MARK WENSNAHAN, JINLUN ZHANG

SECTION 9.2

LEAD AUTHORS: DONALD PEROVICH, ALEXANDER MAKSHITAS

CONTRIBUTING AUTHORS: GENRIKH ALEKSEEV, DAVID BARBER, HAJO EICKEN, MARIKA HOLLAND, STEVEN HUDSON, JANET INTRIERI, JEFFREY KEY, RONALD LINDSAY, SON NGHIEM, DIRK NOTZ, JAMES OVERLAND, CHRISTINA PEDERSEN, MATTHEW SHUPE, JINLUN ZHANG

SECTION 9.3

LEAD AUTHORS: KIT M. KOVACS, CHRISTINE MICHEL

CONTRIBUTING AUTHORS: BODIL BLUHM, TONY GASTON, ROLF GRADINGER, GEORGE HUNT, SUE E. MOORE, PAUL RENAUD, SØREN RYSGAARD

SECTION 9.4

LEAD AUTHORS: BOB E.H. VAN OORT, GRETE K. HOVELSRUD, JAMES D. REIST

CONTRIBUTING AUTHORS: DEREK ARMITAGE, MICHAEL BAFFREY, HAJO EICKEN, DONALD FORBES, JAMES FORD, SHARI GEARHEARD, ANDREA GRANT-FRIEDMAN, HENRY HUNTINGTON, LENE KIELSEN-HOLM, JAMES KUPTANA, AMY LOVECRAFT, DONALD PEROVICH, STEVEN SOLOMON[†]

Contents

Key Findings	2	9.3. Biological impacts of changes in sea ice in the Arctic ..	32
Summary	2	9.3.1. Sea ice and Arctic marine ecosystems	32
9.1. Changes in the physical state of sea ice	4	9.3.2. Ice as a structuring element of polar marine ecosystems	38
9.1.1. Introduction	4	9.3.3. Observations to date regarding ecosystem impacts ...	40
9.1.2. Arctic-wide changes in sea-ice extent, age, and thickness .	4	9.3.4. Looking into the future	46
9.1.3. Seasonal changes in sea ice	11	9.3.5. Knowledge gaps and critical research needs	50
9.1.4. Regional changes in sea ice	12	9.4. Effects of sea-ice change on human society	52
9.1.5. Observations and importance of snow thickness	15	9.4.1. Introduction	53
9.1.6. Changes in factors controlling sea-ice extent and thickness	15	9.4.2. ACIA status of knowledge	54
9.1.7. Modeling: Comparing model output with observational data	17	9.4.3. Current local and scientific observations	55
9.2. Physical feedbacks and forcings	19	9.4.4. Current human interactions with sea ice	55
9.2.1. Introduction	19	9.4.5. Anticipated consequences of sea-ice change	58
9.2.2. The ice-albedo feedback	19	9.4.6. Governance	67
9.2.3. Impacts of black carbon on the sea-ice albedo	21	9.4.7. Adaptation	68
9.2.4. Importance and role of local-scale sea-ice features ...	22	9.4.8. Feedback of human activity to sea-ice change	70
9.2.5. The cloud-radiation feedback and its impact on the surface-heat budget	23	Acknowledgments	70
9.2.6. Feedbacks and forcings related to changes in atmospheric transport	27	References	70
9.2.7. Projection: Impact of feedbacks on rate of sea-ice decay	29		
9.2.8. Negative feedbacks	29		
9.2.9. Thresholds, tipping points and rates of change	30		

Key Findings

- The decline in Arctic summer sea-ice extent has accelerated over the past ten years. The retreat is faster than previously predicted by IPCC models and summer ice-free conditions are likely over most of the Arctic basin by mid-century or earlier.
- Newly developed estimates of sea-ice age, basin-scale sea-ice thickness, and sea-ice volume indicate thinning of the ice cover and loss of old ice types.
- Recent research has better quantified some interactions between the sea ice, ocean, and atmosphere, particularly during the extreme summer ice loss of 2007.
- Predictions of seasonal sea-ice extent are highly variable on a regional basis. Environmental conditions and bathymetry are also highly variable on a regional basis. In combination, these factors will strongly affect the impacts of climate warming on Arctic biological systems.
- The extinction of some Arctic endemic species is likely if current sea-ice trends continue. These losses will represent biodiversity losses of global significance, and reverse millions of years of evolutionary change (since the beginning of the Pleistocene). Northward range expansions for some temperate species and potentially greater overall productivity will enhance foraging opportunities for some animals within High Arctic areas, at a cost to Arctic endemic populations.
- The responses of Arctic endemic cetaceans to changing sea-ice conditions will be influenced by food availability, competition from non-endemic migrant cetaceans and, in some regions, the potential for increased predation from killer whales.
- Indigenous and some local peoples have been challenged by changes in sea ice and those challenges will continue into the future.
- Reduced seasonal sea-ice presence is already leading to greater shoreline exposure to open water and storm waves. These changes impose greater wave and erosion hazards for shoreline, infrastructure, waterfront structures, and cultural heritage sites in some places.
- Loss of sea ice is increasing interest in access and resource rights, such as shipping, resource extraction, military operations, and tourism, which will have impacts across a wide-range of issues.
- Hazards related to sea-ice movement (ride-up and pile-up) onshore are known to have caused fatalities and significant infrastructure damage in the past.
- There are clear limits to any Arctic governance regime (regulatory or soft-law). The drivers of sea-ice change and its consequences occur largely outside the region and fall beyond the jurisdiction of any one Arctic state, and responding to sea-ice change creates profound governance challenges.

Summary

Arctic sea ice has thinned and summer extent has been at or near record low levels almost every year since 2001. Model projections made during the Fourth Assessment of the Intergovernmental Panel on Climate Change (IPCC), indicating near-complete loss of summer sea ice by the end of this century are too conservative (Stroeve et al., 2007) and summers with little or no sea ice in the Arctic are now considered likely by mid-century, possibly sooner (Wang and Overland, 2009). Such a fundamental change in the Arctic environment will have substantial impacts on the Earth's radiation balance and atmospheric and oceanic circulation patterns. Feedbacks in the sea-ice climate system are mostly positive, meaning that the decline in sea ice is having an amplifying effect on the global climate system. The effects of the changing sea-ice environment are already being felt by the plants, animals, and human societies living or operating in the Arctic. The flora and fauna of the Arctic region will need to adapt to changing sea-ice conditions or face extinction. There will also be impacts on human activities in the region, ranging from those undertaken by indigenous Arctic peoples to commercial activities (shipping, resource extraction), tourism, and sovereignty.

Climate change is occurring faster in the Arctic than anywhere else in the world. The rate of increase in Arctic surface air temperature has been about twice the global average over the past few decades (Solomon et al., 2007; Chylek et al., 2009) and this is often referred to as the 'Arctic amplification' (Serreze et al., 2009). The Arctic is a bellwether of change in global climate primarily because of the sensitivity of the thin sea-ice cover – which insulates the comparatively warm ocean from the much colder atmosphere – to changes in air temperature and winds. This sensitivity is enhanced by climate feedbacks associated with a changing cryosphere. Dramatic changes are occurring across the Arctic; one of the most visible indicators of this change is the transformation in the sea-ice cover and the associated impacts on climate, ecosystems, and human societies.

The Arctic sea-ice cover is in decline. There has been a well documented recent retreat of the summer ice cover (Serreze et al., 2007; Comiso et al., 2008), a general thinning of the ice (Giles et al., 2008; Haas et al., 2008; Rothrock et al., 2008; Kwok et al., 2009), and a transition to a younger and more vulnerable ice pack (Maslanik et al., 2007; Barber et al., 2009; Nghiem et al., 2007b). September sea-ice extent reached a record minimum in 2007 (Stroeve et al., 2007) and has since been followed by the second (2011; Figure 9.1), third (2008), fourth (2010) and fifth (2009) smallest observed ice extents since the start of the satellite record in 1979 (Fetterer et al., 2011). In fact, the seven summers since the publication of the Arctic Climate Impact Assessment Report (2005 to 2011) have experienced the six lowest sea-ice extents in the satellite record (since 1979), accelerating an already significant multi-decadal decline. While not every year has experienced a record low minimum extent, the loss of the oldest (5+ years) ice types has continued, particularly in Canada Basin (based on updated data from Maslanik et al., 2007). Because of the less extreme summers of 2008 and 2009 and low transport of ice out of the central Arctic through the 2009/10 and 2010/11 winters, there was a replenishment of younger (2- to 3-year old) multi-

year ice (ice that has survived at least one melt season). This highlights the large year-to-year variability in the Arctic sea-ice cover that is superimposed on the long-term declining trends (Haas et al., 2010).

Several factors may have contributed to the decline in sea-ice cover: a general warming (Richter-Menge et al., 2006), changes in cloudiness (Francis et al., 2005; Kay et al., 2008), changes in atmospheric circulation patterns (Rigor and Wallace, 2004), increased ice drift speed (Rampal et al., 2009) and ice export from the Arctic (Kwok et al., 2010) due to changes in ice dynamics, ocean heat advection from lower latitudes (Shimada et al., 2006; Polyakov et al., 2007; Woodgate et al., 2010), and enhanced solar heating of the upper ocean (Perovich et al., 2007, 2008; Steele et al., 2008). Key feedback processes affecting sea-ice cover include the ice-albedo feedback (e.g., Perovich et al., 2008) and the cloud-radiation feedback (e.g., Hanesiak et al., 2001; Kay et al., 2008; Liu et al., 2009), which may further amplify the projected rate of change.

Sea ice plays a key role for Arctic ecosystems by providing habitat for marine mammals and for a diverse range of productive communities that live within or in association with sea ice. The Arctic also has the most extensive coastal shelves of all the world's oceans; together these cover about 50% of the total area of the Arctic Ocean. A tight coupling of sea-ice ecosystems with pelagic and benthic ecosystems is important on these shallow shelves, some of which are among the most highly productive on Earth, despite the high latitudes. Polynyas (areas of open water surrounded by ice) and marginal ice zones (MIZ) are highly productive areas in the Arctic (Stirling, 1997; Smith and Barber, 2007). Arctic ecosystems have adapted to the presence and timing of sea ice due to the control of sea ice on light, heat, and momentum (Barber et al., 2005). Changes in sea ice affect polynya and MIZ systems and, in particular, the physical-biological coupling within these systems (Barber and Massom, 2007). Changes in Arctic ecosystems have already been observed, including a regime shift in the Bering Sea (Grebmeier

et al., 2006a), increased pelagic production in response to more open water and a longer open-water season (Arrigo et al., 2008), and a decline in the physical condition and reproductive success of polar bears (*Ursus maritimus*) in western Hudson Bay due to earlier ice break-up (Stirling et al., 1999, 2008b).

Sea ice is deeply integrated into the lives of Arctic peoples, but also plays an important role in commercial activities reaching beyond the Arctic. Ice roads are critical for wintertime transportation; sea ice serves as a platform for subsistence hunting; and the high productivity of fisheries is linked to the ice. Changes in sea ice are resulting in coastal erosion in some areas and are affecting the distribution of pollutants. On the other hand, decreased ice cover will make the Arctic more accessible, allowing for increased shipping and access to renewable and non-renewable resources as well as a rise in tourism. Increased activity will in turn have feedback effects not only on the climate but also on the economy and social fabric of the region. At the same time, it will pose challenges related to governance and safety. Despite uncertainties related to future changes in sea ice, the lives of Arctic people are expected to change significantly.

Projections from climate models show a continued, and possibly accelerated, decline in Arctic sea-ice extent, very likely leading to an ice-free summer within this century (Boé et al., 2009), and likely within the next 30 to 40 years (Wang and Overland, 2009; Zhang et al., 2010). However, there is still much uncertainty in the future predictions; this uncertainty arises from natural variations in the climate system; the range of plausible trajectories of greenhouse gas concentrations, aerosols and other climate drivers over the next century; and systematic errors arising from model formulations, particularly the parameterizations of unresolved processes.

This chapter presents current knowledge of sea-ice extent, sea-ice thickness distribution, associated snow cover, key feedback mechanisms, and impacts on Arctic marine ecosystems and Arctic communities. The Arctic Climate Impact Assessment (ACIA, 2005) did not address sea ice in detail, as observations other than for ice extent were scarce. Other climate assessments have paid little attention to sea-ice thickness, concentrating more on sea-ice extent (Solomon et al., 2007; UNEP, 2007; WWF, 2008). This report reviews the significant new information on sea ice, including ice thickness, which has become available since the ACIA report and also includes pre-ACIA findings that were not included in the ACIA report.

In addition to new sea-ice information, there have also been major changes in understanding of feedbacks within the sea ice-climate system and of impacts on biology and human society. The aim of this report is to provide a synthesis of current knowledge of observed and projected changes in Arctic sea ice and the likely impacts on ecosystems and society.




Figure 9.1. September 2011 monthly sea-ice extent (white) and 1979-2000 September average ice-edge location (blue line). Source: Fetterer et al. (2011). Base imagery from NASA Blue Marble.

9.1. Changes in the physical state of sea ice

9.1.1. Introduction

- The decline in Arctic summer sea-ice extent has accelerated over the past ten years. The retreat is faster than previously predicted by IPCC models and summer ice-free conditions are likely over most of the Arctic basin by mid-century or earlier.
 - Interannual variability in basin-wide and regional sea-ice extent is initially likely to increase over the coming decades. As sea-ice extent continues to decrease, variability will also decrease as ice-free summers are approached.
- Newly developed estimates of sea-ice age, basin-scale sea-ice thickness, and sea-ice volume indicate thinning of ice cover and loss of old ice types.
 - Most of the oldest ice types (more than five years old) have been lost.
 - It is likely that the Arctic will become increasingly dominated by first-year ice.

The large-scale physical state of sea ice is defined by the extent (areal coverage), concentration (fractional coverage), and thickness of the ice and overlying snow. Small-scale properties, such as snow density, ice porosity, brine pockets, and temperature, are important for local processes, including biological activity, and also affect the accuracy of some methods to retrieve ice extent/concentration and ice/snow thickness. However, this section focuses on the larger-scale properties of the sea ice and the changes that have been observed.

Sea-ice extent and thickness evolve in concert, both seasonally and interannually, due to the interplay of thermodynamic and dynamic forcing (Box 9.1). Here each are treated separately because the measurement techniques are largely independent, although extent and thickness do change in interrelated ways that determine the overall sea-ice volume or mass balance.

9.1.2. Arctic-wide changes in sea-ice extent, age, and thickness

Sea-ice extent has been most consistently and completely tracked over the past 33 years by satellite-borne passive microwave sensors. Several algorithms have been developed to retrieve sea-ice extent estimates and time series are produced by several organizations. While there are some important differences in the products (as described by Andersen et al. 2007), there is overall consistency in estimates of long-term trends. Time series that are available electronically are noted in Table 9.1. The sea-ice extent/concentration imagery and total extent statistics quoted in this report are derived from passive microwave imagery using the NASA Team sea-ice concentration algorithm (Cavalieri et al., 1984, 1996; Maslanik and Stroeve, 1999; Meier et al., 2006), distributed by the National Snow and Ice Data Center's Sea Ice Index (http://nsidc.org/seaice_index/; Fetterer et al., 2011). It should be noted that these observations are hemispheric and total extent estimates include regions outside of the defined Arctic region of this report (e.g., Sea of

Box 9.1. Large-scale sea-ice thickness distribution and circulation within the Arctic

Sea-ice thickness changes as a result of thermodynamic (winter freezing and summer ablation) and dynamic (thickening by deformation) processes (Box 9.2; Thorndike et al., 1975). On a basin-wide scale, sea ice in the Arctic Ocean moves with two predominant drift systems: the Transpolar Drift and the Beaufort Gyre. The Transpolar Drift advects ice from the Siberian coast region across the Arctic Ocean toward and eventually through Fram Strait. The Beaufort Gyre is a clockwise circulation that circulates ice within the western Arctic in response to average high air pressure in the region. These drift systems, as well as smaller-scale motion patterns in the marginal seas, help control the extent and thickness of the sea-ice cover. Wherever ice drift is directed southward, ice extent protrudes south with it, as in the East Greenland Sea. Wherever ice drift is directed toward obstacles like coasts, ice is pushed against these obstacles and thickens by deformation (i.e., breaking, rafting, and formation of pressure ridges). As a result, on a basin-scale, the thickest sea ice (mean thicknesses 4 to 6 m) is located north of the coasts of Canada and Greenland, while the thinnest sea ice (mean thicknesses 0 to 2 m) extends along the coasts of Siberia, from where it is advected away soon after formation. Changes in the relative strength of the Beaufort Gyre and the Transpolar Drift are important controls on the extent and distribution of multi-year ice (MYI). When the Beaufort Gyre is strong, MYI tends to be retained within the Arctic Ocean; when the Transpolar Drift is strong, more ice is advected out of the Arctic Ocean and MYI area decreases. The relative strengths of these two circulations have been linked to the phase of the Arctic Oscillation (Rigor and Wallace, 2004).




Figure 9.2. Typical winter sea-ice thickness distribution within the Arctic and large-scale circulation patterns.

Table 9.1. Selected publicly accessible sources of Arctic sea-ice extent estimates based on passive microwave satellite data.

Group	Website
Arctic Regional Ocean Observing System (ROOS), Nansen Environmental and Remote Sensing Center, Bergen, Norway	http://www.Arctic-roos.org/
The Cryosphere Today, University of Illinois, Urbana-Champaign, Illinois, USA	http://Arctic.atmos.uiuc.edu/cryosphere/
NASA Goddard Sea Ice Remote Sensing	http://polynya.gsfc.nasa.gov/seaice_datasets.html
University of Bremen	http://www.iup.uni-bremen.de/seaice/amslr/
Japanese Space Exploration Agency (JAXA)	http://www.ijis.iarc.uaf.edu/en/home/seaice_extent.htm
Danish Meteorological Institute Center for Ocean and Ice	http://ocean.dmi.dk/arctic/icecover.uk.php
Sea Ice Index, National Snow and Ice Data Center, University of Colorado, Boulder, USA (used in the present assessment)	http://nsidc.org/data/seaice_index/

Box 9.2. Local ice thickness distribution

Sea-ice thickness and sea-ice concentration vary on small spatial and temporal scales due to local dynamic and thermodynamic forcings. Divergent ice motion causes the opening of cracks, leads, and polynyas. During winter, where water is exposed to the cold air, formation of new, thin ice occurs; near the ice edge this can increase ice extent. In summer, these open water areas are characterized by increased absorption of solar energy. Convergent motion results in a retreat of the ice edge (lowering the extent), or the formation of pressure ridges (piled ice blocks above and below the water

level form when ice floes collide and break) within the ice pack. Ridges can be up to tens of meters thick. As a result, the frequency distribution (histogram) of sea-ice thicknesses in a given region is typically characterized by a strong mode representing the most frequent, level ice formed by freezing and melting, and a long tail toward thicker ice representing the amount and thickness of ridges. Mean sea-ice thickness is strongly affected by the shape of the sea-ice thickness distribution, and does not normally agree with modal ice thickness, but is a result of the mixture of various amounts of thermodynamically and dynamically formed ice.




Figure 9.3. Processes that dynamically modify ice-thickness distribution. Source: Haas and Druckenmiller (2009).

Box 9.3. Uncertainties in ice-extent estimates

Passive microwave remote sensing instruments provide sea-ice extent information day or night, clear or cloudy, and have a near-complete record since late 1978. However, there are many limitations to passive microwave imagery. First, the instantaneous field of view (sensor footprint) is large at ~25 to 50 km, limiting the precision of the ice edge location and concentration at the ice edge because of inherent subpixel ambiguity (Eppler et al., 1992; Hwang and Barber, 2006). In addition, passive microwave instruments are sensitive to the effects of snow cover, liquid water (Hwang et al., 2007a), brine volume change (Hwang et al., 2007b), melt ponds (Yackel et al., 2000), and ice temperature (Hwang et al., 2008). These effects can result in either overestimation or underestimation of sea-ice amounts depending on seasonal and local conditions. Atmospheric emissions can also affect the microwave signal (Oelke, 1997; Andersen et al., 2006). Finally, thin ice also tends to be underestimated by algorithms that convert brightness temperature estimates into ice concentration (Cavalieri, 1994; Hwang et al., 2007b, 2008). In general, biases in sea-ice concentration are ~5% during winter (Steffen et al., 1992; Kwok, 2002), with higher errors in summer due to surface melt (Steffen et al., 1992). However, significantly higher errors have been found, depending on surface and atmospheric conditions (Comiso et al., 1997; Meier, 2005; Andersen et al., 2007). Different algorithms have different error magnitudes depending on conditions and no single algorithm has superior performance in all cases.

For tracking long-term variability and trends, seasonal or annual biases are not as important as the consistency of the time series, particularly when sea-ice concentration anomalies are used (Barber and Hanesiak, 2004). The greatest factor for ice concentration/extent consistency is intercalibration of the products through transitions of different generations of satellite-borne sensors. Careful intercalibration of the time series has minimized such errors (Cavalieri et al., 1999; Comiso and Nishio, 2008) and there is high confidence in the accuracy of the long-term trend estimates.

Ice charts are compiled from manual interpretation by ice analysts of the best available data with the focus on producing the most accurate operational analysis at any given time. As the quantity and quality of input data have progressed, the accuracy of the charts has varied over time and thus the charts are not necessarily consistent for long-term tracking of trends and variability (Partington et al., 2003). From the 1950s through the early 1990s, charts were produced primarily from aircraft reconnaissance imagery, ship observations, and starting in the late 1960s, visible and infrared satellite imagery. From the late 1970s, passive microwave satellite data have filled in regions where visible/infrared imagery was unavailable. Beginning in the early 1990s, synthetic aperture radar data became widely available. The higher spatial resolution and all-sky capabilities of these data significantly increased the amount and quality of data available to operational ice analyses, yielding more detailed and more accurate charts.

Okhotsk). Uncertainties in sea-ice extent estimates are reviewed in Box 9.3.

Long-term sea-ice thickness observations have been performed by drilling at various fast-ice locations along the Arctic coast. Since 1958, ice draft measurements have been performed by sporadic submarine Upward-Looking Sonar (ULS) missions crossing the Arctic Ocean along certain transects, and by moored ULS in confined regions since the early 1990s. Only since 1993 have freeboard measurements been performed by satellite radar altimeters, and since 2003 data have become available from satellite laser altimetry. Ground-based and airborne surveys using the same or other methods have been performed since the 1990s, but are regionally limited and have only rarely resulted in long-term data sets. Uncertainties in sea-ice thickness estimates are reviewed in Box 9.4.

9.1.2.1. Recent changes – since 2000

9.1.2.1.1. Extent

Arctic sea ice has experienced several extreme low summer sea-ice extents since 2000. A new record low since the beginning of the passive microwave satellite record in 1979 has occurred three times in the past decade: in 2002, 2005, and 2007. Most other years in the past decade, although not record-setting, were also extremely low. Each year in the period 2002 to 2011 was at least 12.6% below the 1979–2000 average (Figure 9.5). The seven years (2005 to 2011) since the Arctic Climate Impact Assessment (ACIA, 2005) have experienced the six lowest minimum sea-ice extents in the satellite record. Overall, the 2001–2011 average September monthly sea-ice extent is 5.49 million km²; 22.0% below the 1979–2000 average of 7.04 million km². The trend over the eleven-year period is -191 000 km² per year (-27.1% per decade relative to the 1979–2000 average).

Winter sea-ice extents were also low through much of the decade, although the percentage decreases were not as extreme as for summer sea-ice extent. The 2001–2011 March average (the month with the highest sea-ice extent) is 15.04 million km²; 4.5% below the 1979–2000 March average of 15.75 million km².

The minimum and maximum extremes are indicative of declining trends in sea-ice extent throughout the annual cycle, with larger declines during the summer months and less extreme declines in winter. The overall annual average extent for the period 2001 to 2011 is 11.18 million km²; 7.8% below the 1979–2000 annual average of 12.13 million km².

9.1.2.1.2. Thickness and reduction in multi-year ice extent

Basin-scale ice thickness information has primarily been retrieved from satellite altimeter freeboard measurements (Box 9.4). The European Space Agency's (ESA) ERS and Envisat satellite radar altimeters have performed circum-Arctic observations south of 81.5° N since 1993. Envisat observations between 2002 and 2008 suggest little change until early 2007, but a large decrease (25 cm) following the September 2007 sea-ice extent minimum (Figure 9.6; Giles et al., 2008). However, this drop was regionally confined to parts of the Beaufort and Chukchi Seas, and no significant changes were found in the eastern Arctic Ocean. Observations of this thinning between 2007 and 2008 are confirmed by results

Box 9.4. Uncertainties in sea-ice thickness estimates

Sea ice floats on the water generally in isostatic balance, such that measurements of draft, freeboard, or surface elevation can be converted into total thickness. However, accurate sea-ice thickness measurements are challenging because there is high spatial and temporal variability and the amount of snow on the ice and the snow and ice density structure are usually not well known.

In situ measurements are the most direct and most accurate estimates for the point location or transect that they are measuring. Substantial uncertainties in the mean thickness estimate arise because these local measurements are not necessarily representative of surrounding conditions, since ice thickness can vary greatly over short distances. Biases may also occur because very thin ice and thick ridged ice are underrepresented due to access and sampling difficulties.

Remote observations provide considerably more coverage and potential representativeness, but there are substantial difficulties in converting the measured properties to thickness values. Electromagnetic induction (EM) instruments generally penetrate to the ice-water interface, but snow cover and internal ice properties lead to ambiguities. The spatial and temporal coverage of EM instruments, although more widespread than *in situ* drill holes, can still only cover relatively small regions.

Upward-looking sonar (ULS) measurements from submarines have more spatial coverage, but measurements have been sporadic in time. In addition, sonars measure draft and uncertainty in ice density and snow cover limits the accuracy of the measurements.

Satellite altimetry has shown the potential to provide large-scale coverage over much of the Arctic at regular intervals. However, similar to sonar, altimeters do not directly measure

thickness, but rather freeboard. Because freeboard is only 10% to 15% of the total thickness, any errors in freeboard height are amplified. The problem is particularly acute for laser altimeters, such as ICESat, which measure the total snow + ice freeboard. Thus estimates of snow depth and density are necessary for accurate conversion to thickness. With radar altimeters, such as Cryosat-2, it is generally assumed that the radar signals penetrate through to the snow-ice interface to measure ice-only freeboard. Although less than is the case with laser altimetry, snow still represents a significant source of uncertainty for radar altimetry. Nonetheless, altimeter data have already provided key data on ice thickness and volume and future measurements will provide essential information on the future evolution of the ice cover.

Ground-penetrating radar (GPR) has the potential to obtain both snow and ice thicknesses, but has not yet been extensively used over sea ice.




Figure 9.4. Ice floe cross-section showing definitions of ice and snow thickness, total thickness, draft, freeboard, and surface elevation. The primary measurements of individual ice-thickness observing methods are also indicated.





Figure 9.5. September monthly sea-ice extent and concentration (i.e., fractional area coverage) anomaly, 2003–2011. The grey circle represents areas not covered by the satellite sensors during at least part of the time series; this area has traditionally always been covered by a high concentration of sea ice. Source: based on the NSIDC Sea Ice Index (Fetterer et al., 2011).






Figure 9.6. Comparison of five years of winter sea-ice thickness anomalies in the western Arctic derived from laser (ICESat; Kwok et al., 2009) and radar altimetry (Envisat; Giles et al., 2008). Anomalies are calculated for regions of the Arctic Ocean south of 81.5° N which are covered by both satellites.




Figure 9.7. Decline in winter Arctic first-year (FYI) and multi-year (MYI) sea-ice thickness and volume between 2004 and 2008 derived from ICESat observations (Kwok et al., 2009). Overall thickness is the mean MYI and FYI thickness weighted by their areal coverage; overall volume is the sum of MYI and FYI volume.

from ICESat laser altimetry, although these data also reveal stronger interannual variability (Figure 9.6; Kwok et al., 2009).

ICESat data provide more insight as they cover regions up to 86° N and yield observations of seasonal variations between spring and autumn of each year (Kwok et al., 2004, 2007; Kwok and Cunningham, 2008). Data from ten ICESat campaigns between 2004 and 2008 (Figure 9.7) show rapid thinning and volume loss of the Arctic Ocean sea-ice cover (Kwok et al., 2009). Changes were strongest over multi-year ice regions, which thinned by ~0.6 m over four years. In contrast, the average thickness of the seasonal ice in mid-winter (~2 m), which covered more than two-thirds of the Arctic Ocean in 2007, exhibited a negligible trend.

Changes in multi-year ice (MYI) and first-year ice (FYI) thickness are accompanied by changes in the areal coverage of these ice types, which affect overall ice volume. One of the most significant changes in the Arctic Ocean is a reduction in the coverage of MYI, which has decreased by more than 42% since 2005 (Kwok et al., 2009). As a result, MYI volume in winter experienced a net loss of 6300 km³ (>40%) between 2005 and 2008, while FYI cover gained volume due to increased overall areal coverage compensating the MYI area loss (Figure 9.7). The overall decline in volume and thickness is explained almost entirely by changes in the MYI cover. Combined with a large decline in MYI cover over this short record, there is a reversal in the volumetric and areal contributions of the two ice types to the total volume and area of the Arctic Ocean ice cover. Seasonal ice, having surpassed that of MYI in winter area coverage and volume, became the dominant ice type. The average winter sea-ice volume between 2004 and 2008, including the loss of ~3000 km³ between 2007 and 2008, was ~16 420 km³.

It is presently unclear whether the reduction of old ice is a result of changed and possibly accelerated ice drift and export (Rampal et al., 2009; see also Box 9.1), or is due to reductions in summer sea-ice extent, which reduces the amount of FYI that survives melt and gets promoted to second year ice at the beginning of each winter freeze-up. The annual cycle of MYI coverage reconstructed since 1999 from satellite radar observations (Figure 9.8a) may provide further insights: MYI coverage decreases throughout the winter due to sea-ice export and divergence, and is reset at the end of every summer by the remaining FYI that has survived the summer. Balance between export, melt, and replenishment is necessary to maintain a stable MYI area. Up through the summer of 2005, the annual replenishment was sufficient to maintain a relatively stable MYI coverage of ~4 million km² (Figure 9.8a) although the variability was remarkably high. The 2007 sea-ice replenishment was the lowest after the record minimum in ice extent that summer and helped set the record for lowest MYI coverage. Although more recent ICESat data were not available for this assessment, ice age fields (Maslanik et al., 2007) indicate larger replenishment after the 2008 to 2011 melt seasons.

Figure 9.8b shows the net sea-ice export record through Fram Strait since 2000 (Kwok et al., 2009). Over the nine years, the average net area flux through Fram Strait of ~730 000 km² was close to the 29-year record average of ~700 000 ± 130 000 km². In the absence of replenishment of the ~4 million km² of MYI in the Arctic prior to 2005, it would take only a few years – at an average export rate – to export all of the MYI through Fram Strait. Therefore Figure 9.8 implies that the areal melt of FYI during summer, rather than export, is the main cause for the decreasing MYI coverage.




Figure 9.8. (a) Nine annual cycles of replenishment / export of Arctic Ocean multi-year ice (MYI) area constructed using QuikSCAT data and Fram Strait ice export. Black dots show the approximate times of the ten ICESat campaigns used here. The dashed vertical lines show the replenishment of the MYI reservoir by first-year ice at the end of each summer. The two near-zero replenishment years of 2005 and 2007 are indicated. (b) The annual and seasonal Fram Strait ice export over the same period. Source: Kwok et al. (2009).

9.1.2.2. Changes since the start of satellite measurements

9.1.2.2.1. Extent

Several studies (e.g., Meier et al., 2007; Comiso and Nishio, 2008; Parkinson and Cavalieri, 2008) have examined trends and variability in sea-ice extent for the passive microwave sea-ice record (Box 9.3). The over 33-year record shows a statistically significant decline in extent in all months. The 1979–2011 monthly March extent trend is -2.7% per decade relative to the 1979–2000 average, while the September trend is -12.0% per decade (Figure 9.9). The annual decline trend for 1979–2011 is -4.3% per decade relative to the 1979–2000 average. The past ten years have much larger downward trends and while there is less confidence in such short trends, they are likely to represent an acceleration of the downward trend in sea-ice extent since the beginning of the passive microwave satellite record in 1979 (Comiso, 2006).

9.1.2.2.2. Thickness

There are few satellite-derived sea-ice thickness measurements outside of the past ten years. Results from the ESA ERS satellite radar altimeters obtained for regions south of 81.5° N over the period 1993 to 2001, showed a pan-Arctic ice thickness field which was highly variable from year to year, without revealing significant longer-term changes (Laxon et al., 2003).

9.1.2.2.3. Reduction in sea-ice age

While direct retrievals of thickness from satellite are new to the past 10 to 15 years, there is a longer record of MYI and FYI extents and ice age distribution, calculated by Lagrangian tracking of ice parcels (Belchansky et al., 2004; Rigor and Wallace, 2004; Maslanik et al., 2007) that extends nearly as far back as the satellite-derived extent time series.




Figure 9.9. Average sea-ice extent in the Arctic in March, September, and annually for 1979 to 2011, including trend lines, from passive microwave satellite data. Source: updated from Fetterer et al. (2011).

Analysis of ice age through March 2011 (Figure 9.10) shows that the loss of older ice types within the Arctic Basin has continued and accelerated since 2007. Multi-year ice now makes up less than 30% of the spring ice cover north of 70° N. Some young (2- to 4-year old) MYI was regained in the period 2008 to 2010 due to higher survivability of FYI through summer. However, loss of the oldest ice types continued through 2011, with under 2% of the ice cover comprising ice greater than six years old compared to 20% in 1988. Such differences, in addition to ice thickness, have the potential to affect the survivability of the ice pack.

The reduction of the age and amount of old sea ice may be one of the most fundamental changes in the Arctic Ocean (e.g., Johannessen et al., 1999; Comiso, 2002; Belchansky et al., 2004; Rigor and Wallace, 2004; Kwok, 2007; Nghiem et al., 2007). The remaining ice pack now consists of more FYI and less of relatively thicker MYI, with consequences for the thickness, surface roughness, snow accumulation and albedo of the ice overall (Iacozza and Barber, 1999). This thinning of the ice pack possibly helped set the stage for the extensive retreat of summer ice extent in recent years by pre-conditioning the ice pack to be less resistant to melt and export (Stroeve et al., 2007; Lindsay et al., 2009).




Figure 9.10. Change in fractional coverage of ice of different age categories through the end of March 2011, for the area north of 70° N with at least 40% total ice concentration (upper graphic) and the spatial distribution of ice by age category in March 1985 and March 2011. '1- to 2-year old ice' refers to ice that has survived at least one melt season. Source: updated from Maslanik et al. (2007).

9.1.2.3. Pre-satellite records of extent and thickness

9.1.2.3.1. Extent

Records of sea-ice extent before the passive microwave record become increasingly sparse going back in time. The best sources come from operational ice charting groups that used visible/infrared satellite data starting in the 1960s, aircraft reconnaissance imagery, and ship observations. These data are not as consistent as the passive microwave record because their completeness and quality vary. Extent estimates from operational ice charts and other sources have been compiled by Walsh and Chapman (2001) and were combined into a monthly extent time series since 1870 (Rayner et al., 2003; Meier et al., 2007). However, before 1953 there is little variability because the estimates were often based on climatology. Brönnimann et al. (2008) used modeling and statistical analysis to reconstruct sea-ice extent for the 1900 to 1953 period to obtain more realistic variability; the results indicate that the 1979–2011 decline, particularly the accelerated decline for 2001–2011, are unique in at least the past 100 years.

Longer observational records are only available regionally, with the most complete records from the Russian Arctic. Mahoney et al. (2008) examined ice charts for the Russian Arctic since 1933. The data indicate that during the 1930s warm period, there were some reduced sea-ice extents, but these were found primarily in summer, with little or no decline in other seasons. The current decline is year-round. Also, the 1930s decline was potentially more regional in nature, whereas the current decline is Arctic-wide.

More recent analysis of post-1900 data from the Russian Arctic by Frolov et al. (2009) showed the same general features as found by Mahoney et al. (2008). However, Frolov et al., (2009) also found cyclical patterns at several temporal scales, from 2 to 3 years up to multi-decadal frequencies of 20 years, and 50 to 60 years. These cycles are determined from only the Russian and Atlantic sectors and the long-term cycles are most prominent in the Greenland, Barents, and Kara Sea region. The analysis was based on data through 2003 and it is unclear how the recent extreme summer minimums may affect the significance of the results.

9.1.2.3.2. Thickness

Long-term, basin-wide sea-ice thickness data are only available from submarine ULS ice draft measurements, which have been collected during sporadic military US and UK missions since 1958 (Box 9.4). These data have been declassified over a data release area covering around 38% of the Arctic Ocean. By the 1980s, enough data had accumulated to allow estimates of the large-scale spatial distribution of draft in the Arctic Ocean (Bourke and Garrett, 1987). Concerns were raised as to whether the submarine dataset was sufficiently robust to distinguish any signal of long-term change from 'natural variability', which amounted to more than 1.5 m between some years (McLaren et al., 1990; Wadhams, 1990); thickness changes were found to be primarily related to variations in the origin and age of the surveyed ice and associated changes in drift patterns (McLaren et al., 1992; Shy and Walsh, 1996). Rothrock et al.

(1999) compared measurements performed between 1958 and 1976 with surveys carried out in coincident regions between 1993 and 1997. They found significant thickness reductions of 1.3 m on average, decreasing from an average of 3.1 m in the earlier period to 1.8 m in the latter (Figure 9.11). Similar reductions were observed by Wadhams and Davis (2000). The observed thinning was partially explained by changes in sea-ice drift patterns changing from a predominantly anticyclonic mode to a more cyclonic mode (Tucker et al., 2001; Winsor, 2001; Holloway and Sou, 2002; see also Box 9.1), but thermal forcings (i.e., higher temperatures) were also found to be a major factor (Yu et al., 2004).

Since 1975, data coverage has improved and it is now possible to separate the annual cycle, spatial field, and interannual signal. Over the period 1975 to 2000 the data show a decline of 1.25 m in mean sea-ice thickness (Rothrock et al., 2008). These data, together with the ICESat data, provide the best available and most extended ice thickness time series within the central Arctic Ocean (Figure 9.12; Kwok and Rothrock, 2009). The overall mean winter thickness changed from 3.64 m in 1980 to a mean of 1.89 m during the last winter of ICESat measurements in 2008, a decrease of 1.75 m. Overall, the rate of decrease accelerated to up to -0.2 m during the six-year ICESat record (Kwok and Rothrock, 2009).

9.1.2.4. Indications of pre-1900 sea-ice conditions from paleographic proxy data

Indications of pre-20th century sea-ice conditions can be inferred from proxy data, such as tree rings, ice cores, and sediment cores. A comprehensive review of proxy records in the Arctic indicate that recent sea-ice extents are the lowest in at least the past few thousand years and the recent reduction cannot be explained by variations in any known natural mechanisms (Polyak et al., 2010). Müller et al. (2009) examined sediment cores from the Fram Strait region and found evidence for seasonally ice-free conditions about 14 000 years ago. Changes in Arctic ice shelves (Copland et al., 2007; England et al., 2008) and proxy temperature reconstructions




Figure 9.11. Regions of coincident submarine tracks in 1958–1976 and 1993–1997. Numbers indicate ice thickness difference between the two periods. Source: Rothrock et al. (1999).




Figure 9.12. Interannual changes in winter and summer sea-ice thickness from Rothrock et al. (2008) and Kwok et al. (2009) centered on the ICESat campaigns. Blue error bars show residuals in the regression and quality of ICESat data (Kwok and Rothrock, 2009).

(Kaufmann et al., 2009) provide indirect supporting evidence that current ice conditions are low compared to historical levels over the past several thousand years. These proxy records are not complete enough to provide solid estimates of extent or to determine with high certainty when in the past the Arctic Ocean may have been ice-free during summer. More proxy data and new techniques could be valuable in more precisely determining sea-ice conditions in the distant past and allowing the current decline to be put into a long-term context.

9.1.3. Seasonal changes in sea ice

There is a strong seasonal cycle in Arctic sea ice that affects both extent and thickness. Because the majority of FYI melts completely during summer, there is much more variability in extent than thickness, with summer ice extents less than half the winter values (Figure 9.9).

The seasonal cycle of ice thickness varies considerably depending on ice type, location, and local atmospheric and oceanic conditions. Although both the ocean and the atmosphere can force ablation of sea ice throughout the annual cycle (Carmack et al., 2006; Barber and Massom, 2007), the mass balance is dominated by snow and ice ablation in summer and bottom accretion in winter (Box 9.2). This strong seasonal cycle must be taken into account when comparing thickness measurements from different seasons. The magnitude of the seasonal cycle varies strongly with latitude and regional meteorological and oceanic conditions. Surface and bottom melt of individual locations on drifting ice floes can be measured with Ice Mass Balance Buoys (Richter-Menge et al., 2006). Between 1994 and 2007 the annual average surface melt was 0.64 m in the Beaufort Sea and 0.26 m at the North Pole. Bottom melt ranged between 0.1 and 0.4 m at the North Pole, but can be highly variable and up to 2.1 m in the Beaufort Sea (e.g., Perovich et al., 2008), depending on ice concentration and the amount of shortwave radiation absorbed by the ocean surface mixed layer. Basin-scale seasonal variations (including deformed ice) retrieved from multiple submarine cruises show a similar pattern, with a peak-to-trough amplitude of 1.06 m between 1975 and 2000 (Figure 9.13; Rothrock et al., 2008).




Figure 9.13. The annual cycle of sea-ice draft averaged for the period 1975 to 2000 over the Central Arctic Basin. Source: Rothrock et al. (2008). Dots show the variability of individual profile sections used for the reconstruction, black for summer/autumn, grey for winter/spring. Dots within one standard deviation from the mean are plotted heavier.

9.1.4. Regional changes in sea ice

9.1.4.1. Trends in extent

Over the satellite record since 1979, sea-ice extent has declined both during summer and winter in virtually all regions of the Arctic (Meier et al., 2007; Comiso and Nishio, 2008; Parkinson and Cavalieri, 2008). The most substantial declines have occurred during summer. Many regions in winter show

no trend because they are completely ice covered through the winter months. However in regions with winter variability, most regions show small declining trends, with the exception of increases in the Bering Sea during winter related to changes in atmospheric circulation (Table 9.2). There are few observations for many regions from the pre-satellite records, except for the Russian Arctic (see Section 9.1.2.3).

9.1.4.2. Trends in thickness

Thickness data obtained by methods other than satellite altimetry or submarine ULS are limited to smaller geographical regions due to logistical challenges. Significant data have been obtained in some regions of the Arctic Ocean using ships as operating platforms for drilling, visual/video observations, or electromagnetic induction (EM) surveys, or aircraft for laser- and radar altimetry and EM sounding (Box 9.4). However, the longest time series have been obtained from landfast ice, which is attached to coasts and therefore most accessible. As landfast ice is typically a seasonal phenomenon in the Arctic, it undergoes annual or shorter-term cycles of formation and break-up which sometimes hamper interpretation of thickness data. Many landfast ice records have not been continued in the past ten years due to closure of monitoring stations. Results from fast-ice studies may differ from results of drift-ice studies because fast-ice thicknesses primarily represent thermodynamic growth in shallow water, whereas drift ice comprises both thermodynamically grown and deformed ice, and its thickness is an integrated result of conditions experienced during its drift.

Table 9.2. Trends in sea-ice extent in percentage per decade for the subregions of the Arctic relative to 1979–2009. Statistical significance is indicated by ***bold/italic for 99.9%***, ***bold for 99%***, and *italic for 95%*. Regions are as defined by Meier et al. (2007); the Arctic Ocean region includes the Laptev, Siberian, Chukchi, Beaufort, and Central Arctic regions. Regions/months without value have too little ice to yield reliable statistics. Updated through 2009 based on NSIDC data (Cavalieri et al., 1996, updated 2008; Meier et al., 2006, updated quarterly; Maslanik and Stroeve, 1999, updated daily).

Region	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
Pan-Arctic Total	-3.3	-3.0	-2.9	-3.1	-2.7	-3.5	-6.4	-9.1	-11.7	-5.7	-4.6	-3.3
Bering Sea	6.3	2.0	-1.1	1.6	-1.7	-13.0					-22.2	-1.2
Hudson Bay	0.0	0.0	0.0	0.0	-0.2	-5.6					-26.7	-1.6
Baffin Bay	-7.4	-5.8	-5.9	-6.2	-6.6	-9.9	-18.9	-28.5	-10.1	-24.6	-11.0	-11.3
Greenland Sea	-11.0	-11.6	-11.0	-9.2	-6.4	-5.6	-9.5	-14.5	-13.0	-6.5	-7.8	-10.6
Barents Sea	-16.8	-13.0	-10.2	-12.7	-18.0	-23.3	-30.0	-37.4	-28.8	-18.4	-15.9	-20.2
Kara Sea	0.0	0.0	0.0	-0.1	0.0	-1.5	-14.4	-21.8	-20.9	-7.7	-3.3	-1.0
Laptev Sea	0.0	0.0	0.0	0.0	0.0	-1.2	-4.1	-12.6	-15.9	-0.2	0.0	0.0
Siberian Sea	0.0	0.0	0.0	0.0	0.0	0.2	-1.4	-16.2	-25.6	-7.1	-0.2	0.0
Chukchi Sea	0.0	0.0	0.0	0.0	-0.2	-3.5	-6.7	-18.7	-31.6	-20.9	-9.2	0.0
Beaufort Sea	0.0	0.0	0.0	0.0	0.0	-1.2	-3.1	-6.7	-12.9	-3.1	0.0	0.0
Canadian Archipelago	0.0	0.0	0.0	0.0	-0.1	-1.3	-2.3	-7.5	-12.3	-4.3	0.0	0.0
Central Arctic	0.0	0.0	0.0	0.0	-0.1	0.0	-0.2	-0.6	-1.4	-0.2	-0.1	-0.1
Arctic Ocean	0.0	0.0	0.0	0.0	0.0	-0.7	-2.0	-6.9	-10.7	-3.7	-1.1	0.0

9.1.4.2.1. Results from drift ice regions

During occasional icebreaker cruises into the central Arctic since 1991, visual and drill-hole thickness measurements have been collected, later supplemented by ground and airborne EM surveys. Haas et al. (2008) found significant thinning in the region of the Transpolar Drift. Between 1991 and 2004, modal thickness decreased from 2.5 to 2.2 m in 2004, and then dropped to 0.9 m in 2007 (Figure 9.14). Mean thickness decreased similarly strongly. The thinning was accompanied by reductions in the age of the ice, and replacement of second-year ice by first-year ice in 2007. These changes hamper the separation of thermodynamic and dynamic causes for the observed thinning. Ice thicknesses and their changes are in general agreement with other surface observations (Perovich et al., 2009) and visual and video observations from Russian icebreakers (Frolov et al., 2009), but quantitative comparisons are difficult due to different ship routes, mixtures of ice types, and effects due to proximity to the ice edge.

Most sea ice exits the Arctic Basin through Fram Strait. Moored ULS have been operated across the Strait to monitor ice export since 1990. Until 1996, the data show the export of ice mostly between 1.5 and 3 m (sometimes up to 4 m) thick on average, but with large spatial and temporal variability (Vinje et al., 1998). The latter showed some correlation with phases of the North Atlantic Oscillation. Spreen et al. (2009) combined ICESat thickness retrievals and satellite observed ice drift to update estimates of ice flux through Fram Strait, but observed no significant changes. Published data to date do not allow derivation of any thickness trends in Fram Strait, although ice thickness and volume are clearly affected by the drift and origin of the ice and by variations in the proximity of the ice edge, particularly in summer.

The Barents Sea ice is dominated by FYI and occasional older ice advected from the Arctic Ocean by the East Spitsbergen Current. Along the coast of Svalbard and in Storfjorden, ice can become very thick by deformation. Recent airborne EM surveys over Storfjorden have shown that modal thickness of coastal drift ice can be as high as 2.4 m, significantly thicker than fast ice due to heavy deformation (Hendricks et al., 2011). Deformation and thickness are strongly dependent on prevailing onshore or offshore winds.

Some of the thickest ice of the Arctic Ocean is located north of the coasts of Ellesmere Island and in the Lincoln Sea, with modal thicknesses over 4 m and mean thicknesses ranging from 4 to 6 m (Haas et al., 2006; see also Box 9.2). Due to the high degree of deformation in the region modal thicknesses may not represent thermodynamic equilibrium thicknesses. Between 2004 and 2009, there were no significant changes, but some interannual variability is obvious (Haas et al., 2010), which may be related to the variable occurrence of ice arches in the Lincoln Sea and Nares Strait (Kwok et al., 2010).

Moored ULS have been operated for 12 years in the Eastern Beaufort Sea (Melling et al., 2005). Between 1991 and 2003, ice draft has shown a small thinning trend of -0.07 m/decade, but this has low statistical significance as the net change is comparable to the uncertainty in the measurements. Mean late-winter draft was about 2 m. Airborne ice thickness surveys have also been performed in the region in different seasons (Peterson et al., 2008; Barber et al., 2009), but the data are currently too sparse and ice types too varied to be comparable.




Figure 9.14. Late summer sea-ice age (above) and thickness (below) in the region of the North Pole between 1991 and 2007. Thickness was obtained by means of ground-based (thin lines, •) and airborne (thick lines, ▼) electromagnetic induction sounding. In 2007, first-year ice prevailed in August, but second-year ice was still present in April 2007. The latter distribution was seasonally adjusted to be comparable with summer conditions. Source: Haas et al. (2008).

The thickness distribution of drifting sea ice in the Alaskan Arctic is dominated by a range of processes that result in significant spatial and interannual variability (Boxes 9.1 and 9.2): production of thin, young ice in coastal polynyas (Martin et al., 2004; Melling et al., 2005); advection of MYI from the High Arctic in the Beaufort Gyre (Tucker et al., 2001; Shirasawa et al., 2009); growth of FYI with the commencement of freeze-up and surface and bottom summer melt (Perovich et al., 2003). As a result, drifting sea ice in the Alaskan Arctic is sensitive to changes in forcing, and hence significant trends are more challenging to detect. Generally, the substantial reduction in overall mean (drifting) ice thickness is due to the loss of MYI and greatly enhanced (bottom) melt (Perovich et al., 2008) resulting from a combination of changes in ice circulation taking ice out of the Beaufort Gyre and ice-albedo feedback enhancing solar heating of the region. According to ice-age data (updated from Maslanik et al., 2007), in recent years considerable amounts of old ice advected into the Beaufort and Chukchi Seas have melted completely during summer. However, the thickness of FYI close to the end of winter did not change significantly between 2007 and 2009, and modal thicknesses ranged from 1.6 to 1.8 m (Haas et al., 2010).

9.1.4.2.2. Results from landfast ice regions

Landfast (or simply ‘fast’) ice is non-drifting ice typically locked in place by islands, icebergs, or grounded ridges. The appearance and extent of landfast sea ice vary markedly around the Arctic, typically extending to the shelf break. However, fast-ice extent depends not only on direct thermodynamic boundary conditions, but also on effects of the timing and amount of snow deposition (e.g., Gerland et al., 1999; Hanesiak et al., 1999; Nicolaus et al. 2003) and ocean mixed layer properties (Carmack et al., 2006; Barber et al., 2008b). There is general evidence that the annual cycle of landfast ice is shortening as the Arctic sea-ice retreats (Reeh et al., 2001; Serreze et al., 2007) and air temperatures rise (Comiso, 2006).

In the Russian Arctic, interannual variability of landfast sea-ice extent has been linked to variability in the discharge of the large rivers that drain into the Russian Arctic (Dmitrenko et al., 1999). Landfast ice extent and thickness in the Laptev, East Siberian, and Chukchi Seas exhibited strong multidecadal variability during the 20th century. This variability correlates with both dynamic and thermodynamic atmospheric forcing, but makes it difficult to discern any clear long-term trends (Polyakov et al., 2003). Long time series of fast-ice thickness anomalies have been obtained at five sites from 1936 to 2000, and show an increase in ice thickness from the 1930s to about 1960, and then a decrease from 1960 to 2000 (Figure 9.15; Polyakov et al., 2003). The five individual stations show that trends are a few centimeters per decade and can be both positive and negative for different sites, but that the changes are not very significant.

Along the northern Alaskan coast, Mahoney et al. (2007) found no evidence of long-term change in landfast ice extent between the 1970s and the period 1997 to 2004. However, there were significant differences in the timing of the annual landfast ice cycle in this region. In comparison with observations from the 1970s (Barry et al., 1979), landfast ice formed about one month later along the Alaskan Chukchi coast and broke out on average 6 days and 19 days earlier along the Chukchi and Beaufort Sea coasts, respectively. The later formation of landfast




Figure 9.15. Time series of May fast-ice thickness anomalies at five locations along the Siberian coast. Grey lines show yearly May values and red lines the 6-yr running mean, green lines show linear trends (quoted limits represent 95% confidence levels). Source: Polyakov et al. (2003).

ice in recent years is likely to be related to the later incursion of pack ice into the coastal zone, whereas early breakouts of landfast ice are most closely correlated with earlier onset of thawing air temperatures in summer.

This broadly agrees with measurements collected from Barrow, Alaska over a period of about ten years (Druckenmiller et al., 2009), which indicate thinner ice compared to data published for the 1970s (Weeks and Gow, 1978). These studies also indicate that ice thickening through ridging has changed due to the absence of MYI in recent years, reducing the number of deep-draft, grounded ridges that help stabilize the ice cover (Shapiro and Barnes, 1991).

Ice of the Canadian Arctic Archipelago is a mix of MYI and FYI types and becomes landfast during winter. Extensive drill-hole data were obtained in the 1970s through oil exploration activities. The average ice thickness in late winter was 3.4 m but local means reached 5.5 m (Melling, 2002). First-year ice growth amounted to about 2.3 m at the time. Earlier data from the period 1959 to 1989 showed no clear thickness trends (Brown and Cote, 1992) with thicknesses varying interannually due to both dynamic and thermodynamic atmospheric forcing.

Seasonal fast-ice and snow-cover thickness in Svalbard fjords and coastal ice near Svalbard have been extensively studied since 1997, showing generally decreasing thicknesses (Gerland et al., 1999; Gerland and Hall, 2006; Cottier et al., 2007; Gerland and Renner, 2007). However, interpretation of these changes is difficult because fast-ice evolution in Svalbard fjords varies strongly regionally, with the west coast influenced by the relatively warm Atlantic water of the West Spitsbergen Current, and with gradients in snow deposition. Recent airborne EM surveys over Storfjorden have shown that modal thicknesses of coastal drift ice can be as high as 2.4 m, significantly thicker than fast ice, due to heavy deformation (Hendricks et al., 2011).

A long time series of drill-hole data has been obtained on fast ice off the coast of the island of Hopen (Gerland et al., 2008a). Between 1966 and 2007, seasonal maximum thicknesses decreased by 0.1 m per decade, although the interannual variability is high (Figure 9.16). The latter is also related to the high variability of Barents Sea ice extent, which can contribute to early fast-ice removal on the fairly exposed coast of Hopen.




Figure 9.16. Maximum seasonal sea-ice thickness for the island of Hopen in the Barents Sea. The linear trend is significant at the 0.05 level using a 'significant zero crossings of derivatives test'. Source: Gerland et al. (2008a).

9.1.5. Observations and importance of snow thickness

The snow cover is an essential part of the sea-ice thickness profile (see Box 9.4) and plays an important role in the sea-ice mass balance. Snow strongly modifies the surface albedo of the sea-ice cover and the heat flux through the ice and the amount and distribution of snow on sea ice also affects summer melt pond evolution (e.g., Barber and Yackel, 1999; Yackel et al., 2000; Hanesiak et al., 2001). It also contributes to ice thickness through snow-to-ice transformation (superimposed ice and snow-ice formation). The various controls of the snow cover on the sea-ice mass balance and feedbacks are described in Section 9.2. In addition, snow thickness and density variations affect the accuracy of many sea-ice thickness measurement methods (see Box 9.4).

Despite its importance, there is a lack of snow thickness data over Arctic sea ice due to methodological and logistical limitations in measuring this thin but highly stratified and laterally variable layer. Most datasets are very local and provide only one snapshot in time, both seasonally and interannually. Radionov et al. (1996) and Warren et al. (1999) reviewed data from Russian Arctic drifting stations obtained between 1954 and 1991 by manual snow stake measurements. Snow accumulates rapidly in September and October, moderately in November, very slowly in December and January, then moderately again from February to May. Snow melt on sea ice in the Arctic Ocean typically commences in June, and during August the sea-ice cover is mostly snow free but covered with melt ponds. During the 37-year study period, average snow depth on MYI reached a maximum of 34 cm in May. The deepest snow was observed just north of Greenland and Ellesmere Island, peaking in early June at more than 40 cm, when the snow is already melting north of Siberia and Alaska. Similar results of the annual cycle and maximum end-of-winter snow thicknesses between 30 and 40 cm were obtained by Brown and Cote (1992), Flato and Brown (1996), and Melling (2002) in the Canadian Arctic and Archipelago, and by Sturm et al. (2002) in the Beaufort Sea. Gerland and Haas (2011) showed snow thickness data obtained during expeditions across the Arctic Ocean. In April and May 2007, snow thickness varied from 10 to 15 cm on the Siberian side to around 40 cm off the northern coast of Greenland.

Kwok and Cunningham (2008) have developed a method to construct daily Arctic-wide snow thickness fields from precipitation fields calculated by the European Centre for Medium-Range Weather Forecasts (ECMWF), and by tracking ice floes to account for different accumulation rates along the drift tracks of the ice. Results between 2003 and 2008 are in general agreement with earlier data presented by Warren et al. (1999), and show small interannual variability of only a few centimeters (Kwok et al., 2009).

9.1.6. Changes in factors controlling sea-ice extent and thickness

Sea-ice extent and thickness evolve in response to large-scale and local atmospheric and oceanic forcing on both the dynamics and thermodynamics of the ice (Boxes 9.1 and 9.2). The most direct link between climate forcing and sea ice is through surface air temperature. Increasing air temperatures have been observed in recent decades (Rigor et al., 2000; Johannessen et al., 2004;

Overland et al., 2004, 2008b). Changes in atmospheric circulation have also played an essential role, particularly in the reduction of MYI and amount of deformation. Rigor and Wallace (2004) found that a strongly positive Arctic Oscillation (AO) enhanced the export of MYI between around 1989 and 1996. However, export through Fram Strait seems to be more coherent with the smaller-scale pattern of the North Atlantic Oscillation and the position of its centers of interannual variability. During the 1980s and 1990s, these shifted eastward compared to 1958–1977, resulting in anomalous meridional winds (Hilmer and Jung, 2000). Model results by Koenigk et al. (2006) and Hilmer et al. (1998) showed that the variability of the Fram Strait sea-ice export is mainly governed by the local sea level pressure (SLP) gradient across Fram Strait. The high AO-phase in the late 1980s and 1990s led to an increased SLP-gradient due to an anomalous extension of the Icelandic Low into the Arctic. However, results from models and reanalysis data show there is no significant correlation between AO/NAO and Fram Strait sea-ice export before 1978 (Jung and Hilmer, 2001).

Drifting buoy data suggest a relationship between sea-ice drift and change of atmospheric sea level pressure pattern regressed on the linear decreasing trends of the Arctic sea-ice extent in September (Inoue and Kikuchi, 2007). In recent years the Arctic Dipole Anomaly, characterized by two SLP anomaly centers that result in increased advection of ice across the Arctic, has been strong (Wang et al., 2009). Cloud cover and its influence on the amount of incident solar and longwave radiation has also had an influence (Schweiger et al., 2008a; Kay and Gettelman, 2009).

A key factor in the seasonal evolution of the surface albedo is the date of the onset of melt, when the early spring albedo values drop from ~0.85 to 0.71 or less (Perovich et al., 2002a). In the 2000s, melt onset has begun about two weeks earlier than in the 1980s (Stroeve et al., 2006) according to measurements from satellite passive microwave radiometers (Anderson and Drobot, 2001). Trends toward earlier melt onset dates in most regions of the Arctic have been observed, from -1.0 d/decade in the Bering Sea to -7.3 d/decade in the East Greenland Sea (Markus et al., 2009). Earlier melt onset may lead to an earlier disappearance of snow cover and earlier appearance of melt ponds and maximum melt pond coverage. This significantly changes the total absorbed solar flux during the summer season, which is an important factor controlling sea-ice extent and thickness through the summer melt season. Perovich et al. (2007) found that the total absorbed flux varies linearly with the date of melt onset, increasing by 25% if the onset moves from about 15 June to 23 May. The dependence on the date of freeze-up or the total duration of the melt season is much weaker as this occurs when solar elevation is already low. Albedo is also affected by snow properties and surface contaminants such as black carbon (see Section 9.2).

In addition to the effect on melt and albedo, the atmosphere affects sea ice through wind forcing and its influence on ice dynamics (Boxes 9.1 and 9.2). Ice drift speed within the Arctic Ocean has increased substantially in recent years. Based on drifting buoy data, Rampal et al. (2009) found sea-ice mean speed increased 17% per decade for winter and 8.5% for summer over the period 1979 to 2007. Concomitant with this increase in mean speed, the strain rate of the ice also increased significantly over this period (51% per decade in winter and

52% in summer). Rampal et al. (2009) showed that changes in wind forcing were not important in determining the change in ice speed. Instead, they suggested that sea-ice kinematics play a fundamental role in the albedo feedback loop and sea-ice decline: increasing summer deformation means stronger fracturing and hence more lead opening and reductions in albedo. This accelerates sea-ice thinning in summer and delays refreezing in early winter, decreasing the mechanical strength of the ice cover and allowing even larger drift speeds and deformation, and possibly faster export of sea ice through Fram Strait. Kwok and Rothrock (1999), Kwok et al. (2004), and Kwok (2008) examined the sea-ice area flux through Fram Strait from passive microwave ice motion data, and found a small positive trend over the period 1978 to 2008. A stabilizing process is found in the increased ridging and ice production that would also accompany increased winter ice deformation rates.

Decreased ice concentration during summer melt results in significant *in situ* heating of the ocean surface, which can then further melt ice (Steele et al., 2008). Significant bottom melt of sea ice due to ocean heat has been observed in recent years (Perovich et al., 2009). The role of the oceans in forcing the observed reduction in ice thickness and extent is still a matter of debate. Most or all of the heat of the Atlantic water away from the continental shelves is well sequestered below a strong halocline created by the fresher Pacific water, river input, and a net accumulation of freshwater from precipitation minus evaporation. On the other hand, the Pacific water entering the Arctic Ocean from the Bering Strait is much closer to the surface and may play a role in the reduction of the ice extent in localized regions in the Chukchi Sea and perhaps beyond (Zhang et al., 2009). The precise role of ocean heat transport in the sea-ice decline is more ambiguous. Observations by Shimada et al. (2006) and Woodgate et al. (2010) suggest that increased inflow of warm Pacific waters strongly influenced the dramatic reductions in summer sea ice in the western Arctic. Within the Arctic basin the solar heat absorbed by the ocean may be stored so that ice that advects over the region is rapidly melted (Perovich et al., 2009) or the formation of new ice is delayed. Ocean heat has always played a much larger role in the peripheral seas, such as the Bering and Barents Seas.

The condition of the ice influences its future state. As sea ice thins, it becomes more susceptible to melting completely over the course of a summer, which leads to associated melt, albedo, and ocean forcings (Holland et al., 2006; Lindsay et al., 2009). This leads to the concept of ‘pre-conditioning’, where a thinner ice cover going into the summer melt season is a strong indicator of low total extent at the end of summer. Model simulations demonstrate this effect and show that the initial condition of the ice thickness distribution is an important factor in accurate predictions of summer minimum extent (Lindsay et al., 2008; Zhang et al., 2008a,b; Kauker et al., 2009).

There is still much to understand about the interplay of these factors and their influence on sea ice. It is clear that these factors work together in complex ways and that there are many feedbacks between the sea ice, atmosphere, and ocean (discussed in detail in Section 9.2). The climate forcings and feedbacks with sea ice will ultimately determine the future evolution of the sea-ice cover. Model forecasts of this future evolution and comparisons with observations are addressed in Section 9.1.7.

9.1.7. Modeling: Comparing model output with observational data

There is considerable scatter among simulated rates of Arctic sea-ice loss by most atmosphere-ocean-ice general circulation models (AOGCMs), but in general the observed summer sea-ice loss is faster than anticipated (Stroeve et al., 2007). By 2008, the Arctic had already reached a milestone of two sequential years of low summer sea-ice extent, a situation that the Intergovernmental Panel on Climate Change Fourth Assessment Report (IPCC AR4, IPCC, 2007) projected would not occur until later in the century (Stroeve et al., 2007). However, the reasons for this are complex, and are likely to be related to insufficient parameterizations of the ice-albedo feedback, ice dynamics and deformation, and heat storage in the ocean surface mixed layer. Differences between models result from their different formulations, the impact of random phasing of natural low frequency variability, and different future greenhouse gas emissions scenarios, as shown by Zhang and Walsh (2006).

Ridley et al. (2007) investigated the sensitivity of the Hadley Center Model (HadCM3) to perturbed model parameters and found a large range in the sensitivity of Arctic sea-ice retreat to global temperature change, from 11% to 18 % per °C. From simulations of the Community Climate System Model (CCSM3), Holland et al. (2006) showed that AOGCMs simulate instances of rapid September ice loss much like that which occurred in 2007. However, from the seven ensemble members considered, there is a wide range in the timing of such events with the earliest event occurring in 2013 and the latest not initiated until 2045. These ensemble members use exactly the same model but the initial conditions are slightly different. Given the chaotic nature of natural variability in the climate system, different phasing of the decadal maxima and minima of the sea-ice loss due to natural variability can be expected, in addition to the long-term trend due to external (anthropogenic) forcing. A critical result is that the apparent sea-ice response to the sum of natural and forced atmospheric and oceanic changes is not linear. Once sea ice is removed there is no return to previous conditions as long as the concentration

of greenhouse gases remains high. This is what is probably occurring in the real world after the summer sea-ice losses of 2007 and 2008. However, there is still high natural variability in the system and increases the following year from record or near-record lows, as was seen in 2009, are not unexpected in model projections (Holland et al., 2006; Goosse et al., 2009). It is notable that over 50% of the IPCC AR4 models simulate instances of rapid September ice loss similar to the 2007 observed transition (Holland et al., 2006). This suggests that while models generally underestimate the historical ice loss, they do reasonably simulate the superposition of natural variability and anthropogenically forced change that allows for instances of rapid ice retreat.

Such results are summarized in Figure 9.17 which shows projected sea-ice extent for a subset of the 23 IPCC AR4 models. The six models shown all satisfy an observational constraint, i.e., that they show a similar amount of initial (i.e., pre-industrial) September sea ice and the same seasonal range as the Hadley sea-ice dataset (Rayner et al., 2003). It is clear from the figure that the selected models project a faster rate of sea-ice loss than the average of all models. In addition, some of the time series are near the recent sea-ice minima. If a model was initialized with the observed 2007/2008 minimum extents, a future loss of sea ice to 1 million km² in summer would be expected to occur around 2040, as the future rate of sea-ice loss is dependent on the magnitude of initial conditions (Zhang and Walsh, 2006). However, models respond differently to sudden change and may return to the long-term trend behavior, which corresponds to the prevailing forcing, rather than continue on the trend implied by the recent observations. The ensemble average, which removes the sensitivity due to natural variability and model differences, should be close to the sea-ice response to greenhouse forcing alone. The conclusion that sea ice is retreating faster than expected is based on the comparison of the apparent fast track that the real world is on and in a few ensemble members, representing the contribution from natural variability, compared to the ensemble mean behavior.

The reasons for the large variation in simulated ice-extent loss among the different climate models are difficult to determine. Simulated ice-extent loss is related to the initial




Figure 9.17. Northern hemisphere September sea-ice extent as simulated by six IPCC AR4 under the IPCC A1B emissions scenario. The models were selected for simulating mean and seasonality of sea-ice extent within 20% of the observed values. The thick blue line is the ensemble mean for the six models and the thick yellow line is the ensemble mean for all IPCC AR4 models. The thick red line shows the observed values based on Hadley Centre sea-ice analysis (HadISST). Source: after Wang and Overland (2009).

(mid-20th century) sea-ice state, the changing ice-mass budgets, and how ice-volume loss translates into ice-extent change. Holland et al. (2008a) assessed Arctic sea-ice mass budget changes over the 20th to 21st century from 14 IPCC AR4 models and related these to the changing September ice extent. As shown in Figure 9.18, the relationship between ice-volume loss and ice-extent loss is nonlinear. Models with excessively thick ice generally simulate the largest rates of ice-volume loss. However, this translates into very little ice-extent change (Figure 9.18). In contrast, when the Arctic sea ice thins below about 2 m, which is the typical maximum thickness obtainable by FYI during one winter, substantial rates of ice-extent loss occur as large regions of the ice pack can completely melt out during summer. Models do vary considerably in the September ice-extent change realized by a similar ice-thickness loss even in this thinner ice regime. As shown by Holland et al. (2008a) one contributing factor appears to be the spatial distribution of ice within the Arctic; models with a smaller spread in the March Arctic ice-thickness distribution tend to simulate larger ice-extent loss for a similar mean ice-thickness change. Thus, to simulate a reasonable Arctic ice-extent response, it is necessary to realistically simulate both the mean and spatial distribution of ice within the Arctic.

Bitz (2008) also investigated some of the reasons for the uncertainty in simulated Arctic sea-ice response to external forcing. This author determined that the role of uncertainties in the strength of the surface albedo feedback for sea-ice thickness loss were small. However, the influence of the mean state on uncertainty in sea-ice thickness response (and by extension on simulated sea-ice extent loss) was considerable. This is likely to be due to the importance of the sea-ice thickness for the strength of the stabilizing sea-ice thickness – sea-ice growth rate feedback. This agrees with the results of Holland et al. (2008b) that the initial sea-ice state is critically important for the simulation of the sea-ice thickness and sea-ice extent response to external forcing.

Regional sea-ice models have been used to investigate the potential causes of the 2007 summer sea-ice loss. Kauker et al. (2009) and Wang et al. (2009) looked at anomalous wind

patterns, sea-ice thickness and ocean transport. Lindsay et al. (2009) suggested a long-term trend in sea-ice volume. Gorodetskaya et al. (2008) noted a range of simulated cloud properties in different IPCC models which have an impact on the surface radiation balance for sea ice. The Arctic Ocean Model Intercomparison Project (AOMIP) compared sea-ice concentrations and sea-ice drift in 20th century hindcasts (Gerdes and Koeberle, 2007; Johnson et al., 2007; Martin and Gerdes, 2007). Compared to observations, differences were a result of changes in both the atmospheric forcing used and model characteristics. Model to model uncertainties become larger when sea ice is investigated on a regional basis (Parkinson et al., 2006; Overland and Wang, 2007).

Looking forward, it is clear that models indicate large year-to-year variability in the total summer sea-ice extent, making short-term predictions difficult. As summer sea-ice extent continues to decline, model simulations indicate that this variability will initially increase due to the larger fraction of thinner, FYI that is more susceptible to variable seasonal atmospheric and oceanic forcing (Goosse et al., 2009). As the decline continues further, the variability will decrease due to less summer sea ice overall.

The amount of year-to-year climate variability may be key to the timing of a transition to a seasonally sea ice-free environment. A modeling study investigating future sea-ice response to warming found that, as expected, a stronger average temperature trend makes an earlier loss of summer sea ice more likely (Zhang et al., 2010). However, the year-to-year variability in temperature was also found to play a crucial role. Higher variability, similar to that of the past two decades, increases the likelihood of summer ice-free conditions by 2050, while lower variability (similar to conditions between the late 1940s and the late 1980s) results in a reduced chance of ice-free conditions by 2050.

Understanding the processes influencing sea ice and feedbacks with the climate system, discussed in Section 9.2, are important to developing better models and improved predictions. Accurate predictions are crucial for anticipating and responding to impacts on Arctic biological systems (see Section 9.3) and human society (see Section 9.4).




Figure 9.18. Projected change in September sea-ice area within the Arctic (left) and the 21st century September sea-ice area vs annual average sea-ice thickness (right) for 14 different CMIP3 models. Source: Holland, et al. (2008a).

9.2. Physical feedbacks and forcings

- Recent research has better quantified some interactions between the sea ice, ocean, and atmosphere, particularly during the extreme summer ice loss of 2007.
 - Trends in cloud cover have suppressed some surface warming over the Arctic Ocean.
 - Loss of summer sea ice and increased upper ocean heat storage is modifying regional wind patterns, with the potential for impacting the mid-latitudes over the coming decades as sea ice retreats further.
 - Reduced sea-ice cover has increased solar heat input to the ocean and the amount of melting: an ice-albedo feedback.
 - Heat fluxes from Bering Strait and warmer Atlantic waters are playing a larger role in the decline of sea-ice cover.

9.2.1. Introduction

The observed decline in sea-ice cover is directly linked to dynamic and thermodynamic forcing and is impacted both by positive and negative feedback processes. Polar amplification of climate warming is attributed predominantly to positive feedbacks, including the ice-albedo feedback, and cloud-radiation feedback. Although there is much evidence for significant warming in the Arctic, the attribution and interdependence of the snow and ice albedo and cloud feedbacks on polar amplification is still an area of active research.

This section discusses the feedbacks and forcings that are contributing to the observed decline in Arctic sea-ice cover, as well as those which may be slowing this decline. Specifically, the ice-albedo feedback and the cloud-radiation feedback are examined. The consequences of black carbon on sea-ice albedo are considered and there is a discussion of the impact of surface morphological features on sea-ice conditions and feedback processes. Projections of future ice decay due to feedbacks are presented. Finally, the concept of sea-ice tipping points is introduced and discussed.

9.2.2. The ice-albedo feedback

As ice, or the snow on ice, melts its albedo decreases (see Box 9.5). This results in additional absorption of solar radiation by the ice and more melting, further decreasing the albedo. This positive loop is the ice-albedo feedback. Under warming climate conditions, this feedback can act on longer time scales to enhance the climatic changes. An initial warming of the climate will cause the onset of summer melt to begin earlier and the autumn freeze-up to start later. This leads to a larger area of the Arctic Ocean being covered by open water and darker sea-ice surfaces for a longer period of time. This longer melt season and reduced ice area leads to an increase in the absorption of solar energy, which goes to melting more ice or to heating the ocean. Heat in the ocean will delay the onset of autumn freeze-up, possibly resulting in thinner ice. This process acts over years to decades as a positive feedback on a larger, regional scale. A cooling climate would reverse the process, also leading to a positive feedback, with more ice driving more cooling.

Box 9.5. Sea-ice albedo

Albedo is the fraction of incident sunlight reflected by a surface. A surface that is a perfect absorber of sunlight has an albedo of zero, while a perfect reflector has an albedo of one. Albedo is a key parameter for the surface heat budget, as it strongly influences the radiation budget. Snow-covered sea ice has a much larger albedo than an ice-free ocean surface, meaning that it reflects much more of the sun's energy, limiting the ability of an ice-covered region of ocean to heat up, relative to ice-free ocean areas. Figure 9.19 shows a simulated look at the Arctic from space in summer after melting has begun. The snow-covered sea ice is bright, reflecting roughly 85% of the sunlight incident on the surface (Perovich et al., 2002a), while the open ocean is dark, reflecting only 7% of the incident sunlight (Pegau and Paulson, 2001). As the ice edge retreats, the white, snow-covered sea ice is replaced by black, open water; greatly increasing the input of solar heat to the ice-ocean system. The summer increase in the area of open water, together with the decrease in ice albedo caused by melting, combine to form the ice-albedo feedback (Perovich et al., 2002a).




Figure 9.19. A simulated view from space of Arctic sea ice in August. The view shows the north coast of Alaska, an area of open water where the ice has melted, and the main ice pack.

Figure 9.20 shows representative albedos for different surfaces in the ice pack (Grenfell and Perovich, 1984, 2008; Pegau and Paulson, 2001; Perovich et al., 2002) as well as the resulting amounts of solar energy absorbed by the surfaces on a typical cloudy day in early July (Intrieri et al., 2002) and the estimated thickness of sea ice that the solar energy absorbed in one day could melt.




Figure 9.20. The albedo of different types of sea-ice surface (numbers above bars) and the resulting daily absorbed shortwave flux for a typical cloudy day in early July. The right-hand axis converts the total solar energy absorbed in one day to the thickness of sea ice that this energy could melt. Source: based on Grenfell and Perovich (1984), Pegau and Paulson (2001) and Perovich et al. (2002a).

The large differences among albedos of different sea-ice surfaces also result in an unequal distribution of the melt progression. Once formed, a melt pond will absorb much more energy than the bare ice around it, leading to enhanced melt in and around the pond, growth of the pond, and a further reduction in albedo (Perovich et al., 2002a; Eicken et al., 2004). This aspect of the ice-albedo feedback as well as the lateral melt of ice floes increases its effectiveness by concentrating melt in areas where it will cause the greatest change in albedo.

The albedo feedback due to ice and snow cover has been examined in climate models at least since the work of Budyko (1969) and Sellers (1969). Coupled GCMs have been used to show that the albedo feedback is a major contributor to the projected amplification of future warming in the Arctic, and that it also contributes to warming globally (e.g., Hall, 2004). Quantifying the effect accurately with GCMs is difficult because of significant uncertainties in sea-ice parameterizations in the models (Curry et al., 2001) and because cloud cover must also be accurately modeled. As discussed in Section 9.2.8, there are countervailing factors, such as cloud cover (Covey et al., 1991), which can temper the influence of the ice-albedo feedback.

A pair of recent studies tried to quantify the strength of the ice-albedo feedback by fixing the seasonal cycle of the surface albedo in the climate models and comparing the results to model runs with variable albedo under a doubling of atmospheric carbon dioxide (CO_2) levels. Bitz (2008) found that the impact of the ice-albedo feedback factor on ice thickness was small in the NCAR Community Climate Model (CCSM3) because of the countervailing thin ice growth feedback. This author estimated the feedback factor f by holding the seasonal cycle of the surface albedo of sea ice and ocean fixed while doubling CO_2 . Ice-albedo feedback causes sea ice to thin about 26% more compared to a model run without ice-albedo feedback. A reduction of 26% corresponds to a feedback factor of only $f = 0.21 \pm 0.02$, where the error here is an estimate of uncertainty in the model. As might be expected, the feedback was strongest

in the seasonal ice zones. Also using CCSM3 but fixing the albedo of all surfaces, not just the ocean, Graverson and Wang (2009) found that the surface albedo feedback amplifies the surface-temperature response in the Arctic area by about 33%, whereas the corresponding value for the global-mean surface temperature is about 15%. Even though the surface-albedo feedback is an important process underlying excessive warming at high latitudes, the Arctic amplification is only 15% greater in the variable than in the locked-albedo experiments. These authors found that an increase in water vapor and total cloud cover lead to a greenhouse effect that is greater in the Arctic than at lower latitudes and may explain a part of the Arctic surface air-temperature amplification.

Perovich et al. (2007) investigated how changes in the amount of open water in the ice cover affect the total solar heat input to the ocean. They took a synthetic approach, combining field observations of ocean albedo, satellite-derived ice concentrations, and incident irradiances determined from meteorological models to calculate the amount of solar heat input directly to the upper ocean for every day from 1979 through 2005.

Trends in annual solar heat input directly to the ocean for each grid cell from 1979 to 2005 are mapped in Figure 9.21. Positive trends are pervasive over much of the Arctic with values as large as 4% per year. A smaller region with a negative trend in solar heat input is evident along the northern edge of the Canadian Archipelago. In this region, ice motion from the eastern Arctic has resulted in increases in ice concentration. Overall, 90% of the area shows a positive trend of increasing solar heating while 10% shows a negative trend. Trends were typically modest in magnitude, with the median and mean trend equal to an increase of 0.6 and 0.8 % per year respectively. The mean and median trends appear small; a few centimeters per year of ice thinning and $< 1 \text{ W/m}^2$ of additional heat flux per year. The median solar heat input increased by 17% from 1979 to 2005, while the region of greatest increase showed a more than doubling of the solar heat input.

The enhanced solar heating has had an observable impact on the ice cover. There was a record minimum sea-ice extent in September 2007, with a large ice retreat in the Beaufort Sea. *In situ* ice mass balance measurements in this region showed anomalously large amounts of bottom melting (Perovich et al., 2008). Ice mass balance measurements made from an autonomous buoy showed 2.10 m of bottom melt in 2007 in the Beaufort Sea. This was more than six times the annual average of 0.34 m for the 1990s and two and a half times the observed bottom melt in 2006. This observation indicates that bottom melting was a major contributor to the 2007 ice loss in the Beaufort Sea.

The extreme amount of bottom melting observed in the Beaufort Sea in 2007 required considerable heat from the upper ocean. Earlier work has established the importance of solar heating of open water on bottom melting of the ice (Maykut and McPhee, 1995; Perovich, 2005). The solar radiation deposited in areas of open water was a major contributor to the large amount of ocean heat in 2007. Perovich et al. (2008) showed an ocean solar heat anomaly in the Beaufort Sea for 2007 that was 400–500% higher than the average for 1979–2005 and that this was a direct consequence of a large increase in the area of open water. The solar heat input through open water was sufficient in magnitude and timing to generate the observed bottom melting, illustrating the impact of an ice-albedo feedback on bottom melt.




Figure 9.21. Linear trend of modeled annual total solar heat input directly to the ocean from 1979 to 2005. Source: Perovich et al. (2007).

9.2.3. Impacts of black carbon on the sea-ice albedo

There has been growing concern in recent years over the impact of black carbon on the albedo of sea ice, particularly when the ice is snow covered. Black carbon (BC or soot) is composed of small particles emitted by fossil fuel and biomass combustion. The sources are both natural (forest fires) and from human activities (industry, transport, household). The particles, which are black, absorb sunlight both in the atmosphere and where deposited on the surface, directly affecting the radiative energy balance. In addition, the absorbing BC particles may affect clouds and act on the climate through semi-direct and indirect effects (Hansen et al., 1997; Ackerman et al., 2000). Most of the particles stay close to the sources, mainly at lower latitudes, but some are transported to the Arctic. In the Arctic, some particles are deposited on the snow and ice, where even very low concentrations of BC will reduce the surface albedo.

9.2.3.1. Processes

The transport and deposition of polluted air masses from the lower latitudes to the Arctic varies seasonally and interannually (Shindell et al., 2008). The transport processes are not fully understood and different models give somewhat different results (Koch and Hansen, 2005; Stohl, 2006; Shindell et al., 2008). The phenomenon known as ‘Arctic haze’ is believed to be the main transport mechanism for air pollutants to the Arctic. It occurs in late winter and springtime when the meteorological conditions allow intrusions of pollution plumes from lower latitudes. Near the source, BC tends to be hydrophobic, but with time the particles are transformed and become more

hydrophilic. This makes them prone to take up water and be removed by clouds (Ogren et al., 1983; Ramanathan et al., 2007), be incorporated into snowflakes, or be scavenged as snow falls through the air. Transformation processes and removal mechanisms influence the mixing state of the particles, which in turn influences their optical properties.

Snow- and ice-covered surfaces have a high albedo (Wiscombe and Warren, 1980; Grenfell et al., 1994) and the deposition of BC and other dark particles will reduce this. However, BC is estimated to be about 50 times as effective as soil dust, and 200 times as effective as volcanic ash in its ability to reduce albedo (Warren and Wiscombe, 1980; Warren, 1982, 1884). Model results indicate that nanogram per gram amounts of BC can significantly reduce snow albedo (Warren and Wiscombe, 1980). Concentrations of BC measured in Arctic snow in 1983/84 suggest a possible broadband albedo reduction of 0–4% depending on snow grain size (Warren and Wiscombe, 1985). Radiative forcing by BC in snow can have a significant climatic effect, because of its high ‘efficacy’ resulting from several positive feedbacks (Hansen and Nazarenko, 2004; Jacobson, 2004). Flanner et al. (2007) computed a large radiative forcing over snow-covered regions, particularly in spring.

9.2.3.2. State and trends

The main global sources of BC emissions are China, Pacific Asia, North America and Europe (Bond et al., 2007). Globally, BC emissions are decreasing and projections show a drop from 8.0 Tg in 1996 to 5.3–7.3 Tg by 2030, under different IPCC emissions scenarios (IPCC, 2007), and with different spatial distributions (Streets et al., 2004). Levels of light-absorbing BC have been measured in Arctic air (Sharma et al., 2006) at concentrations of 25 to 75 ng/m³ (Point Barrow, Alaska, 1989–2003), 20 to 40 ng/m³ (Alert, Nord-Canada, 1989–2003), and 15 to 90 ng/m³ (Ny-Ålesund, Svalbard, 2002–2008). Concentrations are highest in winter and lowest in summer. Measurements of the all-year mean BC levels from 1989 to 2003 indicated significant reductions at Alert and Barrow, while more recent data show indications of an increasing trend over the past few years (Sharma et al., 2006). Ny-Ålesund shows a similar recent trend reversal where a decadal reduction until 2006 shifted to a significant increase over following three years.

Observations show relatively low levels of elemental carbon (EC; a proxy for BC) in snow both at Svalbard and Barrow in 2007. Levels in snow depend on both the amount of precipitation and the BC levels in air, as precipitation efficiently cleans the air of hydrophilic carbon. The total deposition for the entire year is important for the albedo, particularly in spring when the snow is melting, as there are indications that the particles concentrate on the surface when the snow is melting. Current EC levels measured in Arctic snow are generally lower than published data from 1983/84 (Clarke and Noone, 1985). The lower values are not entirely due to reduced emissions as different analytical methods were used for the recent and earlier measurements (EC_a and BC_c, respectively; Bond and Bergstrom, 2006). Studies have shown that apparent elemental carbon (EC_a), although noted to be a proxy for BC, is of the order of a factor of two lower than equivalent (BC_a) (Watson et al., 2005). Results from Svalbard 2007 (Forsström et al., 2009) used in the Warren and Wiscombe (1985) model showed that 11% of new snow samples and 63% of old snow samples had

enough BC to reduce the spectral albedo by 1% in new snow at the most sensitive wavelength.

9.2.3.3. Future projections

Changes in BC deposition may exacerbate or moderate future changes in Arctic sea-ice cover. Although the global trend indicates BC reductions, current understanding of deposition processes is not sufficient to reproduce observations using numerical transport models (International Workshop on Black Carbon in Snow, Tromsø 13–14 August 2009).

Transport of BC to the Arctic, rather than emission rates, is currently the factor limiting BC levels in the Arctic. As the temperature difference between the Arctic and lower latitudes weakens due to Arctic amplification of warming, changes in the typical transport patterns can be expected and thus possible shifts in the relative contribution of BC to the Arctic. In addition, the possible increase in Arctic shipping associated with a reduced sea-ice cover would result in more emissions released directly within the Arctic. This has critical implications for climate forcing (Law and Stohl, 2007) as studies show that shipping is already affecting the Arctic atmosphere in summer (Xie et al., 2006; Lack et al., 2008).

Most of the ongoing and predicted rapid changes in the Arctic are a direct consequence of increased levels of greenhouse gases with long atmospheric lifetimes. The only viable way to reduce their impact is to reduce their atmospheric concentration. This is a long-term commitment. Reducing short-lived pollutants, such as BC, holds promise for achieving an impact on a shorter time scale, thereby buffering some of the detrimental effects of long-lived greenhouse gases. In particular, the reductions can slow warming of the atmosphere and melting of the snow and ice (Law and Stohl, 2007).

9.2.4. Importance and role of local-scale sea-ice features

The sea-ice cover is not a flat slab of uniform thickness, but a complex mosaic of ice of various thicknesses, ages, and characteristics. In winter, the sea-ice floes are frozen together to form a flawed, but continuous ice cover. During summer, the ice cover breaks up to form a granular ensemble of individual floes. Meltwater collects on the surface forming ponds. Spatial heterogeneity is found at all length scales in sea ice, but is particularly apparent on lateral length scales from tens of meters upward.

9.2.4.1. Thermodynamic processes

Differential rates of freezing and melting result in the creation of horizontal heterogeneity on length scales of the order of meters or more. One of the most dramatic processes, and that which most clearly impacts sea-ice thickness and extent, is the formation of melt ponds in summer. Melt ponds form as meltwater accumulates on the surface of sea ice from snow and sea-ice melt. The area covered by ponds depends on surface topography, melt rates, and ice permeability. Melt ponds affect the heat and mass balance of the ice cover in various ways (Taylor and Feltham, 2004), for example, the latent heat released in freezing of melt ponds keeps the ice relatively warm and reduces winter ice growth. The most

important effect that melt ponds have on the heat and mass balance of the ice cover is through their impact on albedo. Pond-covered ice has a lower albedo, absorbs more solar radiation, and therefore melts more quickly, than bare sea ice. Melt rates for ponds are estimated to be up to two to three times greater than for bare ice (Fetterer and Untersteiner, 1998; Perovich et al., 2002a). As shown in Figure 9.20, the albedo of pond-covered ice is much less than bare ice or snow-covered ice (e.g., Grenfell and Maykut, 1977; Perovich et al., 2002a; Eicken et al., 2004), and is principally determined by the optical properties and thickness of the ice beneath the pond.

The fractional area of the sea-ice surface covered in ponds is needed to determine the area-averaged albedo of the ice cover, an important quantity in the sea-ice components of GCMs. The pond fractional area has been most extensively studied from visual photography using aircraft and balloons (Derksen et al., 1997; Perovich and Tucker, 1997; Tschudi et al., 2001, 2008; Perovich et al., 2002b; Eicken et al., 2004), but also from satellite imagery (Fetterer and Untersteiner, 1998; Barber and Yackel, 1999). These studies show that the fractional pond coverage has been highly variable, with values ranging from 5% to 80% depending on such factors as ice type (FYI or MYI), time elapsed since the beginning of the melt season, surface roughness, and snow cover.

Current understanding of melt pond evolution comes mostly from field experiments, with the Surface Heat Budget of the Arctic (SHEBA) year-long camp from autumn 1997 to autumn 1998 (e.g., Perovich et al., 1999; Eicken et al., 2002, 2004) providing some of the most detailed information to date. Various attempts have also been made to model melt ponds. Taylor and Feltham (2004) developed a 1-D model of melt ponds that consisted of heat and salt balance equations, and a two-stream radiation model. A subsequent cellular automata model was developed to study the area evolution of melt ponds on sea ice (Lüthje et al., 2006). This model divides a sea-ice floe into square cells, inside which the pond height and ice depth are recorded and allowed to evolve according to the state of the surrounding cells. While the two models have led to improvements in understanding of the processes governing melt pond evolution, their detailed complexity makes them unsuitable for use in GCMs. Flocco and Feltham (2007) and Pedersen et al. (2009) have both developed melt pond models for use in the sea-ice component of a GCM by building on the existing theory of the evolution of sea-ice thickness distribution, taking into account vertical drainage of meltwater, and other factors.

Field observations and modeling studies both indicate that the spatial distribution, and extent, of melt ponds is strongly influenced by ice topography, and thus the age of the ice. Since FYI is relatively flat, the ponds tend to be of larger area and shallower, compared to ponds on MYI (e.g., Eicken et al., 2004). In recent years, the areal fraction of FYI has been increasing relative to MYI (Cavalieri et al., 2003). For a given volume of melt water, shallow ponds covering a large area result in greater melting than deeper ponds covering less area (e.g., Eicken et al., 2004; Lüthje et al., 2006). Since ponds on FYI cover a larger area than those on MYI, the increase in the relative abundance of FYI indicates that the significance of melt ponds to the heat and mass budget is likely to increase.

9.2.4.2. Dynamic processes

The forces acting on the ice cover, predominantly due to winds and ocean currents, can cause ice convergence with thinner ice buckling and over-riding to form pressure ridges or rafted ice. Pressure ridges can extend horizontally over several kilometers, and in cross-section consist of a triangular sail and keel, with the keel typically five to six times deeper than the sail is tall, with total thickness typically between 5 and 20 m. Since thin ice will raft and ridge more easily than thicker ice, ridging can act as a kind of negative feedback process in regions of convergence whereby thinner ice is transformed into thicker, ridged ice and more open water is exposed in adjacent regions of divergence. This open water can be a region of intense ice growth in winter or increased solar absorption in summer.

Sea ice is relatively weak in tension and divergence of the ice cover can result in the formation of cracks, which can join up to form leads. Winter leads are typically long, linear features covering only 1–10% of the area. They are of significant importance since they expose the ocean directly to the atmosphere and are regions of rapid ice growth, large heat loss to the atmosphere, and considerable salt rejection to the ocean.

Sea-ice extent is affected by processes occurring in the marginal ice zone. The seasonal retreat of sea ice at the ice edge is caused by a combination of advection, mechanical floe break-up, and melting at the floe edges and upper and lower interfaces (Squire, 2007). As floes break up, the total perimeter, or edge length, of a given area of sea ice increases. The reduction in floe size affects the response of the ice cover to the incoming wave field, promoting further jostling between the floes, and more break-up. This in turn promotes further lateral melting creating a positive feedback between dynamic and thermodynamic processes.

9.2.5. The cloud-radiation feedback and its impact on the surface-heat budget

Clouds play a dominant role in determining shortwave and longwave radiative transfer in the atmosphere. Cloud area, height, thickness and water content, among other properties, all influence radiative fluxes (Curry and Ebert, 1990). For sea-ice modeling, having an adequate description of cloud cover is especially important for estimating radiative fluxes at the surface because surface melting and ice growth are sensitive to shortwave and longwave radiation (Maykut and Untersteiner, 1971; Curry and Ebert, 1990). As a result, there are strong couplings between the sea ice, surface albedo, and clouds that have been termed the ice-albedo (Section 9.2.2) and cloud-radiation feedbacks (Barry, 1984; Makshtas, 1991; Curry et al., 1995; Makshtas et al., 2003, 2007).

Over the course of a year, the net effect of clouds over the central Arctic Ocean is to warm the surface (Curry and Ebert, 1992; Schweiger and Key, 1992; Intrieri et al., 2002). Only in the middle of summer does the cloud cooling effect overwhelm the warming effect for a period of time that is determined largely by cloud type, sun angle, and surface albedo. Observations over the past decade have revealed that liquid water clouds impart the greatest radiative influence on the Arctic surface radiation budget. In general, low-level stratiform liquid and mixed-phase clouds exert the most significant cloud effect on the surface radiation budget (Sedlar and Tjernstrom, 2009).

Several studies have attempted to evaluate the influence of ice crystal precipitation, also called ‘diamond dust’ (Overland and Guest, 1991; Curry and Ebert, 1992), Arctic haze (Blanchet, 1989), and aerosols (Leck et al., 2002; Prenni et al., 2006; Leck and Bigg, 2008) on the radiation and thermal state of the Arctic atmosphere and surface. For example, Curry and Ebert (1992), building on the cloud statistics of Huschke (1969), found surface longwave fluxes to be very sensitive to the presence of lower-tropospheric ice crystal precipitation. Overland and Guest (1991) compared model results with experimental data and found a discrepancy. They suggested that the missing modeled downward longwave radiation might be explained by ice crystal precipitation. They did not, however, rule out other explanations such as blowing snow or optically-thin clouds.

Despite the intensive development of methods for remotely sensing the atmosphere from space, uncertainties can be large for certain conditions, so *in situ* visual observations continue to play a critical role in the assessment of Arctic cloudiness. Many studies have used the Russian ‘North Pole’ (NP) drifting station cloudiness data, with about sixty years of observations, to verify their findings (Schweiger and Key, 1992; Lindsay, 1998; Makshtas et al., 1999; Lindsay and Makshtas, 2003). One of the most interesting findings from analysis of NP cloudiness data is the distribution of total cloud amount in winter and summer (Makshtas et al., 1999) (Figure 9.22), having a well-pronounced ‘U’ shape with fewer clouds in winter and a very high frequency of overcast conditions in summer. Both circumstances illustrate




Figure 9.22. Frequency of total cloud amount in winter and summer observed at the Russian drifting station ‘North Pole’ for 1954 to 2005 in comparison to NCEP-NCAR Reanalysis data. Source: Makshtas et al. (1999).




Figure 9.23. (a) Seasonal variability in equilibrium sea-ice thickness near the North Pole, calculated with the thermodynamic sea-ice model for surface-level air temperature T_a (green) and also when air temperature is restricted to $T_a = 0\text{ }^{\circ}\text{C}$ if $T_a > 0\text{ }^{\circ}\text{C}$ (blue) and $T_a = -0.5\text{ }^{\circ}\text{C}$ if $T_a > -0.5\text{ }^{\circ}\text{C}$ (red). (b) The same as for 'a' except that during winter the surface-level air temperature differs from the data by $10\text{ }^{\circ}\text{C}$ (red), $2.5\text{ }^{\circ}\text{C}$ (blue), $-2.5\text{ }^{\circ}\text{C}$ (green) and $-10\text{ }^{\circ}\text{C}$ (purple). (c) Values of the turbulent sensible (red) and latent (blue) heat fluxes and the longwave radiation balance (green) during winter 1958/59 near the North Pole calculated with the thermodynamic model. (d) The same as for 'c' except for the summer of 1958.

the variability of cloudiness with predominately clear (0 to 2 tenths) and overcast (8 to 10 tenths) skies. Analyses by Ikeda et al. (2003) and Makshtas et al. (1999) showed a strong negative trend of clear sky amount in winter and a modest negative trend of overcast conditions in summer. These trends would imply a reduction in sea-ice thickness due to a decrease in longwave radiative cooling in winter and an increase in incoming shortwave radiation in summer. Some statistical support of this supposition was given by Ikeda et al. (2003).

Makshtas et al. (2003, 2007) applied a zero-dimensional thermodynamic sea-ice model, similar to Semtner's (1976), to investigate the mechanisms responsible for the sensitivity of sea ice to external parameters. In the model, the energy fluxes between the atmospheric surface layer and the sea-ice surface had been calculated following Jordan et al. (1999) and Radionov et al. (1996). The model was integrated for 50 years at the North Pole with the same atmospheric forcing and an oceanic heat flux of 1 W/m^2 . The results of the standard run (Figure 9.23) show good agreement with the results of Maykut and Untersteiner (1971) for equilibrium sea-ice thickness and Lindsay (1998) for the mean values of energy fluxes during winter and summer. Numerical experiments show that the equilibrium sea-ice thickness is much more sensitive to changes in summer air temperature than winter air temperature. Figure 9.23a demonstrates that restricting the summer air temperature to $0\text{ }^{\circ}\text{C}$ or less and $0.5\text{ }^{\circ}\text{C}$ or less leads to 1.5-fold and 3-fold increases in the equilibrium sea-ice thickness, respectively. In

contrast, changing the surface air temperature in winter by $+10\text{ }^{\circ}\text{C}$ or $10\text{ }^{\circ}\text{C}$ changes the equilibrium sea-ice thickness by only 30% (Figure 9.23b). Figures 9.23c and 9.23d partly explain these results. In winter there is a strong negative feedback between the turbulent sensible heat flux (H) and the longwave radiation balance (R) (e.g., Makshtas et al., 1999). As a result, the conductive heat flux in the sea ice is not very sensitive to changes in air temperature; and, in turn, neither is the growth of ice on the bottom of the ice cover.

In winter, the negative feedback between the sensible heat flux and the net radiation together with insulating properties of snow stipulate the weak dependence of the conductive heat flux through sea ice on air temperature changes and, in turn, ice growth. In summer, on the other hand, the surface temperature of the ice is at or near the freezing point, and the negative feedback between the turbulent and longwave radiative heat fluxes cannot operate. As a result, any increase in the downward sensible heat flux caused by a small increase in the surface-layer air temperature and an increase in absorbed shortwave radiation due to a decrease in mean surface albedo (positive feedback) leads directly to increased melting of the ice cover.

Satellite studies show that winter cloud amount in the central Arctic appears to have been generally decreasing since the early 1980s, corresponding to a decrease in surface temperature (Wang and Key, 2003, 2005; Liu et al., 2008). The same studies show that spring cloud amount in the Arctic has been increasing. While this is somewhat in contrast to the

studies described by Ikeda et al. (2003) and Makshtas et al. (1999) for winter trends based on NP drifting station data, the difference is likely to be one of the spatial domain and period of study. A benefit of using satellite data to diagnose feedback mechanisms is the uncertainty in model simulations. For example, Gorodetskaya et al. (2008) used a variety of GCMs to demonstrate that the discrepancies in the modeled surface net shortwave flux resulting from the large variability in model representations of cloud properties partly explain the range in the model's sea-ice area changes.

The relationship between winds, radiative forcing, heat advection and the dramatic decrease in sea-ice cover over the past two and a half decades has been examined with satellite data. Francis et al. (2005) found that there are distinct regional differences in the relative roles of these parameters in explaining the variability of the ice edge position. The downwelling longwave flux anomalies explained about 40% of the variability, with northward wind anomalies important north of Siberia. Anomalies in solar insolation were negatively correlated with ice retreat in all regions, so the solar flux anomalies are overwhelmed by the longwave influence. Figure 9.24 illustrates the importance of the various parameters for different regions of the Arctic.

A number of recent studies have addressed the relationship between changes in cloud cover and sea ice. They are particularly relevant in light of the record minimum sea-ice extent in 2007. On the time scale of a single season, changes in cloud amount may have minimal influence on summer sea-ice melt. Schweiger et al. (2008a) used an ice-ocean model to examine the relationship between unusually clear skies during summer 2007 and the record sea-ice extent minimum. They found that the negative cloud anomaly and increased downwelling shortwave flux from June through August did not contribute substantially to the record sea-ice extent minimum in September. In contrast, Kay et al. (2008) calculated that their satellite-derived 16% decrease in summer cloud cover in 2007 led to an increase in the downwelling shortwave flux sufficient to melt 0.3 m of ice or warm the surface ocean by 2.4 K.

The influence of trends in sea-ice concentration and cloud cover on surface temperature over the Arctic Ocean from 1982 to 2004 was investigated analytically, and evaluated empirically with satellite products by Liu et al. (2009). They found that changes in sea-ice concentration and cloud cover played major roles in the magnitude of recent Arctic surface temperature trends. Significant surface warming associated with sea-ice loss, over 0.9 K/decade, was found over the Chukchi and




Figure 9.24. Percentages of variance in anomalies of sea-ice maximum retreat explained by anomalies in zonal wind, meridional wind, downwelling longwave flux, and the convergence of advected sensible heat in each peripheral sea of the Arctic Ocean. The bars represent explained variance at lags of 0, 10, 25, 50, and 80 days, where the ice edge anomaly lags the forcing anomaly. Source: Francis et al. (2005).

Beaufort Seas in autumn, accounting for most of the observed 1.1 K/decade warming trend. In winter, surface temperature trends associated with changes in cloud cover were found to be negative over most of the Arctic Ocean, with cloud cover trends explaining -0.91 out of -1.2 K/decade of the surface temperature cooling. In spring, 0.55 K/decade of the total 1.0 K/decade warming can be attributed to the trend associated with cloud cover changes. Figure 9.25 shows the relationship between trends in surface temperature, sea-ice concentration, and cloud cover.

While the ice-cloud relationship of primary interest in ice studies is the radiative impact of cloud cover on the surface energy budget, the influence of changes in ice cover on cloud

properties is an important part of the feedback process (see also Box 9.6). Satellite atmospheric sounder data and the ECMWF Re-Analysis (ERA-40) have both shown that sea-ice retreat is linked to a decrease in low-level cloud amount and an increase in mid-level clouds (Schweiger et al., 2008b). The changes in cloud cover are a result of changes in the atmospheric temperature structure and stability. However, the radiative effect of these changes is relatively small, as the cloud radiative forcing changes are compensated for by changes in the lower tropospheric temperature and humidity structure. Kay and Gettleman (2009) reached a similar conclusion about the relationship of cloud cover changes to modifications in near-surface static stability as a result of decreasing ice extent,




Figure 9.25. The seasonal all-sky surface temperature trend (top left), the temperature trend caused by sea ice concentration changes (top right), the temperature trend caused by cloud cover changes (bottom left), and the residual trends (bottom right) from 1982 to 2004. The residual trend is the difference between the all-sky surface temperature trend (1982–2004) and the sum of the two other trends. Source: Liu et al. (2009).

Box 9.6. Scientific challenges for the cloud-radiation feedback

Observations from satellites and surface. Continuing observations of clouds from the surface and improvement in satellite cloud-property retrievals, such as cloud amount, particle size, and water content, are crucial to improving understanding of cloud statistics and surface radiative impact.

Improvements in cloud modeling. The cloud-radiation feedback remains highly uncertain due to the spread in climate model simulations at high latitudes. Accurate treatment of clouds in models and improvements in cloud model parameterizations are needed to reduce uncertainties in future Arctic and global climate change projections.

Feedbacks and processes taking place on the local scale. Understanding the sensitivity of cloud processes to regional changes at high latitudes (e.g., aerosol, sea-ice extent, snow cover) is required to accurately project climate changes in the Arctic region and their global impacts.

particularly during autumn. It was found that owing to their seasonal timing, the response of cloud cover to sea-ice loss plays a minor role in regulating the summer ice-albedo feedback, but a larger role in the cloud-ice feedback in autumn.

9.2.6. Feedbacks and forcings related to changes in atmospheric transport

9.2.6.1. Wind forcing and ice loss

Atmosphere pressure fields and winds drive ice motion and so can have a large impact on the overall state of the ice cover. To illustrate this, consider the example of 2007 when the Arctic sea-ice extent reached a record minimum (Box 9.7). While this record low of total ice extent was set in September 2007 (Maslanik et al., 2007; Comiso et al., 2008; Drobot et al., 2008; Perovich et al., 2008), the distribution and extent of different sea-ice type and thickness classes in spring (March to May) before summer melt, hold critical information for understanding the many varied and complex causes of the record reduction (Lindsay et al., 2009). Arctic sea ice consists of two major classes: perennial or MYI defined as sea ice that survives at least one summer (Armstrong et al., 1973), and seasonal or FYI that grows in the current freezing season and is typically thinner than perennial ice (Haas et al., 2008). The old and thick MYI is important to the stability of the Arctic sea-ice cover, as it is less affected by interannual variations in ice growth and melt. The SeaWinds scatterometer aboard the QuikSCAT satellite has been proven particularly useful in delineating MYI and FYI (Nghiem, 2003; Nghiem et al., 2005, 2006, 2007; Nghiem and Neumann, 2007).

Atmospheric forcing continued to push the ice cover from the Russian Arctic toward Greenland and to enhance the ice transport out of the Arctic via both Fram Strait and Nares Strait in winter and spring 2008. Ice export was also facilitated by the greater sensitivity of thin ice to wind forcing (Gascard et al., 2008; Rampal et al., 2009). By 1 March 2008, the extent of MYI was reduced by one million km² compared to that

Box 9.7. The Polar Express

Wind forcing plays a significant role in changes in the sea-ice cover. In summer 2007, wind forcing was driven by a dipole anomaly pattern of the surface level pressure with a coexistence of a pronounced atmospheric low pressure over the Barents Sea together with a strong high pressure over Canada Basin. Clockwise winds around the high pressure merged together with counterclockwise winds around the low pressure to set up the persistent wind anomaly along the Transpolar Drift Stream (TDS) that enhanced the ice transport out of the Arctic Basin via Fram Strait (Nghiem et al., 2006; Gascard et al., 2008). This phenomenon is referred to as the ‘Polar Express’ (Figure 9.26) (Nghiem et al., 2007). A strong Polar Express forces ice loss by four processes: (i) compressing sea ice from both sides of the TDS, (ii) pushing sea ice from the Russian Arctic toward Greenland while accelerating the TDS, (iii) transport of sea ice by the TDS out of the Arctic, and (iv) melting of the exported sea ice in the Greenland Sea by warm Atlantic waters originating from the south (Nghiem et al., 2006, 2007). The Polar Express was strong in 2007 and together with other factors contributed to the record low 2007 summer ice extent.




Figure 9.26. Schematic illustration of the Polar Express phenomenon.

at the same time in 2007 (Figure 9.27). QuikSCAT results, together with the buoy-based Drift-Age Model estimates in half a century (1957–2008), showed that MYI extent decreased in the 2000s at the rapid rate of 1.5 million km² per decade, which tripled the decreasing rate in the previous three decades (1970 to 2000) (Nghiem et al., 2008). Observations in 2009 suggested a split between two main perennial ice packs (Figure 9.27): the Transpolar Drift perennial ice pack and the north Greenland perennial ice pack, extending from the North Pole to Fram Strait.

A strong Polar Express event requires: (i) the coexistence of low and high surface level pressure (SLP) anomalies; (ii) the low and high pressure anomaly centers to locate at appropriate places such as the low above the Barents Sea and the high over the Canadian Basin; and (iii) the low and high not to be very far apart. When the locations of the SLP anomaly centers switch to




Figure 9.27. Comparison of Arctic sea-ice age distribution on 1 March 2007, 2008, and 2009.

different places, such as the low over the Russian Arctic Ocean and the high above the north of the Greenland Sea, the dipole pattern may reduce ice transport out of the Arctic, slowing the sea-ice decline.

Previous studies have illustrated connections between sea ice, SLP, and stratospheric forcing on weekly timescales in the Beaufort Sea region from 1979 to 2000 (Lukovich and Barber, 2006). In particular, it was shown that reversals in the Beaufort Gyre occur throughout the annual cycle, with variability in strength and timing of cyclonic circulation of sea ice between years having implications for ice convergence and divergence in the region. Reversals in the Beaufort Gyre were shown to coincide with reversals in SLP for the region of interest. In addition, maximum correspondence was observed between sea ice and stratospheric relative vorticity with a lag of the order of two to six weeks, while negative correlations were observed between surface relative vorticity and sea-ice motion, indicating that sea-ice motion is governed by surface and stratospheric atmospheric phenomena. Noteworthy is the anticyclonic circulation sea-ice regime in summer 2007, characteristic of the SLP high that dominated Canada Basin prior to the record minimum in ice extent in September 2007. Comparatively weak circulation is observed during late summer in 2008.

Recent studies also highlight a correspondence between stratospheric sudden warming (SSW) events and surface synoptic types in the Beaufort Sea region and demonstrate an increase in anticyclonic types during SSWs in winter that persists for up to 20 days (Lukovich et al., 2009). Furthermore, investigation of connections between surface synoptic types and ice motion in the Beaufort Sea region illustrates correspondence between surface cyclonic types and summer reversals in the Beaufort gyre.

Many models have underestimated Arctic sea-ice loss (Stroeve et al., 2007). Recently, Zhang et al. (2008b) and Lindsay et al. (2009) conducted a model study to show that preconditioning, anomalous wind forcing, and ice-albedo feedback were the main contributors responsible for sea-ice loss in 2007, and that Arctic sea ice has become vulnerable to the anomalous atmospheric forcing. Kauker et al. (2009) showed the importance of preconditioning using an adjoint

analysis of a coupled sea ice-ocean model. Wang et al. (2009) examined the SLP fields and used a coupled ice-ocean model to investigate the small extents of sea ice including the record minima observed in 2005 and 2007. What causes the change in the SLP field; how such change can be related to global temperature change; and whether the impacts can be amplified or suppressed by positive or negative feedbacks remain to be investigated.

9.2.6.2. Sea-ice impacts on atmospheric circulation

While it can be argued that decadal shifts in atmospheric wind patterns over the past decade contributed to recent reductions in summer Arctic sea-ice extent (Overland et al., 2008a; Wang et al., 2009), the increase in late summer open-water area is, in turn, directly contributing to a modification of large-scale atmospheric circulation patterns. Once there is a reduction in sea-ice cover in late summer, additional heat is stored in the ocean which is released to the atmosphere during autumn. Beginning in 2002, extensive regions in the Arctic during late autumn have surface air temperature anomalies of more than 4 °C and temperature anomalies above 850 hPa of 1 °C (Serreze et al., 2009). The transfer of heat from the surface to the troposphere is more effective as the strength of the normal Arctic stable boundary layer is eroded from below (Schweiger et al., 2008b).

These higher temperatures reduce the density of the air and contribute to an increase in the 500 to 1000 hPa atmospheric thickness field in every recent year with reduced sea-ice cover. Horizontal gradients in the thickness field impact pressure fields and winds over the Beaufort Sea. Compositing wind fields for late autumn 2002 to 2008 helps to highlight this contribution; for the years with diminished sea-ice cover there were extensive anomalous tropospheric easterly winds of ~1.2 m/s, relative to climatological easterly winds near the surface and upper tropospheric westerlies of ~3 m/s. (Climate Data Center, www.cdc.noaa.gov/cgi-bin/data/composites/printpage.pl). Changes in the Arctic atmosphere also impact farther afield in northern mid-latitudes (Francis et al., 2009). Responses can be complex,

as loss of sea ice north of Eurasia may result in a cooling effect over eastern Asia (Honda et al., 2009). With continuing loss of summer sea ice to less than 20% of its climatological mean over the next decades (Wang and Overland, 2009), increased modification of atmospheric circulation patterns and impacts on the global heat budget are anticipated (Rinke et al., 2006).

9.2.6.3. **Sea-ice impacts on carbon dioxide concentration in atmosphere and ocean**

Many studies have investigated the variability in atmospheric concentrations of (CO_2) over high-latitude Arctic Ocean areas and the role of sea ice in CO_2 variability. Anderson et al. (2004) found that dissolved inorganic carbon (fCO_2) increases with depth below the surface mixed layer. They suggested that this excess is a result of enhanced air-sea exchange of CO_2 caused by sea-ice formation and the rapid transport of high salinity brine out of the surface layer. Semiletov et al. (2004) showed that CO_2 concentration increases from the coastal region toward the ice-covered sea. Alekseev and Nagurny (2005) related winter variation in CO_2 concentration over the Arctic Ocean to ice dynamics. Alekseev and Nagurny (2007) showed that polar amplification of the annual cycle of CO_2 concentration over the Arctic Ocean is connected with active influence of sea ice on formation of a seasonal CO_2 cycle. The formation and growth of ice during winter is accompanied by allocation of CO_2 into the sub-ice water layer and directly to the atmosphere. They speculated that the Arctic Basin is more likely to be a source than a sink of CO_2 over an annual cycle.

9.2.7. **Projection: Impact of feedbacks on rate of sea-ice decay**

It is difficult to quantify the impact of climate feedbacks on rate of sea-ice decay because of their complexity. Surface-albedo feedback, for instance, is closely linked to atmospheric and oceanic processes. The impact of surface-albedo feedback on changes in sea ice depends on the dynamic and thermodynamic air–ice–sea interactions and is strongly influenced by clouds. It is also related to the preconditioning of sea ice (Zhang et al., 2000; Lindsay and Zhang, 2005). Under certain atmosphere, ocean, and sea-ice conditions, surface-albedo feedback may substantially enhance sea-ice decay.

The impact of surface-albedo feedback may best be illustrated by the record retreat of Arctic sea ice in summer 2007. The dramatic sea-ice retreat occurred after years of shrinking and thinning (e.g., Rothrock et al., 1999, 2008; Meier et al., 2007), linked to an increase in surface air temperature and changes in wind circulation (ACIA, 2004; Serreze et al., 2007). Changes in wind circulation are often associated with the Arctic Oscillation. The AO was strongly positive from 1989 to 1995, which advected a considerable amount of MYI out of the Arctic into the North Atlantic (e.g., Hilmer and Jung, 2000; Zhang et al., 2000; Lindsay and Zhang, 2005; Tsukernik et al., 2010). Since then, a more meridional atmospheric circulation pattern (southerly wind anomalies from the Pacific sector of the Arctic Ocean) has been observed (Overland et al., 2008a).

As a result of increasing surface air temperature and changing atmospheric circulation, MYI, particularly the oldest and thickest ice within the multiyear ice pack, has been

rapidly replaced in recent years by thinner FYI (Kwok, 2007; Maslanik et al., 2007; Nghiem et al., 2007) that is more sensitive to changes in atmospheric and oceanic forcing. The reduction in areal extent, thinning of sea ice, and the increased presence of young ice have significantly increased the surface absorption of solar radiation because of the positive ice-albedo feedback (Perovich et al., 2007, 2008).

During summer 2007, the meridional atmospheric circulation pattern was characterized by a strong southerly wind anomaly, which drove ice out of the Pacific sector of the Arctic Ocean and created a large area of thin ice and open water where surface albedo is lowered considerably. This surface-albedo feedback leads to enhanced surface solar heating, which results in increased melting at the ice surface and increased heat deposit in the ocean mixed layer (Steele et al., 2008; Zhang et al., 2008b). A warmer ocean mixed layer causes significant lateral and bottom melting (Perovich et al., 2008). About 70% of the Arctic sea-ice loss in summer 2007 is found to be due directly to the enhanced surface, lateral, and bottom melting, with 30% due to the wind-driven ice advection (Zhang et al., 2008b). The amplified ice melting suggests that under certain atmospheric and oceanic forcing the positive surface-albedo feedback may play a dominant role in sea-ice retreat in the Arctic.

Regional climate models (RCMs) also provide useful information on feedback processes in the Arctic. By prescribing forcing at the model boundaries, these studies can explicitly separate the influence of internal Arctic feedback processes and the forcing from lower latitudes. For example, Döscher et al. (2009) assessed the role of regional vs large-scale atmospheric circulation for interannual Arctic climate variability and found that recent sea-ice trends are largely associated with large-scale forcing outside the Arctic region. However, internally generated variability is not negligible and can be more important for some variables and locations. Regional climate modeling studies have also addressed biases in simulated fields through model intercomparison of specific Arctic climate features, such as the Arctic boundary layer structure (Tjernström et al., 2005). These types of study have provided insight into the major uncertainties associated with simulating future Arctic climate change.

9.2.8. **Negative feedbacks**

Changes in sea-ice cover result from the direct influence of forcing anomalies combined with feedbacks that act to amplify or damp the initial perturbation. As previously discussed, the Arctic is home to strong positive feedbacks making it susceptible to change. However, negative feedbacks must also be present given the relative stability that has presided in the Arctic system over long periods of the geological past (e.g., Polyak et al., 2010). Understanding the role of these negative feedbacks and their interaction with other aspects of system change is critical for developing accurate projections of the future state of the Arctic.

As has been recognized for some time, the conduction of heat through sea ice is dependent on ice thickness, causing thin ice to grow more rapidly than thick ice subject to the same atmospheric and ocean forcing. This relationship is nonlinear, having an inverse dependence on ice thickness. This basic fact of sea-ice thermodynamics gives rise to a fundamental stabilizing

feedback on ice thickness (L'Heveder and Houssais, 2001; Bitz and Roe, 2004). This reduces the net ice mass budget change in simulated future climate projections. Indeed a number of climate models simulate increased ice growth in future climate projections that partially compensates increases in ice melt (Holland et al., 2008b).

There are also indications that sea-ice dynamic processes may stabilize the Arctic sea-ice cover. In uncoupled sea-ice modeling studies, ice dynamics generally reduces the sensitivity of the ice cover to forcing perturbations (e.g., Hibler, 1984; Arbetter et al., 1999). This is related to the ice strength-ice thickness relationship, which causes thinner ice to more easily converge resulting in more ridging and mechanical thickening of the ice pack. This can also modify the ice velocity field and observational evidence does indicate an increase in ice speed associated with the thinning ice pack (Rampal et al., 2009). Coupled model simulations (Hewitt et al., 2001; Vavrus and Harrison, 2003) have found that ice dynamics reduces the climate sensitivity to increased CO₂ concentrations. However, the mechanisms responsible for this vary in different models.

Sea-ice growth, melt, and transport redistribute water and salt in the Arctic with potential climate feedbacks. Increased ice growth and brine rejection can enhance convection, resulting in deeper mixed layers and modified heat entrainment. This can influence the ice-ocean heat flux and provide a feedback to the sea-ice cover. Modeling studies have shown this to be an important mechanism in polynya formation in the Southern Ocean (e.g., Martinson et al., 1981; Goosse and Fichefet, 2001). Changes in sea-ice growth, melt and transport also have potential implications for the large-scale Atlantic meridional overturning circulation (e.g., Holland et al., 2001; Komuro and Hasumi, 2003) and the extension of this circulation into the Arctic (Bitz et al., 2006). Feedbacks associated with sea-ice insulating properties also modify the ocean circulation response to external forcing perturbations (Levermann et al., 2007). Changes in ocean circulation in turn influence the poleward ocean heat transport with consequential effects on sea-ice mass budgets. However, considerable uncertainty remains in the magnitude, importance, and sometimes even the sign of these sea ice-ocean circulation/mixing feedbacks.

9.2.9. Thresholds, tipping points and rates of change

With the recent rapid decrease in summer sea-ice extent in the Arctic and with the stark contrast seen between white, snow-covered ice and black open ocean, the question naturally arises as to whether the dramatic change in the surface means the entire system is poised to change rapidly and irreversibly. *Has the Arctic sea-ice system passed a tipping point?* was a question raised but not answered by Lindsay and Zhang (2005). This question has renewed scientific, political and economic interest after the surprisingly large decrease in Arctic sea-ice extent that occurred in summer 2007. It has evolved into the broader question of how Arctic sea-ice extent will evolve in the future. This section briefly describes current understanding of this issue and also touches upon the question of a possible tipping point for the loss of Arctic sea ice.

Considerable discussion has ensued about how vulnerable the Arctic sea-ice system is to passing a tipping point and indeed

about what constitutes a tipping point in this context. The notion is adopted here that a tipping point exists for sea ice if the ice does not recover from a certain ice loss caused by climatic warming even if the climate forcing were to return to the colder conditions that existed before the onset of that specific ice loss.

A dynamic system may be said to be in a stable state, where changes in the system remain small when it is perturbed; an unstable state, where the system changes rapidly, irreversibly, and of its own accord; or a metastable state, where the system is stable as long as it does not change, but becomes unstable if the state of the system moves a small amount in the right direction. A tipping point may be regarded as a metastable state.

The major forcing parameters that determine the state of the sea ice are the thermodynamic forcing (air temperature, humidity, cloud cover, ocean heat) and the dynamic forcing (winds, currents). The possibility of a tipping point depends on the nature of the feedbacks that result from changes to these forcings. A feedback parameter 'a' may be defined in terms of the changes seen in a system with and without the feedback operating:

$$\Delta X_{\alpha} = \Delta X_0 + a \Delta(X)_{\alpha}$$

where ΔX_{α} is, for example, the change in the September ice extent including the albedo feedback and ΔX_0 is the change expected in the extent due to global warming in the absence of feedbacks (Curry et al., 1995). The change measured might also be the mean surface temperature or the mean ice thickness. The feedback parameter can only be determined from modeling studies where the feedbacks can be turned off. If all of the feedbacks are linear with the forcing, then they only help determine the rate at which the ice changes as a given forcing parameter changes and do not cause a rapid and irreversible change. However if the feedbacks are sufficiently strong and sufficiently nonlinear, it is conceivable that they could contribute to forming a tipping point when the forcing conditions change.

Curry et al. (1995) conducted a study of the ice-albedo feedback in several 1-D models and emphasized the importance of evaluating the sensitivity of a model to perturbations of the forcing. Further, they emphasized that the ice albedo feedback is dependent on a range of physical parameters characterizing the ice cover, including ice extent, ice thickness distribution, snow depth, and melt pond coverage. They determined the feedback parameter 'a' for ice thickness and for surface temperature and found a wide range of values, from 0 to 10, depending on the model used and the parameter 'X' measured.

If the trajectory of the system does not retrace its original path when forcing conditions revert to normal, then the change is said to be irreversible. Eisenmann and Wettlaufer (2009) showed how the sea-ice system in a simple model can exhibit hysteresis when the thermal forcing first warms and then cools the polar regions. They showed that the trajectory reaches a bifurcation point (tipping point) under extreme warming where all of the winter ice is lost. In this case, owing to the albedo feedback, winter ice does not form again until an extreme amount of cooling is imposed.

Flato and Brown (1996) constructed a 1-D thermodynamic model that had two stable states: thin seasonal ice and thick perennial ice. A relatively modest change in climate was

sufficient to cause the model to jump from the thick perennial state to the thin seasonal state, thus exhibiting a tipping point.

Stern et al. (2008) examined the trajectory of a sea-ice system as described by the fractional monthly coverage of thin and thick ice. They examined this trajectory in the CCSM model and in a retrospective model simulation. They also constructed a simple empirical linear model with exchange parameters for each month of the year that converges to a stable annual cycle from any initial state. When a quadratic nonlinear term is included to simulate a crude ice-albedo feedback, the model exhibits two stable states, one with perennial ice and one with ice-free summers, resembling the projections of some climate models for the late 21st century. The existence of two possible stable cycles implies the existence of a tipping point between them.

A number of other studies have not found evidence of a tipping point as the amount of summer open water increases. Holland et al. (2006) found that several GCMs exhibit periods of abrupt ice loss in which the late summer ice extents decline rapidly for a period of five years or more, but the rapid decline does not continue until all of the summer ice is gone and is often followed by partial recoveries, not what would be expected for a tipping point.

A tipping point according to this definition has been suggested to exist for the loss of sea ice owing to various destabilizing feedbacks. Such feedbacks can lead to additional sea-ice loss once the ice cover has decreased by a certain amount. Among these destabilizing feedbacks is the ice-albedo feedback, which is probably the most often cited climatic feedback loop. As discussed in Section 9.2.2, less ice will lead to more absorption of solar radiation, and hence to a warmer Arctic with less ice. According to this simple picture, the ongoing loss of sea ice in the Arctic can only be stopped if the climate were to become significantly cooler. This automatically implies the existence of a tipping point for the loss of Arctic summer sea ice.

However, recent research consistently suggests that despite the ice-albedo feedback, no tipping point exists for the loss of Arctic summer sea ice (Winton, 2006a; Eisenman and Wettlaufer, 2009). There are two important reasons for the possible non-existence of a tipping point for the loss of Arctic summer sea ice. First, recent research suggests that the ice-albedo feedback is potentially less efficient than previously thought (Winton, 2006b; Bitz, 2008; Winton, 2008; Graverson and Wang, 2009). For example, the annual sea-ice minimum is reached in September at a time when incoming solar radiation is already rather weak.

The second reason for the possible non-existence of a tipping point for the loss of Arctic summer sea ice lies in the very high growth rate of thin ice, which provides an efficient resistance of the sea-ice cover to persistent ice loss. With a decreasing summer sea-ice cover, larger and larger areas of the Arctic Ocean become ice-free during summer. As long as winter remains relatively cold, sea ice will start to form in these areas at some point during the growth season. The forming thin ice grows much more rapidly than thick ice, which leads to a recovery of the sea-ice cover during winter. An additional contributor to this recovery is that there is often little snow on the newly forming sea ice. Since snow is an efficient insulator, ice with little snow on its surface can grow much faster than ice with a thick snow cover. This allows for the newly forming

sea ice to reach a thickness that might even be larger than that of ice that survived the summer in the same area (Figure 9.28).

The results imply that if the climate were to become colder, the loss of sea ice that occurred during the past decades can probably be reversed. If, however, the climate continues to warm, the loss of sea ice is likely to decline further in the future. This is caused by the increasingly thinner sea-ice cover becoming increasingly vulnerable to ice loss during summer: With a thinner sea-ice cover, a given amount of energy that is available for melting during summer will cause a larger fraction of the ocean to become completely ice-free (Holland et al., 2006).

The winter ice extent may not be so robust in a warming world. Eisenman and Wettlaufer (2009) used a simple seasonal model of the Arctic sea-ice system to show that the ice-albedo feedback does not cause a bifurcation to all ice-free conditions (a tipping point) as the summer ice extent declines to all open-water conditions, however if the winter maximum thickness declines too far in a seasonally ice-covered regime, the system becomes unstable and all of the ice disappears, even in winter.

Winton (2006a) examined the output of two GCMs that had been run to a quadrupling of the CO₂ where all sea ice disappeared, even in winter. The author found no evidence of acceleration of the ice decline or of polar warming when the summer ice disappeared. However, one of the models showed some indication of an acceleration as all of the winter ice disappeared.

Evidence suggests that summer sea ice is vulnerable to abrupt changes not because the feedbacks are so powerful but because when much of the pack is very young and very thin, small perturbations in the thermal or dynamic forcing can




Figure 9.28. Schematic illustration comparing the ice thickness evolution of newly forming ice and of ice that survived the summer. The snow on top of the ice is represented by the shaded blue and red areas. Ice formation of the newly forming sea ice was prescribed to start on 1 November, two months after the end of the melting season of the ice that survived the summer. Note that nevertheless the newly forming ice reaches a larger maximum thickness than the old ice because of the thinner isolating snow-cover on top of the former. Source: Notz (2010).

cause very large changes in ice extent. This was the case in 2007, when the cumulative effects of many years of gradual warming and episodes of large anomalous ice export from the Arctic Ocean in the early 1990s created large amounts of thin ice in the spring that was vulnerable to melting the following summer. This condition plus unusual winds that blew the remaining ice to one side of the basin caused the abrupt decline of the September ice extent (Lindsay et al., 2009). As the late summer ice extent continues to decline, large variability could be expected in ice extent, but not a tipping point.

This vulnerability of a thinner ice cover to widespread ice loss during summer was one of the reasons for the surprising record low in sea-ice extent in summer 2007. It is likely that similar surprises will occur in future, with the sea-ice cover in the Arctic apparently being in a state of transition to mostly ice-free conditions in late summer. Current understanding of the physics of sea ice and of its interaction with the ocean and the atmosphere is still too limited to reliably forecast the future trajectory of this transition. For example, recent studies suggest possible changes in the atmospheric circulation in a warmer climate (Zhang et al., 2008c). Such changes might cause stable high-pressure systems to form more often in the Arctic during summer, which in turn would accelerate the sea ice to retreat in the coming decades. In addition, the oceanic heat transport into the Arctic might increase in a warmer climate, which could also cause sea ice to disappear much more rapidly than currently projected.

9.3. Biological impacts of changes in sea ice in the Arctic

- Predictions of seasonal sea-ice extent are highly variable on a regional basis. Environmental conditions and bathymetry are also highly variable on a regional basis. In combination, these factors will strongly affect the impacts of climate warming on Arctic biological systems.
 - The central Arctic basins are likely to become more productive under conditions of decreased MYI and increased open-water extent and duration. It is not possible to predict the magnitude of this increase in production or its persistence as a shift is anticipated from light limitation to nutrient limitation.
 - Changing sea-ice and snow patterns will shift the balance between primary production by ice algae and phytoplankton, with unknown consequences for energy flow in Arctic food webs.
 - The timing of sea-ice retreat will affect the availability of ice-associated zooplankton and lipid-rich forage fish, which are critical resources for seabirds, marine mammals and some commercially important fish species (e.g., Atlantic cod).
 - Sub-Arctic species are expanding northward and are likely to compete with Arctic species. Ice-associated bird species are in some cases already declining (e.g. ivory gulls); others are likely to do so in the future.
- The extinction of some Arctic endemic species is likely if current sea-ice trends continue. These losses will

represent biodiversity losses of global significance, and reverse millions of years of evolutionary change (since the beginning of the Pleistocene). Northward range expansions for some temperate species and potentially greater overall productivity will enhance foraging opportunities for some animals within High Arctic areas, at a cost to Arctic endemic populations.

- It is highly likely that distribution and abundance reductions will take place among ice-associated pinniped populations (ringed seals, bearded seals, walrus) due to reductions in the extent and thickness of sea ice. Pack ice-breeding seals (hooded, harp, ribbon, spotted) will experience reproductive failure more frequently as their late winter / early spring breeding habitat becomes less stable. This is already evident in the Atlantic sector of the Arctic (West Ice/Fram Strait and White Sea breeding areas, impacting harp and hooded seals).
- Model results suggest that polar bears are highly likely to be extirpated from seasonally ice-covered regions (where two-thirds of the world's polar bears currently live) within 50 to 70 years.
- The responses of Arctic endemic cetaceans to changing sea-ice conditions will be influenced by food availability, competition from non-endemic migrant cetaceans and, in some regions, the potential for increased predation from killer whales.

9.3.1. Sea ice and Arctic marine ecosystems

Arctic marine ecosystems have several unique physical characteristics that set them apart from marine systems at lower latitudes. Some of the most important include: strong seasonality in light levels, from complete winter darkness to continuous daylight in summer; low overall temperatures with winter extremes; and the presence of extensive shelf seas around a deep central ocean basin. However, the most defining characteristic is perhaps that for the last five million years or more there has been a 'permanent cap' of multi-year ice that extends and retracts seasonally over vast ocean areas with the formation and melt of first-year ice (see Polyak et al., 2010 for historical sea-ice patterns). Together, the MYI and the FYI comprise a unique habitat type that has become home to a wide range of Arctic species (e.g. polar bears *Ursus maritimus*) that have evolved within the sea-ice environment or have joined it over the millions of years of its existence (Figure 9.29).

In addition to its direct role as habitat for Arctic biota, sea ice also plays a major role in terms of structuring Arctic ecosystems (e.g., Alexander, 1980; ACIA, 2004). Sea ice influences all processes operating across the ocean–sea–atmosphere interface (see Sections 9.1 and 9.2). From a biological perspective, one of the key issues is its influence on radiative exchange, which is critical for photosynthesis and surface heat fluxes. Sea ice also influences freshwater fluxes, and momentum exchange between the atmosphere and the oceans, which in turn influences surface stratification and mixing. Ice margins, as well as polynyas (openings within ice-covered areas) are thus typically areas of high productivity where large numbers of marine birds and mammals congregate to feed.

The ongoing changes in Arctic sea ice (e.g., Overland, 2009) are expected to have major consequences for marine ecosystems. The objective of this section is to provide a brief summary of current knowledge of sea ice-associated ecosystems in the Arctic, to report on documented changes that have already been observed in relation to changes in sea-ice conditions, and to predict likely future changes in Arctic ecosystems in relation to current scenarios for projected changes in Arctic sea ice over the 21st century.

9.3.1.1. Biota in sea ice

The sea-ice interior is habitat for an abundant and diverse microscopic community that forms the base of sea-ice associated food webs. The sea-ice biota consists of a complete food web with primary producers, a microbial food chain and three to four trophic levels (e.g., Horner et al., 1992; Deming, 2010).

Microorganisms, nutrients and other inorganic and organic constituents are incorporated into sea ice as the ice is formed. Larger cells are selectively scavenged from the water column into the sea ice at the time of its formation (Gradinger and Ikävalko, 1998; Riedel et al., 2007; Róžańska et al., 2008). The organisms incorporated into sea ice are assumed to be the founding members for the development of the ice-algal bloom that takes place in spring with the seasonal increase in solar radiation. Light availability determines the onset of ice-algal production in spring (e.g., Lavoie et al., 2005). Since snow strongly attenuates light penetration throughout the snow-ice matrix, snow-cover thickness and patchiness influence

the temporal and spatial variability in ice-algal distribution, affecting the timing of ice-algal growth (e.g., Riedel et al., 2006) and horizontal distribution of ice algae (e.g., Rysgaard et al., 2001; Mundy et al., 2007). While light determines the onset of the bloom, nutrients are essential to sustain sea-ice production, and can become limiting toward the end of ice-algal blooms. Self-shading in the dense ice algal layer can also, at times, limit ice-algal production (e.g., Smith et al., 1988). Recent results from the Chukchi and Beaufort Sea (Gradinger, 2009; Róžańska et al., 2009) suggest that nutrient supply from the water column determines the upper limit of ice-algal production (also see Michel et al., 2006).

Organisms are more abundant in Arctic FYI than MYI. This is due to the greater presence of brine pores and channels in FYI that offer more colonization or habitable space for a diversity of microorganisms. In the Arctic, sea-ice algae flourish primarily at the ice–water interface (bottom-ice communities), and algae located here represent up to 95% of the total chlorophyll *a* biomass in FYI in spring, but they can also be found higher up toward the surface of the ice (e.g., Mock and Gradinger, 1999). Ice algae can represent between 4% and > 50% of total primary production in the Arctic on a regional basis (Legendre et al., 1992; Gosselin et al., 1997) and can play a key role in Arctic food webs as an early and concentrated (in space and time) food source for zooplankton grazers at a time when little or no other food is available (Bradstreet and Cross, 1982; Michel et al., 1996; Gradinger, 2009).

Sea-ice communities include hundreds of protist species (Von Quillfeldt et al., 2003; Róžańska et al., 2009). A viable




Figure 9.29. A schematic view of the major biological components and physical features of the Arctic sea-ice community during the spring ice retreat/melt period. Source: drawn by Audun Igesund, Norwegian Polar Institute.

sea-ice protist community may be present throughout the sea-ice season, with a characteristic species succession from flagellate dominance (dinoflagellates and cryptophytes) in winter followed by pennate diatoms during the bloom period (Mikkelsen et al., 2008). The colonial diatom *Nitzschia frigida* is a pivotal species of landfast ice across the Arctic as it is the most frequent, most abundant and most consistently observed species in FYI (Róžańska et al., 2009). Bacterial abundances in the ice can be high and their activity is often linked to dense algal aggregations in bottom communities (Meiners et al., 2008). Heterotrophic protists are considered important bacterivores within the ice. There is also a diverse community of multicellular organisms living within the ice (often referred to as ice meiofauna), including several species of Crustacea (mainly Harpacticoidea), Nematoda, Acoela, Rotifera and Cnidaria (Gradinger, 2002; Bluhm et al., 2009a). In addition to these 'permanent' members of the ice communities, meroplanktonic larvae and juvenile stages of benthic Polychaeta and Gastropoda inhabit the ice for periods of a few weeks to months (Gradinger et al., 2009a). Despite many of the metazoan species found in sea ice being herbivores that feed on ice-algal biomass, typical daily ingestion rates are below 10% of the algal standing stock (e.g., Gradinger, 1999; Michel et al., 2002).

Overall, grazing by in-ice meiofauna and macrofauna does not limit the seasonal build-up of ice-algal biomass in the bottom layers of Arctic sea ice, so the bulk of the ice-algal biomass is available for under-ice grazers or is released into the water column at the time of ice melt (Michel et al., 2002). This coupling between sea ice and pelagic (water column) and benthic (seafloor) ecosystems is important in structuring Arctic marine food chains (Bluhm and Gradinger, 2008).

9.3.1.2. Biota under sea ice

The inherent difficulties in measuring ice-algal production (see Glud et al., 2007), and its patchy distribution, has led to considerable uncertainty as to its role within Arctic ecosystems. Clearly, ice-associated communities are capable of exploiting the newly produced organic matter, but it is only fairly recently that the direct and indirect roles of ice algae for pelagic and benthic food webs have been shown to be significant (Michel et al., 1996, 2002; Renaud et al., 2006; Tamelander et al., 2008; Gradinger et al., 2009b).

Arctic under-ice fauna is dominated by crustaceans, mainly gammarid amphipods, copepods and fish (*Boreogadus saida* and *Arctogadus glacialis*). In some areas, pelagic copepods, most notably *Calanus* and *Pseudocalanus* species, migrate toward the under-ice surface to feed (Runge et al., 1991; Fortier et al., 2001). Recently, swarms of krill have been observed under Bering Sea ice (Gradinger, Bluhm and Iken, University of Alaska, pers. comm.). Pressure ridges often harbor higher concentrations of amphipods and meiofauna compared to level sea ice (Hop et al., 2000; Hop and Pavlova, 2008; Gradinger et al., 2009a). This may be because ice floes that make up the ridging reach below the low-salinity water layer observed during ice melt in summer. Under-ice copepods and amphipods play an important role in linking sea ice-algal production to higher trophic levels. The abundance and feeding ecology of amphipods vary widely. However, in areas of high abundance, amphipods can consume 30% to 60% of the ice-algal biomass (Siferd et al., 1997; Werner, 1997).

Several studies have reported copepods feeding on ice algae, providing some insight into the potential importance of this early food source for zooplankton (e.g., Conover et al., 1986; Fortier et al., 2001). The strongest evidence for just how important this food source may be for the pelagic ecosystem, however, comes from recent studies using stable-isotope and fatty-acid biomarkers. Ice algae contain polyunsaturated fatty-acids (PUFAs), many of which are essential for consumers and must be derived from their diets. Søreide et al. (2006) and Tamelander et al. (2008) showed that ice algae make up significant fractions of the diets of many zooplankton taxa during winter and spring. PUFA biomarkers also directly link ice algae to the diets of key members of Arctic pelagic food-webs (Auel et al., 2002; Søreide et al., 2008).

Søreide et al. (2010) recently showed that ice algae and the timing of its production are not just important for additional food intake, but also play critical roles in the development and survival of *Calanus glacialis*, a key Arctic zooplankton species. *C. glacialis* is among the most important large copepod species across the Arctic, and its predators (fish, seabirds, seals, bowhead whale *Balaena mysticetus*) rely on its high lipid levels to build their own lipid stores (Karnovsky et al., 2003). Its use of ice algae early in the season, therefore, is significant for the functioning of large parts of the Arctic ecosystem.

With body sizes of 1 to 6 cm, sea-ice associated amphipods are a major dietary item for the only ice-associated fish taxa in Arctic waters, the Arctic cod (*Boreogadus saida*) and polar cod (*Arctogadus glacialis*) (Bradstreet and Cross, 1982). In addition to under-ice amphipods, other common prey items for fishes under the ice include the copepods *Calanus glacialis* and *C. finmarchicus*, the hyperiid amphipods *Parathemisto libellula* and *Themisto abyssorum*, and the mysid *Mysis oculata* (Bradstreet et al., 1986; Lønne and Gulliksen, 1989; Süfke et al., 1998). Polar cod also feeds on juvenile Arctic cod (Joensen, 2008).

Arctic cod occurs across the Arctic in variable-sized schools ranging from small groups to several million fishes (Andriyashev, 1954; Craig et al., 1984), and is often associated with sea ice (Bradstreet et al., 1986; Lønne and Gulliksen, 1989). Under-ice aggregations of Arctic cod have recently been reported in the Beaufort Sea (Benoit et al., 2008). Its apparently eurythermal and euryhaline physiology (Craig et al., 1984) allows Arctic cod to inhabit and take advantage of a wide range of habitats. Polar cod occurs in the Arctic and North Atlantic at depths from 0 to 1000 m (www.fishbase.com, retrieved Oct 9, 2009) and is also often ice-associated (Dorrien von et al., 1991). Where the two species co-occur, dietary segregation may occur (Joensen, 2008). Both species are important food items for top trophic animals. Arctic cod is a major food source for ringed seals (*Pusa hispida*), spotted seals (*Phoca largha*) and ribbon seals (*Histiophoca fasciata*), narwhal (*Monodon monoceros*) and beluga (*Delphinapterus leucas*), and provides important food during seasonal migrations of seals feeding in northern waters, while polar cod is common in diets of beluga, narwhal and ringed seals (Bluhm and Gradinger, 2008). Arctic seabirds (murre, guillemots, kittiwakes) prey on Arctic cod throughout the Arctic (Lønne and Gabrielsen, 1992; Hobson, 1993; Weslawski et al., 1997), and this single species can comprise 85% or more of the diet of ringed seals in Svalbard (Labansen et al., 2007).

Ice algae can provide an important food supply to the benthos as a large part of the biomass accumulated during the bloom can sink to the seafloor (e.g., Fortier et al., 2001). Sediment trap studies have identified pulses of algal export from sea ice (e.g., Michel et al., 2006; Forest et al., 2007; Tamelander et al., 2009), which may occur more than one month before the typical phytoplankton pulse (Ambrose and Renaud, 1997; Juul-Pedersen et al., 2008). Benthic communities are fully capable of consuming and assimilating ice algae. Results from a winter-to-summer time series in the Beaufort Sea showed a rapid response by the benthos to ice-algal deposition (Renaud et al., 2008). Experimental studies in the Arctic indicate that seafloor communities respond to a pulse in ice algae within 12 hours (McMahon et al., 2006), and that ice-algal-derived PUFAs are assimilated preferentially (Sun et al., 2007). Rapid, intense response and assimilation suggest that ice–benthic coupling plays a significant role in benthic food webs on Arctic shelves. Increasingly, it is thought that ice algae are important for fueling growth and reproduction of pelagic and benthic taxa, and for ecosystem functioning in general.

9.3.1.3. Biota on the sea ice and at its edges

Ice-edge environments are regions of intense seasonal production and a focal point for trophic transfer to the upper trophic levels during bursts of primary production because seabirds and marine mammals, which must surface to breathe, can easily access concentrated marine production along ice edges. Intermittent wind-driven upwelling at ice edges serves to fuel primary or new production along the ice edges by replenishing nutrients to the surface layer (e.g., Alexander and Niebauer, 1981). As the ice retracts northward during spring, exposing new areas with a build-up of yet unused nutrients (or in some polynyas, cracks and leads) the result is seasonal bursts of productivity that occur in a concentrated fashion along the edges of the ice within the spatially transient marginal ice zone (MIZ) (see Box 9.8). The high productivity of these regions plays a key role in Arctic food chains, particularly because it represents production early in the season when other food for secondary consumers is limited (e.g., Hunt et al., 1996; Karnovsky and Hunt, 2002). The presence of top predators in the MIZ, including seals and whales is largely mediated by the abundance of lower trophic level prey organisms (zooplankton and fish) that are concentrated along the ice edge (e.g., Kaschner et al., 2006). There is little competition from other species for marine mammals that are able to access ice-associated prey beneath the ice (Burns, 2009a). The surface of the sea ice is also important in that it provides habitat for birthing, molting and resting, as well as a mating platform or staging area for some ice-associated seals; a hunting and transportation platform for polar bears; and the ice provides protection from predators and a less turbulent environment that is shielded from strong winds both for seals and whales (Tynan and DeMaster, 1997; Burns, 2009a). Sea ice is a unique habitat for mammals in a global context; it has few surface predators and is virtually free of disease vectors (Burns, 2009a).

Polar bears have a circumpolar Arctic distribution. Nineteen populations of polar bears are currently recognized, varying in size from a few hundred to a few thousand animals within

a global population estimated to be between 20 000 to 25 000 animals (Aars et al., 2006). Polar bears are heavily dependent on sea ice for foraging and on ice corridors for transportation to and from terrestrial denning areas, which often occur along slopes near shore-lines where snowdrifts accumulate sufficient snow (Stirling, 2009). Female polar bears emerge from their dens in spring, following a fasting period of four or five months. They depend on immediate access to sea ice and a plentiful supply of ringed seal, particularly pups, at this time of year. Polar bears are scarce in the permanent MYI of the central Arctic Ocean as they prefer FYI that forms over shelf areas where seals, their primary prey, are most abundant. Ringed seals are the dominant prey of polar bears, but bearded seals (*Erignathus barbatus*) and other ice-associated seals such as harp seals (*Pagophilus groenlandicus*) and hooded seals (*Cystophora cristata*) are important regionally. Even walrus (*Odobenus rosmarus*) are consumed by polar bears in some areas (see Thiemann et al., 2008).

The largest of the Arctic seals, the walrus, ranges across the circumpolar Arctic, but the species' distribution is disjunct and two subspecies are recognized, one in the Pacific (*O. r. divergens*) and the other in the Atlantic (*O. r. rosmarus*). The actual distribution of walrus is restricted by their narrow ecological niche. They depend on shallow water (<100 m) with suitable bottom substrate that can support high bivalve abundances, reliable open water over the rich feeding areas, and haul-out areas near feeding areas (Kovacs and Lydersen, 2006). For much of the year, the haul-out platform is sea ice (e.g., Freitas et al., 2009). Atlantic walrus of all ages and sexes use terrestrial haul-outs in summer and autumn, as do Pacific walrus males. But, Pacific walrus females and calves remain in the MIZ during summer. There are probably in excess of 200 000 walrus worldwide, but many population assessments are out of date and in some areas are non-existent (e.g., Franz Josef Land, Pechora Sea, Laptev Sea). A key sea ice-related sensitivity with walrus is that, at least seasonally, all populations use the MIZ as a platform to move over foraging areas that are too far from land-based haul-out sites to be energetically feasible sites for feeding. The use of the two habitats broadens the feeding distribution markedly, which permits greater overall walrus abundances.

The smallest of the Arctic seals, the ringed seal is also a circumpolar species. The world-population of ringed seals probably numbers in the millions, but few areas have been systematically surveyed (Hammill, 2009). This species is the only northern seal that can maintain breathing holes in thick sea ice and thus has the broadest distribution among the Arctic pinnipeds, ranging north to the Pole. This species is extremely dependent on sea ice, which is its exclusive breeding and haul-out platform (Smith, 1987; Burns, 2009a). Snow on the surface of the sea ice is essential for the construction of lairs (small caves above a breathing hole), in which the seals routinely rest during the winter months and also give birth in the early spring (e.g., Furgal et al., 1996). Ringed seal pups are only about 4 kg when born, so are thermally dependent on having a lair environment. The lair also provides some protection against polar bears, Arctic foxes and other potential predators. Lack of snow build-up on the ice or high spring temperatures and spring rains can result in reproductive failure in this species (e.g., Smith and Harwood, 2001; Stirling and Smith, 2004). Ringed seals

Box 9.8. The role of polynyas and flaw leads in Arctic sea-ice communities

Open-water areas within ice-covered seas are regions of high biological productivity compared to the surrounding ice-covered waters; in addition, the growth of phytoplankton in these areas starts early in the season making them important biological ‘hot spots’ (e.g., Bursa, 1963; Hirche et al., 1991; Stirling, 1997). In contrast, where Arctic sea ice remains mobile throughout the winter (e.g., Hudson Bay and Strait, Barents Sea) small open-water leads occur unpredictably with tidal and wind-driven ice movements, making the small open-water areas that result too ephemeral to support most birds or marine mammals that feed within the water column (e.g., Hunt et al., 1996). An exception is the black guillemot (*Cepphus grylle*), which overwinters in the mobile pack, apparently shifting from lead to lead as conditions change (Gaston and McLaren, 1990).

In some areas, offshore winds and the movement of pack ice may create more extensive shore leads. These leads attract a diverse array of birds which remain in such areas over winter, especially common eiders (*Somateria mollissima*), and to a lesser extent long-tailed ducks (*Clangula hyemalis*) and king eiders (*S. spectabilis*) (Gilchrist and Robertson, 2000), as well as ice-associated seals and whales (Kingsley et al., 1985; Heide-Jørgensen and Laidre, 2004; Moore and Laidre, 2006). The overwintering of ice-associated whales within mobile pack ice and temporary polynyas occasionally causes entrapments (Nerini et al., 1984; Finley, 2001), sometimes involving hundreds of whales (Harwood and Smith, 2002). Later freeze-up as a result of climate change may alter the frequency of formation of these types of open-water areas and reduce the predictability of conditions and the reliability of prior experience (Laidre and Heide-Jørgensen, 2005b).

In regions of strong tidal currents, such as those produced in narrow inlets, small tidal polynyas remain open throughout the winter, providing refuges. Such predictable openings although typically small, serve as concentration areas for a wide variety of marine birds, and even whales and seals, if they are large enough (e.g., Kingsley et al., 1985; Richard et al., 1998). These aggregations of potential prey attract ice-based predators (polar bears and Arctic foxes *Vulpes lagopus*) and raptors such as gyrfalcons (*Falco rusticolus*) and snowy owls (*Bubo scandiaca*) (Brown and Nettleship, 1981; Stirling, 1997). If loss of sea ice results in the marine birds and other animals remaining dispersed, the predators that rely on these concentrations may have to seek other food sources.

Numerous small polynyas of this type occur near the Belcher Islands (Sanikiluaq) where they are essential to the year-round existence of a large population of common eiders (Freeman, 1970). The eiders spend the night on the tidal polynyas, flying out at dawn to the open water of shore leads for feeding. When shore leads close, the whole population may be forced to feed in the tidal polynyas and then benthic prey (e.g., bivalves) becomes rapidly depleted (Gilchrist et al., 2006). Similarly, the entire world population of spectacled eiders (*S. fischeri*) overwinters in leads and polynyas south of St. Lawrence Island, in the eastern Bering Sea (Petersen et al., 1999), an area of strong benthic–pelagic coupling that

supports an important bivalve community with a high density of prey for the eiders (Lovvorn et al., 2003; Grebmeier et al., 2006b). The ability to rest on the ice at night, when they are not feeding, is essential to the energy balance of the eiders (see Figure 9.30; Lovvorn et al., 2009).

Polynyas of all kinds are particularly important because they provide early season productivity. In summer, the region of the North Water Polynya, in Baffin Bay, supports some of the largest concentrations of seabirds anywhere in the Arctic (Stirling, 1980, 1997), dominated by little auks (*Alle alle*) which breed in the millions in northwestern Greenland (Kampp et al., 2000). In the North Water Polynya, the distribution and diets of the little auks reflect physical processes responsible for the timing and spacing of polynya opening in spring and subsequent food-web dynamics (Karnovsky and Hunt, 2002). The eastern side of the polynya is a sensible heat polynya (driven by the upwelling of warmer water) and primary production there precedes production elsewhere (Tremblay et al., 2006a). Little auks arrive first in the open waters of the eastern side, and only later in summer occupy the western side, which is predominately a latent heat (wind-induced) polynya. Little auks time their arrival to coincide with the availability of copepods (*Calanus* spp.), their primary prey in May to July. Thus, the timing and location of little auks in the region is determined by the timing of primary production and the upward migration of copepods to crop that production, rather than by the availability of open water itself, although of course the birds must have enough open water to access their prey (Karnovsky and Hunt, 2002).

Changes in the location or predictability of polynyas due to changing sea-ice conditions could have significant impacts on seabird and marine mammal populations. Large polynyas, particularly where they occur over continental shelves, are currently important to all trophic levels of ice-associated ecosystems.



Figure 9.30. Common eiders resting on the ice edge in a polynya in early spring. Source: Grant Gilchrist, Environment Canada.

have the longest lactation period of any of the northern true seals, and need stable ice throughout the period of neonatal dependence (Lydersen and Kovacs, 1999). Ringed seals appear to prefer landfast FYI for breeding, but can be found on all ice types including free-floating pack ice and MYI (Burns, 2009a). Ringed seals remain associated with sea ice throughout the year and feed predominantly on ice-associated prey, which are particularly important to young ringed seals (Freitas et al., 2008a). Polar cod, Arctic cod and large zooplankton species such as *Parathemisto libellula* make up most of the ringed seal diet (e.g., Wathne et al., 2000; Labansen et al., 2007). A key sea ice-related sensitivity with ringed seals is that this species relies on early formation of landfast sea ice in the autumn and on the formation of ridges and rubble zones in FYI, which can capture enough snow for birth lair formation.

Bearded seals have a patchy distribution throughout the Arctic, occurring at low densities across their range. The global population of bearded seals has not been assessed, but probably numbers in the hundreds of thousands (Kovacs and Lydersen, 2006). This species is largely solitary, although small groups can be seen on the ice during late spring and early summer, when they are breeding and then molting. Similar to walruses, bearded seals forage mainly on benthic organisms (Kovacs, 2009a). Therefore, they prefer to reside in drifting pack-ice over shallow water. They are largely coastal animals but can also be found in drifting pack-ice far from shore. Bearded seals avoid densely packed ice unless open-water leads are available. During winter, they concentrate near polynyas or in areas where leads are frequent, or they stay near ice edges. Bearded seals prefer to occupy areas with drifting ice in shallow coastal environments on a year-round basis that have a rich bottom fauna to support their energy requirements. But, in areas where ice disappears entirely, they will haul out on shore for resting or molting (Burns, 2009a).

Four other ice-associated seals live within Arctic and sub-Arctic pack-ice areas. These include harp seals and hooded seals in the North Atlantic region and spotted seals and ribbon seals in the Bering Sea, Chukchi Sea and Sea of Okhotsk. These species all give birth to their young on the pack ice and spend most of their lives associated with sea ice (Burns, 2009a,b; Kovacs, 2009b; Lavigne, 2009; Lowry and Boveng, 2009). With the exception of the spotted seal, these seals only haul-out on ice. Spotted seals are relatively recently evolved from harbor seals and in summer can be seen hauled-out on shore in harbor seal groups. All four of the Arctic pack-ice seals display broad diets, consuming a wide variety of small fish and invertebrate species. They favor lipid-rich schooling fishes such as polar cod, Arctic cod and capelin (*Mallotus villosus*). Hooded seals also eat larger prey such as Greenland halibut (*Reinhardtius hippoglossoides*) and deep-dwelling red fish (*Sebastes* spp.), and they share a diet of cephalopods with ribbon seals (Haug et al., 2007). They are all sensitive to the availability of vast fields of pack ice in late winter / early spring.

Three species of cetacean are endemic to the Arctic: the narwhal, the beluga (or white whale) and the bowhead whale. Beluga and bowhead whales have a circumpolar distribution, while the narwhal occurs primarily in the Atlantic sector (Heide-Jørgensen, 2009; O'Corry-Crowe, 2009; Rugh and Shelden, 2009).

The narwhal is the most specialized of the three endemic species (Laidre et al., 2008). They are typically found in waters

north of 60° N in the eastern Canadian High Arctic, offshore eastern and western Greenland, Svalbard and Franz Joseph Land. Narwhal overwinter in deep, ice-covered habitat along the continental slope and spend roughly two months in summer in ice-free shallow bays and fjords. These disjunct seasonal distributions are connected by annual migrations of roughly 1000 km that last about two months. Narwhal appear to feed little during summer, but some polar and Arctic cod can be found in their stomachs at this time as well as *Gonatus* squid, which seem to be eaten in all seasons in all localities (Heide-Jørgensen, 2009). Peak feeding for narwhal takes place from November to March in dense pack-ice habitat, which is focused on Greenland halibut, and which may be key to their survival (Laidre and Heide-Jørgensen, 2005a). In contrast, beluga occupy estuaries, continental shelf and slope waters as well as deep ocean basins in conditions that range from open water to dense FYI. Some beluga undertake long migrations between summer and wintering sites, while others remain in the same region year-round (e.g., Lydersen et al., 2001; Richard et al., 2001). Migratory beluga occur along the western and northern coasts of Alaska, in the Canadian High Arctic and western Hudson Bay. Non-migratory beluga often make seasonal shifts in distribution and in winter can be found near the MIZ. They are generalist feeders that eat a wide variety of prey including invertebrate and vertebrate species found in benthic, pelagic and ice-associated environments (Seaman et al., 1982; Dahl et al., 2000; Loseto et al. 2009; O'Corry-Crowe, 2009).

Bowhead whales are well adapted to ice-covered waters, spending summers in the High Arctic and winters in sub-Arctic seas. Bowheads occur in polynyas in winter, but can move easily through extensive areas of nearly solid sea ice and break through ice up to 45cm thick. Although strongly ice adapted, bowheads often feed in open water areas, especially in late summer and autumn, when sea ice can be hundreds of kilometres offshore (Moore et al., 2010). Bowheads eat invertebrate prey including copepods, euphausiids, mysids and gammarid amphipods (Lowry, 1993). A variety of other baleen whales and a few toothed whales also migrate into Arctic waters during summer, but sea ice represents a distributional barrier to these animals rather than useable habitat. The key ice related sensitivity for the ice-adapted whales is how the sea ice structures the ecosystem and influences prey availability. But, sea ice also provides a sheltered environment where whales can seek refuge from turbulent seas and escape predation by killer whales (*Orcinus orca*) (George et al., 1994; Burns, 2009a; see Section 9.3.3.4).

Seabirds are also a major biological feature of Arctic ice edges. Being highly mobile, birds are in a good position to exploit the seasonally available prey of the MIZ. In addition, a few species remain throughout the winter at high latitudes, taking advantage of polynyas or recurrent flaw-leads. Some seabirds use sea ice for resting both during migrations and foraging excursions and several species of seabird can be considered more-or-less obligate sea-ice associates: the thick-billed murre (*Uria lomvia*), a deep-diving species of auk (to 150 m in the Atlantic Arctic; Elliott and Gaston, 2009); the ivory gull (*Pagophila eburnea*), a small, tern-like, surface-feeding gull and; in the non-breeding season, Ross's gull (*Rhodostethia rosea*), another small surface feeder. In addition, in the north Pacific, Kittlitz's murrelet (*Brachyramphus brevirostris*), is considered

a specialist on tidewater inlets where glaciers reach the sea. Although its range extends southward well beyond the limits of the Arctic, the black guillemot is common in the High Arctic where it is found especially in narrow cracks and leads in sea ice and remains at high latitudes throughout the winter (Renaud and Bradstreet, 1980). Likewise, several species of eider (large benthic-feeding diving ducks) remain in ice-covered areas throughout the winter.

In summer, many other marine birds make temporary use of open water areas created by the retreat of winter ice cover. The most common are several species of gull (glaucous *Larus hyperboreus*, Iceland *L. glaucoides*, Thayer's *L. thayeri*, Sabine's *Xema sabini*), the black-legged kittiwake (*Rissa tridactyla*), three species of jaegers (parasitic *Stercorarius parasiticus*, pomarine *S. pomarinus*, long-tailed *S. longicaudus*), the little auk, the Arctic tern (*Sterna paradisaea*), two puffins (Atlantic *Fratercula arctica*, horned *F. corniculata*) and several species of auklet (parrakeet *Cyclorhynchus psittacula*, crested *Aethia cristata*, least *A. pusilla*).

The position of birds within Arctic marine food webs of the seasonal ice zone has been investigated using nitrogen isotope ratios (Hobson, 1993; Hobson et al., 2002a,b), and fatty acid composition of tissues, as well as more traditional methods involving stomach or throat pouch content analyses (Bradstreet, 1980; Roby et al., 1981; Gaston and Bradstreet, 1993; Lønne and Gabrielsen, 1992; Karnovsky et al., 2008). The large gulls, glaucous gull and Thayer's gull, occupy the highest trophic levels, commensurate with their status as predators of smaller birds and scavengers on the kills of polar bears. The ivory gull also occupies a high trophic level (Karnovsky et al., 2009), presumably because it frequently scavenges marine mammal remains from polar bear kills and sites where people hunt marine mammals. At the opposite end of the spectrum, the smallest auks, little auk and least auklet have a diet composed primarily of copepods. Other seabirds exhibit diets comprising a mixture of large crustaceans (e.g., amphipods, euphausiids) and small fish, especially polar cod. The diet of thick-billed murre has been investigated extensively throughout the circumpolar Arctic. Arctic cod appears to be an important constituent of adult diets as well as making up the bulk of food fed to nestlings (Gaston and Hipfner, 2000). In early summer, as sea ice breaks-up and the murrens shift into newly opened areas, birds concentrate at the margins of consolidated pack ice. The pattern of distribution agrees with evidence that these birds feed under, as well as beside the fast ice, making use of under-ice fauna (see Section 9.3.1.2). In the Bering Sea, thick billed-murrens feed their chicks a broader diet including juvenile walleye pollock (*Theragra chalcogramma*), squid, and even euphausiids when fish are not available (Sinclair et al., 2008).

Timing of breeding of thick-billed murrens at the large breeding colony on Prince Leopold Island, in Parry Channel (Northwest Passage) has been shown to be strongly correlated with the timing of ice break-up, with breeding generally more successful in years of early break-up (Gaston et al., 2005a). The same is true for black-legged kittiwakes, northern fulmars (*Fulmarus glacialis*) and glaucous gulls breeding at the same site (Gaston et al., 2005b).

9.3.2. Ice as a structuring element of polar marine ecosystems

Sea-ice cover greatly affects element cycling and regulates primary production in polar environments. In ice-covered areas, the propagation of light to the underside of the ice is impeded by strong backscattering and attenuation, primarily in the snow cover but also within the sea-ice matrix. The attenuation of light by snow, and to a lesser extent by ice, and by ice algae and other particulate and dissolved material in the ice, influences the amount and spectral composition of light reaching the ice under-surface (e.g., Perovich et al., 1998). This results in very low under-ice irradiances and under-ice phytoplankton biomasses typically lower than 0.5 mg chl/a/m³ (e.g., Conover et al., 1999), and has major ecological significance, reflected by a positive correlation between annual primary production and the length of the open-water period in polar and sub-polar regions (Rysgaard et al., 1999; Rysgaard and Glud, 2007).

9.3.2.1. Ice-associated vs open-water food webs

Ice-associated food webs in the Arctic are based on intense and localized primary production at the ice–water interface or at receding ice edges (see Section 9.3.1), which starts when solar radiation is sufficient for photosynthesis. This production is concentrated in space and time, although there is a large interannual and regional variability in the timing of ice-algal blooms (e.g., Fortier et al., 2002) and the timing and location of ice-edge blooms. Primary production in the water column (excluding receding ice edges) typically takes place after ice break-up and depends on a balance between stratification and mixing, the former keeping phytoplankton cells within the surface layer where enough irradiance is available for photosynthesis, and the latter fuelling nutrient supply that supports the production (Sverdrup, 1953). While light is a key factor determining the levels of primary production in the ice and open waters, it is ultimately the nutrient supply delivered to the surface waters through tidal-mixing (e.g., Cota et al., 1987), wind-mixing (Tremblay et al., 2006a) or upwelling (Mundy et al., 2009) that determines the maximum biomass produced by the algae and other photosynthesizing organisms. Therefore, early in the season, removal of light limitation by decreasing the snow and ice cover, or via the release of particulate and dissolved substances from the sea ice, allows the onset of a phytoplankton bloom and potential carbon flow to higher trophic levels. This has been shown experimentally by Glud et al. (2007) (Figure 9.31), and has also been observed in polynyas (Tremblay et al., 2002, 2006a) and ice-covered (Fortier et al., 2002) or open-water (e.g., the Barents Sea, Wassmann et al., 2006) regions in the Arctic.

When light is not limiting, nitrogen-based nutrient supply, mainly through vertical mixing, becomes a key factor for sustaining primary production (Tremblay and Gagnon, 2009). For this reason, not all open-water areas sustain high primary production, as stratification and mixing determine nutrient supply in these regions (e.g., the North Water Polynya, see Tremblay et al., 2002). As an example, the former Northeast Water Polynya (no longer considered a polynya due to changed ice conditions) had much lower productivity than the North

Water Polynya due to little vertical replenishment of nutrients in the former area (Kattner and Budéus, 1997; Tremblay et al., 2002b).

It has been suggested that Arctic systems export a greater fraction of primary production to the deeper layers (and ultimately the sea floor) than temperate and tropical locations (Petersen and Curtis, 1980). Seasonal ice melt releases ice algae and mucopolysaccharides that can sink rapidly to the benthos, and a temporal mis-match between phytoplankton production at ice edges and zooplankton grazer populations may also result in the sinking of large quantities of phytoplankton-derived detritus to the sea floor (Tamelander et al., 2008). It is important to note, however, that there is a lot of variability in the quantity and composition of ice-associated material reaching the sea floor, as it depends on a combination of factors including the abundance of zooplankton grazers, the rapidity of melt, and water depth (Fortier et al., 2002; Michel et al., 2006). Benthic communities in seasonally ice-covered areas are typically well-developed as they are tightly coupled to the productivity regime. This is reflected in stocks, diversity and food-web structure (e.g., Grebmeier, 1993; Hobson et al., 1995; Piepenburg, 2005; Carroll et al., 2008; Conlan et al., 2008; Ambrose et al., 2009; Cochrane et al., 2009). Current estimates suggest that one-third to one-half of new production is cycled through the benthos annually on Arctic shelves (Renaud et al., 2008; Blicher et al., 2009). The vertical flux of organic material in open-water areas can also be high, but is often more refractory (see Wassmann et al., 2006, Wassmann, 2008). Consequently, the pelagic-dominated food web of open waters often exhibits higher retention in surface waters and *in situ* degradation by zooplankton and the microbial food web compared to ice-covered regions.

9.3.2.2. First-year vs multi-year ice

The relative contribution of MYI and FYI to total sea-ice extent has changed dramatically over the past decade (see Sections 9.1 and 9.2). From an ecological perspective, a major difference between FYI and MYI is their transient vs permanent nature, respectively. While FYI melts to leave ice-free waters during summer, MYI has traditionally been a ‘permanent fixture’ within the Arctic that has provided a refuge/habitat for birds, marine mammals, and under-ice fauna (see Section 9.3.1). Differences in the structure and surface characteristics of FYI and MYI (e.g., crystallographic structure, melt ponds, snow accumulation etc., see Section 9.2) are important influences on their role in Arctic food webs. Generally speaking, FYI is much more productive than MYI, although the species diversity of ice algae has been found to be higher in MYI than FYI in the Canada Basin (Melnikov et al., 2002). In addition, melt ponds, which can cover extensive areas of MYI in spring (see Section 9.2), are habitat for a variety of freshwater and marine algal species (Melnikov et al., 2002). Phytoplankton production under MYI is very low, about an order of magnitude lower than in neighboring open-water areas, mainly due to low light intensity underneath the ice (Lee and Whitledge, 2005). By combining production estimates under MYI and in open-water areas, Lee and Whitledge (2005) obtained a revised estimate of annual phytoplankton production of 5 g/m², on average, for this region. This estimate does not include the long strands (up to 4–6 m) of *Melosira arctica* that attach to the under-surface of MYI (Melnikov and Bondarchuk, 1987; Booth and Horner, 1997), nor production associated with the presence of melt ponds.

While much of the ecological work in the Arctic has been carried out in areas of FYI, MYI, primarily in the central Arctic




Figure 9.31. Effect of increased irradiance at an ice edge for under-ice production. (a) Scalar irradiance relative to downwelling irradiance at the sea-ice surface as measured around a diver hole (hole size about 1 m²) and (b) primary production measured at the same positions. Zero ‘0’ indicates the position of the ice edge and dots the points of actual measurements. Source: Glud et al. (2007).

Basin, has been shown to be important for various elements of the ecosystem. These include: the diversity of algal species in melt ponds and in MYI, the under-ice accumulations of mucilaginous diatoms such as *Melosira arctica* (Melnikov et al., 2002), the higher contribution of ice algae to the total annual primary production in areas of MYI (Gosselin et al., 1997; Bluhm and Gradinger, 2008) and the role of MYI as critical habitat for long-lived ice-associated species (e.g., *Gammarus wilkitzkii*; Hop and Pavlova, 2008). The thick, multi-year nature of this ice has, in the past, served as refugia for marine mammals, including polar bears, during summers in years with extensive melt of FYI.

9.3.3. Observations to date regarding ecosystem impacts

Sea ice in the Arctic has already changed markedly. From 1979 to 2011, there has been a significant decline in sea ice extent (-12.0% per decade for September) relative to the 1979–2011 average (see Section 9.1.2.2.1) and a significant loss of MYI has occurred. Sea-ice thickness has also decreased overall, largely due to the reduction in MYI extent and volume as the thickness of FYI appears to have remained fairly constant. Biological impacts related to the decrease in Arctic sea ice are being documented in many regions of the Arctic at a variety of trophic levels.

9.3.3.1. Primary production

A major consequence of the decrease in sea-ice extent is the increase in open-water area, which models suggest will dramatically increase the duration of the phytoplankton growing season, and hence result in increased phytoplankton

biomass and total production (Arrigo et al., 2008; Pabi et al., 2008; see Box 9.9). Two recent remote-sensing studies indicate that reduced sea-ice cover over the past decade resulted in an increase in phytoplankton biomass and total Arctic primary production, with most change in the Eurasian sector (Arrigo et al., 2008; Pabi et al., 2008). These observations agree with the earlier prediction by Sakshaug (2004) that a positive phase of the AO/NAO would increase total primary production in the Arctic Ocean, especially on the Eurasian side. Alternatively, Grebmeier et al. (2010) reported that the effect of extreme ice retreats and seasonal asymmetry in sea-ice loss on primary production is equivocal in the Pacific Arctic sector, with no clear shift in satellite-derived chlorophyll concentrations for the period 2003 to 2008. These divergent observations can be reconciled within the context of regional differences in sea-ice changes and associated physical forcings, and in the type of ecosystems and their responses to these changes, thereby emphasizing the importance of regionality in observed and predicted changes in the Arctic.

Changes in the size-structure of phytoplankton communities have been documented in Canada Basin, with increasing abundances of small species and decreasing abundances of large species during the past decade (2004 to 2008), attributed to stronger stratification associated with surface melt (Li et al., 2009). Changes in species composition were also documented for ice-associated microalgae living within and under the ice in a study comparing observations in the late 1990s with those for 1979/80 (Melnikov et al., 2002).

The timing of ice melt and retreat is a key structuring element for Arctic marine food webs, and for the reproductive success of marine birds and mammals (see Sections 9.3.1.3 and 9.3.3.4). Fortier et al. (2002) showed that early snow melt and

Box 9.9. The low ice year of 2007

The lowest sea-ice cover on record occurred in 2007 (Overland, 2009). Based on remote-sensing data and a primary production algorithm parameterized for Arctic waters, the estimated annual primary production of 513 TgC/y in 2007 exceeded the 1998–2002 average by 23% (see Figure 9.32; Arrigo et al.

al., 2008). Total Arctic primary production increased by 35 TgC/y from 2006 to 2007, with the highest increase observed in the Siberian sector of the Arctic. Most (70%) of the 2006 to 2007 increase was explained by a longer phytoplankton growth season, while the remainder (30%) was explained by an increase in open-water area (Arrigo et al., 2008).




Figure 9.32. Change in (a) annual primary production and (b) length of the phytoplankton growing season in the Arctic between 2006 and 2007. Source: Arrigo et al. (2008).

release of ice algae induced an under-ice phytoplankton bloom and high sinking fluxes of organic material to the benthos, representing a net addition to the annual flux of carbon in the absence of nutrient limitation. Importantly, atmospheric forcings (e.g., rainfall, solar radiation) are instrumental in determining the rapidity of snow and ice melt (see also Section 9.2), and therefore influence the release of material from the ice into the water column, and the timing and amount of under-ice phytoplankton growth (Fortier et al., 2002; Michel et al., 2006). It is estimated that melt began 13 days earlier, on average, in the 2000s compared to the 1980s (Stroeve et al., 2006, 2007) and that, for the entire Arctic, the length of the melt season has increased by about 20 days (Markus et al., 2009).

The timing of ice formation in autumn is also believed to be an ecologically critical element of physical-biological coupling in the Arctic marine system. There is evidence for later ice formation (see Section 9.2) which is likely to influence the incorporation of material in the sea ice during autumn, as well as snow accumulation.

9.3.3.2. Zooplankton and benthic invertebrate communities

Changes in invertebrate community structure, biomass and oxygen consumption have occurred in Arctic seas, especially the sub-Arctic seas, over the past decades (e.g., see Box 9.10). It is difficult to attribute the extent to which these changes are due to warming, sea-ice changes, increased freshwater runoff or to other environmental and biological conditions. Some examples of these changes include declines in amphipod biomass in the Chirikov Basin (Moore et al., 2003; Coyle et al., 2007); declines in infaunal biomass south of St Lawrence Island (Dunton et al., 2005; Grebmeier et al., 2006a,b); increases in intertidal biomass in Svalbard (Weslawski et al., 2010); and increases in epifauna biomass within areas influenced by the Alaska Coastal Current in Norton Sound (Hamazaki et al., 2005) and Kotzebue Sound (Feder et al., 2005), as well as in the (heavily fished) southeastern Bering Sea (Connors et al., 2002). Recent investigations of the annual growth of the bivalve *Clinocardium ciliatum* (Sejr et al., 2009) and the sea urchin *Strongylocentrotus droebachiensis* (Blicher




Figure 9.33. Growth performance of the bivalve *Clinocardium ciliatum* estimated as maximum annual shell growth plotted against the productive open-water period. Data for the sea urchin *Strongylocentrotus droebachiensis* recalculated from Blicher et al. (2007) are included. Linear regression for the combined dataset of both species: $G_{\max} = 0.24 \times [\text{POWP}] + 19.4$, $p < 0.01$, $R^2 = 0.78$. Source: Sejr et al. (2009).

et al., 2009) along a climate gradient from the sub-Arctic to high-Arctic showed a significant positive correlation between the growth of these benthic species and the average productive open-water (ice-free) period (Figure 9.33). Furthermore, local variations in growth correlated well to local variations in sea-ice conditions. These results indicate that sea-ice cover influences growth rates of benthic fauna, probably through light limitation of primary production (Sejr et al., 2009). At sites with pronounced sea-ice cover, food availability may be linked to sea-ice dynamics through the bottom-up regulation exerted by sea ice on phytoplankton production, which renders such areas especially susceptible to future climate change.

Benthic community changes, such as switches from long-lived, slow-growing Arctic to faster-growing temperate species can be expected in the southern areas of the Arctic. Northern range extensions, possibly due to climate change, have recently been documented in the Chukchi Sea for some epifaunal megafauna (Sirenko and Gagaev, 2007). Other species shifts have been noted for bivalves (Richman and Lovvorn, 2003). On a pan-Arctic scale, concentrations of the commercially valuable snow crab (*Chionoecetes opilio*) appear to have shifted northward in the Bering and Chukchi Seas (Orensanz et al., 2004; Bluhm et al., 2009b), and in the European Arctic a self-sustained population now occurs in the Barents Sea (Alvsvåg et al., 2009) where the first snow crabs were documented in 1996 (Kuzmin et al., 1998). These shifts are not only potential ecological indicators of climate warming, but also affect the current sub-Arctic crab fishery and possibly other Arctic fisheries in the future.

In the fjords of Svalbard, only minor changes have been observed in soft-sediment benthic communities over the past 10 to 20 years, despite evidence of intense warming of fjord

Box 9.10. Climate driven variability in the Bering Sea

A recent, well-documented example of climate-driven variability is the Bering Sea regime shift complex (Grebmeier et al., 2006a). The regime shift that took place in 1997 included changes in sea-surface temperature, a reduction in sea-ice extent and wind forcings of ocean currents. Since that time, several coccolithophorid blooms have occurred in the Bering Sea. These are thought to have replaced the previously occurring summer flagellate community (Schumacher et al., 2003). Zooplankton communities have changed from crustacean-dominated, to a dominance of gelatinous plankton (which subsequently decreased again). The prey of the dominant jellyfish species during the late 1990s and early 2000s, *Chrysaora melanaster*, included euphausiids, copepods and amphipods, as well as juvenile pollack and hence overlapped with some Arctic marine mammals (Bluhm and Gradinger, 2008).

waters during this period (e.g., Renaud et al., 2008; Kedra et al., 2010). The presence of a sill within some fjords has been suggested to determine the influence of the warmer shelf waters on the biota of these areas to some extent. A retrospective study of decapod crustacean communities during investigations spanning 100 years has shown an increase in generalist feeders at the expense of specialist shrimps, but without a direct causal link to climatic fluctuation (Berge et al., 2009).

9.3.3.3. Fish species and fisheries

Loss of Arctic sea-ice cover and regional warming will have significant impacts on fish species of ecological and economic importance. Across the Arctic, the planktivorous capelin and the omnivorous polar and Arctic cod play vital roles in the transfer of pelagic production from zooplankton to higher trophic levels such as marine mammals and seabirds. These fish derive much of their high lipid content from lipid-rich Arctic zooplankton species (e.g., *Calanus glacialis*, *Themisto libellula*), and it is this fat content that is critical for sustaining and fueling reproduction in their predators. In the Barents Sea, these fish species are highly dependent on the roles of sea ice and shore-fast ice as habitat and as a driver of planktonic processes, although it should be noted that capelin do live in the Gulf of Alaska and other areas where there is no FYI or MYI.

In their seasonal migrations, capelin follow the receding ice edge northward, feeding on developing zooplankton populations which themselves are taking advantage of intense but ephemeral ice-edge algal blooms. Population size and feeding success of capelin depend on many environmental and ecological factors; water temperature and seasonal ice distribution are important as they affect the degree of match or mismatch in timing of capelin arrival in an area and the availability of food (e.g., Gjørseter, 1998; Orlova et al., 2002, 2005, 2009). Polar and Arctic cod are also dependent on zooplankton food and the influence of ice on developmental phenology of zooplankton will also influence these species (Lønne and Gulliksen, 1989; Hop et al., 1997; Fortier et al., 2006; Orlova et al., 2009). Flexible life-history strategies by polar cod, however, may help them persist with earlier melting of sea ice and increased warming of Arctic waters (Fortier et al., 2006). At least during some stages of their life, these fish may be closely associated with sea ice, using the irregular underside of the ice as refuges from predators and as occasional feeding areas. It is unclear how important this use of the sea-ice habitat is to persistence of the species. It is clear, however, that success of forage fish such as capelin and Arctic cod is critical for the commercial fish stocks that feed on them. Atlantic cod *Gadus morhua* feed heavily on planktivorous fish in the Barents Sea; and it is the availability of lipid-rich Arctic copepods that results in optimum body condition of the forage fish (e.g., Gjørseter et al., 2002; Orlova et al., 2009).

Changes in planktonic community structure due to warming of Arctic waters are likely to negatively impact capelin and polar/Arctic cod as the fat-rich Arctic zooplankton are replaced by boreal species (Beaugrand et al., 2010; Hopcroft et al., 2010). This interaction between climate, zooplankton community composition, and condition of planktivorous fish is a complex but important ecosystem dynamic. For example, young walleye pollock in the Bering Sea grow more slowly but

accumulate sufficient energy reserves to overwinter during cold years, when larger *Calanus* and euphausiids are abundant (Coyle et al., 2008; Hunt et al., 2008). During warm years, however, small neritic copepods dominate the zooplankton and, while providing resources for rapid growth of early life stages of pollock, result in age-0 pollock with energy stores too low to survive their first winter (Moss et al., 2009). Furthermore, lack of larger zooplankton in warmer years may make young walleye pollock more susceptible to predation (Farley et al., 2007; Farley and Trudel, 2009). Thus, climate impacts on lower trophic levels may propagate through the ecosystem and eventually affect seabirds, marine mammals, and commercial fish species (e.g., Karnovsky et al., 2003). Finally, northward expansion of potential competitors and predatory species could also have negative impacts both on forage-fish populations and the benthic fauna on which walrus, bearded seals and some sea ducks forage (Grebmeier et al., 2006a). A northward shift in boreal species is widely predicted (ACIA, 2005), and has already been observed in the North Pacific and in the Bering and Barents Seas (e.g., Hare and Mantua, 2000; Mueter and Litzow, 2008; Drinkwater, 2009). Whether these species successfully reproduce in Arctic waters (i.e., true expansion shifts) will affect their long-term ecological role. For example, *C. glacialis* advected from the Bering Sea into the Arctic Ocean appears to play only a transient ecological role as their viability declines as they penetrate further into Arctic waters (Nelson et al., 2009).

Target species of commercial and subsistence fisheries in the Arctic are also likely to be impacted by loss of sea ice and warming. Atlantic cod and Greenland halibut are important species in the European Arctic, including around Greenland. The former is a boreal species that has expanded into northern Greenland and Barents Sea waters during historical warm periods (see Renaud et al., 2007, and references within), and has been observed in increasing densities in west Svalbard fjords since 2004 (Berge et al., 2008). Reduction of ice cover and warming of waters in these northern regions may lead to greater populations and enhanced fisheries value of this species (Drinkwater, 2005, 2006), but it is unclear how the channeling of high levels of pelagic production to this top predator will influence food supply for seabirds and marine mammals. Greenland halibut, on the other hand, is an Arctic species and could be expected to decline substantially in response to rising temperatures, as it has during warm periods in the Bering Sea (NPFMC, 2009). A strong positive AO/NAO phase (meaning warmer conditions in the Barents/Norwegian Sea) between 1989 and 1994 corresponded with very low stock and catch values for Greenland halibut (Albert and Høines, 2003).

9.3.3.4. Marine mammals and seabirds

The earliest warning signs of climate change in the Arctic gave rise to immediate concern for the potential impacts on marine mammals of the region (Stirling and Derocher, 1993; MacGarvin and Simmonds, 1996; Tynan and DeMaster, 1997; Carmack and McLaughlin, 2001; Kelly, 2001). There is particular concern for 'ice-loving' Arctic marine mammals (e.g., ACIA, 2005; Johnston et al., 2005; Laidre and Heide-Jørgensen, 2005b; Moore and Laidre, 2006; Simmonds and Isaac, 2007; Kovacs and Lydersen, 2008; Laidre et al., 2008; Moore and

Huntington, 2008). Loss of sea ice represents a reduction in total habitat area available to ice-associated marine mammals that is already affecting some species, and in the longer term, it is expected that foraging success, fertility rates, and mortality rates etc. will be impacted for additional populations and species (see Section 9.3.4). Theoretically speaking, specialist feeders are likely to be more heavily impacted by changes in Arctic food webs than species that are generalist feeders, and ice-breeders that require long periods of stable ice in late spring are likely to be impacted more rapidly than late winter ice-breeders that require ice for shorter periods of time (Kovacs and Lydersen, 2008; Laidre et al., 2008).

Alterations in distribution would be expected to be among the first changes observed due to changes in ice extent and seasonal availability. Vibe's (1967) analysis of the relationship between multi-decadal environmental fluctuations and marine mammal harvest success in West Greenland was one of the first studies that explored decadal-term patterns of distribution of Arctic marine mammals in relation to ice type and distribution. Vibe (1967) clearly showed the importance of availability of specific ice types in determining the distribution of marine mammals of the region. More recent analyses of decadal patterns of sea ice and their influence on marine mammals suggest that changes in recent years are likely to impact resident marine mammal populations at regional and hemispheric scales (Barber and Iacozza, 2004). While northward expansions are possible for temperate species, for example grey whales (*Eschrichtius robustus*) in the Pacific sector (Stafford et al., 2007; Moore, 2008a,b), high-Arctic endemics have limited capacity for range shifts northward. But, changes are clearly taking place. Vast herds of harp seals have been observed off western Greenland and eastern Svalbard during the period from January to March, times of year that they are not normally in these regions (Rosing-Asvid, 2008; Norwegian Polar Institute Marine Mammal Sighting Data Base) and a new harp seal whelping ground has been discovered off southern Greenland (Rosing-Asvid, 2008). Grey seals have also been conclusively documented in southern Greenland as of summer 2009, which is a notable range expansion northward for this species (Rosing-Asvid, 2010). The degree to which animals are capable of 'relocation' of breeding areas is unknown; tradition plays a significant social role in being in the right place at the right time for many ice-breeding species that disperse broadly outside the breeding period.

In the Canadian High Arctic, killer whales appear to be extending their season of Arctic habitation and expanding their range northward, at least in periods when ice conditions permit (e.g., Ferguson, 2009; Higdon and Ferguson, 2009). Early season sightings of this species have also occurred in recent years at very high latitudes in the Northeast Atlantic (early March at above 80° N, Norwegian Polar Institute Marine Mammal Sighting Data Base), although the lack of comparative historical data limits interpretation of these sightings. Other anecdotal data suggest that some temperate cetaceans are shifting their summer distributions northward. For example, sei whales (*Balaenoptera borealis*) and harbor porpoises (*Phocoena phocoena*) have been seen in Svalbard waters in recent years for the first time, and unusually high densities of fin whales (*B. physalus*) and minke whales (*B. acutorostrata*) have occurred in July and August along the shelf break west

of Spitsbergen recently (Norwegian Polar Institute Marine Mammal Sighting Data Base). Blue whales (*B. musculus*) are also being sighted with some regularity near Svalbard, although population increases, rather than range shifts due to changing ice conditions, might be the reason for the increased incidence of this species in this area (Norwegian Polar Institute Marine Mammal Sighting Data Base).

Major declines in abundance or pup production have recently been documented for hooded seals in the Northeast Atlantic, harp seals in the White Sea and ringed seals in Hudson Bay, which have been attributed largely to climate change impacts on ice conditions (Ferguson et al., 2005; Chernook and Boltnev, 2008; ICES, 2008). Low ice years have also been correlated with low body condition indexes for female ringed seals and ovulation rates as low as 50% of the norm in extreme low ice years (Harwood et al., 2000). Ice-seals in other areas are also likely to be experiencing declines in reproductive success, and perhaps also condition, but lack of monitoring activities make it impossible to assess the current extent of change. For example, ringed seals on the west coast of Svalbard have not had sufficient ice for normal breeding levels to occur since 2005 (Kovacs and Lydersen, Norwegian Polar Institute, pers. obs.) and are likely to be in decline. In western Hudson Bay, a clear link was established between climate warming, reduced ice presence, and observed declines in polar bear abundance and reductions in their physical and reproductive condition (e.g., Stirling et al., 1999) and similar finding have now been reported from other regions (see Box 9.11). Alternatively, there has been no dramatic change to bowhead whale distribution or migratory timing in the Pacific Arctic sector. The Bering-Chukchi-Beaufort population has increased at a rate of 3% per year since the late 1970s (George et al., 2004), with indications from calf counts and harvested whale body condition that reduced sea ice in the eastern Beaufort Sea has (at least for the time being) actually been good for this population (George et al., 2006; IWC, 2010).

A growing body of data suggests that Pacific walrus are also showing negative impacts of sea-ice reductions (<http://alaska.usgs.gov>). Abandoned calves have been reported at sea (Cooper et al., 2006), which suggests that females with dependent young might be experiencing nutritional stress with their usual sea-ice resting platform retracting during summer north of the continental shelf, separating them from feeding areas. Mothers and calves are certainly spending more time on land (see Arnborn, 2009), where stampede incidents have recently caused significant mortality of both adults and young animals (from hundreds to thousands of individuals) (e.g., Fischbach et al., 2009). There are also suggestions that Pacific walrus have shifted their diet toward eating more seals and fewer benthic invertebrates (Rausch et al., 2007; also see Gjertz, 1990; Sheffield et al., 2001, but also see Sheffield and Grebmeier, 2009), which may lead to higher prevalence of trichinellosis (Rausch et al., 2007); this parasite has shown marked increases in the past decade in ice-associated marine mammals in Svalbard (Jensen et al., 2010). However, the magnitude of the impact of this dietary shift by walrus in the Pacific is difficult to assess. Some harvest data show that the proportion of females in the catch has increased while the relative proportions of pregnant females have declined and the age of first reproduction has shifted (Chad Jay, U.S. Geological Survey, pers. comm.). These changes are suggested to be related to harvest

Box 9.11. Sea ice decline and polar bears

Polar bears are dependent on sea ice as their primary hunting platform; their diet is predominantly made up of ice-associated seals. Most polar bears travel thousands of kilometres over sea ice searching for mates and hunting for seals each year. In one of the southernmost populations of polar bears, in western Hudson Bay, changes in the date of break-up of the sea ice were suspected in the early 1990s (Derocher et al., 2004). Early ice-break up and delayed freeze-up, has resulted in a shorter sea-ice season in the region which has caused the bears to spend more time ashore resulting in reductions in condition, reproductive rates, survival, and population size (Stirling et al., 1999, 2004; Parks et al., 2006; Stirling and Parkinson, 2006).

Litter production rate and natality declines, as well as reductions in body length, have also been detected in Svalbard polar bears, which show a relationship to large-scale climate variation (Derocher, 2005). However, in this region density-dependent factors cannot be ruled out as being part of the cause of these changes (see Aars et al., 2009). Reduced prey availability for polar bears due to changing ice conditions has been suggested to be the case for bears in eastern Greenland, where bears are now smaller than they were some decades ago; although contaminant increases may also be playing a role in the observations in this region (Pertoldi et al., 2009). Most recently, polar bears in the Beaufort Sea have exhibited reduced breeding rates, lower cub litter survival and reduced adult survivorship, that are correlated with increasing duration of the ice-free period (Regehr et al., 2006, 2007, 2010). These conclusions follow earlier reports from this area of cannibalized and starved bears and suggestions that Beaufort Sea bears were periodically nutritionally stressed during the early part of this century because of increasing duration of the open-water season and possible decreases in seal populations, or their accessibility to bears (Stirling et al., 2008a).

Polar bear distribution has shifted in the Alaskan Beaufort Sea in recent decades, with more bears being associated with land and open water, particularly in early autumn. These changes are thought to reflect a behavioral response by polar bears to changes in ice type and cover and the timing of ice

formation and ablation (Gleason and Rode, 2009). Polar bear denning locations have shifted in some regions in response to changing ice conditions, with fewer dens in MYI and more ashore (e.g., Fischbach et al., 2007). The tendency for bears to spend more time ashore (e.g., Schliebe et al., 2008) has the potential for an increase in the number of human-bear interactions (e.g., Towns et al., 2009) and may give false impressions of regional densities (Stirling and Parkinson, 2006). In more southerly areas such as western and southern Hudson Bay, it also puts denning bears at risk of new threats such as forest fires (Richardson et al., 2007).

Polar bears are capable of opportunistically altering their foraging behavior to take advantage of locally abundant prey, and to some degree compensate for a decline in a dominant prey species (Thiemann et al., 2008). Dietary shifts have been documented in the Hudson Bay polar bear population, with fewer ice-seals and more open-water seals in the diet of bears over the period 1991 to 2007 (McKinney et al., 2009) and an increased consumption of terrestrially-based food such as large quantities of goose eggs (Smith et al., 2010). Although polar bears will consume a wide variety of food types, it seems unlikely that current population sizes could be maintained on alternative dietary energy sources if the diet does not include significant quantities of marine mammals, which are normally accessed from a sea-ice platform (see Figure 9.34; also see Hobson et al., 2009; Rockwell and Gormezano, 2009; and Dyck and Kebreab, 2009, for preliminary discussions of this topic).

Failures in polar bear management systems to respond to population changes in a timely manner have resulted in severe overharvesting in Baffin Bay and Kane Basin, populations which are shared by Canada and Greenland (e.g., Taylor et al., 2008), and highlight the need for responsive management procedures for this and other species under the currently rapidly changing environmental conditions (Wiig et al., 1995; also see Clark et al., 2008; Dowsley and Wenzel, 2008; Dowsley, 2009). The observed negative consequences of sea-ice declines on polar bears to date, and future sea-ice predictions (see Section 9.3.4), led to the species being listed on the IUCN (International Union for Conservation of Nature) Red List and the Endangered Species Act of the United States, in 2008.



Figure 9.34. Polar bears stranded on land during summer often have difficulty getting enough food to restore their fat reserves for the following winter period (left). Polar bears normally use sea ice as their primary hunting platform, where they maintain good body condition on their diet of ice-associated seals (right). Photos by Kit M. Kovacs and Christian Lydersen, Norwegian Polar Institute (left) and Hans Wolkers, Norwegian Polar Institute (right).

management and changing environmental conditions (Garlich-Miller et al., 2006). Atlantic walrus might be somewhat more resilient to changes in sea ice because they utilize more nearshore areas for feeding (Born, 2005), but less extensive seasonal ice coverage is almost certain to have a long-term impact on benthic food resources that walrus of both subspecies depend upon and if walrus are spatially restricted because of distance to suitable haul-out areas, abundances are likely to decline (Kovacs and Lydersen, 2008).

Changes in the harvests of several species have been noted with respect to changing sea-ice conditions in the North Atlantic Arctic. West Greenland harvests of harp seals have increased 100-fold for adults and 10-fold for juveniles in the past 20 years; in the 1980s only some hundred adults were taken and fewer than 2000 young animals, this has increased to in excess of 20 000 of each age group in the period 1995 to 2005 (Rosing-Asvid, 2008). Given the size of the stocks, this does not represent a specific management problem in this case. However, other increased catches might be more significant from a conservation point of view. Increases in narwhal catches by hunters in Siorapaluk, Greenland, have taken place since 2002 due to changed sea-ice conditions, with lighter ice coverage allowing easier access for hunters (Nielsen, 2009). This increased harvest has unknown implications because of a lack of information about the status of this stock; both scientific surveys and ecological knowledge suggest that it is an independent stock unit, but there is insufficient information to provide management advice. In the rapidly changing conditions in the Arctic, it is essential that management systems be provided with up-to-date stock status, and that they have the capacity to respond quickly to changes (see Section 9.3.5).

Timing of ice break-up is known to have a strong effect on the timing and success of breeding for thick-billed murres in northern Hudson Bay, where early ice years tend to be sub-optimal for chick rearing (Gaston et al., 2005a; see Box 9.12). For black guillemots in the Beaufort Sea, reduction in ice

cover during summer has been linked to reproductive failure due to a reduction in the availability of Arctic cod when sea ice is far from the shore (Moline et al., 2008). A reduction in sea ice in the Bering Sea during the late 20th century affected the timing of breeding of seabirds and has been implicated in population declines of murres and kittiwakes at St Paul Island (Byrd et al., 2008a,b). In general, during warm years with little ice, planktivorous species seem to be more challenged than piscivorous species in finding food (Kitaysky and Golubova, 2000; Stempniewicz et al., 2007; Benowitz-Fredericks et al., 2008). In all the areas mentioned above, immigration has been observed by auk species that normally have more southerly distributions (horned puffin, razorbill *Alca torda*, ancient murrelet *Synthliboramphus antiquus*).

Conversely, in more High Arctic areas, such as Barrow Strait, early ice break-up has been associated with earlier breeding and enhanced reproductive success for black-legged kittiwakes, glaucous gulls and thick-billed murres (Gaston et al., 2005b). Thick-billed murre populations have shown high rates of population increase during periods of moderate climate warming in many areas (Irons et al., 2008). However, the population trend for this species throughout northern regions in Norway, including the High Arctic archipelago of Svalbard, is currently declining, despite a general rise both in air and water temperatures in the region (Lorentsen and Christensen-Dalsgaard, 2010). Populations of black-legged kittiwakes are increasing in the Canadian High Arctic (Mallory et al., 2009) possibly as a result of enhanced reproductive success due to earlier ice break-up. The cause of the rapid decline in ivory gulls in the Canadian High Arctic and possibly elsewhere, since the 1970s (Gilchrist and Mallory, 2005) is unknown. However, the core range of the remaining birds in the Canadian population has retreated northward, suggesting that, irrespective of the cause of the population trend, the remaining birds are concentrating in areas of prolonged summer ice cover (Gilchrist and Mallory, 2005).

Box 9.12. Breeding and feeding of thick-billed murres in Hudson Bay

In northern Hudson Bay, synchronization of breeding with the timing of ice break-up appears to be important in determining breeding success of thick-billed murres. Between 1988 and 2008, the timing of sea-ice break-up advanced by about 17 days. Over the same period, the timing of breeding by the murres has advanced by less than a week, apparently causing a mismatch between the time at which chicks hatch and the optimal timing with respect to food availability (Gaston et al., 2009).

The diets of thick-billed murre nestlings at Coats and Digges Island have been monitored since the 1980s. In the early years, the diet at both colonies was dominated by Arctic cod, but since the 1990s, capelin has made up a much larger share of the diet, up to 70%, at Coats Island (Figure 9.35; Gaston et al., 2003). At Digges Island, where Arctic cod comprised more than 80% of the diet in the early 1980s, capelin made up 85% of the nestling diet in 2004. Arctic cod being an ice-associated fish, these changes may be linked to progressively earlier break-up of sea ice in Hudson Bay since the early 1990s (Stirling and Parkinson, 2006).




Figure 9.35. Proportion of Arctic cod and capelin fed to nestling thick-billed murres at Coats Island between 1981 and 2009 (no data for 1982 and 1983). Source: Gaston et al., (2003) and A.J. Gaston (Canadian Wildlife Service, unpubl. data).

9.3.4. Looking into the future

By their very nature, predictions are speculative, but given the potential for major change in the Arctic due to sea-ice decline, it is important to prepare mitigation strategies (see Section 9.4) and management plans for flora and fauna with the best available models and expert predictions (see Table 9.3 for a summary). The physical models that predict sea-ice extent still contain a lot of variability (see Section 9.1), but all of the models converge to predict a – more or less rapid – decline in September sea-ice extent during this century. Observations of sea-ice extent and thickness (see Section 9.1) indicate that conditions are moving toward a seasonally ice-free Arctic more rapidly than GCMs (Section 9.1) and high resolution coupled ocean-sea ice-atmosphere models (Section 9.2) have predicted. Current estimates suggest that the Arctic may be free of MYI somewhere during the period 2013 to 2030 (Wang and Overland, 2009). Recent results by Barber et al. (2009) and Kwok et al. (2009) support the earlier part of this temporal range. The variability in model results underscores the challenges posed by the complexity of the Arctic climate-ocean system, including variability in large-scale and regional circulation patterns and feedback processes between the atmosphere and ocean.

In Arctic ecosystems, food-web structure dictates much of the fate of organic matter, as reflected in differences in biogeochemical cycling regimes at various spatial and temporal

scales. Therefore ecosystem responses to changes in physical forcings are neither direct nor linear; they are therefore difficult to predict with confidence. Additionally, the impacts of changes in Arctic sea ice, which are the focus of this review, cannot be considered in isolation from other changes taking place in the Arctic. Superimposed on sea-ice associated changes in light availability, stratification and mixing, timing of ice formation/melt, and ice-edge position, other major changes such as increased riverine input, increased sea-surface temperature, increased air temperatures, melting and receding glaciers, changes in precipitation and atmospheric forcings all contribute to modify Arctic marine ecosystems. In addition, ecosystem responses will vary regionally, depending on different regimes of oceanic and climatic forcings but also in relation to regional variation in bathymetry and variation within the biological communities themselves, including pivotal species and carbon flow pathways. Based on variability observed in the past which is high both on interannual and decadal scales in the Arctic (e.g., Barber and Iacozza, 2004), and with some background studies such as those reporting the impacts of cold and warm years in the Barents Sea (Orlova et al., 2009), and in the Bering Sea (Hunt et al., 2008), predictive scenarios for the more extreme conditions that are forecast for the coming decades can be extrapolated with modest levels of certainty (e.g., Box 9.13).

Table 9.3. Some key potential biological impacts in response to decreasing sea-ice extent and lengthening of the open-water period in the Arctic. Likelihood (very unlikely, unlikely, possible, likely, very likely) and confidence (low, medium, high) are defined according to ACIA (2005).

Predicted impact	Likelihood of prediction	Confidence in prediction
Increase in phytoplankton production	Very likely	High
Increase in total primary production	Very likely	Medium
Increase in benthic primary production on shelves	Likely	High
Increase in sedimentation of organic carbon in areas of increased production	Very likely	Medium
Advance in the timing of the phytoplankton bloom on shelves	Very likely	Medium
Development of an autumn phytoplankton bloom in areas where the open-water period is over five months long	Possible	Low
Decrease in ice-algal production on shelves	Likely	Low
Increase in ice-algal production in central basins	Very likely	Medium
Increase in bacterial respiration and remineralization of organic matter	Very likely	High
Increase in nutrient supply through wind mixing and upwelling on shelves	Very likely	High
Disruption in zooplankton life-histories	Very likely	Medium
Decline in populations of MYI faunal taxa	Very likely	Medium
Decline in feeding conditions for benthos and demersal species in nearshore areas	Likely	Low
Shift in the abundance of pivotal copepod and fish species	Very likely	High
Change in diet of ice-associated birds	Likely	High
Shift in distribution of marine birds	Likely	High
Northward shift in breeding distributions of pack-ice breeding pinnipeds	Very likely	Medium
Declining abundance of ice-associated endemic marine mammal populations	Very likely	High
Increase in abundance of temperate migrant marine mammals during summer (and longer resident times in the Arctic)	Very likely	High
Dietary shifts for migrant baleen whales in Arctic water	Likely	High
Increased mortality of Arctic endemic species due to killer whale predation in some areas	Very likely	High
Northward spread of diseases and parasites of marine mammals and other fauna	Very likely	High

Box 9.13. Case study: Effect of advanced melt in the Canadian Archipelago on primary production

A recent high resolution ice-ocean regional model for the Canadian Archipelago (Sou and Flato, 2009) predicts spring ice break-up to occur ten days earlier, on average, in the period 2041 to 2060. Regionally, ice break-up is predicted to be up to two to five weeks earlier in northern Baffin Bay, Nares Strait and the Amundsen Gulf. Bringing together published data on the typical development of the ice-algal bloom and its sinking export, and of the summer phytoplankton bloom in the Archipelago, makes it possible to draw a conceptual model of the effects of a two- to five-week earlier melt period. Advancing ice melt by a two-week period does not affect the onset of the ice-algal bloom but does shorten the duration of the bloom. The direct consequences are a decrease in the overall production and possibly biomass accumulation of ice algae, and an earlier and smaller release of ice algae biomass from the ice. Assuming that zooplankton grazers would still be synchronized with the availability of ice algae, this simple model indicates that ice–pelagic coupling (i.e., flow of carbon toward pelagic grazers) would be favored at the expense of ice–benthic coupling since little biomass would be available for sinking after zooplankton grazing.

Under the scenario of a five-week advance in ice melt, melt occurs prior to the development of the ice-algal bloom, shunting carbon flow pathways from sea ice production to the pelagos and benthos. Under such a scenario, the potential development of an ice-algal bloom would basically depend on the availability of light early in the season, determined by latitude and by conditions at the snow-ice surface. As many climate scenarios predict an increase in precipitation in the Arctic (ACIA, 2005), it is very likely that a five-week advance in ice melt north of 70° N would completely remove the potential for an ice-algal bloom to take place.

This case study illustrates one current conceptual model for how Arctic shelves may respond to decreased sea ice, that is, by shifting from the current benthic-dominated system to one where more energy is directed toward pelagic food webs (Carroll and Carroll, 2003). There is some evidence that this may be occurring in the Bering Sea (Hunt et al., 2002, 2008; Grebmeier et al., 2006a; Mueter et al., 2009), but this region is not necessarily representative of the entire Arctic. Differences in physical drivers, trophic structure, and biotic components in different regions must be considered carefully before extending predictions to other Arctic shelves (see Tremblay et al., 2008). For example, recent modeling studies using the latest climate forecasts have predicted modest increases in annual primary production in the Barents Sea, but decreased grazing pressure, perhaps leading to enhanced food for the benthos (Ellingsen et al., 2008). The apparent requirement for a specific phenology in the primary production regime for zooplankton development (Baier and Napp, 2003; Søreide et al., 2010) also suggests that a change in timing of blooms may create a mismatch with grazer populations, and perhaps more export of algal material (see Figure 9.36, see also Michel et al., 2006).




Figure 9.36. Present and predicted trends in bottom ice chlorophyll *a* (chl *a*), chl *a* sinking fluxes and suspended chl *a* concentrations in the Canadian Archipelago (Resolute Passage) for scenarios of a two-week and five-week advanced melt period (Sou and Flato, 2009). The trend in suspended chl *a* is from Gaussian regression adjusted to all data points in Figure 7 of Michel et al. (2006); trends for bottom ice chl *a* and chl *a* sinking fluxes are adjusted to data collected in 1992, adapted from Michel et al. (1996).

9.3.4.1. **Change in seasonality and lengthening of the open-water period**

Owing to the overriding influence of light on primary production (in the absence of nutrient limitation), it is predicted that an increase in the duration of the open-water period will increase phytoplankton production. It is also likely that the lengthening of the open-water period in spring, thus far seen only in the Atlantic sector, will advance the period of phytoplankton production (Wiktor, 1999; Rysgaard and Glud, 2007). In autumn, if freeze-up is delayed (predicted to occur two to four weeks later in the Canadian Archipelago; Sou and Flato, 2009), a second phytoplankton bloom may take place, if it is fuelled by nutrient replenishment through vertical mixing (Figure 9.36). This has been observed in the North Water Polynya where the open-water period extends over about six months (Tremblay et al., 2006b; Garneau et al., 2007), and is similar to boreal regions. The late formation of FYI can also lead to increased dynamic processes creating increased rubbing, ridges and other forms of surface deformation. This could increase catchment of snow on top of FYI, thereby limiting photosynthesis at the ocean-ice interface (Barber et al., 2008a).

However, since nutrient inventories and the nutrient supply to surface phytoplankton ultimately determine the maximum phytoplankton yield and the biomass available to the food web, a combination of factors, and not just the duration of the open-water period, will interact to determine the extent (and location) of increased phytoplankton production (e.g., Tremblay and Gagnon, 2009). Higher freshwater input from sea-ice melt and terrestrial runoff, together with warming of the surface layer will increase surface stratification, thereby possibly offsetting the potential for increased nutrient supply from deep waters to the surface layer due to increased storms and wind mixing in open-water areas. On the shelves, allochthonous input of nutrients and denitrification contribute to nutrient inventories and fluxes to primary producers. Additional factors such as increased transport and resuspension of dissolved and particulate material, including sediments, modify the quantity and spectral quality of light available to primary producers on shallow shelves. Such modifications in the physical environment are likely to trigger changes in the species composition of phytoplankton communities and different productivity regimes and pathways of cycling of organic matter.

9.3.4.2. **Shift from multi-year to first-year ice**

According to model predictions (see Section 9.1), FYI will become the dominant ice type in the Arctic over the 21st century. The Arctic has already lost a very significant proportion of its MYI (Barber et al., 2009; Kwok et al., 2009) and is poised to lose the remaining MYI in the near future if the strength and direction of current feedbacks remain unaltered (see Section 9.2).

The biological impacts associated with a shift from MYI to FYI are many and complex and will derive from the strong modifications in physical forcings associated with MYI melt (e.g., increase in freshwater content and stratification, increase in light availability) together with direct impacts associated with the loss of permanent sea ice. It has been suggested that there will be a reorganization of Arctic food chains such that they will become more similar to those in the Antarctic where FYI

makes up 80% of the sea ice (Moline et al., 2008). In the central Arctic, increased numbers and size of leads and openings, and the increase in the duration of the open-water period are likely to increase primary production. However, increased surface stratification due to ice melt will act in an opposing manner since a small change in salinity may counteract the potential for wind-induced mixing (see Sakshaug, 2004; Carmack et al., 2006). Freshening of the surface layer is expected to impact the delivery and cycling of nutrients to surface waters, thereby influencing the amount and type of primary production. As proposed by Li et al. (2009), if reported changes in phytoplankton size structure (i.e., an increase in small phytoplankton) were to persist, this would entail major cascading effects on carbon flow and trophic pathways in Arctic ecosystems.

Over the past three decades, it is estimated that the atmosphere-ocean flux of CO₂ has tripled in the Arctic Ocean (from 24 to 66 TgC/y), attributed to direct (increased atmosphere-ocean exchange) and indirect (increased primary production) effects of the loss of sea ice (Bates et al., 2006). It has also been suggested that outgassing of CO₂ will increase with increased sea-surface temperature (8 gC/m²/y per 1 °C; Anderson and Kallin, 2001).

The location of fast-ice and MIZ edges relative to the shelf slope break and regional bathymetry is also an important aspect of ecosystem response. Modeling work (Carmack and Chapman, 2003) has shown that an ice edge can have an 'optimal' location, which results in stimulating upwelling of nutrient-rich waters into the euphotic zone. Significant increases in production can be expected as long as the ice edge withdraws no further than a location that permits the continuation of wind-forced upwelling of nutrient-rich waters along the shelf break, as proposed by Sakshaug (2004). The position of the ice edge and its associated effects on physical and chemical characteristics will also influence Arctic shelf communities. As the ice edge retreats northward, the delineation between Arctic and boreal communities is also likely to retreat to the north resulting in range expansions of temperate species, and range contractions of Arctic species. Range expansion by boreal species was documented during previous warm periods in the North Atlantic (reviewed by Renaud et al., 2008) and the Bering Sea (Grebmeier et al., 2006b; Mueter and Litzow, 2008). But when boreal communities reach the shelf break, shelf-dependent benthos and plankton will have few available refuges and High Arctic species will face increased competition as well as changing environmental conditions that are not in their favor and are likely to decline, with largely unknown implications for ecosystem functioning (Renaud et al., 2008).

Within the sea-ice realm, pressure ridges might be important habitats, although little can be said currently because they have received limited research attention. Ridges form when ice piles up under pressure, reaching drafts of over 20 m even in summer (Eicken et al., 2005) and these ice piles accumulate snow on the surface that can be important to some animals such as ringed seals, they also create texture under the ice that can serve as shelter for small animals. Based on recent findings of higher faunal abundances related to rafted sea ice compared to level ice during summer melt (Hop and Pavlova, 2008; Gradinger et al., 2009a,b), it is possible that pressure ridges will be especially relevant for the survival of sea ice-related invertebrates over the next decades in areas of dramatic sea ice loss.

Based on current understanding of vertical flux patterns in MYI vs FYI, it has been predicted that as ice melts and the FYI zone expands, the vertical flux of organic matter to the sea floor may increase (Wassmann, 2008). Because this shift from MYI to FYI will occur primarily over oligotrophic deep basins, an increase in productivity and vertical carbon flux could have important implications for carbon remineralization in the water column and for deep-sea benthic communities. Kirchman et al. (2009) postulated that decreasing ice and increased temperatures in the Arctic will increase the flow of carbon toward bacteria at the expense of larger organisms.

9.3.4.3. Predictions for marine mammals and seabirds

Changes observed to date in marine mammal populations under changing ice regimes strongly suggest that impacts will continue to intensify. Range shifts are already taking place and are expected to continue. Population reductions of many ice-associated species already documented in the Atlantic Arctic sector are expected to continue, perhaps at escalated rates. Compression of the ranges of endemic ice-associated species, as well as competition from temperate species moving north, are likely to result in increased competition for food. For example, Pacific walrus are already spending more time at land-based haul-outs (see Arnborn, 2009). If this trend continues they could deplete nearshore benthic resources, which would result in a lower carrying capacity for this species, even if benthic community health is otherwise unaltered. One small area within the range of Atlantic walrus might however be enhanced as a foraging area by changing ice conditions. Thick ice in eastern Greenland currently limits access by walrus to plentiful inshore bivalve banks to the short summer period. Less ice in this region might extend the foraging season in this area and permit more Atlantic walrus to occupy the region (Born, 2005).

Species that are strongly tied to sea-ice habitats, such as the polar bear, ringed seal and ivory gull, may become limited to small sea-ice refugia (e.g., summer sea ice is predicted to persist for longer in the Canadian Arctic Archipelago than elsewhere; see Pfirman, 2009). However, such refuges will support only limited numbers of animals. In general, the decline in sea ice is going to be detrimental to ice-adapted species and advantageous to migrant marine mammal species that currently occupy the Arctic seasonally (Moore and Huntington, 2008). But, the latter group of animals may also face challenges, with future food resources being more dispersed both spatially and temporally compared to the MIZ situation.

Northward range contractions or a shift to breeding earlier in the season are likely to be initial responses to protracted periods of reproductive failure among ice-associated pinnipeds unable to find ice-habitat(s) in traditional areas at the respective breeding times of the various species (Burns, 2009a). Shifting to a terrestrial-breeding situation would require a remarkable degree of behavioral plasticity that has not been seen to date in regions/years where ice reductions have been rapid and major (Kovacs and Lydersen, 2008). And such a shift, if it were possible for some species, is likely to be accompanied by very high levels of mortality for the pups, particularly among species where pups do not swim prior to weaning. Outside the

breeding season, in years when sea ice is not available, spotted seals, bearded seals and ringed seals in some few areas do haul out to rest onshore (Burns, 2009a), but this is clearly not their preferred resting habitat and long-term consequences of such a haul-out habitat shift at a greater scale are unknown in terms of predation or disease-related mortality. Energetics modeling suggests that ringed seals in Svalbard will no longer benefit from offshore summer migrations to the ice edge when the retraction of ice from the archipelago reaches distances of 600 to 700 km (Freitas et al., 2008b). Despite the ability of the pack-ice seal species to remain pelagic, without ice for extended periods, it is likely that populations of these seals will have an increased probability of decline in the relatively near future because of breeding habitat deterioration (e.g., Johnston et al., 2005) given the situation already exhibited among Northeast Atlantic hooded seals and White Sea harp seals. Although projections for ice conditions in the Bering Sea during late winter suggest that the pack ice in that region might continue to sustain ribbon and spotted seal breeding.

Large future reductions in most subpopulations of polar bears are expected, such that this species will be lost from many areas where it is common today (e.g., Wiig et al., 2008; Regehr et al., 2010). Habitat losses are expected to be greatest in the southern seas of the polar basin, especially the Chukchi and Barents seas, and least along the Arctic Ocean shores of Banks Island over to northern Greenland. Density and energetic effects are likely to become important as polar bears make increasingly long migrations from traditional winter ranges to remnant high-latitude summer sea ice. The impacts are likely to be sex- and age-group specific and may ultimately preclude bears from seasonally returning to their traditional ranges (Amstrup et al., 2008; Thiemann et al., 2008; Durner et al., 2009). Expected abundance declines range between 30% and 70% for the next half century and, in the extreme case, it is expected that the circumpolar population of polar bears will exist only as a few distinctly isolated populations within relatively few decades (e.g., IUCN, 2008). This sort of population subdivision is expected to reduce gene flow among population clusters in the future (Crompton et al., 2008). These alarming projections for the future of this iconic wildlife species have not gone unopposed (see Dyck et al., 2007, 2008; Armstrong et al., 2008; O'Neill et al., 2008), but the polar bear science community has refuted these 'procedural' issues (e.g., Stirling et al., 2008b; Amstrup et al., 2009) and stand united in their projections for polar bear declines (e.g., Amstrup et al., 2008; Durner et al., 2009).

Unlike Arctic pinnipeds that rely on sea ice as a platform, the relationship of cetaceans to sea ice rests principally on how ice structures trophic pathways (Bluhm and Gradinger, 2008). Possible changes in pelagic–benthic coupling are expected to impact marine mammals that use benthic resources. The question is, of course, how will this impact Arctic species, including cetaceans? The answer lies within the ability of each species to adapt to changing food webs. In the case of narwhal, loss of pack ice in their wintertime benthic feeding habitat may be of particular concern. This factor contributed their extreme sensitivity index to climate change when ranked among all Arctic marine mammals (Laidre et al., 2008). Conversely, the flexibility in beluga diet may provide them with some resilience to changing prey. Similarly, the generalist feeding habits of

grey whales may give them an advantage over the largely planktivorous bowhead whale in a changing Arctic, although recent observations of bowheads feeding on euphausiids alongside grey whales suggests these whales may be capable of rapid adjustments to shifts in prey availability (Moore et al., 2010). Overall, the feeding ecology of marine mammals (e.g., generalist vs specialist feeders) and their capacity to adapt to new or different food resources will play a key role in their success in a changing environment.

Similar to other marine mammals, projections for the future with regard to cetaceans and sea-ice decline vary by region, with the greatest changes anticipated for the 'inflow' sectors of the Pacific and Atlantic Arctic where an additional 125 ice-free days are expected (Moore and Huntington, 2008). While it is anticipated that these regions may become more productive, existing food webs may be significantly altered. Predictable, high concentrations of prey, such as those that occur following phytoplankton blooms along retracting ice edges, are important for efficient foraging for baleen whales, so the effect of sea-ice reduction on potential prey is a key link in forecasting impacts (e.g., Tynan, 2004). Further, it has been surmised that sea ice also provides protection for Arctic cetaceans from predators such as sharks and killer whales. Increased presence of the latter may have significant impacts on endemic Arctic seals and whales in an Arctic with less sea ice (Ferguson, 2009; Higdon and Ferguson, 2009). Thus, Arctic cetaceans face multiple challenges in that they will have to adapt to altered food webs, while potentially dealing with increased competition for prey with seasonally migrant species that remain in Arctic waters for longer periods, and in some areas cope with increased levels of predation.

In addition to the direct impacts of habitat loss, marine mammals in the Arctic are likely to face increased disease and parasite risks as a result of other currently temperate marine mammals moving north and the warming both of air and seawater (Harvell et al., 1999; Rausch et al., 2007; Van Bresse et al., 2009) and perhaps also increased risks from contaminants (MacDonald et al., 2003, 2005; Noyes et al., 2009). Over the coming decades it is also highly likely that Arctic marine mammals will face increased impacts from human traffic and development in previously inaccessible, ice-covered areas (Kovacs and Lydersen, 2008; Fuller et al., 2008; Arctic Council, 2009). In combination, these various changes are likely to result in substantial distributional changes and/or abundance reductions for many endemic Arctic marine mammal species. The behavioral plasticity that they will exhibit (or not) is impossible to predict. These species have never before been challenged by the extreme environmental change predicted for Arctic sea-ice communities. If species are fixed in traditional spatial and temporal cycles, and are unable to shift them within decadal time scales, some populations will be threatened with extirpation. In somewhat longer time frames, species extinctions can also be envisaged.

Because most marine birds are highly philopatric, changes in breeding range are likely to be slow for colonial species. Nevertheless, in Canada, the range of the ivory gull has contracted severely over the past 30 years, corresponding with a reduction of about 80% in the overall population (Gilchrist and Mallory, 2005). Smaller, but significant reductions have also been noted for glaucous gulls in several parts of their range (CAFF

Seabird Group, unpubl.). A pattern of population expansion for ice-associated species in the northernmost parts of their range, along with reductions and range contractions at the southern edge will almost certainly continue, being accompanied by range expansions of more southerly species (e.g., razorbill, Gaston and Woo, 2008). The extent to which competition from more southerly species will impact populations of Arctic species is unknown, but negative impacts are likely (e.g., Irons et al., 2008). Less predictable spatial and temporal primary production in the future is likely as MYI is replaced by FYI and seasonal shifts occur. This could impact seabirds which require dense concentrations of prey, particularly during the critical chick-rearing period for successful reproduction. Change from highly concentrated production associated with ice edges and MIZ to more dispersed pelagic production may result in advantages to wide-ranging, more K-selected species (e.g., northern fulmar) and reductions in those species following a strategy of higher annual reproductive output (e.g., black-legged kittiwake).

9.3.5. Knowledge gaps and critical research needs

There are currently large gaps in knowledge that limit understanding of the complex interactions between Arctic biota and their physical environment. Over the past few decades, many scientific papers have solicited increased research effort in the Arctic to fill these gaps (e.g., Hansell et al., 1998). International Polar Year (IPY) studies will provide a vast amount of new knowledge and a vital foundation for future work, but many questions remain to be answered, which will require monitoring activity over a protracted period on the scale of ocean basins. Specifically, long-term commitments to ocean observatories that explicitly examine biological responses to changes in the physical structuring of the Arctic are urgently needed (e.g., Grebmeier et al., 2010). Such long-term series, together with process studies, will improve understanding of the response of sea ice to changing physical forcing mechanisms and feedbacks within and between the physical and biological components of the system.

At present, there is poor understanding of many of the key environmental forcing factors, their temporal and spatial scales of variability, and of ecosystem structure and function within the Arctic Ocean. This alone makes it difficult to predict ecosystem change due to loss of sea ice.

Currently, the Arctic Ocean is considered a net sink for atmospheric CO₂ (Bates and Mathis, 2009). However, it is only possible to speculate with respect to the direction and magnitude of future changes in the role of the Arctic Ocean as a source or sink of CO₂. The Arctic may be in a period of transition toward a new equilibrium, which will depend on a balance of biogeochemical processes operating at multiple scales, for example, atmosphere–ocean–ice exchanges, primary production and export to depth, respiration and remineralization of organic material. It has been proposed that sea ice plays a significant role in CO₂ drawdown and redistribution through ice formation, transport and melt (Jones and Coote, 1981; Anderson et al., 2004; Rysgaard et al., 2007, 2009). Furthermore, the recent discovery of calcium carbonates in sea ice (Dieckmann et al., 2008) and the release of dissolved

inorganic (and organic) carbon during ice formation, speaks to biogeochemical processes taking place in sea ice. These processes require further attention to have a fuller comprehension of their functioning and to be able to quantify the role of sea ice in the global carbon cycle. Reductions in sea ice are expected to directly affect these processes and future CO₂ drawdown. This knowledge is essential to constrain global greenhouse gas emissions scenarios and climate model predictions.

Few long-term biological sampling series exist because of the difficulty associated with re-sampling communities throughout the year or over multiple years or even decades. The various scales of variability that characterize Arctic marine ecosystems and the complexity of physical factors which, in isolation or in combination, influence biological organisms and communities, make it difficult to establish cause-effect relationships for predictions and adaptation. Seasonal changes in algal and faunal abundance and diversity are dramatic in sea ice and the water column (Makabe et al., 2009; Story-Manes and Gradinger, 2009), with dampened variability in benthic communities because of their typically slower growth rates and longer life-spans. However, interannual and interdecadal alterations have been detected both in pelagic (Brodeur et al., 2002; Hunt et al., 2008) and benthic habitats (Grebmeier et al., 2006a,b). In ice-covered areas, the need for long-term time-series using a combination of both traditional and recently developed sampling technologies is essential for developing a better understanding of the changes occurring in the Arctic.

Changes in the productivity of a summer ice-free Arctic will largely depend on a balance between factors that influence nutrient supply (i.e., water column stratification) and light availability. Therefore, changes in sea ice cannot be assessed in isolation from other environmental changes such as increased river runoff and increased erosion. As an example, because it is not yet possible to assess or predict the effect of changes in the delivery of nutrients via storms / shelf-break upwelling, it is not yet possible to predict changes in the magnitude of primary production, or the location of biological 'hot spots', on Arctic shelves. Such hot-spots are of vital importance to top trophic predators that require considerable energy intakes over the short summer period of productivity. MIZs have traditionally been a focal point for production and energy transfer to top trophic levels. But, if the timing of ice retreat or melt comes earlier, there is uncertainty as to whether animals will be able to track these phenological changes quickly enough. Key attributes such as plasticity in the timing of reproduction and foraging patterns are difficult to predict based on current knowledge. Ecological studies of how animals are adjusting to changing conditions in the Arctic are vital for increasing predictive capacity.

In addition, since community size structure plays a key role in food-web transfers, it is essential to improve characterization of bottom-up (physical factors) and top-down (e.g., grazing) controls on community composition and carbon flow pathways. The widespread occurrence and diversity of microbes in all Arctic habitats (e.g., Lovejoy et al., 2006; Le Romancer et al., 2007; Deming, 2010) warrants a better understanding of their physiology and ecological roles in Arctic food webs and in the cycling of carbon and other materials.

At all levels within the food web, range expansion of boreal species into the Arctic will affect community structure, strength

of links in the food web, and food availability for current Arctic species. It is important to determine how food webs will adjust to changes in species diversity and competitive stress, and to understand the sensitivity of the Arctic ecosystem to this aspect of changes in ice regimes.

Among ice-associated marine mammals, poor baseline data on even the most basic population parameters, such as population size, make tracking global changes in Arctic populations, and extrapolating to future scenarios of environmental change challenging. Abundance is a basic metric for measuring impacts and 'health' of mammalian populations. But, the logistical difficulties in enumerating dispersed marine mammal populations make population surveys very expensive and hence infrequent, incomplete or simply non-existent. Despite the financial and logistic challenges, comprehensive monitoring plans must be put in place immediately for key ice-associated species. Several international plans have been developed, but remain unfinanced (Simpkins et al., 2009; IWC, 2010). Lack of knowledge regarding how some of these animals currently interact with their environments also limits the capacity to make accurate predictions regarding the impacts of climate change. A first-step in predicting likely consequences of future climate change for Arctic marine mammals is developing a detailed understanding of how these species use their environment today (see O'Corry-Crowe, 2008). Finding the means to monitor key populations of Arctic marine mammals as ecosystem sentinels can provide a window into a rapidly changing ecosystem (Moore, 2008a). In some areas of the Arctic, one means of doing this is to form research partnerships with Arctic residents that rely on marine mammals for subsistence. These collaborations provide access for attachment of satellite transmitters to track animal movements and, via harvest monitoring, to investigate changes in diet, body condition and contaminant burdens concomitant with ecosystem variability (Metcalf and Robards, 2008; Moore and Huntington, 2008). Integration of findings from community-based investigations with those from ocean observations is fundamental to any effort to predict long-term ramifications of sea-ice loss for marine mammals (Grebmeier et al., 2010).

The rapid ecosystem changes currently taking place in the Arctic (see Post et al., 2009) could cause significant biodiversity losses in this unique biome (e.g., Markham, 1996; Kovacs and Lydersen, 2008). In this context, it is important that management systems have up-to-date information on all harvested stocks, so that they can be responsive to changing conditions (Prowse et al., 2009; also see Section 9.4). Precautionary harvest levels are in order for all ice-associated species given the predictions for the direction and magnitude of change expected in their sea-ice habitats.

Co-ordination of major national and international efforts is of paramount importance at this time of rapid change in the Arctic to achieve the best use of limited resources in the research community. Currently, there is considerable redundancy among activities performed by agencies exploring climate change impacts, although new data becoming available for assessments are often limited. For example, IUCN is updating its 2008 Red Lists for marine mammals because of the impacts of climate change, which were not incorporated into the recent assessment process. Concurrently, the Marine Mammal Commission of the United States is doing a global assessment of the status of

marine mammals, largely because of the risks posed by climate change. Several independent non-governmental organizations have also begun similar initiatives. The CAFF (Conservation of Arctic Flora and Fauna) CBMP (Circumpolar Biodiversity Monitoring Programme) has also focused significant attention on this faunal group. But, the reality is that for Arctic areas few new data are available for these assessments and many populations, spread over vast regions of the Arctic, have never been surveyed and are not currently being monitored.

Integration of multidisciplinary research in a broad Arctic context has made major steps forward during the IPY period, but there is still a great deal of improvement that could take place across the interdisciplinary Arctic scientific research community.

9.3.5.1. Recommendations

- The top priority for immediate action by the Arctic Council is to ensure that the governments of the Arctic countries arrange long-term commitments to ocean observatories, and process studies that explicitly examine biological responses to changes in the physical environment within the Arctic.
- If sea ice declines occur in the manner predicted in the coming decades, consideration should be given by Canada and Greenland, to creating a World Heritage Site in the Northwest Greenland / Northeast Canadian Archipelago region as a refuge for ice-associated species, as it is likely to be the only area within the Arctic to retain some MYI as well as reasonably extensive summer sea-ice cover.
- Regional scientific assessments and monitoring activities of biological community components across the Arctic, using standardized methodologies among areas, are highly recommended. The rate and extent of sea-ice change currently taking place in the Arctic has not occurred in recorded history and is of significant, broad scientific interest. Results from such monitoring and assessment activities will support decision-making for the sustainability of ecosystem services and biological conservation, and help human populations in the North make transitions to alternate resource use (Berkes and Jolly, 2001; see also Section 9.4).
- Concerted international efforts should be undertaken to preserve endemic Arctic flora and fauna.

9.4. Effects of sea-ice change on human society

- Indigenous and some local peoples have been challenged by changes in sea ice and those challenges will continue into the future.
 - Predictions based on traditional and local knowledge have become less reliable and Arctic residents have to act with greater caution and develop new knowledge and strategies.
 - Increased use of technology (GPS, satellite imagery) is a potential local adaptation strategy.
 - Subsistence and natural resource use activities must adapt further to changing natural resource bases, including changes in timing, distribution, and abundance of animals and fish.

- Travel safety is being reduced. In addition to increased hazards, some smaller communities may become more isolated, and social interactions negatively impacted.
- Barriers to adaptation include limited access to financial resources, wildlife management regimes, reduced outdoor experience and applicable knowledge among younger generations, and institutional memory.
- Cultural resources are being compromised in some locations, a result of coastal erosion, permafrost thaw, and constrained access and availability of traditional/ local foods.
- Reduced seasonal sea-ice presence is already leading to greater shoreline exposure to open water and storm waves. These changes impose greater wave and erosion hazards for shoreline, infrastructure, waterfront structures, and cultural heritage sites in some places.
 - Some ice-bound coasts with negligible past wave climate will be highly susceptible to wave reworking.
 - Even where seasonal open water has been extensive in the past, later freeze-up and earlier break-up increase the probability of storm wave action, even with no change in storm activity.
- Loss of sea ice is increasing interest in access and resource rights, such as shipping, resource extraction, military operations, and tourism, which will have impacts across a wide-range of issues.
 - Resource management planning does not comprehensively anticipate impacts of a declining sea-ice extent.
 - There is a general lack of preparedness, across local, national and international levels, to respond to increased pollution and hazards (e.g., search and rescue needs) as sea ice decreases and access to ice-free areas increases.
- Hazards related to sea-ice movement (ride-up and pile-up) onshore are known to have caused fatalities and significant infrastructure damage in the past.
 - Changing climate will reduce the probability of multi-year shore ice pile-up.
 - Thinner ice may be more susceptible to pile-up and a shortening of the ice season will not decrease the probability of occurrence.
- There are clear limits to any Arctic governance regime (regulatory or soft-law). The drivers of sea-ice change and its consequences occur largely outside the region and fall beyond the jurisdiction of any one Arctic state, and responding to sea-ice change creates profound governance challenges.
 - Existing international and national institutions (e.g., Arctic Council, co-management agencies) can play a critical role as boundary organizations to bring various sub-governmental (e.g., villages, states, provinces) and non-governmental actors (e.g., Inuit Circumpolar Council) together to enhance the flow of information and knowledge.

9.4.1. Introduction

Estimates of the Arctic population vary between 4 million (AHDR, 2004) and 9.9 million (Duhaime and Caron, 2009), depending on geographic definition and seasonal variations, with the indigenous population accounting for between 400 000 and around 1.3 million. Roughly half of all Arctic residents live in the Russian Federation, where the population fluctuates seasonally through work related migration. Many Arctic inhabitants, both indigenous and non-indigenous, live near the coast where sea-ice variability is a dominant feature of the environment. This variability has consequences for subsistence livelihoods, as well as for industrial and economic activities such as commercial fisheries and hydrocarbon development.

Ecosystem services are the benefits humans derive from ecological processes and their functions. Sea ice in the Arctic is critical for ecosystem services and human activities, but may also impede both. Figure 9.37 illustrates the interaction between different types of sea ice and human activities. Eicken et al. (2009) grouped sea-ice system services (SISS) into four broad categories (see Box 9.14). These services/impediments have a spatio-temporal dimension relevant to humans with respect to seasonality and sea-ice type.

In addition, there are important linkages between the Arctic sea-ice system and the rest of the world; these include physical (Arctic climate system feedbacks globally), chemical

(pollutant transport to the Arctic), biological (migratory biota and ecosystem connections), and societal (tourism, resource extraction, policy and politics) linkages. Sea ice dominates many aspects of these linkages, in some cases controlling the direction, nature and rates of change, as well as controlling processes and systems within and among Arctic areas. Thus, immediate and long-term changes in sea ice will directly and indirectly affect human activities worldwide. Reviewing the consequences of sea-ice change, it is essential to distinguish between changes to landfast ice and pack ice, as these are used differently by humans. It is also important to realize that challenges to some will represent opportunities to others.

The aim of this section is to identify and link the key effects of sea-ice changes with key aspects of human society (indigenous and non-indigenous) and activities in the Arctic. The balance among these effects will determine the net influence of sea-ice change on human society and activities, regionally and at a pan-Arctic level.

Projections of the consequences of sea-ice change for human society are limited by an accumulation of uncertainties. Uncertainties in understanding and modeling the physics of sea-ice change are amplified when projecting biological effects, and even more so when considering consequences for society. Societal, political and economic influences operating independently of climate change further increase uncertainty.




Figure 9.37. Interactions between sea ice and human society. The graphic indicates various ice types extending from the shore (left) to the deep ocean (right) and associated services to humans and ecosystems. The spatial scale of service action is indicated by the double-headed arrows with which the services are associated and cross-referenced to Table 9.4 by number/letter combinations. Source: based on Eicken et al. (2009).

Box 9.14. Sea-ice system services

Following the general structure presented in the Millennium Ecosystem Assessment (2005), Eicken et al. (2009) grouped sea-ice system services (SISS) into four broad categories: regulating, provisioning, cultural, and supporting (Table 9.4). Most services (or impediments) are captured within

these categories. There is temporal variation in the services (or impediments) due to changes in sea ice through the year (presence and quality) as well as spatial variation due to the location of the sea ice (offshore ice vs landfast ice) and at different scales of influence.

Table 9.4. Sea-ice system services and impediments affecting human society in the Arctic. Source: modified from Eicken et al. (2009). Service category numbers and nature of service letters are cross-referenced on Figure 9.37. Decreased sea ice will result in generally positive (+) or generally negative (-) effects on humans in the particular example. Effects with uncertain direction are indicated by a question mark.

Service category	Nature of service	Comments
1. Regulating	a. Climate regulator – Arctic and global	Albedo feedback (-); carbon dioxide dissolution regulation (-); thermal feedback (-); nearshore weather regulator/moderator (e.g., fog) (-)
	b. Hazard/impediment to shipping, fishing fleets and coastal infrastructure	Likely decline in physical hazard, thus widening seasons or areas of operations (+, but may require specialized adaptations to exploit); increased ice variability may increase hazard (-)
	c. Stabilizing element for coasts, infrastructure and activities	Platform for human activity (e.g., shelf hydrocarbon development) (-)
	d. Geological role of ice	Protects coastlines from storms (shore-fast ice buttresses land-based permafrost (-); floating ice reduces ocean wind fetch(-); sediment rafting (-?); bottom disturbance (-); thinner ice in the nearshore zone will result in less extensive coastal permafrost – implications for wharves and construction on piles into permafrost (-)
	e. Contaminant regulator	Ice-stored contaminants released (-)
2. Provisioning	a. Transportation corridor	Human ice travel alongshore (-); marine mammals via flaw leads and on ice surface (+?)
	b. Platform for local subsistence and industrial activities	Subsistence hunting of surface (polar bears, seals) or floe-edge (narwhal, walrus) foods (-); stable fishing platform (e.g., long-lining for Greenland halibut) (-); ice islands for hydrocarbon development (-); ice roads (-)
	c. Multi-year ice (as freshwater source)	Decreased or more distant supply (-)
	d. Access to food sources	Travel to floe edge rougher (-), floe edge closer (+), but shorter duration of stable ice (-)
3. Cultural	a. Subsistence activities on and near ice	Activities lessened, teaching opportunities decreased (-)
	b. Cultural and spiritual landscape	Ice loss (-)
	c. Tourism, recreational fishing and hunting	Ice-associated fauna as focal point decreased (-); ship-based tourism access increased (+)
4. Supporting	a. Sea-ice based ecosystems	Habitat for ice flora and fauna on surface, interstitially and on under surface decreased (-); productive food webs decreased/changed (-/+)
	b. Biodiversity reservoir	Extremophiles (bacteria, viruses) and ice-adapted biota decreased (-)

9.4.2. ACIA status of knowledge

The Arctic Climate Impact Assessment (ACIA, 2005) was the first comprehensive effort to assess climate change and its effects in the Arctic region. The assessment focused on changes expected to occur within the 21st century, based on observed data and a moderate scenario of projected future warming (IPCC emissions scenario B2). Although an assessment of economic impacts and community vulnerability to climate change was limited, ACIA projected major cultural, ecological

and economic impacts, including higher production costs resulting from increased costs of infrastructure maintenance, and reduced ocean transportation costs due to longer shipping seasons (see Chapter 1, Section 1.1, for a list of the ACIA key findings).

ACIA projected a summer sea-ice decline of more than 50% over the next 50 to 100 years which would extend the Northern Sea Route navigation season “by two to four months from present” (Walsh et al., 2005) and lead to increased exploration for hydrocarbons and minerals (Loeng et al., 2005). Increased

activity could enable overall economic growth, increase investment options, provide for extensive social services, help create public trust funds for future benefit, and result in local-scale economic stimulation.

Although ACIA noted that a longer ice-free open water season in summer would benefit some local communities, the overall impacts on Arctic residents, especially indigenous traditional lifestyle, health and well-being, were projected to be negative. Sea-ice loss was projected to result in marine mammals being less accessible to hunters, to changes in or losses of traditional hunting grounds, and to modifications of inter-generational transfer of traditional knowledge and culture. Decreased sea-ice coverage was also projected to increase the probability of storms in open water, which would affect near-shore productivity (Walsh et al., 2005). With access to traditional/local foods declining, social and cultural values were considered likely to change or weaken. Shifts in human diets may also have economic consequences. Nuttall et al. (2005) stated that changes in natural resource use may lead to major changes in economic conditions, demography, societal structure and cultural values. Projections of sea-ice change were corroborated by local indigenous observations and scientific monitoring, confirming that many of the changes have already taken place and are now having an impact on travel, safety and lifestyles (Huntington and Fox, 2005).

ACIA also emphasized cross-cutting issues such as effects of sea-ice change on human health (Berner et al., 2005), infrastructure and coastal erosion (Instanes et al., 2005; Walsh et al., 2005), climate change in the context of multiple stressors (McCarthy et al., 2005), and multiple interactions between effects and processes in and beyond the Arctic. The ACIA report concluded that there was a need for qualitative analyses of the economic impacts of climate change, with impact assessments taking a local focus and including all Arctic residents, thereby increasing the relevance for Arctic residents.

9.4.3. Current local and scientific observations

Documentation and use of traditional knowledge has been central to climate change research at the community level. Many Inuit elders and experienced hunters have noted changing sea-ice conditions over the past decade, including later ice freeze-up, earlier ice break-up, a longer ice-free open water period in summer, and altered ice dynamics. These changes have been attributed to rising temperatures and changing temperature variability, especially during the transition periods between seasons, and changes in wind patterns (Ogi et al., 2010). Recent years have witnessed extreme ice conditions, in many ways unprecedented in local knowledge. For example, experienced hunters have noted significant changes in Igloolik, Nunavut, the site of climate change research for over a decade (Fox, 2002; Ford et al., 2006, 2009; Laidler and Ikumaq, 2008; Laidler et al., 2009):

“When I was younger I remember that the ice freezes at the end of September ... Now it freezes [in] late October even [the] first week of November.” Harry Ittusujurat, 2005.

“This is the year [the ocean has] been really, really late in freezing up. It has been later than I ever remember. The

reason we call this month Tusaqtuut is because this is the time [when] everything is frozen and communication between families would be easier at this time ... but we're still not allowed to go straight [to the mainland] because the ice is very dangerous [and] thin.” Augustine Taqqaugak, December 2006.

Sea-ice data for the Igloolik region derived from the Canadian Ice Service and Environment Canada weather stations correspond with Inuit observations (Ford et al., 2009; Laidler et al., 2009), showing a trend of later ice freeze-up of ~0.7 d/y, or one week per decade, between 1969 and 2005. Detailed analysis indicates that the bulk of the change has occurred since 1990 (Laidler et al., 2009). Consistent with later freeze-up there has been significant warming in October and November, increasing by almost 0.2 °C/y between 1977 and 2002. Similar correspondence between Inuit observations and instrumental records has also been found at other times of the year (Ford et al., 2009; Laidler et al., 2009).

Changes in sea-ice extent and condition appear to be occurring much faster than projected in the ACIA report. Sections 9.1 and 9.2 report an acceleration in sea-ice decline in extent and age over the past ten years, both for landfast and pack-ice, although regional differences exist. The physical changes in sea ice in combination with their biological impacts (Section 9.3) are of direct relevance to human society, individuals and activities, in the north. The changes will also require regulation, governance and organization of services at all scales, including at the pan-Arctic level. Although climate change will bring some opportunities, whether these are sustainable over the long-term is a key issue (e.g., Anisimov et al., 2007).

9.4.4. Current human interactions with sea ice

9.4.4.1. Indigenous peoples

For many indigenous peoples (see Figure 10.1) sea ice is fundamental to their culture and identity and is used as a platform for travelling (mainly on landfast ice) and for local subsistence activities, such as hunting and fishing. Across the Arctic, hunting and fishing practices (which mostly take place at the floe edge where landfast ice and pack ice create open-water leads) are adapted to local sea-ice conditions and the seasonal and behavioral patterns of the species harvested. Harvesting is important for nutritional health, economy, identity, and cultural, spiritual and social well-being (Huntington et al., 1998; AHDR, 2004; Hovelsrud et al., 2008). Traditional/local foods are a valuable source of energy, nutrients and minerals and make an important contribution to the diet in many communities. These foods generally have a higher nutritional value than typical store-bought foods. Although store-bought foods are common, subsistence harvesting remains important in all coastal communities, and in areas where income is scarce or where people are living below the poverty line (Nuttall et al., 2005), but can be found across Arctic households independent of income (Aslaksen et al., 2009). Polar bear and seal skins, and sport hunting of polar bears and walrus are an important source of income and employment in some communities (Mathias

et al., 2008). Major changes in, or even loss of, sea ice and the consequent changes in traditional/local food availability will have significant impacts on health, social relationships, and hunting activities (Nuttall et al., 2005; Furgal and Seguin, 2006; Ford, 2009c; Ford et al., 2010) as well as on the personal economies of coastal inhabitants.

In many communities, thinner sea ice and active cracks in the ice, combined with less predictable weather have implications for hunting, harvesting and travelling (Gearheard et al., 2006; Ford et al., 2008; Bravo, 2009; Ford and Pearce, 2010). Access to key hunting areas has been constrained particularly in spring and autumn, resulting in shortages of traditional/local foods such as seal, walrus, and caribou. In parts of the Canadian Arctic, hunters are required to travel further to access hunting areas (Ford et al., 2010; Pearce et al., 2010). Preliminary findings of an ongoing IPY project on the effects of global warming on Arctic marine mammals describe how sea-ice decline in Hudson Bay drives a shift in the ecosystem from a polar bear / seal system with Inuit hunters at the apex to one dominated by cetaceans with killer whales at the apex, thus eroding Inuit traditional subsistence culture (DFO, 2010:11). In Greenland, a number of local and regional sea-ice travel routes can no longer be used and hunters traveling by dog team are forced to travel overland, which is more time consuming and can be more dangerous than sea-ice travel (Goldhar et al., 2010). Changing sea-ice conditions, beyond expected natural variability, have increased the risk of hunting and travelling on the ice, and have led to a greater incidence of accidents and death (Ford et al., 2006, 2008; Hovelsrud et al., 2008).

"We have lost the skills so much. What would not have been dangerous 50 years ago is now dangerous [to young Inuit]." James Ungalak, Igloodik, 2004.

"Nowadays [the younger generations] just want to go out [hunting] without realizing what the weather is going to be like ... Consequently it's more dangerous for them." Peter Awa, Igloodik, 2004.

"GPS enhances your navigation, but if it runs out of batteries it doesn't enhance navigation, it disables you. It can be your blessing and your downfall at the same time." Theo Ikkuqaq, Igloodik, 2004.

In this context, it has been argued that climate change effects experienced to-date are 'dangerous' and compromising the human rights of some indigenous peoples (Crump, 2008; Ford, 2009c).

The relationship between changing sea-ice conditions and local impacts is complex, mediated by the interaction of multiple biophysical and human stresses operating over different spatial and temporal scales. Thus, the increasing danger of using the ice needs to be linked to changes in risk-taking associated with reduced time to hunt, diminishing land skills and decreased traditional knowledge among younger generations, decreasing reliability of traditional knowledge as conditions change, and use of new hunting technology. Likewise, the implications of changing sea-ice conditions for food security are exacerbated by rising commodity prices, increasing costs of hunting (fuel prices, equipment), and weakening of sharing networks. Harvest

and access changes are compounded by community isolation, restrictions and uncertainty about travel, and increased stress in communities (e.g., Berner et al., 2005). Although the local effects appear overall to be negative, a longer ice-free open-water season in summer could also be beneficial for hunting and travelling activities, but this assumes that prey are available, skills for open-water hunting are developed, and appropriate boats and financial capacity are available in the communities (Wenzel, 2009).

While research has documented significant vulnerabilities in local communities to sea-ice change, recent work has also noted emerging adaptive capacity which is moderating some of the negative impacts. Inuvialuit hunters and fishers in the western Canadian Arctic, for example, are changing their mode of transport (e.g., using boats instead of snowmobiles) to adapt to spring break-up occurring earlier each year (Ford et al., 2010; Pearce et al., 2010). Some studies highlight how social learning and responsive local institutions have emerged as the community adapts to changing ice conditions, thus helping reduce the dangers of using the ice in a changing climate (Ford, 2009a; Ford et al., 2009).

Many individuals and communities adapt by taking advantage of new conditions and minimizing impacts by using new technology, changing resource use patterns, and/or switching to the consumption of store-bought foods. In many cases these adaptations require monetary investments. The ability of households to make these investments is constrained by limited financial capacity: for example, an average household income in Igloodik is two-thirds the Canadian average, living costs are significantly higher (store-bought food is on average twice as expensive as the same food bought outside the Arctic), and unemployment is high (officially 16%, unofficially over 30%) (Ford and Berrang-Ford, 2009).

The Sea Ice for Walrus Outlook (SIWO) is an ongoing effort that combines local knowledge and observations with scientific assessments and satellite data, to present weekly information on sea-ice condition relevant to walrus in the northern Bering Sea and southern Chukchi Sea regions of Alaska (www.arcus.org/search/siwo). In addition, the IPY 'Sea Ice Knowledge and Use' (SIKU) project (Krupnik et al., 2010) has produced the first detailed insight and comparative documentation of the patterns of indigenous knowledge and use of sea ice across from the Bering Strait to Greenland. Such information is of great value to hunters as well as others traveling on sea ice. Although there are also groups in the community that do not depend on hunting and/or have access to financial resources to adapt, the changing ice conditions threaten the cultural and spiritual identity as well as the quality of nutrition for all local peoples.

A prevalent reaction is a sense of dislocation as familiar conditions give way to those that are as yet not well understood, continue to change, and become more variable. Recovery from temporary environmental change may be possible for some time, as shown by the return of hunting practices and the continuation of associated knowledge and skills in some communities. Savoonga, Alaska, successfully began whale hunting again from the traditional location in the early 1970s, despite a break of nearly a century, in part because some whalers had continued to hunt in the neighboring village of Gambell (Noongwook et al., 2007). Owing to considerable interannual variability in the past, the indigenous peoples of the Arctic are highly adaptable and flexible in their practices and general

outlook (Huntington et al., 2007; Forbes and Stammer, 2009; Wenzel, 2009; Ford et al., 2010). However, adaptive efforts are currently strained by the extent and speed of recent changes in sea ice, because traditional knowledge may no longer be as relevant for understanding the environment and there is a high degree of uncertainty about what will come next.

9.4.4.2. Shipping

Current shipping in the Arctic is mostly local in nature (Chircop, 2009). Arctic marine shipping currently consists of tankers transporting natural gas from northern Norway to the United States, hundreds of cruise ships visiting Greenland and dozens visiting the Canadian Arctic each summer, while a few travel to the geographic North Pole. Adventurers are also heading north in growing numbers, some sailing small boats through the Northwest Passage in remote and incompletely charted and sometimes stormy waters (Byers, 2009). In addition to tourism and servicing offshore oil and gas installations, marine shipping also includes the larger fishing vessels, warships and other government ships operated for non-commercial purposes (Molenaar and Corell, 2009a). In the Canadian Arctic and around the east and west Greenlandic coasts most transport occurs in summer. In the Russian Arctic, year-round marine transport has been maintained since 1978/79 between the port of Dudinka on the Yenisey River and Murmansk (Molenaar and Corell, 2009a).

The Arctic sea ice has only recently retreated enough to make trans-Arctic navigation a possibility (see Section 9.4.5.1.3). Since 2000, a small but increasing number of trans-Arctic summer voyages have taken place mainly in relation to science and tourism. In September 2009 the first commercial ships navigated the Northern Sea Route. The current level of trans-Arctic shipping is moderately high through the Northern Sea Route and low through the Northwest Passage (northern Canada).

Arctic navigation is challenged by drifting icebergs, a lack of accurate charts and insufficient experience in navigating in ice-covered areas (Molenaar and Corell, 2009a). While most tankers are ice-strengthened, many tourist ships operating in the Arctic were not designed for ice-covered waters, increasing the likelihood of shipping accidents. The International Maritime Organization (IMO) has recently approved a 'Polar Code' for all ships operating in polar waters, covering ship standards, safety and reporting requirements (IMO, 2009) and this is expected to become mandatory in 2012. These guidelines form the first internationally recognized standards for the construction and operation of ships in ice-covered Arctic waters. Although international policies are being developed to support development in the Arctic (e.g., Commission of the European Communities, 2008), infrastructure (e.g., charting, communications, ports, environmental monitoring, search and rescue, salvage, aids to navigation, oil spill response, supplies and spares) is currently limited or lacking to support high levels of marine traffic.

9.4.4.3. Local and commercial fisheries

Fisheries in Arctic waters are of great economic importance, at both the national and international level, and contribute substantially to the economy of many Arctic countries, in

particular Greenland, Iceland, the Faroe Islands and Norway (Glomsrød et al., 2009). Although the economic importance of fisheries may vary widely at the regional level, it is the backbone of local economies for many northern communities.

The marginal ice zone is a nutrient-rich zone with high levels of primary production (Section 9.3) that support a range of species higher up the food chain (fish, seabirds, marine mammals). Except for Greenland halibut, polar cod, capelin, and Greenland cod, most commercial fish species are found in waters south of the Arctic Ocean (Loeng et al., 2005). The area around the Polar Front in the Barents Sea, where warm Atlantic water meets cold polar water, is one of the most productive marine areas in the world and supports a large international fishing industry (Sherman et al., 2009). The main commercial fisheries presently occur in the Barents Sea and to the east and south of the Norwegian Sea (Commission of the European Communities, 2008), although a substantial amount of commercial fishing also occurs in the Bering Sea and in Icelandic and Greenlandic waters. The area in the Bering Sea (Alaska) formerly covered by sea ice has become a favorable habitat for many subarctic species, and as a result, there has been an increase in biomass for most fish stocks in the area (Mueter and Litzow, 2008). There has also been a continued trend toward more subarctic ecosystem conditions in the northern Bering Sea, which may have profound impacts on commercial and coastal fisheries as well as on marine mammal and diving seabird populations (Grebmeier et al., 2006a). However, a recent federal vote by the North Pacific Fishery Management Council in Alaska (Stram and Evans, 2009) placed a ban on commercial fishing in its Arctic waters mostly north of the Bering Sea, stressing the need to assess how global warming is affecting the region before allowing fishing for stocks such as Arctic cod, saffron cod and snow crab.

"There's concern over unregulated fishing, there's concern about warming, there's concern about how commercial fishing might affect resources in the region, local residents and subsistence fishing and the ecosystem as a whole." Bill Wilson, a North Pacific Fishery Management Council aide, Washington Post, February 6, 2009.

Warming ocean waters and a retreating ice edge are leading to new opportunities as new species appear and existing fish stocks are showing horizontal and vertical changes in distribution as their seasonal migration is related to the formation and melting of the sea ice (Sundby and Nakken, 2008; Sherman et al., 2009; West and Hovelsrud, 2010). This has consequences for coastal fishermen in terms the need for different fishing gear, increased risk with longer trips at sea, problems with delivering the catch to landing facilities, and fishing regulations limiting adaptation to changing fisheries. Drifting sea ice and icebergs are an obvious problem for offshore fisheries, but also pose challenges to marine-based aquaculture in fjords and bays, and the booming whale-watching industry, which is attracting an ever increasing number of visitors and is supplementing fishing as source of livelihood in some coastal communities (Einarsson, 2009).

While many commercial and locally harvested fish species are sensitive to climate change, the main impacts on fisheries are of a non-climatic nature, such as shifting fisheries management and regulations, closing of landing facilities with resulting

job loss, globalization, and market integration (Keskitalo and Kulyasova, 2009; West and Hovelsrud, 2010). Other fisheries (and shipping) concerns associated with sea ice include poor infrastructure for search and rescue, especially in more northerly areas, and the lack of charts and iceberg monitoring.

9.4.4.4. **Non-renewable resources**

9.4.4.4.1. **Hydrocarbons**

Within the Arctic Circle, one-third of the area is above sea level, one-third comprises continental shelves at depths of 500 m or less, and the remainder consists of deep ocean basins historically covered by sea ice. The onshore areas account for almost 10% of the world's known conventional petroleum resources (cumulative production and remaining proved reserves) and by 2007 more than 400 oil and gas fields, containing 40 billion barrels of oil, 1136 trillion cubic feet of natural gas, and 8 billion barrels of natural gas liquids had been developed, mostly in the West Siberian Basin of Russia and on the North Slope of Alaska (Gautier et al., 2009).

Most of the Arctic however, especially offshore, is essentially unexplored with respect to hydrocarbons and it is estimated that around 84% of the undiscovered oil and gas in the Arctic occurs offshore (USGS, 2008). While deep oceanic basins have relatively low hydrocarbon potential the Arctic continental shelves are one of the world's largest remaining prospective areas. Until now, little exploration has occurred offshore. Even where offshore wells have been drilled primarily on shelf areas, in the Mackenzie Delta, the Barents Sea, the Sverdrup Basin, and offshore Alaska, most of the discoveries remain undeveloped (Gautier et al., 2009). This is mainly due to the remoteness of the area, costs and technological challenges associated with operations in ice-infested environments, and abundant relatively low-extraction-cost petroleum.

To date, Arctic hydrocarbon exploration, development and production make use of ice-islands, Gravity Base Structure (GBS) platforms in relatively shallow water or detachable floating systems. Adaptations in the Arctic offshore oil and gas industry include a clear increase in amounts of production equipment being installed on the seabed, eliminating the need for a floating platform and thus avoiding sea-ice related hazards. Significant progress has been made in design, construction, transportation, installation, and removal of offshore structures, while remaining challenges include an increase in safety and emergency response, improved infrastructure, the need to address icing problems, improved ice and iceberg data mapping, and protection of structures from icebergs and ice pressure ridges.

Challenges for oil and gas facilities in the Arctic fall into two categories: (i) overcoming the physical environment (e.g., sea ice and wave action) and (ii) meeting regulatory requirements and increasing societal expectations related to environmental performance and social benefits (Efthymiou and Winkler, 2009).

9.4.4.4.2. **Minerals**

Current practices in Arctic metal mining usually proceed through a seasonal cycle of winter extraction, concentration of ore, and storage followed by a summer export season once

shipping lanes are open. Thus, challenges and opportunities linking mining and sea ice are mainly related to increased opportunities for shipping as sea-ice changes occur.

9.4.4.5. **Tourism**

Accessibility in the Arctic has increased through improved transport technologies ranging from cruise ships and air transport to specialized vehicles to access remote areas. Polar tourism has developed substantially, both in terms of numbers and in geographical and seasonal reach (Stewart and Draper, 2006; UNEP, 2007). The sector is diverse and is aimed at the mass market. Activities include sports fishing and hunting, ecotourism, adventure tourism, and cultural and heritage tourism. Iconic Arctic species such as the polar bear draw tourists northward (e.g., Forgione and Martin, 2008) but also hold considerable 'existence' value for many people who will never visit the Arctic but enjoy knowing that Arctic species exist. Sport hunting of polar bears has become an important means of contributing to economies for certain Inuit communities, whereas in other areas polar bear hunting is allowed for subsistence use only (e.g., Hovelsrud et al., 2008). Cultural tourism is an important part of the economy in Nunavut, Greenland, and northern Scandinavia, and is currently being developed in northern Russia by the Russian Association of Indigenous People of the North, Siberia and Far East (RAIPON) (UNEP, 2007).

Tourism is an integral part of local economies, personal income, revenues and financial capital for northern infrastructure. Arctic economies and gateway cities in the Southern Hemisphere have seen tourism evolve from an incidental activity to a vital sector upon which they increasingly rely (UNEP, 2007). Challenges for tourism can be divided into three categories: technical challenges, mainly related to shipping; infrastructure, including search and rescue; and sustainability (Stewart and Draper, 2008). Ironically, the first ship to transit the Northwest Passage in 1984 was also the first cruise ship to sink in polar waters, off the coast of the Antarctic Peninsula, in 2007. The incident illustrates the importance of contingency planning for emergencies and the need for circumpolar safety and environmental regulatory mechanisms to be in place for the expected increase in tourism and shipping. In most regions of the Arctic, the number of seasonal tourists exceeds the population in rural settlements. This puts a stress on the community and its population; in many instances an annual income must be earned in only a few months. Many Arctic residents are challenged by balancing cultural and social norms with the need for a viable economy (UNEP, 2007).

9.4.5. **Anticipated consequences of sea-ice change**

Arctic sea ice is declining much faster than previously predicted by IPCC models and the Arctic Ocean is likely to be ice-free for short periods during summer within the next few decades (see Section 9.1; Stroeve et al., 2007). High interannual variability in sea-ice extent will continue, but will decrease as ice-free summers are approached. The Arctic basin is projected to be mostly ice-free in summer by mid-century or before. The winter pack ice is projected to be increasingly dominated by first-year ice (Koç et al., 2009) and there are estimates suggesting that

the Arctic may be free of multi-year ice over the next couple of decades.

The retreat, thinning and temporary absence of sea ice will have profound impacts on ice-dependent species and as yet unforeseen effects on the ecosystem. This is likely to affect people and sectors active in the Arctic alike, through new challenges and new opportunities, requiring further economic

and societal adaptation. Most of the likely losses will be through the decline and seasonal shifts in landfast sea ice with particular consequences for indigenous lifestyles and coastlines. Most of the likely benefits will be through both landfast- and pack-ice decline, with consequences for industry, shipping and fishing (re-supply, hydrocarbons etc.). Impacts and responses for human societies are summarized in Figure 9.38 and Table 9.5.




Figure 9.38. Interactive follow-on and cumulative effects of sea-ice change on humans, illustrating the direct and indirect human relationships with sea ice use (and potential changes). Large arrows of the same color as the block indicate effects from/on the whole block. Smaller arrows and dashed blocks indicate effects between components between blocks (e.g., habitat loss, ice fauna decline and contaminants have consequences for local harvest, cultural identity and health and wellbeing). This figure should be viewed in association with Table 9.5.

Table 9.5. Results, responses and rate of change of effects of sea-ice change on humans.

Type of sea-ice change	Direction of effects	Rate of change	Result	Response
Shorter duration of landfast ice	Landfast ice travel (locals)	<20 years	Personal safety and food security compromised	Changes in transport mode. New equipment needed
Poorer ice quality	Harvesting opportunities	<20 years	Personal safety and food security compromised	Changes in transport mode. New equipment needed
Melt of MYI	Release of legacy contaminants	<30 years	Personal safety and food security compromised	Change in diet
Longer/larger open-water season at the coast	Wider fetch (combined with increased storminess)	< 20 to 30 years	Coastal erosion Harbor degradation	Shoreline stabilization, resettlement Engineering options
Longer/larger areas of ice-free ocean	Increased possibilities for shipping Increased possibilities for non-renewable resource exploitation Changes in species composition	30 to 50 years	More traffic More tourism More disturbance Better re-supply More jobs (?) Ballast/Pollution More accidents Changes in fishing opportunities	Improved: mapping; infrastructure; harbors; search and rescue; emergency, prevention, preparedness and response; training Coordination of tourism International legal agreements

9.4.5.1. Challenges and opportunities

9.4.5.1.1. Travel, safety and food security

Observations indicate that sea-ice conditions are changing in such a way that the value of traditional knowledge is decreasing. The changing sea-ice conditions are increasing risk of travelling on and between sea-ice floes. For example, hunters must travel increasing distances to access the animal populations they are hunting (Ford et al., 2007; Hovelsrud et al., 2008) and a reduction in landfast ice in the western Canadian Arctic combined with more open water has resulted in unpredictable fog events, making coastal travel treacherous and communication between communities more difficult (Barber et al., 2008b).

An increase in human activities such as fisheries, tourism, and industrial development will be followed by an increased demand for seasonal icebreaking of harbors and shipping routes. Feedback effects on the environment through increased shipping and industrial activities (pollution, habitat fragmentation by icebreakers, noise) represent a major challenge for local communities (Koivurova and Hossain, 2008). Regulation will be needed to avoid disturbing hunting activities and destroying travel routes over the sea ice. At the local level, less sea ice may lead to increased transportation by boat, which may lead to higher fuel costs, straining the household economy. Changing sea-ice conditions and increasing concern about hunter safety create the need for costly new technology (GPS, satellite phone). Increased use of technology may further erode the utility and transfer of traditional knowledge, with major social and cultural implications (Ford et al., 2010; Pearce et al., 2010).

The projected changes in sea-ice distribution and extent and the formation of polynyas will affect the distribution and ranges of many species, directly through habitat change and indirectly through changes in predator-prey relationships. Such changes will have consequences for local communities dependent on a mixed cash-subsistence economy. The trend of shorter seasonal duration of landfast ice and poorer ice quality is expected to continue. While there is great uncertainty about the type and rate of changes, it is likely that hunting and travelling activities will be increasingly affected, compromising personal safety, food security, and culture.

Changes in the availability of traditional/local foods and in food security may have negative impacts on well-being, physical and mental health, family and network relations, and the social and cultural fabric and identity, and may increase lifestyle diseases such as diabetes and obesity (e.g., Ford and Berrang-Ford, 2009). Female community members have been identified as being at particularly high risk of food insecurity (Beaumier and Ford, 2010). However, changes in sea ice could also improve access to resources such as fish, and combined with more rapid technological development this may positively affect harvesting activities and income. Nevertheless, and despite the uncertainties in future projections, the changes in sea ice are likely to require adaptation strategies that go beyond those that are currently taking place. The projected increasing sea-ice variability and the decreasing predictability of conditions, combined with social, economic and political drivers of change may increase vulnerability of local communities and peoples.

The decline in sea ice may result in rapid changes in Arctic weather, and severe weather events are projected to become more prevalent in future (Kolstad and Bracegirdle, 2008). Strong wind events can have major effects on coastal sea ice and may create open-water areas that affect travel and subsistence activities on the ice. It can also lead to open water and the formation of low clouds and fog which, when formed during autumn and early winter, can result in freezing drizzle and significant icing on aircraft and vessels (Hanesiak et al., 2010). The North-East Atlantic is particularly prone to marine cold-air outbreaks (MCAOs). As sea-ice retreats, the highest frequency of MCAOs will also retreat northward, resulting in a decrease in the strength of MCAOs along the densely populated coastlines of Norway, Iceland, the British Isles and northern Europe in general. Initially, traditional sea-ice use and commercial activities in the Arctic (fisheries, oil and gas industry, shipping) will be more exposed to storms and icing, but over the long-term this type of weather will move northward following the retreat of the sea ice (Kolstad and Bracegirdle, 2008).

9.4.5.1.2. Fisheries

Although global aggregated marine primary production is not expected to change substantially over the next four or five decades, there is a stronger basis for projecting changes in primary production at the regional level. This is supported by observational evidence, particularly for the North Pacific and North Atlantic, but also for the Bering Sea; a general northward shift in species is expected with increased biomass production in Arctic waters and associated declines in fish species with more southerly distributions (Sherman et al., 2009; WMO, 2009). However, species are limited in how far north their range distributions can shift, and there is potential for the extirpation, and even extinction of some species (Loeng et al., 2005). A northward shift in lower trophic-level species will impact higher trophic-level species, and ultimately humans, while species in the marginal ice zone may benefit from earlier ice break-up (Anisimov et al., 2007). The impacts of changes in sea ice on future Arctic productivity cannot be considered in isolation from the other changes taking place in the region. Ecosystem responses will vary regionally, depending on oceanic and climatic forcing, and require consideration of many rate and yield-limiting processes.

Qualitative changes in species composition as a result of northward migration may lead to increased fish stocks regardless of changes in sea-ice related primary production. Together with wind-induced flux of warm Atlantic water into the region, changes in stratification, light penetration, salinity, pH and oxygen in the upper water masses, will act directly on the abundance, distribution and composition of key commercial fish species and plankton species in the Arctic (Stenevik and Sundby, 2007; Brander, 2010). New species moving into the Arctic could lead to competition with indigenous species, new predators, diseases and parasites (Furgal and Prowse, 2008).

The implications of change may differ for coastal and industrial fisheries. Sea-ice retreat will increase the area of open water and this may have implications for food security through a decline in ice-associated coastal fishing, such as Greenland halibut long-lining on the frozen fjords (Côté and Williams, 2008). Less sea ice may also lead to greater fetch and

storminess, resulting in greater risk for coastal fishermen at sea and economic losses for those staying on shore (West and Hovelsrud, 2010). On the other hand, a decline in sea ice may generate new possibilities for coastal fishing from small boats and a larger seasonal window for fishing, but this will come at the cost of new investments. A shift in the freshwater budget is likely to result in Greenland halibut moving from deep waters to shelf areas, requiring changes to the fishery (Loeng et al., 2005).

For industrial fisheries, a decline in sea-ice dependent fish species but an overall increase in pelagic productivity in the coastal seas and improved access to the Arctic Ocean could mean a substantial net benefit over the long-term. This is dependent on which fish species flourish under the new conditions and how management regimes and policies respond (e.g., Molenaar and Corell, 2009b; Sherman et al., 2009). Anisimov et al. (2007) suggested that increased productivity in the marginal ice zone is likely to benefit many commercially important species. Biomass is likely to increase for key commercial species in the Barents Sea (e.g., Atlantic cod and herring) and these species are likely to shift their centers of summer distribution eastward in response to sea-ice loss, thus increasing their availability to Russian fishing fleets. There is also the potential for an eastward colonization of new spawning areas, and this may forecast a wider geographical distribution for these species (Stenevik and Sundby, 2007). With increased importance of the Norwegian and Russian sectors of the Barents Sea, it is likely that fishing rights, cooperative management plans and catch limits will need to be renegotiated.

While the opening of new areas earlier in the season may offer new opportunities, changes in the sea-ice regime may also pose challenges to coastal fisheries in terms of drifting ice and icebergs. Other concerns relate to access to and sustainability of species including Greenland cod (particularly in Greenland), Pacific salmon (western North American Arctic), deep-water shrimp (Greenland), and pollock (Bering Sea). Fish stock abundance is the result of a combination of human and environmental factors. As it is difficult to predict many of the consequences of sea-ice change on commercial stocks, the implications for fisheries are extremely uncertain (Mueter and Litzow, 2008).

9.4.5.1.3. Shipping

The decline in sea ice will progressively open longer seasonal windows for navigation through Arctic waters, increasing the opportunity for trans-polar commercial shipping and considerably shortening the route between Europe and the Pacific (Figure 9.39). Climate models project that the loss of summer sea ice will extend the navigation season in the Northern Sea Route from three to six months and from two to four months for the Northwest Passage by the end of the 21st century according to the IPCC A1B emissions scenario. Through the 21st century, models indicate a steady increase in the Northern Sea Route navigation length of about 4.5 (± 1.3) and 3.6 (± 1.7) months averaged over the 'best' and all models, respectively. This suggests that transit via the Northern Sea Route from Western Europe to the Far East may be up to 15% more profitable in comparison to Suez Canal transit by the end of the 21st century (Khon et al., 2010). Such an increase in navigation season length and the increased potential for Arctic shipping will potentially save billions of dollars a year (Borgerson, 2008). Ships will reduce travel distance by 40% (compared to current shipping routes) by using the Northern Sea Route, and it is expected that the transit transport from Russia will increase. This could save energy, reduce emissions, promote trade, diminish pressure on the main trans-continental navigation channels and have great economic benefit (Commission of the European Communities, 2008).

Sea-ice decline recently made it possible for two merchant ships to pass through the Northern Sea Route, albeit with icebreaker support (Barents Observer, September 2009). The predicted volume of transport through the Northern Sea Route, primarily associated with transporting natural resources, gas and oil, may increase to 5.5 million tonnes in 2010, and to 12.8 million tonnes by 2020 (Ho, 2010).

While less ice in the Arctic Ocean will increase the potential for naval and maritime operations, several obstacles remain, including seasonal drift ice and icebergs, annual variations in ice cover in the central Arctic Ocean, and local sea-ice formation along sea routes. However, this increased potential must be seen




Figure 9.39. Northern Sea Route and the Northwest Passage compared with currently used shipping routes.

within the context of factors such as global demand and prices for natural resources, changes in ship design and technology, a growing world economy, and the size of vessels compared with the capacity of the Panama or the Suez canals, as well as the increasing emphasis on shipping due to diminishing numbers of ice roads (Mathias et al., 2008). Although the sea routes along the Siberian coast may open earlier, the depth of water along the coast may limit the size and freight capacity of the ships (Johannessen and Pettersson, 2008). The East Greenland Current, the main current leaving the Arctic, will continue to transport sea ice long distances southward along the coast of Greenland and through Icelandic waters (Jakobsson, 2003). In the United States, the Coast Guard polar icebreakers are aging and need replacing, and the country has limited capacity and ability to expand and operate in the Arctic environment (US National Ice Center and US Arctic Research Commission, 2007). Other challenges include a lack of infrastructure, environmental risks, and uncertainties about future trade patterns. Ships will need to deal with an increase in storm surges, wave heights and wind direction, resulting in icing on equipment, hull, propulsion systems and appendages (Molenaar and Corell, 2009a). As a result, there is a higher risk of shipping incidents. Arctic marine shipping may also cause adverse impacts on the marine environment through accidental discharges of polluting substances, operational discharges and emissions, navigation impacts on marine species, the introduction of non-indigenous organisms through ballast-water release or attached to vessel hulls, and icebreaking (e.g., physical habitat effects) (Molenaar and Corell, 2009a). Due to the remoteness of the area, the response time will be relatively long once shipping incidents do occur and may be inadequate to address impacts to the marine environment and marine biodiversity.

Risk-assessments and the marine insurance industry are likely to be crucial factors in the economic viability of Arctic marine shipping (VanDerZwaag and Chircop, 2008; Molenaar and Corell, 2009a). In particular, the following issues need to be resolved (Ho, 2010):

- Environmental monitoring and forecasting services providing meteorological, oceanographic and sea-ice information to support shipping all year round will need to be significantly enhanced.
- Search and rescue as well as icebreaker support services, with increased seasonal and regional access, will need to be provided in a comprehensive manner.
- Experienced mariners trained for Arctic operations and accurate hydrological charts are needed to operate the ships.
- New ship technology is required for independent ship operations in ice-covered waters, which will remain present for most of the year.
- When traffic gets heavier, it may be necessary to implement vessel traffic systems along narrow straits that may end up as choke points, such as the Barents Strait.
- An integrated governance and regulatory framework is needed based on the United Nations Convention on the Law of the Sea (UNCLOS).

Different solutions have been investigated for building safe and

cost-efficient transport chains. One solution is to use dedicated ice-strengthened vessels for the ice-covered part of the route and to apply ship-to-ship transfer in open water (e.g., for commodities such as liquefied natural gas). Policy objectives include the development of infrastructure (on land, for air support, and for dredging of Arctic ports), use of satellite navigation systems for improved maritime surveillance, and promotion of full implementation of existing obligations concerning navigational rules, maritime safety, route networks, and environmental standards in the Arctic, in particular those drawn up by the IMO. The potential to provide specially-designed, environment-friendly ships, including icebreakers, is an important asset for the future (Commission of the European Communities, 2008).

Although the Arctic may be navigable before 2050, and routes along the coast of Siberia even earlier, routine ocean-to-ocean commercial navigation is not expected to develop significantly for quite some time (US National Ice Center and US Arctic Research Commission, 2007). More investment is required in infrastructure and the provisioning of marine services to ensure safe and secure ship transit with minimal environmental impact (Ho, 2010). For the near future, Arctic shipping is expected to take place largely between points within the Arctic rather than ocean-to-ocean transit, and commercial maritime activity in the Arctic will probably be driven more by economics, dominated by the development of natural resources and tourism, than by declining sea ice. High prices for hydrocarbons will be an important driver of shipping activities, because of the cost-benefits of shorter trans-Arctic shipping routes and the expected exploration and exploitation of hydrocarbon resources in the Arctic marine area. Increased tourism to see 'iconic species' before they become extinct may also drive an increase in Arctic traffic. As the Arctic sea ice thins, the difference between Arctic residents' view of change and the shipping industry's view of opportunity may become more pronounced. Future expansion of Arctic marine shipping is likely to attract diverse stakeholders with different interests in the Arctic, from countries outside the eight Arctic nations, and rules of engagement with northern peoples will need to be renegotiated. Trans-Arctic marine shipping is expected to be an important driver of this development (Commission of the European Communities, 2008; Molenaar and Corell, 2009a).

9.4.5.1.4. Non-renewable resources

The United States Geological Survey (USGS, 2008) concluded that about 30% of the world's undiscovered gas and 13% of the world's undiscovered oil may be found north of the Arctic Circle (1669 trillion cubic feet, 90 billion barrels of oil, 44 billion barrels of natural gas liquids), mostly offshore under less than 500 m of water. Undiscovered natural gas is three times more abundant than oil in the Arctic and is largely concentrated in Russia. The study included only those resources believed to be recoverable using existing technology, but with the important assumptions for offshore areas that the resources would be recoverable even in the presence of permanent sea ice and oceanic water-depth. More than 70% of the mean undiscovered oil resources are estimated to occur in five provinces: Alaska (the largest with 31%), Amerasia Basin, East Greenland Rift Basins, East Barents Basins, and West Greenland / East Canada. More than 70% of the undiscovered natural gas is estimated to occur in three provinces: the West

Siberian Basin, the East Barents Basins, and Alaska. However, these first estimates are, in many cases, based on very scant geological information, and understanding of Arctic resources will certainly change as more data become available (Gautier et al., 2009).

A loss of sea-ice cover will affect offshore exploration drilling in several ways. Key challenges for the future include (AMAP, 2007; Efthymiou and Winkler, 2009; Seidlitz, 2009):

- Combination of water depth beyond the feasible range of GBS platforms and moderate to heavy ice conditions
- Combination of sea ice and icebergs
- Potential for increased wave action and storm surges
- Narrow weather and seasonal window for exploration and development
- High costs (although variable between regions and onshore and offshore structures generally much higher than equivalent southern developments) due to improving design, infrastructure, logistics and transportation, waste management, labor productivity, etc.
- Hard, rock-strewn seafloors
- Emergency response (spills, safety and rescue)
- Winterization of facilities including design for fire and blast footprint reduction.

Arctic hydrocarbon development is viewed by the industry as an opportunity to develop new technology to improve efficiency and reduce costs. Advances have already been made in current focus areas of Arctic subsea processing, compression and power transmission, drilling and pumping technologies, and communication technology. Other focus areas are ice-load and ice-scour prediction, offshore Arctic drilling systems, Arctic tanker technology and emergency, evacuation and spill response systems and technology, and cost effective logistics. Although subsea production has potential, given the right reservoir conditions and sufficient open-water season for drilling, inspection, maintenance and repair operations, challenges remain. These include flow assurance, protection from deep-keeled ice pressure ridges and icebergs, and inaccessibility during the ice-bound season.

Hydrocarbon discoveries will change the economic landscape and way of life of local inhabitants. Addressing the regulatory and stakeholder issues, including the study of impacts on environment and local communities, should be a key focus area for industry, communities, and government (Seidlitz, 2009). Local public resistance to the locations of large-scale, obtrusive facilities, such as oil refineries and GTL (gas to liquids) plants, is an issue to be resolved (IEA/OECD, 2009), although pragmatism is illustrated by the quotes below:

“Climate change will be very beneficial to society [in Greenland]. It will improve fishing and above all make it easier to drill for oil and gas. The US Geological Survey calculates that the greatest unused oil reserves on Earth are in the Greenland waters – and they are in the east, where the ice is melting fastest.” Jesper Madsen, DMU environmental research institute in Roskilde, Denmark, in The Times, May 7, 2008.

“The agenda is the agenda of the oil companies, we cannot stop the development but we want a part of the benefits and want to play a role in resources development.” comment of Geir Tommy Pedersen, head of the Sami Council, to AFP on the sidelines of the Arctic Frontier Conference in Tromsø, Norway, January 2008.

Impacts of oil and gas development on people, communities and governments can be both positive and negative (AMAP, 2007). They could drive social and economic change, create employment opportunities and revenues, impact households as workers may be away for long periods, and many of the jobs will be filled with employees from outside the region. Impacts on the environment and traditional practices are very likely to be disruptive. In many countries, attempts to counteract harmful effects on the environment have resulted in the development of environmental regulations and restrictions for where drilling may occur. In the United States, for example, drilling has not been allowed on offshore coastal zones for many years. Environmental catastrophes in ice-infested environments (e.g., shipping spill, oil well blow-outs) are not likely to be contained within the same season in which they occur, but will require remedial action at least into the following season. Low temperatures may further exacerbate the clean-up because the material (especially heavier crude oil) congeals rather than breaks down. While the oil and gas industry in general does not consider the consequences of climate change as a major concern, the local installations are sensitive to the expected increase in storm surges, increasing wave heights, change in wind direction, and rising sea level, which will have consequences for icing on equipment and installations and for environmental safety (West and Hovelsrud, 2008).

Although oil and gas activity in the Arctic is projected to increase (AMAP, 2007), risk of oil spills, spills remediation costs, and the likelihood of further changes in environmental regulations discourage investment in Arctic oil facilities. Development will depend on market conditions, technological innovation, the sizes of undiscovered accumulations, and regulatory issues such as the US presidential decision (May 2010) to extend the moratorium on new offshore hydrocarbon developments as a result of the Gulf of Mexico incident. In combination with the Arctic weather conditions and enormous investments in infrastructure needed to develop new fields in the Arctic region, exploitation for oil or gas in these areas is unlikely to start much before 2020 (IEA/OECD, 2009). The estimated oil resources therefore, if found, would not come into production at once but would be added to reserves and produced incrementally over decades (Gautier et al., 2009). This is also reflected in recent model projections (Lindholt and Glomsrød, 2009) for various Arctic regions, which indicate that although global gas production will increase in most regions outside the Arctic up to 2030, the Arctic share of global gas production will actually decline from around 21% in 2008 to around 9% in 2030. Projections for oil likewise indicate that the Arctic share of global oil production will drop from about 10% to roughly 7% in 2030. Until 2030, the vast majority of Arctic oil and gas will be Russian, 81% and 94% respectively, while around 14% of the oil will come from Alaska.

9.4.5.1.5. Tourism

Although facilitated by improved accessibility, Arctic tourism is likely to increase independently of sea-ice change. Latent demand and the tendency for cruise visitors to make return visits form the basis of the predicted moderate increase in cruise tourism (Stewart and Draper, 2006). On the other hand, cruise ship tourism worldwide is developing rapidly, and loss of sea ice may open up waterways and possibilities for increased cruise traffic (Glomsrød et al., 2009). However, several recent accidents have shown that sea ice, as well as response time in the case of accidents, remains a hazard (Stewart and Draper, 2008). To counteract the hazards, icebreakers are used to assist cruise ships that are not ice-strengthened. The increasing volume of icebreaker and cruise traffic is of local concern. Similar to Arctic shipping, accidents and lack of search and rescue infrastructure are key issues. In addition, other types of life-saving technologies used in the North are being questioned, such as how long a basic lifeboat can permit survival in ice-filled Arctic waters.

“And if it can’t [permit survival in ice-filled Arctic waters], why are we letting all the cruise ships go up north with lifeboats on them?” Mary Williams, director general of the National Research Council of Canada’s Institute for Ocean Technology, CBC news, June 5th, 2008.

Loss of Arctic sea ice will affect wildlife habitat, and the numbers and migratory behavior of wildlife species. To minimize further impact, careful consideration of extended seasons, cruise tourism transport schedules, and fisheries conditions are of critical importance to ensure the cultural and economic well-being of Arctic people (UNEP, 2007). In addition, there are environmental, economic, social and cultural impacts ranging from wildlife disturbances (e.g., noise, habitat change) to garbage, waste and pollution problems that need to be regulated. While the potential economic benefits from tourism increases for local communities, such an increase may also negatively affect those communities. For example, ice-dependent polar bear populations will, with reduced sea-ice, have increasingly smaller habitats and with more people in the area human-bear interactions will increase. Given international pressure for sustainable management of remaining populations, indigenous communities depending on hunting polar bears (for tourism or subsistence) may have to adopt alternative livelihoods (Hovelsrud et al., 2008). Further sea-ice melt and expansion of tourist seasons may result in extended use of infrastructure and longer duration of employment and income benefits. How Arctic communities allow their natural and cultural resources to be used by large numbers of visitors and whether or not this is viewed as a disruption, depends on the attitude and resources of the community. Impacts may be mitigated through collaborative management with tour operators and in some instances, tax revenues and special fees may offset local costs.

Although there are many protected areas on land in the Arctic, there are few if any marine protected areas (UNEP/GRID-Arendal, 2007). Opening up of waterways and further development of Arctic tourism should therefore take place in a sustainable manner. An EU policy brief (Commission of the European Communities, 2008) proposed the promotion

of sustainable Arctic tourism through three main policy objectives: protecting and preserving the Arctic in unison with its population, promoting sustainable use of resources, and contributing to enhanced Arctic multilateral governance. Two main considerations pertain to both protection of the environment and ensuring benefits to local coastal communities. Concrete actions include support that increases cruise ship safety, improves guiding, restricts access to highly vulnerable areas, and encourages environmentally friendly tourism, involving local communities. This corresponds well with the proposed principles and a ‘code of conduct’ for tourists and tour operators (UNEP/UNWTO, 2005), stipulating guidelines for ensuring good management, income for communities, and protection of culture and environment, which are of key importance in an increasingly accessible Arctic.

9.4.5.2. Overarching issues

9.4.5.2.1. Coastal change and infrastructure

Sea ice can both prevent and cause erosion of coast and infrastructure, and plays an important role as a regulating element in coastal sediment dynamics. Sea ice protects the coast from the erosive action of storms (Atkinson, 2005) and preserves the thermal state of subsea permafrost (Solomon et al., 2008). ACIA (2005) reported that coastal erosion rates along the Arctic coast have increased over the past 30 years. Low-lying coastal plains, which are not tectonically active, are especially vulnerable to coastal erosion. Although rocky (lithified) coasts predominate in the European and western Russian Arctic and in parts of the Canadian Arctic Archipelago, human settlements are often associated with unlithified sectors of the coast because these provide more suitable locations for human activities. Rapid erosion is typically associated with unlithified, frozen sections of the Arctic shoreline, and projections of sea-ice decline and progressively longer open water seasons imply increasing exposure of Arctic coasts to erosion. Coastal erosion rates vary considerably between and within regions and over time, and erosion presents a significant problem for communities, infrastructure of various types, cultural heritage sites, and in some cases protective coastal landforms.

The complex interactions between declining sea ice and other consequences of climate change (rising sea level, shifting river discharges, run-off, altered sedimentation rates in coastal areas, permafrost degradation) will increasingly affect Arctic coasts, coastal infrastructure and coastal marine ecosystems, and potentially human resource use (Martin et al., 2009; see also Chapter 5). Major forcing parameters are waves, currents and water levels, and, especially for the Arctic, sea surface temperature, salinity, decreasing sea ice and increasing open-water fetch, ground temperatures, and excess ground-ice content. With sea ice forming later in the season, the coast is more exposed to a projected increased number of autumn storms, and to storms with longer fetch. The subsequent coastal erosion may threaten some Arctic communities (Forbes et al., 2008; Perovich and Richter-Menge, 2009). Even a small increase in the intensity of storms and coastal surges is likely to increase infrastructure damage and costs substantially (Stern et al., 2006). Recent time-lapse photography of crumbling Alaskan coastlines shows the combined eroding action of declining sea ice, warming ocean waters, and wave action (Livescience, 2009).

The erosion rates from these forces are greater than anything seen along the world's coastlines, resulting in the coast between Alaska's Point Barrow and Prudhoe Bay eroding by several tens of meters per year.

In addition, a decrease in landfast ice increasingly exposes coastal permafrost to wave action and increased temperatures, leading to thaw (see also Chapter 5). This can have serious consequences for existing infrastructure (e.g., structures or buildings depending on ice-bonded surface for strength could be at risk over the decadal time scale). Although new coastal permafrost may form when sea ice freezes to newly aggraded sediments, it is likely that this permafrost will be unstable because of increased temperatures of the seabed. Rising ground temperatures will increase seasonal thaw depth and enhance coastal erosion processes. Thermal niche development and ice-wedge thaw can promote rapid failure of low coastal bluffs even in the absence of significant wave action (Hoque and Pollard, 2009).

Other hazards involve ice ride-up, ice pile-up and the formation of nearshore pressure ridges, primarily as a result of wind action, which may provide a mechanism for nearshore scour and landward sediment transport (Reimnitz et al., 1990). Ice ride-up has been reported extending more than 100 m inland (Taylor, 1978; Kovacs and Sodhi, 1980); Ogorodov (2005) cited a case of at least 150 m and suggested evidence for much more. While the effects are often superficial (Kovacs and Sodhi, 1980; Kovacs, 1983), they include an example of damaging ride-up of 0.4 m of ice that knocked a lighthouse off its foundation and destroyed standing infrastructure on fishing harbor wharves (Forbes et al., 2004). Ice pile-up in extreme events has been reported as high as 36 m (Sverdrup et al., 1904) and 50 m (Zubov, 1945). Pile-up typically occurs rapidly (~30 minutes), has been known to cause fatalities, and can cause significant damage, impinging on waterfront residences, breakwaters, navigation infrastructure, coastal roads, and even overtopping dunes (Forbes et al., 2004).

Because of the highly episodic and rare occurrence of damaging ice motion, such as ice ride-up and pile-up, little effort has been devoted to mitigate and forecast such hazards (Druckemiller et al., 2009), and many communities where damage has occurred may not have anticipated the event before it happened. Current community responses to increasing ice-free fetch, longer open-water seasons, and increasing impacts from erosion run the gamut from protection (e.g., dynamic beach nourishment) to retreat. The situation in some communities is sufficiently dire that they are considering immediate relocation (e.g., Shishmaref: www.shishmarefrelocation.com). In other cases (e.g., Tuktoyaktuk, Northwest Territories, Canada, see Figure 9.40) phased retreat to a new location is an option which is now being considered (Johnson et al., 2003). While engineering solutions are available for shore protection, these measures may address one problem but create another by altering the dynamics of erosion and deposition processes (ACIA, 2005).

Some coastal landforms (e.g., spits and barrier islands) are highly sensitive to the balance between sediment supply and loss, such that rapid change can occur once a threshold is exceeded. Some barrier islands on the Alaskan Beaufort coast have diminished in surface area since 1955 and recent (1990–2007) migration rates of 24 m/y greatly exceed earlier



Figure 9.40. Beach erosion at Ukkuqsi, Barrow Alaska (upper). Photo courtesy of Anne Jensen. Erosion at Tuktoyaktuk, Northwest Territories, Canada (middle). The shore has eroded as much as 200 m in 55 years in some locations. Concrete and rock revetments now protect parts of the outer coast (lower), but erosion continues at the unprotected locations. Erosion of the uninhabited and unprotected island at the harbor mouth will threaten the long-term viability of the harbor within the next 50 years. Middle and lower photos: Martin Fortier/ArcticNet.

(1955–1990) rates of 5 m/y (Ravens and Lee, 2009). Longer open-water duration and increased occurrence of large waves (longer fetch), perhaps in combination with negative effects from permafrost degradation, may contribute to this coastal erosion (Martin et al., 2009).

Projected changes in climate and consequent oceanographic forcing include continued sea-level rise, decreased sea-ice extent and duration, and increased air and sea surface temperatures. Reduced length of the winter ice season (in areas with only seasonal sea ice) will limit the window for ice motion onshore, while increasing shore exposure to storm waves. In High Arctic regions, the progressive loss of multi-year ice will reduce the probability of thick ice pile-up, but overall thinning of seasonal ice may increase the frequency of ice movement onshore. Increased fetch may also expose coastlines to ocean swell – a condition to which many Arctic coasts have had limited exposure and which could alter shoreline processes. Although some recent studies (e.g., Jones et al., 2008) present erosion rate

measurements based on historical and modern observations covering the past 175 years, allowing detection of loss of both cultural and historical sites and modern infrastructure, those types of detailed analyses are still lacking for most of the Arctic coast. At present there are no predictive models that can be used to quantify projections of increased rates of coastal erosion, and although there are likely to be physical limits to the rate at which erosion products can be removed from the shore face, which will put an upper limit on erosion rates, sea-ice decline in combination with climate-change driven changes is likely act to increase the risk associated with coastal erosion.

9.4.5.2.2. Contaminants and human health

The Arctic serves as a major heat sink for the Northern Hemisphere, and wind and water deposited contaminants can be stored in sediments and sea ice (both multi-year legacy contaminants and depositions in younger ice). The relationship between sea-ice change and contaminants is difficult to ascertain, but an increase of contaminants in the Arctic is possible both through direct and indirect effects of melting sea ice. Melting of sea ice will result in a release of contaminants from ice and frozen sediments and possibly lead to their incorporation into food webs. Increasing rates of coastal erosion will increase input of contaminants sequestered there (e.g., mercury – Outridge et al., 2008). Using DDT and PCBs (polychlorinated biphenyls) as an example, it appears that melting sea ice will add little to the contaminant load of the Arctic Ocean (NCP, 2003; AMAP, 2009).

Conversely, a reduction in sea ice is likely to lead to increased transport of contaminants into the Arctic following a variety of pathways. A projected increase in precipitation due to an extended ice-free area in the Arctic Ocean will probably lead to increased transport of airborne contaminants such as PCBs, toxaphene and HCH (hexachlorocyclohexane) to seawater, freshwater systems and terrestrial environments (McMichael et al., 2003; AMAP, 2009). On the other hand, HCH might be removed faster than it accumulates through evaporation (Macdonald et al., 2005) and increased microbial activity in warmer water can reduce the half-life of HCH (Harner et al., 2000). An increased demand for oil and gas worldwide combined with increased access to Arctic resources is likely to increase transportation and resource development dramatically over the next 20 years, and will lead to an increased potential for spills, the appearance of invasive species via migration or originating from vessel ballast water, and of contaminant movement into the Arctic (Berner et al., 2005; Occhipinti-Ambrogi, 2007; AMAP, 2009).

Contaminant exposure in human populations is harder to predict. Côté and Williams (2008) highlighted the increased amount ('load') of chemicals from oil development in Arctic Canada that could increase the load of chemicals carried by ocean currents and accumulated in the fat of animals consumed by people. Concerns about organochlorine compounds and heavy metals in traditional/local foods are significant among Arctic peoples. The lack of infrastructure, the cold conditions and the potential for freezing of contaminants can complicate clean-up actions and are a risk to the environment. However, while oil, drilling fluids and drill cuttings can contain mercury, cadmium and lead in varying amounts and occasionally some persistent

organic pollutants (POPs) and radionuclides, quantities are very small and most wastes in modern operations are now 'contained' (e.g., through the use of on-site tanks, holding ponds, down-hole dumping) (AMAP, 2009). Past oil and gas activities in parts of Arctic Russia may have led to some health impacts; however, peer reviewed documentation is unavailable (AMAP, 2009). While human health can suffer from pollution and social disruption, the revenues of oil and gas activity can improve overall health care and well-being (AMAP, 2007, 2009).

Potentially increasing levels of contaminants in marine mammals and other Arctic species can also contaminate food webs relied upon by Arctic peoples (DFO, 2006). This can impact Arctic peoples' diets through biomagnification which has already resulted in an estimated ten-fold higher intake by Arctic residents of toxins in food (Berner et al., 2005). In addition, higher temperatures may allow certain disease vectors and microorganisms to survive longer over the winter causing changes in wildlife health, a concern where traditional/local foods are consumed (Berner et al., 2005). However, the location, population size and availability of marine food species will change as temperatures rise and sea ice retreats, and the structure of the food web might also change as a result of invasive species (AMAP, 2009). These changes could increase or decrease human exposure depending on the concentrations of lipophilic compounds in food species and the extent to which different food species are consumed. Such issues may also affect marine mammal health, reproduction and populations, and thus also the diet of Arctic people. The cultural services of typically used resources may be lost, and to replace cultural associations with the practice of harvests and the sharing of foods is likely to be more difficult than to replace the actual nutrients of the foods themselves (Hovelsrud et al., 2008).

9.4.5.2.3. Search and rescue, environmental stewardship

Declining sea ice will improve marine access to the Arctic, increasing the length of the summer navigation season, and allowing more offshore oil and gas activity and commercial fisheries. All have economic consequences for the region and beyond as well as potential environmental impacts on the marine ecosystem and fisheries that may affect Arctic communities. These changes will combine with an increase in accidents, risk of oil/fuel/cargo spills (see Table 9.6 for an overview of accidents between 1995 and 2004), disturbance to wildlife, chronic habitat degradation through noise, bottom disturbance, pollution, and destabilization of 'fast ice' associated with marine traffic (Furgal and Prowse, 2008; AMAP, 2009). Increased human activity in general creates a risk of synergistic and cumulative effects, leading to more rapid impacts and potentially to reaching critical thresholds sooner, leaving less time for effective conservation action (Huntington et al., 2007).

Between 1995 and 2004, the majority of accidents in Arctic waters concerned fishing vessels and bulk or cargo vessels (77% and 19% respectively), and occurred mostly in the Bering and Barents seas (Table 9.6). The retreat of sea ice and subsequent increase in activity is also expected to lead to an increase in environmental accidents, with oil spills the greatest threat (AMAP, 2007). Oil tankers entail particular risks, since Arctic ecosystems are exceedingly fragile, oil degrades and dissipates

Table 9.6. Number of accidents and incidents in the circumpolar north during the period 1995 to 2004 as well as the type of vessel involved in the accident. Source: Accident Incident database <http://arcticdata.is>, accessed 18 February 2010.

Area / Type of vessel	Vessels lost	Fatalities	Fuel spill	Ice damage
Arctic Archipelago				
Bulk carrier / Cargo ship	0	0	1	8
Government vessel / Tug / Barge	0	0	0	2
Total	0	0	1	10
Arctic Ocean				
Government vessel	0	0	0	1
Baffin Bay/Davis Strait				
Bulk carrier / Cargo ship	0	0	0	4
Tanker	0	0	0	2
Fishing vessel	0	0	0	2
Passenger ship	0	0	0	1
Total	0	0	0	9
Barents Sea				
Fishing vessel	2	12	1	0
Bulk carrier / Cargo ship	0	0	2	0
Total	2	12	3	0
East Bering Sea				
Fishing vessel	3	22	6	0
Bulk carrier / Cargo ship	2	8	4	1
Passenger ship	0	0	1	0
Total	5	30	11	1
Hudson Bay				
Bulk carrier / Cargo ship	1	4	0	3
Oil/Gas service & supply / Tanker	0	0	2	1
Total	1	4	2	4
Norwegian Sea				
Fishing vessel	0	0	2	0
Cargo / Passenger ship	0	0	2	0
Tanker	0	0	1	0
Total	0	0	5	0
West Bering Sea				
Fishing vessel	3	21	0	0
Other				
Cargo / Container ship	1	2	1	0
Fishing vessel	1	1	0	3
Government vessel	0	0	0	1
Tug / Barge	1	3	1	0
Total	3	6	2	4
Grand total	14	73	24	28

very slowly at low temperatures, and long distances would render clean-up efforts expensive and time-consuming (Barber et al., 2008b; Byers, 2009; Figure 9.41).

A Global Maritime Distress and Safety System currently exists, and a Search and Rescue (SAR) convention has been in place since 1979, encouraging states to establish SAR regions, the pooling of facilities, establishment of common procedures, and training and liaison visits (Jensen, 2008). International regulation of vessel-source pollution is primarily organized by the IMO. Canada and the Russian Federation rely in addition on Article 234 of UNCLOS – entitled ‘Ice-covered Areas’ – for prescribing standards that are more stringent than generally accepted international rules and standards (Molenaar and Corell, 2009a). The Arctic states have also adopted several relevant bilateral and regional instruments on monitoring, contingency planning and preparedness for pollution incidents (e.g., The Protocol on Preparedness, Response and Co-operation to pollution Incidents by Hazardous and Noxious Substances, 2000); although not all Arctic states are parties to every agreement. The relevant IMO instruments primarily have a global scope of application and therefore apply to the entire Arctic marine area. The only IMO instrument that is specifically tailored to the Arctic is the non-legally binding (and currently under revision) IMO Arctic Shipping Guidelines (Molenaar and Corell, 2009a).

With the exception of northern Norway and regions in northwestern Russia (Hoel, 2009; Denisov and Mikhaylichenko, 2009), most Arctic marine areas are still missing modern navigation charts, port services, communications, salvage, SAR capability, adequate emergency prevention, preparedness and response and environmental response, and comprehensive weather and sea-ice information. The provision of salvage in Arctic waters will encounter difficulties due to remoteness, harsh climatic conditions, darkness for half of the year, relatively few ports that could provide even temporary repairs or a safe haven, lack of experience of salvors in ice-covered waters, the likely requirement for icebreaking and Polar Class vessels, lack of dedicated salvage depots, and the particular fragility of the Arctic environment (VanDerZwaag and Chircop, 2008). In addition, increased storminess will complicate SAR actions in the Arctic (Kolstad and Bracegirdle, 2008).

Although navigation of the Arctic may be possible before 2050 and hydrocarbon development may increase with increased accessibility, more investment in infrastructure and SAR services and more studies of impacts on environment and local communities are needed to ensure safe shipping and hydrocarbon exploitation with minimal environmental and community impacts (Chircop, 2009; Seidlitz, 2009; Ho, 2010). Rescue operations both by ship and by air need a larger geographical basis than is currently available to support predicted operation levels, and the International Convention on Oil Pollution Preparedness, Response and Co-operation, 1990 (OPRC) demands in addition on-board and on-land emergency response installations (including responding to ice damage) and calls for the establishment of oil spill combating equipment, training, and detailed plans for dealing with pollution incidents. Improved mapping, surveillance and monitoring (of shipping traffic and icebergs), disaster management (groundings/sinkings) and training of local SAR personnel are of key importance (OPRC, 1990; Chircop, 2009).




Figure 9.41. Schematic illustration of the behavior of oil in ice-covered water. Source: AMAP (2007; after Bobra and Fingas, 1986).

9.4.6. Governance

The institutional and governance dimensions of projected sea-ice change in the Arctic are profound, and must be addressed in connection with a number of cross-cutting issues affecting the region (e.g., Armitage et al., 2007; Huebert and Yeager, 2008; Young, 2009a). Oil, natural gas and mineral developments, airborne pollutants, sovereignty claims and security concerns, the socio-economic dimensions of renewable resource (fisheries, wildlife) extraction, and demands of northerners to have a greater role in decision-making as they adapt to changes all involve interrelated, multi-scale and complex issues of governance. While cross-cutting governance issues pertaining to the whole cryosphere are discussed in more detail in Chapter 10, particular sea-ice concerns are illustrated in Tables 9.5, 9.7 and Figure 9.38). Internationally, sea-ice change and its consequences will place additional pressure on the existing frameworks for cooperation developed by Arctic nations (see Young, 2005; Stokke and Honneland, 2007). The Arctic Council has been identified as a critical actor in terms of environmental governance (Young, 2005; Huebert and Yeager, 2008) in large part by enhancing the knowledge regarding the consequences of change in the Arctic.

A key governance mechanism is UNCLOS (current version, 1994). This agreement is the primary mechanism for dispute resolution related to rights of exploitation and navigational routes in international waters and provides a legally binding framework to resolve state-based conflicts (Huebert and Yeager, 2008; Stokke, 2009). In brief, it defines key territorial boundaries among coastal nations into zones that can be regulated and exploited. Uncertainty exists as to whether current agreements and governance regimes are adequate to respond to outcomes of rapid sea-ice change and its social, economic and political consequences. For some, it requires a new regional 'Arctic Treaty', which may ensure the sovereign rights of Arctic nations but with greater flexibility to respond to the outcomes of change (see Huebert and Yeager, 2008; Rothwell, 2009). The five Arctic Ocean boundary nations' 'Ilulissat Declaration' (May 2008), appears to be an effort to stem the rush for Arctic territory. While noting that UNCLOS is the correct mechanism to resolve Arctic Ocean interest conflicts it also notes that 'national implementation' of the mechanism's provisions is the means by

which to address concerns. For others, existing arrangements (i.e., UNCLOS) already provide a foundation for resolving Arctic development challenges catalyzed by sea-ice change (Stokke, 2009; Young, 2009a,b).

As sea ice retreats, Arctic countries' efforts to secure sovereign claims to Arctic territory raise questions regarding potential militarization, fishery rights and natural resource development. One current debate among Arctic nations is the 'natural prolongation' of land territory defined as the continental shelf. The nations do not rule out an Arctic governed by adaptive flexible institutions designed to enhance equitable access to resources, but signal a top-down sovereignty-based solution to the diminishing sea-ice problem rather than solutions that might come from the sub-national needs of sea-ice service users across the Arctic as a whole. The consequences of sea-ice change for local communities (indigenous and non-indigenous) raise governance issues concerning involvement of local peoples in non-renewable resource extraction and the co-management of natural resources (Ayles et al., 2007; Kofinas et al., 2007; Agrawal, 2008; Armitage et al., 2009; Berkes, 2009; see also Chapter 10 for detailed discussion).

Several conclusions can be drawn. First, there are clear limits to any Arctic governance regime (regulatory or soft-law), because the drivers of sea-ice change occur largely outside the region and fall beyond the jurisdiction of any one Arctic state. Second, there is a need for effective interplay across societal levels and scales between Arctic institutions and existing issue-specific regimes (Stokke and Honneland, 2007; Young, 2009b). Finally, there is a clear need for further monitoring and the use of monitoring data in knowledge co-production and shared learning. Effective monitoring connects with increasingly well-established community-based approaches in which local resource users and others collaborate with scientists and managers in sharing observations of change (Riedlinger and Berkes, 2001; Laidler, 2006; Bravo, 2009).

9.4.7. Adaptation

ACIA predicted unprecedented climate change for Arctic regions, and changes are being documented by instrumental records and local and indigenous observations (e.g., Huntington and Fox, 2005; McBean et al., 2005; Gearheard et al., 2006; Hovelsrud and Smit, 2010). The Arctic Human Development Report (AHDR,

Table 9.7. Cross-cutting issues of sea-ice change and the consequences for peoples and human activities.

Consequence of sea-ice change	Consequences for peoples and human activities
Increased marine and air access	Requires new transportation systems and routes which will pass through areas currently used for subsistence harvesting or otherwise impact natural systems people depend on for provisioning services Higher accessibility will make resource development of oil and gas, fisheries, freshwater, and forests linked by rivers to sea ice less expensive Indigenous and rural Arctic peoples will experience disruption to cultural patterns and practices of well-being, cultural transmission, and access to land and sea. These disruptions will be perceived differently by different people New areas may become attractive for fishing. For some of the Arctic High Seas waters there is not yet an international conservation and management regime in place. This might lead to unregulated fisheries (McIlgorm et al., 2009) Increased access and use will require better weather and ice forecasting; more comprehensive charting and related infrastructure development and updating
Increased and cheaper access across the Arctic	Conservation measures may be harder to enforce (see AHDR, 2004: resource governance chapter)
Increased variability in the physical environment	Requires increased preparedness (e.g., weather prediction accompanied by better monitoring/forecasting) and increased need for engineering to account for a hyper-variable environment

2004) demonstrated that Arctic peoples are susceptible to changing environmental conditions, and are already having to adapt. Among locally relevant climate related changes are projected increases in temperature and precipitation, reductions in sea-ice extent, and increases in the frequency and magnitude of hazardous conditions, including those associated with permafrost thaw, sea-ice stability, and increasing exposure to storms along the Arctic coast (Couture et al., 2002; Johannessen et al., 2004; Kattsov and Källén, 2005; Christensen et al., 2007; Barber et al., 2008b; Sou and Flato, 2009; Zhou et al., 2009). These changes have major implications for ecosystems and for people's livelihoods and wellbeing, and occur in the context of ongoing social, cultural, economic, and political transformations in northern communities (Fenge, 2001; Ford and Smit, 2004; Anisimov et al., 2007; Rattenbury et al., 2009).

Current observations show that sea-ice change has major impacts on the residents of the circumpolar region and that there is need for adaptation to changing conditions, both to new opportunities and challenges. The consequences of changing sea-ice conditions for local communities occur across a number of dimensions, including: resource availability; resource management policy and regulations; non-local or conflicting interests in resource extraction; limited economic opportunity and limited access to markets; demographics; attitudes and perceptions of change; local-global linkages; infrastructure; threats to cultural identity and well-being; transfer of local and traditional knowledge; and flexibility in economic and livelihood terms, and enabling institutions. These are in many cases found in combination and may also combine across scale and sectors. Such combinations may act as facilitators or constraints on adaptation (Hovelsrud and Smit, 2010). The complexity of local adaptation to sea-ice change is further illustrated by the different concerns within a community, within and between sectors or stakeholder groups; these concerns involve both direct and indirect consequences of sea-ice change for a local community and that it is a challenge for politicians and policy-makers to plan under uncertainty and across borders.

The differential vulnerability to sea-ice change in the Arctic is

consistent with findings from other regions (Smit and Wandel, 2006; Leichenko and O'Brien, 2009). In an Inuit community for example, groups vulnerable to sea-ice change include those dependent on hunting for livelihoods and food, young Inuit who use the ice for hunting and travel but do not have the depth of understanding to do so safely, and households with limited financial means to afford to adapt. Many adaptations take advantage of new conditions and minimize impacts by using new technology, changing resource use patterns, and/or switching to the consumption of store-bought foods and in many cases this involves financial investment. The ability of households to make this investment is constrained by limited financial capacity, the national tax systems, and other institutional constraints. There are also groups in a community unlikely to be affected by changing ice conditions, including those who do not hunt, are not dependent on products from the hunt, and/or have access to financial resources to adapt.

While research has documented significant vulnerabilities in Arctic communities to sea-ice change, recent work has also noted emerging adaptive capacity which is moderating some of the negative impacts. Social learning, responsive local institutions, livelihood flexibility, and adaptive management have emerged as critical to adaption to changing conditions, and which are helping reduce the dangers of using the ice in a changing climate (Ford, 2009b; Ford et al., 2009; Hovelsrud and Smit, 2010).

Adaptation to sea-ice change is predominantly a local concern, because the changes are felt at the local level first and by peoples and communities whose livelihoods and well-being are closely linked to the local environment and weather. However, other human activities also need to adapt. The development of the IMO 'Polar Code' for ships in the Arctic is one example of adaptation occurring at the international level. The level of awareness of the need for adaptation, and the development of adaptation strategies to Arctic conditions on behalf of extractive industries will have consequences for local vulnerability. Without proper guidelines and regulations in place for industrial development and resource use such as commercial fisheries, cruise traffic and shipping to adapt to changing ice conditions, local communities become more vulnerable.

Adaptation and development of adaptation strategies occur along several dimensions of uncertainty. First, there is uncertainty in the global and regional circulation models used to project future climate change. This is due both to uncertainty in the natural climate variability and in how the climate will behave in the future as a result of human influences. Second, there is uncertainty in determining the different drivers of change (climatic, social, economic, political) and in their interactions and combined impacts on human society. Third, there is uncertainty in understanding the adaptive capacity of a community, a region, a nation, and internationally. Politicians and decision makers will need to consider various levels of uncertainty with respect to adaptation to climate change. Even though existing knowledge is in many respects incomplete there is enough knowledge to understand current and future trends and changes for policy development, and for improved management of fisheries and marine ecosystems (Brander, 2010).

In summary, local focus and traditional/local knowledge are essential in studies *on* and *for* adaptation. There are variations in adaptation needs and strategies between sectors and different levels within the local community. Local understanding of change and adaptation needs is generalizable through the transfer of practical knowledge, and to help increase the scientific knowledge base. More and integrated knowledge about adaptation is needed across scientific disciplines and local/traditional knowledge, and between scientists and decision-makers and on the international arena.

9.4.8. Feedback of human activity to sea-ice change

Sea ice may be viewed as a social-ecological system with a variety of processes coupling the physical, biological, and social components. While a reduction in sea ice will lead to increased accessibility in the Arctic, the substantial increase in human activities may also impact the sea-ice services derived from the ice cover. Comprehensive, overarching surveys of activities and the magnitude of their effects on the sea-ice cover are comparatively few, and typically confined to specific topics, such as the impact of airborne pollutants on sea-ice ecosystems (e.g., Macdonald et al., 2000; Macdonald, 2007; AMAP, 2009). However, local effects have often been examined in greater detail in the context of environmental impact statements that are part of proposed industrial development in Arctic regions (e.g., IMPVA, 2008).

At the local level, feedbacks are mostly expected in the context of modifications of the coastline that are conducive to enhanced entrainment of sediments into sea ice. Both seasonal ice formation and ice melt at the local and regional level are strongly impacted by the influx of freshwater from terrestrial runoff (e.g., Macdonald et al., 2000). Moreover, large-scale river discharge and potential modifications, such as through damming of large rivers can impact stratification and hence impact ice production rates (Cattle, 1985). River discharge has been shown to be affected by human activities in several areas of the Arctic (e.g., Ye et al., 2005) and dams or water withdrawal for irrigation may significantly change river discharge and thereby have significant impacts on the sea-ice regime. Modification of freshwater discharge and its impact on ice formation could promote enhanced ice formation in

the Arctic with impacts that might reverberate at the global level if, for example, discharge from the large Siberian rivers was reduced substantially.

The distribution of shoals and shallow areas is also a key constraint in stabilizing the landfast ice cover (Reimnitz et al., 1994; Mahoney et al., 2007). Hence, coastal development such as dredging of harbors or other areas to mitigate the effects of coastal retreat, or the construction of artificial gravel or ice islands in the context of offshore oil and gas development (Instanes et al., 2005), can have major impacts on the ice cover in the coastal zone. It may also greatly reduce primary production in the sea ice (Gradinger et al., 2009b) by increasing the amount of sediment entrained into sea ice, either through enhanced resuspension as a direct or indirect result of offshore activities or through reduction in ice stability enhancing sediment entrainment in a mobile coastal ice environment (Eicken et al., 2005). While these impacts are only likely to be important on a very confined, local scale in the immediate vicinity of coastal development sites, they can significantly affect use of the ice cover at this scale, both by industry and by coastal communities.

While local effects such as coastal change and river discharge affect landfast ice, human emissions of greenhouse gases, dust and black carbon may result in further reductions in albedo affecting the ice cover on a much wider scale (Eicken et al., 2005; Huntington et al., 2007). Hydrocarbon exploration, production and transportation cause considerable emissions to air and are important variables in regional Arctic emission inventories of greenhouse gases used in climate scenarios. The geographic location of emissions of CO₂ has no impact on the warming potential. For particles (black carbon) on the other hand, the location of the emissions is important and increased activity in the Arctic results in an increase in local emissions, with concurrent effects on the surface albedo (see Chapter 2). Sea-ice retreat will also lead to a shift in patterns and timing of shipping and icebreaker activity (Chircop, 2009). There will be a general increase in ship traffic in new areas, and Arctic marine shipping may adversely impact sea ice through operational discharges and emissions and navigation impacts on sea ice (Molenaar and Corell, 2009a). However, it is possible that changing ice types and a reduced ice-cover season will limit icebreaking needs.

With activities in the Arctic increasing and adding to global impacts on sea ice, feedback effects are likely to play an increasingly important role in the further reduction of sea ice, especially on the local-scale at the Arctic coasts.

Acknowledgments

The authors thank Dr. David Barber for providing a complete review of the first draft of Section 9.3, which greatly improved our subsequent work. We also thank Dr. Ian Stirling for reviewing the polar bear material in this section, his insight is appreciated. This work has been financed by the agencies employing the team of authors (The Norwegian Polar Institute, Fisheries and Oceans Canada, University of Alaska, Environment Canada, NOAA/Fisheries Science & Technology and Greenland's Nature Institute), and the Ministry of Foreign Affairs and the Ministry of the Environment of Norway.

References

- Aars, J., N.F. Lunn and A.E. Derocher, 2006. Polar Bears: Proceedings of the 14th working meeting of the IUCN/SSC Polar Bear Specialist Group. World Conservation Union.
- Aars, J., T.A. Marques, S. Buckland, M. Andersen, S. Belikov, A. Boltunov and Ø. Wiig, 2009. Estimating the Barents Sea polar bear subpopulation size. *Marine Mammal Science*, 25:35–52.
- ACIA, 2004. Impacts of a Warming Arctic: Arctic Climate Impact Assessment. 139 pp. Cambridge University Press.
- ACIA, 2005. Arctic Climate Impact Assessment. 1042 pp. Cambridge University Press.
- Ackerman, A.S., O.B. Toon, D.E. Stevens, A.J. Heymsfield, V. Ramanathan and E.J. Welton, 2000. Reduction of tropical cloudiness by soot. *Science*, 288:1042–1047.
- Agrawal, A., 2008. The role of local institutions in adaptation to climate change. IFRI working paper. School of Natural Resources and Environment, University of Michigan.
- AHDR, 2004. Arctic Human Development Report. Stefansson Arctic Institute, Akureyri.
- Albert, O.T. and A.S. Høines, 2003. Comparing survey and assessment data: consequences for stock evaluation of Northeast Arctic Greenland halibut. *Scientia Marina*, 67:171–180.
- Alekseev, G.V. and A.P. Nagurny, 2005. Influence of sea ice cover on carbon dioxide concentration in the Arctic atmosphere in the winter period. *Doklady Earth Sciences*, 401A:486–489.
- Alekseev, G.V. and A.P. Nagurny, 2007. Role of sea ice in the formation of annual carbon dioxide cycle in the Arctic. *Doklady Earth Sciences*, 417A:1398–1401.
- Alexander, V., 1980. Interrelationships between the seasonal sea ice and biological regimes. *Cold Regions Science and Technology*, 2:157–178.
- Alexander, V. and H.J. Niebauer, 1981. Oceanography of the eastern Bering Sea ice-edge in spring. *Limnology and Oceanography*, 26:1111–1125.
- Alvsvåg, J., A.L. Agnalt and K.E. Jorstad, 2009. Evidence for a permanent establishment of the snow crab (*Chionoecetes opilio*) in the Barents Sea. *Biological Invasions*, 11:587–595.
- AMAP, 2007. Arctic Oil and Gas. Arctic Monitoring and Assessment Programme (AMAP). Oslo, Norway, 57 pp.
- AMAP, 2009. AMAP Assessment 2009: Human Health in the Arctic. Arctic Monitoring and Assessment Programme (AMAP), 254 pp. Oslo, Norway.
- Ambrose, W.G., Jr. and P.E. Renaud, 1997. Does a pulsed food supply to the benthos affect polychaete recruitment patterns in the Northeast Water Polynya? *Journal of Marine Systems*, 10:483–495.
- Ambrose, W.G., Jr., P.E. Renaud, S. Cochrane, S.G. Denisenko and J. Skardhamar, 2009. Polychaete diversity patterns on two Arctic shelves: impacts of ice and primary production? *Zoosymposia*, 2:457–485.
- Amstrup, S.C., B.G. Marcot and D.C. Douglas, 2008. A Bayesian network modeling approach to forecasting the 21st Century worldwide status of polar bears. In: DeWeaver, E.T., C.M. Bitz and L. Tremblay (Eds.). *Arctic sea ice decline: observations, projections, mechanisms and implications*, pp. 213–268, American Geophysical Union.
- Amstrup, S.C., H. Caswell, E.T. DeWeaver, I. Stirling, D.C. Douglas, B.G. Marcot and C.M. Hunter, 2009. Rebuttal of 'Polar bear population forecasts: a public-policy forecasting audit'. *Interfaces*, 39:353–369.
- Andersen, S., R.T. Tonboe, S. Kern and H. Schyberg, 2006. Improved retrieval of sea ice total concentration from spaceborne passive microwave observations using Numerical Weather Prediction model fields: An intercomparison of nine algorithms. *Remote Sensing of Environment*, 104:374–392.
- Andersen, S., R. Tonboe, L. Kaleschke, G. Heygster and L.T. Pedersen, 2007. Intercomparison of passive microwave sea ice concentration retrievals over the high-concentration Arctic sea ice. *Journal of Geophysical Research*, 112:C08004.
- Anderson, M.R. and S.D. Drobot, 2001. Spatial and temporal variability in snowmelt onset over Arctic sea ice. *Annals of Glaciology*, 33:74–78.
- Anderson, L.G. and S. Kalitin, 2001. Carbon fluxes in the Arctic Ocean – potential impact by climate change. *Polar Research*, 20:225–232.
- Anderson, L.G., E. Falck, E.P. Jones, S. Jutterström and J. Swift, 2004. Enhanced uptake of atmospheric CO₂ during freezing of seawater: A field study in Storfjorden, Svalbard. *Journal of Geophysical Research*, 109:C06004.
- Andriyashev, A.P., 1954. Fishes of the Arctic seas of the USSR. Guide to identification of USSR fauna of the Zoological Institute of the USSR Academy of Science, pp. 566, Academic Science Press.
- Anisimov, O., D. Vaughan, T. Callaghan, C. Furgal, H. Marchant, T. Prowse, H. Vilhjálmsson and J. Walsh, 2007. Polar regions (Arctic and Antarctic). In: Parry, M.L., O.F. Canziani, J.P. Palutikof, P.J. van der Linden and C.E. Hanson (Ed.). *Climate Change 2007: Impacts, Adaptation and Vulnerability*, pp. 653–685, Cambridge University Press.
- Arbetter, T.E., J.A. Curry and J.A. Maslanik, 1999. Effects of rheology and ice thickness distribution in a dynamic-thermodynamic sea ice model. *Journal of Physical Oceanography*, 29:2656–2670.
- Arctic Council, 2009. Arctic Marine Shipping Assessment 2009 Report. Arctic Council, Protection of the Arctic Marine Environment (PAME). 189 pp.
- Armitage, D., F. Berkes and N. Doubleday (Eds.), 2007. *Adaptive Co-Management: Collaboration, Learning and Multi-Level Governance*. 160 p pp. University of British Columbia Press.
- Armitage, D., R. Plummer, F. Berkes, R.I. Arthur, A.T. Charles, I.J. Davidson-Hunt, A.P. Diduck, N.C. Doubleday, D.S. Johnson, M. Marschke, P. McConney, E.W. Pinkerton and E.K. Wollenberg, 2009. Adaptive co-management for social-ecological complexity. *Frontiers in Ecology and the Environment*, 7:95–102.
- Armstrong, T., B. Roberts and C. Swithinbank, 1973. *Illustrated Glossary of Snow and Ice*. Second Edition. 64 pp. Scott Polar Research Institute, Cambridge.
- Armstrong, J.S., K.C. Green and W. Soon, 2008. Polar bear population forecasts: a public-policy forecasting audit. *Interfaces*, 38:382–395.
- Arnbom, T., 2009. Walrus – facing new challenges in a changing Arctic. *Circle*, 4:15–17.
- Arrigo, K.R., G. van Dijken and S. Pabi, 2008. Impact of a shrinking Arctic sea ice cover on marine primary production. *Geophysical Research Letters*, 35:L19603.
- Aslaksen, J., W. Dallmann, D. Holen, E. Høydaal, J. Kruse, B. Poppel, M. Stapleton and E. Turi, 2009. Interdependency of subsistence and market economies in the Arctic. In: Glomsrød, S. and I. Aslaksen (Eds.). *The Economy of the North 2008*, pp. 75–98, Statistics Norway.
- Atkinson, D., 2005. Observed storminess patterns and trends in the circum-Arctic coastal regime. *Geo-Marine Letters*, 25:98–109.
- Auel, H., R. Harjes, R. da Rocha, D. Stübing and W. Hagen, 2002. Lipid biomarkers indicate different ecological niches and trophic relationships of the Arctic hyperiid amphipods *Themisto abyssorum* and *T. libellula*. *Polar Biology*, 25:374–383.
- Ayles, B., R. Bell and A. Hoyt, 2007. Adaptive fisheries co-management in the Western Canadian Arctic. In: Armitage, D., F. Berkes and N. Doubleday (Eds.). *Adaptive Co-Management: Collaboration, Learning and Multi-Level Governance*, pp. 125–150, University of British Columbia Press.
- Baier, C.T. and J.M. Napp, 2003. Climate-induced variability in *Calanus marshallae* populations. *Journal of Plankton Research*, 25:771–782.
- Barber, D.G. and J. Hanesiak, 2004. Meteorological forcing of sea ice concentrations in the Southern Beaufort Sea over the period 1978 to 2001. *Journal of Geophysical Research*, 109:C06014.
- Barber, D.G. and J. Iacozza, 2004. Historical analysis of sea ice conditions in M'Clintock Channel and the Gulf of Boothia, Nunavut: implications for ringed seal and polar bear habitat. *Arctic*, 57:1–14.
- Barber, D.G. and R.A. Massom, 2007. The role of sea ice in Arctic and Antarctic Polynyas. In: Smith, W. and D. Barber (Eds.). *Polynyas: Windows to the World*. Elsevier Oceanography Series, 74:1–54.
- Barber, D.G. and J. Yackel, 1999. The physical, radiative and microwave scattering characteristics of melt ponds on Arctic landfast sea ice. *International Journal of Remote Sensing*, 20:2069–2090.
- Barber, D.G., L. Fortier and M. Byers, 2005. The incredible shrinking sea ice. *Policy Options*, 27:66–71.
- Barber, D.G., B.J. Hwang, J. Ehn, J. Iacozza, R. Galley, J. Hanesiak, T. Papakyriakou and J.V. Lukovich, 2008a. The ocean-sea ice-atmosphere (OSA) interface in the Southern Beaufort Sea. In: Fortier, L., D. Barber and J. Michaud (Eds.). *On Thin Ice – A synthesis of the Canadian Arctic Shelf Exchange Study (CASES)*, pp. 37–67, Aboriginal Issues Press.
- Barber, D.G., J.V. Lukovich, J. Keogak, S. Baryluk, L. Fortier and G. Henry, 2008b. The changing climate of the Arctic. *Arctic*, 61:7–26.
- Barber, D.G., R. Galley, M.G. Asplin, R. De Abreu, K.-A. Warner, M. Pudko, M. Gupta, S. Prinsenberg and S. Julien, 2009. Perennial pack ice in the

- southern Beaufort Sea was not as it appeared in the summer of 2009. *Geophysical Research Letters*, 36:L24501.
- Barents Observer, 2009. First through Northeast Passage. Barents Observer. 09/09/2009.
- Barry, R.G., 1984. The nature and significance of cloud-cryosphere interactions in the marginal snow and ice zones. In: Morner, N.-A. and Karlen, W. (Eds.). *Climatic Changes on a Yearly to Millennial Basis*, pp. 605–607, Reidel.
- Barry, R.G., R.E. Moritz and J.C. Rogers, 1979. The fast ice regimes of the Beaufort and Chukchi Sea coasts, Alaska. *Cold Regions Science and Technology*, 1:129–152.
- Bates, N.R. and J.T. Mathis, 2009. The Arctic Ocean marine carbon cycle: evaluation of air-sea CO₂ exchanges, ocean acidification impacts and potential feedbacks. *Biogeosciences*, 6:6695–6747.
- Bates, N.R., M.S. Bradley, S. Moran, D.A. Hansell and J.T. Mathis, 2006. An increasing CO₂ sink in the Arctic Ocean due to sea-ice loss. *Geophysical Research Letters*, 33:L23609.
- Beaugrand, G., M. Edwards and L. Legendre, 2010. Marine biodiversity, ecosystem functioning, and carbon cycles. *Proceedings of the National Academy of Sciences*, 107:10120–10124.
- Beaumier, M. and J. Ford, 2010. Food insecurity among Inuit females exacerbated by socio-economic stresses and climate change. *Canadian Journal of Public Health*, 101:196–201.
- Belchansky, G.I., D.C. Douglas, I.V. Alpatov and N.G. Paltonov, 2004. Spatial and temporal multiyear sea ice distributions in the Arctic: A neural network analysis of SMM/I data, 1988–2001. *Journal of Geophysical Research*, 109:C10017.
- Benoit, D., Y. Simard and L. Fortier, 2008. Hydroacoustic detection of large winter aggregations of Arctic cod (*Boreogadus saida*) at depth in ice-covered Franklin Bay (Beaufort Sea). *Journal of Geophysical Research*, 113:C06S90.
- Benowitz-Fredericks, Z.M., M.T. Shultz and A.S. Kitaysky, 2008. Stress hormones suggest opposite trends of food availability for planktivorous and piscivorous seabirds in 2 years. *Deep Sea Research Part II*, 55:1868–1876.
- Berge, J., Ø. Varpe, J. Søreide, P. Renaud, B. Gulliksen and O.J. Lønne, 2008. Climate change and effects on marine life – two examples from Svalbard's fjords. *Svalbardposten*, pp. 22–23, 12 September 2008.
- Berge, J., P.E. Renaud, K. Eiane, B. B. Gulliksen, F.R. Cottier, Ø. Varpe and T. Brattegard, 2009. Changes in the decapod fauna of an Arctic fjord during the last 100 years (1908–2007). *Polar Biology*, 32:953–961.
- Berkes, F. and D. Jolly, 2001. Adapting to climate change: social-ecological resilience in a Canadian western Arctic community. *Conservation Ecology*, 5: 18.
- Berkes, F., 2009. Evolution of co-management: Role of knowledge generation, bridging organizations and social learning. *Journal of Environmental Management*, 90:1692–1702.
- Berner, J., C. Furgal, P. Bjerregaard, M. Bradley, T. Curtis, E. De Fabo, J. Hassi, W. Keatinge, S. Kvernmo, S. Nayha, H. Rintamaki and J. Warren, 2005. Human health. In: *Arctic Climate Impact Assessment*, pp. 863–906, Cambridge University Press.
- Bitz, C.M., 2008. Some aspects of uncertainty in predicting sea ice retreat. In: DeWeaver, E.T., C.M. Bitz and L. Tremblay (Eds.). *Arctic Sea Ice Decline: Observations, Projections, Mechanisms, and Implications*, pp. 63–76, American Geophysical Union.
- Bitz, C.M. and G.H. Roe, 2004. A mechanism for the high rate of sea-ice thinning in the Arctic Ocean. *Journal of Climate*, 17:3622–3631.
- Bitz, C.M., P. Gent, R. Woodgate, A. Hall, M.M. Holland and R. Lindsay, 2006. The influence of sea ice on ocean heat uptake in response to increasing CO₂. *Journal of Climate*, 19:2437–2450.
- Blanchet, J.P., 1989. Toward estimation of climatic effects due to Arctic aerosols. *Atmospheric Environment*, 23:2609–2625.
- Blicher, M.E., S. Rysgaard and M.K. Sej, 2007. Growth and production of sea urchin *Strongylocentrotus droebachiensis* in a high-Arctic fjord, and growth along a climatic gradient (64 to 77 degrees N). *Marine Ecology Progress Series*, 341:89–102.
- Blicher, M.E., M.K. Sej and S. Rysgaard, 2009. High carbon demand of dominant macrozoobenthic species indicates their central role in ecosystem carbon flow in a sub-Arctic fjord. *Marine Ecology Progress Series*, 383:127–140.
- Bluhm, B.A. and R. Gradinger, 2008. Regional variability in food availability for Arctic marine mammals. *Ecological Applications*, 18:S77–S96.
- Bluhm, B.A., R.R. Gradinger and S.B. Schnack-Schiel, 2009a. Sea ice meio- and macrofauna. In: Thomas, D. and G. Dieckmann (Eds.). *Sea Ice*, pp. 357–394, Wiley-Blackwell.
- Bluhm, B.A., K. Iken, S.L. Mincks, B.I. Sirenko and B.A. Holladay, 2009b. Community structure of epibenthic megafauna in the Chukchi Sea. *Aquatic Biology*, 7:269–293.
- Bobra, A.M. and M.F. Fingas, 1986. The Behaviour and Fate of Arctic Oil Spills. *Water Science & Technology Vol 18 No 2* pp 13–23.
- Boé, J., A. Hall and X. Qu, 2009. September sea-ice cover in the Arctic Ocean projected to vanish by 2100. *Nature Geoscience*, 2: 341–343.
- Bond, T.C. and R.W. Bergstrom, 2006. Light absorption by carbonaceous particles: an investigative review. *Aerosol Science and Technology*, 40:27–67.
- Bond, T.C., E. Bhardwaj, R. Dong, R. Jogani, S. Jung, C. Roden, D.G. Streets and N.M. Trautmann, 2007. Historical emissions of black and organic carbon aerosol from energy-related combustion. *Global Biogeochemical Cycles*, 21: GB2018.
- Booth, D.C. and R.A. Horner, 1997. Microalgae on the Arctic Ocean Section, 1994; species abundance and biomass. *Deep Sea Research II*, 44:1607–1622.
- Borgerson, S., 2008. Arctic meltdown: the economic and security implications of global warming. *Foreign Affairs*, 87:63–77.
- Born, E.W., 2005. An assessment of the effects of hunting and climate on walrus in Greenland. PhD. Thesis. 346 pp. NHM, Oslo, Norway.
- Bourke, R.H. and R.P. Garrett, 1987. Sea ice thickness distribution in the Arctic Ocean. *Cold Regions Science and Technology*, 13:259–280.
- Bradstreet, M.S.W., 1980. Thick-billed murres and black guillemots in the Barrow Strait area, NWT, during spring – Diets and food availability along ice edges. *Canadian Journal of Zoology*, 58:2120–2140.
- Bradstreet, M.S.W. and W.E. Cross, 1982. Trophic relationships at High Arctic ice edges. *Arctic*, 35:1–12.
- Bradstreet, M.S.W., K.J. Finley, A.D. Sekerak, W.B. Griffiths, C.R. Evans, M.F. Fabijan and H.E. Stallard, 1986. Aspects of the biology of arctic cod (*Boreogadus saida*) in arctic marine food chains. VIII, 193 pp. Fisheries and Oceans, Canada, Winnipeg.
- Brander, K., 2010. Impacts of climate change on fisheries. *Journal of Marine Systems*, 79:389–402.
- Bravo, M., 2009. Community-based monitoring and self-interest. *Circle*, 1:11–13.
- Brodeur, R.D., H. Sugisaki and G.L. Hunt, Jr., 2002. Increases in jellyfish in the Bering Sea: implications for the ecosystem. *Marine Ecology Progress Series*, 233:89–103.
- Brönnimann, S., T. Lehmann, T. Griesser, T. Eewen, A.N. Grantm and R. Bleisch, 2008. Can we reconstruct Arctic sea ice back to 1900 with a hybrid approach? *Climate of the Past Discussions*, 4:955–979.
- Brown, R.D. and P. Cote, 1992. Interannual variability of landfast ice thickness in the Canadian High Arctic, 1950–89. *Arctic*, 45:273–284.
- Brown, R.G.B. and D.N. Nettleship, 1981. Importance biologique des polynies pour les oiseaux de mer coloniaux de l'Arctique. [in French]. In: Stirling, I. and H. Cleator (Eds.). *Les polynies dans l'Arctique canadien*, pp. 63–70, Environment Canada, Canadian Wildlife Service, Ottawa.
- Budyko, M.I., 1969. The effect of solar radiation variations on the climate of the Earth. *Tellus*, 21:611–619.
- Burns, J., 2009a. Arctic marine mammals. In: Perrin, W., B. Würsig and J. Thewissen (Eds.). *Encyclopedia of Marine Mammals*, 2nd Edition, pp. 48–54, Academic Press.
- Burns, J., 2009b. Harbor and spotted seals. In: Perrin, W., B. Würsig and J. Thewissen (Eds.). *Encyclopedia of Marine Mammals*, 2nd Edition, pp. 533–542, Academic Press.
- Bursa, A.S., 1963. Phytoplankton in coastal waters of the Arctic Ocean at Point Barrow. *Arctic*, 16:239–262.
- Byers, M., 2009. Conflict or cooperation: What future for the Arctic? *Swords and Ploughshares*, 17:18–21.
- Byrd, G.V., J.A. Schmutz and H.M. Renner, 2008a. Contrasting population trends of piscivorous seabirds in the Pribilof Islands: A 30-year perspective. *Deep Sea Research II*, 55:1846–1855.
- Byrd, G.V., W.J. Sydeman, H.M. Renner and S. Minobe, 2008b. Responses of piscivorous seabirds at the Pribilof Islands to ocean climate. *Deep Sea Research II*, 55:1856–1867.
- Carmack, E. and D.C. Chapman, 2003. Wind-driven shelf/basin exchange

- on a broad Arctic shelf: the joint roles of ice cover extent and shelf break bathymetry. *Geophysical Research Letters*, 30:1778.
- Carmack, E. and F. McLaughlin, 2001. Arctic Ocean change and consequences to biodiversity: a perspective on linkage and scale. *Memoirs of the National Institute for Polar Research (Japan)*, 54:365-375.
- Carmack, E., D. Barber, J. Christensen, R. Macdonald, B. Rudels and E. Sakshaug, 2006. Climate variability and physical forcing of the food webs and the carbon budget on panarctic shelves. *Progress in Oceanography*, 71:145-181.
- Carroll, M.L. and J. Carroll, 2003. The Arctic seas. In: Black, K. and G. Shimmield (Eds.). *Biogeochemistry of Marine Systems*, pp. 127-156, Blackwell.
- Carroll, M.L., S.G. Denisenko, P.E. Renaud and W.G. Ambrose, Jr., 2008. Benthic infauna of the seasonally ice-covered western Barents Sea: Patterns and relationships to environmental forcing. *Deep Sea Research II*, 55:2340-2351.
- Cattle, H., 1985. Diverting Soviet rivers: Some possible repercussions for the Arctic Ocean. *Polar Records*, 22:485-498.
- Cavalieri, D.J., 1994. A microwave technique for mapping thin sea ice. *Journal of Geophysical Research*, 99:12561-12572.
- Cavalieri, D.J., P. Gloersen and W.J. Campbell, 1984. Determination of sea ice parameters with the NIMBUS-7 SMMR. *Journal of Geophysical Research-Atmosphere*, 89:5355-5369.
- Cavalieri, D.J., C. Parkinson, P. Gloersen and H.J. Zwally, 1996, updated 2008. Sea ice concentrations from Nimbus-7 SMMR and DMSP SSM/I passive microwave data, 1979-2008. National Snow and Ice Data Center, Boulder, CO.
- Cavalieri, D.J., C.L. Parkinson, P. Gloersen, J.C. Comiso and H.J. Zwally, 1999. Deriving long-term time series of sea ice cover from satellite passive-microwave multisensor data sets. *Journal of Geophysical Research*, 104:15803-15814.
- Cavalieri, D.J., C.L. Parkinson and K.Y. Vinnikov, 2003. Contrasting Arctic and Antarctic decadal sea ice variability. *Geophysical Research Letters*, 30:1970.
- Chernook, V.I. and A.I. Boltnev, 2008. Regular instrumental aerial surveys detect a sharp drop in the birth rates of the harp seal in the White Sea. *Marine Mammals of the Holarctic*, 4:100-104.
- Chircop, A., 2009. The growth of international shipping in the Arctic: is a regulatory review timely? *International Journal of Marine and Coastal Law*, 24:355-380.
- Christensen, J.H., B. Hewitson, A. Busuioc, A. Chen, X. Gao, I. Held, R. Jones, R.K. Kolli, W.-T. Kwon, R. Laprise, V. Magaña Rueda, L. Mearns, C.G. Menéndez, C. Guillermo, J. Räisänen, A. Rinke, A. Sarr and P. Whetton, 2007. Regional climate projections. In: Solomon, S., D. Qin, M. Manning, Z. Chen, M. Marquis, K.B. Averyt, M. Tignor and H.L. Miller (Eds.). *Climate Change 2007: The Physical Science Basis*, pp. 847-940, Cambridge University Press.
- Chylek, P., C.K. Folland, G. Lesins, M.K. Dubey and M. Wang, 2009. Arctic air temperature change amplification and the Atlantic Multidecadal Oscillation. *Geophysical Research Letters*, 36:L14801.
- Clark, D.A., D.S. Lee, M.M.R. Freeman and S.G. Clark, 2008. Polar bear conservation in Canada: defining the policy problems. *Arctic*, 61:347-360.
- Clarke, A.D. and K.J. Noone, 1985. Soot in the Arctic snowpack: A cause for perturbations in radiative transfer. *Atmospheric Environment*, 19:2045-2053.
- Cochrane, S.K.J., S.G. Denisenko, P.E. Renaud, C.S. Embrow, W.G. Ambrose, Jr., I.H. Ellingsen and J. Skardhamar, 2009. Benthic macrofauna and productivity regimes in the Barents Sea – Ecological implications in a changing Arctic. *Journal of Sea Research*, 61:222-233.
- Comiso, J.C., 2002. A rapidly declining perennial sea ice cover in the Arctic. *Geophysical Research Letters*, 29:1956.
- Comiso, J.C., 2006. Arctic warming signals from satellite observations. *Weather*, 61:70-76.
- Comiso, J.C. and F. Nishio, 2008. Trends in the sea ice cover using enhanced and compatible AMSR-E, SSM/I, and SMMR data. *Journal of Geophysical Research*, 113:C02507.
- Comiso, J.C., D.J. Cavalieri, C.L. Parkinson and P. Gloersen, 1997. Passive microwave algorithms for sea ice concentration: A comparison of two techniques. *Remote Sensing of Environment*, 60: 357-384.
- Comiso, J.C., C.L. Parkinson, R. Gersten and L. Stock, 2008. Accelerated decline in the Arctic sea ice cover. *Geophysical Research Letters*, 35:L01703.
- Commission of the European Communities, 2008. Communication from the commission to the European Parliament and the Council: The European Union and the Arctic region. COM, 763.
- Conlan, K.E., A. Aitken, E. Hendrycks, E. Melling and C. McClelland, 2008. Distribution patterns of Canadian Beaufort Shelf macrobenthos. *Journal of Marine Systems*, 74:864-886.
- Connors, M.E., A.B. Hollowed and E. Brown, 2002. Retrospective analysis of Bering Sea bottom trawl surveys: regime shift and ecosystem reorganization. *Marine Ecology Progress Series*, 55:209-222.
- Conover, R.J., A.W. Herman, S.J. Prinsenberg and L.R. Harris, 1986. Distribution of and feeding by the copepod *Pseudocalanus* under fast ice during the arctic spring. *Science*, 232:1245-1247.
- Conover, R.J., N. Mumm, P. Bruecker and S. MacKenzie, 1999. Sources of urea in arctic seas: seasonal fast ice? *Marine Ecology Progress Series*, 179:55-69.
- Cooper, L.W., C.J. Ashjian, S.L. Smith, L.A. Codispoti, J.M. Grebmeier, R.G. Campbell and E.B. Sheer, 2006. Rapid seasonal sea-ice retreat in the Arctic could be affecting Pacific walrus (*Odobenus rosmarus divergens*) recruitment. *Aquatic Mammals*, 32:98-102.
- Copland, L., D.R. Mueller and L. Weir, 2007. Rapid loss of the Ayles Ice Shelf, Ellesmere Island, Canada. *Geophysical Research Letters*, 34:L21501.
- Cota, G.F., S.J. Prinsenberg, E.B. Bennett, J.W. Loder, W.R. Lewis, J.L. Anning, N.H.F. Watson and L.R. Harris, 1987. Nutrient fluxes during extended blooms of Arctic ice algae. *Journal of Geophysical Research*, 92:1951-1962.
- Côté, F. and T. Williams, 2008. The Arctic: environmental issues. InfoSeries, Parliamentary and Research Service Publication PRB 08-04E, Library of Parliament, Ottawa.
- Cottier, F.R., F. Nilsen, M.E. Inall, S. Gerland, V. Tverberg and H. Svendsen, 2007. Wintertime warming of an Arctic shelf in response to large-scale atmospheric circulation. *Geophysical Research Letters*, 34: L10607.
- Couture, R., S. Robinson, M. Burgess and S. Solomon, 2002. Climate change, permafrost, and community infrastructure: A compilation of background material from a pilot study of Tuktoyaktuk, North West Territories. Geological Survey of Canada, Open File 3867.
- Covey, C., T.E. Taylor and R.E. Dickinson, 1991. Upper limit for sea ice albedo feedback contribution to global warming. *Journal of Geophysical Research-Atmosphere*, 96:9169-9174.
- Coyle, K.O., B.A. Bluhm, B. Konar, A. Blanchard and R.C. Highsmith, 2007. Amphipod prey of gray whales in the northern Bering Sea: comparison of biomass and distribution between the 1980s and 2002-2003. *Deep Sea Research II*, 54:2906-2918.
- Coyle, K.O., A.I. Pinchuk, L.B. Eisner and J.L. Napp, 2008. Zooplankton species composition, abundance and biomass on the eastern Bering Sea shelf during summer: The potential role of water-column stability and nutrients in structuring the zooplankton community. *Deep Sea Research II*, 55:1775-1791.
- Craig, P.C., W.B. Griffiths and S.R. Johnson, 1984. Trophic dynamics in an arctic lagoon. In: Barnes, P., D. Schell and E. Reimnitz (Eds.). *The Alaskan Beaufort Sea: ecosystems and environments*, pp. 237-380, Academic Press.
- Crompton, A.E., M.E. Obbard, S.D. Petersen and P.J. Wilson, 2008. Population genetic structure in polar bears (*Ursus maritimus*) from Hudson Bay, Canada: implications of future climate change. *Biological Conservation*, 141:2528-2539.
- Crump, J., 2008. Many strong voices: climate change and equity in the arctic. *Indigenous Affairs*, 1/2:24-33.
- Curry, J.A. and E.E. Ebert, 1990. Sensitivity of the thickness of Arctic sea ice to the optical properties of clouds. *Annals of Glaciology*, 14:43-46.
- Curry, J.A. and E.E. Ebert, 1992. Annual cycle of radiation fluxes over the Arctic Ocean: sensitivity to cloud optical properties. *Journal of Climate*, 5:1267-1280.
- Curry, J.A., J.L. Schramm and E.E. Ebert, 1995. Sea ice-albedo climate feedback mechanism. *Journal of Climate*, 8:240-247.
- Curry, J.A., J.L. Schramm, D.K. Perovich and J.O. Pinto, 2001. Applications of SHEBA/FIRE data to evaluation of snow/ice albedo parameterizations. *Journal of Geophysical Research-Atmosphere*, 106:15345-15355.
- Dahl, T.M., C. Lydersen, K.M. Kovacs, S. Falk-Petersen, J. Sargent, I. Gjert and B. Gulliksen, 2000. Fatty acid composition of the blubber in white whales (*Delphinapterus leucas*). *Polar Biology*, 23:401-409.

- Deming, J., 2010. Sea ice bacteria and viruses. In: Thomas, D. and G.S. Dieckmann (Eds.). *Sea Ice*, Second Edition, pp. 247–282, Wiley-Blackwell.
- Denisov, V. and Y. Mikhaylichenko, 2009. Management of the Russian Arctic Seas. In: Hoel, A. (Ed.). *Best Practices in Ecosystem-Based Oceans Management in the Arctic*, pp. 19–35, Norwegian Polar Institute.
- DFO, 2006. Marine Mammal Research: An Overview. Centre of Expertise in Marine Mammalogy. Fisheries and Oceans Canada, Communications Branch of the Department of Fisheries and Oceans; Cat. No: Fs23-489/2005.
- DFO, 2010. Key findings from International Polar Year 2007–2008 at Fisheries and Oceans Canada: Executive Summary. Communications Branch of the Department of Fisheries and Oceans; Cat. No: Fs23-560/1-2010E.
- Derksen, C., J. Piwowar and E. LeDrew, 1997. Sea-ice melt-pond fraction as determined from low level aerial photographs. *Arctic and Alpine Research*, 29:345–351.
- Derocher, A.E., 2005. Population ecology of polar bears at Svalbard, Norway. *Population Ecology*, 47:267–275.
- Derocher, A.E., N.J. Lunn and I. Stirling, 2004. Polar bears in a warming climate. *Integrative and Comparative Biology*, 44:163–176.
- Dieckmann, G.S., G. Nehrke, S. Papadimitriou, J. Göttlicher, R. Steininger, H. Kennedy, D. Wolf-Gladrow and D.N. Thomas, 2008. Calcium carbonate as ikaite crystals in Antarctic sea ice. *Geophysical Research Letters*, 35:L08501.
- Dmitrenko, I.M., V.A. Gribov, D.L. Volkov, H. Kassens and H. Eicken, 1999. Impact of river discharge on the fast ice extension in the Russian Arctic shelf area. Paper presented at the 15th International Conference on Port and Ocean Engineering under Arctic Conditions (POAC99), pp. 311–321, Helsinki University of Technology, 23–27 August 1999.
- Dorrien, C.F., von, D. Piepenburg and M.K. Schmid, 1991. On the abundance of Arctic cod *Arctogadus glacialis* in the Northeast Water Polynya. *Polar Research*, 27:362–374.
- Döscher, R., K. Wyser, H.E.M. Meier, M. Qian and R. Redler, 2009. Quantifying Arctic contributions to climate predictability in a regional coupled ocean-ice-atmosphere model. *Climate Dynamics*, 34:1157–1176.
- Dowsley, M., 2009. Community clusters in wildlife and environmental management using TEK and community involvement to improve co-management in an era of rapid environmental change. *Polar Research*, 28:43–59.
- Dowsley, M. and G. Wenzel, 2008. 'The time of the most polar bears': a co-management conflict in Nunavut. *Arctic*, 61:177–189.
- Drinkwater, K.F., 2005. The response of Atlantic cod (*Gadus morhua*) to future climate change. *ICES Journal of Marine Science*, 62:1327–1337.
- Drinkwater, K.F., 2006. The regime shift of the 1920s and 1930s in the North Atlantic. *Progress in Oceanography*, 68:134–151.
- Drinkwater, K.F., 2009. Comparison of the response of Atlantic cod (*Gadus morhua*) in the high-latitude regions of the North Atlantic during the warm periods of the 1920s–1960s and the 1990s–2000s. *Deep Sea Research II*, 56:2087–2096.
- Drobot, S., J. Stroeve, J. Maslanik, W. Emery, C. Fowler and J. Kay, 2008. Evolution of the 2007–2008 Arctic sea ice cover and prospects for a new record in 2008. *Geophysical Research Letters*, 35:L19501.
- Druckemiller, M.L., H. Eicken, M.A. Johnson, D.J. Pringle and C.C. Williams, 2009. Towards an integrated coastal sea-ice observatory: System components and a case study at Barrow, Alaska. *Cold Regions Science and Technology*, 56:61–72.
- Duhaime, G. and A. Caron, 2009. Economic and social conditions of Arctic regions. In: Glomsrød, S. and J. Aslaksen, *The Economy of the North 2008*. pp. 11–23, Statistics Norway.
- Dunton, K.H., J.L. Goodall, S.V. Schonberg, J.M. Grebmeier and D.R. Maidment, 2005. Multi-decadal synthesis of benthic-pelagic coupling in the western arctic: Role of cross-shelf advective processes. *Deep Sea Research II*, 52:3462–3477.
- Durner, G.M., D.C. Douglas, R.M. Nielson, S.C. Amstrup, T.L. McDonald, I. Stirling, M. Mauritzen, E.W. Born, Ø. Wiig, E. DeWeaver, M.C. Serreze, S.E. Belikov, M.M. Holland, J. Maslanik, J. Aars, D.A. Bailey and A.E. Derocher, 2009. Predicting 21st-century polar bear habitat distribution from global climate models. *Ecological Monographs*, 79:25–58.
- Dyck, M.G. and E. Kebreab, 2009. Estimating the energetic contribution of polar bear (*Ursus maritimus*) summer diets to the total energy budget. *Journal of Mammalogy* 90:585–593.
- Dyck, M.G., W. Soon, R.K. Baydack, D.R. Legates, T.F. Ball and L.O. Hancock, 2007. Polar bears of western Hudson Bay and climate change: are warming spring air temperatures the 'ultimate' survival control factor? *Ecological Complexity*, 4:73–84.
- Dyck, M.G., W. Soon, R.K. Baydack, D.R. Legates, S. Baliunas, T.F. Ball and L.O. Hancock, 2008. Reply to response to Dyck, et al. (2007). On polar bears and climate change in western Hudson Bay by Stirling et al. (2008). *Ecological Complexity*, 5:289–302.
- Efthymiou, M. and M. Winkler, 2009. In Deep Water. <http://www.offshore-technology.com/features/feature52918/>. Accessed online at 02.feb.2010.
- Eicken, H., H.R. Krouse, D. Kadko and D.K. Perovich, 2002. Tracer studies of pathways and rates of meltwater transport through Arctic summer sea ice. *Journal of Geophysical Research*, 107:C8046.
- Eicken, H., T.C. Grenfell, D.K. Perovich, J.A. Richter-Menge and F. Frey, 2004. Hydraulic controls of summer Arctic pack ice albedo. *Journal of Geophysical Research*, 109:C08007.
- Eicken, H., R. Gradinger, A. Graves, A. Mahoney, I. Rigor and H. Melling, 2005. Sediment transport by sea ice in the Chukchi and Beaufort Seas: Increasing importance due to changing ice conditions? *Deep Sea Research II*, 52:3281–3302.
- Eicken, H., A. Lovcraft and M. Druckemiller, 2009. Sea-ice system services: a framework to help identify and meet information needs relevant for Arctic Observing Networks. *Arctic*, 62:119–136.
- Einarsson, N., 2009. From good to eat to good to watch: whale watching, adaptation and change in Icelandic fishing communities. *Polar Research*, 28:129–138.
- Eisenman, I. and J.S. Wettlaufer, 2009. Nonlinear threshold behavior during the loss of Arctic sea ice. *Proceedings of the National Academy of Sciences*, 106:28–32.
- Ellingsen, I.H., P. Dalpadado, D. Slagstad and H. Loeng, 2008. Impact of climatic change on the biological production in the Barents Sea. *Climatic Change*, 87:155–175.
- Elliott, K.H. and A.J. Gaston, 2009. Accuracy of depth recorders. *Waterbirds*, 32:183–191.
- England, J.H., T.R. Lakeman, D.S. Lemmen, J.M. Bednarski, T.G. Stewart and D.J.A. Evans, 2008. A millennial-scale record of Arctic Ocean sea ice variability and the demise of the Ellesmere Island ice shelves. *Geophysical Research Letters*, 35: L19502.
- Eppler, D.T., L.D. Farmer, A.W. Lohanick, M.R. Andersen, D.J. Cavalieri, J. Comiso, P. Gloersen, C. Garrity, T.C. Grenfell, M. Hallikainen, J.A. Maslanik, C. Matzler, R.A. Melloh, I. Rubinstein and C.T. Swift, 1992. Passive microwave signatures of sea ice In: Carsey, F. (Ed.). *Microwave Remote Sensing of Sea Ice*, pp. 47–71, American Geophysical Union.
- Farley, E.V., Jr. and M. Trudel, 2009. Growth rate potential of juvenile sockeye salmon in warmer and cooler years on the Eastern Bering Sea shelf. *Journal of Marine Biology*, 2009:640215.
- Farley, E.V., Jr., J.M. Murphy, M. Adkison and L. Eisner, 2007. Juvenile sockeye salmon distribution, size, condition and diet during years with warm and cool spring sea temperatures along the eastern Bering Sea shelf. *Journal of Fish Biology*, 71:1145–1158.
- Feder, H.M., S.C. Jewett and A. Blanchard, 2005. Southeastern Chukchi Sea (Alaska) epibenthos. *Polar Biology*, 28:402–421.
- Fenge, T., 2001. The Inuit and climate change. *ISUMA*, 2:79–85.
- Ferguson, S.H., 2009. Killer whales on the rise in the Canadian Arctic. *Circle*, 4:20–23.
- Ferguson, S.H., I. Stirling and P. McLoughlin, 2005. Climate change and ringed seal (*Phoca hispida*) recruitment in Western Hudson Bay. *Marine Mammal Science*, 21:121–135.
- Fetterer, F. and N. Untersteiner, 1998. Observations of melt ponds on Arctic sea ice. *Journal of Geophysical Research-Oceans*, 103:24821–24835.
- Fetterer, F., K. Knowles, W. Meier and M. Savoie, 2002, updated 2011. *Sea Ice Index, 1979–2010*. National Snow and Ice Center, Boulder, CO. Digital Media.
- Finley, K.J., 2001. Natural history and conservation of the Greenland whale, or bowhead in the Northwest Atlantic. *Arctic*, 54:55–76.
- Fischbach, A.S., S.C. Amstrup and D.C. Douglas, 2007. Landward and eastward shift of Alaskan polar bear denning associated with recent sea ice changes. *Polar Biology*, 30:1395–1405.
- Fischbach, A.S., D.H. Monson and C.D. Jay, 2009. Enumeration of Pacific walrus carcasses on beaches of the Chukchi Sea in Alaska following a mortality event, September 2009. U.S. Geological Survey Open File

- Report. 2009-1291.
- Flanner, M.G., C.S. Zender, J.T. Randerson and P.J. Rasch, 2007. Present-day climate forcing and response from black carbon in snow. *Journal of Geophysical Research*, 112:D11202.
- Flato, G.M. and R.E. Brown, 1996. Variability and climate sensitivity of landfast Arctic sea ice. *Journal of Geophysical Research-Oceans*, 101:25767-25777.
- Flocco, D. and D.L. Feltham, 2007. A continuum model of melt pond evolution on Arctic sea ice. *Journal of Geophysical Research*, 112:C08016.
- Forbes, B. and F. Stammer, 2009. Arctic climate change discourse: the contrasting politics of research agendas in the West and Russia. *Polar Research*, 28:28-42.
- Forbes, D., G. Parkes, G. Manson and L. Ketch, 2004. Storms and shoreline retreat in the southern Gulf of St. Lawrence. *Marine Geology*, 210:169-204.
- Forbes, D., G. Manson, D. Mate and A. Qammaniq, 2008. Cryospheric change and coastal stability: combining traditional knowledge and scientific data for climate change adaptation. *Ice and Climate News*, 11:17-18.
- Ford, J., 2009a. Sea ice change in Arctic Canada: are there limits to Inuit adaptation? In: Adger, N., I. Lorenzoni and K.L. O'Brian (Eds.). *Adapting to Climate Change: Thresholds, Values, and Governance*, pp. 114-128, Cambridge University Press.
- Ford, J., 2009b. Vulnerability of Inuit food systems to food insecurity as a consequence of climate change: A case study from Igloolik, Nunavut. *Regional Environmental Change*, 9:83-100.
- Ford, J., 2009c. Dangerous climate change and the importance of adaptation for the Arctic's Inuit population. *Environmental Research Letters*, 4:1-9.
- Ford, J. and L. Berrang-Ford, 2009. Food security in Igloolik, Nunavut: an exploratory study. *Polar Records*, 45:225-236.
- Ford, J. and T. Pearce, 2010. What we know, do not know, and need to know about climate change vulnerability in the western Canadian Arctic: a systematic literature review. *Environmental Research Letters*, 5.
- Ford, J. and B. Smit, 2004. A framework for assessing the vulnerability of communities in the Canadian Arctic to risks associated with climate change. *Arctic*, 57:389-400.
- Ford, J., et al., 2006. Vulnerability to climate change in Igloolik, Nunavut: What we can learn from the past and present. *Polar Records*, 42:1-12.
- Ford, J., T. Pearce, B. Smit, J. Wandel, M. Allarut, K. Shappa, H. Ittusujurat and K. Qrunnut, 2007. Reducing vulnerability to climate change in the Arctic: The case of Nunavut, Canada. *Arctic*, 60:150-166.
- Ford, J., T. Pearce, J. Gilligan, B. Smit and J. Oakes, 2008. Climate change and hazards associated with ice use in Northern Canada. *Arctic Antarctic and Alpine Research*, 40:647-658.
- Ford, J., B. Smit, J. Wandel and J. MacDonald, 2009. Sea ice, climate change, and community vulnerability in northern Foxe Basin. *Climate Research*, 38:137-154.
- Ford, J., T. Pierce, F. Duerden, C. Furgal and B. Smit, 2010. Climate change policy responses for Canada's Inuit population: the importance of and opportunities for adaptation. *Global Environmental Change*, 20:177-191.
- Forest, A., M. Sampei, H. Hattori, R. Makabe, H. Sasaki, M. Fukuchi, P. Wassmann and L. Fortier, 2007. Particulate organic carbon fluxes on the slope of the Mackenzie Shelf (Beaufort Sea): Physical and biological forcing of shelf-basin exchanges. *Journal of Marine Systems*, 68:39-54.
- Forgione, M. and H. Martin, 2008. Now threatened, polar bears are a bigger draw in Churchill, Canada. *Los Angeles Times*. 15 May 2008.
- Forsström, S., J. Ström, C.A. Pedersen, E. Isaksson and S. Gerland, 2009. Elemental carbon distribution in Svalbard snow. *Journal of Geophysical Research*, 114:D19112.
- Fortier, M., L. Fortier, H. Hattori, H. Saito and L. Legendre, 2001. Visual predators and the diel vertical migration of copepods under Arctic sea ice during the midnight sun. *Journal of Plankton Research*, 23:1263-1278.
- Fortier, M., L. Fortier, C. Michel and L. Legendre, 2002. Climatic and biological forcing of the vertical flux of biogenic particles under seasonal arctic sea ice. *Marine Ecology Progress Series*, 225:1-16.
- Fortier, M., P. Sirois, J. Michaud and D. Barber, 2006. Survival of Arctic cod larvae (*Boreogadus saida*) in relation to sea-ice and temperature in the Northeast Water Polynya (Greenland Sea). *Canadian Journal of Fisheries and Aquatic Sciences*, 63:1608-1616.
- Fox, S., 2002. These are things that are really happening: Inuit perspectives on the evidence and impacts of climate change in Nunavut. In: Krupnik, I. and D. Jolly (Eds.). *The Earth is Faster Now: Indigenous Observations of Climate Change*, pp. 12-53, Arctic Consortium of the United States, ARCUS.
- Francis, J.A., E. Hunter, J. Key and X. Wang, 2005. Clues to variability in Arctic minimum sea ice extent. *Geophysical Research Letters*, 32: L21501.
- Francis, J.A., W. Chan, D.J. Leathers, J.R. Miller and D.E. Veron, 2009. Winter Northern Hemisphere weather patterns remember summer Arctic sea ice extent. *Geophysical Research Letters*, 36:L07503.
- Freeman, M., 1970. Observations of the seasonal behaviour of the Hudson Bay eider (*Somateria mollissima sedentaria*). *Canadian Field Naturalist*, 84:145-153.
- Freitas, C., K.M. Kovacs, R.A. Ims, M.A. Fedak and C. Lydersen, 2008a. Ringed seal post-moulting movement tactics and habitat selection. *Oecologia*, 155:193-204.
- Freitas, C., K.M. Kovacs, R.A. Ims and C. Lydersen, 2008b. Predicting habitat use by ringed seals (*Phoca hispida*) in a warming Arctic. *Ecological Modelling*, 217:19-32.
- Freitas, C., K.M. Kovacs, R.A. Ims, M.A. Fedak and C. Lydersen, 2009. Deep into the ice: over-wintering and habitat selection in Atlantic walrus. *Marine Ecology Progress Series*, 375:247-261.
- Frolov, I.E., Z.M. Gudkovich, V.P. Karklin, E.G. Kovalev and V.M. Smolyanitsky, 2009. *Climate Change in Eurasian Arctic Shelf Seas, Centennial Ice Cover Observations*. 166 pp. Springer-Praxis.
- Fuller, T., D.P. Morton and S. Sarkar, 2008. Incorporating uncertainty about species' potential distributions under climate change into the selection of conservation areas with a case study from the Arctic Coastal Plain of Alaska. *Biological Conservation*, 141:1547-1559.
- Furgal, C.M., S. Innes and K.M. Kovacs, 1996. Characteristics of ringed seal (*Phoca hispida*) subnivalian lairs and habitat and their influence on predation. *Canadian Journal of Zoology*, 74:858-874.
- Furgal, C. and T. Prowse, 2008. Northern Canada. In: Lemmen, D., E. Warren, J. Lacroix and E. Bush, (Eds.). *From Impacts to Adaptation: Canada in a Changing Climate 2008*, pp. 57-118, Government of Canada, Ottawa.
- Furgal, C. and J. Seguin, 2006. Climate change, health, and vulnerability in Canadian Northern Aboriginal communities. *Environmental Health Perspectives*, 114:1964-1970.
- Garlich-Miller, J.L., L.T. Quakenbush and J.J. Bromaghin, 2006. Trends in age structure and productivity of Pacific walrus harvested in the Bering Strait region of Alaska, 1952-2002. *Marine Mammal Science*, 22:880-896.
- Garneau, M.-E., M. Gosselin, B. Klein, J.E. Tremblay and E. Fouilland, 2007. New and regenerated production during a late summer bloom in an Arctic polynya. *Marine Ecology Progress Series*, 345:13-26.
- Gascard, J.-C., J. Festy, le Goff, H. and 23 others, 2008. Exploring Arctic transpolar drift during dramatic sea ice retreat. *Eos, Transactions, American Geophysical Union*, 89: 21-22.
- Gaston, A.J. and M.S.W. Bradstreet, 1993. Intercolony differences in the summer diet of thick-billed murre in the Eastern Canadian Arctic. *Canadian Journal of Zoology*, 71:1831-1840.
- Gaston, A.J. and J.M. Hipfner, 2000. Thick-billed murre (*Uria lomvia*). 32 pp. *Birds of North America*, Philadelphia, PA.
- Gaston, A.J. and P.L. McLaren, 1990. Winter observations of black guillemots *Cephus grylle* in Hudson Bay and Davis Strait. *Studies in Avian Biology*, 14:67-70.
- Gaston, A.J. and K.J. Woo 2008. Razorbills *Alca torda* follow subarctic prey into the Canadian Arctic: colonization results from climate change? *Auk*, 125:939-942.
- Gaston, A.J., K. Woo and J.M. Hipfner, 2003. Trends in forage fish populations in northern Hudson Bay since 1981, as determined from the diet of nestling thick-billed murre *Uria lomvia*. *Arctic*, 56:227-233.
- Gaston, A.J., H.G. Gilchrist and J.M. Hipfner, 2005a. Climate change, ice conditions and reproduction in an Arctic nesting marine bird: the thick-billed murre (*Uria lomvia*, L.). *Journal of Animal Ecology*, 74:832-841.
- Gaston, A.J., H.G. Gilchrist and M.L. Mallory, 2005b. Variation in ice conditions has strong effects on the breeding of marine birds at Prince Leopold Island, Nunavut. *Ecography*, 28:331-344.
- Gaston, A.J., H.G. Gilchrist, M.L. Mallory and P.A. Smith, 2009. Changes

- in seasonal events, peak food availability and consequent breeding adjustment in a marine bird: a case of progressive mis-matching. *Condor*, 111:111–119.
- Gautier, D., 2009. Assessment of undiscovered oil and gas in the Arctic. *Arctic*, 324:1175–1179.
- Gearheard, S., W. Matumeak, I. Angutikjuaq, J. Maslanik, H.P. Huntington, J. Leavitt, D. Matumeak Kagak, G. Tigullaraq, and R.G. Barry, 2006. 'It's not that simple': a collaborative comparison of sea ice environments, their uses, observed changes, and adaptations in Barrow, Alaska, USA, and Clyde River, Nunavut, Canada. *Ambio*, 35:203–211.
- George, J.C., L.M. Philo, K. Hazard, D. Withrow, G.M. Carroll and R. Suydam, 1994. Frequency of killer whale (*Orcinus orca*) attacks and ship collisions based on scarring on bowhead whales (*Balaena mysticetus*) of the Bering-Chukchi-Beaufort Seas stock. *Arctic*, 47:247–255.
- George, J.C., J. Zeh, R. Suydam and C. Clark, 2004. Abundance and population trend (1978–2001) of western arctic bowhead whales surveyed near Barrow, Alaska. *Marine Mammal Science*, 20:755–757.
- George, J.C., C. Nicolson, S. Drobot, J. Maslanik and R. Suydam, 2006. Sea ice density and bowhead whale body condition: preliminary findings. Paper presented at the Biennial Conference on the Biology of Marine Mammals. Conference on the Biology of Marine Mammals, San Diego, CA.
- Gerdes, R. and C. Köberle, 2007. Comparison of Arctic sea ice thickness variability in IPCC climate of the 20th century experiments and in ocean sea ice hindcasts. *Journal of Geophysical Research*, 112: C04S13.
- Gerland, S. and C. Haas, 2011. Snow-depth observations by adventurers traveling on Arctic sea ice. *Annals of Glaciology*, 52:369–376.
- Gerland, S. and R. Hall, 2006. Variability of fast ice thickness in Spitsbergen fjords. *Annals of Glaciology*, 44:231–239.
- Gerland, S. and A.H.H. Renner, 2007. Sea ice mass balance in an Arctic fjord. *Annals of Glaciology*, 46: 435–442.
- Gerland, S., J.-G. Winther, K.B. Ørbæk and B. Ivanov, 1999. Physical properties, spectral reflectance and thickness development of first year fast-ice in Kongsfjorden, Svalbard. *Polar Research*, 18:275–282.
- Gerland, S., A.H.H. Renner, F. Godtlielsen, D. Divine and T.B. Løyning, 2008. Decrease of sea ice thickness at Hopen, Barents Sea, during 1966–2007. *Geophysical Research Letters*, 35:L06501.
- Gilchrist, H.G. and M.L. Mallory, 2005. Declines in abundance and distribution of the ivory gull (*Pagophila eburnea*) in Arctic Canada. *Biological Conservation*, 121:303–309.
- Gilchrist, H.G. and G.J. Robertson, 2000. Observations of marine birds and mammals wintering at polynyas and ice edges in the Belcher Islands, Nunavut, Canada. *Arctic*, 53:61–68.
- Gilchrist, H.G., J. Heath, L. Arragutainaq, G. Robertson, K. Allard, S. Gilliland and M. Mallory, 2006. Combining scientific and local knowledge to study common eider ducks wintering in Hudson Bay. In: Riewe, R. and J. Oakes (Eds.). *Climate Change: linking traditional and scientific knowledge*, pp. 189–201, Aboriginal Issues Press.
- Giles, K.A., S.W. Laxon and A.L. Ridout, 2008. Circumpolar thinning of Arctic sea ice following the 2007 record ice extent minimum. *Geophysical Research Letters*, 35:L22502.
- Gjertz, I., 1990. Ringed seal *Phoca hispida* fright behavior caused by walrus *Odobenus rosmarus*. *Polar Research*, 8:317–319.
- Gjøsæter, H., 1998. The population biology and exploitation of capelin (*Mallotus villosus*) in the Barents Sea. *Sarsia*, 83:453–496.
- Gjøsæter, H., P. Dalpadado and A. Hassel, 2002. Growth of Barents Sea capelin (*Mallotus villosus*) in relation to zooplankton abundance. *ICES Journal of Marine Science*, 59:959–967.
- Gleason, J.S. and K.D. Rode, 2009. Polar bear distribution and habitat association reflect long-term changes in fall sea ice conditions in the Alaskan Beaufort Sea. *Arctic*, 62:405–417.
- Glomsrød, S., I. Mäenpää, L. Lindholt, H. McDonald and S. Goldsmith, 2009. Arctic economies within the Arctic nations. In: Glomsrød, S. and J. Aslaksen (Eds.). *The Economy of the North 2008*, pp. 37–68, Statistics Norway.
- Glud, R.N., S. Rysgaard, M. Kühl and J.W. Hansen, 2007. The sea ice in Young Sound: Implications for carbon cycling. In: Rysgaard, S. and R.N. Glud (Eds.). *Carbon cycling in Arctic marine ecosystems: Case study Young Sound. Meddelelser om Grønland*, pp. 61–86, Commission for Scientific Research in Greenland, Copenhagen.
- Goldhar, C., J. Ford and L. Berrang-Ford, 2010. Prevalence of food insecurity in a Greenlandic community and importance of social-economic environmental stressors. *International Journal of Circumpolar Health*, 69:285–303.
- Goosse, H. and T. Fichefet, 2001. Open-ocean convection and polynya formation in a large-scale ice-ocean model. *Tellus A*, 53:94–111.
- Goosse, H., O. Arzel, C.M. Bitz, A. de Montety and M. Vancoppenolle, 2009. Increased variability of the Arctic summer ice extent in a warmer climate. *Geophysical Research Letters*, 36:L23702.
- Gorodetskaya, I.V., L.-B. Tremblay, B. Liepert, M.A. Cane and R.I. Cullather, 2008. The influence of cloud and surface properties on the Arctic Ocean shortwave radiation budget in coupled models. *Journal of Climate*, 21:866–882.
- Gosselin, M., M. Levasseur, A. Wheeler, R.A. Horner and B.C. Booth, 1997. New measurements of phytoplankton and ice algal production in the Arctic Ocean. *Deep Sea Research II*, 44:1623–1644.
- Gradinger, R., 1999. Integrated abundances and biomass of sympagic meiofauna from Arctic and Antarctic pack ice. *Polar Biology*, 22:169–177.
- Gradinger, R., 2002. Sea ice microorganisms In: Bitten, G. (Ed.), *Encyclopedia of Environmental Microbiology*, pp. 2833–2844, Wiley and Sons.
- Gradinger, R., 2009. Sea-ice algae: Major contributors to primary production and algal biomass in the Chukchi and Beaufort Seas during May/June 2002. *Deep Sea Research II*, 56:1201–1212.
- Gradinger, R. and J. Ikävalko, 1998. Organism incorporation into newly forming Arctic sea ice in the Greenland Sea. *Journal of Plankton Research*, 20:571–586.
- Gradinger, R., B. Bluhm and K. Iken, 2009a. Arctic sea ice ridges – safe heavens for sea ice fauna during periods of extreme ice melt? *Deep Sea Research II*, 57:86–95.
- Gradinger, R.R., M. Kaufman and B.A. Bluhm, 2009b. The pivotal role of sea ice sediments for the seasonal development of near-shore Arctic fast ice biota. *Marine Ecology Progress Series*, 394:49–63.
- Graverson, R.G. and M. Wang, 2009. Polar amplification in a coupled climate model with locked albedo. *Climate Dynamics*, 33:629–643.
- Grebmeier, J.M., 1993. Studies of pelagic-benthic coupling extended onto the Soviet continental shelf in the northern Bering and Chukchi Seas. *Continental Shelf Research*, 13:653–688.
- Grebmeier, J., J. Overland, S. Moore, E. Farley, E. Carmack, L. Cooper, K. Frey, J. Helle, F. McLaughlin and S. McNutt, 2006a. A major ecosystem shift in the northern Bering Sea. *Science*, 311:1461–1464.
- Grebmeier, J.M., L.W. Cooper, H.M. Feder and B.I. Sirenko, 2006b. Pelagic-benthic coupling and ecology dynamics in the Pacific-influenced Amerasian Arctic. *Progress in Oceanography*, 71:331–361.
- Grebmeier, J.M., S.E. Moore, J.E. Overland, K. Frey and R. Gradinger, 2010. Bio-response to recent extreme sea ice retreats in the Pacific Arctic. *Eos, Transactions, American Geophysical Union*, 91:161–168.
- Grenfell, T.C. and G.A. Maykut, 1977. The optical properties of ice and snow in the Arctic basin. *Journal of Glaciology*, 18:445–463.
- Grenfell, T.C. and D.K. Perovich, 1984. Spectral albedos of sea ice and incident solar irradiance in the southern Beaufort Sea. *Journal of Geophysical Research-Oceans*, 89:3573–3580.
- Grenfell, T.C. and D.K. Perovich, 2008. Incident spectral irradiance in the Arctic Basin during the summer and fall. *Journal of Geophysical Research*, 113:D12117.
- Grenfell, T.C., S.G. Warren and P.C. Mullen, 1994. Reflection of solar radiation by the Antarctic snow surface at ultraviolet, visible and near-infrared wavelengths. *Journal of Geophysical Research-Oceans*, 99:18669–18684.
- Haas, C. and M. Druckenmiller, 2009. Ice thickness and roughness measurements. In: H. Eicken (Ed.), *Field Techniques for Sea Ice Research*, pp. 49–116, University of Alaska Press.
- Haas, C., S. Hendricks and M. Doble, 2006. Comparison of the sea ice thickness distribution in the Lincoln Sea and adjacent Arctic Ocean in 2004 and 2005. *Annals of Glaciology*, 44:247–252.
- Haas, C., A. Pfaffling, S. Hendricks, L. Rabenstein, J.L. Etienne and I. Rigor, 2008. Reduced ice thickness in Arctic Transpolar Drift favors rapid ice retreat. *Geophysical Research Letters*, 35:L17501.
- Haas, C., S. Hendricks, H. Eicken and A. Herber, 2010. Synoptic airborne thickness surveys reveal state of Arctic sea ice cover. *Geophysical Research Letters*, 37:L09501.
- Hall, A., 2004. The role of surface albedo feedback in climate. *Journal of Climate*, 17:1550–1568.

- Hamazaki, T., L. Fair, L. Watson and E. Brennan, 2005. Analyses of Bering Sea bottom-trawl surveys in Norton Sound: absence of regime shift effect on epifauna and demersal fish. *ICES Journal of Marine Science*, 62:1597-1602.
- Hammill, M.O., 2009. Ringed seals. In: Perrin, W., B. Würsig and J. Thewissen (Eds.). *Encyclopedia of Marine Mammals*, 2nd Edition, pp. 972-974, Academic Press.
- Hanesiak, J.M., D.G. Barber and G.M. Flato, 1999. The role of diurnal processes in the seasonal evolution of sea ice and its snow cover. *Journal of Geophysical Research-Oceans*, 104:13593-13604.
- Hanesiak, J., J. Yackel and D. Barber, 2001. Effect of melt ponds on first-year sea ice ablation – integration of RADARSAT-1 and thermodynamic modeling. *Canadian Journal of Remote Sensing*, 27:433-442.
- Hanesiak, J., R. Stewart, P. Taylor and 26 others, 2010. Storm studies in the Arctic (STAR). *Bulletin of the American Meteorological Society*, 91:47-68.
- Hansell, R.I.C., J.R. Malcolm, H. Welch, R.L. Jefferies and P.A. Scott, 1998. Atmospheric change and biodiversity in the Arctic. *Environmental Monitoring and Assessment*, 49:303-325.
- Hansen, J. and L. Nazarenko, 2004. Soot climate forcing via snow and ice albedos. *Proceedings of the National Academy of Sciences*, 101:423-428.
- Hansen, J., M. Sato and R. Ruedy, 1997. Radiative forcing and climate response. *Journal of Geophysical Research-Atmosphere*, 102:6831-6864.
- Hare, S.R. and M.J. Mantua, 2000. Empirical evidence for North Pacific regime shifts in 1977 and 1989. *Progress in Oceanography*, 47:103-146.
- Harner, T., K. Wiberg and R. Norstrom, 2000. Enantiomer fractions are preferred to enantiomer ratios for describing chiral signatures in environmental analysis. *Environmental Science and Technology*, 34:218-220.
- Harvell, C.D., K. Kim, J.M. Vurkholder, R.R. Colwell, P.R. Epstein, D.J. Grimes, E.E. Hofmann, E.K. Lipp, A.D.M.E. Osterhaus, R.M. Overstreet, J.W. Porter, G.W. Smith and G.R. Vasta, 1999. Review: marine ecology – emerging marine diseases – climate links and anthropogenic factors. *Science*, 285:1505-1510.
- Harwood, L.A. and T.G. Smith, 2002. Whales of the Inuvialuit Settlement Region in Canada's Western Arctic: An overview and outlook. *Arctic*, 55:77-93.
- Harwood, L.A., T.G. Smith and H. Melling, 2000. Variation in reproduction and body condition of the ringed seal (*Phoca hispida*) in western Prince Albert Sound, NT, Canada, as assessed through a harvest-based sampling program. *Arctic*, 53:422-431.
- Haug, T., K.T. Nilssen, L. Lindblom and U. Lindstrom, 2007. Diets of hooded seals (*Cystophora cristata*) in coastal waters and drift ice waters along the east coast of Greenland. *Marine Biology Research*, 3:123-133.
- Heide-Jørgensen, M.P., 2009. Narwahl. In: Perrin, W., B. Würsig and J. Thewissen (Eds.). *Encyclopedia of Marine Mammals*, 2nd Edition, pp. 754-758. Academic Press.
- Heide-Jørgensen, M.P. and K.L. Laidre, 2004. Declining extent of open-water refugia for top predators in Baffin Bay and adjacent waters. *Ambio*, 33: 487-494.
- Hendricks, S., S. Gerland, L.H. Smedsrud, C. Haas, A.A. Pfaffhuber and F. Nilsen, 2011. Sea-ice thickness variability in Storfjorden, Svalbard. *Annals of Glaciology*, 52:61-68.
- Hewitt, C.D., C.S. Senior and J.F.B. Mitchell, 2001. The impact of dynamic sea-ice on the climate sensitivity of a GCM: a study of past, present and future climates. *Climate Dynamics*, 17:655-668.
- Hibler, W.D., 1984. The role of sea ice dynamics in modeling CO₂ increases. In: Hansen, J.E. and T. Takahashi (Eds.). *Climate processes and climate sensitivity*, pp. 238-253, American Geophysical Union.
- Higdon, J.W. and S.H. Ferguson, 2009. Loss of arctic sea ice causing punctuated change in sightings of killer whales (*Orcinus orca*) over the past century. *Ecological Applications*, 19:1365-1375.
- Hilmer, M. and T. Jung, 2000. Evidence for a recent change in the link between the North Atlantic Oscillation and Arctic sea ice export. *Geophysical Research Letters*, 27:989-992.
- Hilmer, M., M. Harder and P. Lemke, 1998. Sea ice transport: a highly variable link between the Arctic and North Atlantic. *Geophysical Research Letters*, 25:3359-3362.
- Hirche, H.-J., M.E.M. Baumann, G. Kattner and R. Gradinger, 1991. Plankton distribution and the impact of copepod grazing on primary production in Fram Strait, Greenland Sea. *Journal of Marine Systems*, 2:477-494.
- Ho, J., 2010. The implications of Arctic sea ice decline on shipping. *Marine Policy*, 34:713-715.
- Hobson, K.A., 1993. Trophic relationships among high Arctic seabirds – insights from tissue-dependent stable isotope models. *Marine Ecology Progress Series*, 95:7-18.
- Hobson, K.A., W.G. Ambrose, Jr. and P.E. Renaud, 1995. Sources of primary production, benthic–pelagic coupling, and trophic relationships within the Northeast Water Polynya: insights from ¹³C and ¹⁵N analysis. *Marine Ecology Progress Series*, 128:1-10.
- Hobson, K.A., A.T. Fisk, N. Karnovsky, M. Holst, J.-M. Gagnon and M. Fortier, 2002a. A stable isotope (δ¹⁵N) model for the North Water Polynya food web: implications for evaluating trophodynamics and the flow of energy and contaminants. *Deep Sea Research II*, 49:5131-5150.
- Hobson, K.A., G.T. Gilchris and K. Falk, 2002b. Isotopic investigations of seabirds of the North Water Polynya: Contrasting trophic relationships between the eastern and western sectors. *Condor*, 104:1-11.
- Hobson, K.A., I. Stirling and D.S. Andriashek, 2009. Isotopic homogeneity of breath CO₂ from fasting and berry-eating polar bears: implications for tracing reliance on terrestrial foods in a changing Arctic. *Canadian Journal of Zoology*, 87:50-55.
- Hoel, A.H., 2009. Norway and integrated oceans management - the case of the Barents Sea. In: Hoel, A.H. (Ed.). *Best Practices in Ecosystem-Based Oceans Management in the Arctic*, pp. 43-52, Norwegian Polar Institute, Tromsø.
- Holland, M.M., C.M. Bitz, M. Eby and A.J. Weaver, 2001. The role of ice-ocean interactions in the variability of the North Atlantic thermohaline circulation. *Journal of Climate*, 14:656-675.
- Holland, M.M., C.M. Bitz and L.B. Tremblay, 2006. Future abrupt reductions in the summer Arctic sea ice. *Geophysical Research Letters*, 33:L23503.
- Holland, M.M., M.C. Serreze and J. Stroeve, 2008a. The sea ice mass budget of the Arctic and its future change as simulated by coupled climate models. *Climate Dynamics*, 34:185-200.
- Holland, M.M., C.M. Bitz, B. Tremblay and D.A. Bailey, 2008b. The role of natural versus forced change in future rapid summer Arctic ice loss. In: DeWeaver, E.T., C.M. Bitz and L. Tremblay (Eds.). *Arctic Sea Ice Decline: Observations, Projections, Mechanisms, and Implications*, pp. 133-150, American Geophysical Union.
- Holloway, G. and T. Sou, 2002. Has Arctic sea ice rapidly thinned? *Journal of Climate*, 15:1691-1701.
- Honda, M., J. Inoue and S. Yamane, 2009. Influence of low Arctic sea ice minima on anomalously cold Eurasian winters. *Geophysical Research Letters*, 36:L08707.
- Hop, H. and O. Pavlova, 2008. Distribution and biomass transport of ice amphipods in drifting sea ice around Svalbard. *Deep Sea Research II*, 55:2292-2307.
- Hop, H., H.E. Welch and R.E. Crawford, 1997. Population structure and feeding ecology of Arctic cod schools in the Canadian high Arctic. Paper presented at the Fish Ecology in Arctic North America Symposium, pp. 68-80, 19-21 May 1992, Fairbanks, Alaska.
- Hop, H., M. Poltermann, O.J. Lonne, S. Falk-Petersen, R. Korsnes and W.P. Budgell, 2000. Ice amphipod distribution relative to ice density and under-ice topography in the northern Barents Sea. *Polar Biology*, 23:357-367.
- Hopcroft, R.R., K.N. Kosobokova and A.I. Pinchuk, 2010. Zooplankton community patterns in the Chukchi Sea during summer 2004. *Deep Sea Research Part II: Topical Studies in Oceanography*, 57: 27-39.
- Hoque, M. and W. Pollard, 2009. Arctic coastal retreat through block failure. *Canadian Geotechnical Journal*, 46:1103-1115.
- Horner, R.A., S.F. Ackley, G. Dieckmann, B. Gulliksen, T. Hoshiai, L. Legendre, I.A. Melnikov, W.S. Reeburgh, M. Spindler and C.W. Sullivan, 1992. Ecology of sea-ice biota. 1. Habitat, terminology, and methodology. *Polar Biology*, 12:417-427.
- Hovelsrud, G. and B. Smit (Eds.), 2010. *Community Adaptation and Vulnerability in the Arctic Regions*. 353 pp. Springer Verlag.
- Hovelsrud, G., M. McKenna and H. Huntington, 2008. Marine mammal harvests and other interactions with humans. *Ecological Applications*, 18:S135-S147.
- Huebert, R. and B. Yeager, 2008. *A New Sea: The need for a regional agreement on management and conservation of the arctic marine environment*, 46 pp. WWF International Arctic Programme, Oslo.
- Hunt, G.L., Jr., V. Bakken and F. Mehlum, 1996. Marine birds in the marginal ice zone of the Barents Sea in late winter and spring. *Arctic*, 49:53-61.

- Hunt, G.L., Jr., P. Stabeno, G. Walters, E. Sinclair, R.D. Brodeur, J.M. Napp and N.A. Bond, 2002. Climate change and control of the southeastern Bering Sea pelagic ecosystem. *Deep Sea Research II*, 49:5821–5853.
- Hunt, G.L., Jr., P.J. Stabeno, S. Strom and J.M. Napp, 2008. Patterns of spatial and temporal variation in the marine ecosystem of the southeastern Bering Sea, with special reference to the Pribilof Domain. *Deep Sea Research II*, 55:1919–1944.
- Huntington, H. and S. Fox, 2005. The changing Arctic: Indigenous perspectives. In: *Arctic Climate Impact Assessment*, pp. 61–98, Cambridge University Press.
- Huntington, H., J. Mosli and V. Shustov, 1998. Peoples of the Arctic: characteristics of human populations relevant to pollution issues. In: *AMAP Assessment Report: Arctic Pollution Issues* pp. 141–182, Arctic Monitoring and Assessment Programme, Oslo.
- Huntington, H., M. Boyle, G. Flowers, J. Weatherly, L. Hamilton, L. Hinzman, C. Gerlach, R. Zulueta, C. Nicolson and J. Overpeck, 2007. The influence of human activity in the Arctic on climate and climate impacts. *Climatic Change*, 82:77–92.
- Huschke, R.E., 1969. Arctic Cloud Statistics from 'Air-calibrated' Surface Weather Observations. Rand Corporation. Santa Monica, CA. 79 pp.
- Hwang, B.J. and D.G. Barber, 2006. Pixel-scale evaluation of SSM/I sea-ice algorithms in the marginal ice zone during early fall freeze-up. *Hydrological Processes*, 20:1909–1927.
- Hwang, B.J., A. Langlois, D.G. Barber and T.N. Papakyriakou, 2007a. On detection of the thermophysical state of landfast first-year sea ice using in-situ microwave emissions during spring melt. *Remote Sensing of Environment*, 111:148–159.
- Hwang, B.J., J.K. Ehn, D.G. Barber, R. Galley and T.C. Grenfell, 2007b. Investigations of newly formed sea ice in the Cape Bathurst polynya: 2 Microwave emission. *Journal of Geophysical Research*, 112:C05003.
- Hwang, B.J., J.K. Ehn and D.G. Barber, 2008. Impact of ice temperature on microwave emissivity of thin newly formed sea ice during fall freeze-up. *Journal of Geophysical Research*, 113:C02021.
- Iacozza, J. and D.G. Barber, 1999. Modelling the distribution of snow on sea ice using variograms. *Atmosphere-Oceans*, 37:21–51.
- ICES, 2008. Report of the Joint ICES/NAFO Working Group on Harp and Hooded Seals, 27–30 August 2008, Tromsø, Norway. ICES CM 2008/ACOM. 63 pp.
- IEA/OECD, 2009. World energy outlook 2009. 691 pp. International Energy Agency and Organisation for Economic Co-operation and Development.
- Ikeda, M., J. Wang and A. Makshtas, 2003. Importance of clouds to the decaying trend and decadal variability in the arctic ice cover. *Journal of the Meteorological Society of Japan*, 81:179–189.
- Ilulissat Declaration, 2008. Ilulissat Declaration: Arctic Ocean Conference Ilulissat, Greenland, 27–29 May 2008.
- IMO, 2009. Guidelines for ships operating in polar waters. Adopted on the 26th IMO Assembly, 23 November – 2 December 2009. International Maritime Organization.
- IMPVA, 2008. Arctic Offshore Technology Assessment of Exploration and Production Options for Cold Regions of the US Outer Continental Shelf. IMV Projects Atlantic Project No. C-0506-15, Technical Report No. TR-001. 365 pp. United States Department of the Interior Minerals Management Service.
- Inoue, J. and T. Kikuchi, 2007. Outflow of summertime Arctic sea ice observed by ice drifting buoys and its linkage with ice reduction and atmospheric circulation patterns. *Journal of the Meteorological Society of Japan*, 85:881–887.
- Instanes, A., O. Anisimov, L. Brigham, D. Goering, B.L. L.N. Khristalev and J.O. Larsen, 2005. Infrastructure: Buildings, Support Systems, and Industrial Facilities. In: *Arctic Climate Impact Assessment*, pp. 907–944, Cambridge University Press.
- Intrieri, J.M., C.W. Fairall, M.D. Shupe, P.O.G. Persson, E.L. Andreas, P.S. Guest and R.E. Moritz, 2002. An annual cycle of Arctic surface cloud forcing at SHEBA. *Journal of Geophysical Research*, 107: C8039.
- IPCC, 2007. Climate Change 2007: The Scientific Basis. Contribution of Working Group I to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change. Solomon, S., D. Qin, M. Manning, Z. Chen, M. Marquis, K.B. Averyt, M. Tignor and H.L. Miller (Eds). Cambridge University Press.
- Irons, D.B., T. Anker-Nilssen, A.J. Gaston, G.V. Byrd, K. Falk, G. Gilchrist, M. Hario, M. Hjærnquist, Y.V. Krasnov, A. Mosbech, B. Olsen, A. Petersen, J.B. Reid, G.J. Robertson, H. Strøm and K.D. Wohl, 2008. Fluctuations in circumpolar seabird populations linked to climate oscillations. *Global Change Biology*, 14:1455–1463.
- IUCN, 2008. IUCN Red List of Endangered Animals. International Union for Conservation of Nature.
- IWC, 2010. Report of the International Whaling Commission workshop on cetaceans and climate change. *Journal of Cetacean Research and Management*, 11:451–480.
- Jacobson, M.Z., 2004. Climate response of fossil fuel and biofuel soot, accounting for soot's feedback to snow and sea ice albedo and emissivity. *Journal of Geophysical Research*, 109:D21201.
- Jakobsson, T., 2003. Sea Ice Incidents in Icelandic Waters and their Monitoring. Polar Publishing.
- Jensen, Ø., 2008. Arctic shipping guidelines: towards a legal regime for navigation safety and environmental protection. *Polar Records*, 44:107–114.
- Jensen, S.K., C. Lydersen, K.M. Kovacs, K. Åsbakk and J. Aars, 2010. The prevalence of *Toxoplasma gondii* in polar bears and its marine mammalian prey; evidence for a marine transmission pathway? *Polar Biology*, 33:599–606.
- Joensen, J., 2008. Comparative feeding ecology of the sympatric cod fishes *Arctogadus glacialis* and *Boreogadus saida* in North-East Greenland evaluated from diet and stable isotope analysis. MS Thesis, 54 pp. University of Tromsø, Norway.
- Johannessen, O. and L. Pettersson, 2008. Arctic climate and shipping in Gottenmoeller. In: Tamnew, R. (Ed.). High North, High Stakes: Security, Energy, Transport, Environment, pp. 95–114, Fagbokforlaget, Bergen.
- Johannessen, O.M., E.V. Shalina and M.W. Miles, 1999. Satellite evidence for an arctic sea ice cover in transformation. *Science*, 286:1937–1939.
- Johannessen, O.M., L. Bengtsson, M.W. Miles, S.I. Kuzmina, V.A. Semenov, G.V. Alekseev, A.P. Nagurnyi, V.F. Zakharov, L.P. Bobylev, L.H. Pettersson, K. Hasselmann and H.P. Cattle, 2004. Arctic climate change: observed and modelled temperature and sea-ice variability. *Tellus*, 56A:328–341.
- Johnson, K., S. Solomon, D. Berry and P. Graham, 2003. Erosion progression and adaptation strategy in a northern coastal community. Paper presented at the 8th International Conference on Permafrost, pp. 489–494, 20–25 July 2003, Zurich, Switzerland.
- Johnson, M., S. Gaffigan, E. Hunke and R. Gerdes, 2007. A comparison of Arctic Ocean sea ice concentration among the coordinated AOMIP model experiments. *Journal of Geophysical Research*, 112:C04S11.
- Johnston, D.W., A.W. Friedlaender, L.G. Torres and D.M. Lavigne, 2005. Variation in sea ice cover on the east coast of Canada from 1969–2002: climate variability and implications for harp and hooded seals. *Climate Research*, 29:209–222.
- Jones, E.P. and A.R. Coote, 1981. Oceanic CO₂ produced by the precipitation of CaCO₃ from brines in sea ice. *Journal of Geophysical Research-Oceans*, 86:11041–11043.
- Jones, B., K. Hinkel, C. Arp and W. Eisner, 2008. Modern erosion rates and loss of coastal features and sites, Beaufort Sea coastline, Alaska. *Arctic*, 61:361–372.
- Jordan, R.E., E.L. Andreas and A.P. Makshtas, 1999. Heat budget of snow-covered sea ice at North Pole 4. *Journal of Geophysical Research-Oceans*, 104:7785–7806.
- Jung, T. and M. Hilmer, 2001. The link between the North Atlantic Oscillation and Arctic sea ice export. *Journal of Climate*, 14:3932–3943.
- Juul-Pedersen, T., C. Miche, M. Gosselin and L. Seuthe, 2008. Seasonal changes in the sinking export of particulate material under first-year sea ice on the Mackenzie Shelf (western Canadian Arctic). *Marine Ecology Progress Series*, 353:13–25.
- Kampp, K., K. Falk and C.E. Pedersen, 2000. Breeding density and population of little auks (*Alle alle*) in a Northwest Greenland colony. *Polar Biology*, 23:517–521.
- Karnovsky, N.J. and G.L. Hunt, Jr., 2002. Estimation of carbon flux to dovekies (*Alle alle*) in the North Water. *Deep Sea Research II*, 49:5117–5130.
- Karnovsky, N.J., S. Kwasniewski, J.M. Weslawski, W. Walkusz and A. Beszczynska-Moller, 2003. Foraging behavior of little auks in a heterogeneous environment. *Marine Ecology Progress Series*, 253:289–303.
- Karnovsky, N.J., K.A. Hobson, S. Iverson, G.L. Hunt, Jr. and L.B. Spear, 2008. Seasonal changes in food habits of seabirds in the North Water Polynya: a multiple-indicator approach using stomach content, stable isotope and fatty-acid analyses. *Marine Ecology Progress Series*, 357:291–299.
- Karnovsky, N.J., K.A. Hobson, Z.W. Brown and G.L. Hunt, Jr., 2009.

- Distribution and diet of ivory gulls (*Pagophila eburnea*) in the North Water Polynya. *Arctic*, 62:65–74.
- Kaschner, K., R. Watson, A.W. Trites and D. Pauly, 2006. Mapping worldwide distributions of marine mammal species using a relative environmental suitability (RES) model. *Marine Ecology Progress Series*, 316:285–310.
- Kattner, G. and G. Budéus, 1997. Nutrient status of the Northeast Water Polynya. *Journal of Marine Systems*, 10:185–197.
- Kattsov, V. and E. Källén, 2005. Future climate change: modelling and scenarios for the Arctic. In: *Arctic Climate Impact Assessment*, pp. 99–150, Cambridge University Press.
- Kaufman, D.S., D.P. Schneider, N.P. McKay, C.M. Ammann, R.S. Bradley, K.R. Briffa, G.H. Miller, B.L. Otto-Bliesner, J.T. Overpeck, B.M. Vinther and A.L.K.P. Members, 2009. Recent warming reverses long-term Arctic cooling. *Science*, 325:1236.
- Kauker, F., T. Kaminski, M. Karcher, R. Giering, R. Gerdes and M. Voßbeck, 2009. Adjoint analysis of the 2007 all time Arctic sea-ice minimum. *Geophysical Research Letters*, 36:L03707.
- Kay, J.E. and A. Gettelman, 2009. Cloud influence on and response to seasonal Arctic sea ice loss. *Journal of Geophysical Research*, 114:D18204.
- Kay, J.E., T.L. L'Ecuyer, A. Gettelman, G. Stephens and C. O'Dell, 2008. The contribution of cloud and radiation anomalies to the 2007 Arctic sea ice extent minimum. *Geophysical Research Letters*, 35:L08503.
- Kedra, M., M. Włodarska-Kowalczyk and J.M. Weslawski, 2010. Decadal change in macrobenthic soft-bottom community structure in a high Arctic fjord (Kongsfjorden, Svalbard). *Polar Biology*, 33:1–11.
- Kelly, B.P., 2001. Climate change and ice breeding pinnipeds. In: Walther, G.-R., C. Burga and P. Edwards, (Eds.). 'Fingerprints' of climate change: adapted behaviour and shifting species ranges, pp. 43–55, Kluwer Academic/Plenum Publishers.
- Keskitalo, E. and A. Kulyasova, 2009. The role of governance in community adaptation to climate change. *Polar Research*, 28:60–70.
- Khon, V.C., I.I. Mokhov, M. Latif, V.A. Semenov and W. Park, 2010. Perspectives of Northern Sea Route and Northwest Passage in the twenty-first century. *Climate Change*, 100:757–768.
- Kingsley, M.C.S., I. Stirling and W. Calvert, 1985. The distribution and abundance of seals in the Canadian High Arctic, 1980–1982. *Canadian Journal of Fisheries and Aquatic Sciences*, 41:1189–1210.
- Kirchman, D.L., V. Hill, M.T. Cottrell, R. Gradinger, R.R. Malmstrom and A. Parker, 2009. Standing stocks, production, and respiration of phytoplankton and heterotrophic bacteria in the western Arctic Ocean. *Deep Sea Research II*, 56:1237–1248.
- Kitaysky, A.S. and E.G. Golubova, 2000. Climate change causes contrasting trends in reproductive performance of planktivorous and piscivorous alcids. *Journal of Animal Ecology*, 69:248–262.
- Koç, N., B. Njåstad, R. Armstrong, R. Corell, D. Jensen, K. Leslie, A. Rivera, Y. Tandong and W. J.-G. (Eds.), 2009. Melting snow and ice: a call for action. 51 pp. Centre for Ice, Climate and Ecosystems, Norwegian Polar Institute.
- Koch, D. and J. Hansen, 2005. Distant origins of Arctic black carbon: A Goddard Institute for Space Studies Model Experiment. *Journal of Geophysical Research*, 110:D042404.
- Koenigk, T., U. Mikolajewicz, H. Haak and J. Jungclaus, 2006. Variability of Fram Strait sea ice export: causes, impacts and feedbacks in a coupled climate model. *Climate Dynamics*, 26:17–34.
- Kofinas, G., S. Herman and C. Meek, 2007. Novel problems require novel solutions: Innovation as an outcome of adaptive co-management. In: Armitage, D., F. Berkes and N. Doubleday (Eds.). *Adaptive Co-Management: Collaboration, Learning and Multi-Level Governance*, pp. 249–267, University of British Columbia Press.
- Koivurova, T. and K. Hossain, 2008. Offshore Hydrocarbon: Current Policy Context in the Marine Arctic, pp. 1–43.
- Kolstad, E. and T. Bracegirdle, 2008. Marine cold-air outbreaks in the future: an assessment of IPCC AR4 model results for the Northern Hemisphere. *Climate Dynamics*, 30:871–885.
- Komuro, Y. and H. Hasumi, 2003. Effects of surface freshwater flux induced by sea ice transport on the global thermohaline circulation. *Journal of Geophysical Research*, 108:C3047.
- Kovacs, A., 1983. Shore Ice Ride-up and Pile-up Features. Part 1: Alaska's Beaufort Sea Coast. CRREL report 83-9, pp. US Army Corps of Engineers, Cold Regions Research & Engineering Laboratory.
- Kovacs, K.M., 2009a. Bearded seal. In: Perrin, W., B. Würsig and J. Thewissen, *Encyclopedia of Marine Mammals*, 2nd Edition, pp. 97–101, Academic Press.
- Kovacs, K.M., 2009b. Hooded seal. In: Perrin, W., B. Würsig and J. Thewissen, *Encyclopedia of Marine Mammals*, 2nd Edition, pp. 569–572, Academic Press.
- Kovacs, K.M. and C. Lydersen (Eds.), 2006. *Birds and Mammals of Svalbard*. 203 pp. Polarhåndbok No.13. Norwegian Polar Institute.
- Kovacs, K.M. and C. Lydersen, 2008. Climate change impacts on seals and whales in the North Atlantic Arctic and adjacent shelf seas. *Science Progress*, 91:117–150.
- Kovacs, A. and D. Sodhi, 1980. Shore ice pile-up and ride-up: field observations, models, theoretical analyses. *Cold Regions Science and Technology*, 2:209–288.
- Krupnik, I., C. Aporta, S. Gearheard, G. Laidler and L. Kielsen-Holm (Eds.), 2010. *SIKU: Knowing Our Ice: Documenting Inuit Sea Ice Knowledge and Use*. 300 pp. Springer.
- Kuzmin, S.A., S.M. Akhtar and D.T. Menis, 1998. The first findings of snow crab *Chionoecetes opilio* (Decapoda, Majidae) in the Barents Sea. *Zoologicheskij Zhurnal*, 77:489–491.
- Kwok, R., 2002. Sea ice concentration estimates from satellite passive microwave radiometry and openings from SAR ice motion. *Geophysical Research Letters*, 29:1311.
- Kwok, R., 2007. Near zero replenishment of the Arctic multiyear sea ice cover at the end of 2005 summer. *Geophysical Research Letters*, 34:L05501.
- Kwok, R., 2008. Outflow of Arctic sea ice into the Greenland and Barents Seas: 1979–2007. *Journal of Climate*, 22:2438–2457.
- Kwok, R. and G.F. Cunningham, 2008. ICESat over Arctic sea ice: Estimation of snow depth and ice thickness. *Journal of Geophysical Research*, 113:C08010.
- Kwok, R. and D. Rothrock, 1999. Variability of Fram Strait ice flux and North Atlantic Oscillation. *Journal of Geophysical Research-Oceans*, 104:5177–5189.
- Kwok, R. and D.A. Rothrock, 2009. Decline in Arctic sea ice thickness from submarine and ICESat records: 1958 – 2008. *Geophysical Research Letters*, 36:L15501.
- Kwok, R., H.J. Zwally and D. Yi, 2004. ICESat observations of Arctic sea ice: A first look. *Geophysical Research Letters*, 31:L16401.
- Kwok, R., G.F. Cunningham, H.J. Zwally and D. Yi, 2007. Ice, Cloud, and land Elevation Satellite (ICESat) over Arctic sea ice: Retrieval of freeboard. *Journal of Geophysical Research*, 112:C12013.
- Kwok, R., G.F. Cunningham, M. Wensnahan, I. Rigor, H.J. Zwally and D. Yi, 2009. Thinning and volume loss of the Arctic Ocean sea ice cover: 2003–2008. *Journal of Geophysical Research*, 114:C07005.
- Kwok, R., L. Toudal Pedersen, P. Gudmandsen and S.S. Pang, 2010. Large sea ice outflow into the Nares Strait in 2007. *Geophysical Research Letters*, 37:L03502.
- L'Heveder, B. and M.-N. Houssais, 2001. Investigating the variability of the Arctic sea ice thickness in response to a stochastic thermodynamic atmospheric forcing. *Climate Dynamics*, 17:107–125.
- Labansen, A.L., C. Lydersen, T. Haug and K.M. Kovacs, 2007. Spring diet of ringed seals (*Pusa hispida*) from north-western Spitsbergen, Norway. *ICES Journal of Marine Science*, 64:1246–1256.
- Lack, D., B. Lerner, C. Granier, T. Baynard, E. Lovejoy, P. Massoli, A.R. Ravishankara and E. Williams, 2008. Light absorbing carbon emissions from commercial shipping. *Geophysical Research Letters*, 35:L13815.
- Laidler, G., 2006. Inuit and scientific perspectives on the relationship between sea-ice and climate change: The ideal complement? *Climatic Change*, 78:407–444.
- Laidler, G. and T. Ikummaq, 2008. Human geographies of sea ice: freeze/thaw processes around Igloolik, Nunavut, Canada. *Polar Records*, 44:127–153.
- Laidler, G., J.D. Ford, W.A. Gough, T. Ikummaq, A.S. Gagnon, S. Kowal, K. Qrunal and C. Irngaut, 2009. Travelling and hunting in a changing Arctic: Assessing Inuit vulnerability to sea ice change in Igloolik, Nunavut. *Climatic Change*, 94:363–397.
- Laidre, K.L. and M.P. Heide-Jørgensen, 2005a. Winter feeding intensity of narwhales (*Monodon monoceros*). *Marine Mammal Science*, 21:45–57.
- Laidre, K.L. and M.P. Heide-Jørgensen, 2005b. Arctic sea ice trends and narwhal vulnerability. *Biological Conservation*, 121:509–517.

- Laidre, K.L., I. Stirling, L.F. Lowry, Ø. Wiig, M.P. Heide-Jørgensen and S.F. Ferguson, 2008. Quantifying the sensitivity of arctic marine mammals to climate-induced habitat change. *Ecological Applications*, 18:S97–S125.
- Lavigne, D.M., 2009. Harp seal. In: Perrin, W., B. Würsig and J. Thewissen, *Encyclopedia of Marine Mammals*, 2nd Edition, pp. 543–546, Academic Press.
- Lavoie, D., K. Denman and C. Michel, 2005. Modelling ice algae growth and decline in a seasonally ice-covered region of the Arctic Ocean (Resolute Passage, Canadian Archipelago). *Journal of Geophysical Research*, 110:C11009.
- Law, K.S. and A. Stohl, 2007. Arctic air pollution: origins and impacts. *Science*, 315:1537–1540.
- Laxon, S., N. Peacock and D. Smith, 2003. High interannual variability of sea ice thickness in the Arctic region. *Nature*, 425:947–950.
- Le Romancer, M., M. Gaillard, C. Geslin and D. Prieur, 2007. Viruses in extreme environments. *Reviews in Environmental Science and Biotechnology*, 6:17–31.
- Leck, C. and K. Bigg, 2008. A modified aerosol–cloud–climate feedback hypothesis. *Environmental Chemistry*, 4:400–403.
- Leck, C., M. Norman, E.K. Bigg and R. Hillamo, 2002. Chemical composition and sources of the high Arctic aerosol relevant for fog and cloud formation. *Journal of Geophysical Research-Atmosphere*, 107:4135.
- Lee, S.H. and T.E. Whitledge, 2005. Primary and new production in the deep Canada Basin during summer 2002. *Polar Biology*, 12:190–197.
- Legendre, L., S.F. Ackley, G.S. Dieckmann, B. Gulliksen, R. Horner, T. Hoshiai, I.A. Melnikov, W.S. Reebergh, M. Spindler and C.W. Sullivan, 1992. Ecology of sea ice biota. 2 Global significance. *Polar Biology*, 12:429–444.
- Leichenko, R. and K. O'Brien, 2009. Mapping double exposure to climate change and trade liberalization as an awareness raising tool. In: Patt, A.G., D. Schröter, R.J.T. Klein and A.C. de la Vega-Leinert (Eds.). *Assessing Vulnerability to Global Environmental Change: Making Research Useful for Adaptation Decision Making and Policy*. Earthscan Publications, London.
- Levermann, A., J. Mignot, S. Nawrath and S. Rahmstorf, 2007. The role of northern sea ice cover for the weakening of the thermohaline circulation under global warming. *Journal of Climate*, 20:4160–4171.
- Li, W.K., F.A. McLaughlin, C. Lovejoy and E. Carmack, 2009. Smallest algae thrive as the Arctic Ocean freshens. *Science*, 326:539.
- Lindholt, L. and S. Glomsrød, 2009. Future production of petroleum in the Arctic under alternative oil prices. In: Glomsrød, S. and J. Aslaksen (Eds.). *The Economy of the North 2008*, pp. 69–74, Statistics Norway.
- Lindsay, R.W., 1998. Temporal variability of the energy balance of thick Arctic pack ice. *Journal of Climate*, 11:313–333.
- Lindsay, R.W. and A.P. Makshtas, 2003. Air-sea interaction in the presence of the Arctic pack ice. In: Bobylev, L., K. Kondratyev and O.M. Johannessen, (Eds.). *Arctic Environment Variability in the Context of Global Change*, pp. 203–236, Praxis Publishing Ltd..
- Lindsay, R.W. and J. Zhang, 2005. The dramatic thinning of arctic sea ice, 1988–2003. Have we passed a tipping point? *Journal of Climate*, 18:4879–4894.
- Lindsay, R.W., J. Zhang, A.J. Schweiger and M.A. Steele, 2008. Seasonal predictions of ice extent in the Arctic Ocean. *Journal of Geophysical Research*, 113:C02023.
- Lindsay, R.W., J. Zhang, A.J. Schweiger, M.A. Steele and H. Stern, 2009. Arctic sea ice retreat in 2007 follows thinning trend. *Journal of Climate*, 22:165–176.
- Liu, Y., J. Key and X. Wang, 2008. The influence of changes in cloud cover on recent surface temperature trends in the Arctic. *Journal of Climate*, 21:705–715.
- Liu, Y., J. Key and X. Wang, 2009. The influence of changes in sea ice concentration and cloud cover 2661 on recent Arctic surface temperature trends. *Geophysical Research Letters*, 36:20.
- Livescience (2009) Time-Lapse Photos Show Dramatic Erosion of Alaska Coast. Posted 14 December 2009, accessed 23 March 2010. www.livescience.com/environment/091214-agu-arctic-climate-warming.html.
- Loeng, H., K. Brander, E. Carmack, S. Denisenko, K. Drinkwater, B. Hansen, K. Kovacs, P. Livingston, F. McLaughlin and E. Sakshaug, 2005. Marine systems. In: *Arctic Climate Impact Assessment*, pp. 453–538, Cambridge University Press.
- Lønne, O.J. and G.W. Gabrielsen, 1992. Summer diet of seabirds feeding in sea-ice-covered waters near Svalbard. *Polar Biology*, 12:685–692.
- Lønne, O.J. and B. Gulliksen, 1989. Size, age, and diet of polar cod, *Boreogadus saida* (Lepechin 1773), in ice covered waters. *Polar Biology*, 9:187–191.
- Loretsen, S.-H. and S. Christensen-Dalsgaard, 2010. The Norwegian national monitoring programme for seabirds. NINA Report. 439, 53 pp. Norwegian Institute for Nature Research.
- Loseto, L.L., G.A. Stern, T.L. Connelly, D. Deibel, B. Gemmill, A. Prokopowicz, L. Fortier and S.H. Ferguson, 2009. Summer diet of beluga whales inferred by fatty acid analysis of the eastern Beaufort Sea food web. *Journal of Experimental Marine Biology and Ecology*, 374:12–18.
- Lovejoy, C., R. Massana and C. Pedrós-Alí, 2006. Diversity and distribution of marine microbial eukaryotes in the Arctic Ocean and adjacent seas. *Applied and Environmental Microbiology*, 72:3085–3095.
- Lovvorn, J.R., S.E. Richman, J.M. Grebmeier and L.W. Cooper, 2003. Diet and body condition of spectacled eiders wintering in pack ice of the Bering Sea. *Polar Biology*, 26:259–267.
- Lovvorn, J.R., J.M. Grebmeier, L.W. Cooper, J.K. Bump and S.E. Richman, 2009. Modeling marine protected areas for threatened eiders in a climatically changing Bering Sea. *Ecological Applications*, 19:1596–1613.
- Lowry, L.F., 1993. Foods and feeding ecology. In: Burns, J.J., J. Montaguie and C. Cowles (Eds.). *The bowhead whale*, pp. 201–238, Society for Marine Mammalogy.
- Lowry, L. and P. Boveng, 2009. Ribbon seal. In: Perrin, W., B. Würsig and J. Thewissen, *Encyclopedia of Marine Mammals*, 2nd Edition, pp. 955–958, Academic Press.
- Lukovich, J.V. and D.G. Barber, 2006. Atmospheric controls on sea ice motion in the southern Beaufort Sea. *Journal of Geophysical Research*, 111:D18103.
- Lukovich, J.V., M. Asplin and D.G. Barber, 2009. Atmospheric forcing of the Beaufort Sea ice gyre: Surface-stratosphere coupling. *Journal of Geophysical Research-Oceans*, 114: C00A03.
- Lüthje, M., D.L. Feltham, P.D. Taylor and M.G. Worster, 2006. Modelling the summertime evolution of sea-ice melt ponds. *Journal of Geophysical Research*, 111:C02001.
- Lydersen, C. and K.M. Kovacs, 1999. Behaviour and energetics of ice-breeding, North Atlantic phocid seals during the lactation period. *Marine Ecology Progress Series*, 187:265–281.
- Lydersen, C., A.R. Martin, K.M. Kovacs and I. Gjertz, 2001. Summer and autumn movements of white whales (*Delphinapterus leucas*) in Svalbard, Norway. *Marine Ecology Progress Series*, 219:265–274.
- Macdonald, R., 2007. Contaminants, global change and cold regions. In: Ørbæk, J.B. (Ed.). *Arctic Alpine Ecosystems and People in a Changing Environment*, pp. 305–327, Springer.
- Macdonald, R., L.A. Barrie, T.F. Bidleman and 26 others, 2000. Contaminants in the Canadian Arctic: 5 years of progress in understanding sources, occurrence and pathways. *Science of the Total Environment*, 254:93–234.
- Macdonald, R.W., T. harner, J. Fyfe, H. Loeng and T. Weingartner, 2003. AMAP Assessment 2002: The Influence of Global Change on Contaminant Pathways to, within, and from the Arctic. xi, 65 pp. Arctic Monitoring and Assessment Programme, Oslo, Norway.
- Macdonald, R., T. Harner and J. Fy, 2005. Recent climate change in the Arctic and its impact on contaminant pathways and interpretation of temporal trend data. *Science of the Total Environment*, 342:5–86.
- MacGarvin, M. and M.P. Simmonds, 1996. Whales and climate change. In: Simmonds, M. and J. Hutchinson (Eds.). *The conservation of whales and dolphins – Science and Practice*, pp. 321–332, John Wiley and Sons.
- Mahoney, A., H. Eicken, A.G. Gaylor and L. Shapiro, 2007. Alaska landfast sea ice: Links with bathymetry and atmospheric circulation. *Journal of Geophysical Research*, 112:C02001.
- Mahoney, A.R., R.G. Barry, V. Smolyanitsky and F. Fetterer, 2008. Observed sea ice extent in the Russian Arctic, 1933–2006. *Journal of Geophysical Research*, 113:C11005.
- Makabe, R., H. Hattori, M. Sampei, Y. Ota, M. Fukuchi, L. Fortier and S. Sasaki, 2009. Regional and seasonal variability of zooplankton collected using sediment traps in the southeastern Beaufort Sea, Canadian Arctic. *Polar Biology*, 33:257–270.
- Makshtas, A.P., 1991. The Heat Budget of Arctic Ice in the Winter. 77 pp. International Glaciological Society, Cambridge.
- Makshtas, A.P., E. Andreas, P. Syvashchennikov and V. Timachev, 1999. Accounting for clouds in sea ice models. *Atmospheric Research*, 52:77–113.

- Makshtas, A., S. Shoutilin and E. Andreas, 2003. Possible dynamic and thermal causes for the recent decrease in sea ice in the Arctic. *Journal of Geophysical Research*, 108:C3232.
- Makshtas, A.P., D. Atkinson, M. Kulakov, S. Shutilin, R. Krishfield and A. Proshutinsky, 2007. Atmospheric forcing validation for modeling the central Arctic. *Geophysical Research Letters*, 34:L20706.
- Mallory, M.L., J.A. Akearok and A.J. Gaston, 2009. Status of high arctic black-legged kittiwake (*Rissa tridactyla*) colonies in Barrow Strait, Nunavut, Canada. *Arctic*, 62:96–101.
- Markham, A., 1996. Potential impacts of climate change on ecosystems: a review of implications for policymakers and conservation biologists. *Climate Research*, 6:179–191.
- Markus, T., J.C. Stroeve and J. Miller, 2009. Recent changes in Arctic sea ice melt onset, freeze-up, and melt season length. *Journal of Geophysical Research*, 114:C12024.
- Martin, T. and R. Gerdes, 2007. Sea ice drift variability in Arctic Ocean Model Intercomparison Project models and observations. *Journal of Geophysical Research*, 112:C04S10.
- Martin, S., R. Drucker, R. Kwok and B. Holt, 2004. Estimation of the thin ice thickness and heat flux for the Chukchi Sea Alaskan coast polynya from Special Sensor Microwave/Image data, 1990–2001. *Journal of Geophysical Research*, 109:C10012.
- Martin, P., J.L. Jenkins, F.J. Adams, M.T. Jorgenson, A.C. Matz, D.C. Payer, P.E. Reynolds, A.C. Tidwell and J.R. Zelenak, 2009. Wildlife response to environmental Arctic change: Predicting future habitats of Arctic Alaska. Report from the Wildlife Response to Environmental Arctic Change (WildREACH), Predicting Future Habitats of Arctic Alaska Workshop, 17–18 November 2008, Fairbanks, Alaska. 138 pp.
- Martinson, D.G., P. Killworth and A. Gordon, 1981. A convective model for the Weddell Polynya. *Journal of Physical Oceanography*, 11:466–488.
- Maslanik, J. and J. Stroeve, 1999, updated daily. Near-Real-Time DMSP SSM/I Daily Polar Gridded Sea Ice Concentrations, 2009–2010. National Snow and Ice Data Center, Boulder, CO.
- Maslanik, J.A., C. Fowler, J. Stroeve, S. Robot, J. Zwally, D. Yi and W. Emery, 2007. A younger, thinner Arctic ice cover: Increased potential for rapid, extensive sea-ice loss. *Geophysical Research Letters*, 34:L24501.
- Mathias, J., B. Ayles, S. Blarney, T. Charles, H. Fast and P. Irniq, 2008. Arctic Change and Coastal Communities: Overview of the Coastal Zone Canada Conference, Tuktoyaktuk, August 2006. *Arctic*, 61: iii–xi.
- Maykut, G.A. and N. Untersteiner, 1971. Some results from a time dependent thermodynamic model of sea ice. *Journal of Geophysical Research-Oceans*, 76:1550–1575.
- Maykut, G.A. and M. McPhee, 1995. Solar heating of the Arctic mixed layer. *Journal of Geophysical Research-Oceans*, 100:24691–24703.
- McBean, G., G.V. Alekseev, D. Chen, E. Forland, J. Fyfe, P.Y. Groisman, R. King, H. Melling, R. Vose and P.H. Whitfield., 2005. Arctic climate: past and present. Arctic Climate Impact Assessment, pp. 22–60, Cambridge University Press.
- McCarthy, J., R. Corell, N.E. Selin, S. Fox, G. Hovelsrud-Broda, S.D. Mathiesen, C. Polsky, H. Selin and N.J.C. Tyler, 2005. Climate change in the context of multiple stressors and resilience. Arctic Climate Impact Assessment, pp. 945–988, Cambridge University Press.
- McIlgorm, A., S. Hanna, G. Knapp, P. Le Floch, F. Millerd and M. Pan, 2009. How will climate change alter fishery governance? Insights from seven international case studies. *Marine Policy*, 34:170–177.
- McKinney, M.A., E. Peacock and R.J. Letcher, 2009. Sea ice-associated diet change increases the levels of chlorinated and brominated contaminants in polar bears. *Environmental Science and Technology*, 43:4334–4339.
- McLaren, A.S., R.G. Barry and R.H. Bourke, 1990. Could Arctic ice be thinning? *Nature*, 345:762.
- McLaren, A.S., J. Walsh, R.H. Bourke, R. Weaver and W. Wittmann, 1992. Variability in sea-ice thickness over the North Pole from 1977 to 1990. *Nature*, 358:224–226.
- McMahon, K.W., W.G. Ambrose, Jr., B.J. Johnson, M.-Y. Sun, G.R. Lopez, C. Clough and M.L. Carroll, 2006. Benthic community response to ice algae and phytoplankton in Ny Alesund, Svalbard. *Marine Ecology Progress Series*, 310:1–14.
- McMichael, A., D.H. Campbell-lendrum, C.F. Corvalen, K.L. Ebi, A. Githeki, J.D. Scheraga and A. Woodward, 2003. Climate change and human health: Risks and responses. xi, 322 p. pp. World Health Organization.
- Meier, W.N., 2005. Comparison of passive microwave ice concentration algorithm retrievals with AVHRR imagery in Arctic peripheral seas. *IEEE Transactions on Geoscience and Remote Sensing*, 43:1324–1337.
- Meier, W., F. Fetterer, K. Knowles, M. Savoie and M. Brodzik, 2006, updated daily. Sea ice concentrations from Nimbus-7 SMMR and DMSP SSM/I passive microwave data, 2008–2010. National Snow and Ice Data Center, Boulder, CO. Digital media.
- Meier, W.N., J. Stroeve and F. Fetterer, 2007. Whither Arctic sea ice? A clear signal of decline regionally, seasonally and extending beyond the satellite record. *Annals of Glaciology*, 46:428–434.
- Meiners, K., C. Krembs and R. Gradinger, 2008. Exopolymer particles: microbial hotspots of enhanced bacterial activity in Arctic fast ice (Chukchi Sea). *Aquatic Microbial Ecology*, 52:195–207.
- Melling, H., 2002. Sea ice of the northern Canadian Arctic Archipelago. *Journal of Geophysical Research*, 107:C3181.
- Melling, H., D.A. Riedel and Z. Gedalof, 2005. Trends in the draft and extent of seasonal pack ice, Canadian Beaufort Sea. *Geophysical Research Letters*, 32:L24501.
- Melnikov, I.A. and L.L. Bondarchuk, 1987. Ecology of the mass aggregations of colonial diatom algae under the Arctic drifting sea ice. *Oceanology*, 27:317–321.
- Melnikov, I.A., L.G. Kolosova, H.E. Welch and L.S. Zhitina, 2002. Sea ice biological communities and nutrient dynamics in the Canadian Basin of the Arctic Ocean. *Deep Sea Research I*, 49:1623–1649.
- Metcalf, V. and M. Robards, 2008. Sustaining a healthy human-walrus relationship in a dynamic environment: challenges for co-management. *Ecological Applications*, 18:S148–S156.
- Michel, C., L. Legendre, R.G. Ingram, M. Gosselin and M. Levasseur, 1996. Carbon budget of ice algae under FYI: evidence of a significant transfer to zooplankton grazers. *Journal of Geophysical Research-Oceans*, 101:18345–18360.
- Michel, C., T.G. Nielsen, M. Gosselin and C. Nozais, 2002. Significance of sedimentation and grazing by ice micro- and meiofauna for carbon cycling in annual sea ice (Northern Baffin Bay). *Aquatic Microbial Ecology*, 30: 57–68.
- Michel, C., R.G. Ingram and L. Harris, 2006. Variability of oceanographic and ecological processes in the Canadian Arctic Archipelago. *Progress in Oceanography*, 72:379–401.
- Mikkelsen, D., S. Rysgaard and R.N. Glud, 2008. Microalgal composition and primary production in Arctic sea ice: a seasonal study from Kobbefjord (Kangerluarsunnguag), West Greenland. *Marine Ecology Progress Series*, 368:65–74.
- Millennium Ecosystem Assessment, 2005. Ecosystems and Human Well-being: Synthesis. 137 pp. Island Press.
- Mock, T. and R. Gradinger, 1999. Determination of Arctic ice algal production with a new in situ incubation technique. *Marine Ecology Progress Series*, 177:15–26.
- Molenaar, E. and R. Corell, 2009a. Arctic Shipping. 28 pp. Background Document, Arctic Transform: Transatlantic Policy Options for Supporting Adaptation in the Marine Environment.
- Molenaar, E. and R. Corell, 2009b. Arctic Fisheries. 27 pp. Background Document, Arctic Transform: Transatlantic Policy Options for Supporting Adaptation in the Marine Environment.
- Moline, M.A., N.J. Karnovsky, Z. Brown, G.J. Divoky, T.K. Frazer, C.A. Jacoby, J.J. Torres and W.R. Fraser, 2008. High latitude changes in ice dynamics and their impact on polar marine ecosystems. *Annals of the New York Academy of Sciences*, 1134:534–540.
- Moore, S.E., 2008a. Marine mammals as ecosystem sentinels. *Journal of Mammalogy* 89:534–540.
- Moore, S.E., 2008b. Climate change. In: Perrin, W., B. Würsig and J. Thewissen, *Encyclopedia of Marine Mammals*, 2nd Edition, pp. 238–241, Academic Press.
- Moore, S.E. and H.P. Huntington, 2008. Arctic marine mammals and climate change: impacts and resilience. *Ecological Applications*, 18:S157–S165.
- Moore, S.E. and K.L. Laidre, 2006. Trends in sea ice cover within habitats used by bowhead whales in the western Arctic. *Journal of Applied Ecology*, 16:932–944.
- Moore, S.E., J.M. Grebmeier and J.R. Davies, 2003. Grey whale distribution relative to forage habitat in the northern Bering Sea: current conditions and retrospective summary. *Canadian Journal of Zoology*, 81:734–742.
- Moore, S.E., J.C. George, G. Sheffield, J. Bacon and C.J. Ashjian, 2010. Bowhead whale distribution and feeding near Barrow, Alaska in late summer 2005–06. *Arctic*, 63:195–205.
- Moss, J.H., E.V. Farley, Jr., A.M. Feldmann and J.N. Ianelli, 2009. Spatial distribution, energetic status, and food habits of Eastern Bering Sea

- age-0 walleye pollock. *Transactions of the American Fisheries Society*, 138:497–505.
- Mueter, F. and M. Litzow, 2008. Sea ice retreat alters the biogeography of the Bering Sea continental shelf. *Ecological Applications*, 18:309–320.
- Mueter, F.J., C. Broms, K.F. Drinkwater, K.D. Friedland, J.A. Hare, G.L. Hunt, Jr., W. Melle and M. Taylor, 2009. Ecosystem responses to recent oceanographic variability in high-latitude Northern Hemisphere ecosystems. *Progress in Oceanography*, 81:93–110.
- Müller, J., G. Massé, R. Stein and S.T. Belt, 2009. Variability of sea-ice conditions in the Fram Strait over the past 30,000 years. *Nature Geoscience*, 2:772–776.
- Mundy, C.J., J. Ehn, D.G. Barber and C. Michel, 2007. Influence of snow cover and algae on the spectral dependence of transmitted irradiance through Arctic landfast first-year sea ice. *Journal of Geophysical Research*, 112:C03007.
- Mundy, C.J., M. Gosselin, J. Ehn, Y. Gratton, A. Rossnagel, D.G. Barber, J. Martin, J.E. Tremblay, M. Palmer, K.R. Arrigo, G. Darnis, L. Fortier, B. Else and T. Papakyriakou, 2009. Contribution of under-ice primary production to an ice-edge upwelling phytoplankton bloom in the Canadian Beaufort Sea. *Geophysical Research Letters*, 36:L17601.
- NCP, 2003. Canadian Arctic Contaminants Assessment Report II: Sources, Occurrence, Trends and Pathways in the Physical Environment. Ottawa. Department of Indian Affairs and Northern Development, Northern Contaminants Program.
- Nelson, R.J., E.C. Carmack, F.A. McLaughlin and G.A. Cooper, 2009. Penetration of Pacific zooplankton into the western Arctic Ocean tracked with molecular population genetics. *Marine Ecology Progress Series*, 381:129–138.
- Nerini, M.K., H.W. Braham, W.M. Marquette and D.J. Rugh, 1984. Life history of the bowhead whale, *Balaena mysticetus* (Mammalia: Cetacea). *Journal of Zoology*, 204:443–468.
- Nghiêm, S.V., 2003. Arctic Field Validation Campaign for Satellite Remote Sensing of Sea Ice. 44 pp. Jet Propulsion Laboratory, Pasadena, CA.
- Nghiêm, S.V. and G. Neumann, 2007. Arctic sea-ice monitoring, 2007. McGraw-Hill Yearbook of Science and Technology, 2007:12–15.
- Nghiêm, S.V., M.V. Woert and G. Neumann, 2005. Rapid formation of a sea ice barrier east of Svalbard. *Journal of Geophysical Research*, 110:C11013.
- Nghiêm, S.V., Y. Chao, G. Neumann, P. Li, D.K. Perovich, T. Street and P. Clemente-Colón, 2006. Depletion of perennial sea ice in the East Arctic ocean. *Geophysical Research Letters*, 33:L17501.
- Nghiêm, S.V., I.G. Rigor, D.K. Perovich, P. Clemente-Colón, J. Weatherly and G. Neumann, 2007. Rapid reduction of Arctic perennial sea ice. *Geophysical Research Letters*, 4:L19504.
- Nghiêm, S.V., I.G. Rigor, P. Clemente-Colón, D.K. Perovich, J. Richter-Menge, Y. Chao, G. Neumann and M. Ortmeier, 2008. Recent state of Arctic sea ice. *Eos, Transactions, American Geophysical Union*, 89:C44A-01.
- Nicolaus, M., C. Haas and J. Bareiss, 2003. Observations of superimposed ice formation at melt-onset on fast ice on Kongsfjorden, Svalbard. *Physics and Chemistry of the Earth*, 28:1241–1248.
- Nielsen, M.R., 2009. Is climate change causing the increasing narwhal (*Monodon monoceros*) catches in Smith Sound, Greenland? *Polar Research*, 28:238–245.
- Noongwook, G., Native Village of Savoonga, Native Village of Gambell, H. Huntington and J. George, 2007. Traditional knowledge of the bowhead whale (*Balaena mysticetus*) around St. Lawrence Island, Alaska. *Arctic*, 60:47–54.
- Notz, D., 2010. The big melt: Is the loss of Arctic sea ice unstoppable. *Geophysical Research Abstracts*, 12:EGU2010-15023.
- Noyes, P.D., M.K. McElwee, H.D. Miller, B.W. Clark, L.A. Van Tiem, K.C. Walcott, K.N. Erwin and E.D. Levin, 2009. The toxicology of climate change: Environmental contaminants in a warming world. *Environment International*, 35:971–976.
- NPFMC, 2009. Stock assessment and fishery evaluation report for the groundfish resources of the Bering Sea/Aleutian Islands regions. North Pacific Fishery Management Council.
- Nuttall, M., F. Berkes, B. Forbes, G. Kofinas, T. Vlassova and G. Wenzel, 2005. Hunting, herding, fishing, and gathering: Indigenous peoples and renewable resource use in the arctic. In: *Arctic Climate Impact Assessment*, pp. 649–690, Cambridge University Press.
- O’Corry-Crowe, G., 2008. Climate change and the molecular ecology of arctic marine mammals. *Ecological Applications*, 18:S56–S76.
- O’Corry-Crowe, G., 2009. Beluga whale. In: Perrin, W., B. Würsig and J. Thewissen, *Encyclopedia of Marine Mammals*, 2nd Edition, pp. 108–112, Academic Press.
- O’Neill, S.J., T.J. Osborn, M. Hulme, I. Lorenzoni and A.R. Watkinson, 2008. Using expert knowledge to assess uncertainties in future polar bear populations under climate change. *Journal of Applied Ecology*, 45:1649–1659.
- Occhipinti-Ambrogi, A., 2007. Global change and marine communities: alien species and climate change. *Marine Pollution Bulletin*, 55:342–352.
- Oelke, C., 1997. Atmospheric signatures in sea-ice concentration estimates from passive microwaves: Modelled and observed. *International Journal of Remote Sensing*, 18:1113–1136.
- Ogi, M., K. Yamazaki and J. Wallace, 2010. Influence of winter and summer surface wind anomalies on summer Arctic sea ice extent. *Geophysical Research Letters*, 37:L07701.
- Ogorodov, S., 2005. The role of sea ice in coastal and sea bottom dynamics of the Pechora Sea. In: Bauch, H.A., Y.A. Pavlidis, Y.I. Polyakova, G.G. Matishov and N. Koç (Eds.), *Pechora Sea Environments: Past, Present, and Future*, pp. 113–124, Alfred-Wegener-Institut für Polar- und Meeresforschung, Bremerhaven.
- Ogren, J.A., R. Charlson and P. Groblicki, 1983. Determination of elemental carbon in rainwater. *Analytical Chemistry*, 55:1569–1572.
- OPRC, 1990. International Convention on Oil Pollution Preparedness, Response, and Co-operation. Adopted 30 November 1990, Entry into Force: 13 May 1995.
- Orensanz, J., B. Ernst, D.A. Armstrong, P. Stabeno and P. Livingston, 2004. Contraction of the geographic range of distribution of snow crab (*Chionoecetes opilio*) in the Eastern Bering Sea: An environmental ratchet? *California Cooperative Oceanic Fisheries Investigations Report*, pp. 65–79. California Cooperative Oceanic Fisheries.
- Orlova, E.L., N.G. Ushakov, V.N. Nesterova and V.D. Boitsov, 2002. Food supply and feeding of capelin (*Mallotus villosus*) of different size in the central latitudinal zone of the Barents Sea during intermediate and warm years. *ICES Journal of Marine Science*, 59:968–975.
- Orlova, E.L., V.D. Boitsov, A.V. Dolgov, G.B. Rudneva and V.N. Nesterova, 2005. The relationship between plankton, capelin, and cod under different temperature conditions. *ICES Journal of Marine Science*, 62:1281–1292.
- Orlova, E.L., A.V. Dolgov, G.B. Rudneva, I.A. Oganin and L.L. Konstantinova, 2009. Trophic relations of capelin (*Mallotus villosus*) and polar cod (*Boreogadus saida*) in the Barents Sea as a factor of impact on the ecosystem. *Deep Sea Research II*, 56:2054–2067.
- Outridge, P., R. Macdonald, F. Wang, G. Stern and A. Dastoor, 2008. A mass balance inventory of mercury in the Arctic Ocean. *Environmental Chemistry*, 5:89–111.
- Overland, J.E., 2009. The case for global warming in the Arctic. Paper presented at the Influence of climate change on the changing Arctic and sub-Arctic conditions. NATO Advanced Research Workshop on Influence of climate change on the changing Arctic, pp. 13–23. 8–10 May 2008, Liège, Belgium.
- Overland, J.E. and P. Guest, 1991. The Arctic snow and air temperature budget over sea ice during winter. *Journal of Geophysical Research-Oceans*, 96:4651–4662.
- Overland, J.E. and M. Wang, 2007. Future regional Arctic sea ice declines. *Geophysical Research Letters*, 34:L17705.
- Overland, J.E., M. Spillane, D. Percival, M. Wang and H. Mofield, 2004. Seasonal and regional variation of pan-Arctic surface air temperature over the instrumental record. *Journal of Climate*, 17:3263–3282.
- Overland, J., J. Turner, J. Francis, N. Gillett, G. Marshall and M. Tjernstrom, 2008a. The Arctic and Antarctic: Two faces of climate change. *Eos, Transactions, American Geophysical Union*, 89:177.
- Overland, J.E., M. Wang and S. Salo, 2008b. The recent Arctic warm period. *Tellus*, 60A:589–597.
- Pabi, S., G.L. van Dijken and K.R. Arrigo, 2008. Primary production in the Arctic Ocean, 1998–2006. *Journal of Geophysical Research*, 113:C08005.
- Parkinson, C.L. and D.J. Cavalieri, 2008. Arctic sea ice variability and trends, 1979–2006. *Journal of Geophysical Research*, 113:C07003.
- Parkinson, C.L., K.Y. Vinnikov and D.J. Cavalieri, 2006. Evaluation of the simulation of the annual cycle of Arctic and Antarctic sea ice coverages by 11 major global climate models. *Journal of Geophysical Research*, 111:C07012.

- Parks, E.K., A.E. Derocher and N.J. Lunn, 2006. Seasonal and annual movement patterns of polar bears on the sea ice of Hudson Bay. *Canadian Journal of Zoology*, 84:1281–1294.
- Partington, K., T. Flynn, D. Lamb, C. Bertoia and K. Dedrick, 2003. Late twentieth century northern hemisphere sea-ice record from U.S. national ice center charts. *Journal of Geophysical Research*, 108:C1–C9.
- Pearce, T., B. Smit, F. Duerden, J.D. Ford, A. Goose and F. Kataoyak, 2010. Inuit vulnerability and adaptive capacity to climate change in Ulukhaktok, Northwest Territories, Canada. *Polar Record*, 24:1–21.
- Pedersen, C.A., E. Roeckner, M. Lüthje and J. Winther, 2009. A new sea ice albedo scheme including melt ponds for ECHAM5 general circulation model. *Journal of Geophysical Research*, 114:D08101.
- Pegau, W.S. and C.A. Paulson, 2001. The albedo of Arctic leads in summer. *Annals of Glaciology*, 33:221–224.
- Perovich, D.K., 2005. On the aggregate-scale partitioning of solar radiation in Arctic Sea Ice during the SHEBA field experiment. *Journal of Geophysical Research*, 110:C03002.
- Perovich, D. and J. Richter-Menge, 2009. Loss of sea ice in the Arctic. *Annual Review of Marine Science*, 2009.1:417–441.
- Perovich, D.K. and W.B. Tucker, III, 1997. Arctic sea-ice conditions and the distribution of solar radiation during summer. *Annals of Glaciology*, 25:445–450.
- Perovich, D.K., C.S. Roesler and W.S. Pegau, 1998. Variability in sea ice optical properties. *Journal of Geophysical Research-Oceans*, 103:1193–1209.
- Perovich, D.K., T.C. Grenfell, B. Light, J.A. Richter-Menge, M. Sturm, W.B. Tucker, III, H. Eicken and G.A. Maykut, 1999. SHEBA: Snow and Ice Studies. CD ROM.
- Perovich, D.K., T.C. Grenfell, B. Light and P.V. Hobbs, 2002a. Seasonal evolution of the albedo of multiyear Arctic sea ice. *Journal of Geophysical Research-Oceans*, 107:8044.
- Perovich, D.K., W.B. Tucker, III and K.A. Ligett, 2002b. Aerial observations of the evolution of ice surface conditions during summer. *Journal of Geophysical Research*, 107:C8048.
- Perovich, D.K., T.C. Grenfell, J.A. Richter-Menge, B. Light, W.B. Tucker, III and H. Eicken, 2003. Thin and thinner: Sea ice mass balance measurements during SHEBA. *Journal of Geophysical Research-Oceans*, 108:8050.
- Perovich, D.K., B. Light, H. Eicken, K.F. Jones, K. Runciman and S.V. Nghiem, 2007. Increasing solar heating of the Arctic Ocean and adjacent seas, 1979–2005. Attribution and role in the ice-albedo feedback. *Geophysical Research Letters*, 34:L19505.
- Perovich, D.K., J.A. Richter-Menge and K.F. Jones, 2008. Sunlight, water, and ice: Extreme Arctic sea ice melt during the summer of 2007. *Geophysical Research Letters*, 35:L11501.
- Perovich, D.K., T.C. Grenfell, B. Light, B.C. Elder, J. Harbeck, C. Polashenski, W.B. Tucker, III and C. Stelmach, 2009. Transpolar observations of the morphological properties of Arctic sea ice. *Journal of Geophysical Research*, 114:C00A04.
- Pertoldi, C., C. Sonne, R. Dietz, N.M. Schmidt and V. Loeschke, 2009. Craniometric characteristics of polar bear skulls from two periods with contrasting levels of industrial pollution and sea ice extent. *Journal of Zoology*, 279:321–328.
- Petersen, G.H. and M.A. Curtis, 1980. Differences in energy flow through major components of subarctic, temperate and tropical marine shelf ecosystems. *Dana* 1:53–64.
- Petersen, M.R., W.W. Larned and D.C. Douglas, 1999. At-sea distribution of spectacled eiders: a 120-year-old mystery solved. *Auk*, 116:1009–1020.
- Peterson, I.K., S.J. Prinsenberg and J.S. Holladay, 2008. Observations of sea ice thickness, surface roughness and ice motion in Amundsen Gulf. *Journal of Geophysical Research*, 113:C06016.
- Pfirman, S., 2009. The last Arctic sea ice refuge. *Circle*, 4:6–8.
- Piepenburg, D., 2005. Recent research on Arctic benthos: common notions need to be revised. *Polar Biology*, 28:733–755.
- Polyak, L., R.B. Alley, J.T. Andrews, J. Brigham-Grette, T.M. Cronin, D.A. Darby, A.S. Dyke, J.J. Fitzpatrick, S. Funder, M. Holland, A.E. Jennings, G.H. Miller, M. O'Regan, J. Savelle, M.C. Serreze, K. St. John, J.W.C. White and E. Wolff, 2010. History of sea ice in the Arctic. *Quaternary Science Reviews*, 29:1757–1778.
- Polyakov, I.V., G.V. Alekseev, R.V. Bekryaev, U.S. Bhatt, R. Colony, M.A. Johnson, V.P. Karklin, D. Walsh and A.V. Yulin, 2003. Long-term ice variability in Arctic marginal seas. *Journal of Climate*, 16:2078–2085.
- Polyakov, I., L. Timokhov, E. Hansen and 16 others, 2007. Observational program tracks Arctic Ocean transition to a warmer state. *Eos, Transactions, American Geophysical Union*, 88:398.
- Post, E., M.C. Forchhammer, M.S. Bret-Harte and 22 others, 2009. Ecological dynamics across the Arctic associated with recent climate change. *Science*, 325:1355–1358.
- Prenni, A.J., J.Y. Harrington, M. Tjernström, P.J. DeMott, A. Avramov, C.N. Long, S.M. Kreidenweis, P.Q. Olsson and J. Verlinde, 2006. Can ice-nucleating aerosols affect arctic seasonal climate? *Bulletin of the American Meteorological Society*, 88:541–550.
- Prowse, T.D., C. Fugal, F.J. Wrona and J.D. Reist, 2009. Implications of climate change for Northern Canada: freshwater, marine and terrestrial ecosystems. *Ambio*, 38:282–289.
- Radionov, V.F., N.N. Briazgin and E.I. Alexandrov, 1996. Snow cover in the Arctic Basin (in Russian). 124 pp. *Gidrometeoizdat*, St. Petersburg. [English translation. 1997. Tech. Rep. APLUW TR 9701. 98 pp. Polar Science Center University of Washington, Seattle, WA.]
- Ramanathan, V., M.V. Ramana, G. Roberts, D. Kim, C. Corrigan, C. Chung and D. Winker, 2007. Warming trends in Asia amplified by brown cloud solar absorption. *Nature*, 448:575–578.
- Rampal, R., J. Weiss and D. Marsan, 2009. Positive trend in the mean speed and deformation rate of Arctic sea ice, 1979–2007. *Journal of Geophysical Research*, 114:C05013.
- Rattenbury, K., K. Kielland, G. Finstad and W. Schneider, 2009. A reindeer herder's perspective on caribou, weather and socio-economic change on the Seward Peninsula, Alaska. *Polar Research*, 28:71–88.
- Rausch, R.L., J.C. George and H.K. Brower, 2007. Effect of climate warming on the Pacific walrus, and potential modification of its helminth fauna. *Journal of Parasitology*, 93:1247–1251.
- Ravens, T. and W. Lee, 2009. Evolution of a North Slope barrier island (Narwhal Island, North Arctic Alaska) 1955–2007. *Eos, Transactions, American Geophysical Union*, 88: Abstract H34B-08.
- Rayner, N.A., D.E. Parker, E.B. Horton, C.K. Folland, L.V. Alexander, D.P. Rowell, E.C. Kent and A. Kaplan, 2003. Global analyses of sea surface temperature, sea ice and night marine air temperature since the late nineteenth century. *Journal of Geophysical Research-Atmosphere*, 108:4407.
- Reeh, N., H.H. Thomsen, A.K. Higgins and A. Weidick, 2001. Sea ice and the stability of north and northeast Greenland floating glaciers. *Annals of Glaciology*, 33:474–480.
- Regehr, E.V., S.C. Amstrup and I. Stirling, 2006. Polar bear population status in the southern Beaufort Sea. U.S. Geological Survey Open File Report, 2006-1337.
- Regehr, E.V., N.J. Lunn, S.C. Amstrup and I. Stirling, 2007. Effects of earlier sea ice breakup on survival and population size of polar bears in western Hudson Bay. *Journal of Wildlife Management*, 71:2673–2683.
- Regehr, E.V., C.M. Hunter, H. Caswell, S.C. Amstrup and I. Stirling, 2010. Survival and breeding of polar bears in the southern Beaufort Sea in relation to sea ice. *Journal of Animal Ecology*, 79:117–127.
- Reimnitz, E., P. Barnes and J. Harper, 1990. A review of beach nourishment from ice transport of shoreface materials, Beaufort Sea, Alaska. *Journal of Coastal Research*, 6:439–470.
- Reimnitz, E., D. Dethleff and D. Nürnberg, 1994. Contrasts in Arctic shelf sea-ice regimes and some implications: Beaufort Sea and Laptev Sea. *Marine Geology*, 119:215–225.
- Renaud, W. and M.S.W. Bradstreet, 1980. Late winter distribution of black-guillemots in northern Baffin Bay and the Canadian High Arctic. *Canadian Field Naturalist*, 94:421–425.
- Renaud, P.E., A. Riedel, C. Michel, N. Morata, M. Gosselin, T. Juul-Pedersen and A. Chiuchiolio, 2006. Seasonal variation in benthic community oxygen demand: A response to an ice algal bloom in the Beaufort Sea, Canadian Arctic? *Journal of Marine Systems*, 67:1–12.
- Renaud, P.E., M. Wlodarska-Kowalczyk, H. Trannum, B. Holte, J.M. Weslawski, S. Cochrane, S. Dashle and B. Gulliksen, 2007. Multidecadal stability of benthic community structure in a high-Arctic glacial fjord (van Mijenfjord, Spitsbergen). *Polar Biology*, 30:295–230.
- Renaud, P.E., M.L. Carroll and W.G. Ambrose, Jr., 2008. Effects of global warming on Arctic sea-floor communities and its consequences for higher trophic levels. In: Duarte, C. (Ed.). *Impacts of Global Warming on Polar Ecosystems*, pp. 139–175, FBBVA Press, Bilbao.
- Richard, P.R., J.R. Orr, R. Dietz and L. Dueck, 1998. Sightings of belugas and other marine mammals in the North Water, late March 1993. *Arctic*, 51:1–4.

- Richard, P.R., A.R. Martin and J.R. Orr, 2001. Summer and autumn movements of belugas of the Eastern Beaufort Sea stock. *Arctic*, 54:223–236.
- Richardson, E., I. Stirling and B. Kochtubajda, 2007. The effects of forest fires on polar bear maternity denning habitat in western Hudson Bay. *Polar Biology*, 30:369–378.
- Richman, S. and J. Lovvorn, 2003. Effects of clam species dominance on nutrient and energy acquisition by spectacled eiders in the Bering Sea. *Marine Ecology Progress Series*, 261:283–297.
- Richter-Menge, J., J. Overland, A. Proshutinsky and 22 others, 2006. State of the Arctic Report. NOAA Office of Oceanic and Atmospheric Research, Special Report. 42 pp.
- Ridley, J., L. Lowe, C. Brierley and G. Harris, 2007. Uncertainty in the sensitivity of Arctic sea ice to global warming in a perturbed parameter climate model ensemble. *Geophysical Research Letters*, 34:L19704.
- Riedel, A., C. Michel and M. Gosselin, 2006. Seasonal study of sea-ice exopolymeric substances on the Mackenzie shelf: Implications for the transport of sea-ice bacteria and algae. *Aquatic Microbial Ecology*, 45:195–206.
- Riedel, A., C. Michel, M. Gosselin and B. LeBlanc, 2007. Enrichment of nutrients, exopolymeric substances and microorganisms in newly formed sea ice on the Mackenzie shelf. *Marine Ecology Progress Series*, 342:55–67.
- Riedlinger, D. and F. Berkes, 2001. Contributions of traditional knowledge to understanding climate change in the Canadian Arctic. *Polar Records*, 37:315–328.
- Rigor, I.G. and J.M. Wallace, 2004. Variations in the age of Arctic sea-ice and summer sea-ice extent. *Geophysical Research Letters*, 31:L09401.
- Rigor, I., R. Colony and S. Martin, 2000. Variations in surface air temperature observations in the Arctic, 1979–1997. *Journal of Climate*, 13:896–914.
- Rinke, A., W. Maslowski, K. Dethloff and J. Clement, 2006. Influence of sea ice on the atmosphere: A study with an Arctic atmospheric regional climate model. *Journal of Geophysical Research*, 111:D16103.
- Roby, D.D., K.L. Brink and D.N. Nettleship, 1981. Measurements, chick-meals and breeding distribution of Dovekies *Alle alle* in Northwest Greenland. *Arctic*, 34:241–248.
- Rockwell, R.F. and L.J. Gormezano, 2009. The early bear gets the goose: climate change, polar bears and lesser snow geese in western Hudson Bay. *Polar Biology*, 32:539–547.
- Rosing-Asvid, A., 2008. A new harp seal whelping ground near South Greenland. *Marine Mammal Science*, 24:730–736.
- Rosing-Asvid, A., 2010. First confirmed record of gray seals in Greenland. *Arctic*, 63:381–504.
- Rothrock, D.A., Y. Yu and G.A. Maykut, 1999. Thinning of the arctic sea-ice cover. *Geophysical Research Letters*, 26:3469–3472.
- Rothrock, D.A., D.B. Percival and M. Wensnahan, 2008. The decline in arctic sea-ice thickness: Separating the spatial, annual, and interannual variability in a quarter century of submarine data. *Journal of Geophysical Research*, 113:C05003.
- Rothwell, D., 2009. Time for a New Arctic Treaty. *Circle*, 1:6–8.
- Róžańska, M., M. Poulin and M. Gosselin, 2008. Protist entrapment in newly formed sea ice in the coastal Arctic Ocean. *Journal of Marine Systems*, 74:887–901.
- Róžańska, M., M. Gosselin, M. Poulin, J.M. Wiktor and C. Michel, 2009. Influence of environmental factors on the development of bottom ice protist communities during the winter-spring transition. *Marine Ecology Progress Series*, 386:43–59.
- Rugh, D.J. and K.E.W. Shelden, 2009. Bowheads. In: Perrin, W., B. Würsig and J. Thewissen, *Encyclopedia of Marine Mammals*, 2nd Edition, pp. 131–133, Academic Press.
- Runge, J.A., J.-C. Therriault, L. Legendre, R.G. Ingram and S. Demers, 1991. Coupling between ice microalgal productivity and the pelagic, metazoan food web in southeastern Hudson Bay: a synthesis of results. *Polar Records*, 10:325–338.
- Rysgaard, S. and R.N. Glud, 2007. Carbon cycling and climate change: Predictions for a high Arctic marine ecosystem (Young Sound, NE Greenland). In: Rysgaard, S. and R.N. Glud (Eds.). *Carbon Cycling in Arctic Marine Ecosystems: Case Study Young Sound*. Meddelelser om Grønland, 58:206–214.
- Rysgaard, S., T.G. Nielsen and B.W. Hansen, 1999. Seasonal variation in nutrients, pelagic primary production and grazing in a high-Arctic coastal marine ecosystem, Young Sound, Northeast Greenland. *Marine Ecology Progress Series*, 179:13–25.
- Rysgaard, S., M. Kuhl, R.N. Glud and J.W. Hansen, 2001. Biomass, production and horizontal patchiness of sea ice algae in a high-Arctic fjord (Young Sound, NE Greenland). *Marine Ecology Progress Series*, 223:15–26.
- Rysgaard, S., R.N. Glud, M.K. Sej, J. Bendtsen and J.B. Christensen, 2007. Inorganic carbon transport during sea ice growth and decay: A carbon pump in polar seas. *Journal of Geophysical Research*, 112:C03016.
- Rysgaard, S., J. Bendtsen, T. Pedersen, H. Ramløv and R.N. Glud, 2009. Increased CO₂ uptake due to sea ice growth and decay in the Nordic Seas. *Journal of Geophysical Research*, 114:C09011.
- Sakshaug, E., 2004. Primary and secondary production in the Arctic Seas. In: Stein, R. and R.W. MacDonald (Eds.). *The Organic Carbon Cycle in the Arctic Ocean*, pp. 57–81, Springer.
- Schliebe, S., K.D. Rode, J.S. Gleason, J. Wilder, K. Proffitt, T.J. Evans and S. Mille, 2008. Effects of sea ice extent and food availability on spatial and temporal distribution of polar bears during the fall open-water period in the Southern Beaufort Sea. *Polar Biology*, 31:999–1010.
- Schumacher, J.D., N.A. Bond, R.D. Brodeur, P.A. Livingston, J.M. Napp and P.J. Stabeno, 2003. Climate change in the southeastern Bering Sea and some consequences for biota. In: Hempel, G. and K. Sherman (Eds.). *Large Marine Ecosystems of the World: Trends in exploitation, protection, and research*, pp. 17–40, Elsevier.
- Schweiger, A.J. and J.R. Key, 1992. Arctic cloudiness. Comparison of ISCCP-C2 and Nimbus-7 satellite-derived cloud products with a surface-based cloud climatology. *Journal of Climate*, 5:1514–1527.
- Schweiger, A.J., J. Zhang, R.W. Lindsay and M. Steele, 2008a. Did unusually sunny skies help drive the record sea ice minimum of 2007? *Geophysical Research Letters*, 35:L0503.
- Schweiger, A.J., R.W. Lindsay, S. Vavrus and J.A. Francis, 2008b. Relationships between Arctic sea ice and clouds during autumn. *Journal of Climate*, 21:4799–4810.
- Seaman, G.A., L.F. Lowry and K.J. Frost, 1982. Foods of beluga whales (*Delphinapterus leucas*) in western Alaska. *Cetology*, 44:1–19.
- Sedlar, J. and M. Tjernström, 2009. Stratiform cloud-inversion characterization during the Arctic melt season. *Boundary-Layer Meteorology*, 132:455–474.
- Seidlitz, D., 2009 Arctic Technology Development. Paper presented at the USA-Norway Arctic Petroleum Technology workshop, January 21, 2009, Tromsø, Norway.
- Sejr, M.K., M.E. Blicher and S. Rysgaard, 2009. Sea ice cover affects inter-annual and geographic variation in growth of the Arctic cockle *Clinocardium ciliatum* (Bivalvia) in Greenland. *Marine Ecology Progress Series*, 389:149–158.
- Sellers, W.D., 1969. A global climatic model based on the energy balance of the Earth-atmosphere system. *Journal of Applied Meteorology*, 8:392–400.
- Semiletov, I., A. Makshtas, S. Akasofu and E.L. Andreas, 2004. Atmospheric CO₂ balance: The role of Arctic sea ice. *Geophysical Research Letters*, 31:L05121.
- Semtner, A.J., Jr., 1976. A model for the thermodynamic growth of sea ice in numerical investigations of climate. *Journal of Physical Oceanography*, 6:379–389.
- Serreze, M.C., M.M. Holland and J. Stroeve, 2007. Perspectives on the Arctic's shrinking sea-ice cover. *Science*, 315:1533–1536.
- Serreze, M.C., A.P. Barrett, J.C. Stroeve, D.N. Kindig and M.M. Holland, 2009. The emergence of surface-based Arctic amplification. *The Cryosphere*, 3:11–19.
- Shapiro, L.H. and P.W. Barnes, 1991. Correlation of nearshore ice movement with seabed ice gouges near Barrow, Alaska. *Journal of Geophysical Research-Oceans*, 96:16979–16989.
- Sharma, S., E. Andrews, L.A. Barrie, J.A. Ogren and D. Lavoué, 2006. Variations and sources of the equivalent black carbon in the high Arctic revealed by long-term observations at Alert and Barrow: 1989–2003. *Journal of Geophysical Research*, 111:D14208.
- Sheffield, G. and J.M. Grebmeier, 2009. Pacific walrus (*Odobenus rosmarus divergens*): Differential prey digestion and diet. *Marine Mammal Science*, 25:761–777.
- Sheffield, G., F.H. Fary, H. Feder and B.P. Kelly, 2001. Laboratory digestion of prey and interpretation of walrus stomach contents. *Marine Mammal Science*, 17:310–330.
- Sherman, K., I. Belkin, K. Friedland, J. O'Reilly and K. Hyde, 2009.

- Accelerated warming and emergent trends in fisheries biomass yields of the world's Large Marine Ecosystems. *Ambio*, 38:215–224.
- Shimada, K., T. Kamoshida, M. Itoh, S. Nishino, E. Carmack, F. McLaughlin, S. Zimmerman and A. Proshutinsky, 2006. Pacific Ocean inflow: influence on catastrophic reduction of sea ice cover in the Arctic Ocean. *Geophysical Research Letters*, 33:L08605.
- Shindell, D.T., H. Teich, M. Chin and 29 others, 2008. A multi-model assessment of pollution transport to the Arctic. *Atmospheric Chemistry Physics Discussions*, 8:8385–8429.
- Shirasawa, K., H. Elcken, K. Tateyama, T. Takatsuka and T. Kawamura, 2009. Sea-ice thickness variability in the Chukchi Sea, spring and summer 2002–2004. *Deep Sea Research II*, 56:1182–1200.
- Shy, T.L. and J.E. Walsh, 1996. North Pole ice thickness and association with ice motion history. *Geophysical Research Letters*, 23:2975–2978.
- Siferd, T.D., T.E. Welch, W.A. Bergmann and M.F. Curtis, 1997. Seasonal distribution of sympagic amphipods near Chesterfield Inlet, N.W.T., Canada. *Polar Biology*, 18:16–22.
- Simmonds, M.P. and S.J. Isaac, 2007. The impacts of climate change on marine mammals: early signs of significant problems. *Oryx*, 41:19–26.
- Simpkins, M., K.M. Kovacs, K. Laidre and L. Lowry, 2009. A framework for monitoring Arctic marine mammals: findings from a workshop sponsored by the U.S. Marine Mammal Commission and U.S. Fish and Wildlife Service, Valencia, March 2007. 13 pp. Circumpolar Biodiversity Monitoring Program, Akureyri, Iceland.
- Sinclair, E.H., L.S. Vlietstra, D.S. Johnson, T.K. Zeppelin, G.V. Byrd, A.M. Springer, R.R. Ream and G.L. Hunt, Jr., 2008. Patterns in prey use among fur seals and seabirds in the Pribilof Islands. *Deep Sea Research II*, 55:1897–1918.
- Sirenko, B.I. and S.Y. Gagaev, 2007. Unusual abundance of macrobenthos and biological invasions in the Chukchi Sea. *Russian Journal of Marine Biology*, 33:355–364.
- Smit, B. and J. Wandel, 2006. Adaptation, adaptive capacity, and vulnerability. *Global Environ Change*, 16:282–292.
- Smith, T.G., 1987. The ringed seal, *Phoca hispida*, of the Canadian Western Arctic. *Canadian Bulletin of Fisheries and Aquatic Sciences*, 216:81.
- Smith Jr, W.O. and D. Barber (Eds.), 2007. *Polynyas: Windows to the World*. 474 pp. Elsevier.
- Smith, G.G. and L.A. Harwood, 2001. Observations of neonate ringed seals, *Phoca hispida*, after early break-up of the sea ice in Prince Albert Sound, Northwest Territories, Canada, spring 1998. *Polar Biology*, 24:215–219.
- Smith, R.E.H., J. Anning, P. Clement and G. Cota, 1988. Abundance and production of ice algae in Resolute Passage, Canadian Arctic. *Marine Ecology Progress Series*, 48:251–263.
- Smith, P.A., K.H. Elliott, A.J. Gaston and H.G. Gilchrist, 2010. Has early ice clearance increased predation on breeding birds by polar bears? *Polar Biology*, 33:1149–1153.
- Solomon, S., D. Qin, M. Manning, Z. Chen, M. Marquis, K.B. Averyt, M. Tignor and H.L. Miller (Eds.), 2007. Contribution of Working Group I to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change, 2007. Cambridge University Press, 996 pp.
- Solomon, S., A. Taylor and C. Stevens, 2008. Nearshore ground temperatures, seasonal ice bonding, and permafrost formation within the bottom-fast ice zone, Mackenzie Delta, NWT. Paper presented at the Ninth International Conference on Permafrost, pp. 1675–1680. June 29 – July 3, 2008, Fairbanks, Alaska.
- Søreide, J.E., H. Hop, M.L. Carroll, S. Falk-Petersen and E.N. Hegseth, 2006. Seasonal food-web structures and sympagic-pelagic coupling in the European Arctic revealed by stable isotopes and a two-source food web model. *Progress in Oceanography*, 71:59–87.
- Søreide, J.E., S. Falk-Petersen, E.N. Hegseth, H. Hop, M.L. Carroll, K.A. Hobson and K. Blachowiak-Samolyk, 2008. Seasonal feeding strategies of *Calanus* in the high-Arctic Svalbard region. *Deep Sea Research II*, 55:2225–2244.
- Søreide, J.E., E. Leu, J. Berge, M. Graeve and S. Falk-Petersen, 2010. Timing of blooms, algal food quality and *Calanus glacialis* reproduction and growth in a changing Arctic. *Global Change Biology*, 16:3154–3163.
- Sou, T. and G. Flato, 2009. Sea ice in the Canadian Arctic archipelago: modeling the past (1950–2004) and the future (2041–60). *Journal of Climate*, 22:2181–2198.
- Spreen, G., S. Kern, D. Stammer and E. Hansen, 2009. Fram Strait sea ice volume export estimated between 2003 and 2008 from satellite data. *Geophysical Research Letters*, 36:L19502.
- Squire, V.A., 2007. Of ocean waves and sea-ice revisited. *Cold Regions Science and Technology*, 49:110–133.
- Stafford, K.M., S.E. Moore, M. Spillane and S. Wiggins, 2007. Gray whale calls recorded near Barrow, Alaska, throughout the winter of 2003–04. *Arctic*, 60:167–172.
- Steele, M., W. Ermold and J.L. Zhang, 2008. Arctic Ocean surface warming trends over the past 100 years. *Geophysical Research Letters*, 35:L02614.
- Steffen, K., J. Key, D.J. Cavalieri, J.C. Comiso, P. Gloersen, K. St. Germain and I. Rubinstein, 1992. The estimation of geophysical parameters using passive microwave algorithms. In: Carsey, F. (Ed.). *Microwave Remote Sensing of Sea Ice*, pp. 201–228, American Geophysical Union.
- Stempniewicz, L., K. Blachowiak-Samolyk and J.M. Weslawski, 2007. Impact of climate change on zooplankton communities, seabirds populations and arctic terrestrial ecosystems – A scenario. *Deep Sea Research II*, 54:2934–2945.
- Stenevik, E. and S. Sundby, 2007. Impacts of climate change on commercial fish stocks in Norwegian waters. *Marine Policy*, 31:19–31.
- Stern, N., S. Peters, V. Bakhshi and 20 others, 2006. *Stern Review: The Economics of Climate Change*. HM Treasury, London.
- Stern, H., R. Lindsay, C. Bitz and P. Hezel, 2008. What is the trajectory of Arctic sea ice? In: DeWeaver, E.T., C.M. Bitz and L. Tremblay (Eds.). *Arctic Sea Ice Decline: Observations, Projections, Mechanisms, and Implications*, pp. 175–185, American Geophysical Union.
- Stewart, E. and D. Draper, 2006. Sustainable cruise tourism in Arctic Canada: An integrated coastal management approach. *Tourism in Marine Environments*, 3:77–88.
- Stewart, E. and D. Draper, 2008. The sinking of the MS Explorer : implications for cruise tourism in Arctic Canada. *Arctic*, 61:224–228.
- Stirling, I., 1980. The biological importance of polynyas in the Canadian Arctic. *Arctic*, 33:303–315.
- Stirling, I., 1997. The importance of polynyas, ice edges, and leads to marine mammals and birds. *Journal of Marine Systems*, 10:9–21.
- Stirling, I., 2009. Polar bears. In: Perrin, W., B. Würsig and J. Thewissen, *Encyclopedia of Marine Mammals*, 2nd Edition, pp. 888–890, Academic Press.
- Stirling, I. and A.E. Derocher, 1993. Possible impacts of climate warming on polar bears. *Arctic*, 46:240–245.
- Stirling, I. and C.L. Parkinson, 2006. Possible effects of climate warming on selected populations of polar bears (*Ursus maritimus*) in the Canadian Arctic. *Arctic*, 59:261–275.
- Stirling, I. and T.G. Smith, 2004. Implications of warm temperatures, and an unusual rain event for the survival of ringed seals on the coast of southeastern Baffin Island. *Arctic*, 57: 59–67.
- Stirling, I., N.J. Lunn and J.O. Iacozza, 1999. Long-term trends in the population ecology of polar bears in western Hudson Bay in relation to climatic change. *Arctic*, 52:294–306.
- Stirling, I., N.J. Lunn, J. Iacozza, C. Elliott and M. Obbard, 2004. Polar bear distribution and abundance on the southwestern Hudson Bay coast during open water season, in relation to population trends and annual ice patterns. *Arctic*, 57:15–26.
- Stirling, I., E. Richardson, G.W. Thiemann and A.E. Derocher, 2008a. Unusual predation attempts of polar bears on ringed seals in the southern Beaufort Sea: possible significance of changing spring ice conditions. *Arctic*, 61:14–22.
- Stirling, I., A.E. Derocher, W.A. Gough and K. Rode, 2008b. Response to Dyck, et al. (2007) on polar bears and climate change in western Hudson Bay. *Ecological Complexity*, 5:193–201.
- Stohl, A., 2006. Characteristics of atmospheric transport into the Arctic troposphere. *Journal of Geophysical Research*, 111:D11306.
- Stokke, O., 2009. Arctic environmental governance: Are new regimes needed? *Circle*, 1:8–10.
- Stokke, O. and G. Honneland, 2007. *International cooperation and Arctic governance: regime effectiveness and northern region building*. xvii, 196 pp. Routledge.
- Story-Manes, S. and R. Gradinger, 2009. Small scale vertical gradients of Arctic ice algal photophysiological properties. *Photosynthesis Research*, 102:53–66.
- Stram, D.L. and D.C.K. Evans, 2009. Fishery management responses to climate change in the North Pacific. *ICES Journal of Marine Science*,

- 66:1633–1639.
- Streets, D.G., T.C. Bond, T. Lee and C. Jang, 2004. On the future of carbonaceous aerosol emissions. *Journal of Geophysical Research*, 109:D24212.
- Stroeve, J.C., T. Markus and W.N. Meier, 2006. Recent changes in the Arctic melt season. *Annals of Glaciology*, 44:367–374.
- Stroeve, J., M.M. Holland, W. Meier, T. Scambos and M. Serreze, 2007. Arctic sea ice decline: Faster than forecast. *Geophysical Research Letters*, 34:L09501.
- Sturm, M., H. K. and D.K. Perovich, 2002. Winter snow cover on the sea ice of the Arctic Ocean at the Surface Heat Budget of the Arctic Ocean (SHEBA): Temporal evolution and spatial variability. *Journal of Geophysical Research-Oceans*, 107:8047.
- Süfke, L., D. Piepenburg and C.F. von Dorrien, 1998. Body size, sex ratio and diet composition of *Arctogadus glacialis* (Peters, 1874) (Pisces: Gadidae) in the Northeast Water Polynya (Greenland). *Polar Biology*, 20:357–362.
- Sun, M.-Y., M.L. Carroll, W.G. Ambrose, Jr., L.M. Clough, L. Zou and G.R. Lopez, 2007. Rapid consumption of phytoplankton and ice algae by Arctic soft-sediment benthic communities: Evidence using natural and ¹³C-labeled food materials. *Journal of Marine Research*, 65:551–588.
- Sundby, S. and O. Nakken, 2008. Spatial shifts in spawning habitats of Arcto-Norwegian cod related to multi-decadal climate oscillations and climate change. *ICES Journal of Marine Science*, 65:953–962.
- Sverdrup, H., 1953. On conditions for vernal blooming of phytoplankton. *Journal du Conseil International pour l'Exploration de la Mer*, 18:287–295.
- Sverdrup, O., P. Schei, H.G. Simmons, E. Bay and E.H. Hea, 1904. *New Land: Four Years in the Arctic Regions*. Longmans, Green and Co., London.
- Tameler, T., M. Reigstad, H. Hop, M.L. Carroll and P. Wassmann, 2008. Pelagic and sympagic contribution of organic matter to zooplankton and vertical export in the Barents Sea marginal ice zone. *Deep Sea Research II*, 55:2330–2339.
- Tameler, T., M. Reigstad, H. Hop and T. Ratkova, 2009. Ice algal assemblages and vertical export of organic matter from sea ice in the Barents Sea and Nansen Basin (Arctic Ocean). *Polar Biology*, 32:1261–1273.
- Taylor, R., 1978. The occurrence of grounded ice ridges and shore ice piling along the northern coast of Somerset Island, NWT. *Arctic*, 31:133–139.
- Taylor, P.D. and D.L. Feltham, 2004. A model of melt pond evolution on sea ice. *Journal of Geophysical Research*, 109:C12007.
- Taylor, M.K., J. Laake, P.D. McLoughlin, H.D. Cluff, E.W. Born, A. Rosing-Asvid and F. Mesier, 2008. Population parameters and harvest risks for polar bears (*Ursus maritimus*) of Kane Basin, Canada and Greenland. *Polar Biology*, 31:491–499.
- Thiemann, G.W., S.J. Iverson and I. Stirling, 2008. Polar bear diets and Arctic marine food webs: insights from fatty acid analysis. *Ecological Monographs*, 78:591–613.
- Thorndike, A.S., D.A. Rothrock, G.A. Maykut and R. Colony, 1975. The thickness distribution of sea ice. *Journal of Geophysical Research*, 80:4501–4513.
- Tjernström, M., M. Žagar, G. Svensson, J. Cassano, S. Pfeifer, A. Rinke, K. Wyser, K. Dethloff, C. Jones and T. Semmler, 2005. Modeling the Arctic Boundary Layer: An evaluation of six ARCMIP regional-scale models with data from the SHEBA project. *Boundary-Layer Meteorology*, 117:337–381.
- Towns, T., A.E. Derocher, I. Stirling, N.J. Lunn and E. Hedman, 2009. Spatial and temporal patterns of problem polar bears in Churchill, Manitoba. *Polar Biology*, 32:1529–1537.
- Tremblay, J.-É. and J. Gagnon, 2009. The effects of irradiance and nutrient supply on the productivity of Arctic waters: a perspective on climate change. Paper presented at the NATO Advanced Research Workshop on Influence of climate change on the changing Arctic, pp. 73–92, 8–10 May 2008, Liège, Belgium.
- Tremblay, J.-É., Y. Gratton, J. Fauchot and N.M. Price, 2002. Climatic and oceanic forcing of new, net and diatom production in the North Water. *Deep Sea Research II*, 49:4927–4946.
- Tremblay, J.-É., C. Michel, K.A. Hobson, M. Gosselin and N.M. Price, 2006a. Bloom dynamics in early-opening waters of the Arctic Ocean. *Limnology and Oceanography*, 51:900–912.
- Tremblay, J.-É., H. Hattori, C. Michel, M. Ringuette, F. Fortier, C. Lovejoy, K.A. Hobson, Z.P. Mei, D. Amiel and K. Cochran, 2006b. Pathways of biogenic carbon flow in the eastern North Water. *Progress in Oceanography*, 71:402–425.
- Tremblay, J.-É., K. Simpson, J. Martin, L. Miller, Y. Gratton, D. Barber and N.M. Price, 2008. Vertical stability and the annual dynamics of nutrients and chlorophyll fluorescence in the coastal, southeast Beaufort Sea. *Journal of Geophysical Research*, 113:C07S90.
- Tschudi, M.A., J.A. Curry and J.A. Maslanik, 2001. Airborne observations of summertime surface features and their effect on surface albedo during FIRE/SHEBA. *Journal of Geophysical Research-Atmosphere*, 106:15335–15344.
- Tschudi, M.J. D. Maslanik and D. Perovich, 2008. Estimation of melt pond coverage on Arctic sea ice. *Transactions on Geoscience and Remote Sensing*, 112:2605–2614.
- Tsukernik, M., C. Deser, M. Alexander and R. Tomas, 2010. Atmospheric forcing of Fram Strait sea ice export: A closer look. *Climate Dynamics*, 35:1349–1360.
- Tucker, W.B., III, J.W. Weatherly, D.T. Eppler, L.D. Farmer and D.L. Bentley, 2001. Evidence for rapid thinning of sea ice in the western Arctic Ocean at the end of the 1980s. *Geophysical Research Letters*, 28:2851–2854.
- Tynan, C.T., 2004. Cetacean populations on the SE Bering Sea shelf during the late 1990s: implications for decadal changes in ecosystem structure and carbon flow. *Marine Ecology Progress Series*, 272:281–300.
- Tynan, C.T. and D.P. DeMaster, 1997. Observations and predictions of arctic climate change: potential effects on marine mammals. *Arctic*, 50:308–322.
- UNEP, 2007. *Tourism in the Polar Regions: The Sustainability Challenge*. 55 pp. United Nations Environment Programme / The International Ecotourism Society.
- UNEP/GRID-Arendal, 2007. *Protected areas in the Arctic*. UNEP/GRID-Arendal Maps and Graphics Library, Accessed March 25, 2009.
- UNEP/UNWTO, 2005. *Making Tourism More Sustainable: A Guide for Policy Makers*. United Nations Environment Programme / UN World Tourism Organization.
- US National Ice Center and US Arctic Research Commission, 2007. *Impact of an Ice-Diminishing Arctic on Naval and Maritime Operations*, July 10–12, 2007, Washington, D.C. summary report.
- USGS, 2008. *Circum-Arctic Resource Appraisal: estimates of Undiscovered Oil and gas North of the Arctic Circle*. US Geological Survey Fact Sheet 2008–3049.
- Van Bresse, M.F., J.A. Raga, G. Di Guardo, P.D. Jepson, P.J. Duignan, U. Siebert, T. Barrett, M.C.D. Santos, I.B. Moreno, S. Siciliano, A. Aguilar and K. Van Waerebeek, 2009. Emerging infectious diseases in cetaceans worldwide and the possible role of environmental stressors. *Diseases of Aquatic Organisms*, 86:143–157.
- VanDerZwaag, D., and A. Chircop, 2008. *Governance of Arctic Marine Shipping*. Project Report. Protection of the Arctic Marine Environment (PAME).
- Vavrus, S. and S.P. Harrison, 2003. The impact of sea-ice dynamics on the Arctic climate system. *Climate Dynamics*, 20:741–757.
- Vibe, C., 1967. Arctic animals in relation to climatic fluctuations. *Meddelelser om Grønland*, 170:1–226.
- Vinje, T., N. N. Nordlund and Å. Kvambekk, 1998. Monitoring ice thickness in Fram Strait. *Journal of Geophysical Research-Oceans*, 103:10437–10449.
- Von Quillfeldt, C.H., W.G. Ambrose, Jr. and L.M. Clough, 2003. High number of diatom species in first year-ice from the Chukchi Sea. *Polar Biology*, 26:806–818.
- Wadhams, P., 1990. Evidence for thinning of the Arctic ice cover north of Greenland. *Nature*, 345:795–797.
- Wadhams, P. and N.R. Davis, 2000. Further evidence of ice thinning in the Arctic Ocean. *Geophysical Research Letters*, 27:3973–3975.
- Walsh, J.E. and W.L. Chapman, 2001. 20th-century sea-ice variations from observational data. *Annals of Glaciology*, 33:444–448.
- Wang, X. and J. Key, 2003. Recent trends in Arctic surface, cloud, and radiation properties from space. *Science*, 299:1725–1728.
- Wang, X. and J. Key, 2005. Arctic surface, cloud, and radiation properties based on the AVHRR Polar Pathfinder data set. Part II: Recent trends. *Journal of Climate*, 18:2575–2593.
- Wang, M. and J.E. Overland, 2009. A sea ice free summer Arctic within 30 years? *Geophysical Research Letters*, 36:L07502.
- Walsh, J., O. Anisimov, J.O.M. Hagen, T. Jakobsson, J. Oerlemans, T.D. Prowse, V. Romanovsky, N. Savelieva, M. Serreze, A. Shiklomanov, I. Shiklomanov and S. Solomon, 2005. *Cryosphere and hydrology*.

- In: Arctic Climate Impact Assessment, pp. 183–242, Cambridge University Press.
- Wang, J., J. Zhang, E. Watanabe, M. Ikeda, K. Mizobata, J.E. Walsh, X. Bai and B. Wu, 2009. Is the Dipole Anomaly a major driver to record lows in Arctic summer sea ice extent? *Geophysical Research Letters*, 36:L05706.
- Warren, S.G., 1982. Optical properties of snow. *Reviews of Geophysics*, 20:67–89.
- Warren, S.G., 1984. Impurities in snow: effects on albedo and snowmelt. *Annals of Glaciology*, 5:177–179.
- Warren, S.G. and W.J. Wiscombe, 1980. A model for the spectral albedo of snow. II: Snow containing atmospheric aerosols. *Journal of the Atmospheric Sciences*, 37:2734–2745.
- Warren, S.G. and W.J. Wiscombe, 1985. Dirty snow after nuclear war. *Nature*, 313:467–470.
- Warren, S.G., I.G. Rigor, N. Untersteiner, V.F. Radionov, N.N. Bryazgin, Y.I. Aleksandrov and R. Colony, 1999. Snow depth on Arctic sea ice. *Journal of Climate*, 12:1814–1829.
- Wassmann, P., 2008. Impacts of global warming on Arctic pelagic ecosystems and processes. In: Duarte, C. (Ed.). *Impacts of Global Warming on Polar Ecosystems*, pp. 111–138, FBBVA Press, Bilbao.
- Wassmann, P., M. Reigstad, T. Haug, B. Rudels, M.L. Carroll, H. Hop, G.W. Gabrielsen, S. Falk-Petersen, S.G. Denisenko, E. Arashkevich, D. Slagstad and O. Pavlova, 2006. Food webs and carbon flux in the Barents Sea. *Progress in Oceanography*, 71:232–287.
- Wathne, J.A., T. Haug and C. Lydersen, 2000. Prey preferences and niche overlap of ringed seals *Phoca hispida* and harp seals *P. groenlandica* in the Barents Sea. *Marine Ecology Progress Series*, 194:233–239.
- Watson, J.G., J.C. Chow and L.-W. Chen, 2005. Summary of organic and elemental carbon / black carbon analysis methods and intercomparison. *Aerosol and Air Quality Research*, 5:65–102.
- Weeks, W.F. and A.J. Gow, 1978. Preferred crystal orientations along the margins of the Arctic Ocean. *Journal of Geophysical Research*, 83:5105–5121.
- Wenzel, G., 2009. Canadian Inuit subsistence and ecological instability – if the climate changes, must the Inuit? *Polar Research*, 28:88–89.
- Werner, I., 1997. Grazing of Arctic under-ice amphipods on sea-ice algae. *Marine Ecology Progress Series*, 160:93–99.
- Weslawski, J.M., L. Stempniewicz and K. Galaktionov, 1997. Summer diet of seabirds from the Frans Josef Land Archipelago, Russian Arctic. *Polar Research*, 13:173–181.
- Weslawski, J.M., J. Wiktor and L. Kotwicki, 2010. Increase in biodiversity in the arctic rocky littoral, Sorkapland, Svalbard, after 20 years of climate warming. *Marine Biodiversity*, 40: 123–130.
- West, J.J. and G.K. Hovelsrud, 2008. Climate change in Northern Norway: Toward an understanding of socio-economic vulnerability of natural resource- dependent sectors and communities. *CICERO Report 2008:04*, 37 pp. Centre for International Climate and Environmental Research - Oslo.
- West, J. and G.K. Hovelsrud, 2010. Cross-scale adaptation challenges in the coastal fisheries: findings from Lebesby, Northern Norway. *Arctic*, 63:338–354.
- Wiig, Ø., E. Born and E.W. Garner (Eds.), 1995. Polar bears. *Proceedings of the Eleventh Working Meeting of the IUCN/SSC Polar Bear Specialist Group*, 25–27 January 1993, Copenhagen, Denmark. World Conservation Union.
- Wiig, Ø., J. Aars and E.W. Born, 2008. Effects of climate change on polar bears. *Science Progress*, 91:151–173.
- Wiktor, J., 1999. Early spring microplankton development under fast ice covered fjords of Svalbard, Arctic. *Oceanologia*, 41:51–72.
- Winsor, P., 2001. Arctic sea ice thickness remained constant during the 1990s. *Geophysical Research Letters*, 28:1039–1041.
- Winton, M., 2006a. Does the Arctic sea ice have a tipping point? *Geophysical Research Letters*, 33:L23504.
- Winton, M., 2006b. Amplified Arctic climate change: What does surface albedo feedback have to do with it? *Geophysical Research Letters*, 33:L03701.
- Winton, M., 2008. Sea Ice – albedo feedback and nonlinear Arctic climate change. In: DeWeaver, E.T., C.M. Bitz and L. Tremblay (Eds.). *Arctic Sea Ice Decline: Observations, Projections, Mechanisms, and Implications*, pp. 111–131, American Geophysical Union.
- Wiscombe, S. and S.G. Warren, 1980. A model for the spectral albedo of snow. I: Pure snow. *Journal of the Atmospheric Sciences*, 37:2712–2733.
- WMO, 2008. The State of Polar Research: A statement from the International Council for Science / World Meteorological Organization Joint Committee for the International Polar Year 2007–2008.
- Woodgate, R.A., T. Weingartner and R. Lindsay, 2010. The 2007 Bering Strait oceanic heat flux and anomalous Arctic sea-ice retreat. *Geophysical Research Letters*, 37:L01602.
- WWF, 2008. Arctic Climate Impact Science, An Update Since ACIA. M. Sommerkorn, and N. Hamilton (Eds.), World Wildlife Federation International Arctic Programme, Oslo, Norway.
- Xie, Z., L. Sun, J.D. Blum, Y. Huang and W. He, 2006. Summertime aerosol chemical components in the marine boundary layer of the Arctic Ocean. *Journal of Geophysical Research*, 111:D10309.
- Yackel, J., J. Hanesiak and D.G. Barber, 2000. Melt ponds on sea ice in the Canadian Arctic Archipelago. Part 1 – Variability in morphology and surface radiation. *Journal of Geophysical Research-Oceans*, 105:22049–22060.
- Ye, B., D. Yang, K. Jiao, T. Han, Z. Jin, H. Yang and Z. Li, 2005. The Urumqi River source Glacier No. 1, Tianshan, China: Changes over the past 45 years. *Geophysical Research Letters*, 32:L21504.
- Young, O., 2005. Governing the Arctic: from cold war theater to mosaic of cooperation. *Global Governance*, 11:9–15.
- Young, O., 2009a. Whither the Arctic? Conflict or cooperation in the circumpolar north. *Polar Records*, 45:73–82.
- Young, O., 2009b. Arctic in play: governance in a time of rapid change. *International Journal of Marine and Coastal Law*, 24:423–442.
- Yu, Y., G.A. Maykut and D.A. Rothrock, 2004. Changes in the thickness distribution of Arctic sea ice between 1958–1970 and 1993–1997. *Journal of Geophysical Research*, 109:C08004.
- Zhang, X. and J. Walsh, 2006. Toward a seasonally ice-covered Arctic Ocean: Scenarios from the IPCC AR4 model simulations. *Journal of Climate*, 19:1730–1747.
- Zhang, J., D.A. Rothrock and M. Steele, 2000. Recent changes in Arctic Sea ice: The interplay between ice dynamics and thermodynamics. *Journal of Climate*, 13:3099–3114.
- Zhang, J., M. Steele, R.W. Lindsay, A. Schweiger and J. Morison, 2008a. Ensemble one-year predictions of arctic sea ice for the spring and summer of 2008. *Geophysical Research Letters*, 35:L08502.
- Zhang, J., R.W. Lindsay, M. Steele and A. Schweiger, 2008b. What drove the dramatic retreat of Arctic sea ice during summer 2007? *Geophysical Research Letters*, 35:L11505.
- Zhang, X., A. Sorteberg, J. Zhang, R. Gerdes and J.C. Comiso, 2008c. Recent radical shifts of atmospheric circulations and rapid changes in Arctic climate system. *Geophysical Research Letters*, 35:L22701.
- Zhang, J., M. Steele and R. Woodgate, 2009. The role of Pacific Water in the dramatic retreat of arctic sea-ice during summer 2007. *Chinese Journal of Polar Science*, 19:93–107.
- Zhang, J., M. Steele and A. Schweiger, 2010. Arctic sea ice response to atmospheric forcings with varying levels of anthropogenic warming and climate variability. *Geophysical Research Letters*, 37:L20505.
- Zhou, F., A. Zhang, R. Li and R. Hoeve, 2009. Spatio-temporal simulation of permafrost geothermal response to climate change scenarios in a building environment. *Cold Regions Science and Technology*, 56:141–151.
- Zubov, N., 1945. Arctic Ice. 1. National Technical Information Service, Springfield VA, Report A0426082 (translated from original Russian).

10. Arctic Societies, Cultures, and Peoples in a Changing Cryosphere

LEAD AUTHORS: GRETE K. HOVELSRUD, BIRGER POPPEL, BOB E.H. VAN OORT, JAMES D. REIST

CONTRIBUTING AUTHORS: DEREK ARMITAGE, HALVOR DANNEVIG, HENRY HUNTINGTON, AMY LOVECRAFT, STINE RYBRÅTEN, JEREMY L. WHITE

Contents

Key Findings	2	10.6. Cumulative effects and synergies in and beyond the Arctic	24
10.1. Introduction	2	10.6.1. Cryospheric drivers of change	25
10.2. Living in the North	3	10.6.2. Non-cryospheric drivers of change	27
10.2.1. Arctic populations and economies	3	10.6.3. Beyond the Arctic	28
10.2.2. Livelihood activities	7	10.6.4. 'Winners and losers'	28
10.2.3. Human health and well-being	10	10.7. Gaps in knowledge and future needs	29
10.3. Increased activities and access with local implications	11	10.7.1. Research needs	29
10.3.1. Transport and infrastructure, tourism	11	10.7.2. Observation, monitoring, modeling, and downscaling needs	30
10.3.2. Changes in access and availability of renewable and non-renewable resources	14	10.7.3. Meeting governance and technology needs	31
10.4. Adaptation across scales	17	Appendix 10.1. Relevant projects under the International Polar Year	32
10.4.1. Adaptation and adaptive capacity	18	References	34
10.4.2. Challenges and opportunities	20		
10.4.3. Hazards and safety	20		
10.4.4. Technological developments as an adaptation	21		
10.4.5. Adaptation to extreme weather events	22		
10.5. Governance	22		
10.5.1. Multi-level governance institutions and co-management	23		
10.5.2. Industrial development and regulation	24		

Key Findings

- The changing cryosphere causes physical and biological changes with consequences for livelihoods and living conditions.
- While indigenous peoples and local Arctic communities will be challenged to maintain their way of life, opportunities including increased shipping and commercial development of renewable and non-renewable resources are expected to benefit mainly non-Arctic actors.
- Local, regional, and international challenges include maintaining traditional land use and sea use; hunting, harvesting, and herding activities; infrastructure; search and rescue; pollution; human health; and indigenous and local rights and involvement.
- Coastal erosion, thawing permafrost, and changing sea-ice conditions (such as thickness, extent, and age), when combined with non-cryospheric drivers of change (such as increased economic activity, socio-economic development, demographics, governance, and the health and well-being of the Arctic society and people) will result in multi-faceted and cascading effects.
- Indigenous peoples and other local residents are resilient and active rather than passive actors, but the rate of cryospheric changes will continue to challenge current adaptive capacity.
- Major uncertainties remain in terms of the direct and indirect impacts of cryospheric change on human society, in and beyond the Arctic, and in terms of the timescale of changes and adaptations.
- Understanding of cryospheric change is needed at different scales. Local projections are required by local residents and external groups or industries with economic interests to adapt to changes, and regional understanding of the role of the cryosphere in climate forcing must be considered in developing global mitigation responses.

10.1. Introduction

The aim of this chapter is to identify and link the key effects of cryospheric change with key aspects of human society and activities in the Arctic. Ice, water, and snow are integral to living conditions and livelihood activities throughout the region and in recent years major changes in the Arctic cryosphere have been documented (see the preceding chapters of this report). These comprise a significant component of overall climate change impacts. Impacts of cryospheric change, albeit laden with uncertainty, occur over broad spatial and temporal scales and across local, regional, national, and international societal levels. In addition to the effects of a changing cryosphere, human society in the Arctic is also exposed to non-climatic factors such as the extractive industries, demographic changes, technological developments, and other impacts of globalization processes.

These changes are, in turn driven by complex linkages between changing cryospheric conditions, global resource demands, and societal changes. It is within this wider context of change that the consequences of cryospheric change for human society and activities must be understood. In this chapter, ‘human society’ refers to large and small, indigenous and non-indigenous communities; Arctic migrants (i.e., seasonal workers); industrial sectors (i.e., fisheries, tourism, mining, petroleum); international relations; and governance. The cross-scale approach (linking local, regional, national, and international scales) to understanding how cryospheric and societal conditions combine to shape adaptation and vulnerability provides the foundation for this chapter.

The Arctic Climate Impact Assessment (ACIA, 2005), which provides the baseline for the present assessment emphasized that a focus on relevant cross-cutting issues and multiple stressors that shape vulnerability and resilience to change were needed in future assessments. ACIA concluded that future assessments of economic consequences of climate change should include all Arctic residents, include integrative vulnerability studies, and increase the relevance for Arctic residents through local focus. One of the major findings on the polar regions in the Intergovernmental Panel on Climate Change (IPCC) Fourth Assessment Report (AR4) (IPCC, 2007) is that changes in the terrestrial cryosphere, hydrology, permafrost, and sea ice are increasingly affecting biophysical systems and having cascading effects on Arctic societies. Furthermore, the AR4 found that cryospheric changes will have costs and benefits for Arctic socio-economic systems and activities. The resilience shown historically by Arctic indigenous peoples is now severely tested, and substantial investments are needed to adapt or relocate physical structures and communities and to enhance adaptive capacity. The benefits, dependent on local conditions, include reduced heating costs, increased agricultural and forestry opportunities, more navigable northern sea routes, and greater marine access to resources.

The present assessment has identified the following findings as the most significant since ACIA (2005): (i) there have been dramatic changes in the cryosphere in this decade; (ii) the rate at which these changes have taken place is more rapid than previously observed; and (iii) the effects of changes in the cryosphere substantively alter living conditions in the Arctic and have significant implications for individuals and households at

local, regional, national, and global scales (Chapter 1). Current local-scale observations of change (by indigenous and non-indigenous residents) include a significant thinning of sea ice and freshwater ice, a shortening of the winter ice season, a reduction in snow cover, changes in the distributions of wildlife and plant species, thawing permafrost, and increased coastal erosion (e.g., Tyler et al., 2007; Forbes, 2008; Furgal and Prowse, 2008; Ford et al., 2009; Andrachuk and Pearce, 2010; Forbes et al., 2010; Hovelsrud et al. 2010b). Such observations are corroborated by many scientific findings (see Chapters 4 to 9).

The previous chapters describe how cryospheric changes have affected and will affect people in the North. Changes in snow cover and snow duration; permafrost; sea-ice extent, duration, and age; timing of freeze-up and break-up of ice on rivers and lakes; and melting of glaciers and ice caps will create challenges as well as opportunities for people both inside and outside the Arctic. While giving the Arctic region a more defined role in the world economy, cryospheric changes will pose challenges for individuals and local communities, for national and international governance, safety, search and rescue operations, resource management, and demands on technological advances across virtually all sectors of human endeavor in the Arctic.

Sea-ice retreat creates longer open-water seasons and will be generally positive for the transportation sector. These changes may have positive spinoffs for the North, creating employment opportunities and revenues and providing economic opportunities in developing the potential renewable and non-renewable resources in the region. The projected trend of increased tourism, including cruise-ship tourism will create opportunities for entrepreneurs and operators in the region, provided the human skills and financial resources are available. A changing snow regime may provide an increased hydropower potential, and thus opportunities for industrial development in remote areas with demand for more power (e.g., mines). The changing permafrost may offer opportunities for some agricultural activities if it thaws completely.

Drawing on the most recent data about present and future conditions, on current understanding of the complex linkages between environmental and socio-economic conditions, and on the information provided in the preceding chapters, this chapter covers the livelihood activities, sectors, and challenges and opportunities most relevant when considering a changing cryosphere. A detailed assessment of all sectors at all scales for all regions of the Arctic is beyond the scope of this chapter.

10.2. Living in the North

- Key shifts in physical access afforded by the cryosphere will affect individuals, communities, and sectors in the North through multiple pathways with the direction and magnitude of the overall effects dependent upon spatial and temporal scales.
- Accessibility shifts combined with societal changes will affect the economy, health and well-being, and quality of life of all northerners. These shifts will result in far-reaching effects at regional and national levels and beyond the Arctic.

Changes in the cryosphere are expected to have significant impacts on the living conditions and livelihood activities within

and outside the Arctic. In addition, such changes will affect seasonal residents and non-residents with interests in the region. The relationship between a changing cryosphere and local impacts is complex, mediated by the interaction of multiple biophysical and human stressors operating over different spatial and temporal scales. For example, risk assessment of using sea ice for travel and hunting must be linked with reduced time to hunt, diminishing land and sea skills and knowledge among younger generations, decreased reliability of traditional knowledge as conditions change, and use of new technology. The overall risk must be balanced by the individual against the need for harvesting (i.e., food security). Moreover, from the individual perspective of a coastal community resident, earlier and increased marine access afforded by sea-ice decline may result in lower costs for supplies, equipment, and non-traditional/non-local foods.

Thus, the sum of such effects on livelihoods, living conditions, and health and well-being is the key issue. This integration of effects from all cryospheric (and other) changes is important across individual, community, regional, and national levels in the Arctic. Although the changing cryosphere will first and foremost impact peoples (indigenous and non-indigenous) and sectors in the High Arctic, significant consequences for the southern Arctic will also occur through, for example, thawing permafrost, changing snow conditions, and changes in frozen river and lake ice (e.g., Anisimov et al., 2007; Furgal and Prowse, 2008).

10.2.1. Arctic populations and economies


The Arctic covers 11% of the global surface area. Demographic estimates vary with definitions of Arctic geographical extent and seasonal migration. Depending on the geographical definition, population figures vary between 4 million (AHDR, 2004) and 9.9 million (Duhaime and Caron, 2009) (see Figure 10.1). Estimates of indigenous populations range from 400 000 to roughly 1.3 million.

Between 2000 and 2005, the Arctic population declined by nearly 1%, with the greatest decline in the Russian Arctic and the smallest decline in Arctic Sweden and Norway. In all other Arctic regions, populations have increased (Mäenpää, 2009). Seasonal variation due to work-related migration is particularly applicable in the Russian Federation, which accounts for roughly 75% of all Arctic inhabitants, 7.1 million (down from 7.9 million in 1995) (Glomsrød et al., 2009), and by far the largest share of Arctic land area.

The Arctic is characterized by a dispersed settlement pattern with few large cities. About one-third of Arctic residents live in settlements with a population size of less than 5000 and one-tenth of the Arctic population lives in one of the five largest cities (> 100 000 inhabitants; see Figure 10.1) (Bogoyavlensky and Siggner, 2004). The Arctic is an exporter of raw materials and energy and an importer of final goods and services; in 2005, the Arctic area was responsible for generating 0.5% of the global gross domestic product (GDP) (Mäenpää, 2009).


The gender balance varies throughout the Arctic regions. With the exception of the Russian Arctic regions, overall there are more men than women in the Arctic (Bogoyavlensky and Siggner, 2004; Duhaime and Caron, 2009). This is partly a consequence of greater migration by men than women into

a




b

Population of Arctic regions



Indigenous population of Arctic regions, % of total






Figure 10.1. Population and economy of the Arctic. (a) Settlements in the Arctic and their population (~2010), (b) total and indigenous population distribution (figure adapted from Nyman Larsen et al., 2010 and Nordregio, www.nordregio.se), (c) the distribution of Arctic peoples subdivided according to language families (adapted from Winfried K. Dallmann, Norwegian Polar Institute, 2004), (d) Gross Product (Gross Domestic Product or Gross Regional Product) within the circumpolar Arctic by sector and country (based on data from Glomsrød et al., 2004).

Arctic regions seeking jobs primarily in the construction and extraction industries. In addition, there is a tendency among younger women in parts of the Arctic to leave to take advantage of education and career opportunities outside the Arctic (e.g., Rauhut et al., 2008; Poppel, 2010).

Since their arrival in the Arctic, the indigenous peoples have lived from the renewable resources of the sea (fish, marine mammals), the land (land mammals, birds, berries), and freshwaters (fish). Although not considered in official Arctic gross regional product (GRP) assessments, the contributions from commercial and subsistence fishing, hunting, and herding activities are documented as playing a significant role in the mixed cash-subsistence economies (e.g., Rasmussen, 2005a; Poppel, 2006; Kruse et al., 2008; Aslaksen et al., 2009; Poppel and Kruse, 2009). Alaskan harvest surveys during the 1990s found an average harvest of wildlife (fish and game) of 375 pounds (~170 kilograms) per rural resident (Wolfe, 2000), and more recent surveys indicate that subsistence fishing and hunting are still a vital part of the economy in many Alaskan communities (Krieg et al., 2009). The importance of subsistence activities can be measured in different ways. The Survey of Living Conditions in the Arctic (SLiCA: Poppel et al., 2007; Poppel and Kruse, 2009) offers opportunities to analyze economic, integrative, nutritional, social, cultural, and identity aspects of subsistence. One of the SLiCA findings was an indication of the importance of traditional/local food to the diet: two out of three Inuit households report that half or more of the household's food consumption is traditional/local food items. The SLiCA report also documented that traditional/local food is still shared between households. In Greenland, Arctic Canada, and northern Alaska, on average 75% of the Inuit households had shared traditional/local food with other households during the previous 12 months (Poppel et al., 2007).

Renewable harvesting is linked to the subsistence-based informal economy and to the market economy. In 2002, the total catch of fish in the Arctic region represented around 10% (7.26 million tonnes) of the global catch of wild fish (Lindholt, 2006). In addition, in 2002 the Arctic region's catch of shrimp and snow crab made up 5.3% (355 000 tonnes) of the total world crustacean catch (Lindholt, 2006).

The GRP is a measure of the total value of goods and services in a given territory. Comparing the contributions from the primary sector (exploitation of natural resources), the secondary sector (manufacturing and construction), and the tertiary sector (public and private services) to GRP, as well as to the overall Arctic GDP, the tertiary sector is the most dominant (Figure 10.1). Only in Arctic Russia is the primary sector more dominant (Glomsrød et al., 2009). This means that, apart from the Russian Arctic, public services such as education, health, and social work account for a significant part of all economic activities (Duhaime, 2004). The largest economies in the Arctic belong to Alaska (United States) and Russia, mainly due to mining and petroleum activity. Regions where more traditional subsistence activities, such as hunting and fishing, play a more dominant role (e.g., Greenland and northern Canada) have much lower GRP. Similarly, reindeer herding in Russia and Scandinavia is of substantial importance to the livelihoods and lifestyles of reindeer herders like the Sámi and the Nenets but does not contribute greatly to GRP in these regions.




Figure 10.2. Composition and relative size of the main industries (upper) and natural resource-based industries (lower) in the Arctic in 2005. Source: Glomsrød et al. (2009).

The abundance of renewable and non-renewable resources, and the generated share of GDP, varies from region to region (Figure 10.2). In 2005, fishing was the most important resource-based activity in the Greenlandic, Icelandic, and Faroese economies; oil and gas extraction was by far the largest industry in Alaska and Arctic Russia; and minerals (particularly diamonds) contributed the most to GDP for the Canadian Arctic. Fish and energy resources added most value to the Norwegian GDP. In Sweden, the greatest value was added by mineral extraction, and in Finland by timber (Glomsrød et al., 2009). In 2007, Arctic oil and gas activities amounted to one tenth of the world's total oil production and one-quarter of the world's total gas production. Of this, 80% of the oil and 99% of the gas were extracted within the Russian Arctic (AMAP, 2007). The Arctic is also rich in minerals other than oil. The Arctic region contains a large variety of mineral resources: coal, iron, and ferro-alloy minerals (e.g., nickel, cobalt, tungsten), non-ferrous minerals, and precious metals (e.g., zinc, lead, palladium, platinum), and industrial minerals (e.g., diamonds, apatite) (Lindholt, 2006).

The GRP assessments of regional economies do not show the distribution of income within the region and do not provide an exact measure of the total disposable income to be shared among households and individuals in the region. This is because resource rents and returns to the fixed capital may be transferred out of the region and because other mechanisms such as state transfers can contribute to household disposable income. Generally, the net result for all Arctic regions shows that the disposable income of households per capita is lower than GRP per capita (Glomsrød et al., 2009), which supports the hypothesis that the Arctic is a net exporter of raw materials and energy.

For many Arctic indigenous peoples, the cryosphere is fundamental to their cultures and identities in myriad ways. In general terms, the cryosphere has traditionally been used as a platform for travelling, and for livelihood activities such as herding, hunting, and fishing (e.g., Nuttall et al., 2005; Tyler et al., 2007; Ford and Furgal, 2009). The cryosphere also plays a fundamental role in the life and work of non-indigenous residents, through non-renewable resource extraction; hunting, fishing and recreational activities; and extensive use of seasonal ice roads across wet tundra, rivers, and lakes. These roads provide key transportation routes for relatively inexpensive transport of heavy equipment, foodstuffs, and other supplies for residents and industry. Accessibility afforded by these roads reduces the cost of living in the North (see Chapters 5 and 6; Furgal and Prowse, 2008).

Arctic residents rely on their extensive traditional and local knowledge (see description in Section 10.2.2), and on their observations of the environment and weather when making decisions on when, where, and how to build, travel, or harvest. Many Inuit elders and experienced hunters have noted changing sea-ice conditions over the past decade, including later ice freeze-up and earlier break-up, a longer ice-free open-water period in summer, and altered ice dynamics. It has been reported that Inuit observations often correspond to the instrumental record (see Ford et al., 2009; Laidler et al., 2009), and the value of integrating scientific, local, and indigenous knowledge is increasingly acknowledged (e.g., Gearheard et al., 2006; Hovelsrud and Winsnes, 2006; Weatherhead et al., 2010).

The documentation and incorporation of traditional and local knowledge is currently central to research on community adaptation to climate change (e.g., Hovelsrud and Smit, 2010).

10.2.2. Livelihood activities

Livelihood activities, which historically have been closely connected to the natural (primarily renewable) resource base, are also influenced by globalization (e.g., Keskitalo, 2008). Traditional subsistence economies without some form of cash flow no longer exist in the Arctic, but there are still many smaller indigenous communities with mixed cash-subsistence economies (Figure 10.3) in which hunting, harvesting, and herding are combined with predominantly service and administrative jobs (e.g., Hovelsrud, 1999; Duhaime, 2004; Poppel and Kruse, 2009). Shifts toward wage-based economies may erode traditional knowledge among younger generations. In turn, the decreasing ability to ‘live off the land’ contributes to further shifts. Traditional knowledge is gained through experiences in the natural environment and is based on oral tradition reflecting the past, present, and future. It is passed down through generations and pertains to the environment and a human’s activities in it as a holistic relationship. The accumulated knowledge from the past must always be fine-tuned to fit the present (e.g., Hovelsrud and Winsnes, 2006). Hence, traditional knowledge is dynamic and not statically situated in the past. Subsistence activities are adapted to seasonal and interannual variations in, among others, snow and ice, but the current dramatic and rapid changes of the cryosphere further challenge their continuation and in combination with other drivers will most likely contribute to the shift toward wage-based economies.

Many of the smaller communities, relying on harvesting, are vulnerable to changes in the natural resource base and respond by diversifying the targeted species, supplementing with wage jobs and a social safety net of sharing and cooperation. Flexibility in the ability to harvest different species of fish or game and in cash-earning activities is critical to reducing vulnerabilities to change and for ensuring well-being, societal integrity, and human security (Rasmussen, 2005b; Poppel, 2006; Poppel and Kruse, 2009; Hovelsrud and Smit, 2010).



Figure 10.3. There are no longer any societies in the Arctic that only engage in subsistence activities without a flow of cash. All Arctic households and economies have some level of cash flow. The level of cash flow varies by region, season, and household.

10.2.2.1. Reindeer husbandry

Reindeer husbandry is an important livelihood activity for the Sámi across Fennoscandia, as well as for several indigenous peoples in Arctic Russia. Topography, local variation in pasture condition, and the response of snowpack dynamics to weather have implications for the complex relationship between snow, ice, and reindeer pasture conditions (e.g., Kumpula and Colpaert, 2003, 2007; Roturier and Roué, 2009). Reindeer herders employ traditional knowledge to respond to varying pasture conditions (e.g., Tyler et al., 2007). Such herding strategies are shaped by factors such as season, snow type, temperature, landscape, and the physical condition of the animals. Strategies are also influenced by previous experience of unusual weather conditions, such as ice layers on the surface of the snow. Snow types range from those influenced by weather (new and light or icy types) to those transformed by reindeer grazing, digging, and trampling. These snow types are well documented by Sámi (e.g., Magga, 2006), as is their effect on herding practice (e.g., Roturier and Roué, 2009).

Reindeer pasture will be directly affected by the changing snow, permafrost, and lake and river ice conditions (Anisimov et al., 2007). Increased frequency of rain-on-snow and mid-winter melt events in some regions of the Arctic, associated with earlier spring snowmelt and coverage, results in an earlier start of the growing season (Schmidt et al., 2006; Meltofte et al., 2008). This has a generally positive impact on the herbivores' pastures (Forchhammer et al., 2005), particularly inland (Karlsen et al., 2007). However, the earlier break-up of lake and river ice, which accompanies earlier snowmelt, presents challenges for reindeer migration from winter to summer pastures, particularly for newborn calves (Rybråten and Hovelsrud, 2010).

Among the Nenets, rain-on-snow and winter warming events are known to increase ice layer formation over pastures, affecting reindeer access to pastures (Forbes, 2008; Forbes and Stammer, 2009). Freeze-thaw events may also damage reindeer pastures. In Fennoscandia, reindeer mortality and reduced calf production have tended to be higher in winters with heavy ice crust formation (Helle and Kojola, 2008; Moen, 2008). In contrast, studies from Svalbard found no links between icing and reindeer mortality (Tyler, 2010). Mold formation in the soil, which may result from snow falling on unfrozen ground during mild, rainy autumns, is harmful to the animals and may kill calves (Eriksson, 1976; Pruitt, 1984; Turunen et al., 2009). Snow depth, density, and elevation have additional ramifications for reindeer husbandry. Snow depth, which varies by region (snow cover is projected to generally increase in Arctic Russia and Canada and decrease in the European Arctic; see Chapter 4), also determines the energy that reindeer expend seeking grazing areas, by walking across the snow surface and digging through the snowpack.

Reindeer husbandry involves many hazardous tasks, particularly during reindeer gathering prior to migration or slaughter. During these periods the herders use vehicles (motorcycles, snowmobiles, helicopters, airplanes, boats) to gather the reindeer, often working long days (Daerga et al., 2004). Changes to snow conditions may negatively affect these tasks, increasing pressure on time and encouraging risk taking, thus increasing health and safety concerns.

Arctic winter precipitation is likely to increase and

depending on the conditions (i.e., rain *vs* snow and the frequency of freezing rain events) will have implications for the future success of reindeer herding. An increase in snow density may be negative in some areas if combined with increased wind, leading to heavier snow packing. Less multi-annual snow at high elevations in summer will decrease the possibilities for reindeer to evade flies and mosquitoes by moving to higher altitude. Although the direct consequences of cryospheric change may seem predominantly negative for reindeer husbandry, the broader context of socio-economic as well as market and political conditions must also be considered.

10.2.2.2. Fishing and hunting

Many inhabitants of the High Arctic, both indigenous and non-indigenous, live near the coasts where sea-ice variability, resulting from dynamic and thermodynamic processes, is a dominant feature of the environment. Across the Arctic, livelihood activities are adapted to local sea-ice conditions and the seasonal and behavioral patterns of the species harvested. Changing sea-ice conditions affect the distribution of these fish, marine mammals, and seabirds species. Existing fish stocks show horizontal and vertical distributional changes as their seasonal migration is related to the formation and melting of the sea ice (Sherman et al., 2009; Sundby and Nakken, 2008; West and Hovelsrud, 2010).

Arctic hunting activities are particularly sensitive to snow, ice, and permafrost conditions (Ford and Furgal, 2009). Marine mammals, particularly seals, have been essential for survival for many coastal indigenous peoples in the Arctic, and loss of hunting grounds, changes to species' availability (see Wiig et al., 2008), and seasonal hunting patterns present challenges for local communities. Access to key hunting areas has been constrained, particularly in spring and autumn, resulting in shortages of traditional/local food items such as seal, walrus, and caribou. However, sea-ice refugia are expected to persist in the Canadian and Greenland archipelago and secure the survival of ice-related species such as narwhal, and some seal and whale species (Armitage, 2005; Gearheard et al., 2006; Hovelsrud et al., 2008; Laidre et al., 2008; Moore and Huntington, 2008; Ford, 2009; Wenzel, 2009). In cold weather, the reindeer in Greenland move toward the coast, where they become more accessible to hunters; while in warmer weather, the animals move toward cooler conditions closer to the ice margin in order to reduce insect harassment. This significantly increases the distance the hunters will have to walk to search for the animals and to carry the harvest back to their boats.

In parts of the Canadian Arctic, hunters are required to travel farther to access hunting areas (Ford et al., 2010a; Pearce et al., 2010). In some instances, travel has had to change temporally as well as spatially, and sometimes simply to another location and not necessarily further away (e.g., SIKU project: Krupnik et al., 2010). In Greenland, a number of local and regional sea-ice travel routes can no longer be used, and hunters traveling by dog team are forced to travel overland, which is more time consuming and can be more dangerous than sea-ice travel under typical conditions (Goldhar et al., 2010).

Hunting and fishing have important symbolic and cultural values in many indigenous communities and are important to

Box 10.1. Traditional beliefs and health

For indigenous peoples, the cryosphere is fundamental to their cultures and identities, and its changes provide the context for current changes in their personal relations, health, and well-being. The concept of well-being is complex with physical, mental, emotional, and spiritual aspects. The complex interrelation is a theme explored by many indigenous cultures.

There often seems to be a discrepancy between the indigenous feeling of well-being and that defined by social scientists. This also has profound implications for conventional Western views on health, where the focus on individual health problems (abuse, maladjustment, lifestyle symptoms) contrasts with that of the collective or community-based approach by many indigenous peoples.

For Inuit, health is deeply connected to social behavior and its relationship with diseases. In the traditional Inuit belief system, Inuit disease is a consequence of transgression against the social or spiritual orders. At the same time, ‘common sense empiricism’ coexists within the Inuit belief system: snow blindness, for example, is common-sense pathology and does not require a metaphysical explanation. While biomedicine is better informed about the workings of the body, traditional Inuit understanding of the relations between person, family, social group, community, and the environment represents a global view of health that is not shared by biomedicine (Bowd, 2005). This is an important area to consider in future studies of Inuit health and well-being.

nutrition and health; individual, household, and community economies; identity; and cultural, spiritual, and social well-being (see Box 10.1) (Huntington et al., 1998; AHDR, 2004; Poppel, 2006; Hovelsrud et al., 2008; Poppel and Kruse, 2009). Although the overall commercial value of seal hunting is limited, the subsistence harvest of seals, other marine mammals and fish continues to play important roles for indigenous communities (e.g., Rasmussen, 2005a). The SLiCA project indicates that four out of ten Inuit households harvest about 50% or more of the meat consumed (Poppel et al., 2007; Poppel and Kruse, 2009). Thus, subsistence and informal economic activities still provide a significant part of their diet, as well as their health and culture. Seal meat, for example, is an important part of the diet, health, and culture for many Arctic indigenous peoples. It is also important for feeding sled dogs and critical for hunting, fishing, and tourism (Nuttall et al., 2005; Rasmussen, 2005a; Ford et al., 2010a; Pearce et al., 2010). Because of extensive food-sharing networks, changing ice conditions also challenge the cultural and spiritual identity of and nutritional quality for community members who do not rely on hunting and/or do not have access to financial resources to adapt (e.g., Goldhar and Ford, 2010).

10.2.2.3. Agriculture

Agriculture in the Arctic has not changed significantly since the ACIA report (Juday et al., 2005) (see Glomsrød et al., 2009, for a regional comparison of the contribution of agriculture to the regional GDP). Agriculture is a relatively small industry in most of the Arctic in terms of value added (see Figure 10.2, category

‘other food’; Juday et al., 2005). Still the sector constitutes an important foundation for settlements in the Eurasian part of the Arctic and in southern Greenland (Tholstrup and Rasmussen, 2009). Arctic agriculture is a mixture of large-scale commercial production and subsistence agricultural production with a focus on cool season forage crops (e.g., alfalfa, red clover, timothy), vegetables (e.g., beans, peas, potatoes), and small grains (e.g., wheat, canola). Livestock production is concentrated on cattle, goats, lamb, sheep, pigs, poultry, and reindeer. Subsistence agriculture, in combination with other food production activities such as fishing and hunting, is present throughout the Arctic, albeit not in great numbers. Agricultural development is constrained by lack of wider market access resulting from remoteness, lack of infrastructure, and sparse population (Juday et al., 2005; Hovelsrud et al., 2010a). Except for reindeer husbandry, crop production is generally more sensitive to cryospheric conditions than livestock production (Juday et al., 2005), but with considerable regional variation within the Arctic. Duration of snow cover, freeze-thaw events, icing, and permafrost constitute the primary cryospheric limitations to Arctic agricultural production.

Although regional differences exist, a changing cryosphere is expected to have predominantly positive impacts on agriculture in the Arctic. In areas with a reduction in snow cover, the growing season may be extended (Torvanger et al., 2004; Falloon and Betts, 2010; Grønlund, 2009; Tholstrup and Rasmussen, 2009). Earlier snowmelt will also lengthen the growing season and reduce the likelihood of fungal damage to crops. A stable snow cover of at least 120 days is required for fungus to develop and harm crops. On the other hand, plants that are well adapted to Arctic conditions may not prove adaptable to a longer growing season (e.g., Aaheim et al., 2009). Ice crust formation and rain-on-snow events (i.e., generally increased variability in precipitation regimes) may also affect agricultural production (Grønlund, 2009). Less snow may expose plants to wind and frost damage through reduced insulation (Bjerke and Tømmervik, 2008; Grønlund, 2009).

Rain-on-snow events and melting and refreezing of snow may result in frost damage, with potentially major economic consequences (Putkonen and Roe, 2003; Aaheim et al., 2009; Grønlund, 2009). Similarly, increased runoff from glaciers, melting snow, and presence or absence of permafrost can affect drainage capacity and result in frost damage if refreezing occurs (e.g., Grønlund, 2009). In general, projections of increasingly mild weather (see Chapter 3) are expected to decrease the frequency of frost damage events. On the other hand, increased precipitation and runoff combined with episodes of freezing and thawing could considerably increase soil erosion in agricultural fields (Øygarden, 2003; O’Brien et al., 2006; Grønlund 2009).

Changes in nutrient flow and distribution resulting from increased runoff can positively affect agriculture, but can also enhance contaminant transfer to rivers, lakes, and the sea (Falloon and Betts, 2010). Other negative impacts of excess water include soil waterlogging, anaerobicity, and reduced plant growth (Bradley et al., 2005). Farming operations on wet soils may cause compaction damage (Finlayson et al., 2002; Webb et al., 2005; Montanarella, 2007) or agricultural machinery may simply not be adapted to wet soil conditions (Eitzinger et al., 2007).

10.2.2.4. Forestry

Large tracts of boreal forest cover sub-Arctic and low Arctic areas of the North (e.g., ~57 million hectares in the Yukon, Nunavut, and Northwest Territories of Canada) (Furgal and Prowse, 2008). Similar to marine and freshwater ecosystems, a healthy terrestrial ecosystem is essential to cultural, spiritual, and social well-being of indigenous and local peoples of this area. Moreover, large economic benefits are derived from merchantable timber. Increased freeze-thaw events may cause damage to forests and timber, and increased fungal or insect attacks may destroy drying timber and reduce economic profit (Aaheim et al., 2009). In addition and depending on the region, heavier snowfalls and icing may crush tree canopies and hinder new growth (Keskitalo, 2008). Reindeer grazing has potentially two opposing effects on forest expansion. The removal of lichen may allow birch seeds to germinate and sprout successfully, while reindeer grazing on birch seedlings, shoots, and leaves may hinder the advance of the treeline (Houle and Fillion, 2003; Tømmervik et al., 2004, 2009; Dalen and Hofgaard, 2005).

In general, snow is an important factor in damage to forests (Kilpelainen et al., 2010). In Finland, where forestry is of great economic importance, the risk of snow damage to forests is projected to decrease by about 50% toward the end of the 21st century. The effects of cryospheric change on forests will interact synergistically with other non-climatic changes to ultimately result in greater impacts on forestry.

10.2.2.5. Tourism

Over the years, access to the Arctic has increased through improved transport technologies, such as ice-strengthened ships, air transport, and specialized vehicles. As a result, Arctic tourism has developed substantially, in terms of the number of tourists as well as geographical and seasonal reach (UNEP, 2007; Stewart and Draper, 2006a). The sector is diverse, aimed at the mass market, and includes sports fishing and hunting, ecotourism, adventure tourism, dogsledding, and cultural and heritage tourism. Iconic Arctic species such as the polar bear draw tourists northward (e.g., Forgiione and Martin, 2008; Dickson et al., 2009), but also hold considerable value for many people who will never visit the region.

Tourism is an integral part of local economies, individual and household incomes, revenues, and financial capital for northern infrastructure and has become an alternative source of income for many local communities and gateway cities, enabling a positive interaction between new economic opportunities and traditional activities (Rasmussen, 2005b; UNEP, 2007; Tholstrup and Rasmussen, 2009). Tourism activities include the production and sale of indigenous handicrafts and artwork such as carvings, weavings, and prints. Sport hunting of polar bears is important to economies for some Inuit communities, whereas in other areas such hunting is allowed for subsistence use only (e.g., Hovelsrud et al., 2008).

As provided through the examples above, cryospheric change will result in major changes in livelihood activities throughout the North from the individual to the national level.

10.2.3. Human health and well-being

Changing cryospheric conditions directly and indirectly affect the health of Arctic inhabitants. Cryospheric conditions directly affect work, travel, and safety. Indirectly, higher temperatures in combination with altered ultraviolet (UV) levels will affect wildlife (composition and abundance) and increase the risk of zoonotic diseases (Berner et al., 2005; AMAP, 2009).

Climate change has been shown to propagate infectious disease agents into the Arctic and further modifications are expected; a more accessible Arctic will increase human exposure and vulnerability to new and emerging infectious diseases (Parkinson, 2008).

The release of antibacterial pharmaceuticals from human settlements may also weaken human resistance under cold Arctic conditions (Kallenborn et al., 2008). Infrastructure essential for community sanitation and drinking water provision may be degraded or destroyed through the action of thawing permafrost or extreme weather events, such as flooding or storms. This may lead to increased possibility of food- and water-borne diseases and respiratory infections (Parkinson and Butler, 2005).

Melting ice and thawing permafrost may also release persistent environmental legacy pollutants (such as POPs and metals) from past human activities at lower latitudes that have been carried into the Arctic in the prevailing winds and ocean currents and stored in the cryosphere (AMAP, 2009). Contaminants may be released from local sources such as sea ice, permafrost, ice sheets, degrading glacial snow, and from distant sources (Gregor and Gummer, 1989; Pinglot et al., 1999; Hermanson et al., 2005). These can negatively affect the immune system in animals and humans (Kraemer et al., 2005; Hansen et al., 2008) as well as degrade the quality of traditional/local foods. Cycling rates or entry points of contaminants into biotic systems may also change, thus affecting the health and productivity of ecosystems. This may reduce the quality of traditional/local foods as well as commercial products (Chapter 11, Section 11.3).

A decrease in freshwater ice (river, lake, permafrost) and longer open-water seasons mean greater freshwater availability, which as a consequence of climate change also will be warmer; both of these factors will foster zoonotic diseases. Higher ambient temperatures, for example, may result in an increase in some temperature-sensitive food-borne diseases, such as gastroenteritis. In addition, small changes in temperature and humidity will affect the distribution and behavior of many vector-borne diseases such as West Nile virus (e.g., Petersen and Roehrig, 2001; Parkinson and Butler, 2005). Higher temperatures also benefit bacteria, parasites, and insects (Bradley et al., 2005) and may drive increased propagation of zoonotic pathogens (e.g., *Giardia*, *Toxoplasma*, and *Echinococcus*) in water- and food-borne pathways.

Food contamination problems may become particularly acute where permafrost 'ice houses' are used for local and community storage of foodstuffs. In this case, thawing permafrost will negatively affect communities relying on traditional/local foods, thereby having consequences for human health and well-being (Parkinson and Evengård, 2009). Although significant for all coastal communities, subsistence harvesting remains very important in places with few jobs and little cash income as traditional/local foods provide a valuable

source of energy, nutrients, and minerals (Nuttall et al., 2005; Rasmussen, 2005a; Poppel and Kruse, 2009).

Changing sea- and river-ice conditions affect travel safety and inhibit access to key hunting, fishing, and herding areas already constrained by changing natural resource use. The health and economy of some Arctic inhabitants are already affected by changes in the timing of hunting, fishing, and herding activities. A reduction in land-fast ice combined with increased open-water area makes sea ice and fog conditions less predictable, making coastal travel treacherous and communication between communities more difficult (Barber et al., 2008). Traditional travel routes to hunting and fishing grounds or for visiting family are in many places no longer safe, forcing people to travel longer distances, which compromises safety (Ford et al., 2007; Hovelsrud et al., 2008).

Although traditional knowledge is flexible and highly adapted to major fluctuations in weather and resource base, the current rate and magnitude of change challenges the relevance of such knowledge and affects the health and well-being of older generations (e.g., Krupnik and Jolly, 2002; Weatherhead et al., 2010). The significant changes to travel routes and ice conditions therefore present challenges to traditional knowledge, which has implications for cultural and social relations (Ford et al., 2006a,b, 2008; Hovelsrud et al., 2008; Tremblay et al., 2008). Younger generations employ a combination of modern technology, traditional knowledge, and different methods and equipment to ensure a safe and sufficient harvest. Although technological innovations may improve safety, they are costly and are susceptible to failure. They are therefore often seen as an addition, not a replacement for traditional knowledge (Tremblay et al., 2008; Ford et al., 2009; Ford and Furgal, 2009).

10.3. Increased activities and access with local implications

- Reductions in cryospheric components (e.g., ice sheets and sea ice) that presently serve as barriers to access are likely to stimulate increased interest in northern industrial development, particularly in non-renewable resource sectors. This will be offset to some degree by transportation issues (e.g., diminished accessibility by ice roads) that may limit development capacities and rates.
- Consequences include a further shift toward wage-based economies, demands for skilled workers, increased migration, and requirements for enhanced sustainable management, environmental protection, and overall governance.
- Increased demands (e.g., skilled local workers, environmental reviews, management needs, services, and governance) will be required and will further strain a system already struggling to cope with widespread change from multiple factors with limited adaptive capacity.
- Increased challenges to indigenous peoples will have far-reaching effects on language and culture.
- Increased industrial development and related socio-economic and cultural changes in the Arctic will be an inevitable outcome of cryospheric changes driven

by climate change. Cascading needs for infrastructure, services, and related development will foster increased energy consumption. Increased production of black carbon ('soot') will result from such activities which, if not properly regulated, will feedback positively to local cryospheric degradation, further exacerbating more rapid climate and cryospheric change.

A variety of factors influence and finally determine decisions whether to locate and develop industrial and other economic activities in the Arctic. These include world market prices, level of costs, and the level of education and training of the local labor force. In addition, unfavorable climate conditions and challenging logistics have undoubtedly been major barriers to increased economic activities in the Arctic region to date. The changing cryosphere is projected to open previously inaccessible or unprofitable areas for large-scale industrial developments, shipping, and tourism with differing impacts on local communities and activities across the Arctic. Direct cryospheric changes will combine with direct and indirect effects from increased industrial activities to result in synergistic and cascading effects. Traditional livelihood activities, such as hunting, fishing and herding are susceptible to increased activities in the region. The regulatory and preparedness aspects of changing access are discussed Section 10.5.

10.3.1. Transport and infrastructure, tourism

Sea ice, snow cover, permafrost, and ice roads on lakes and rivers are vital for transport and low-cost provisioning to remote communities that do not have highway systems. They are also important for industrial areas and developments that cannot use air access or major northward river barge traffic for transporting heavy loads, fuel, and large equipment (Vuglinsky and Gronskaia, 2006; Furgal and Prowse, 2008; Prowse et al., 2009). Dogsleds and snowmobiles are used for hunting and reindeer herding in the Arctic and winter road networks are important for resupplying many communities (e.g., Furgal and Prowse, 2008). Snow cover, frozen rivers, and land-fast sea ice are all critical elements for safe travel, and a reduction in these conditions creates challenges and risks. Access to the sea and transport to, from and within northern regions are determining factors for hunting, fishing, exchange of goods among communities and with regions outside the Arctic, and maintenance of social networks and family ties in the Arctic. Frozen rivers and lakes are also used by reindeer herders during migration. Ice roads contribute significantly to national economies and create a vital lifeline to northern communities and mines (see Box 10.2). Although statistics on ice-road use and volumes are available (Furgal and Prowse, 2008), the importance of ice roads to northern communities has not been scientifically documented (Ford et al., 2008). Similarly, barge traffic along the large northward-flowing rivers that characterize the Arctic contributes significant seasonal capacity for northern transportation.

Enhanced river barges and land-based all-weather roads and railways as well as increased infrastructure to service such transport (e.g., enhanced dredging of rivers) will be needed as an alternative to ice roads to ensure continued access to industrial developments and communities (Prowse et al., 2009) (see also Box 10.2). A six- to nine-week reduction in

Box 10.2. Winter road access to northern communities

Land- and ice-based transportation declines associated with the degradation of cryospheric components is clearly a developing issue of wide concern. This will be exacerbated by increased impetus and activities associated with northern development and until resolved will hamper such development.

The importance of ice roads for access to northern communities is shown by the impact of thawed winter roads in the province of Manitoba, Canada, due to mild weather in March 2010. Typically, the road carries more than 2500 shipments each year to more than 30 000 First Nations people. The stranding of many freight-haulers and local drivers resulted in dwindling construction supplies, rising food and fuel prices and a related rise in unemployment. A state of emergency was declared in 11 communities. First Nations Grand Chief Harper is quoted as saying, “*This has become a human rights issue – no one should be cut off like this. No one should feel this isolated*” (Carlson, 2010).

the ice-road season on the Mackenzie River, for example, could result in a 50% increase in the use of barge-based transport (Lonergan et al., 1993). In areas where open rivers are currently critical for reaching remote regions, such as in Russia, a longer ice-free season is beneficial in economic terms and will provide better access for the increased activities in the Arctic. However, compensatory development will be required due to local reductions in road networks resulting from permafrost degradation. A shorter snow-cover season will reduce snow- and ice-removal costs and improve the mobility and safety of passenger and freight travel through reduced winter hazards (U.S. National Research Council, 2008). In addition, a reduction in snow and ice cover might extend the construction season.

While transport over sea ice, ice roads, and permafrost will become more problematic, sea-ice retreats creating longer open-water seasons will be generally positive for the transportation sector. These changes may have positive spinoffs for the Arctic, as the focus of economies and investors, from inside and outside the Arctic, will be directed to the economic opportunities in developing the potential renewable and non-renewable resources in the region.

The decline in sea-ice extent in the Arctic will increase the opportunity for trans-polar commercial shipping and considerably shorten the route between Europe and the Pacific (see Figure 10.4). Ships will reduce travel distance by 40% by sailing the Northern Sea Route compared with current shipping routes. It is projected that the transit transport from Russia will increase, although seasonal ice will remain an uncertain hazard. A shorter route for ships could save energy, reduce emissions, promote trade, diminish pressure on the main trans-continental navigation channels, and have great economic benefit (Commission of the European Communities, 2008; Molenaar and Corell, 2009). On the other hand, large areas of open warmer water may also lead to increased cloudiness and fog events (Walsh and Chapman, 1998) challenging navigation for shipping and local vessels. An increase in shipping will have significant consequences for local coastal communities, particularly given that marine resupply is likely to




Figure 10.4. Arctic transportation routes – roads, shipping, and pipelines.

experience easier and longer seasons. Although the Arctic may be navigable before 2050, and routes along the Siberian coast even earlier, more investment is required in infrastructure and the provisioning of marine services to ensure safe and secure ship transit with minimal environmental impact (Ho, 2010). As a result, for the near future, Arctic shipping is expected to be largely to points in the Arctic rather than ocean-to-ocean transits and commercial maritime activity in the Arctic will probably be driven more by economics, dominated by the development of natural resources and tourism, than by diminishing sea ice (see also Chapter 9, Section 9.4.4.1).

An increased need for transport and infrastructure in the Arctic due to developing extractive industries and commercial and tourism related shipping also requires the development of community infrastructure, harbors, search and rescue, and local service sectors. Changes in the frequency and magnitude of iceberg calving may influence access for planned infrastructure development, marine transport, fisheries, and oil and gas exploration and production on Arctic continental shelves, where activity is expected to increase significantly over the coming decades. Adaptation, mitigation, and monitoring techniques will be necessary to minimize the potentially serious impacts. One negative impact expected is disturbance to seals and whales, which contribute significantly to the diet and the informal economy of indigenous peoples throughout the region.

10.3.1.1. Infrastructure

Infrastructure includes physical facilities with permanent foundations or the essential elements of a community. It includes schools, hospitals, various types of buildings and structures, and facilities such as roads, railways, airports, harbors, power stations, communication systems, and power, water, and sewage lines. Infrastructure forms the basis for local, regional, and national communication and for economic

Box 10.3. Permafrost threat to infrastructure

While most settlements in the Arctic are relatively small communities, most are located on the coast where permafrost is commonly present. The Arctic population is set to increase (Furgal and Prowse, 2008), and northern Russia already has large cities of over 100 000 inhabitants in permafrost areas. Alaska has a population of about 500 000 in permafrost areas, the main portion (80%) living in areas with a permafrost extent of less than 50% (U.S. Arctic Research Commission Permafrost Task Force, 2003).

Most developments in the Arctic have taken place with an awareness of current permafrost conditions, but projected climate-driven changes in permafrost are likely to affect these and future developments beyond current planning and engineering provisions and can pose a significant challenge to infrastructure, environment, and health in the Arctic.

Coastal Arctic regions have concentrations of industrial facilities associated with oil and gas such as the Prudhoe Bay region in northern Alaska, the Mackenzie Delta in Canada (although production has not yet started there), and the Pechora Basin in Russia. Damage to pipelines may have dramatic environmental effects, especially when oil or gas is released at the coast or at sea. About 35 000 pipeline failures are registered annually along the 350 000-km network of pipelines in western Siberia. Over 20% are probably due to deformations and weakening of foundations induced by permafrost thaw (Anisimov and Reneva, 2006). The world's largest terrestrial oil spill was the 160 000 tonnes of oil-containing liquid in Vozei in 1994, and even 15 years later soil contamination in the surrounding area is still high. The spill was likely to have been caused by uneven ground settlement due to permafrost thaw and thermokarst.



Figure 10.5. Pipeline under construction in the Russian Arctic.

growth. Particular concerns are associated with permafrost thawing and degradation and coastal erosion effects on the stability and maintenance of transportation routes and on industrial development in such regions (see Box 10.3) (e.g., IPCC, 2007). Thawing permafrost may have an impact on air transport through effects on runways (see Chapter 5, Section 5.3.5.1.3). Coasts and infrastructure become more prone to erosion and destruction as the sea ice retreats, permafrost thaws, and the dynamics of freeze-up and break-up events on lakes and rivers cause floods. Damage from ice action and flooding

to installations such as bridges, pipelines, drilling platforms, and hydropower also poses major economic costs.

Thawing permafrost will affect coastal and inland facilities and infrastructure, but costs and risks are more closely linked to the design lifetime of the structure than with thawing permafrost (see Chapter 5, Table 5.5). Nevertheless, many buildings and structures were built assuming a more permanent permafrost layer, which has consequences for their structural stability and safety, especially as rising air temperatures and snow depth exacerbate permafrost thaw (Romanovsky et al., 2010). Proper design and engineering will counteract permafrost changes to a certain extent, but an accelerated thawing of permafrost and rapidly changing conditions may require immediate design changes for high-risk projects such as water-retaining structures, tailings, and storage facilities for hazardous wastes and sewage (see Box 10.3).

Coastal infrastructure will be increasingly exposed to coastal erosion due not only to increased exposure and thawing of coastal permafrost, but also to sea level rise, longer open-water fetch as sea ice declines, and potential flood damage from river-ice jams. Recent research describes how coastal erosion is increasingly threatening Arctic coasts (Martin et al., 2009). In addition to substantial land loss and impacts on infrastructure, such erosion may expose waste dumps at abandoned military and oilfield sites, with potentially severe effects on the health of wildlife and coastal communities. Smaller coastal communities are especially vulnerable to increased contaminant levels from saltwater intrusion as permafrost thaws, coasts erode, and infrastructure is damaged (Berner et al., 2005). In addition, such communities have to deal with damaged infrastructure resulting from permafrost thaw (Anisimov et al., 2007; Andrachuk and Pearce, 2010; Ford et al., 2010a). Infrastructure located in river channels (e.g., gas fields in the Mackenzie River Delta) may be exposed to flood damage from ice jams and backwater flooding (Prowse et al., 2009). In addition, ice instability and related ice damage (e.g., freezing rain events on distribution networks) may increase with a projected increased use of hydropower installations. Especially in coastal mountainous areas, rockfalls and landslides caused by permafrost thaw and increased storminess might cause additional hazards to infrastructure and safety, while some rockfalls may lead to local tsunamis and thereby increase impact (see Chapter 5, section 5.3.5.1.1).

10.3.1.2. Tourism

An increasingly important source of income for many communities, tourism also depends on good access. Arctic tourism relies on traditional perceptions of the Arctic environment and expectations about the experience that relate to ice and snow, mountains and tundra, and animals (Pagnan, 2003). With the exception of some cruise lines traveling to the Arctic from Europe and North America, and some Alpine ski operations, tourism in the region consists of small-scale operations (Pagnan, 2003). Tourist activities include traditional hunting and fishing, trophy hunting, expedition-style and destination cruising, dogsledding, and cultural and aboriginal tourism (Notzke, 1999).

The Arctic draws tourists that seek solitude and inaccessible and inhospitable qualities, which may change with reduction in sea ice and opening up of the region.

Current trends indicate that ‘climate change’ tourism, for example travelling to Greenland or Alaska to view rapidly retreating glaciers, is a growing attraction. A more accessible Arctic may draw greater numbers of another type of tourist who seeks land-based tourism activities, such as sport hunting, winter-based activities, ecological and nature tourism, and retreats and conferences (Stewart and Draper, 2006b). Changes in the predictability of snow conditions, such as winter thaws, increased avalanches, slush torrents and floods will have consequences for winter activities such as dogsledding, skiing, reindeer sledding, and snowmobile touring (e.g., Dawson et al., 2007). Snow conditions also affect ecosystems, biodiversity, and landscape amenity values, and if the scenic values are diminished through environmental changes associated with changes in snow, then tourism will be affected.

Cruise ship tourism is developing rapidly worldwide, and loss of sea ice may open up waterways and opportunities for increased cruise traffic (e.g., Glomsrød et al., 2009), perhaps on the scale presently observed in Svalbard and Alaska (Pagnan, 2003; Johnston, 2006). In addition, visitors on more traditional cruises are becoming more adventurous, seeking out more remote locations such as the Arctic, and it is likely that such cruise tourism will increase independently of sea-ice change (Stewart and Draper, 2006a,b; Snyder and Stonehouse, 2007). On the other hand, a changing cryosphere is altering the character and distribution of the sea ice and increased risks of accidents (e.g., hull penetration by multi-year ice) may have negative implications for cruise tourism, in particular for transits through the Northwest Passage and in the High Arctic (Stewart et al., 2007; see

also Section 10.4.3). Supporting these ventures (e.g., with shipping, infrastructure maintenance, and search and rescue) creates its own sustainability challenge (e.g., Stewart and Draper, 2008).

Changing sea-ice and snow conditions will reduce the opportunities to view snow- and ice-dependent wildlife, such as seals, walrus, and polar bears (Lemelin, 2005; Richardson et al., 2005). The effects of shrinking or disappearing glaciers on tourism in the Arctic are not well documented, but a few studies from the Alps and North America show that hazards related to shrinking glaciers increasingly affect popular mountaineering activities on and around glaciers (Jetté-Nantel and Agrawala, 2007; Smiraglia et al., 2008) and have already limited skiing on glaciated slopes (Abegg et al., 2007). Declining or disappearing glaciers are also found to have a negative impact on the attractiveness for visitors in glaciated natural parks (Scott et al., 2007; Wolf and Orlove, 2008).

10.3.2. Changes in access and availability of renewable and non-renewable resources

Access to Arctic resources will be enhanced by many cryospheric changes even though some changes (e.g., degradation of permafrost and earlier melt of river and lake ice) may reduce accessibility over land. Increased accessibility is particularly relevant for non-renewable resources (e.g., coastal ore deposits and hydrocarbons on shelves) but is also relevant for some renewable resources (e.g., sub-Arctic marine fisheries presently subject to seasonal ice presence) (see Figure 10.6).




Figure 10.6. Current marine shipping uses in the Arctic.




Figure 10.7. Probability of the presence of (at least one) undiscovered oil or gas field (with recoverable resources greater than 50 million barrels of oil equivalent). Source: USGS (2008).

10.3.2.1. Hydrocarbons and mining

The Arctic is an important supplier of oil and gas to the global market, and it is likely that climate change will have positive and negative financial impacts on exploration, production, and transportation activities. With a growing global demand for hydrocarbons and minerals, the Arctic stockpile of resources is likely to have an increasingly important role in the global economy. Increased access and activity afforded by cryospheric changes (particularly decreased sea-ice presence) will create challenges for extraction, transport, engineering, search and rescue needs, and responses to accidents.

According to Lindholt (2006), 97% of total Arctic oil and gas production is located in Russia and Alaska. Canada, Greenland, and the Barents Sea are potential locations for future oil and gas production (Figure 10.7). It is estimated that roughly 84% of the undiscovered oil and gas in the Arctic occurs offshore (USGS, 2008). Most of the discoveries remain undeveloped (Gautier et al., 2009), primarily due to remoteness, costs, and technological challenges associated with ice-infested environments (sea ice, icebergs) combined with abundant petroleum extracted at a relatively low cost. With a projected increase in activity, the industry will have to contend with risks of oil spills, spill remediation costs, and stricter environmental regulations. Risk assessments and the marine insurance industry are likely to play a crucial role in industry-related shipping (AMAP, 2007; VanderZwaag et al., 2008; Molenaar and Corell, 2009). Climate change impacts on oil and gas development have so far been minor, but are likely to result in financial costs and benefits in the future (see Section 10.3.1.1.). Reduced sea-ice cover will affect offshore drilling, due to potential for increased wave action and storm surges, and perhaps variable regimes of drifting ice.

The Arctic holds large stores of minerals (Lindholt, 2006) and potentially large reserves of undiscovered sources of raw materials. A reduction in glaciers, ice sheets, and sea ice in and around Greenland, for example, will increase accessibility to new areas with the potential for commercial exploitation of minerals and energy resources. Mining activities in the Arctic are important contributors to national economies and to the global economy. The extraction process itself is not likely to be significantly affected by a changing cryosphere, but the industry will benefit from improved marine transportation conditions to production sites and markets. Any expansion of hydrocarbon and mining activities is likely to require further expansion of air, marine, and land transportation systems and all related regulatory activities.

Impacts of hydrocarbon and mining development on people, communities, and governments can be positive and negative (AMAP, 2007). Such impacts could drive social and economic change, create revenue and employment opportunities, affect households as workers may be away for long periods, and foster increased immigration to the Arctic as jobs are filled by employees from outside the region.

10.3.2.2. Hydropower and wind power generation

Expansion of industry and population in some areas of the Arctic has already increased electricity demands (Furgal and Prowse, 2008), and this trend is expected to continue as the hydropower potential may itself attract industries with high energy consumption (e.g., aluminum smelters) that need abundant, cheap, and ‘green’ (having no greenhouse gas emissions) energy. However, dams and reservoirs essential to hydroelectric production may carry their own suite of environmental effects (e.g., altered flow regimes and contaminant liberation from flooded sediments), which may be enhanced by cryospheric change. The drive to increase renewable sources of energy has led to the rapid increase in the development of large-scale windmill facilities in the Arctic.

Production of hydroelectric power is important in several Arctic countries and still has a vast potential with large as yet unregulated northern rivers (e.g., Prowse et al., 2004, 2009; Chapter 6, Section 6.5.3.2 and Chapter 7, Section 7.7.3.3) and future projections expecting an increase of inflow (Prowse et al., 2009). Some of the current hydroelectric power plants’ capacities and designs are seasonally constrained by the effects of river ice, but this could markedly change under future cryospheric conditions. The location of the mineral production process depends on costs, including energy costs. Access to hydropower or alternatives close to extraction sites might be profitable for mining companies; however, susceptibility of over-land distribution networks to cryospheric impacts must be factored into developmental scenarios. Increased hydroelectric capacity, in turn, might result in cascading development effects as more jobs are created, more labor is needed, and facilities are enhanced for increased workforces. At the same time, the adaptive capacity of many Arctic communities will be challenged as they are confronted by many significant changes over a short period.

The availability of resources for hydropower is expected to increase significantly in some areas of the Arctic due to increased precipitation, melt, and runoff. For example, the

hydropower potential in northern Europe is expected to grow by more than 25% by 2050 (Jochem and Schade, 2009) and by up to 30% by the 2070s (IPCC, 2007). Projected increases in winter rain and snowfall and increased freeze and thaw cycles are expected to lead to enhanced winter snowmelt and decline in winter storage and hence to more even runoff over the year (Gode et al., 2007; Furgal and Prowse, 2008). In Swedish sub-Arctic Suoma, the increase in runoff due to increased precipitation is projected to be as much as 53% by 2100 (Gode et al., 2007). In addition, glacial runoff (which is significant for hydropower generation in Scandinavia, Iceland, Greenland, western Canada, and Alaska) is projected to increase. The increased potential for hydroelectric power in Greenland, owing to more meltwater from the ice-sheet margin, is already included in the new Greenlandic economic strategies. However, only a few studies have tried to assess how cryospheric change may affect glacial runoff with subsequent consequences for hydropower production. Bergström et al. (2007) found that increased glacial runoff would contribute to increased hydropower production in the Nordic countries until the latter half of the 21st century, when maximum runoff is reached for most of the catchment studied. In the long term, the glacial mass will be reduced and the runoff will decrease.

A key factor is the stability of the water supply to the new power plants, which depends on the freeze-up conditions (Beltaos and Prowse, 2009). In addition, increased amounts of silt and sand in glacial meltwater may fill dammed lakes and affect the viability of the dams, eventually requiring additional reconstruction in order to maintain the water flow needed (see Chapter 7, Section 7.7.3.3). Alternatively, the bedrock topography exposed to the retreating ice may cause new meltwater drainage patterns, leading to a partial or complete drying out of the water supply to the hydropower plants. Research from glaciated catchments in the western United States and in the Alps highlights that existing hydropower dam infrastructure might not be able to utilize the increased runoff caused by climate change (e.g., Barnett et al., 2005). It is reasonable to assume that this too could be the case for hydropower production in glaciated catchments in the Arctic.

The increased availability of runoff in some regions may require expansion of reservoir capacities. Other challenges result from irregular resource availability that may lead to irregular production and increase potential problems linked to ice formation, break-up, and jamming in rivers downstream of hydropower outlets. This must also be linked to the potential changes in energy demand and changes in energy prices in the face of future climate, which will influence production and thereby influence future ice problems of the hydropower industry.

10.3.2.3. Reindeer husbandry

For the past 30 to 40 years, long-range reindeer migration patterns have been restricted in Fennoscandia (Riseth 2003) and the Nenets-Yamal area due to the ongoing development of oil and gas extraction and transport infrastructure (Forbes et al., 2009). The construction and operation of these plants require a relatively widespread network of roads, buildings, and power lines, and many of the Scandinavian facilities have been sited within important reindeer pasture areas. Aversion or

avoidance of certain reindeer pastures can lead to less optimal range use, complications with herding, increased costs, and reduced production. Such developments may negatively affect the foraging behavior of reindeer and must be seen in relation to changing snow conditions and land use. The rate and magnitude of changing snow-cover conditions are expected to vary significantly due to regional differences, between coasts and inland, and at different elevations (Brown and Mote, 2009). These cryospheric changes combined with the encroaching industrial developments will have significant implications for reindeer herders' choice of pastures.

10.3.2.4. Land use

Land use such as forestry and agriculture relies on productive ecosystems and efficient access during key periods. An increasing Arctic population will increase pressure on resource bases on such land use (e.g., Forbes, 2008; Keskitalo, 2008; Tømmervik et al., 2009). Permafrost underlies much of the area; thus its degradation along with reductions in length of the winter season may result in drainage and drying of land with consequences for fire regimes (i.e., enhancement) and services realized from the ecosystem (e.g., reduced harvests due to reduced access via winter roads). Such impacts will be highly regionalized, and regional variations in precipitation, particularly changes in snowfall, will exacerbate or mitigate such effects.

Increased productivity in boreal forests is expected, but reduced accessibility to timber outside frost periods will be a threat to the forestry industry (Lindner et al., 2010). Delayed access to felled timber, due to earlier snowmelt, may have a considerable impact on the quality of the timber due to insect damage and aging (Keskitalo, 2008; Øseth, 2010).

10.3.2.5. Fisheries

A changing cryosphere will have consequences for access to coastal and offshore fisheries. Fisheries are important throughout the Arctic (Glomsrød et al., 2009). Reduced sea ice has impacts on the abundance, migration, seasonal distribution, and composition of key commercial fish stocks (e.g., Atlantic cod and herring, with the resulting change in access) (see Chapter 9, Section 9.3.3.3; IPCC, 2007; Stenevik and Sundby, 2007; Brander, 2010). Key stocks will increase and are likely to shift their summer distribution northward in response to sea-ice loss and a projected increase in primary production (Chapter 9, Section 9.3.4.1). The potential for an eastward colonization of new spawning areas also exists in the Barents Sea area, and this may result in wider geographical redistribution of the stocks (Stenevik and Sundby, 2007). Currently, projections of how biophysical changes will influence commercial fisheries resources, in terms of specific stocks and species, are limited and uncertain (e.g., Loeng et al., 2005; Loeng, 2008), but the widely predicted northward shift of boreal species has already been observed in the North Pacific and the Bering Sea and Barents Sea (see Chapter 9, Section 9.3.4.3). While effects on species and location will vary across the Arctic, a northward shift will affect coastal and offshore fisheries. Fish stock abundance is shaped through a combination of human and environmental factors, and it is difficult to assess how cryospheric changes will affect future fisheries as changes in access, technology, and

species composition occur (e.g., Mueter and Litzow, 2008).

A general expectation of climate change for much of the Arctic is that increased precipitation will add to the volume of northward-flowing rivers, but the connection to cryosphere degradation is limited to degradation over the longer term of ice caps, glaciers, and the Greenland Ice Sheet. Both processes will contribute to increased freshwater input to the Arctic Ocean, which will be exacerbated by sea-ice loss. Freshening of marine surface layers will enhance stratification and reduce wind-induced mixing. This decreases nutrient transfer from deeper waters, thereby influencing amounts and types of primary production (see Chapter 9, Sections 9.3 and 9.4 and references therein) and, in turn, affecting production pathways to commercially viable fish stocks.

In Greenland and Alaska, a reduction in sea ice combined with increased glacial runoff and river discharges, altered sedimentation rates, and rising sea temperature is causing changes in nutrient transfer and production and will increasingly affect coastal marine ecosystems (Martin et al., 2009; see also Chapter 9, Section 9.4.4.3). With a freshwater budget shift, Greenland halibut is likely to move from deep waters to shelf areas, requiring changes to the fishery (Loeng et al., 2005; Côté and Williams, 2008), and in Alaska the fisheries depend on the strength of the Alaska Coastal Current. The result may be smaller stocks of Greenland halibut and northern shrimp in the Atlantic area and realignment of entire ecosystem pathways in the Pacific, both of which are fundamentally important for fisheries and marine mammals. Other species may enter the area as a result, offering new opportunities. Conversely, new species could lead to competition and colonization of habitat, diseases, new predators, and parasites (Furgal and Prowse, 2008).

For offshore industrial fisheries, a decline in sea ice-dependent fish species but an overall increase in pelagic productivity in the marginal seas and improved access to the Arctic Ocean are likely to be beneficial, provided minimal mismatch occurs between species and productivity pathways. Drifting sea ice and icebergs are an obvious problem for offshore fishing operations, although with ongoing warming a reduction in the density of spring-summer drift ice would be considered a positive effect. Reduced sea ice may also provide a larger seasonal window for offshore fishing and access to new possibilities for coastal fisheries, while increased storminess due to more open water may be a challenge.

Altered access to the Arctic is likely to trigger development and infrastructure needs (e.g., non-renewable resource development and compensatory activities for resupply as ice roads disappear). These, in turn, result in cascading effects on local infrastructure, services, and Arctic residents. An immediate consequence of the above is that demand presently outstrips capacity; as climate change effects generally and cryospheric change effects in particular occur, ensuing demands will vastly increase. The obvious adaptive response to such demand is increased population (through immigration and seasonal workers), further accelerating socio-economic change and exacerbating local development and change scenarios and demands. Increased demands will in turn increase demand for local energy (heating, electrical service, hydrocarbon use, etc.) to support community needs, increased industrial service and transportation needs, and non-renewable resource extraction. In turn, increased activities will foster increased emissions of greenhouse gases.

10.4. Adaptation across scales

- Changing cryospheric conditions require adaptation by local residents and businesses and by organizations and stakeholders with interests in the Arctic.
- Adaptive actions are being taken regardless of uncertainty in cryospheric and societal future conditions.
- Social and economic challenges stemming from a changing cryosphere may be alleviated through policy development and governance.

Arctic communities have generally adapted well to high natural variability in climate and the resource base (e.g., Huntington et al., 2007a,b; Forbes and Stammer, 2009; Wenzel, 2009; Ford et al., 2010b). It is generally argued that current adaptive efforts are strained by the magnitude and rate of climatic change, and the IPCC (2007) found that the resilience historically shown by Arctic indigenous peoples is being severely tested. Furthermore, the complex inter-linkages (including combined and cascading effects) between societal and environmental change represent unprecedented challenges to the current adaptive capacity (e.g., West and Hovelsrud, 2010). Globalization also plays a role in shaping local vulnerability, adaptive capacity, and resiliency (see Box 10.4). It is increasingly common to discuss two types of adaptation: reactive and proactive (e.g., Crabbé and Robin, 2006; Füssel, 2007; Amundsen et al., 2010). Reactive adaptation is in response to current climate and risk management practices, while proactive adaptation is the planning and implementation of adaptive measures to future climate change and unprecedented events (Füssel, 2007). Studies indicate that reactive adaptation is the most common form, triggered by extreme weather events (e.g., Næss et al., 2005; Penning-Rowsell et al., 2006; Amundsen et al., 2010). Studies of reactive adaptation can be used to analyze the capacity of an individual, institution, or community to adapt to current conditions and past extreme events, which can then inform analysis of the adaptive capacity to future climate change and

Box 10.4. Vulnerability, exposure sensitivity, and adaptive capacity

Vulnerability refers to the manner and degree to which a community is susceptible to conditions that directly or indirectly affect the well-being or sustainability of the community. This includes the sensitivity of the ecosystem of which the community is part or on which the community depends. Use of this term does not presume that communities are particularly vulnerable – some may have relatively few or no vulnerabilities.

Vulnerability is a function of exposure sensitivity and adaptive capacity (Adger and Kelly, 1999; Smit and Pilifosova, 2001; Turner et al., 2003; Ford and Smit, 2004; Wisner et al., 2004; Kofinas, 2005; Keskitalo, 2008). Adaptive capacity is closely related to resilience and reflects an individual's or community's ability to cope with, adjust to, or recover from an exposure sensitivity. It is reflected in the community's management of current and past stresses, its ability to anticipate and plan for future change, and its resilience to perturbations.

unprecedented events (Ford et al., 2006a,b; Rasmussen, 2005b; Smit et al., 2010). However, reactive adaptation is insufficient as a long-term strategy to meet many of the effects of cryospheric change. Thus, proactive adaptation and strategies are urgently needed in order to provide the basis for adequate preparedness. These are especially relevant for aspects requiring lead times for implementation, such as infrastructure development.

10.4.1. Adaptation and adaptive capacity

Cryospheric changes are felt first and foremost at the local level and by peoples and communities whose livelihoods and well-being are closely linked to the natural environment. While adaptation is clearly a local concern, institutions across societal scales (municipal, regional, international), sectors, and nations operating in the Arctic must also adapt (Hovelsrud and Smit, 2010). Current adaptations are spatially and temporally diverse and connect local, national, and international levels. Table 10.1 presents an overview of the cross-cutting societal implications, adaptation strategies, and challenges related to adaptation to cryospheric change identified in this chapter.

Social learning, responsive local institutions, livelihood flexibility and diversification, and adaptive management have emerged as critical elements for adaptation (Rasmussen, 2005b; Poppel and Kruse, 2009; Ford, 2009; Ford et al., 2009; Hovelsrud and Smit, 2010; Hovelsrud et al., 2010b). Good governance across societal levels (see Section 10.5) is critical for facilitating such adaptations and for strengthening adaptive capacity. It is important to remember that adaptation to changing cryospheric conditions occurs in the context of, and is inextricably linked to societal change. In addition, it is necessary to distinguish between adaptations to slower versus more rapid changes. The latter may require proactive measures and emergency plans to counteract the consequences of, among other things, extreme events for which anticipatory planning is inadequate. As adaptation is predominantly a local process, local projections of climate and cryospheric conditions are increasingly required from the forecasting communities. The development of and input to local projections will benefit from increased cooperation between scientists and local and indigenous communities. In addition to institutional guidelines or policies, economic and market pressures, technology, and the potential for diversification determine the adaptive capacity of a community or sector (e.g., Keskitalo, 2010).

Table 10.1 illustrates how local impacts create cross-cutting challenges for adaptation and governance. For example, increased industrial activities combined with changing cryospheric conditions create new challenges with local consequences. The development of adaptive strategies to Arctic conditions by industrial sectors will affect local vulnerability. If proper adaptive guidelines and regulations that anticipate future climate scenarios are not in place for industrial development and resource use (such as commercial fisheries, cruise traffic, and shipping), then local communities become more vulnerable to changing ice conditions. The development of the International Maritime Organization (IMO) international 'Polar Code' (IMO, 2009; see also Chapter 9, Section 9.4.4.2) for ships in the Arctic serves as a proactive form of adaptation to changing ocean conditions by setting standards for safety and reporting. The Polar Code forms the first internationally recognized guidelines for the construction

and operation of ships in ice-covered Arctic waters. The IMO guidelines aim to promote the safety of navigation and to prevent pollution from ship operations in Arctic ice-covered waters and to further regulate its development in a clear action to avoid damage to the marine environment. Further guidelines for operations and activities in the Arctic will be necessary to strengthen the adaptive capacity of the operators and actors.

Another example of cross-cutting adaptation, listed in Table 10.1, pertains to thawing permafrost. Currently technology is available to adapt infrastructure to the imminent problems related to thawing permafrost. Permafrost thawing and warming may lead to traffic-related challenges (Woo et al., 2007), and in a warming climate road systems may have to be upgraded more rapidly to counteract the increased rate in permafrost thaw, although systems on permafrost already have a short lifetime and climate change may not noticeably increase maintenance (see Chapter 5, Section 5.3.5.1.3). Future adaptation to reduced transport possibilities on ice roads involves enhanced surface flooding or spray-ice layering and modification of transport schedules to concentrate on the coldest part of winter (Prowse et al., 2009). Where possible, such permafrost adaptations will ensure that local communities and industrial activities can be maintained.

Table 10.1 further illustrates that at the local level, current adaptations moderate some of the regional negative impacts of shorter seasonal duration of land-fast ice and poorer ice quality. For example, adaptations to early spring break-up in the western Canadian Arctic include changing modes of transportation from snowmobiles to boats (Ford et al., 2010a; Pearce et al., 2010). Others increase their adaptive capacity by being flexible and use new technology, change resource use patterns, or reduce reliance on harvested foods (Hovelsrud et al., 2008; Andrachuk and Pearce, 2010; Ford et al., 2010a; Goldhar and Ford, 2010; Goldhar et al., 2010). While there is great uncertainty concerning the type and rate of changes, the trend to an increasingly warmer Arctic is expected to continue, with temperatures projected to rise by 3 to 7 °C toward 2100. The greatest changes are expected to take place in autumn and winter over areas with sea-ice loss (see Chapter 3). It is likely that hunting patterns and strategies and traveling activities will be increasingly affected, compromising safety, food security, and cultures and requiring new adaptive strategies (e.g., Hovelsrud and Smit, 2010). New adaptations may require monetary investments straining resources further (see also Chapter 9, Section 9.4.4.1).

Another local adaptation example comes from reindeer husbandry in which understanding the sensitivity of the reindeer grazing system to changing snow conditions is integral to reindeer herding cultures. Detailed environmental knowledge about how hard a snow or ice layer (bottom crust) must be to hinder foraging in winter is more important for the quality of pastures than snow accumulation (Kumpula and Colpaert, 2003). When ice layers, especially bottom crusts, restrict access to pastures stronger animals may still be able to dig through the ice layers that weaker animals cannot penetrate. Hence, as an adaptation many reindeer herders maintain a few strong castrated males to break through the hard layers (Reinert et al., 2008). Another adaptation option, albeit costly, is to supplement the natural diet with food pellets to alleviate poor grazing conditions.

Coastal erosion in communities in low-lying coastal zones has required adaptive measures such as protection of

Table 10.1. Cross-cutting challenges and adaptation.

Cryospheric change (exposure sensitivity)	Implications and challenges	Adaptation strategies and governance implications	Source
Sea ice			
Shorter duration of land-fast sea ice	Land-fast ice travel and hunting hampered	Changes in transport mode and new equipment such as GPS and satellite phone required	Barber et al., 2008
Poorer ice quality	Safety of sea ice-based hunting by indigenous groups compromised	Shift to open-sea hunting and fishing, could require changes in regulations	Pearce et al., 2010; Poppel, 2006; Ford et al., 2010a
Longer and larger open-water season at the coast	Increased fetch (combined with increased storminess) erodes coastline	Shoreline stabilization and engineering options, eventually relocation; government agency with authority to relocate communities	Forbes et al., 2008; Perovich and Richter-Menge, 2009
Reduced sea ice	Changes in fish stocks and fisheries, increased access for fisheries	Fishery regulations must change	Stenevik and Sundby, 2007; Brander, 2010
Reduced sea ice	Increased traffic at sea in the future	IMO standards for ships that sail in the Arctic	Commission of the European Communities, 2008
Reduced sea ice	Increased industrial activity in the future, oil and gas exploration	Higher costs of security provision, stricter environmental regulations	AMAP, 2007
Permafrost			
Thawing of permafrost – increased coastal erosion	Threatens coastal settlements	Shoreline stabilization and engineering options, eventually relocation; government agency with authority to relocate communities	Johnson et al., 2003; Bronen, 2008; Martin et al., 2009
Thawing of permafrost – increased runoff	Release of legacy pollutants that affect the food chain and have negative health effects	Increased surveillance of contaminants in traditional/local foods; investigation of health and ecosystem effects on biota	Kraemer et al., 2005; Hansen et al., 2008
Thawing of permafrost – drainage of forested areas	Tree death caused by drought; increased forest fire occurrence	Development of increased surveillance and response capabilities to fires; altered management regimes to enhance harvesting of ‘at risk’ forests	Furgal and Prowse, 2008
Thawing of permafrost	Damage to poorly engineered and constructed infrastructure	Proper design and engineering will to a certain extent counteract permafrost changes	Berner et al., 2005; Anisimov et al., 2007
Glaciers and ice caps			
Increased calving	Threat to planned infrastructure development, marine transport, fisheries, and oil and gas exploration	Improved mapping, surveillance, and monitoring	OPRC, 1990; Chircop, 2009; Molenaar and Corell, 2009
Glacier retreat	Increased hydropower production	Increased water storage capacity	Bergström et al., 2007
Glacier retreat	Reduced attractiveness to tourists		Scott et al., 2007; Wolf and Orlove, 2008
Snow			
Increased frost and thaw and ice cover on tundra	Reindeer access to fodder altered, increased mortality	Traditional Ecological Knowledge – use traditionally castrated male reindeer to break the ice crust; flexibility in choice of pastures	Tyler et al., 2007; Kumpula and Colpaert, 2003
Increased growing season	Increased productivity in forestry and agriculture		Lie et al., 2008
Less snow and shorter winter season	Reduced opportunities for winter tourism		Dawson, et al., 2007
Increased amount of snow	Increased hydropower production	Increased water storage capacity	Gode et al., 2007; Furgal and Prowse, 2008
Increased amount of snow	Damage to forests	Implications for fire regimes; see above	Kilpelainen et al., 2010
Increase in winter thaw	Increased tree death for certain conifers	Implications for fire regimes; see above	Kilpelainen et al., 2010
Milder winters	Increased damage to forests from insects and pests	Implications for fire regimes; see above	Heliövaara and Peltonen, 1999
Increased snowfall and higher winter temperatures	Increase in avalanches	Increased forecasting and surveillance of hazards	Allard et al., 2007
Earlier snowmelt	Drought in dryer areas during spring and summer		Gronlund, 2009
Milder winters	Less frost damage on pastures		Gronlund, 2009
Rivers and lakes			
Reduction in ice duration and ice thickness	Reduced operation of ice roads	Concentrate on the coldest period of winter, eventually construction of land-based road or rail networks	Prowse et al., 2009
Reduction in ice duration	Increased barge transport on rivers and lakes	Development and enhancement of infrastructure to support such (e.g., dredging)	Lonergan et al., 1993; Woo et al., 2007

shorelines and buildings. Such measures include planning and consideration of relocation of communities due to coastal erosion and flooding (Furgal and Prowse, 2008). Adaptation through relocation is a difficult process because proper institutions and financing are lacking (Bronen, 2008), and original locations may have been chosen for very good and still valid reasons. Here the local adaptive capacity is closely linked to institutional capacity and policy.

10.4.2. Challenges and opportunities

Challenges and opportunities shaped by cryospheric changes emerge between and across societal scales and along different temporal scales (see Table 10.1). Some changes pose challenges to some individuals and sectors, and opportunities for others. Indigenous peoples in particular are likely to have to devise new adaptation strategies to alleviate the impacts of a changing cryosphere on the environment, health, and traditional practices. Traditional knowledge, being dynamic and adjustable to a broad range of variability in the environment and natural resources, is an important component of adaptive capacity and will be instrumental in developing such adaptations. If traditional harvesting activities are compromised by changing sea-ice conditions, opportunities to harvest new species with familiar technology may arise. On the other hand, existing technology may not be sufficient to exploit new species. Such challenges may be met by changing harvesting methods from sea ice to open water by investing in boats. In turn, this may lead to other economic opportunities, such as some forms of tourism (e.g., Stewart et al., 2007) that may increasingly shift northward as a result of a changing cryosphere. According to one study, based on one global circulation model, tourism in Canada and Russia could potentially increase by 25% through global warming of only 1 °C (Hamilton et al., 2005; Stern, 2006). The projected trend of increased tourism will provide opportunities for entrepreneurs and operators in the region, provided the human skills and financial resources are available. While continued warming will challenge the use of ice roads for transportation, the resulting open-water networks may provide opportunities for increased barging. Heavy transport to land-locked locations will face major challenges in the absence of ice roads and with increasing permafrost thaw and subsidence (Prowse et al., 2009) and may require adaptive measures such as construction of land-based road or rail networks.

The potential impacts of changes on communities in different parts of the Arctic are diverse. For example, hunters in the northern parts of Greenland feel challenged by thin and less reliable sea ice during winter, while others with more focus on fisheries view these changes as an opportunity to expand fishing activities. The local socio-economic situation and politics determine whether the effects of changing sea ice on relevant fish species will present challenges or opportunities at the local level.

An increasingly ice-free Arctic Ocean offers a number of opportunities for naval and maritime operations in terms of shipping and resource extraction. However, significant ice- and weather-related challenges remain. Operators must adapt to seasonal drift ice and icebergs, annual variations in ice cover, continued local sea-ice formation, and icings on ships and installations due to increased storm surges and wind (Molenaar and Corell, 2009). Free-drifting icebergs

are particularly challenging and can lead to shutdown of offshore hydrocarbon production, be a threat to shipping and cause major economic losses. The relatively shallow water depth along the Siberian coast, for example, limits the size and freight capacity of ships (Johannessen and Pettersson, 2008), reducing the opportunities of an ice-free passage. Other shipping-related challenges include limited search and rescue capabilities, infrastructure, and uncertainties about future trade patterns. Challenges for oil and gas facilities include employing appropriate technology, developing risk assessments, and meeting regulatory requirements and increasing societal expectations related to environmental performance and social benefits (VanderZwaag et al., 2008; Efthymiou and Winkler, 2009).

A changing snow regime provides opportunities for some Arctic societies in terms of increased hydropower potential, a more even distribution of water supply and less flood damage, and reduced snow removal costs. Increased potential for hydropower will provide opportunities for industrial development in remote areas with demand for more power (e.g., mines). Conversely, reduced hydropower potential because of drought may challenge development and increase demands for other sources of energy (e.g., wind, coal, diesel). In addition, drought in forests because of reduced meltwater in spring may represent a challenge for the forest industry, and melting snowcaps may reduce attractiveness for tourists. For local and indigenous peoples a changing snow regime will challenge traditional resource management.

Industries and developers will need to invest in stabilizing current infrastructure to meet the engineering, design, and connectivity challenges of thawing permafrost. Local residents may find it challenging that their transportation routes and perhaps local use areas (e.g., lakes for fishing) are disrupted. The changing permafrost offers few opportunities, apart from some agricultural activities.

10.4.3. Hazards and safety

A changing cryosphere poses new hazards associated with the risks of on-ice travel, ranging from that for commercial traffic on ice roads to the use of backcountry lake- and river-ice networks for travel and access to traditional food sources by Arctic residents (e.g., Ford et al., 2008). Current observations show that ice conditions are already unpredictable and changing in such a way that previous understanding of local environments, travel routes, and safety skills may be challenged and insufficient. Changing conditions and increasing concerns about hunter safety create a need for costly new technology (e.g., GPS, satellite phone), although it is noted that such devices may be susceptible to failure and must be an addition to, not a replacement for, traditional or local knowledge (Tremblay et al., 2008; Ford and Furgal, 2009; Ford et al., 2009). The changing sea-ice conditions increase risk and safety in two ways. First, and already a challenge, hunters will have to travel increasingly farther or to different and unknown locations to access the animal populations (Ford et al., 2007; Hovelsrud et al., 2008; Tremblay et al., 2008). Second, a reduction in land-fast ice in the western Canadian Arctic combined with more open water make the sea-ice conditions less predictable and result in unpredictable fog events, making coastal travel treacherous (Barber et al., 2008).

Hazards associated with decreasing Arctic glaciers include rockslides, debris flows, ice avalanches, glacial mudflows, and outburst floods (see Chapter 7). In combination with changes in the permafrost on surrounding slopes, the hazard increases. One result of the destabilization is floods (*jökulhlaups*) from ice-dammed and sub-glacial lakes, especially in volcanic areas such as in Iceland, Alaska, and Kamchatka, where hazards to people and infrastructure are well documented. Glacial lakes that pose a hazard to people and infrastructure are commonly drained by pipes. Retreating glaciers could lead to an increase in possible hazardous *jökulhlaups*, but little is currently known about increased risks to communities in the Arctic. Compared to other glaciated regions such as the Himalayas, the Alps, or the Andes, glaciated regions in the Arctic are generally sparsely populated and the impacts of these hazards on communities and infrastructure are probably limited. In the Himalayas, increased frequency of *jökulhlaups* may lead to severe damage and loss of lives downstream (UNEP, 2007; Agrawala, 2008). A few potentially dangerous glacial lakes are reported in Norway (Elverhøy et al., 2002) and Canada (Geertsema and Clague, 2005). In general, the hazard from glacial retreat to communities in the Arctic is limited (for a review of hazards see Chapter 7, Sections 7.5 and 7.7). In addition to retreating glaciers, greater snow accumulation and changes to ice-layer production at high elevations may increase the frequency of snow avalanches and slush torrents and thereby become a greater hazard for people.

Although summer sea-ice cover is projected to disappear toward 2020, seasonal variations in sea-ice extent and thickness will remain. The reduction in sea ice will not only open up seaways, but will also create new hazards for shipping and offshore oilrigs (Figure 10.8). Regional differences in first-year ice and multi-year ice may lead to an increase in drifting multi-year ice and icebergs, creating choke points in narrow channels leading to significant navigation hazards (Wilson et al., 2004). This may affect all forms of shipping, including cruise tourism, particularly for transit through the Northwest Passage and in the High Arctic (Stewart et al., 2007).

An overarching issue for all activities in the Arctic is a general lack of preparedness, across local, national, and international

levels, to respond to increased pollution, accidents, and search and rescue needs as access to ice-free areas increases. The new waterways are not sufficiently charted, and there is a need for iceberg and environmental monitoring and for infrastructure (ports, navigation aids, supplies, spares), which is currently limited or lacking, to support high levels of marine traffic (see also Chapter 9, Section 9.4.4.2).

10.4.4. Technological developments as an adaptation

Adaptation by technological developments will be necessary in a changing cryosphere. Infrastructure and buildings constructed on ice-rich permafrost cause permafrost thaw (e.g., Nelson et al., 2002; Anisimov et al., 2007) and this is discussed in Chapter 5 as a major reason for structural damage to buildings (see Section 5.4). The challenge is particularly large in Russia, where many housing and industrial facilities in the northern and southern Russian Arctic, especially in the Sakha Republic, were built on permafrost. Techniques to reduce warming and thawing, such as heat pumps, convection embankments, thermosyphons, winter-ventilated ducts, and passive cooling systems are already common practice in North America, Scandinavia, and Russia (e.g., Instanes et al., 2005). Permafrost engineers must address the problem of preserving infrastructure under projected future climate conditions. One solution is to construct new buildings at the rate at which existing buildings are damaged and abandoned. For existing projects such as the Norman Wells pipeline along the Mackenzie River in the Northwest Territories, Canada, monitoring programs are important not only to facilitate the mitigation of environmental impacts associated with the project (Naviq and AMEC, 2007; Prowse et al., 2009), but also to mitigate the effects of ongoing climate change. As a way of adapting, the Canadian government has enhanced the permafrost-monitoring program in the Mackenzie region to ensure impacts related to hydrocarbon resource development are minimized. For high-risk projects such as hazardous waste storage, the environmental protection agencies can apply the principle of ‘perpetual’ design, which implies engineering to meet a wide range of uncertainties in the future.



Figure 10.8. Icebergs constitute a hazard to Arctic offshore oil operations. A tug boat stands by to tug an iceberg away from a drilling area. Photo: Will Rose / Greenpeace.

Shipping in Arctic waters requires adaptive technology that can handle treacherous and unpredictable ice conditions, such as ice-strengthened hulls (as required by the IMO 'Polar Code' guidelines). Different solutions for securing safe and cost-efficient transport have been developed or are under development (IMO, 2009; Ho, 2010). These include using dedicated ice-strengthened vessels or ice breakers for the ice-covered areas and applying ship-to-ship transfer in open water (e.g., for commodities such as liquefied natural gas), satellite navigation systems for improved maritime surveillance, and double acting ships with the bow optimized for open-water conditions and the stern designed for icebreaking (Commission of the European Communities, 2008; Molenaar and Corell, 2009). Increased shipping will, however, require more accurate hydrographic charting, enhanced infrastructure to support shipping, better weather forecasting, and enhanced capacity to respond to emergencies and accidents.

Extractive industries view adaptation to Arctic conditions as an opportunity to develop new technology to improve efficiency and reduce costs. Advances have already been made in current focal areas of Arctic sub-sea processing, compression and power transmission, drilling and pumping technologies, and communication technology. Other focal areas are ice-load and ice-scour prediction; offshore Arctic drilling systems; Arctic tanker technology and emergency, evacuation, and spill response systems and technology; and cost-effective logistics.

10.4.5. Adaptation to extreme weather events

With a changing cryosphere, an increased frequency of extreme events is projected. Observations of such increases are already being reported (e.g., Oozeva et al., 2004; Nickels et al., 2005; Laidler and Elee, 2006). In particular, sea-ice retreat is likely to result in more severe weather in future (Kolstad and Bracegirdle, 2008). Increased weather variability is having profound societal and cultural impacts on residents across the Canadian Arctic (e.g., Furgal and Seguin, 2006; Riewe and Oakes, 2006). Traditional sea-ice use and commercial activities such as fisheries, extractive industries, and shipping will both be affected by more extreme weather in the future. Strong winds affecting coastal sea ice and creating open-water areas have consequences for travel and harvesting activities. Open water also leads to the formation of low clouds and fog, which produce freezing drizzle and significant icing on aircraft and vessels (Hanesiak et al., 2010), and requires innovation of drilling procedures as well as procedures for other stages of resource development. Currently, the Northeast Atlantic (the Greenland, Iceland, Norwegian, and Barents Seas) is particularly prone to marine cold-air outbreaks (MCAOs).

The frequency of severe snowfalls and extreme precipitation events is also projected to increase over large areas of the Arctic (Christensen et al., 2007). Snowpack density changes over time and as a result of climate change with consequences for buildings and infrastructure (e.g., Strasser, 2008). It is no longer enough to calculate snow load for buildings based on historical mean snow density (Newark et al., 1989). Similarly, projected increased avalanche occurrences will require adaptive measures.

Wind action may cause significant ice ride-up and pile-ups, which could extend more than 100 m inland (Taylor, 1978;

Kovacs and Sodhi, 1980). Ice pile-up in extreme events has been reported as high as 36 m (Sverdrup, 1904) and 50 m (Taylor, 1978). Pile-ups occur quickly (in about 30 minutes) and have caused fatalities and significant damage to infrastructure and roads, even overtopping dunes (Forbes et al., 2004). Because of the highly episodic and rare occurrence of damaging ice motion, little has been done to mitigate ice ride-up and pile-up hazards, little effort has been devoted to forecasting, and many communities where damage has occurred may not have anticipated the hazard before it occurred.

Sea-ice decline combined with increased frequency of storm events increases exposure to coastal erosion. Increased open-water fetch and waves are major contributors to coastal erosion, which is exacerbated by permafrost degradation along coastal tundra areas. With sea ice forming later in the season, the coast is more exposed to the projected rise in the number of autumn storms and storms with longer fetch. The complex interactions between declining sea ice and other consequences of climate change (e.g., rising sea level, shifting river discharges, runoff, altered sedimentation rates in coastal areas) will increasingly affect Arctic coasts, coastal infrastructure, coastal marine ecosystems, and potentially human resource use (Forbes et al., 2008; Martin et al., 2009; Perovich and Richter-Menge, 2009; see also Chapters 5 and 9). Adaptation measures to such events include development of protective infrastructure, often at great cost, and relocation of settlements and existing infrastructure.

10.5. Governance

- Cryospheric change and the resulting changes across all aspects of human endeavor in the Arctic require effective and inclusive governance at all levels including:
 - local-scale attention to sustainable management, regulation of key activities, mitigative, and adaptive solutions;
 - regional-scale promotion of effective and integrated management of all development with appropriate enforcement;
 - national-scale enactment of appropriate laws and development of regulatory criteria; and
 - international-scale development of global conventions regulating climate forcers and international standards for activities.
- Existing governance structures face challenges across scales and major effort is required to develop and implement new governance structures or refashion older regimes.

Governance is key to solving societal challenges, across local, national, and international scales, emerging from a changing cryosphere. Cryospheric changes create new, albeit differentiated by region, forms of access to the Arctic affecting the adaptive capacity and resilience of local communities, national management, and international regulations. Human rights issues, including indigenous rights (Declaration on the Rights of Indigenous Peoples, 2007), may be challenged and resolution mechanisms required. Inclusive governance will be necessitated at all societal and international, regional, national, and local administrative levels. Governance challenges resulting

from a changing Arctic cryosphere must be seen and addressed in connection with other issues affecting the region (e.g., ACIA, 2005; Armitage et al., 2007; Huebert and Yeager, 2008; Young, 2009a). Oil, natural gas, and mineral developments; airborne pollutants; sovereignty claims and security concerns; the socio-economic dimensions of renewable resource (e.g., fisheries and wildlife) extraction; and demands of northerners to have a greater role in decision-making as they adapt to changes all involve interrelated, multi-scale, and complex issues of governance. Figure 10.9 shows marine jurisdiction in the Arctic.

10.5.1. Multi-level governance institutions and co-management

Cryospheric changes will place additional pressure on existing frameworks for cooperation developed by Arctic nations (see Young, 2005; Stokke and Honneland, 2007). Efforts to secure sovereignty claims to Arctic territory raise militarization issues in relation to natural resource development. Although the Arctic states have not ruled out a region governed by adaptive flexible institutions designed to enhance equitable access to resources, top-down, sovereignty-based approaches to declining sea ice and resource competition are signaled (e.g., The Ilulissat Declaration, 2008). Such approaches, however, may be in opposition to solutions derived from sub-national needs of sea-ice service users across the Arctic.

The 1982 United Nations Convention on the Law of the Sea (UNCLOS) (current version, 1994) constitutes the primary mechanism for dispute resolution related to rights of exploitation and navigational routes in international waters and provides a legally binding framework to resolve state-based conflicts (Huebert and Yeager, 2008; Stokke, 2009). An additional 'Arctic Treaty' has been advocated, which may ensure the sovereign rights of Arctic nations, but with greater

flexibility to respond to the outcomes of cryospheric change (see Huebert and Yeager, 2008; Rothwell, 2009). However, the Ilulissat Declaration (May 2008), signed by the five Arctic Ocean boundary nations, supported the view that UNCLOS provided the necessary framework for resolving potential territorial disagreements and development challenges (Young, 2009a,b; Stokke, 2009).

This indicates an ongoing commitment to the current national level Arctic actors to engage in nation-to-nation debates over the future of the Arctic rather than promoting any new international legal strategies or institutions (Lovecraft and Eicken, 2009), maintaining the predominant position of nation states in shaping Arctic policy. The declaration thus implies that sub-national or regional interests (e.g., indigenous groups, non-governmental organizations, and local and regional governments) are not an independent part of the 'orderly' settlement of any possible overlapping claims.

The Arctic Council, a non-treaty, intergovernmental, ministerial-level forum, addresses issues of common concern, in particular on sustainable development and environmental protection, and has been identified as a critical actor in terms of environmental governance (Young, 2005; Huebert and Yeager, 2008). This role is enacted through the enhancement of the knowledge base regarding the consequences of change in the Arctic. However, as issues regarding the Arctic, especially shipping issues, may impact other stakeholders who are not members of the Arctic Council, a more inclusive approach may be required (Ho, 2010). An example of such could be to use, for example, the Antarctic Treaty as a basis or example for multi-lateral use of the region.

Effective co-management arrangements, defined here as the sharing of power and decision-making authority between state-based agencies, communities, and other actors, can play




Figure 10.9. Marine jurisdiction in the Arctic. Source: International Boundaries Research Unit, Durham University. Briefing notes referred to in the key are available at www.durham.ac.uk/ibru/resources/arctic.

a central role in fostering the co-production and sharing of knowledge about change and how best to respond to different types of change (Ayles et al., 2007; Kofinas et al., 2007; Armitage et al., 2009; Berkes, 2009). Co-management arrangements are also shown to foster vertical and horizontal institutional linkages that connect local communities with higher order decision makers, thereby fostering multi-level governance (Agrawal, 2008; Berkes, 2009). However, co-management regimes must be carefully designed to foster fit between local users' (usually indigenous communities) concerns and national or sub-national government priorities in order to promote long-term sustainability (Robards and Lovecraft, 2010). In the absence of fully participatory implementation, co-management mismatches can arise and hinder resource users' ability to develop adaptive capacity and governments' ability to collect accurate resource data.

Local institutions have a critical role in structuring the impacts and vulnerabilities of different groups to change, in reconciling individual and collective responses to change by providing incentives and disincentives to collaborate, and facilitating the delivery of resources (information, financial resources) to help various actors cope with change and build capacity to adapt to future changes (Agrawal, 2008).

Applying inclusive, collaborative processes, in which indigenous participants from communities and regions and non-indigenous stakeholders (e.g., scientists) work together, has been shown to produce valuable and integrative insights and to contribute to policy development and governance processes that reduce vulnerability and facilitate adaptation (Riedlinger and Berkes, 2001; Laidler, 2006; Keskitalo and Kulyasova, 2009; Ford et al., 2010b; Hovelsrud and Smit, 2010). This reflects a wider process whereby several Arctic states have shifted more political power and administrative authority to northern peoples (e.g., through land claims), while indigenous peoples are obtaining more representation on such bodies as the Arctic Council (Huebert and Yeager, 2008; Ho, 2010).

10.5.2. Industrial development and regulation

As the cryospheric changes increase, the difference between Arctic residents' view of change and industry's view of opportunities may become more pronounced. Future development of the possibilities for expanded industrial activities in the Arctic is likely to attract diverse stakeholders, and rules of engagement with northern peoples will need to be rethought. The United Nations Declaration on the Rights of Indigenous Peoples (2008) provides the basis for such discussions (see also the United Nations International Labour Organization Convention 169).

Hydrocarbon discoveries may change the economic conditions and way of life of local inhabitants. This depends foremost on the geographical location of these resources (see also Figure 10.7), but also on the involvement of the local population, on the distribution of revenues at a national level, and on the global market for these resources. Addressing the regulatory and stakeholder issues, including the study of impacts on the environment and local communities, should be a key focus area for industries and communities and governments (Seidlitz, 2009).

In 2007, the Arctic Monitoring and Assessment Programme (AMAP) undertook an assessment of oil and gas activities in the Arctic. Having found that oil and gas activity is a major driver of social and economic change, and will most likely increase, the report concluded that governance, regulatory systems, and international standards are important aspects of the performance of the oil and gas industry in the Arctic (AMAP, 2007).

Trans-Arctic marine shipping is expected to be an important driver of Arctic development (Commission of the European Communities, 2008; Molenaar and Corell, 2009), the regulation of which may require local institutional engagement, especially as shipping expansion may impact on stakeholders that are not members of the Arctic Council (Ho, 2010). In some Arctic waters, indigenous peoples have been the sole seasonal users of an Arctic waterway for perhaps hundreds of years. Fisheries and oil and gas activities are to a certain degree 'competing over space' at sea, which will continue and perhaps become more acute in a global warming and cryospheric change context. It will therefore be important to enhance marine safety and ensure marine environmental protection through proper rules and regulations.

Responses to non-renewable resource extraction often include industry applied and broader education and training programs. However, increased demand for local labor has implications for competing local businesses and industry, and concern has been raised about the transferability of industry-specific skills. As oil and gas and mining activities move through their lifecycle and specific jobs shift to different geographical areas, job retention may require willingness to move, separating local residents from their homelands and extended families. Thus, existing and anticipated developmental possibilities can still form barriers for local involvement in non-renewable resource development.

10.6. Cumulative effects and synergies in and beyond the Arctic

- The effects of climate change on various cryospheric components may accumulate both additively and synergistically (i.e., multiplicatively) to result in substantive direct and indirect impacts on humans in the Arctic. These will affect different human groups and sectors of society in different ways.
- Cryospheric change effects will further interact both additively and synergistically with other factors affecting human development in the Arctic (e.g., population growth, industrialization, transition from subsistence to cash and from informal to formal economies, and renewable resource production), resulting in rapid and unprecedented changes for peoples across the Arctic.
- Mitigative and adaptive strategies, including effective scalable and rapid responses to challenges, appropriate anticipatory management protocols for human endeavors, and relevant governance, are all required to meet the challenges of such change.

The combination of changes to the cryosphere with other climatic changes (e.g., temperature rise and sea level rise) and

non-climatic drivers (e.g., increased industrial activity, socio-economic development, and changing demographic patterns, governance, and health and well-being of the Arctic societies and people) will result in multifaceted and cascading effects.

The impacts of individual cryospheric changes on society are clearly numerous. However, a systematic assessment of cumulative effects is still missing. The extent and direction of changes are not easily identified, and it is the combination of many factors that creates the opportunities and challenges locally and beyond the Arctic. Accurate projections of complex cryospheric-societal interactions are not possible to make on theoretical grounds (see also Box 10.5 and Figure 10.10). In addition, the consequences of such interactions depend on context and location (e.g., Huntington et al., 2007b). In some cases, adaptive measures may have unexpected negative consequences and may even exacerbate the problem (maladaptation). This section recognizes the limitations of current knowledge, but through available examples ventures to discuss some possible cumulative effects and synergies.

10.6.1. Cryospheric drivers of change

A number of cumulative effects of a changing cryosphere emerge from the different chapters of this assessment report, and this

section highlights a few of these interactions by describing how changes in cryospheric elements or other climatic drivers of change may exacerbate or counteract each other.

Thawing permafrost is linked to snow conditions, and sea-ice reduction may expose coastal permafrost to greater wave action and fetch. Coastal areas with saline and discontinuous permafrost are particularly exposed to the combination of increased wave action, sea level rise, and thermal erosion, and presently no simple engineering solutions exist (see Chapter 5). This combination will lead to increased coastal erosion, with consequences for infrastructure and increased contaminant load (e.g., mercury) (see Outridge et al., 2008). In addition, cumulative effects on permafrost (temperature, precipitation, storm frequency and magnitude, and slow, down-slope movements over time) will add to its thawing rate and will potentially increase impacts on settlements, roads and railways, and infrastructure such as sanitation structures.

Melting sea ice combined with thawing permafrost will release contaminants trapped in the frozen ground and ice (also discussed in Chapter 11, Section 11.3). Melting sea ice will also open waterways and increase the pathways for transport of contaminants into the Arctic Ocean (see also Chapter 9, Sections 9.1 and 9.2). Due to air and ocean currents carrying pollutants into the Arctic from their source regions at lower

Box 10.5. Uncertainty

Projections of the consequences of cryospheric change for human society are impeded by the accumulation of uncertainties across several levels. Models that themselves are only an estimate of changes may be hampered by a lack of observations of physical variables, extrapolations of other measurements, deductions of parameters from other variables, measurement errors, biases, and preferential locations of measurement stations. In addition to inheriting the uncertainty of physical models, models of climate impacts have their own uncertainties:

- The climate system's natural variability is unpredictable, including interannual to multi-decadal variations. These natural variations can mask (or exacerbate) anthropogenically driven changes over annual to decadal scales, yet they can have effects as large as anthropogenic sources.
- High uncertainty exists in the greenhouse gas forcings (e.g., IPCC scenarios A2, A1B, B1).
- Uncertainties also exist with respect to how aspects of cryospheric change may act to exacerbate theoretical expectations (e.g., methane production and release from degrading permafrost). The effects of these uncertainties will increase over time as the consequences of mitigation strategies are realized. Natural variability is a major reason for across-model simulations (projections) for particular time periods – most models capture natural variations, but their timing will not coincide with those of other models (or the real world) if these variations are natural or internal.

Uncertainties in measurements, modeling, and understanding the physical changes of the cryosphere are amplified when projecting their effects on ecosystems upon which people rely;

that is, responses of complex biological systems are in themselves inherently unpredictable, which increases uncertainty of the status of future ecosystem services potentially available from them. Further amplification of uncertainty results when considering the consequences of such changes upon humans and their societies. Figure 10.10 illustrates how changes in cryospheric components may enhance or counterbalance impacts, but also shows how the level of uncertainty about impacts grows with the level of integration of cryospheric components.

Societal, political, and economic influences operating independently of climate change further increase the basic uncertainty inherent in the system. For example, future trade patterns and commodity prices, infrastructure development and technological advances, future greenhouse gas emissions, environmental policies, and how climate will behave as a result of human influence are unknown factors playing a role in future vulnerability to cryospheric and related climate changes relevant to Arctic peoples. Similarly, the nature and scope of adaptive activities, new ways of 'doing business', and many future options are unknowable at present, except perhaps in the most general context. Uncertainty from all sources also increases over a temporal horizon; that is, the more distant in the future the projection is made, the greater the inherent uncertainty in outcomes. Despite the fact that these factors compromise projections of the future, they do not negate the need for adequate preparedness.

While biogeophysical and modeling uncertainties can be estimated, the increasing complexities and levels of uncertainty limit the possibilities to quantify the extent of impacts of cryospheric changes on human society (von Below and Persson, 2008). Anticipating, adapting to, and managing climate and cryospheric changes within these uncertainties are required in a timely manner. Although limited, there is currently sufficient knowledge to understand the direction and trends of the changes for developing appropriate policies to meet the challenges.




Figure 10.10. Uncertainty. Changes for each cryospheric component will have physical, biological, and societal consequences. Integrative aspects (indicated by increasing overlap of components toward the center of the figure) at different temporal and spatial scales may counterbalance or enhance certain consequences. At the same time, the degree of uncertainty of consequences increases with increasing overlap of cryospheric components (toward the center of the figure, indicated by dashed circles).

latitudes, the Arctic acts as a sink for various types of pollution (Macdonald et al., 2005; AMAP, 2009), including particulate aerosols such as black carbon (Box 10.6). Several studies indicate that airborne pollution leads to accelerated melting of sea ice, and a proposed industrial development in Arctic regions may enhance this effect (e.g., Shindell and Faluvegi, 2009). Accordingly, melting sea ice and thawing permafrost may

release great amounts of stored pollutants and adversely affect the health of Arctic residents. Decisions about spatial planning, land use and transportation routes need to incorporate the potential increased risk of slope failure, rockfalls, pollutant release, and coastal erosion to ensure safe communities.

Changes in snow, ice, and permafrost conditions affecting wildlife and fish species important for human livelihoods

Box 10.6. Black carbon

Black carbon (carbonaceous aerosols) results from incomplete combustion of fossil fuels and other organic material (e.g., forest fires) and is a potent, although short-lived, climate-forcing agent. Black carbon is only one of a number of aerosols that may have contributed significantly to Arctic surface temperature increases. Shindell and Faluvegi (2009) estimated that black carbon was responsible for 1.09 ± 0.81 °C of the contribution to warming by aerosols in general (1.48 ± 0.28 °C) between 1976 and 2007. In contrast to carbon dioxide (CO₂), whether delivered from local sources or through transport from longer distances the effects of black carbon are mostly local in that it directly affects the albedo of local snow and ice surfaces (Ramanathan and Carmichael, 2008; Shindell et al., 2008). Deposition of black carbon onto high-albedo surfaces such as snow and ice reduces albedo and enhances radiative absorption, thus fostering melting. Much black carbon deposition occurs in the immediate area of its production, but significant amounts are transported northward from southern sources in the Northern Hemisphere (Hegg et al., 2009). These sources include industrial and agricultural combustion, forest fires, desertification, and general greenhouse gas production. Local northern sources include localized development (e.g., mines, shipping, forest fires). Mitigative measures such as filtering

of soot and increased efficiency associated with fossil fuel combustion are highly effective in reducing the production of black carbon. As a result, as industrial development increases in the North and transportation pathways shift with cryospheric change, regulation of black carbon production from all sources, especially those resulting locally from activities in the Arctic, is required at all scales (local, regional, national, pan-Arctic). Such regulation will benefit from increased compliance and enforcement at all scales and across all sectors; however, initiation of environmental standards is required limiting black carbon production during northern development. Similarly, reduction of black carbon production from southern sources, thereby limiting its transport to the Arctic, is an immediate mitigative measure that could yield substantive benefits by slowing many aspects of cryosphere degradation. There is, however, a potential positive feedback effect linking cryospheric processes promoting drying of sub-Arctic forest and tundra environments (e.g., permafrost degradation, drainage) that, in turn, might foster increased wildfire frequency. Increased fire occurrence will, of course, produce more black carbon and accelerate melt of snow and ice. Thus, increased black carbon production resulting from cryospheric degradation (and all consequences of such) is an example of an integrative forcer linked to cumulative effects of climate change generally.

are likely to exacerbate consequences of societal change and modernization. That is, direct effects from development (e.g., landscape impacts of industrial developments) may affect the northern renewable resource sector, which in turn will also integrate impacts from cryospheric changes (see also Chapter 11, Section 11.4 and the ecological impacts sections in each chapter).

10.6.2. Non-cryospheric drivers of change

Cryospheric change is just one of many factors that shape vulnerability and adaptation to changes in Arctic communities and sectors. Such changes occur in the context of many other factors including resource accessibility, allocation, and extraction policies; limited economic opportunities and markets; access constraints; demographics; attitudes and perceptions of change; bidirectional local-to-global linkages; infrastructure; threats to cultural identity and well-being; transfer of local and traditional knowledge; economic and livelihood flexibility; and enabling institutions. These aspects are rarely independent of each other and frequently combine across scales and sectors (Hovelsrud et al., 2010b). In many cases, socio-economic changes are likely to have greater immediate significance than cryospheric changes, which in turn will affect the ability to adapt.

In general, the effects of industrial development and infrastructural encroachment are experienced by reindeer herders throughout the Arctic as being far more significant than those of cryospheric change (Stammler, 2005; Tyler et al., 2007; Forbes, 2008; Forbes et al., 2009). For example, reindeer herders in the Nenets Autonomous Okrug and the Yamal Nenets Autonomous Okrug consider unbridled oil and gas development on their territories to be a far greater threat to their resilience than extreme weather events (Nuttall

et al., 2005; Forbes, 2008; Forbes et al., 2009). The placement of infrastructure in pasture areas has raised alarm among reindeer herders who fear detrimental effects from windmill parks and mines on reindeer foraging behavior and efficiency, land access and quality, and consequently their livelihoods. Increased industrial activity challenges migration and grazing on traditional pastures (Stammler, 2005; Forbes et al., 2009), leading to areas of unused and underused grazing areas (Caballero et al., 2007; Forbes and Stammler, 2009). Avoidance of certain reindeer pastures can lead to a reduction in optimal range use, leading to complications with herding, increased costs, and reduced production.

Another example is the projected increase in tourism. While there are potential economic benefits for local communities from increased tourism, such an increase may also negatively affect those communities. Given international pressure for sustainable management of wildlife, indigenous communities that depend on hunting, for example, polar bears (for tourism or subsistence) may have to adopt alternative livelihoods (e.g., Hovelsrud et al., 2008). Further expansion of tourist seasons may result in extended use of infrastructure and longer duration of employment and income benefits. How Arctic communities allow their natural and cultural resources to be used by large numbers of visitors and whether or not this is viewed as a disruption depends on the attitude and resources of the community. Impacts may be mitigated through collaborative management with tour operators and in some instances, tax revenues and special fees may offset local costs.

In a review of projects from the Human Dimension of the Arctic System initiative, Huntington et al. (2007b) stated that human activities can greatly amplify the effects of climatic variability and change on Arctic societies (Figure 10.11). This is




Figure 10.11. Example of complexity of cumulative effects. Source: Huntington et al. (2007b).

exemplified by a study of the cod stock collapse in the late 1950s, which resulted from the combined effects of environmental change and high fishing pressure. When combined, these effects were more severe than the environment or fishing might have caused alone. Similarly, in a study of coastal erosion in Barrow, Alaska, public health was greatly improved through the use of ‘utilidors’ (utility corridors) for drinking water and sewage. However, two of the pump stations that pump sewage into the lagoon are close to the shore and exposed to major storms, which leaves the entire system at risk of flooding. This made Barrow more vulnerable to coastal erosion and flooding, even if sea ice had not been decreasing (for both studies see Huntington et al., 2007b for references). The latter example also shows how adaptations may turn out to be counterproductive and exemplifies the complexity of and current limits in understanding of the issue.

Ongoing demographic changes may have similar or even more wide-ranging consequences than changes in the cryosphere (or climate). Gender perspectives of development and generation shifts are two important demographic factors. Traditional gender roles regarding who the breadwinner is in a family are changing. In some indigenous communities for example, there is an increasing shift away from the traditional male ‘hunter’ toward female wage earners, and the new generation may seek other forms of employment than the traditional resource-use activities. Out-migration is another critical demographic factor with consequences for livelihood activities (Rauhut et al., 2008).

Globalization and world markets are also important players in shaping change in the Arctic. However, within this wider milieu the immediate and ongoing additive effects of cryospheric change will compound the effects of changes in the Arctic. In Greenland (Chapter 8), the impacts of climate change have reinforced ongoing socio-economic changes in the same way that climate change has contributed to outlining possible development paths. On the other hand, current adaptations to climate change and policy are predominantly reactive rather than proactive. Cryospheric changes may demand a more proactive adaptation approach in the future to ensure sustainable livelihoods in the Arctic.

10.6.3. Beyond the Arctic

There are important linkages between the Arctic cryosphere and the rest of the world; these include physical (e.g., Arctic climate system feedbacks globally), chemical (e.g., pollutant transport to the Arctic), biological (e.g., migratory biota and ecosystem connections), and societal (e.g., tourism, resource extraction, management, politics) linkages. While global climate change is exacerbating Arctic cryospheric change, these changes will in turn cascade to far-reaching subsequent effects of global consequence. The physical feedback connections are discussed extensively in other chapters: for example, Chapter 5 (Section 5.3.4), Chapter 6 (Section 6.3.1), Chapter 8 (Section 8.3.3.3), Chapter 9 (Section 9.2) and Chapter 11 (Section 11.1). The cold Arctic region typically acts as a sink for heat, greenhouse gases, particulate aerosols, and contaminants and performs fundamental regulatory functions for global climate systems. Degraded cryospheric components will increasingly act less so with highly uncertain consequences; however, hemispheric- and global-scale effects are likely. In some cases, these will be responses to Arctic change that affect the

globe (i.e., simple outputs), whereas in others they will constitute feedback effects which may further alter global processes (e.g., climate system change, weather pattern change, shifting from sink to source for some greenhouse gases, possibly both CO₂ and methane). Such changes are very likely to affect human society beyond the Arctic in some context over the short (i.e., decadal) and long (i.e., century and beyond) term.

Cumulative effects with consequences for society on a broader scale include the feedback from changing snow conditions and surface albedo and the release of methane by thawing terrestrial and sub-sea permafrost to the climate system (e.g., see Chapter 4, Section 4.4.4 and Chapter 5, Section 5.3.4) leading to accelerated global warming. Such amplification needs to be included when developing mitigation efforts and in updated models projecting future climate change. In contrast, the increased period of open water on lakes and increased growing season for vegetation will lead to increased evaporation and transpiration, drying of the landscape, and a negative feedback to climate, especially when combined with drainage of tundra water bodies fostered by permafrost degradation, although the balance between these two processes is highly uncertain (see Chapter 4).

Changes in the Arctic cryosphere coupled with other climate-driven changes have hemispheric and global-scale societal effects, which may include the following:

- Enhanced ice outflow (icebergs and ice export) leading to shipping hazards in the North Atlantic.
- Alteration of oceanic and riverine heat and freshwater transport to Arctic environments and alteration of oceanic circulation patterns, affecting ecosystems and impacting fisheries and hunting activities.
- Alteration of the structure and functional relationships within and services received from terrestrial, freshwater, and marine Arctic and sub-Arctic ecosystems, including possible loss of iconic species and altered biodiversity.
- Increased activities in the Arctic leading to increased risk of pollution and increased shipping bringing noise pollution and ballast water that contains contaminants and invasive species (Berner et al., 2005; Occhipinti-Ambrogi, 2007; AMAP, 2009).
- Uptake of pollutants via microorganisms into the Arctic food web (e.g., fisheries) that have local and global health impacts.
- Economic opportunities that may provide impetus to national and global economies but must be developed in a sustainable manner.
- Significant contribution to global sea level rise and thus follow-on effects for low-lying coastal regions throughout the world.

10.6.4. ‘Winners and losers’

The concept of ‘winners and losers’ is complex, context- and location-specific, varies with time, and pertains to multiple factors of change (cryospheric and societal). Industries, which may be located outside the Arctic, will generally gain from cryospheric change, but this is contingent on global and local economic and infrastructure developments. Likewise, while

some local indigenous communities may be viewed as ‘losers’, some communities may be ‘winners’ from emerging industries (through jobs, revenues, health care etc.) or changes in wildlife or fish stocks. Yet others may not benefit from industrial development in their region and climatic or environmental changes will add to the challenges (Huntington et al., 2007a,b). In addition, while a community may ‘win’ in some respects (e.g., economic and health), it may ‘lose’ in others (e.g., loss of traditional livelihood and culture). Some argue that the notion of ‘winners and losers’ is not applicable in the Arctic context. There is a need to balance the potential for long-term economic benefits with the shorter-term costs that an unpredictable and changing climate forces cultures to bear in terms of livelihood and social identity.

10.7. Gaps in knowledge and future needs

- Cryospheric degradation will result in cascading effects on Arctic environments and peoples; their livelihoods, living conditions, and quality of life; and the regional climate systems. These effects will have global consequences.
- The precise ways that people and communities will be affected need further study, particularly with regard to adaptation, changes in behavior, health, and resource development.
- Effective observations and monitoring across geographical and temporal scales, sectors, and disciplines are all required in a linked interdisciplinary manner to provide measurement of change, assess efficacy of mitigative and adaptive strategies, and to prioritize needs for governance and other appropriate responses.

The impacts of Arctic change generally are occurring sooner, more rapidly, and more broadly than anticipated only a short time ago. The changes are exacerbated by cryospheric changes and demand substantive and rapid responses from all levels of government within nations, the development of international conventions and protocols, and effective and rapid action through international governance mechanisms. Responses at all levels must include adaptive and mitigative actions as well as appropriate regulatory and compliance actions to protect cultural integrity, promote human health, and ensure sustainable economic well-being. Integrative and adaptive forecasts that can help identify effective responses are required in order to facilitate the early development of policies. Better and more inclusive (especially of Arctic residents) ways of doing business are required. How to do so across scales is a major gap.

10.7.1. Research needs

As this chapter has illustrated, much can be said about the ways that a changing cryosphere affects or is likely to affect people in and beyond the Arctic. As should also be clear, there remains a great deal that is unknown or uncertain, both in terms of the trajectory of cryospheric change and in terms of human response and adaptation. Research is needed in two general areas: to better understand how people *can* adapt to a changing cryosphere and to learn from the ways that people

are adapting already. While this section provides examples of important research areas, an exhaustive list is not possible given the range of topics and ways to consider response and adaptation in human societies.

The capacity to adapt and respond effectively to cryospheric change can vary greatly among individuals, communities, and regions. Similarly, vulnerability to changes can differ even between communities that have many similarities. Research in this area is needed to better understand the underlying conditions and processes that shape vulnerability and adaptive capacity, and to better understand the aspirations and priorities of the people and communities in question in order to identify adaptation goals and pathways.

In a similar vein, little is known about the processes and consequences of migration, relocation, and resettlement of Arctic communities. Some have already occurred for various reasons, and more may be anticipated due to cryospheric change such as coastal and riverbank erosion, loss of permafrost and sea level rise. This question involves local dimensions (in terms of individual experiences) and regional and national dimensions (in terms of the ability of governments to support the construction and establishment of new community sites if needed). Such changes must be considered against the backdrop of urbanization around the Arctic.

The loss of sea ice in particular has generated considerable international interest in Arctic natural resources as well as the strategic importance of the region. While there is a great deal of speculation, the global significance of Arctic shipping routes remains uncertain, and the prospects for exploiting many resources depend greatly on worldwide market forces, not just on physical access. The Arctic remains remote and cold, and the development of minerals, petroleum, and fisheries faces many challenges. As such resources are developed, further research is needed to determine optimal ways of doing so to meet regional and national goals such as financial well-being, political independence, and long-term sustainability.

Coastal and riverbank erosion, although not new phenomena in the Arctic, appear to be increasing. Comprehensive assessments have not yet been carried out on the vulnerability of Arctic communities and infrastructure to erosion or on the implications for the placement of infrastructure related to resource extraction. This issue relates in part to that of migration, relocation, and resettlement, in that the ability of national governments to respond to erosion depends in part on the scale of the problem. One community relocation may be possible, but dozens may cost more money than is available, reducing the number of possible responses as time goes by. Rising sea level will also play a role in the long-term effectiveness of any measures taken in the short term.

Ice is not only a barrier to commercial transportation and development. Ice roads allow a relatively inexpensive, low-impact means of getting equipment and supplies to remote locations in the Arctic. They are also used in some regions to connect communities that do not have year-round road access. However, the use of ice roads obviously depends on lasting, reliable ice. As the climate warms and if weather becomes more variable, the reliability and duration of ice roads may diminish. This will raise costs for businesses and communities where simple alternatives to the seasonal ice roads may not exist. More research is needed to examine the economic and social roles

that ice roads play in the Arctic, the vulnerability of ice roads to a changing cryosphere, and the prospects for alternatives.

The impacts of a changing cryosphere on human health have not been examined in detail, although the effects of low air temperatures, low humidity, and other features of Arctic winters have been studied. A changing cryosphere may remobilize contaminants and other air and water pollutants, increasing the availability of these substances to humans either directly or indirectly through the food web. In addition, retreat of glaciers and declining snow cover may lead to more dust in the air from wind events, adding another health stressor. More research is needed on the likely health effects of a changing cryosphere, in part to help health care professionals recognize and respond to new trends in health.

The safety and well-being of Arctic residents may also be affected by a changing cryosphere. Thinner ice, different conditions on land and at sea, and different patterns of fish and wildlife distribution may increase risks, especially if the production of new knowledge about the changing conditions cannot keep pace with the rate of change. More study is needed on risk perception, risk avoidance, and knowledge production in Arctic communities to help determine how to foster effective adaptation. This work should also examine how instrumental and modeling data can be provided to Arctic residents to help them make decisions about their daily activities.

As previously discussed, cryospheric changes are not the only drivers of change, and it is important that research is initiated on the multifaceted processes where impacts of cryospheric changes intertwine with consequences of industrial development in the Arctic. In some areas, hydrocarbon and mining developments are a greater threat to indigenous resilience than a changing climate (Nuttall et al., 2005; Forbes, 2008; Forbes and Stammler, 2009). In order to understand the impact of such developments on indigenous peoples, it is necessary to investigate environmental and societal conditions in combination with consequences of developments and across local, national, and international scales. To date, technology and the use of best practices have reduced environmental impacts, but additional risks may occur as conditions change or new areas are explored and developed. More generally, it is important to assess the combined impacts of cryospheric, industrial, and societal changes on the livelihoods, living conditions, and quality of life of the indigenous peoples and other Arctic residents.

10.7.2. **Observation, monitoring, modeling, and downscaling needs**

A key contributor to effective adaptation and response is reliable information about the consequences of cryospheric change for a locale. While environmental conditions cannot be predicted accurately, information on likely future trends and events is nonetheless useful for planning. In addition, real-time information can help reduce risks from hazards such as icebergs, floods, and severe storms. A major challenge is to provide such information on temporal and spatial scales relevant to the users. The areas described below are examples of information needs, but as with the description of research needs, the list is not exhaustive.

Establishing baselines of present conditions in order to

monitor changes in snow, permafrost, treeline, and sea, river, and lake ice is especially important. In addition, there is a particular need to monitor the effects of cryospheric changes on socio-economic conditions and biodiversity. This will increase understanding of linkages between, and allow for improved forecasting of future changes. Moreover, by mapping how local and indigenous communities and sectors adapt to change, it is possible to create transferable knowledge. Several monitoring networks are already in place: the Sustaining Arctic Observing Networks (SAON) is a newly established network, endorsed by the Arctic Council, which focuses broadly on observing changes in environmental and physical systems. The network will also include observations of social and economic conditions.

Of key importance are improved mapping, surveillance, and monitoring of drifting ice and icebergs, annual variations in ice cover, and continuing local sea-ice formation along with the frequency of storm surges, wave heights, and wind. A number of programs have been developed (e.g., Arctic Report Card, Polar View). Such monitoring is relevant for ship traffic, industrial developments, and local hunting routes (OPRC, 1990; Chircop, 2009). Medium- and long-range forecasts of ice break-up and freeze-up will be an important aid for companies in deciding on the seasonal window for operation, whereas near real-time monitoring will facilitate safe and productive local travel as well as hunting and fishing. For hunting activities that are particularly sensitive to snow and ice conditions (Ford and Furgal, 2009), knowledge of changes in the timing and amount of snow is important. Monitoring snow cover, winter thaw, and rain will also provide information relevant for hydropower and risks related to drought, snow load, avalanches, and floods. The rate of change in snow conditions requires adaptation by reindeer herders and others relying on terrestrial conditions for resource harvesting and travelling. Traditional knowledge of reindeer, pastures, and snow conditions is essential for successful adaptation (e.g., Tyler et al., 2007). In addition, people in the Arctic need information on qualified changes in snow conditions, such as maximum accumulations for snow load calculations, water supply, flood management, avalanche risk, and snow clearing for permafrost stabilization to adapt (Allard et al., 2007).

Monitoring existing structures built on permafrost, follow-up of historical data, and back calculation of known failures are important to gain a better understanding of the ways such structures are affected. Permafrost also plays a role in preserving ancient and recent records of human culture and past biota that are of considerable value to archaeologists and paleontologists. As permafrost thaws, these unique records will be destroyed, and there is a need to survey areas of thawing permafrost to secure the archives of the past. The need for monitoring is not restricted to cryospheric elements, but extends to monitoring the consequences of increased shipping, tourism, and industrial activity such as pollution, emissions, navigation impacts on marine species, and introduction of non-indigenous organisms through ballast water exchanges.

In addition to monitoring, there is a need for new and improved projections of future trends. In particular, to continue developing downscaling techniques to map future cryospheric changes relevant at local and regional levels. Adaptation is a response to local changes in cryospheric conditions and their impacts, and downscaled projections of future conditions that

capture locally relevant changes help adaptation (Hovelsrud et al., 2010a). For such downscaling efforts to be successful, it is necessary to involve local people, indigenous as well as non-indigenous, to identify the most relevant cryosphere (or climate) elements. Downscaled projections can be combined with spatial use of land, lakes, rivers, and sea ice to provide useful information for the users (Hovelsrud et al., 2010a; Rybråten and Hovelsrud, 2010). Projections of specific parameters will need to cover geographical and seasonal extent and coverage (such as location, packing, and thickness of ice) and ideally on timescales ranging from hourly to months. In addition, research is needed to better understand how to connect science to stakeholders for better decision-making in governance.

Incorporating local and traditional knowledge in the interpretation of satellite-derived snow- and ice-cover products and in the development of community-based monitoring programs will provide local data for scenario development and enhance community involvement and decision-making. Local focus and traditional and local knowledge are essential in studies on and for adaptation (Krupnik et al., 2010; Smit et al., 2010) (see Appendix 10.1 for a list of relevant projects under the International Polar Year (IPY) 2007/08). Local understanding of change and adaptation needs can be generalized through the transfer of practical knowledge and can help increase the scientific knowledge base. More and integrated knowledge about adaptation is needed across scientific disciplines and local and traditional knowledge, between scientists and decision makers, and on the international arena (Hovelsrud et al., 2010a).

Not all needs call for creating new and more data; much information on local impacts currently exists in local records and is compiled in unpublished reports and documents in municipalities and infrastructure maintenance authorities (e.g., roads, railways). It is often difficult to locate such data and information, which is critical for assessing the socio-economic impacts of changing conditions. Such information is highly relevant to monitoring and observing change and is an important source for developing adaptation strategies. It is therefore important to catalogue this type of information and make it available. In addition, current monitoring and observation efforts would benefit from including identification of user needs in order to provide useful information for communities and industries for ensuring safety and for developing environmentally sound activities (Hovelsrud and Smit, 2010; Krupnik et al., 2010).

10.7.3. Meeting governance and technology needs

With an expected increase in human activities such as fisheries, tourism, and industrial development follows an increased demand for seasonal ice-breaking of harbors and routes.

Increases in shipping and marine-based development activities will require increases in environmental regulation, safety preparedness and response, and improvements in marine charting, weather, and ice forecasting. Improved disaster management (groundings, sinkings) and training of local search and rescue personnel are of key importance (OPRC, 1990; Chircop, 2009).

Retreating glaciers could lead to an increase in possible

hazardous jökulhlaups, but little is currently known about increased risk to communities in the Arctic. There is limited knowledge about hazards from the distribution, frequencies, and impacts of such events in the Arctic. For increased avalanche potential, adaptation strategies could build on existing measures from other regions; however, regional assessments and development of effective forecasting of risk is required. In a changing cryosphere, adaptation by technological developments will be necessary. Infrastructure must be designed to withstand projected future climate conditions. Regardless of the solutions, monitoring programs will be important not only for facilitating the mitigation of environmental impacts but also for mitigating the effects of ongoing climate change.

A changing cryosphere will affect wildlife habitat, population sizes, and migratory behavior (see Chapter 9, Section 9.3). To minimize further impact, careful consideration of cruise tourism transport schedules and hunting and fisheries conditions are of critical importance to ensuring the cultural and economic well-being of Arctic peoples (UNEP, 2007). In addition, there are environmental, economic, social, and cultural impacts from garbage, waste, and pollution problems that require regulation.

There are clear limits to any Arctic governance regime (regulatory or soft-law), because the drivers of cryospheric change occur largely outside the region and fall beyond the jurisdiction of any one Arctic state. Current changes signal the need for effective interplay across societal levels and scales between Arctic institutions and existing regimes (Stokke and Honneland, 2007; Young, 2009b). In addition, there is a clear need for further monitoring and the use of monitoring data in knowledge co-production and shared learning (Riedlinger and Berkes, 2001; Laidler, 2006; Bravo, 2009).

The wide-ranging changes affecting all aspects of the Arctic, when combined with the fundamental and far-reaching added changes resulting from cryospheric shifts, will result in many challenges associated with all aspects of development. Managing such changes sustainably represents a further challenge particularly in the context of developmental cascades. To achieve orderly development, effective governance strategies must address not only the changes anticipated and responsive adaptive or mitigation measures, but also future opportunities. Appropriate regional-scale management bodies may be required to integrate and assess the totality of shifting environments (cryosphere and climate) and developmental plans over varying timescales. Representation of indigenous peoples and other Arctic residents on such decision-making bodies is imperative.

Appendix 10.1. Relevant projects under the International Polar Year

International Polar Year (IPY) projects related to people in the Arctic, based on the IPY honeycomb chart and project database and selected from 194 projects containing the keywords ‘human’ or ‘people’. The IPY in combination with other international research programs will continue to provide a wealth of knowledge on Arctic climate change and impacts.

Topic	IPY-id	Acronym	Full project name
Dynamic Social Strategies	6		Dynamic Social Strategies in Arctic Environments: Long-term Perspectives on Movement and Communication
Historical Exploitation of Polar Areas	10	LASHIPA	Large Scale Historical Industrial Exploitation of Polar Areas
USNPS Environmental Change	21		U.S. National Park Service Understanding environmental change and its biological, physical, social, subsistence, and cultural effects in national parks and protected areas of Alaska, Chukotka, and the Yukon, through research, monitoring, education, and outreach
History of International Polar Years	27		Changing Trends in Polar Research as Reflected in the History of the International Polar Years
Sami in Literature	30		Representations of Sami in Nineteenth Century Polar Literature: The Arctic ‘Other’
Monitoring Development in Traditional Indigenous Land Use Areas	46	MODIL-NAO	Traditional Indigenous Land Use Areas in the Nenets Autonomous Okrug, Northwest Russia
Arctic Change	48	ISAC	International Study of Arctic Change
The Linguistic and Cultural Heritage Electronic Network	82	LICHEN	LICHEN: The Linguistic and Cultural Heritage Electronic Network
History of IPY Field Stations	100		Polar Field Stations and IPY History: Culture, Heritage, Governance (1882 – Present)
Northern Climate Variability	120	NORCLIM	Northern High Latitude Climate variability during the past 2000 years: implications for human settlement
Language, Literature, & Media	123		Glocalization – Language, Literature, and Media among Inuit and Sami people
Community Adaptation & Vulnerability	157	CAVIAR	Community Adaptation and Vulnerability in Arctic Regions
Rangifer Monitoring	162	CARMA	Starting the clock for the CARMA Network: Impacts on Human-Rangifer Systems in the Circumarctic
Inuit, Narwhals, & Tusks	164		Inuit and Scientific Descriptions of the Narwhal, Connecting Parallel Perceptions: Inter-disciplinary Studies of the Narwhal with a Focus on Tusk Function
Sea Ice Knowledge & Use	166	SIKU	Sea Ice Knowledge and Use: Assessing Arctic Environmental and Social Change
Human Health Initiative	167	AHHI	Arctic Human Health Initiative
Community Resilience & Diversity	183		Arctic Resiliency and Diversity: Community Response to Change
Food Safety & Wildlife Health	186		Engaging communities in the monitoring of zoonoses, country food safety and wildlife health
Exchange Local Knowledge	187	ELOKA	Exchange for Local Observations and Knowledge of the Arctic (formerly APOC (Arctic Peoples Observations Center), #358)
Northern Material Culture	201	NORMA	Northern Material Culture through International Polar Year Collections, Then and Now: In the Footsteps of Murdoch and Turner
Protecting Traditional Knowledge	206		Legal and Constitutional Frameworks for Protecting Traditional Ecological Knowledge in Northern Canada
Global Change, Social Challenges	210		Global Change – Social Challenges Processes of socio-economic changes in the Circumpolar North, with focus on gender and inter- and intra-generational relations
Political Economy of Development	227		The Political Economy of Northern Development
Bering Sea Community Monitoring	247	BSSN	Bering Sea Sub-Network of Community-Based Environmental Monitoring, Observation and Information Stations
Community-based Research Alliance	248	AICEMI	Arctic Indigenous Community-based Monitoring and Information Stations Network: Arctic Community-based Research Alliance
Conservation Hunting	259		Conservation Hunting in the Arctic: An Analysis of Constraints and Opportunities
Impacts of Ecosystem Disturbances	275		Polar Disturbance and Ecosystem Services: Links between Climate and Human Well-being
Initial Colonization	276	ICOL	Initial Human Colonization of Arctic in Changing Palaeoenvironments

Northern Genealogies	285		Northern Genealogies: Development of an ethnodemographic informational system on the peoples of Siberia and the Russian North
Impacts of Oil & Gas Activity	310	GAPS	The Impacts of Oil and Gas Activity on Peoples in the Arctic Using a Multiple Securities Perspective
Fishery Ecosystems	325	ArcOD	Marine and estuarine ecosystems in the eastern, central, and western Canadian Arctic
Land Rights & Resources	337	CLUE	Dynamics of Circumpolar Land Use and Ethnicity
Economy of the North	355	ECONOR	The Economy of the North
Food Surveillance System	384		Integrity of the Traditional Food System and Environmental Health in the Circumpolar North
Survey of Living Conditions	386	SLiCA-RAAS	Survey of Living Conditions in the Arctic, SLiCA – Remote Access Analysis System
Reindeer Herding & Climate Change	399	EALÁT	Reindeer Herders Vulnerability Network Study: Reindeer Pastoralism in a Changing Climate
Monitoring Human-Rangifer Migrations	408	NOMAD	Social-science migrating field station: monitoring the Human-Rangifer link by following herd migration
Land & Coastal Resources	411	ARD	Norwegian and Russian Arctic Resources: Prospects for Social and Economic Development
Integrated Tools for Communities	431	ARCTEC	ARCTEC: A Cumulative Effects Toolbox for Northern Ecological and Social Systems
Well-being of Arctic Indigenous People	433		Pressures and Impacts on the Health and Well-being of Indigenous People of the Arctic: Invitational International Symposium and Symposium Publication
Cultural Heritage in Ice	435		Culturally and Scientifically Significant Materials Recovered from Melting Ice and Cryosols: Recovery, Research, Stabilization, and Community Education
Relocation & Resettlement in the North	436	MOVE	Moved by the State: Perspectives on Relocation and Resettlement in the Circumpolar North
People, Wilderness, & Tourism	448		People and wilderness resources in Arctic. Is local subsistence harvest and exclusive wilderness tourism a road to sustainable well-being or a source of conflict
Sustainable Development	456	PASDAC	Practical Applications for Sustainable Development in Arctic Communities
Arctic Social Indicators	462	ASI	Arctic Social Indicators
Modeling and Observation	40	DAMOCLES	Developing Arctic Modeling and Observing Capabilities for Long-term Environmental Studies
International Study of Arctic Change	48	ISAC	International Study of Arctic Change
Cryos – State of the Cryosphere	105	Cryos	State and Fate of Polar Cryosphere

References

- Aaheim, A., H. Dannevig, T. Ericsson, B. van Oort, L. Innbjør, T. Rauken, H. Vennemo, H. Johansen, M. Tofteng, C. Aall, K. Groven and E. Heiberg, 2009. Konsekvenser av klimaendringer, tilpasning og sårbarhet i Norge – Rapport til Klimatilpasningsutvalget. [in Norwegian]. CICERO Report. 4:238 pp.
- Abegg, B., S. Agrawala, F. Crick and A. Montfalcon, 2007. Climate change impacts and adaptation in winter tourism. In: Agrawala, S. (Ed.). *Adaptation in the European Alps. Adapting Winter tourism and natural hazard management*, pp. 25–60, Organization for Economic Co-operation and Development, OECD Publishing.
- ACIA, 2005. *Arctic Climate Impact Assessment*. 1042 pp. Cambridge University Press.
- Adger, W.N. and P.M. Kelly, 1999. Social vulnerability to climate change and the architecture of entitlements. *IPCC Special Issue on 'Adaptation to Climate Change and Variability', Mitigation and Adaptation Strategies for Global Change*, 4:253–266.
- Agrawal, A., 2008. The role of local institutions in adaptation to climate change. IFPRI working paper. 65 pp. School of Natural Resources and Environment, University of Michigan.
- Agrawala, S., 2008. Responses to glacier retreat in the context of development planning in Nepal. In: Orlove, B., E. Wiegandt and B.H. Luckman (Eds.). *Darkening Peaks. Glacier Retreat, Science and Society*, pp. 241–248, University of California Press.
- AHDR, 2004. *Arctic Human Development Report*. 242 pp. Stefansson Arctic Institute, Akureyri, Iceland.
- Allard, M., R. Fortier, D. Sarrazin, F. Calmels, D. Fortier, D. Chaumont, J.P. Savard and A. Tarussov, 2007. L'impact du réchauffement climatique sur les aéroports du Nunavik : caractéristiques du pergélisol et caractérisation des processus de dégradation des pistes. Final report. [in French]. 199 pp. Ouranos Consortium.
- AMAP, 2007. *Arctic Oil and Gas. Arctic Monitoring and Assessment Programme*. 57 pp.
- AMAP, 2009. *AMAP Assessment 2009: Human Health in the Arctic. Arctic Monitoring and Assessment Programme*. xiv+254 pp.
- Amundsen, H., F. Berglund and H. Westskog, 2010. Overcoming barriers to climate change adaptation a question of multilevel governance? *Environment and Planning C*, 28:276–289.
- Andrachuk, M. and T. Pearce, 2010. Vulnerability and adaptation in two communities in the Inuvialuit settlement region. In: Hovelsrud, G.K. and B. Smit (Eds.). *Community Adaptation and Vulnerability in the Arctic Regions*, pp. 63–82, Springer.
- Anisimov, O. and S. Reneva, 2006. Permafrost and changing climate: The Russian perspective. *Ambio*, 35:169–175.
- Anisimov, O.A., D.G. Vaughan, T.V. Callaghan, C. Furgal, H. Marchant, T.D. Prowse, H. Vilhjálmsson and J.E. Walsh, 2007. Polar regions (Arctic and Antarctic). In: Parry, M.L., O.F. Canziani, J.P. Palutikof, P.J. van der Linden and C.E. Hanson (Eds.). *Climate Change 2007: Impacts, Adaptation and Vulnerability. Contribution of Working Group II to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change*, pp. 653–685, Cambridge University Press.
- Arctic Council, 2009. *Arctic Marine Shipping Assessment 2009 Report*.
- Armitage, D.R., 2005. Community-based narwhal management in Nunavut, Canada: Change, uncertainty, and adaptation. *Society and Natural Resources*, 18:715–731.
- Armitage, D., F. Berkes and N. Doubleday (Eds.), 2007. *Adaptive Co-Management: Collaboration, Learning and Multi-Level Governance*. 360 pp. University of British Columbia Press.
- Armitage, D.R., R. Plummer, F. Berkes, R.I. Arthur, A.T. Charles, I.J. Davidson-Hunt, A.P. Diduck, N.C. Doubleday, D.S. Johnson, M. Marschke, P. McConney, E.W. Pinkerton and E.K. Wollenberg, 2009. Adaptive co-management for social-ecological complexity. *Frontiers in Ecology and the Environment*, 7:95–102.
- Aslaksen, I., W. Dallmann, D.L. Holen, E. Høydahl, J. Kruse, B. Poppel, M. Stapleton and E.I. Turi, 2009. Interdependency of subsistence and market economies in the Arctic. In: Glomsrød, S. and I. Aslaksen (Eds.). *The Economy of the North 2008*, pp. 75–98. Statistics Norway.
- Ayles, B., R. Bell and A. Hoyt, 2007. Adaptive fisheries co-management in the western Canadian Arctic. In: Armitage, D., F. Berkes and N. Doubleday (Eds.). *Adaptive Co-Management: Collaboration, Learning and Multi-Level Governance*, pp. 125–150.
- Barber, D.G., J.V. Lukovich, J. Keogak, S. Baryluk, L. Fortier and G.H.R. Henry, 2008. The changing climate of the Arctic. *Arctic*, 61:7–26.
- Barnett, T.P., J.C. Adam and D.P. Lettenmaier, 2005. Potential impacts of a warming climate on water availability in snow-dominated regions. *Nature*, 438:303–309.
- Beltaos, S. and T. Prowse, 2009. River-ice hydrology in a shrinking cryosphere. *Hydrological Processes*, 23:122–144.
- Bergström, S., T. Jóhannesson, G. Aðalgeirsdóttir and 29 others, 2007. Impacts of climate change on river runoff, glaciers and hydropower in the Nordic area. Joint final report from the CE Hydrological Models and Snow and Ice Groups, CE Report CE-6. 24 pp. Norden-Nordic Energy Research, Reykjavik, Iceland.
- Berkes, F., 2009. Evolution of co-management: Role of knowledge generation, bridging organizations and social learning. *Journal of Environmental Management*, 90:1692–1702.
- Berner, J., C. Furgal, P. Bjerregaard, M. Bradley, T. Curtis, E. De Fabo, J. Hassi, W. Keatinge, S. Kvernmo, S. Nayha, H. Rintamaki and J. Warren, 2005. Human health. In: *Arctic Climate Impact Assessment*, pp. 863–906, Cambridge University Press.
- Bjerke, J.W. and H. Tømmervik, 2008. Observerte skader på nordnorske planter i løpet av vår og sommer 2006: omfang og mulige årsaker. [in Norwegian]. *Blyttia*, 66:90–96.
- Bogoyavlensky, D. and A. Siggner, 2004. Arctic demography. In: *Arctic Human Development Report*, pp. 27–41, Stefansson Arctic Institute, Akureyri, Iceland.
- Bowd, A.D., 2005. Otitis media: health and social consequences for aboriginal youth in Canada's north. *International Journal of Circumpolar Health*, 64:5–15.
- Bradley, M., S.J. Kutz, E. Jenkins and T.M. O'Hara, 2005. The potential impact of climate change on infectious diseases of Arctic fauna. *International Journal of Circumpolar Health*, 64:468–477.
- Brander, K., 2010. Impacts of climate change on fisheries. *Journal of Marine Systems*, 79:389–402.
- Bravo, M., 2009. Community-based monitoring and self-interest. *The Circle*, 1:11–13.
- Bronen, R., 2008. Alaskan communities' rights and resilience. *Forced Migration Review No. 31 – Climate change and displacement*, pp. 30–32.
- Brown, R.D. and P.W. Mote, 2009. The response of northern hemisphere snow cover to a changing climate. *Journal of Climate*, 22:2124–2145.
- Caballero, R., J.A. Riseth, N. Labba, E. Tyran, W. Musial, E. Motik, A. Boltshauser, P. Hofstetter, A. Gueydon, N. Roeder, H. Hoffmann, M.B. Moreira, I.S. Coelho, O. Brito and A. Gil, 2007. Comparative typology in six European low-intensity systems of grassland management. *Advances in Agronomy*, 96:351–420.
- Carlson, K.B., 2010. End of the roads; Warm weather melting main link to remote communities. *Canadian National Newspaper*. March 20, 2010.
- Chircop, A., 2009. The growth of international shipping in the Arctic: Is a regulatory review timely? *The International Journal of Marine and Coastal Law*, 24:355–380.
- Christensen, J.H., B. Hewitson, A. Busuioac and 14 others, 2007. Regional climate projections. In: Solomon, S., D. Qin, M. Manning, Z. Chen, M. Marquis, K.B. Averyt, M. Tignor and H.L. Miller (Eds.). *Climate Change 2007: The Physical Science Basis. Contribution of Working Group I to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change*, pp. 847–940, Cambridge University Press.
- Commission of the European Communities, 2008. Communication from the commission to the European Parliament and the Council: The European Union and the Arctic region. 20.11.2008, COM (2008) 763.
- Côté, F. and T. Williams, 2008. *The Arctic: Environmental issues. Parliamentary Information and Research Service Publication. Infoseries, PRB 08-04E*. 7 pp. Library of Parliament, Ottawa, Canada.
- Crabbé, P. and M. Robin, 2006. Institutional adaptation of water resource infrastructures to climate change in Eastern Ontario. *Climatic Change*, 78:103–133.
- Daerga, L., A. Edin-Liljegren and P. Sjolander, 2004. Work-related musculoskeletal pain among reindeer herding Sami in Sweden – a pilot study on causes and prevention. *International Journal of Circumpolar Health*, 63:343–348.
- Dalen, L. and A. Hofgaard, 2005. Differential regional treeline dynamics in the Scandes Mountains. *Arctic Antarctic and Alpine Research*, 37:284–296.
- Dawson, J., M.T. Patrick and S.D. Slocombe, 2007. Climate change, marine tourism and sustainability in the Canadian Arctic: Contributions

- from systems and complexity approaches. *Tourism in Marine Environments*, 4:69-83.
- Dickson, B., J. Hutton and B. Adams, 2009. *Recreational Hunting, Conservation and Rural Livelihoods: Science and Practice*. 384 pp. Wiley-Blackwell.
- Duhaime, G., 2004. Economic systems. In: *Arctic Human Development Report 2004*, pp. 74-75. Stefansson Arctic Institute, Akureyri, Iceland.
- Duhaime, G. and A. Caron, 2009. Economic and social conditions of Arctic regions In: Glomsrød, S. and I. Aslaksen (Eds.). *The Economy of the North 2008*, pp. 11-23, Statistics Norway, Oslo, Norway.
- Efthymiou, M. and M. Winkler, 2009. In deep water. www.offshore-technology.com/features/feature52918/ Accessed: October 27, 2010.
- Eitzinger, J., A. Utset, M. Trnka, Z. Zalud, M. Nikolaev and I. Uskov, 2007. Weather and climate and optimization of farm technologies at different input levels. In: Sivakumar, M.V.K. and R.P. Motha (Eds.). *Managing Weather and Climate Risks in Agriculture*, pp. 141-170, Springer.
- Elverhøy, H., R.V. Engeset, L.M. Andreassen, J. Kohler, Y. Gjessing and H. Björnsson, 2002. Assessment of possible jökulhlaups from Lake Demmevatn in Norway. In: Snorrason, A., H.P. Finnadóttir and M. Moss (Eds.). *Extreme of the Extremes: Extraordinary Floods*, pp. 31-31, IAHS Press.
- Eriksson, O., 1976. Snöförhållandenas inverkan på renbetningen. [in Swedish]. (The influence of snow conditions on reindeer pasturing). *Meddelanden från Växtbiologiska Institutionen, Uppsala: Uppsala University*, 1976:1-19.
- Falloon, P. and R. Betts, 2010. Climate impacts on European agriculture and water management in the context of adaptation and mitigation – the importance of an integrated approach. *Science of the Total Environment*, 408:5667-5687.
- Finlayson, J.D., K. Betteridge, A. MacKay, B. Thorrold, P. Singleton and D.A. Costall, 2002. A simulation model of the effects of cattle treading on pasture production on North Island, New Zealand, hill land. *New Zealand Journal of Agricultural Research*, 45:255-272.
- Forbes, B.C., 2008. Equity, vulnerability and resilience in social-ecological systems: a contemporary example from the Russian Arctic. *Research in Social Problems and Public Policy* 15:203-236.
- Forbes, B.C. and F. Stammer, 2009. Arctic climate change discourse: the contrasting politics of research agendas in the West and Russia. *Polar Research*, 28:28-42.
- Forbes, D.L., G.S. Parkes, G.K. Manson and L.A. Ketch, 2004. Storms and shoreline retreat in the southern Gulf of St. Lawrence. *Marine Geology*, 210:169-204.
- Forbes, D.L., G.K. Manson, D. Mate and A. Qammaniq, 2008. Cryospheric change and coastal stability: combining traditional knowledge and scientific data for climate change adaptation. *Ice and Climate News*, 11:17-18.
- Forbes, B.C., F. Stammer, T. Kumpula, N. Meschtyb, A. Pajunen and E. Kaarlejärvi, 2009. High resilience in the Yamal-Nenets social-ecological system, West Siberian Arctic, Russia. *Proceedings of the National Academy of Sciences of the United States of America*, 106:22041-22048.
- Forbes, B.C., M.M. Fauria and P. Zetterberg, 2010. Russian Arctic warming and 'greening' are closely tracked by tundra shrub willows. *Global Change Biology*, 16:1542-1554.
- Forchhammer, M.C., E. Post, T.B.G. Berg, T.T. Høye and N.M. Schmidt, 2005. Local-scale and short-term herbivore-plant spatial dynamics reflect influences of large-scale climate. *Ecology*, 86:2644-2651.
- Ford, J.D., 2009. Vulnerability of Inuit food systems to food insecurity as a consequence of climate change: a case study from Igloolik, Nunavut. *Regional Environmental Change*, 9:83-100.
- Ford, J.D. and C. Furgal, 2009. Foreword to the special issue: climate change impacts, adaptation and vulnerability in the Arctic. *Polar Research*, 28:1-9.
- Ford, J.D. and B. Smit, 2004. A framework for assessing the vulnerability of communities in the Canadian arctic to risks associated with climate change. *Arctic*, 57:389-400.
- Ford, J.D., B. Smit, J. Wandel and J. MacDonald, 2006a. Vulnerability to climate change in Igloolik, Nunavut: what we can learn from the past and present. *Polar Record*, 42:127-138.
- Ford, J.D., B. Smit and J. Wandel, 2006b. Vulnerability to climate change in the Arctic: A case study from Arctic Bay, Canada. *Global Environmental Change*, 16:145-160.
- Ford, J., T. Pearce, B. Smit, J. Wandel, M. Allurur, K. Shappa, H. Ittusujurat and K. Qrunnut, 2007. Reducing vulnerability to climate change in the Arctic: The case of Nunavut, Canada. *Arctic*, 60:150-166.
- Ford, J., T. Pearce, J. Gilligan, B. Smit and J. Oakes, 2008. Climate change and hazards associated with ice use in Northern Canada. *Arctic, Antarctic and Alpine Research*, 40:647-659.
- Ford, J.D., W.A. Gough, G.J. Laidler, J. MacDonald, C. Irngaut and K. Qrunnut, 2009. Sea ice, climate change, and community vulnerability in northern Foxe Basin, Canada. *Climate Research*, 38:137-154.
- Ford, J.D., T. Bell and D. St-Hilaire-Gravel, 2010a. Vulnerability of community infrastructure to climate change in Nunavut: a case study from Arctic Bay. In: Hovelsrud and Smit (Eds.). *Community Adaptation and Vulnerability in the Arctic Regions*, pp. 107-130, Springer.
- Ford, J.D., T. Pearce, F. Duerden, C. Furgal and B. Smit, 2010b. Climate change policy responses for Canada's Inuit population: The importance of and opportunities for adaptation. *Global Environmental Change*, 20:177-191.
- Forgione, M. and H. Martin, 2008. Now endangered, polar bears are a bigger draw in Churchill, Canada. *Los Angeles Times*. May 15, 2008.
- Furgal, C. and T.D. Prowse, 2008. Northern Canada. In: Lemmen, D.S., F.J. Warren, J. Lacroix and E. Bush (Eds.). *From Impacts to Adaptation: Canada in a Changing Climate 2008*, pp. 57-118, Government of Canada, Ottawa.
- Furgal, C. and J. Seguin, 2006. Climate change, health, and vulnerability in Canadian northern Aboriginal communities. *Environmental Health Perspectives*, 114:1964-1970.
- Füssel, H.M., 2007. Adaptation planning for climate change: concepts, assessment approaches, and key lessons. *Sustainability Science*, 2:265-275.
- Gautier, D.L., K.J. Bird, R.R. Charpentier, A. Grantz, D.W. Houseknecht, T.R. Klett, T.E. Moore, J.K. Pitman, C.J. Schenk, J.H. Schuenemeyer, K. Sorensen, M.E. Tennyson, Z.C. Valin and C.J. Wandrey, 2009. Assessment of undiscovered oil and gas in the Arctic. *Science*, 324:1175-1179.
- Gearheard, S., W. Matumeak, I. Angutikjuaq, J. Maslanik, H.P. Huntington, J. Leavitt, D.M. Kagak, G. Tigullaraq and R.G. Barry, 2006. «It's not that simple»: A collaborative comparison of sea ice environments, their uses, observed changes, and adaptations in barrow, Alaska, USA, and Clyde River, Nunavut, Canada. *Ambio*, 35:203-211.
- Geertsema, M. and J.J. Clague, 2005. Jökulhlaups at Tulsequah Glacier, northwestern British Columbia, Canada. *The Holocene*, 15:310-316.
- Glomsrød, S., I. Mäenpää, L. Lindholt, H. McDonald and S. Goldsmith, 2009. Arctic economies within the Arctic nations. In: Glomsrød, S. and I. Aslaksen (Eds.). *The Economy of the North 2008*. pp. 37-68. Statistics Norway.
- Gode, J., J. Axelsson, S. Eriksson, K. Holmgren, G. Hovsenius, E. Kjellström, P. Larsson, L. Lundström and G. Persson, 2007. Tänkbara konsekvenser för energisektorn av klimatförändringar - Effekter, sårbarhet, anpassning. [in Swedish with an English summary]. (Possible consequences of climate change on the energy sector - effects, vulnerability and adaptation). *Elforsk rapport*. 07:112 pp.
- Goldhar, C. and J. Ford, 2010. Climate change vulnerability and food security in Qeqertarsuaq, Greenland. In: Hovelsrud, G.K. and B. Smit (Eds.). *Community Adaptation and Vulnerability in the Arctic Regions*, pp. 263-283, Springer.
- Goldhar, C., J.D. Ford and L. Berrang-Ford, 2010. Prevalence of food insecurity in a Greenlandic community and the importance of social, economic and environmental stressors. *International Journal of Circumpolar Health*, 69:285-303.
- Gregor, D.J. and W.D. Gummer, 1989. Evidence of atmospheric transport and deposition of organochlorine pesticides and polychlorinated biphenyls in Canadian Arctic snow. *Environmental Science and Technology*, 23:561-565.
- Grønlund, A., 2009. Virkning av klimaendring på arealbruk i norsk arktis. [in Norwegian]. *Bioforsk Rapport*. 4:16 pp. Norsk Polarinstitutt / Bioforsk, Tromsø, Norway.
- Hamilton, J.M., D.J. Maddison and R.S.J. Tol, 2005. Effects of climate change on international tourism. *Climate Research*, 29:245-254.
- Hanesiak, J., R. Stewart, P. Taylor and 26 others, 2010. Storm studies in the Arctic (STAR). *Bulletin of the American Meteorological Society*, 91:47-68.
- Hansen, K.M., J.H. Christensen, J. Brandt, L.M. Frohn, C. Geels, C.A. Skjøth and G.B. Hedegaard, 2008. Overview of POPs in the environment:

- Modeling their distribution and spread. In: Barnes, I. and M.M. Kharytonov (Eds.). Proceedings of the NATO Advanced Research Workshop on Simulation and Assessment of Chemical Processes in a Multiphase Environment. Alushta, Ukraine. 1 September 2007.
- Hegg, D.A., S.G. Warren, T.C. Grenfell, S.J. Doherty, T.V. Larson and A.D. Clarke, 2009. Source attribution of black carbon in arctic snow. *Environmental Science and Technology*, 43:4016–4021.
- Heliövaara, K. and M. Peltonen, 1999. Bark beetles in a changing environment. *Ecological Bulletins*, 47:48–53.
- Helle, T. and I. Kojola, 2008. Demographics in an alpine reindeer herd: effects of density and winter weather. *Ecography*, 31:221–230.
- Hermanson, M.H., E.H. Isaksson, C. Teixeira, D.C.G. Muir, K.M. Compther, Y.F. Li, I. Igarashi and K. Kamiyama, 2005. Current-use and legacy pesticide history in the Austfonna ice cap, Svalbard, Norway. *Environmental Science and Technology*, 39:8163–8169.
- Ho, J., 2010. The implications of Arctic sea ice decline on shipping. *Marine Policy*, 34:713–715.
- Houle, G. and L. Filion, 2003. The effects of lichens on white spruce seedling establishment and juvenile growth in a spruce-lichen woodland of subarctic Quebec. *Ecoscience*, 10:80–84.
- Hovelsrud, G.K., 1999. Contemporary seal hunting households: Trade bans and subsidies. In: Tannenbaum, N. and D. Small (Eds.). *At the Interface: The Household and Beyond*. University Press of America.
- Hovelsrud, G.K. and B. Smit (Eds.), 2010. *Community Adaptation and Vulnerability in the Arctic Regions*. 353 pp. Springer.
- Hovelsrud, G.K. and C. Winsnes, 2006. *User Knowledge and Scientific Knowledge in Management Decision Making*. The North Atlantic Marine Mammal Commission, Reykjavik, Iceland, 4–7 January 2003.
- Hovelsrud, G.K., M. McKenna and H.P. Huntington, 2008. Marine mammal harvests and other interactions with humans. *Ecological Applications*, 18:S135–S147.
- Hovelsrud, G.K., H. Dannevig, J.J. West and H. Amundsen, 2010a. Adaptation in fisheries and municipalities: Three communities in northern Norway. In: Hovelsrud, G.K. and B. Smit (Eds.). *Community Adaptation and Vulnerability in the Arctic Regions*, pp. 23–62, Springer.
- Hovelsrud, G.K., J. White, M. Andrachuk and B. Smit, 2010b. Community adaptation and vulnerability integrated. In: Hovelsrud, G.K. and B. Smit (Eds.). *Community Adaptation and Vulnerability in the Arctic Regions*, pp. 335–348, Springer Publishers.
- Huebert, R. and B. Yeager, 2008. *A New Sea: The need for a regional agreement on management and conservation of the arctic marine environment*. WWF International Arctic Programme. 46 pp. Oslo, Norway.
- Huntington, H.P., J.M. Mosli and V.B. Shustov, 1998. Peoples of the Arctic: Characteristics of human populations relevant to pollution issues. In: AMAP Assessment Report: Arctic Pollution Issues. Arctic Monitoring and Assessment Programme, pp. 141–182.
- Huntington, H.P., M. Boyle, G.E. Flowers, J.W. Weatherly, L.C. Hamilton, L. Hinzman, C. Gerlach, R. Zulueta, C. Nicolson and J. Overpeck, 2007a. The influence of human activity in the Arctic on climate and climate impacts. *Climatic Change*, 82:77–92.
- Huntington, H.P., L.C. Hamilton, C. Nicolson, R. Brunner, A. Lynch, A.E.J. Ogilvie and A. Voinov, 2007b. Toward understanding the human dimensions of the rapidly changing arctic system: insights and approaches from five HARC projects. *Regional Environmental Change*, 7:173–186.
- Ilulissat Declaration, 2008. Arctic Ocean Conference Ilulissat, Greenland, 27–29 May 2008. Danish Ministry for Foreign Affairs.
- IMO, 2009. Guidelines for ships operating in polar waters. Adopted on the 26th IMO Assembly, 23 November – 2 December 2009. International Maritime Organization.
- Instanes, A., O. Anisimov, L. Brigham, D. Goering, L.N. Khrustalev, B. Ladanyi and J.O. Larsen, 2005. Infrastructure: buildings, support systems, and industrial facilities. In: Arctic Climate Impact Assessment, pp. 907–944, Cambridge University Press.
- IPCC, 2007. *Climate Change 2007 - Impacts, Adaptation and Vulnerability*. Working Group II Contribution to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change. Cambridge University Press.
- Jetté-Nantel, S. and S. Agrawala, 2007. Climate change impacts and adaptation in hazards management. In: Agrawala, S. (Ed.). *Adaptation in the European Alps. Adapting Winter tourism and natural hazard management*, Organization for Economic Co-operation and Development, OECD Publishing.
- Jochem, E. and W. Schade, 2009. *Adaptation and Mitigation Strategies Supporting European Climate Policy*. ADAM Deliverable D-M1.2, Fraunhofer Institute for Systems and Innovation Research, Munich.
- Johannessen, O.M. and L.H. Pettersson, 2008. Arctic climate and shipping in Gottenmoeller. In: Tamnes, R. (Ed.). *High North, High Stakes: Security, Energy, Transport, Environment*, pp. 95–114, Fagbokforlaget, Norway.
- Johnson, K., S. Solomon, D. Berry and P. Graham, 2003. Erosion progression and adaptation strategy in a northern coastal community. In: Phillips, M., S.M. Springman and L.U. Arenson (Eds.). *Proceedings of the 8th International Conference on Permafrost*, pp. 489–494. July 20–25, 2003, Zurich, Switzerland..
- Johnston, M.E., 2006. Impacts of global environmental change on tourism in the polar regions. In: Gössling, S. and C.M. Hall (Eds.). *Tourism and Global Environmental Change, Ecological, Social, Economic and Political Interrelationships*, pp. 37–53, Routledge.
- Juday, G.P., V. Barber, P. Duffy, H. Linderholm, S. Rupp, S. Sparrow, E. Vaganow and J. Yarie, 2005. Forests, land management, and agriculture. In: *Arctic Climate Impact Assessment*, pp. 781–862.
- Kallenborn, R., J. Fick, R. Lindberg, M. Moe, K.M. Nielsen, M. Tysklind and T. Vasskog, 2008. Pharmaceutical residues in Northern European environments: consequences and perspectives. In: Kümmerer, K. (Ed.). *Pharmaceuticals in the Environment. Sources, Fate, Effects and Risk*, pp. 61–74, Springer.
- Karlsen, S.R., I. Solheim, P.S.A. Beck, K.A. Hogda, F.E. Wielgolaski and H. Tommervik, 2007. Variability of the start of the growing season in Fennoscandia, 1982–2002. *International Journal of Biometeorology*, 51:513–524.
- Keskitalo, E.C.H., 2008. Vulnerability and adaptive capacity in forestry in northern Europe: a Swedish case study. *Climatic Change*, 87:219–234.
- Keskitalo, C., 2010. Vulnerability and adaptive capacity in a multi-use forest municipality in northern Sweden. In: Hovelsrud, G.K. and B. Smit (Eds.). *Community Adaptation and Vulnerability in the Arctic Regions*, pp. 285–311, Springer.
- Keskitalo, E.C.H. and A.A. Kulyasova, 2009. The role of governance in community adaptation to climate change. *Polar Research*, 28:60–70.
- Kilpeläinen, A., H. Gregow, H. Strandman, S. Kellomäki, A. Venäläinen and H. Peltola, 2010. Impacts of climate change on the risk of snow-induced forest damage in Finland. *Climatic Change*, 99:193–209.
- Kofinas, G., 2005. Hunters and researchers at the co-management interface: Emergent dilemmas and the problem of legitimacy. *Anthropologica*, 47:179–196.
- Kofinas, G., S. Herman and C. Meek, 2007. Novel problems require novel solutions: Innovation as an outcome of adaptive co-management. In: Armitage, D., F. Berkes and N. Doubleday (Eds.). *Adaptive Co-Management: Collaboration, Learning and Multi-Level Governance*, pp. 249–267.
- Kolstad, E.W. and T.J. Bracegirdle, 2008. Marine cold-air outbreaks in the future: an assessment of IPCC AR4 model results for the Northern Hemisphere. *Climate Dynamics*, 30:871–885.
- Kovacs, A. and D.S. Sodhi, 1980. Shore ice pile-up and ride-up: field observations, models, theoretical analyses. *Cold Regions Science and Technology*, 2:209–288.
- Kraemer, L.D., J. Berner and C.M. Furgal, 2005. Potential impact of climate on human exposure to contaminants in the Arctic. *International Journal of Circumpolar Health*, 64:498–508.
- Krieg, T., D.L. Holen and D. Koster, 2009. Subsistence harvests and uses of wild resources in Igiugig, Kokhanok, Koliganek, Levelock, and New Stuyahok, Alaska, 2005. Division of Subsistence, Alaska Department of Fish and Game, Technical Paper No. 322.
- Krupnik, I. and D. Jolly, 2002. The earth is faster now: indigenous observations of Arctic environmental change. *Frontiers in Polar Social Science*. Arctic Research Consortium of the United States, Fairbanks, Alaska.
- Krupnik, I., C. Aporta, S. Gearheard, G.J. Laidler and L. Kielsen-Holm (Eds.), 2010. *SIKU: Knowing Our Ice: Documenting Inuit Sea Ice Knowledge and Use*. 479 pp. Springer.
- Kruse, J., B. Poppel, L. Abrytina, G. Duhaime, S. Martin, M. Poppel, M. Kruse, E. Ward, P. Cochran, V. Hanna, V. Møller, D. Huschka and A. Michalos, 2008. Survey of living conditions in the Arctic. In: Møller, V., D. Huschka and A.C. Michalos (Eds.). *Barometers of Quality of Life Around the Globe: How Are We Doing?*, pp. 107–134, Springer Verlag.
- Kumpula, J. and A. Colpaert, 2003. Effects of weather and snow conditions on reproduction and survival of semi-domesticated reindeer (*Rangifer*

- tarandus tarandus*). Polar Research, 22:225-233.
- Kumpula, J. and A. Colpaert, 2007. Snow conditions and usability value of pasture land for semi-domesticated reindeer (*Rangifer tarandus tarandus*) in northern boreal forest area. Rangifer, 27:25-39.
- Laidler, G.J., 2006. Inuit and scientific perspectives on the relationship between sea ice and climate change: The ideal complement? Climatic Change, 78:407-444.
- Laidler, G. and P. Elee, 2006. Sea ice processes and change: exposure and risk in Cape Dorset, Nunavut. In: Riewe, R. and J. Oakes (Eds.). Climate Change: Linking Traditional and Scientific Knowledge, pp. 155-175, Aboriginal Issues Press.
- Laidler, G.J., J.D. Ford, W.A. Gough, T. Ikummaq, A.S. Gagnon, S. Kowal, K. Qrunnut and C. Irngaut, 2009. Travelling and hunting in a changing Arctic: assessing Inuit vulnerability to sea ice change in Igloolik, Nunavut. Climatic Change, 94:363-397.
- Laidre, K.L., I. Stirling, L.F. Lowry, O. Wiig, M.P. Heide-Jorgensen and S.H. Ferguson, 2008. Quantifying the sensitivity of arctic marine mammals to climate-induced habitat change. Ecological Applications, 18:S97-S125.
- Lemelin, R.H., 2005. Wildlife tourism at the edge of chaos: Complex interactions between humans and polar bears in Churchill, Manitoba. In: Berkes, F., R. Huebert, F.H., M. Manseau and A. Diduck (Eds.). Breaking Ice: Renewable Resources and Ocean Management in the Canadian North, pp. 183-202, University of Calgary Press.
- Lie, I., J.Å. Riseth and B. Holst, 2008. Samisk reindrift i et skiftende klimabilde. Historiske erfaringer og tilpasninger, og framtidige konsekvenser av klimaendringer for reindrift i Norge. [in Norwegian with an English summary]. Norut Alta Rapport 6:123 pp. Alta, Norway.
- Lindholt, L., 2006. Arctic natural resources in a global perspective. In: Glomsrød, S. and I. Aslaksen (Eds.). The Economy of the North, pp. 27-37, Statistics Norway, Oslo, Norway.
- Lindner, M., M. Maroschek, S. Netherer, A. Kremer, A. Barbati, J. Garcia-Gonzalo, R. Seidl, S. Delzon, P. Corona, M. Kolstrom, M.J. Lexer and M. Marchetti, 2010. Climate change impacts, adaptive capacity, and vulnerability of European forest ecosystems. Forest Ecology and Management, 259:698-709.
- Loeng, H., 2008. Klimaendringer i Barentshavet - Konsekvenser av økte CO₂-nivåer i atmosfæren og havet. [In Norwegian]. Report No. 126, Norsk Polarinstitutt, 32 pp.
- Loeng, H., K. Brander, E. Carmack, S. Denisenko, K. Drinkwater, B. Hansen, K. Kovacs, L. P., M. F. and E. Sakshaug, 2005. Marine systems. In: Arctic Climate Impacts Assessment, pp. 453-538, Cambridge University Press.
- Loneragan, S., R. Difrancesco and M.K. Woo, 1993. Climate change and transportation in northern Canada: An integrated impact assessment. Climatic Change, 24:331-351.
- Lovecraft, A.L. and H. Eicken, 2009. The sea ice system services framework: Development and application. In: Eicken, H., R. Gradinger, M. Salganek, K. Shrasawa, D. Perovich and M. Lepparanta (Eds.). Handbook on Field Techniques in Sea-ice Research: A Sea-ice System Services Approach. University of Alaska Press.
- Macdonald, R.W., T. Harner and J. Fy, 2005. Recent climate change in the Arctic and its impact on contaminant pathways and interpretation of temporal trend data. Science of the Total Environment, 342:5-86.
- Mäenpää, I., 2009. Comparative analysis of Arctic economies at macro level. In: Glomsrød, S. and I. Aslaksen (Eds.). The Economy of the North 2008, pp. 26-34, Statistics Norway, Oslo, Norway.
- Magga, O.H., 2006. Diversity in Saami terminology for reindeer, snow, and ice. International Social Science Journal, 58:25-34.
- Martin, P.D., J.L. Jenkins, F.J. Adams, M.T. Jorgenson, A.C. Matz, D.C. Payer, P.S. Reynolds, A.C. Tidwell and J.R. Zelen, 2009. Wildlife Response to Environmental Arctic Change. In: Report of the Wildlife Response to Environmental Arctic Change (WildREACH): Predicting Future Habitats of Arctic Alaska Workshop, 17-18 November 2008. 138 pp. U.S. Fish and Wildlife Service, Fairbanks, Alaska.
- Meltofte, H., T.R. Christensen, B. Elberling, M.C. Forchhammer and M. Rasch (Eds.), 2008. High-Arctic Ecosystem Dynamics in a Changing Climate. 563 pp. Academic Press.
- Moen, J., 2008. Climate change: Effects on the ecological basis for reindeer husbandry in Sweden. Ambio, 37:304-311.
- Molenaar, E.J. and R. Corell, 2009. Arctic Shipping. Background paper. 33 pp. The Heinz Center, Washington, DC.
- Montanarella, L., 2007. Trends in land degradation in Europe. In: Sivakumar, M.V.K. and N. Ndegwa (Eds.). Climate and Land Degradation, pp. 83-104, Springer.
- Moore, S.E. and H.P. Huntington, 2008. Arctic marine mammals and climate change: Impacts and resilience. Ecological Applications, 18:S157-S165.
- Mueter, F.J. and M.A. Litzow, 2008. Sea ice retreat alters the biogeography of the Bering Sea continental shelf. Ecological Applications, 18:309-320.
- Næss, L.O., G. Bang, S. Eriksen and J. Vevatne, 2005. Institutional adaptation to climate change: Flood responses at the municipal level in Norway. Global Environmental Change, 15:125-138.
- Naviq and AMEC, 2007. Monograph on the Norman Wells Pipeline Geotechnical Design and Performance-2006 Update. Geological Survey of Canada Open File. 214 pp. Naviq Consulting Inc. and AMEC Earth & Environmental.
- Nelson, F.E., O.A. Anisimov and N.I. Shiklomanov, 2002. Climate change and hazard zonation in the circum-Arctic permafrost regions. Natural Hazards, 26:203-225.
- Newark, M.J., L.E. Welsh, R.J. Morris and W.V. Dnes, 1989. Revised ground snow loads for the 1990 National Building Code of Canada. Canadian Journal of Civil Engineering, 16:267-278.
- Nickels, S., C. Furgal, M. Buell and H. Moquin, 2005. Unikkaarqatigiit - Putting the human face on climate change: Perspectives from Inuit of Canada. 129 pp. Joint publication of Inuit Tapiriit Kanatami, Nasivik Centre for Inuit Health and Changing Environments at Université Laval and the Ajunnginiq Centre at the National Aboriginal Health organization, Ottawa, Canada.
- Notzke, C., 1999. Indigenous tourism development in the Arctic. Annals of Tourism Research, 26:55-76.
- Nuttall, M., F. Berkes, B. Forbes, G. Kofinas, T. Vlassova and G. Wenzel, 2005. Hunting, herding, fishing, and gathering: Indigenous peoples and renewable resource use in the Arctic. In: Arctic Climate Impact Assessment, pp. 649-690, Cambridge University Press.
- Nymand Larsen, J., P. Schweitzer and G. Fondahl, 2010. Arctic Social Indicators: A follow-up to the AHDR. Nordic Council of Ministers. TemaNord 2010:519.
- O'Brien, K., S. Eriksen, L. Sygna and L.O. Naess, 2006. Questioning complacency: Climate change impacts, vulnerability, and adaptation in Norway. Ambio, 35:50-56.
- Occhipinti-Ambrogio, A., 2007. Global change and marine communities: Alien species and climate change. Marine Pollution Bulletin, 55:342-352.
- Oozeva, C., C. Noongwook, G. Noongwook, C. Alowa and I. Krupnik, 2004. Watching ice and weather our way: Sikumengllu eslamengllu esghapallegput. 207 pp. Arctic Studies Center, Smithsonian Institution, and Savoonga Whaling Captains Association, Washington, DC and Savoonga, Alaska.
- OPRC, 1990. International Convention on Oil Pollution Preparedness, Response and Co-operation. Adoption: 30 November 1990. Entry into force: 13 May 1995. www.imo.org/About/Conventions/ListOfConventions/Pages/International-Convention-on-Oil-Pollution-Preparedness,-Response-and-Co-operation-%28OPRC%29.aspx Accessed: October 27, 2010.
- Øseth, E., 2010. Klimaendringer i norsk Arktis - Konsekvenser for livet i nord. [in Norwegian]. Norsk Polarinstitutt Rapportserie. 136:134 pp. Norwegian Polar Institute, Tromsø, Norway.
- Outridge, P.M., R.W. Macdonald, F. Wang, G.A. Stern and A.P. Dastoor, 2008. A mass balance inventory of mercury in the Arctic Ocean. Environmental Chemistry, 5:89-111.
- Øygarden, L., 2003. Rill and gully development during an extreme winter runoff event in Norway. Catena, 50:217-242.
- Pagnan, J., 2003. The impact of climate change on Arctic tourism- a preliminary review. Paper presented at 'Climate Change and Tourism'. April 9-11, 2003 Djerba, Tunisia.
- Parkinson, A.J., 2008. The International Polar Year, 2007-2008, an opportunity to focus on infectious diseases in Arctic regions. Emerging Infectious Diseases, 14:1-3.
- Parkinson, A.J. and J.C. Butler, 2005. Potential impact of climate change on infectious diseases in the Arctic. International Journal of Circumpolar Health, 64:475-486.
- Parkinson, A.J. and B. Evengård, 2009. Climate change, its impact on human health in the Arctic and the public health response to threats of emerging infectious diseases. Global Health Action, 2:3.
- Pearce, T., B. Smit, F. Duerden, J.D. Ford, A. Goose and F. Kataoyak, 2010. Inuit vulnerability and adaptive capacity to climate change in

- Ulukhaktok, Northwest Territories, Canada. *Polar Record*, 46:157-177.
- Penning-Rowsell, E., C. Johnson and S. Tunstall, 2006. 'Signals' from pre-crisis discourse: Lessons from UK flooding for global environmental policy change? *Global Environmental Change*, 16:323-339.
- Perovich, D.K. and J.A. Richter-Menge, 2009. Loss of sea ice in the Arctic. *Annual Review of Marine Science*, 1:417-441.
- Petersen, L.R. and J.T. Roehrig, 2001. West Nile virus: A reemerging global pathogen. *Emerging Infectious Diseases*, 7:611-614.
- Pinglot, J.F., M. Pourchet, B. Lefauconnier, J.O. Hagen, E. Isaksson, R. Vaikmaa and K. Kamiyama, 1999. Accumulation in Svalbard glaciers deduced from ice cores with nuclear tests and Chernobyl reference layers. *Polar Research*, 18:315-321.
- Poppel, B., 2006. Interdependency of subsistence and market economies in the Arctic. In: Glomsrød, S. and I. Aslaksen (Eds.). *The Economy of the North*, pp. 65-80, Statistics Norway, Oslo, Norway.
- Poppel, M., 2010. Kvinder og velfærd i Grønland. [in Danish]. In: Raffnsdóttir, G.L. (Ed.). *Kvinder og Velfærd i Vestnorden*, pp. 39-68, Nordisk Ministerråd, Copenhagen, Denmark.
- Poppel, B. and J. Kruse, 2009. The importance of a mixed cash and harvest herding based economy to living in the Arctic: an analysis based on Survey of Living Conditions in the Arctic (SLiCA). In: Muller, V. and D. Huscka (Eds.). *Quality of Life in the New Millennium: Advances in the Quality-of-Life Studies, Theory and Research*, pp. 27-42, Springer Verlag.
- Poppel, B., J. Kruse, G. Duhaime and L. Abryutina, 2007. SLiCA Results. Institute of Social and Economic Research, University of Alaska.
- Prowse, T.D., F.J. Wrona and G. Power, 2004. Dams, reservoirs and flow regulation. In: *Threats to Water Availability in Canada*. NWRI Scientific Assessment Report, pp. 9-18, National Water Research Institute, Environment Canada.
- Prowse, T.D., C. Furgal, R. Chouinard, H. Melling, D. Milburn and S.L. Smith, 2009. Implications of climate change for economic development in northern Canada: Energy, resource, and transportation sectors. *Ambio*, 38:272-281.
- Pruitt Jr., W.O., 1984. Snow and living things. In: Olson, R., F. Geddes and R. Hastings (Eds.). *Northern Ecology and Resource Management*, pp. 51-57, University of Alberta Press.
- Putkonen, J. and G. Roe, 2003. Rain-on-snow events impact soil temperatures and affect ungulate survival. *Geophysical Research Letters*, 30:1188.
- Ramanathan, V. and G. Carmichael, 2008. Global and regional climate changes due to black carbon. *Nature Geoscience*, 1:221-227.
- Rasmussen, R.O., 2005a. Analyse af fangerhvervet i Grønland. [in Danish]. 158 pp. Grønland Hjemmestyre, Direktoratet for Fangst af Fiskeri, Nuuk, Greenland.
- Rasmussen, R.O., 2005b. Adjustment to reality - Social response to climate changes in Greenland. In: Ørbæk, J.B., R. Kallenborn, I. Tombre, E.N. Hegseth, S. Falk-Petersen and A.H. Hoel (Eds.). *Arctic Alpine Ecosystems and People in a Changing Environment*, pp. 167-180, Springer.
- Rauhut, D., R. Rasmussen, J. Roto, P. Francke and S. Östberg, 2008. The Demographic Challenge to the Nordic Countries. Nordregio WP. 1:154 pp. Nordregio, Stockholm, Sweden.
- Reinert, E.S., J. Aslaksen, I.M.G. Eira, S.D. Mathiesen, H. Reinert and E.I. Turi, 2008. Adapting to climate change in reindeer herding: The nation-state as problem and solution. *Working Papers in Technology Governance and Economic Dynamics*. 16:40 pp.
- Richardson, G., M.R. Wadley, K.J. Heywood, D.P. Stevens and H.T. Banks, 2005. Short-term climate response to a freshwater pulse in the Southern Ocean. *Geophysical Research Letters*, 32:L03702.
- Riedlinger, D. and F. Berkes, 2001. Contributions of traditional knowledge to understanding climate change in the Canadian Arctic. *Polar Record* 37:315-328.
- Riewe, R. and J. Oakes (Eds.), 2006. *Climate Change: Linking Traditional and Scientific Knowledge*. 289 pp. Aboriginal Issues Press.
- Riseth, J.Å., 2003. Sámi reindeer management in Norway: Modernization challenges and conflicting strategies. In: Jentoft, S., H. Minde and R. Nielsen (Eds.). *Indigenous Peoples: Resource Management and Global Rights*, pp. 229-247, Eburon, Delft, The Netherlands.
- Robards, M.D. and A.L. Lovcraft, 2010. Evaluating co-management for social-ecological fit: Indigenous priorities and agency mandates for Pacific walrus. *Policy Studies Journal*, 38:257-279.
- Romanovsky, V.E., S.L. Smith and H.H. Christiansen, 2010. Permafrost thermal state in the Polar northern hemisphere during the International Polar Year 2007-2009: a synthesis. *Permafrost and Periglacial Processes*, 21:106-116.
- Rothwell, D., 2009. Time for a new Arctic treaty. *The Circle*, 1:6-8.
- Roturier, S. and m. Roué, 2009. Of forest, snow and lichen: Sámi reindeer herders' knowledge of winter pastures in northern Sweden. *Forest Ecology and Management* 258:1960-1967.
- Rybråten, S. and G.K. Hovelsrud, 2010. Local effects of global climate change: Differential experiences of sheep farmers and reindeer herders in Unjárga/Nesseby, a coastal Sámi community in Northern Norway. In: Hovelsrud, G.K. and B. Smit (Eds.). *Community Adaptation and Vulnerability in the Arctic Regions*, pp. 313-334, Springer.
- Schmidt, N.M., C. Baittinger and M.C. Forchhammer, 2006. Reconstructing century-long snow regimes using estimates of high arctic *Salix arctica* radial growth. *Arctic, Antarctic and Alpine Research*, 38:257-262.
- Scott, D., B. Jones and J. Konopek, 2007. Implications of climate and environmental change for nature-based tourism in the Canadian Rocky Mountains: A case study of Waterton Lakes National Park. *Tourism Management*, 28:570-579.
- Seidlitz, D., 2009. Arctic technology development. Paper presented at the USA-Norway Arctic Petroleum Technology workshop, 21 January 2009, Tromsø, Norway.
- Sherman, K., I.M. Belkin, K.D. Friedland, J. O'Reilly and K. Hyde, 2009. Accelerated warming and emergent trends in fisheries biomass yields of the world's large marine ecosystems. *Ambio*, 38:215-224.
- Shindell, D. and G. Faluvegi, 2009. Climate response to regional radiative forcing during the twentieth century. *Nature Geoscience*, 2:294-300.
- Shindell, D.T., M. Chin, F. Dentener and 31 others, 2008. A multi-model assessment of pollution transport to the Arctic. *Atmospheric Chemistry and Physics*, 8:5353-5372.
- Smiraglia, C., C. Diolaiuti, M. Pelfini, M. Beld, M. Citterio, T. Camielli and C. D'Agata, 2008. Glacier changes and their impacts on mountain tourism. Two case studies from the Italian Alps. In: Orlove, B., E. Wiegandt and B.H. Luckman (Eds.). *Darkening Peaks. Glacier Retreat, Science and Society*, pp. 206-215, University of California Press.
- Smit, B. and O. Pilifosova, 2001. Adaptation to climate change in the context of sustainable development and equity. In: McCarthy, J.J., O.F. Canziani, N.A. Leary, D.J. Dokken and K.S. White (Eds.). *Climate Change 2001: Impacts, Adaptation, and Vulnerability. Contribution of Working Group II to the Third Assessment Report of the Intergovernmental Panel on Climate Change*, pp. 877-912, Cambridge University Press.
- Smit, B., G.K. Hovelsrud, J. Wandel and M. Andrachuk, 2010. Introduction to the CAVIAR project and framework. In: Hovelsrud, G.K. and B. Smit (Eds.). *Community Adaptation and Vulnerability in the Arctic Regions*, pp. 1-22, Springer.
- Snyder, J.M. and B. Stonehouse (Eds.), 2007. *Prospects for Polar tourism*. 123 pp. CAB International.
- Stammler, F., 2005. Reindeer nomads meet the market. Culture, property and globalisation at the 'end of the land'. 379 pp. Literatur Verlag, Berlin.
- Stenevik, E.K. and S. Sundby, 2007. Impacts of climate change on commercial fish stocks in Norwegian waters. *Marine Policy*, 31:19-31.
- Stern, N., 2006. The Economics of Climate Change: The Stern Review. 649 pp. Cambridge University Press.
- Stewart, E.J. and D.L. Draper, 2006a. Sustainable cruise tourism in arctic Canada: An integrated coastal management approach. *Tourism in Marine Environments*, 13:77-88.
- Stewart, E.J. and D.L. Draper, 2006b. Community responses to tourism development in Canada's North: Preliminary findings. In: Riewe, R. and J. Oakes (Eds.). *Climate Change: Linking Traditional and Scientific Knowledge*, pp. 245-256, Aboriginal Issues Press.
- Stewart, E.J. and D. Draper, 2008. The sinking of the MS Explorer: Implications for cruise tourism in Arctic Canada. *Arctic*, 61:224-228.
- Stewart, E.J., S.E.L. Howell, D. Draper, J. Yackel and A. Tivy, 2007. Sea ice in Canada's Arctic: Implications for cruise tourism. *Arctic*, 60:370-380.
- Stokke, O.S., 2009. Arctic environmental governance: Are new regimes needed? *The Circle*, 1:8-10.
- Stokke, O.S. and G. Honneland (Eds.), 2007. *International cooperation and Arctic governance: regime effectiveness and northern region building*. 196 pp. Routledge.
- Strasser, U., 2008. Snow loads in a changing climate: new risks? *Natural Hazards and Earth System Sciences*, 8:1-8.
- Sundby, S. and O. Nakken, 2008. Spatial shifts in spawning habitats of

- Arcto-Norwegian cod related to multidecadal climate oscillations and climate change. *ICES Journal of Marine Science*, 65:953–962.
- Sverdrup, O., 1904. *The New Land - Four Years in Arctic Regions*. 526 pp. Longmans Green, London
- Taylor, R.B., 1978. The occurrence of grounded ice ridges and shore ice piling along the northern coast of Somerset Island, NWT. *Arctic*, 31:133–149.
- Tholstrup, L. and R.O. Rasmussen, 2009. *Climate Change - and the North Atlantic*. 130 pp. Norden, Stockholm, Sweden.
- Tømmervik, H., B. Johansen, I. Tombre, D. Thannheiser, K.A. Høgda, E. Gaare and F.E. Wielgolaski, 2004. Vegetation changes in the Nordic mountain birch forest: The influence of grazing and climate change. *Arctic, Antarctic and Alpine Research*, 36:323–332.
- Tømmervik, H., B. Johansen, J.Å. Riseth, S.R. Karlsen, B. Solberg and K.A. Høgda, 2009. Above ground biomass changes in the mountain birch forests and mountain heaths of Finnmarksvidda, northern Norway, in the period 1957–2006. *Forest Ecology and Management*, 257:244–257.
- Torvanger, A.M., M. Twena and B. Romstad, 2004. *Climate Change Impacts on Agricultural Productivity in Norway*. CICERO Working Paper. 34 pp. Center for International Climate and Environmental Research, Oslo, Norway.
- Tremblay, M., C. Furgal, C. Larrivée, T. Annanack, P. Tookalook, M. Qiisik, E. Angiyou, N. Swappie, J.P. Savard and M. Barrett, 2008. Climate change in northern Quebec: Adaptation strategies from community-based research. *Arctic*, 61:27–34.
- Turner, B.L., R.E. Kasperson, P.A. Matson, J.J. McCarthy, R.W. Corell, L. Christensen, N. Eckley, J.X. Kasperson, A. Luers, M.L. Martello, C. Polsky, A. Pulsipher and A. Schiller, 2003. A framework for vulnerability analysis in sustainability science. *Proceedings of the National Academy of Sciences of the United States of America*, 100:8074–8079.
- Turunen, M., P. Soppela, H. Kinnunen, M.L. Sutinen and F. Martz, 2009. Does climate change influence the availability and quality of reindeer forage plants? *Polar Biology*, 32:813–832.
- Tyler, N.J.C., 2010. Climate, snow, ice, crashes, and declines in populations of reindeer and caribou (*Rangifer tarandus* L.). *Ecological Monographs*, 80:197–219.
- Tyler, N.J.C., J.M. Turi, M.A. Sundset, K.S. Bull, M.N. Sara, E. Reinert, N. Oskal, C. Nellemann, J.J. McCarthy, S.D. Mathiesen, M.L. Martello, O.H. Magga, G.K. Hovelsrud, I. Hanssen-Bauer, N.I. Eira, I.M.G. Eira and R.W. Corell, 2007. Saami reindeer pastoralism under climate change: Applying a generalized framework for vulnerability studies to a sub-arctic social-ecological system. *Global Environmental Change*, 17:191–206.
- UNEP, 2007. *Tourism in the Polar Regions. The Sustainability Challenge*. 68 pp. The International Ecotourism Society, Washington, DC.
- U.S. Arctic Research Commission Permafrost Task Force, 2003. *Climate Change, Permafrost, and Impacts on Civil Infrastructure*. Permafrost Task Force Report. Special Report 01-03:72 pp.
- U.S. National Research Council, 2008. *Potential impacts of climate change on U.S. transportation / Committee on Climate Change and U.S. Transportation, Transportation Research Board and Division on Earth and Life Studies, National Research Council of the National Academies*. Transportation Research Board Special Report. 298 pp.
- USGS, 2008. *Circum-Arctic Resource Appraisal: Estimates of Undiscovered Oil and Gas North of the Arctic Circle*. USGS Fact Sheet. 2008-3049:4 pp.
- VanderZwaag, D.L., A. Chircop, E. Franckx, H. Kindred, K. MacInnis, M. McConnell, A. McDonald, T.L. McDorman, S. Mills, T. Puthucherril, S. Rolston, P. Saunders and K.J. Spears, 2008. *Governance of Arctic Marine Shipping*. Project Report. PAME. 118 pp. Dalhousie University, Halifax, Canada.
- von Below, D. and T. Persson, 2008. *Uncertainty, Climate Change and the Global Economy*. NBER Working Paper No. 14426. U.S. National Bureau of Economic Research.
- Vuglinskly, V.S. and T.P. Gronskaia, 2006. Changing of rivers and lakes ice regime within the Russian territory and their possible consequences for economy. [in Russian]. *Modern Problems of Hydrometeorology*, pp. 229–245, Asterion, St. Petersburg, Russia.
- Walsh, J.E. and W.L. Chapman, 1998. Arctic cloud-radiation-temperature associations in observational data and atmospheric reanalyses. *Journal of Climate*, 11:3030–3045.
- Weatherhead, E., S. Gearhead and R.G. Barry, 2010. Changes in weather persistence: Insight from Inuit knowledge. *Global Environmental Change*, 20:523–528.
- Webb, J., S.G. Anthony, L. Brown, H. Lyons-Visser, C. Ross, B. Cottrill, P. Johnson and D. Scholefield, 2005. The impact of increasing the length of the cattle grazing season on emissions of ammonia and nitrous oxide and on nitrate leaching in England and Wales. *Agriculture Ecosystems and Environment*, 105:307–321.
- Wenzel, G.W., 2009. Canadian Inuit subsistence and ecological instability – if the climate changes, must the Inuit? *Polar Research*, 28:89–99.
- West, J. and G.K. Hovelsrud, 2010. Cross-scale adaptation challenges in the coastal fisheries: findings from Lebesby, Northern Norway. *Arctic*, 63:338–354.
- Wiig, Ø., J. Aars and E.W. Born, 2008. Effects of climate change on polar bears. *Science Progress*, 91:151–173.
- Wilson, K.J., J. Falkingham, H. Melling and R. De Abreau, 2004. Shipping in the Canadian Arctic, other possible climate change scenarios. Paper presented at the IGARSS International Geoscience and Remote Sensing Symposium, 20–24 September 2004, Anchorage, Alaska.
- Wisner, B., P. Blaikie, T. Cannon and I. Davis, 2004. *At Risk*. Second edition. 396 pp. Routledge.
- Wolf, B. and B. Orlove, 2008. Environment, history and culture as influences on perception of glacier dynamics: the case of Mt. Shasta. In: Orlove, B., E. Wiegandt and B.H. Luckman (Eds.). *Darkening Peaks. Glacier Retreat, Science, and Society*, pp. 3–19, University of California Press.
- Wolfe, R.J., 2000. *Subsistence in Alaska: A year 2000 Update*. Division of Subsistence, Alaska Department of Fish and Game.
- Woo, M., M. Mollinga and S.L. Smith, 2007. Climate warming and active layer thaw in the boreal and tundra environments of the Mackenzie Valley. *Canadian Journal of Earth Sciences*, 44:733–743.
- Young, O.R., 2005. Governing the Arctic: From cold war theater to mosaic of cooperation. *Global Governance*, 11:9–15.
- Young, O.R., 2009a. Whither the Arctic? Conflict or cooperation in the circumpolar north. *Polar Record*, 45:73–82.
- Young, O., 2009b. The Arctic in play: governance in a time of rapid change. *The International Journal of Marine and Coastal Law*, 24:423–442.

11. Cross-cutting Scientific Issues

SECTION 11.1

LEAD AUTHORS: TERRY V. CALLAGHAN, MARGARETA JOHANSSON, JEFFREY R. KEY, TERRY PROWSE

CONTRIBUTING AUTHORS: MARIA ANANICHEVA, ALEXANDER KLEPIKOV

SECTION 11.2

LEAD AUTHORS: DORTHE DAHL-JENSEN, KONRAD STEFFEN, MARTIN SHARP

CONTRIBUTING AUTHORS: ANTHONY ARENDT, REGINE HOCK

SECTION 11.3

LEAD AUTHORS: ROLAND KALLENBORN, ROBIE MACDONALD

CONTRIBUTING AUTHORS: CRISPIN HALSALL, JANET PAWLAK, TERRY BIDLEMAN

SECTION 11.4

LEAD AUTHOR: WARWICK F. VINCENT

CONTRIBUTING AUTHORS: TERRY V. CALLAGHAN, DORTHE DAHL-JENSEN, MARGARETA JOHANSSON, KIT M. KOVACS, CHRISTINE MICHEL, TERRY PROWSE, JAMES D. REIST, MARTIN SHARP

SECTION 11.5

LEAD AUTHOR: JEFFREY R. KEY

CONTRIBUTING AUTHORS: CARL EGEDE BØGGILD, MARTIN SHARP, DAQING YANG, ALEXANDER KLEPIKOV

Contents

Key Findings	2	11.4. Impacts of changing snow, water, ice and permafrost on Arctic ecosystems	27
11.1. Synthesis of feedbacks and interactions: From the cryosphere to the climate system – effects over various spatial and temporal scales	3	11.4.1. Introduction	27
Summary	3	11.4.2. Snow	27
11.1.1. Introduction	3	11.4.3. Water	29
11.1.2. Feedbacks	3	11.4.4. Ice	29
11.1.3. Synthesis	11	11.4.5. Permafrost	32
11.1.4. Uncertainties and recommendations	11	11.4.6. Conclusions	33
11.2. Sea-level change	14	11.5. Observational needs and knowledge gaps for the cryosphere	33
11.2.1. Introduction	14	Summary	33
11.2.2. Instrumental sea-level record	14	11.5.1. Introduction	34
11.2.3. The role of Arctic mountain glaciers and ice caps, and the Greenland Ice Sheet	15	11.5.2. Sea ice	36
11.2.4. Additional sources contributing to sea-level rise	16	11.5.3. The Greenland Ice Sheet	36
11.2.5. Projections into the future	17	11.5.4. Terrestrial snow	37
11.2.6. Impacts of sea-level rise	18	11.5.5. Permafrost and seasonally frozen ground	38
11.3. Contaminant pathways and change in the cryosphere	19	11.5.6. Glaciers and ice caps	38
Summary	19	11.5.7. Freshwater ice	39
11.3.1. Introduction	19	11.5.8. Solid precipitation	40
11.3.2. Impact of cryospheric change on contaminant pathways	20	11.5.9. Summary	41
11.3.3. Impact of cryospheric change on local sources of contaminants in the Arctic	25	Acknowledgments	42
11.3.4. Future research priorities	26	References	42
11.3.5. Future perspectives	26		
11.3.6. Conclusions	27		

This chapter presents an integrated assessment of cross-cutting scientific issues that affect multiple components of the cryosphere. These include assessments of feedback mechanisms and global sea-level rise; ways in which cryospheric change affects the transport and bioavailability of contaminants within the Arctic region; ways in which cryospheric change affects Arctic ecosystems; and systems available for observing changes in the Arctic cryosphere.

Key Findings

- In the Arctic cryosphere-climate system more feedbacks result in further warming than result in cooling or reduced rates of warming.
- The overall net effect of all the feedbacks on regional and global climate is difficult to assess because of the variability in the spatial and temporal scales over which the feedbacks operate.
- Arctic mountain glaciers, ice caps, and the Greenland Ice Sheet contributed over 40% of the global sea-level rise of around 3 mm per year observed between 2003 and 2008.
- In the future, global sea level is projected to rise by 0.9 to 1.6 m by 2100 (relative to the level in 2000) and Arctic ice loss will make a substantial contribution to this.
- Exposure of Arctic residents and top predators to contaminants released after many years from melting snow and ice and which accumulate in food chains, could further increase.
- Changes in the Arctic cryosphere cause fundamental changes to the characteristics of Arctic ecosystems and in some cases loss of entire habitats.
- Extreme climate events are likely to continue to have severe effects on many ecosystem types.
- There are large gaps in snow and ice observation networks and in knowledge of cryospheric processes. Closing these gaps will increase the potential for understanding, assessing, predicting, mitigating and adapting to climate change.

11.1. Synthesis of feedbacks and interactions: From the cryosphere to the climate system – effects over various spatial and temporal scales

Summary

Changes in Arctic climate are a result of complex interactions between the cryosphere, atmosphere, ocean and biosphere. The present assessment has substantiated and quantified many of the linkages, processes, interactions and feedbacks between the cryosphere and climate across a range of spatial and temporal scales revealing that:

- In the cryosphere–climate system more feedbacks are identified as positive and result in further warming than are identified as negative and result in cooling (or reduced rates of warming).
- Several positive feedbacks are finite: warming due to reduced albedo will no longer increase in areas that have totally lost snow or ice cover.
- Feedbacks operate at different spatial scales. Many of the feedbacks, such as those operating through albedo and evapotranspiration, will have significant local effects that together could result in a global impact. Some processes such as carbon dioxide (CO₂) emissions are likely to have very small global effects but uncertainty is high. Others, such as subsea methane (CH₄) emissions, could have large global effects.
- Some cryospheric processes in the Arctic have teleconnections with other regions, for example, the loss of sea ice north of Eurasia may result in a cooling effect over eastern Asia, and changes in snow cover affect atmospheric circulation. Conversely, major changes in the cryosphere have been largely a result of large-scale processes, particularly atmospheric and oceanic circulation.
- There are also interactions between the elements of the cryosphere acting through the atmosphere and ocean.
- The cryospheric components of the Arctic play a pivotal role in freshwater generation, its intra-Arctic storage, and routing to the North Atlantic where it can produce an important feedback to regional and global climate. With continued climate warming it is highly likely that the cryospheric components will play an increasingly important role.
- Terrestrial snow cover, sea ice and permafrost are involved in multiple temporal and spatial feedback regimes whereas land ice is involved in fewer feedbacks.
- The overall net effect of all the feedbacks is difficult to assess because of the variability in the spatial and temporal scales over which they operate.
- General circulation models (GCMs) do not include all major feedbacks, in part because they do not include all processes that lead to feedbacks (e.g., freshwater runoff from glaciers and ice sheets). Furthermore, the feedbacks may not be accurately parameterized in the models. The lack of full coupling between surface dynamics and the atmosphere is a major gap in current GCMs.

11.1.1. Introduction

Feedback processes are a phenomenon that has been known for more than a century. They are responses to a driving mechanism that subsequently accelerate (positive feedback) or retard (negative feedback) the original driving process. At the end of the 19th century, Arrhenius (Bolin, 2007) described the classic feedback whereby increased air temperature leads to an increase in the amount of water vapor in the atmosphere, which in turn leads to additional atmospheric warming. More recently, Curry et al. (1995) detailed the sea ice–albedo feedback mechanism, including snow cover, melt ponds, and leads. Overpeck et al. (2005) took a broader approach to the analysis of Arctic feedbacks by including all major components of Arctic climate: sea ice, permafrost, terrestrial ice, thermohaline circulation, terrestrial biomass, and marine primary production, as well as population and economic production. Francis et al. (2009) used a similar presentational approach to distil the system into its fundamental physical and human parts, document the key relationships between those parts, and identify the feedback loops. Both Overpeck et al. (2005) and Francis et al. (2009) examined the changes in feedback loops under the scenario of continued warming and a greatly reduced permanent sea-ice cover.

With the vast amount of recently published information on observed and projected trends in the cryosphere, there is a need to re-evaluate the feedbacks between the changing cryosphere and climate warming. There are many feedbacks from the cryosphere to the climate system: some are direct, but others are complex and indirect; for example, climate effects on the cryosphere that then affect ecosystems that in turn affect the climate system. Some of the complexity and variety of interactions between the atmosphere, ocean, and cryosphere is illustrated in Figure 11.1. Further complexity arises owing to scaling issues: individual feedbacks operate over different time scales and their effects can vary from local to global spatial scales. Furthermore, some feedbacks to climate warming are negative and result in reduced rates of climate warming or even cooling, while others are positive and lead to enhanced warming. Consequently, although some feedback mechanisms have been known for a long time, an overall assessment of the net effect of many different potential feedbacks on climate warming has not yet been achieved.

This section summarizes the feedbacks associated with a changing Arctic cryosphere presented elsewhere in this report, describes other feedbacks and interactions that span the various cryospheric components, and provides a preliminary assessment of their relative magnitudes. However, the calculation of the net effects of all feedbacks requires complex modeling that remains a priority for future research.

11.1.2. Feedbacks

11.1.2.1. Greenhouse gases

11.1.2.1.1. Carbon dioxide (land, freshwater, marine)

Carbon dioxide is a greenhouse gas with a radiative forcing of 1.66 W/m². The adjustment time of CO₂ in the atmosphere is approximately 100 years (Forster et al., 2007). It is exchanged between the atmosphere and the biosphere




Figure 11.1. Local, regional, and global feedbacks and processes related to changes in the Arctic cryosphere. The numbered yellow circles refer to impacts and processes: (1) Melting and retreating snow cover increases radiation absorption, a radiative feedback. (2) Melting of large ice sheets contributes to sea-level rise and the freshwater flux with potential effects on thermohaline circulation and global climate. (3) Retreating sea ice contributes to increased radiative absorption (ice-albedo feedback) and heat and moisture fluxes to the atmosphere, which impact cloud cover. (4) As permafrost degrades, CH₄ production may increase. With wetland drying, CO₂ emissions may increase, and the atmosphere warms over time. (5) Thawing permafrost changes geomorphic / geochemical processes and fluxes. (6) Increasing precipitation plus melting snow and ice increases river flow and changes the freshwater flux. (7) Shrinking lake-ice cover has ecological impacts generally leading to greater productivity but negatively impacting surface transport. (8) Changes in the magnitude and timing of snowmelt runoff and river-ice processes have both positive and negative impacts. (9) Retreating glaciers initially increase runoff but lower flows eventually result as ice masses diminish. (10) Changes in cloud cover affect the surface radiation budget, which impacts sea ice, in turn affecting cloud cover (cloud-radiation feedback). Source: after Prowse (2009).

through the processes of photosynthetic capture by green plants, short-term autotrophic respiration by plants, and long-term heterotrophic respiration of dead plant material by microbes. A mismatch, particularly in wet areas, between the rate of fixation of atmospheric CO_2 and its release from the biosphere has led to a net accumulation of carbon in the Arctic for thousands of years with considerable amounts preserved in permafrost (see Chapter 5). Around 44% of the world's near-surface labile soil carbon is found in Arctic soils (McGuire et al., 2009; see also references in Chapter 5), which is equivalent to about twice as much carbon as is currently present in the global atmosphere (Anisimov et al., 2007; McGuire et al., 2009; Tarnocai et al., 2009). This carbon store is sensitive to climate warming.

The major cryospheric controls on carbon *capture* from the atmosphere are the duration of the snow-free period that determines when photosynthesis can occur efficiently, the timing of the snow-free season (earlier snow melt allows plants to harvest high levels of solar radiation whereas solar angles are low and radiation is reduced at the end of the snow-free period; Callaghan et al., 2004a) and damage to vegetation from extreme winter warming events that thaw snow briefly in mid-winter (Bokhorst et al., 2009). Euskirchen et al. (2006) estimated increased carbon drawdown at about $9.5 \text{ gC/m}^2/\text{y}$ for each day that the growing season was projected to increase between 2001 and 2100. Recent analyses from visible satellite imagery of changes in snow-cover extent show that decreases are more marked in the spring period than in the period of snow-cover onset, and that in May–June there has been an average decrease of 18% over the 1966 to 2008 period, thereby extending the snow-free season (see Chapter 4).

The major cryospheric controls on carbon *release* from the soil are thawing permafrost (see Chapter 5) and soil warming during extreme events such as fire. Experimental warming of soils (Dorrepaal et al., 2009) and observations of areas that are experiencing different degrees of warming (Lee et al., 2009; Schuur et al., 2009; Vogel et al., 2009) show that the Arctic is already losing some of the carbon that has been stored for thousands of years. Extrapolations from measured carbon emission rates suggest that 4.5 to 6.0 kg/m^2 (or 9.5–13%) of the soil organic matter carbon pool could be lost on a century time scale (Schuur et al., 2009). Currently, widespread permafrost thawing throughout the Arctic has not been reported, although permafrost temperatures are generally rising. However, recent projections of permafrost temperatures show thawing to be widespread throughout the southern regions of the Arctic by 2090 (see Chapter 5).

Overall, models suggest that the Arctic will remain a weak sink of carbon during warming, mainly because of increased growth and extent of more productive vegetation in the future (Callaghan et al., 2004b; Sitch et al., 2007; McGuire et al., 2009). However, both current and future carbon sink activity can be reversed by short-term disturbances such as forest fires and insect pest outbreaks, during long-term changes. The long-term changes include thawing permafrost and altered hydrology related to permafrost dynamics (see Chapter 5) and changes in snow regime (see Chapter 4) that lead to drying and plant water stress. Also, the models exclude disturbance due to human activities such as deforestation at the treeline. Although the future feedback sign and strength status for CO_2 in the Arctic remain uncertain, it is likely that

century-long processes of negative feedbacks from increased CO_2 sequestration will be interspersed with episodic releases following disturbances. Some of these disturbances (such as forest fires) will also intensify the positive feedback arising from black carbon deposition on snow and ice through long-range transport on an annual time-scale.

The Arctic Ocean could be a significant sink for carbon as sea ice retreats and the ocean warms. Also, the oceans are sinks for carbon over geological time scales as dead organic matter accumulates in deep ocean sediments and carbonate in the shells of some plankton species becomes calcareous rocks. Currently, there can be mismatches between algal blooms at the retreating ice edge (now over the continental shelves) and the zooplankton and bacterio-plankton that feed on them: the algae that are not eaten fall onto the continental shelves and are available for the benthos (creatures living on the seabed) to feed on or form sediments. As the ice edge retreats away from the continental shelves during climate warming, more blooms could occur, which might lead to more organic material falling to the deeper ocean bed off the continental shelves and accumulating there. However, this negative feedback to climate warming might be moderated by ocean acidification. The pH of the ocean is currently decreasing as more CO_2 is drawn down from the atmosphere: the slightly more acidic conditions that result affect the species that use calcium to build cell walls causing less calcium to be deposited onto the ocean bed.

Freshwaters (lakes, ponds, rivers) feed back to the atmosphere through processes that occur in their immediate vicinity (e.g., carbon fluxes, albedo, evaporation) and downstream where the waters enter the Arctic Ocean (see Section 11.1.2.3). As temperatures rise, the number of days of ice cover decreases and more heat is absorbed by the open water which in turn increases CO_2 capture through the longer duration of primary production at higher rates. However, many northern lakes and ponds are already supersaturated with carbon and are net sources to the atmosphere (Jonsson et al., 2003). This source is likely to grow following increases in the supply of organic material from permafrost thawing and carbon transport to the lakes from enhanced terrestrial plant production, but will be determined by the balance between drying and water-logging of the land surface which is as yet unknown.

The processes and feedbacks described above are all biological in nature but physical and chemical processes within the sea ice itself have also been suggested to play a role. Anderson et al. (2004) and Rysgaard et al. (2009) found that levels of dissolved inorganic carbon increase with depth below the surface mixed layer of the Arctic Ocean. This is a result of enhanced air-sea exchange of CO_2 caused by sea-ice formation and the rapid transport of high salinity brine out of the surface layer. Similarly, Alekseev and Nagurny (2007) showed that the polar amplification of the annual cycle of CO_2 over the Arctic Ocean is connected to sea-ice growth, where the formation and growth of ice during the winter is accompanied by an increase of CO_2 in the sub-ice water layer and a CO_2 flux into the atmosphere. Model results showed that melting of sea ice exported from the Arctic Ocean into the East Greenland Current and the Nordic Seas increases the seasonal CO_2 uptake in the area by around 50%. Alekseev and Nagurny (2007) speculated that, overall, the Arctic Basin is more likely to be a source than a sink of CO_2 over an annual cycle.

11.1.2.1.2. Methane (wetlands, lakes, sub-sea)

In anaerobic soils, ponds and lakes of the Arctic, microbes produce CH_4 rather than CO_2 . Methane is 25 times more powerful than CO_2 as a greenhouse gas over a 100-year time frame with a radiative forcing of 0.48 W/m^2 (Forster et al., 2007), so any increases in CH_4 emissions will be particularly important. Unlike CO_2 , CH_4 is difficult to measure over large areas because there are geographical hotspots for CH_4 production and because there are episodic releases of CH_4 . For example, recent research (Mastepanov et al., 2008; see also Chapter 5) has shown large releases of CH_4 in the autumn from High Arctic permafrost areas in northeastern Greenland, and thaw lakes in Siberia are hotspots for CH_4 production (Walter et al., 2006, 2007a,b).

In addition, it is difficult to project future releases of CH_4 from land because wetlands on permafrost are drying in some areas (Smith et al., 2005; Riordan et al., 2006; Bunn et al. 2007; Goetz et al., 2007; see also Chapter 5), which would decrease current CH_4 emissions. Conversely, thermokarst pond formation is occurring elsewhere with concomitant increases in CH_4 emissions (Christensen et al., 2004; Ström and Christensen, 2007; Myers-Smith et al., 2008; see also Chapter 5). A relatively small source of CH_4 can result in positive radiative forcing even though most of a large area can be a net sink for carbon if vegetation is productive.

Particularly large sources of CH_4 occur in former soils that were inundated when sea levels rose after the last ice age. These areas are the vast continental shelves of the Arctic. Recent investigations in the Laptev Sea have shown high levels of CH_4 throughout the water column and extending up to 1800 m in the atmosphere (Shakhova et al., 2008a,b, 2010; Westbrook et al., 2009). Overall, a 1% release of CH_4 stored in subsea hydrates would be equivalent to a doubling of atmospheric CO_2 concentration in terms of its radiative effect. Although the uncertainties of the size of the subsea carbon reserves and their stability are great, the potential risk from CH_4 release, some of which is already being documented (Shakhova et al., 2008a,b, 2010), is sufficiently large to cause concern.

11.1.2.1.3. Nitrous oxide (tundra peatlands)

Very high emissions of the powerful greenhouse gas nitrous oxide (N_2O ; radiative forcing of 0.16 W/m^2 , Forster et al., 2007) have recently been discovered from peat circles in patterned ground of the discontinuous permafrost zone in Russia (Repo et al., 2009). These peat circles are widespread in certain regions. Elberling et al., (2010) also reported high N_2O emissions of 34 mg $\text{N/m}^2/\text{d}$ in cores taken from northeastern Greenland and incubated in the laboratory that are equivalent to daily N_2O emissions from tropical forests on a mean annual basis. These discoveries bring Arctic permafrost N_2O sources, previously thought of as of very little importance, to the agenda for global studies of N_2O dynamics and their impacts via feedbacks.

11.1.2.1.4. Water vapor

Water vapor is a greenhouse gas with a radiative forcing of 0.07 W/m^2 (stratospheric water vapor from CH_4 ; Forster et al., 2007). In the Arctic, it is transported from the surface to the atmosphere via evaporation from open water and wet surfaces, evapotranspiration from vegetation, and sublimation from snow (King et al., 2008) and ice. The feedback effects of the processes generating water vapor are complex in that evaporation leads to local cooling, but the increased atmospheric

concentrations of water vapor can lead to warming over a wider area because of mixing and transport of water vapor in the atmosphere (positive feedback). It is further complicated by the possibility of increased atmospheric water vapor enhancing cloud formation, which can have either a warming or cooling effect on the surface depending on the cloud height and time of year (Rouse et al., 1997, also discussed below). Assessing and comparing the local versus wider impacts of water vapor will require additional research.

Direct evaporation from melting snow and ice will decrease as the areas of glaciers, lake, pond and river ice, and the duration of ice and snow cover decrease over much of the Arctic (see Chapters 3, 4 and 5). Sublimation should increase initially as the temperature difference between snow and air increases.

Evapotranspiration is expected to increase in those areas of the Arctic where plant production increases, for example in response to a warmer, earlier and longer snow-free season (Euskirchen et al., 2006). Projections of increased forest growth and extent in the Barents region of the Russian Arctic show that by 2080 summer temperatures will have decreased by 1.5°C due to evaporative cooling (Göttel et al., 2008). Although this cooling is a local effect, the atmospheric mixing of the water vapor is likely to increase warming over larger geographical scales and other feedbacks are also associated with changes in vegetation, such as albedo.

11.1.2.1.5. Ozone and bromine

An important feature of Arctic atmospheric chemistry is the relationship between sea ice, bromine, and ozone. Releases of bromine gas species from the ocean can result in sudden ozone depletion in the lower troposphere during spring. One possible mechanism of bromine release is sea-salt aerosol production from snow lying on sea ice during blowing snow events. A reduction in Arctic sea ice would reduce the importance of this process in the chemistry of the Arctic atmosphere. In chemistry model simulations, Voulgarakis et al. (2009) found large spring ozone increases (up to 50–60%) over the Arctic, due mainly to a reduction in the impact of bromine chemistry, caused by sea-ice retreat. Tropospheric ozone has a relatively small radiative impact (warming), although the effect is greater over bright surfaces (Shindell et al., 2006). With a declining ice cover potentially giving rise to an increase in tropospheric ozone, the feedback would be positive. The impact of a shrinking sea-ice cover on polar stratospheric ozone was studied by Scinocca et al. (2009). They found that the stratospheric response is springtime polar cooling that is dynamical rather than radiative in origin. In the model simulations, the response lags the onset of the sea-ice loss by about a decade. It is associated with an enhanced weakening of the North Atlantic Meridional Overturning Circulation.

11.1.2.2. Transfer of heat and energy between the cryosphere, atmosphere, and ocean

11.1.2.2.1. Albedo

A continued and increased melt of mountain glaciers and ice caps, the Greenland Ice Sheet, and sea ice; an earlier melt of river and lake ice; and a decrease in snow cover will all impact on the Arctic radiation budget. Albedo, the fraction of the

incident sunlight that is reflected by the surface, will decrease and more solar radiation will be absorbed by the ground or open water. This will lead to additional warming. Furthermore, a decrease in albedo resulting from a decrease in snow cover over land may result in a further change in albedo through a change in the vegetation in response to surface warming (Chapin et al., 2005; Euskirchen et al., 2007, 2009). Permafrost thaw is also expected to lead to changes in albedo as areas dry out or become waterlogged. Indirectly, changes in surface albedo can modify large-scale circulation (Dethloff et al., 2006).

For the Arctic glaciers (including those in Greenland surrounding the ice sheet) projected volume loss ranges between 0.049 to 0.131 m sea-level equivalent (SLE), or 12–32% of their current volume by 2100 depending on the choice of GCM (Radić and Hock, 2010). In the Russian Arctic, there will be differences in the extent of glacial retreat between the Arctic continental climate systems of the mountains and Kamchatka. Any translation of losses of ice volume into decreased extent will reduce albedo due to increases of bare ground.

Projections of sea-ice extent show a continued and possibly accelerating decline, leading to an ice-free Arctic Ocean in summer within this century and possibly even within the next thirty years. The thinning of the ice pack, earlier melt onset, and increased open water will contribute to a reduction in albedo. While a variety of recent studies have demonstrated the importance of increased absorption of solar radiation resulting from less sea ice (and hence a lower albedo surface), some recent research suggests that the ice–albedo feedback is potentially less efficient than previously thought (Winton, 2006, 2008; Bitz, 2008; Graverson and Wang, 2009). For example, the annual sea-ice minimum is reached in September at a time when incoming solar radiation is already rather weak.

The albedo of terrestrial snow-covered surfaces in the Arctic is a major feedback to climate over a large area (Fernandes et al., 2009), and an important feedback to climate globally through atmospheric and oceanic teleconnections. Recent observations show a general decrease in snow-cover extent and duration that has led to decreases in albedo. Projections indicate increases in snow cover in some areas at the highest latitudes, strong decreases in the southern Arctic, and uncertainty in areas between. These changes will generally lead to an overall net reduction in the albedo feedback. Snow properties also affect albedo, for example, grain size, age of the snow cover, and the content of extraneous material such as black carbon from industrial pollution and biomass burning south of the Arctic. In fact, warming resulting from black carbon deposition on snow is equivalent to that resulting from a doubling of atmospheric CO₂ in Eurasia (Flanner et al., 2008; see also Chapter 4).

The reflective properties of snow are strongly modified by vegetation in many and complex ways (Pomeroy et al., 2006; Essery et al., 2008; see also Chapter 4). While snow typically absorbs around 10% of thermal radiation incident on it, black spruce *Picea mariana* can absorb 95% of thermal radiation leading to a significant positive feedback (Juday et al., 2005). The snow feedback will be decreased as vegetation height increases above the snow pack during the ongoing and projected process of shrub and tree range extensions into the Arctic (Sturm et al., 2001; Tape et al., 2006). Although increases in shrub advance in the Alaskan Arctic have not yet resulted in warming, it is predicted that an increase of shrubs could increase summer heating of the atmosphere by 3.7 W/m², which

is equivalent to a doubling of CO₂ or a 2% increase in the solar constant (Chapin et al., 2005). In the Barents region, changes in albedo through forest advance could increase temperatures by 1 °C in spring. This example should be compared with the cooling effect of increased evapotranspiration in summer and the expected cooling (not yet calculated) of the increased draw-down of atmospheric CO₂ giving an extra 2 to 17 kg C/m² by 2080. Together, these projections demonstrate the complexity of feedbacks arising from changes in vegetation: the feedbacks operate in different directions, through different mechanisms and over different periods of time.

11.1.2.2.2. Cloud feedbacks

The exact nature of the cloud radiation feedback in a warming climate is uncertain. Clouds both reflect solar radiation and absorb longwave (terrestrial) radiation, the magnitudes of which depend on cloud amount, height, particle phase and size, and thickness. Some satellite studies have shown that wintertime cloud amount in the Arctic appears to have been generally decreasing since the early 1980s, but springtime cloud amount has been increasing. While wintertime clouds in the Arctic have a warming effect, springtime cloud can have either a net warming or cooling effect. The overall radiative impact of these cloud cover changes on the surface is one of increased cooling. Therefore, changes in cloud cover may have actually suppressed Arctic warming to some degree (Wang and Key, 2003).

The influence of changes in cloud cover on sea-ice extent and *vice versa* is an important part of the feedback process, but has not been studied extensively until recently. On the time scale of a single season, changes in cloud amount may have minimal influence on summer sea-ice melt. The negative cloud anomaly (less than average cloud amount) and increased downwelling shortwave radiation flux from June through August 2007 did not appear to contribute substantially to the record ice extent minimum in September. On the other hand, there are clearly interdependencies between trends in cloud cover, surface temperature, and sea ice extent. Over the past few decades, more than 80% of the observed surface warming in the western Arctic Ocean during autumn is attributable to decreasing sea ice. Similarly, over 80% of the winter surface cooling in the central Arctic is a result of changes in cloud cover. In spring, only about half of the surface warming is a result of changes in cloud cover (Liu et al., 2009).

Satellite and reanalysis data have shown that sea-ice retreat is linked to a decrease in low-level cloud amount and an increase in mid-level clouds (Schweiger et al., 2008). This is in contrast to the common notion that a warming ocean surface will increase surface evaporation and lead to more low clouds. While surface evaporation does increase, near surface atmospheric instability increases, so cloud formation occurs in the mid-troposphere rather than nearer the surface. However, the radiative effect of these changes is relatively small, as the cloud radiative forcing changes are compensated for by changes in the lower tropospheric temperature and humidity structure. Because of the seasonal timing of this process, the response of cloud cover to sea-ice loss plays a minor role in regulating the summertime ice–albedo feedback. Its role in the cloud–ice feedback in autumn is potentially larger, although the ice–albedo feedback itself is weaker in autumn due to the

relatively low amount of solar radiation at very high latitudes (Kay and Gettleman, 2009).

Increasing temperatures and levels of ultraviolet (UV)-B radiation affect biological emissions from marine ecosystems (Zepp et al., 1995). The grazing of phytoplankton by zooplankton triggers the release of dimethyl sulfide (DMS), which is emitted to the atmosphere where it acts as condensation nuclei for water droplet formation. In other words, the release of DMS from the surface stimulates cloud formation. Furthermore, UV-B radiation converts some dissolved organic sulfur to carbonyl sulfide and warming of the ocean reduces its solubility, thereby releasing more to the atmosphere where more cloud nuclei are formed. The currently increasing presence of sea-ice leads during the summer melt in the Arctic Ocean increases the biological activity of the region. This may result in an accumulation of organic material, especially in the surface microlayer. Particulate organic matter, including microorganisms, small water-insoluble particles and microaggregates, can form a substantial part of the summer aerosol over the open leads in the central Arctic Ocean, thereby enhancing cloud formation (Matrai et al., 2008).

11.1.2.2.3. Atmospheric circulation

Overall, the atmosphere is a driver of change in the Arctic (Francis et al., 2009). It primarily forces rather than responds to changes in the cryosphere, a good example being changes in atmospheric wind patterns over the past decade that have contributed to recent reductions in summer Arctic sea-ice extent (Ogi et al., 2010). But the increase in late summer open water area has, in turn, directly contributed to a modification of large-scale atmospheric circulation patterns. With a reduction in sea-ice cover in late summer, additional heat that was stored in the ocean is then released to the atmosphere in autumn. The transfer of heat from the surface to the troposphere is more effective as the strength of the normally stable Arctic boundary layer is eroded (Overland and Wang, 2010). In years with reduced sea-ice cover the lower tropospheric thickness is greater. This has a large-scale impact, even into the northern mid-latitudes, as the pressure fields and therefore winds are directly related to the atmospheric thickness. Responses can be complex, as the loss of sea ice north of Eurasia may result in a cooling effect over eastern Asia.

There is also a relationship between snow cover and atmospheric circulation. Recent observational studies show that above-normal winter snow depth over European Russia and a corresponding below-normal snow depth over central Siberia – the east-west snow dipole – are associated with reduced Indian monsoon rainfall and above normal sea-surface temperatures (SSTs) over the eastern and central tropical Pacific Ocean during subsequent winters (Ye and Bao, 2001; Ueda et al., 2003; Peings and Douville, 2010). Similarly, below-normal winter snow depth over European Russia and a corresponding above-normal snow depth over central Siberia are associated with increased monsoon rainfall and below normal SSTs. Some GCMs also show this relationship, but the patterns may differ somewhat from the observations. Forcing from the Himalaya region dominates, where a delayed snowmelt leads to a reduction in surface sensible heating and consequently a weakened latitudinal temperature gradient. The result is less

Indian rainfall, particularly during the early part of the summer season.

The large-scale effect of changes in snow cover through the snow albedo feedback (SAF) has recently been examined. For example, Fletcher et al. (2009) demonstrated a non-local influence of SAF on the summertime circulation in the extratropical Northern Hemisphere. In models with stronger SAF, increased land surface warming is associated with large-scale sea-level pressure anomalies over the northern oceans and a poleward intensified subtropical jet. This would result in a change in heat and moisture fluxes into/out of the Arctic, although the feedback on snow cover and the impact on sea ice is not clear.

Accumulation and ablation on ice sheets, ice caps, and glaciers depend on the atmosphere circulation patterns, and atmospheric circulation is, in turn, affected by the presence of, and changes in, these features. Ice sheets and ice caps change the elevation and form of the Earth's surface. This changes the air temperature and deforms the atmospheric circulation, forming a 'wave shadow'. For this reason, the Icelandic Low exists throughout the entire year, with the Greenland Ice Sheet to the west, as opposed to the Aleutian Low, which disappears in summer. Smaller ice caps influence the atmosphere on smaller scales. Due to the cooling effect of the Greenland Ice Sheet, the air temperature drops as much as 5 to 10 °C in the atmospheric layer several hundred meters above it. Over the ice caps (Franz Josef Land, Svalbard, Novaya Zemlya, Severnaya Zemlya) and large mountain glaciers, the cooling is about 2 to 3 °C and spreads upward to 200 to 250 m. This may affect the cyclone trajectories ('storm tracks') and the life cycle of pressure systems (Krenke, 1982). Katabatic winds over the glacier surface have an impact on near surface atmospheric circulation. The intensity of such processes depends on changes in glacier size.

Changes in the patterns of atmospheric circulation due to glacier and ice cap retreat and/or disappearance may change the accumulation and ablation rates on the glaciers. For example, more cyclones in winter leads to more accumulation; more anticyclones in summer leads to more ablation. However, the consequences are currently unknown.

Recent modeling by Lunt et al. (2004) supports the influence of the Greenland Ice Sheet on atmospheric circulation. In their study, the conceptual removal of the Greenland Ice Sheet results in an increase in atmospheric thickness (geopotential height) in that region. The region of cooling in the Barents Sea in December, January and February is most intense at the surface and is associated with substantial growth of the sea ice throughout the year. The cooling appears to be forced from above by the atmosphere, and amplified by the sea ice-albedo effect. The cooling appears to be linked with enhanced equatorward flow east of Greenland, associated with the increased geopotential height over Greenland, which brings cold air from the pole equatorward over the Barents Sea. In addition to changes in the stationary waves in the atmosphere, the conceptual removal of Greenland also affects the transient behavior of the atmosphere. In the no-Greenland case, the intensity of the North Atlantic winter storm tracks is decreased. Associated with this is a corresponding decrease in large-scale precipitation. The decrease in storm track activity is likely to be related to the fact that in the no-Greenland case, the meridional

temperature gradient is decreased over the North Atlantic.

A retreating sea-ice margin may enhance melting over the Greenland Ice Sheet. Rennermalm et al. (2009) explored the spatial and temporal covariance of sea-ice extent and ice sheet surface-melt around Greenland from 1979 to 2007. Significant covariance was found in western Greenland. An examination of wind direction patterns and a lag analysis of ice retreat/advance and surface-melt event timings suggested that a change in sea-ice extent is a potential driver of ice-sheet melt, in that late summer wind directions bring onshore advection of ocean heat, enhanced by reductions in offshore sea ice.

There is a strong linkage between sea-ice loss and terrestrial permafrost temperature. Lawrence et al. (2008) examined how rapid sea-ice loss affects the terrestrial Arctic climate and ground thermal state using a GCM. It was found that the accelerated warming signal penetrates up to 1500 km inland and substantially increases ground heat accumulation. Furthermore, enhanced heat accumulation leads to rapid degradation of warm permafrost and may increase the vulnerability of colder permafrost to degradation under continued warming. In contrast to the relationship between snow cover and the Indian monsoon, which operates on a yearly time scale, the changes in atmospheric circulation impact permafrost on decadal scales.

11.1.2.3. Interactions with the freshwater budget of the Arctic

All of the cryospheric components play, to varying degrees, roles in the freshwater budget of the Arctic. Changes in the cryosphere can affect the strength of the thermohaline circulation in the North Atlantic, where it is called the Atlantic Meridional Overturning Circulation (AMOC), and hence, global climate. Assessing the magnitude of these effects requires not only an understanding of how the thermohaline circulation responds to freshwater inputs, but also the sources, locations, distributions, and pathways of freshwater into and out of the Arctic (Randall et al., 2007).

In general, the Arctic Ocean receives freshwater inputs from direct precipitation, Pacific water via the Bering Strait (referenced to a particular salinity), terrestrial ice masses, and runoff from river basins, which includes large areas of the northern hemisphere continents. Importantly, the major river basins contributing flow to the Arctic Ocean are of a nival regime (runoff is dominated by snowmelt), where the snowmelt freshet is the largest and most important hydrological event of the year. Within the Arctic Ocean, freshwater amounts also change due to losses from evaporation and to the growth (-) and ablation (+) of sea ice. Very large volumes of freshwater can also be 'stored' in deep basins with highly variable residence times. Freshwater export from the Arctic Ocean occurs primarily through Fram Strait and the Canadian Archipelago to the Atlantic Ocean, where it plays a role in the formation of deep water in the Greenland-Iceland-Norwegian (GIN) Seas.

It is the export of freshwater that has been identified within paleo-records as weakening the thermohaline circulation and causing major cooling events over the North Atlantic. For example, an Arctic Ocean pathway fed by freshwater flows from the Mackenzie River-Beaufort Gyre, instead of the previously supposed Great Lakes-St. Lawrence routing, has been recently identified as being responsible for the shutting down of the

North Atlantic thermohaline circulation, resulting in major cooling associated with the Younger Dryas Period (Peltier, 2007; Murton et al., 2010).

Since publication of the Arctic Climate Impact Assessment in 2005 (ACIA, 2005), a number of updates have been made concerning the relative size of the overall freshwater budget terms and of the cryospheric components that contribute to them. These are considered in Section 11.1.2.3.2, gleaned from the preceding chapters of this report and related literature. First, some example post-ACIA freshwater budget evaluations are considered.

11.1.2.3.1. Recent budget estimates

Total freshwater inputs to the Arctic Ocean, calculated at about 8500 km³/y, are dominated by river flow (38%), inflow through the Bering Strait (30%), and precipitation-evaporation directly occurring on the Arctic Ocean (24%) (Serreze et al., 2006). Importantly, this estimate is an order of magnitude smaller than the total amount stored in the Arctic Ocean. Freshwater exports from the Arctic Ocean occur principally through the straits of the Canadian Arctic Archipelago (35%) and via Fram Strait as liquid freshwater (26%) and sea ice (25%). For such calculations, the volumes of freshwater are referenced to a mean ocean salinity of 34.8. Also recognizing that a steady state of the freshwater budget should not be expected, Serreze et al. (2006) noted that their values indicate larger freshwater inflow through Bering Strait and larger liquid freshwater outflow through Fram Strait than earlier estimates by others.

Peterson et al. (2006) conducted an analysis of changes in freshwater budget components for a broader 'Arctic region' than Serreze et al. (2006), which included the additional large land-ocean catchment of Hudson Bay in North America as well as the Nordic Seas and North Atlantic subpolar basins. Increasing precipitation-evaporation over the marine environments and larger river flow, probably also tied to increases in high-latitude precipitation, was estimated to have contributed ~20 000 km³ of freshwater to the total region from lows in the 1960s to highs in the 1990s. Notably, the river trend included a decline in flow for the Hudson Bay system. Sea-ice ablation added a slightly smaller amount of ~15 000 km³, and glacial melt added ~2000 km³. Due to the lack of complete mass-balance estimates for the Greenland Ice Sheet, its contributions were excluded from the latter amount but it was noted to have been ~80 km³/y in the 1990s and to have recently increased to ~220 km³/y (Peterson et al., 2006). The most recent estimate of current annual loss of ice from the Greenland Ice Sheet is similar at about 205 ± 50 Gt/y¹ (2005–2006) (see Chapter 8).

11.1.2.3.2. Freshwater budget components and changes

Snowmelt and river discharge

Compared to all other world oceans, the Arctic Ocean receives a disproportionately large amount of river runoff to its total volume via the Lena, Mackenzie, Ob, and Yenisey rivers that are dominantly nival rivers. River flow provides the largest input to the Arctic Ocean freshwater budget (Prowse and Flegg, 2000). Although the seasonality of observed multi-decadal increases

¹ A mass loss rate of 360 Gt/y is equivalent to a mean sea level rise of ca. 1mm/y.

in total Eurasian river flow to the Arctic Ocean has not been fully examined, Chapters 4 and 5 note that some increases in the magnitude and advances in timing of the snowmelt freshet on northern rivers have been observed and greater changes are expected in the future. This will be due not only to changes in the size and seasonality of snowmelt but also to the effects of thawing permafrost in changing flow pathways and storage. Such changes in the timing and magnitude of flows are important to how river water is distributed, directed and/or stored in the Arctic Ocean (e.g., Cooper et al., 2008; Jones et al., 2008).

Mountain glaciers and ice caps, and the Greenland Ice Sheet

The overall freshwater contribution from the glaciers (328 556 km²) in a broadly defined, pan-Arctic drainage basin, as well as small ice caps around the Greenland Ice Sheet (but not including the ice sheet itself), is ~1700 km³ for the period 1961 to 2001 (Dyurgerov and Carter, 2004). Freshwater contributions from these glaciers varied annually from near zero to just under 200 km³, far less than contributed by the corresponding nine major rivers (5282 km³/y) within the same pan-Arctic region. However, there is a greater 'positive change signal' from the glaciers than river discharge (Dyurgerov and Carter, 2004). Partly included in this total are the glaciers from the Alaska-Yukon region, which contribute to the North Pacific Ocean waters near the principal Arctic Ocean inflow point, the Bering Strait. These glaciers have experienced some of the most rapid wastage. In the case of Alaska, for example, freshwater contributions have increased from 52 ± 15 km³/y over the 1950s to 1990s period to ~96 km³/y from the mid-1990s to 2001 (Arendt et al., 2002), and more recent sampling suggests increased ablation particularly at low elevations. In reference to the Bering Strait to which these glaciers contribute, flow volumes to the Arctic Ocean have been significantly revised upward (i.e., by ~50% to ~2500 km³/y; Woodgate and Aagaard, 2005), although the exact contribution of ablating glaciers to such volume increases remains unknown.

Some freshwater budget analyses contain little discussion about the role of the Greenland Ice Sheet, despite its strategic placement as a freshwater source in the North Atlantic. In addition to freshwater volume, the location of the input may also be important (Randall et al., 2007) and meltwater runoff from the ice sheet is potentially a major source of freshening that has not yet been included in relevant models (Randall et al., 2007).

Sea ice

The Arctic Ocean is a salt- rather than temperature-stratified ocean and hence, sea-ice growth/ablation and ocean dynamics can be greatly modified by changes in freshwater. It is the salt-stratified upper layers that provide the vertical stability to permit formation of an ice cover. Surface freshwater layers, however, also contribute with the halocline to thermally shield sea ice from bottom melt, which can be driven by the large quantities of heat contained in warmer, deeper water originating from the Atlantic Ocean. Carmack (2000) estimated that the volume of ice forming and melting each year amounted to a 1.45 m equivalent of freshwater (depth of freshwater across the ocean) assuming an un-deformed ice cover, and an additional 0.45 to 0.7 m of freshwater if the

mass in ice ridges is also considered. However, sea ice has undergone significant changes in areal coverage and thickness.

For some key episodic losses, sea ice-bottom melt has been linked to solar heating of the upper ocean (Perovich et al., 2008). Bottom melt can also result from the loss of thermal insulation from the warmer Atlantic water provided by the surface layers of freshwater and cold halocline. The stability of these upper layers, particularly with enhanced vertical mixing, has been identified as a 'key wild card' regarding future sea-ice loss (Serreze et al., 2007). Sea ice is also exported through Fram Strait along with sea-ice meltwater, but export of sea-ice meltwater seems to be the least likely to influence thermohaline circulation (Jones et al., 2008). This could play a large role in changing ice conditions.

Ocean storage and pathways

The fate of sea-ice meltwater and other forms of freshwater is not simply direct export because the Arctic Ocean also holds significant freshwater in storage with variable releases. While about one-quarter of the total is held on shelves, the majority is in the Eurasian and Canada basins, the latter being the largest single freshwater storehouse in the Arctic Ocean. This has been ascribed to the deep halocline of Canada Basin, which stores freshwater from sea ice meltwater, meteoric water (ocean precipitation and terrestrial runoff), and low-salinity Pacific water from the Bering Strait. Estimates of this storage (like the other freshwater budget terms) vary in the literature, and are primarily due to changes in import-export to Canada Basin and, in the accuracy and ability to measure its content. Despite variations in its estimated volume (e.g., ~46 000 km³; Carmack, 2000) and 25 600 km³ (Yamamoto-Kawai et al., 2008), it is generally accepted that the largest source of the average annual freshwater input (~3200 km³) to this and other freshwater storehouses in the Arctic Ocean (Yamamoto-Kawai et al., 2009) is river runoff – estimated by Yamamoto-Kawai et al. (2008) for Canada Basin to be 800 km³/y and to be just slightly smaller than the amount removed by sea-ice formation (900 km³/y). They further estimated that the average export of ice and liquid freshwater from Canada Basin contributes ~40% of the freshwater flux to the North Atlantic.

The storage values vary with time due to atmospheric circulation, which can control pathways of freshwater to/from storage basins as well as the storage/release from within the storage basins (i.e., Ekman pumping, which under anticyclonic [cyclonic] circulation stores [releases] freshwater). Most recently, measurements from Canada and Makarov basins indicate that there has been a freshwater storage increase of up to 8500 km³, and by extrapolation, almost 11 000 km³ in all the deep basins of the western Arctic. By contrast, the Eurasian Basin in the eastern Arctic and closer to the main export to the North Atlantic has experienced a loss of about 3300 km³, giving a net gain of 7700 km³ (McPhee et al., 2009). This is a significant increase being about four times the volume associated with the Great Salinity Anomaly (a near-surface pool of fresher-than-usual water tracked in the subpolar gyre currents from around 1968 to 1982, which affected regional climate) and similar in magnitude to the total 1981 to 1995 sea ice attrition (melt plus export) estimated in the above-noted freshwater budget by Peterson et al. (2006).

11.1.2.3.3. Model projections

At the time of the Arctic Climate Impact Assessment (ACIA, 2005), there was concern about the intensification of the hydrological cycle at high latitudes and the effect this would have on the AMOC. ACIA noted that projections by atmosphere-ocean GCMs produced varying results with changes in the maximum strength of the AMOC by the end of the 21st century ranging from zero to a reduction of 30–50%. The suite of ACIA-selected GCMs (Kattsov and Källén, 2005) did not include freshwater runoff from melting ice sheets and glaciers. Hence, it was surmised that the model AMOC sensitivity to global climate change might be too weak, although sensitivity experiments indicate freshwater runoff must be several times ‘present-day’ volumes to appreciably alter the AMOC.

A strong scientific debate remains about the potential significance of freshwater effects on the AMOC (Randall et al., 2007). For example, Holland et al. (2007) noted that a constituent result among models for the period 1950 to 2050 (observations and modeled results) is an acceleration of the hydrological cycle, including increased ocean net-precipitation, river runoff, and net sea-ice melt. They also noted, for liquid water, a larger export to lower latitudes, primarily through Fram Strait, and storage in the Arctic Ocean. By contrast, export and storage of freshwater in the form of sea ice decreases, although there is significant variability in sea-ice budget terms. Largely similar results were reported by Koenigk et al. (2007).

A number of efforts are underway to more accurately define the role of freshwater in AMOC weakening, the Coupled Model Intercomparison Project (CMIP) and Paleoclimate Modelling Intercomparison Project (PMIP) coordinated effort being major examples. All models used in CMIP show that AMOC weakening projected for the 21st century is caused more by changes in the surface heat flux than by freshwater, although its effect on high-latitude stratification plays a contributing role (Arzel et al., 2008). They further noted that interannual exchanges in freshwater between the GIN Seas and the North Atlantic have a major driving influence on the interannual variability of deep convection over the 21st century.

11.1.3. Synthesis

This review and analysis has substantiated and quantified many of the linkages between the cryosphere and climate identified by earlier recent studies (e.g., Francis et al., 2009). Figure 11.2 synthesizes the major feedbacks on climate mediated by cryospheric processes, where the impacts of changes in various forcing variables (e.g., greenhouse gases, albedo) and processes (e.g., atmospheric circulation and thermohaline circulation) on elements of the cryosphere are depicted. The surface or near-surface air temperature is the variable primarily used to drive changes in the cryospheric component and then to assess the magnitude of warming or cooling. The box colors indicate the expected future impact of a change in the variable or process on the climate, where red indicates warming and blue indicates reduced rate of warming or even cooling. The colors also indicate the type of feedback, where red is a positive feedback from current climate warming to future temperature and blue is a negative

feedback. The color does not, however, indicate the direction of change between the two variables alone. For example, a decrease in sea-ice cover increases atmospheric water vapor, which in turn may decrease sea-ice cover even further because water vapor is a greenhouse gas. This is a positive feedback, but the change in sea-ice cover and water vapor are in opposite directions. The box size and intensity of the colors indicates, at least qualitatively, the relative magnitude of the impact. For example, warming caused by a decrease in albedo through a loss of sea ice is expected to be greater than that due to changes in glacier extent. The feedbacks presented in Figure 11.2 represent a relatively simple synthesis of many complex processes. This synthesis is intended to stimulate a better understanding of the processes rather than give a definitive analysis.

The impacts, interactions, and feedbacks in Figure 11.2 are not necessarily independent. In particular, cloud formation is strongly dependent upon the available water vapor, which may be from local sources or transported from lower latitudes (atmospheric circulation). Additionally, changes in one part of the cryosphere may affect changes in others. For example, thin ice has a very high growth rate but is strongly affected by snow cover. Snow is an efficient insulator, so ice with little snow on its surface can grow much faster than ice with a thick snow cover. This allows for the newly forming sea ice to reach a thickness that might even be larger than that of ice that survived the summer. Although the ice-albedo feedback leads to a decreasing summer sea-ice cover, rapidly growing thin ice leads to a recovery of the sea-ice cover during winter. An additional contributor to this recovery is that often there is little snow on the newly forming sea ice. It is presently unclear how an ice-diminished Arctic will impact on snowfall, so it is difficult to assess to what degree the growth of thin ice may offset the increase in ice melt through the ice-albedo feedback.

Despite the interactions between feedbacks, Figure 11.2 provides a snapshot of how changes in a warming climate affect the cryosphere, illustrating the signs and magnitudes of the feedbacks.

11.1.4. Uncertainties and recommendations

Most of the terrestrial feedbacks are poorly quantified over large areas although considerable detail is available for a few specific locations. Generalization of the impacts is difficult at best. *A better observational capacity is needed: an improved coverage of the circum-Arctic area is needed and observations need to be sustained over longer periods. It is particularly necessary to determine the net effects of thawing permafrost and changing snow cover on tundra hydrology – is the net effect a dryer or wetter tundra? The net result will be a major determinant of terrestrial/wetland greenhouse gas emissions.*

Large uncertainties exist in cloud feedbacks and subsea permafrost: *these topics require enhanced and sustained research.*

General circulation models currently include few feedbacks. *Modeling studies including sensitivity analyses need to be intensified to include all the major feedbacks and to calculate the net effects.*

Lack of full coupling between surface dynamics and the atmosphere is a major gap in current GCMs. Chapter 8 recommends more accurate incorporation of surface albedo and snow microphysics in climate models.

There remains considerable controversy about the degree





Figure 11.2. The major feedbacks on climate via the cryosphere. The box colors indicate the expected future impact of a change in the variable or process on the cryosphere (where red indicates warming and blue indicates reduced rates of warming or even cooling). The box size and intensity of the colors indicates, at least qualitatively, the relative magnitude of the impact or levels of understanding (where grey represents uncertainties due to conflicting information etc. and white indicates a knowledge gap). Arrows indicate whether the (warming or cooling) effect is increasing or decreasing over time,



that is, the acceleration or retardation of the process assuming a time horizon over ~30 yrs. The feedbacks presented in this figure represent a relatively simple synthesis of many complex processes. Possible feedbacks due to black carbon are not included in this diagram as they are not addressed in the SWIPA assessment; for information on black carbon impacts on Arctic climate see AMAP (2011b).

to which current levels of freshwater within the Arctic Ocean can affect the strength of the AMOC. *There is a need to evaluate the potential for the cumulative production and release of large amounts of freshwater from all contributing components, including all components of the cryosphere. Also there is a need to assess whether there are specific circulation patterns and durations that could cause significantly large freshwater production from all terrestrial and marine freshwater sources and their ultimate export to the North Atlantic where they could produce a significant effect on the AMOC and global climate.*

The primary source of uncertainty regarding the atmosphere as a driver of change in the Arctic is precipitation. Future changes in its spatial and seasonal distribution are unclear, as are its effects on the sea-ice mass budget, marine primary productivity, and vegetation. *A better understanding of precipitation effects will only be gained through developing and sustaining a more robust observing network.*

11.2. Sea-level change

11.2.1. Introduction

This discussion of sea-level change (see also Box 11.1) is framed in terms of the impact on global mean sea level of net loss of mass from Arctic mountain glaciers and ice caps, and the Greenland Ice Sheet. Reconstructions of sea-level change using geological evidence show that a sea-level rise of one or more metres per century was not uncommon in the past. It has recently been suggested that such rates occurred during the last interglacial warm period 120 000 years ago when the volume of land ice was similar to that at present

Box 11.1. Sea-level terminology

Mean sea level (MSL) is defined as the average height of the ocean surface (i.e., the global average of the elevations of the mid-points between local mean high and low tide levels). The term eustatic refers to changes in global mean sea level due to changes in the mass of water in the oceans, but also through tectonic processes which change the size or shape of the ocean basins. The term steric refers to changes in global mean sea level due to changes in water density arising from thermal expansion or compression and/or salinity variations. The local mean sea level (LMSL) refers to the height of the sea with respect to a local benchmark on land, and is determined by averaging the height difference over a period of time long enough to smooth out fluctuations caused by waves and tides. In some regions, vertical movements of the land can be of the same order (mm/y) as sea-level changes, and measurements of local mean sea level must be corrected for this effect. Such land movements can occur because of ongoing isostatic adjustment of the mantle to temporal variations in surface loading resulting from changes in glacier or ice sheet mass. Isostatic adjustments are greatest near the sources of glacier or ice sheet change (where they are referred to as glacio-isostatic adjustments), but combine with other load signals to form a complex global pattern of crustal uplift and depression (National Research Council, 2011).

(Berger, 2008; Rohling et al., 2008). Worldwide, the coastal zone changed profoundly during the 20th century, primarily due to a growing population and increasing urbanization. In 1990, 23% of the world's population (or 1.2 billion people) lived within 100 km distance and 100 m elevation of the coast at densities about three times higher than the global average (National Research Council, 2011). Around 200 million people live on coastal floodplains, less than 1 m above current sea level. Sea-level rise is thus one of the major global socio-economic hazards associated with climate change. With coastal development continuing at a rapid pace, society is becoming increasingly vulnerable to sea-level rise and variability. Rising sea levels will contribute to more severe storm surges and flooding, even if hurricane intensities do not increase in response to the warming of the oceans. They will also contribute to the erosion of the world's sandy beaches, most of which have been retreating over the past century. Low-lying islands are also vulnerable to sea-level rise.

11.2.2. Instrumental sea-level record

Since 1870, global sea level has risen by about 0.2 m (Bindoff et al., 2007). During the 20th century, the rate of rise in global mean sea level was in the range 1.0 to 2.0 mm/y (Church et al., 2001), with recent analyses for the past 50 years giving values in the upper part of this range (Holgate and Woodworth, 2004; Church and White, 2006). During this period, the ice sheets of Antarctica and Greenland made a relatively small contribution to sea-level change (a few tenths of a millimetre per year at most; Rignot and Thomas, 2002), so the changes observed were due primarily to the combination of steric changes and global mountain glacier / ice cap melt. Since 1993, sea level has been measured accurately globally using altimeters on satellite platforms. Before then, the data were obtained from tide gauges at coastal stations around the world. Satellite and tide-gauge measurements both show that the rate of sea-level rise has accelerated since 1990 (Figure 11.3). Satellite measurements show that sea level rose at an average rate of 3.3 ± 0.6 mm/y from 1993 to 2008 (Ablain et al., 2009). This decreased to




Figure 11.3. Sea-level change during the period 1970 to 2008. Tide gauge data are shown in red (Church and White, 2006) and satellite altimeter data in blue (Cazenave and Llovel, 2010). The grey band shows the IPCC projections reported in its Third Assessment Report (Church et al., 2001) for comparison.




Figure 11.4. Estimated mass losses in all Arctic land ice (mountain glaciers and ice caps, and the Greenland Ice Sheet) from 1960 to 2006. The size of the pie chart indicates the total mass loss from all Arctic land ice, while the respective slices represent the relative contributions from different regions. Except for the most recent estimate, which is only a 1-year net mass loss, estimates are for periods of five mass balance years. Averaging periods and mass loss in Gt/y are given adjacent to each pie chart. 'Greenland periphery' refers to glaciers and ice caps on Greenland that are separate from the main ice sheet. Time-averaged estimates of multi-year geodetic measurements are assigned to all pentads to which each individual measurement refers. Non-ice sheet data are derived from a subset of a global, gridded extrapolation of glaciological and geodetic mass balance measurements (Cogley, 2009). These data are plotted by region in Chapter 7, Figure 7.30. All estimates for periods prior to 1995 do not include the contribution from the Greenland Ice Sheet owing to a lack of reliable data. Estimates for the Greenland Ice Sheet after 1995 are compiled from Chapter 8, Figure 8.19 using the values 50 Gt/y for 1995–2000, 100 Gt/y for 2000–2005, and 205 Gt/y for 2005–2006. Although there are several satellite gravimetric measurements of the mass of land ice on Greenland for the period since 2002 they are excluded from this analysis because the Gravity Recovery and Climate Experiment (GRACE) measures changes in the mass of both the ice sheet and the mountain glaciers and ice caps beyond the ice sheet margin, and changes in these peripheral glaciers are already estimated in the Cogley (2009) pentadal dataset.

2.5 ± 0.6 mm/y for the period 2003 to 2008 (Ablain et al., 2009; Cazenave and Llovel, 2010). Statistical analysis reveals that the rate of rise is correlated with global mean surface temperature (Rahmstorf, 2007; Grinsted et al., 2009). Sea-level rise is a predictable consequence of climate warming for two main reasons: ocean water expands as it heats up, and additional water flows into the oceans from the ice that melts on land.

11.2.3. The role of Arctic mountain glaciers and ice caps, and the Greenland Ice Sheet

The chapters addressing Arctic mountain glaciers and ice caps (Chapter 7) and the Greenland Ice Sheet (Chapter 8) document present knowledge of historical changes in the mass of these ice bodies. Net mass loss from Arctic mountain glaciers and ice caps has increased and corresponds to a rise in mean sea level of 0.5 mm/y in the most recent decade (ca. 1996 to 2006, Dyurgerov et al., 2009) and perhaps even to 0.75 mm/y in the period 2000 to 2005 (Cogley, 2009). The volume of all the world's mountain glaciers and ice caps (all land ice except the Greenland and

Antarctic ice sheets) is estimated to be equivalent to a change in mean sea level of 0.60 ± 0.07 m; the Arctic mountain glaciers and ice caps contain 68% of the total volume of these glaciers and ice caps which is equivalent to 0.41 m of mean sea-level rise (Radić and Hock, 2010). The rate of mass loss from the Greenland Ice Sheet has been increasing rapidly, and its contribution to mean sea-level rise has progressively increased from about 0.14 mm/y (1995–2000), to 0.28 mm/y (2000–2005), to 0.57 mm/y (2005–2006) (averages from Chapter 8, Figure 8.19, assuming that a mass loss rate of 360 Gt/y is equivalent to a rate of rise in global mean sea level of 1mm/y). The most recent estimate of the total mass loss from the Arctic mountain glaciers and ice caps, and the Greenland Ice Sheet (for 2003–2008) thus sums to 1.3 mm/y mean sea-level rise (462 Gt/y) and hence contributes more than half to the most recent estimate of the global rate of mean sea-level rise (2.5 mm/y; Ablain et al., 2009). Both the proportional contribution from the Greenland Ice Sheet and the total contribution from Arctic land ice (i.e., the Greenland Ice Sheet, and the Arctic mountain glaciers and ice caps) to mean sea-level rise have increased strongly since 1995 (Figure 11.4). The uncertainties on the sea-level rise estimates for the

Greenland Ice Sheet and the Arctic mountain glaciers and ice caps vary within the literature, with values of 0.1 to 0.2 mm/y on each of the components resulting in an uncertainty in the sum of the estimated sea-level rise from the two sources combined of 0.23 mm/y (Ablain et al., 2009; Cazenave and Llovel, 2010).

11.2.4. Additional sources contributing to sea-level rise

In order to assess the causes of observed sea-level changes and predicted future sea-level rises, other influences on sea-level rise need to be taken into account. These include thermal expansion of the ocean water, mass losses from the Antarctic Ice Sheet and non-Arctic mountain glaciers and ice caps, and change in land water storage. The loss of mass of the global glaciers and ice caps has increased from 0.8 ± 0.1 mm/y (1993–2003) to 1.4 ± 0.25 mm/y (2003–2007) (Cazenave et al., 2008; Cazenave and Llovel, 2010). The Antarctic Ice Sheet is the largest body of ice in the world, and uncertainties in glacial isostatic adjustments in this area are large, making it difficult to obtain accurate estimates of ice sheet mass loss. The most reliable estimates have been determined from satellite observations made during the past decade. The loss of mass from the Antarctic Ice Sheet is observed to be equivalent to 0.2 ± 0.17 mm/y mean sea-level rise in 1993–2003, increasing to 0.5 ± 0.15 mm/y in 2003–2007 (Cazenave et al., 2008; Cazenave and Llovel, 2010). Thermal expansion of the ocean water was the greatest component of observed mean sea-level rise with a value of 1.0 ± 0.3 mm/y in 1993–2003 (Cazenave and Llovel, 2010). In the most recent period the contribution from thermal expansion has decreased to 0.25 ± 0.8 mm/y (Cazenave and Llovel, 2010). The final component of the mean sea-level rise is the change in storage of water on land due to climatic change and human activities. Estimates based on GRACE satellite observations suggest a negative change in terrestrial water storage in the period 2003–2007, contributing -0.2 ± 0.1 mm/y to mean sea-level (Cazenave and Llovel, 2010). A compilation of historical contributions from thermal expansion, the different land ice components, and change in terrestrial water storage is shown in Figure 11.5 and Table 11.1.




Figure 11.5. Change in total observed mean sea-level rise and its components over the period 1960 to 2003. The components related to the steric sea-level rise are thermal expansion in the upper 700 m and thermal expansion in the deep ocean. The mean sea-level rise from the ice sheets of Antarctica and Greenland, mountain glaciers and ice caps and terrestrial water storage are also shown. Source: based on Domingues et al. (2008).

Table 11.1. Contributions to mean sea-level rise for the periods 1993–2007 and 2003–2007. Quoted errors are one standard deviation. Source: Cazenave and Llovel (2010).

Sea-level rise, mm/y	1993–2007	2003–2007
Observed	3.3 ± 0.4^a	$2.5 \pm 0.4^{a,b}$
Thermal expansion	1.0 ± 0.3^c	0.25 ± 0.8^d (Argo)
Ocean mass	2.3 ± 0.5^e	2.1 ± 0.1^f
Mountain glaciers and ice caps	1.1 ± 0.25^g	1.4 ± 0.25^h
Total ice sheets (Greenland and Antarctic) ^j	0.7 ± 0.2 (0.4 ± 0.15) (0.3 ± 0.15)	1.0 ± 0.2 (0.5 ± 0.15) (0.5 ± 0.15)
Land waters	–	-0.2 ± 0.1^k
Sum of (2 + 4 + 5 + 6)	2.85 ± 0.35	2.45 ± 0.85
Observed rate minus sum	0.45	-0.05

^a The observed sea-level rise is GIA corrected (-0.3 mm/y removed); ^b Ablain et al. (2009); ^c mean of Levitus et al. (2009) and Ishii and Kimoto (2009) values; ^d mean of Willis et al. (2008), Cazenave et al. (2009) and Leuliette and Miller (2009) values; ^e observed rate minus thermal expansion; ^f GRACE with a -2 mm/y GIA correction, Cazenave et al. (2009); ^g based on Kaser et al. (2006) and Meier et al. (2007); ^h Cogley (2009); ⁱ compilation of published results; ^k W. Llovel, K. DoMinh, A. Cazenave, J.F. Cretaux, M. Becker, unpublished manuscript.

11.2.5. Projections into the future

Radić and Hock (2011) computed estimates of the mass changes of more than 120 000 mountain glaciers and around 2600 ice caps around the world to 2100 using an elevation-dependent temperature-index mass balance model driven by output from ten GCMs forced by the IPCC A1B emissions scenario. Future volume changes were up-scaled to all glaciers using a regionally differentiated approach. For the Arctic mountain glaciers and ice caps (including those in Greenland surrounding the ice sheet) the projected volume losses due to melt (mass loss by calving is not included) show a large range (51–136 mm mean SLE or a 13–36% reduction in their current volume by 2100) depending on the choice of GCM (Chapter 7, Figure 7.23). The modeled volume reduction by 2100 varies considerably among regions, with the smallest reductions in Greenland ($8 \pm 4\%$) and the largest in Svalbard ($54 \pm 15\%$), with a large spread among models for most regions (Chapter 7, Figure 7.23). Most models show the greatest Arctic sea-level contributions coming from the Canadian Arctic, Alaska (including the glaciers of northwestern Canada), followed by Svalbard and the Russian Arctic. Contributions from Arctic Canada show a very large range; from a mean SLE contribution of <10 mm to the largest projected contribution for any of seven Arctic regions, indicating a large spread in the projected temperature and precipitation fields among the GCMs for this region (Chapter 7, Figure 7.24).

The above projections do not include mass losses due to calving that result from changes in the dynamics of tidewater glaciers. In the polar regions, there is evidence of accelerating flow and increased calving of tidewater glaciers, especially in Greenland and in western Antarctica, but it is not yet possible to predict reliably whether this will become more widespread, or for how long it may be sustained.

Since the IPCC Fourth Assessment, a number of new studies of ice-sheet mass budget have considerably enhanced understanding of the potential for rapid collapse of ice sheets in response to changing climate (Allison et al., 2009). Recent observations have shown that changes in the rate of ice discharge into the ocean can occur far more rapidly than previously suspected (e.g., Rignot, 2006). Currently there is no dynamic ice-sheet model that can predict the response of the Greenland Ice Sheet to a warmer climate on a century time scale. To get around this difficulty, Pfeffer et al. (2008) attempted to assess the rates of sea-level rise that could occur under a range of physically plausible scenarios. Under their ‘Low 1’ scenario, the sea-level rise contribution from Greenland is estimated by assuming a doubling in ice discharge, and a continued increase in losses by surface melt from both the ice sheet and mountain glaciers and ice caps at present-day rates. In this case, the total contribution to sea-level rise would be about 0.17 m by 2100, with contributions of 0.09 m from ice discharge, and 0.07 m from surface melt, respectively.

In western Antarctica, the Amundsen Coast basin (which includes Pine Island and Thwaites Glaciers), has shown increased mass loss in recent years. These marine-based glaciers contain about 1.5 m SLE of ice, and are particularly sensitive to changes in climate and in ocean circulation and temperature. The average ice velocity in this region is 2 km/y, which is considerably higher than the average velocity for all Antarctic ice streams (0.65 km/y) (Pfeffer et al., 2008). If ice

discharge into the oceans from this region continues to increase, the sea-level rise contribution from western Antarctica will be significant. Pfeffer et al. (2008) estimated the potential sea-level rise contribution from Antarctica by 2100 by (i) doubling the velocities of Pine Island and Thwaites Glaciers within the first decade, (ii) accelerating the rate of ice loss by surface mass balance from the Antarctic Peninsula at the present-day rate of surface mass balance change, and (iii) scaling dynamic losses from the Antarctic Peninsula to losses by surface mass balance with a ratio of 1.31 (as observed in Greenland). The resulting projected sea-level rise is 0.15 m by 2100 (this case is also referred to as the ‘Low 1’ scenario).

Under the ‘Low 1’ scenario, the Greenland and Antarctic ice sheets would together contribute up to 0.31 m to mean sea-level by 2100 (Pfeffer et al., 2008). Under a more extreme scenario, ‘High 1’, that envisages more dramatic increases in dynamic losses, contributions to sea-level rise by 2100 of 0.54 m from Greenland (0.47 m from ice dynamics alone) and 0.62 m from Antarctica (all but 0.01 m from ice dynamics) are projected (Pfeffer et al., 2008), a total of nearly 1.2 m.

According to Radić and Hock (2011), the projected multi-model mean sea-level rise contribution from all mountain glaciers and ice caps on Earth is 0.12 ± 0.04 m by 2100. This is larger than an estimated contribution from surface mass balance of 0.08 m (Pfeffer et al., 2008). In the Radić and Hock study, mass loss by calving is neglected. Pfeffer et al. (2008) suggested that ice discharge from fast-flowing tidewater glaciers and ice cap outlets could add between 0.09 m (Scenario ‘Low 1’) and 0.47 m (Scenario ‘High 1’) to global mean sea level by 2100. Adding in the steric contribution to projected sea-level rise estimated by the IPCC AR4 Working Group 1 (Meehl et al., 2007) of 0.30 ± 0.15 m by 2100, the sum of land ice contributions to global mean sea level by 2100 would range between 0.79 m (Scenario ‘Low 1’) and 2.01 m (Scenario ‘High 1’) (Pfeffer et al., 2008). It should be emphasized, however, that these estimates are not the result of rigorous projections, but of scenarios designed to bracket the potential range of sea-level rise that could occur as a result of changes in ice dynamics.

As an alternative method for projecting the combined contributions of surface mass balance and ice dynamics to 21st century sea-level change, Rahmstorf (2007) and Grinsted et al., (2009) made semi-empirical projections by linking past sea-level changes to observed surface air temperatures (see Figure 11.6). Their statistical projections of sea-level rise for the range of temperature projections associated with the IPCC A1B emissions scenario (2.3 to 4.3 °C temperature increase for 2100) range from 0.97 to 1.56 m above 1990 sea level by 2100. This is consistent with what happened during warming induced by variations in Earth’s orbit during the last interglacial period (Overpeck et al., 2006).

Total projected sea-level rise resulting from all sources by 2100 cannot be estimated with high confidence at present. Lower and upper limits have a range of 0.79 to 2.01 m. A range of 0.9 to 1.6 m is considered the more plausible current estimate by the authors of the SWIPA assessment.

Finally, it should be emphasized that sea-level changes are far from equal from region to region as changes in the Earth’s rotation and gravity field, ice load, ocean temperatures, ocean circulation, and freshwater supplies also impact the local mean sea level (Cazenave et al., 2008; Cazenave and Llovel, 2010). Between

Global sea level relative to 2000, m




Figure 11.6. Semi-empirical estimate of sea-level rise by 2100 (Grinsted et al., 2009), based on projections of future surface temperature change made using climate models forced by the IPCC A1B emissions scenario.

1993 and 2007, the trend in observed sea level varied spatially from -5 mm/y to 15 mm/y. Taking into account the influences of changes in the Earth's rotation, the gravity field and related effects for the period 2000 to 2008, Bamber and Riva (2010) suggested that mass loss from Greenland resulted in local sea-level rise around South America, and local sea-level fall in much of eastern Canada and northwestern Europe. Trends in local mean sea level will also depend on location relative to regions where ice mass loss is occurring due to the isostatic response (Milne et al., 2009). Overall, there is a tendency toward falling local sea level in the vicinity of regions where large decreases in ice mass are occurring.

11.2.6. Impacts of sea-level rise

The impacts of sea-level rise will be felt through an increase in mean sea level as well as through more frequent extreme sea-level events, such as storm surges. Impacts include increased severity and frequency of flooding in low-lying areas, salt water intrusion into surface water bodies and freshwater aquifers, beach erosion, and damage to infrastructure, agriculture, and the environment, including wetlands, intertidal zones, and mangroves, with significant impacts on biodiversity and ecosystem function. Hundreds of millions of people live in low-

lying coastal areas, including heavily populated deltas such as Ganges-Brahmaputra (Bangladesh), the Rhine (Netherlands), and the Mekong (Vietnam) (Nicholls and Cazenave, 2010).

Sea-level rise severely threatens the existence of a number of small island states. They are in danger of becoming completely submerged or facing increased coastal flooding. Several of these states, such as the Maldives in the Indian Ocean, the Bahamas in the Caribbean, and Tuvalu in the Pacific, are topographically flat and at or near sea level. Others are volcanic with only narrow coastal strips that are habitable. Sea-level rise (especially if coupled with storm surges from stronger and longer lasting tropical storms) would have a great impact on the socio-economic condition of small islands and small island states. Adaptation will be challenging in many island settings, and in some places may not be feasible at all.

Changes in ocean circulation due to ocean temperature rise and freshening of sea water may affect regional sea levels, particularly in the northeastern United States, eastern China, and Japan, where sea level is projected to rise more than the global average. This would place large coastal cities, such as Shanghai (China) and New York City (USA) at greater risk of permanent inundation and coastal flooding.

11.3. Contaminant pathways and change in the cryosphere

Summary

Loss of continuous sea-ice cover in Fram Strait has ultimately led to increased re-evaporation of previously trapped hexachlorobenzene (HCB) from open surface waters along the west coast of Spitsbergen (Svalbard) during the winter season. This increased evaporation of HCB is evident in atmospheric monitoring data from the Zeppelin research station on Svalbard. The general loss of sea-ice cover over extensive areas is increasing the potential for widespread re-evaporation of some legacy contaminants and enhanced deposition of others, such as polychlorinated biphenyls (PCBs).

Thawing permafrost is leading to the remobilization of previously stored anthropogenic contaminants into rivers and lakes, and sometimes even into groundwater. Melting of snow fields and glaciers is leading to the release of contaminants deposited over previous decades.

Change in sea-ice cover, hydrology, and organic carbon cycling will result in the redistribution/remobilization of contaminant loads. Such changes in the cryosphere will be accompanied by shifts in ecosystem function and species ranges, which will in turn alter the transfer and biomagnification of contaminants through food webs and, thus, also the exposure of higher trophic levels, including humans, to persistent toxic chemicals.

More extensive areas of open water and longer duration of open water owing to the loss of sea-ice cover will increase a range of human activities in the Arctic (transportation, exploitation of resources, industry, tourism), all of which will increase the risk of additional contaminants entering the Arctic environment from local sources.

11.3.1. Introduction

Contaminant concentrations and transport pathways in the Arctic environment have been monitored for more than two decades within the framework of the Arctic Monitoring and Assessment Programme (AMAP). The extensive AMAP contaminant monitoring program provides a unique opportunity for evaluating the impact of cryospheric change on contaminant fate and distribution within the Arctic environment, by using the contaminant patterns and levels reported as a sentinel for early environmental change in the Arctic cryosphere.

The Arctic was long considered to be pristine, little influenced by anthropogenic contaminants. However, research over the past two decades, strongly motivated by AMAP, has demonstrated the ability of persistent, semi-volatile compounds to travel long distances, with prevailing winds and ocean currents providing effective means to transport contaminants to the Arctic (AMAP, 1998).

This review focuses on the priority contaminants defined by AMAP, which include persistent organic pollutants (POPs) such as PCBs, hexachlorocyclohexane (HCH) isomers, HCB, DDT (dichlorodiphenyltrichloroethane) derivatives, as well as certain metals (e.g., mercury, lead) and radionuclides. These contaminants have been extensively studied for their human

and environmental health implications (AMAP, 2009).

Within the Arctic, a number of concentrating processes (e.g., Macdonald et al., 2002) lead to high exposure to classical POPs, especially for marine top predators. The exposures have consequences for the health and wellbeing of those Arctic residents that exploit marine mammals as traditional food resources (Van Oostdam et al., 1999; AMAP 2011a).

Early discussions of contaminant pathways considered the Arctic as a static system of boxes (environmental compartments or ‘reservoirs’ that contain contaminants, such as the atmosphere, ocean and soil) and arrows (fluxes), where each contaminant could be viewed as either moving between the fixed boxes or stored within them (AMAP, 1998; Macdonald et al., 2000a). Since the early 1990s it has become clear that the Arctic is changing (ACIA, 2005). The present assessment has assembled an impressive body of evidence to show that cryospheric change is pervasive and that the Arctic continues to evolve rapidly (e.g., Stroeve et al., 2007). Given these observations, it is apparent that the size of the boxes, the connections between the boxes, and the directions and sizes of the arrows between them are all subject to change within the cryosphere, and within upstream components in temperate and tropical regions. Surprises in global geochemical systems come from feedbacks (Shindell, 2007). With respect to contaminants and their fate in the Arctic environment, there are three important feedback systems: the hydrological cycle, the cryospheric cycle, and the organic carbon cycle. The Arctic features all three feedbacks and therefore offers a wide range of possible changes to contaminant cycles.

It has long been known that climate warming can affect contaminant pathways simply through inherent physical and chemical properties (e.g., vapor pressure and Henry’s Law constants, McKone et al., 1996). With an increase in average global temperature, the time a contaminant spends in the air will increase, and seasonal thermal forcing will have a greater effect on contaminants that undergo multiple ‘hops’ (i.e., repeated re-mobilization from secondary sources such as ocean surfaces and soils); such contaminants include DDT, PCBs, and mercury (Hg). As the hydrological cycle becomes more active (Stocker and Raible, 2005), contaminant deposition and re-emission will also become more active. On the other hand, the process of global distillation, which forces contaminants out of warm reservoirs in temperate industrial areas and into cold reservoirs at the poles, is likely to decrease because polar amplification will tend to reduce the thermal contrast between the two reservoirs (e.g., Screen and Simmonds, 2010). As highlighted by Macdonald et al. (2003, 2005), thermal forcing is but a small component of the contaminant cycle. Global change in general, and cryospheric change in particular, have a far greater potential to alter contaminant pathways through alteration of water balance (e.g., Smol and Douglas, 2007a), through phase change in water itself (e.g., Kwok et al., 2009), and through consequent change in organic systems (e.g., McGuire et al., 2009). Recent work has begun to reveal the important connections between global change and contaminant pathways in the cryosphere (Outridge et al., 2005; Stern et al., 2005; Garrett and Zhao, 2006; Schindler and Smol, 2006; Eckhardt et al., 2007; Schiedek et al., 2007; Becker et al., 2008, 2009; Gieisz et al., 2008; McKinney et al., 2009; van den Brink et al., 2009; Wang et al., 2010; Bustnes et al., 2010; Carrie et al., 2010).

Every step along the transport and redistribution pathways to and within the Arctic can be affected by climate change because reactivity, adsorption, air-sea exchange, and precipitation all depend on temperature. Some of these processes can be modeled thermodynamically (e.g., partitioning, vapor pressure), but it is clear that crossing the 0 °C isotherm has a unique capacity to alter systems (Macdonald et al., 2005). For example, whether precipitation occurs as rain or snow makes a large difference to contaminant exchange and deposition (Wania and Halsall, 2003; Daly and Wania, 2004; Lei and Wania, 2004; Herbert et al., 2006a,b) as does the presence of ice cover on ocean, lakes, and rivers. In addition to changing the connectivity between reservoirs, changes have already occurred in transport pathways within the atmosphere and ocean (McLaughlin et al., 2002; Macdonald et al., 2005; Shimada et al., 2006). Perhaps one of the greatest ways in which cryospheric change is manifested in contaminant pathways, is by altering the size of storage reservoirs. This is particularly important for classical contaminants that have been loaded heavily into the environment during the anthropocene (e.g., PCBs, DDT, Hg). Thus, the melting of permanent snow and glacial ice that have accumulated contaminant inventories during earlier eras (in many cases for more than 50 years) with high emissions will release these contaminants into the biosphere (Blais et al., 2001; Thies et al., 2007; Wang et al., 2010).

Priorities for Arctic environmental contaminant research with a focus on cryosphere-related processes should aim at an understanding of temporal and spatial distribution patterns including comprehensive source elucidation for selected compounds in ice-associated environments. The latter data will also be necessary to validate multi-compartmental models and identify environmental factors influencing chemical transport processes (e.g., atmospheric, oceanic, riverine and ice-borne transport).

This assessment takes as a point of departure the review by Macdonald et al. (2005) and provides an update on how cryospheric change alters the transport and fate of anthropogenic pollutants in the Arctic, including recommendations for future research priorities. Although climate change also alters the vulnerability of biota to contaminants (e.g., through multiple stressors), the focus here is on pathways. Change in the cryosphere also operates locally including, for example, the release of oil (drilling activities, natural oil seeps, oil sands) or other contaminants by thawing permafrost (increased active layer depth) and the risk of contamination or oil spills from increased shipping and other activities in the Arctic.

11.3.2. Impact of cryospheric change on contaminant pathways

11.3.2.1. Thawing permafrost and melting of glacial ice and snowpack

A decrease in the extent and thickness of permafrost due to warming in the Arctic is expected to release previously deposited contaminants into rivers, lakes and the ocean (Macdonald et al., 2005; Schindler and Smol, 2009; Rydberg et al., 2010). Emissions of naturally occurring potentially toxic substances have also been reported. Currently, permafrost and snow/ice cover prevent diffusion of naturally occurring Radon-222 (^{222}Rn) from rocks and soils into the atmosphere. With warming,

^{222}Rn evasion will increase, as will the deposition of lead-210 (^{210}Pb) to surfaces and the production of polonium-210 (^{210}Po), its granddaughter (Macdonald et al., 2005). Any increase in ^{222}Rn evasion due to warming/permafrost thawing would be accompanied by a widespread increase in the radioactive dose to northern residents.

11.3.2.1.1. Permafrost reduction

Permafrost thawing and the associated increase in seasonally occurring active layers above the permafrost will ultimately allow the release of previously stored anthropogenic contaminants through migration (Dyke, 2001), as well as an increase in microbial transformation. Contaminants previously immobilized in permafrost for many decades will eventually be reactivated and introduced into the Arctic food web. Klaminder et al. (2010) found that thawing permafrost promoted lead (Pb) migration out of soils and into two lakes. Lead was emitted from gasoline combustion processes and continuously transported into the Arctic via the prevailing winds over many decades (from the early 1900s to the 1980s), and is still considered a significant anthropogenic pollutant in the Arctic. The elevated levels of Pb together with higher $^{206}\text{Pb}/^{207}\text{Pb}$ ratios observed in sediments deposited after the 1970s showed that the more than 90% reduction in atmospheric deposition of Pb since the 1990s has not yet been realized within the lake due to an increased supply of Pb from drainage basin storage owing to thawing permafrost.

11.3.2.1.2. Changing characteristics of snow cover and glacier meltdown

Processes in the snowpack directly affect concentrations of gases and contaminants in the Arctic troposphere (Wania et al., 1999; Daly and Wania, 2004; Domine et al., 2007; Hansen et al., 2008; Meyer and Wania, 2008; Meyer et al., 2009a,b). The snowpack is a reservoir for semi-volatile organic contaminants, sequestered from the atmosphere during the winter and released either to the atmosphere or to aquatic systems during spring (e.g., Halsall, 2004; Domine et al., 2007). Due to colder temperatures, the High Arctic snowpack has a higher surface area index ($\sim 2500 \text{ m}^2/\text{m}^2$) than sub-Arctic regions ($\sim 1000 \text{ m}^2/\text{m}^2$), therefore providing a greater capacity to retain sorbed contaminants. Warming of the High Arctic will reduce the snowpack index, thus reducing the efficiency of air-to-surface transfer for more volatile pollutants (Taillandier et al., 2006; Domine et al., 2007). How this change in snowpack structure would be offset against predicted increases in snowfall for some parts of the Arctic is unclear. Nonetheless, surface wastage of permanent snowpack may lead to a considerable pulse of persistent contaminant concentrations into the ambient air (troposphere) or the water, depending on the exact circumstances of melting and the properties of the contaminant in question (see also Chapter 4, Section 4.4.3.4).

Recent studies conclude that ice on glacier surfaces contains considerable amounts of POPs, current-use pesticides and Hg (Donald et al., 1999; Hermanson et al., 2005; Maggi et al., 2006; Bogdal et al., 2009; Faïn et al., 2009; Chapter 7, Section 7.7.3.5). Where there are industrial sources nearby, higher loadings may occur for particular chemicals such as metals (e.g., Chizhova, 2005). Deposited contaminants, once buried beneath the firn, would normally follow the glacier ice, entering

meltwater centuries (from active glaciers) to millennia (from ice caps) after being deposited. Recent accelerated ablation of surface ice during summer is now releasing some of this archive (e.g., Blais et al., 2001; Gieisz et al., 2008) to become available for uptake into local food webs.

11.3.2.1.3. Changing ice cover on lakes and rivers

Reduction in ice cover on lakes may alter contaminant pathways in at least four ways, including: changing the interaction between inflow and lake stratification (Semkin et al., 2005); enhancing the production of sinking organic carbon leading to contaminant burial (Outridge et al., 2007; Carrie et al., 2010; Gantner et al., 2010); increasing photodegradation (e.g., Hammerschmidt and Fitzgerald, 2006); and enhancing air-water exchange (Macdonald et al., 2005). Furthermore, thawing of permafrost in the drainage basin together with a greater frequency of extreme events like floods will augment the input of soil, which may contain previously deposited contaminants (e.g., Klaminder et al., 2010). Fluxes of Hg and dissolved organic carbon, which tend to increase with river flow (Stanley et al., 2002), will also increase in northern rivers if flows become more variable, even if the average flow remains constant. Most of these changes lead to greater supply of contaminants to lakes and greater retention in deep water or sediments. For Hg (Semkin et al., 2005) and perfluorinated compounds (Veillette et al., 2009) it has been shown that over half of the contaminant load in inflowing water shunts through the lake to the outflow if the lake is ice-covered and if there is stratification ($<4^{\circ}\text{C}$ water) beneath the ice. Loss of ice cover and breakdown of thermal stratification, projected to occur increasingly earlier in the year along with loss of ice, lead to greater mixing of inflowing water into the lake. Furthermore, greater turbidity (and density) of inflowing water, a result of more extreme freshets, may also favor entrainment into affected lakes. Other cryospheric changes, including the melting of permanent snow and ice, may produce temporary increases in loadings from contaminants (POPs, metals, radionuclides) deposited from earlier periods of high use, for some compounds more

than 60 years ago (Klaminder et al., 2008; Faïn et al., 2009; Rydberg et al., 2010).

11.3.2.2. Air-sea exchange

The global distribution of p,p' -DDT (1,1,1-trichloro-2,2-bis(4-chlorophenyl)ethane) and its major transformation products, as projected by a coupled ocean-atmosphere model (Stemmler and Lammel, 2009), illustrates the potential for surface oceans to store DDT, transport it northward, and re-release it to the atmosphere. The delayed DDT pulse that arrives in northern waters is influenced by ice cover and water temperature, and these parameters ultimately determine whether the DDT will be volatilized and subsequently taken up by Arctic biota.

The efficacy of the air-sea exchange in Arctic water is governed by ambient temperatures (atmosphere and ocean) and ice coverage. The consequences of vastly reduced ice cover over much of the western Arctic Ocean during the past decade (Stroeve et al., 2007) will be increased evasion of (semi)-volatile contaminants presently trapped below the ice. HCHs are especially prone to this change (e.g., Li et al., 2004). High loadings that accumulated in surface waters of the Arctic Ocean during the 1970s and 1980s are now re-entering the atmosphere due to the sharp reductions in emissions and, consequently, reduced air concentrations (Bidleman et al., 2007). Because there is a relatively large inventory of HCH in the ocean, the removal of ice cover allows the oceanic HCH to enter the atmosphere rapidly through evasion. This was demonstrated near Resolute in the Canadian Archipelago by a shift in enantiomeric composition of atmospheric α -HCH from nearly racemic, implying a long-range atmospheric source of industrial HCH, to a microbially-degraded ratio matching that observed in the surface ocean (Figure 11.7). The conclusions drawn for α -HCH do not necessarily apply to other atmospherically transported POPs, especially those that have not achieved equilibrium with the water. For example, in the case of PCBs or endosulfan (which have not achieved equilibrium with the surface Arctic Ocean) the loss of ice would promote more rapid invasion into water (Macdonald




Figure 11.7. Average air concentrations and enantiomer fractions for α -HCH at Resolute Bay, Canadian Archipelago, before and after ice break-up (Jantunen et al., 2008).




Figure 11.8. Temporal trend analysis for hexachlorobenzene (HCB) in air at the Zeppelin research station (Spitsbergen) using statistical digital filtration. Note: concentration values are given in a logarithmic scale. Source: Hung et al. (2010).

et al., 2000b; Weber et al., 2006; Gioia et al., 2008).

Within the Arctic, trends and concentrations of POPs in the atmosphere during the past ten years have varied regionally (Hung et al., 2010). For HCB, formerly used as a fungicide but now released to the environment predominantly as a by-product of industrial chemical processes, generally downward trends were reported at all Arctic stations. However, during the past four years, levels at the Zeppelin station (Spitsbergen) have been increasing (Figure 11.8).

Increasing air concentrations of HCB, observed only at the Zeppelin station, may partly be explained by increased evasion from the ocean along the western coast of Spitsbergen (Svalbard, Norway), which has been ice-free throughout winter between 2005 and 2009 (Slubowska-Wodengen et al., 2007; Nilsen et al., 2008). A permanently ice-free state at 80° N is unusual and although the evasion of HCB could be interpreted as a manifestation of regional climate change on the POPs distribution in the Arctic, dramatic loss of ice elsewhere in the Arctic Ocean (e.g., Stroeve et al., 2008) implies that exchange has been widely affected in the Arctic Ocean for most POPs. Alternatively, increased air concentrations of HCB may be due to the presence of HCB as an impurity in currently used pesticides in some European countries (Becker et al., 2009; Lohmann et al., 2009).

The Hg cycle in the Arctic Ocean may also be affected by reduced ice cover. The Hg concentration in the upper ocean is the result of a dynamic balance between Hg deposition and Hg evasion (Outridge et al., 2008). The entry of Hg into the ocean from the atmosphere requires conversion of Hg(0) to Hg(II), which can then deposit into water on particles, in contrast to the evasion of Hg, which occurs predominantly via gaseous exchange of Hg(0). One of the deposition processes for Hg – ‘atmospheric mercury depletion events’ – involves halogen chemistry in the atmosphere initiated by solar radiation at polar sunrise (Steffen et al., 2008). Here, the balance between first-year ice, snow and open ocean is critical to the deposition process. On the other hand, photoreduction of Hg(II) in the water produces an excess of Hg(0), which then supports net evasion, provided there is open water (Andersson et al., 2008). Because ice cover interacts with invasion and evasion of Hg differently, the loss of ice cover has the capacity to change the

quantity of total Hg held in the upper ocean, and the balance between forms of Hg.

11.3.2.3. Transport by sea ice

Transpolar ice-drift is known to re-distribute contaminants released from the large eastern Arctic rivers in Siberia (Arctic Russia) or contained in sediments over the Siberian shelves (AMAP, 1998). Recent change in the Arctic has increased the areas over which first-year ice is produced (e.g., Kwok et al., 2009) and the amount of open water exposed to storms in the autumn, and is therefore likely to have impacted the entrainment of sediment into ice by suspension freezing, by removing large areas of multi-year ice. Simulations of contaminant transport by ice using a 3D model (Pavlov, 2007) have investigated the potential for contaminants located in the vicinity of river mouths of major rivers flowing into the Arctic Ocean to be transported elsewhere during the 15 years following release (Figure 11.9).

Recent studies (Hakkinen et al., 2008; Pavlov and Pavlova, 2008) have shown an increase in sea-ice drift velocities in the Arctic Ocean over the past three decades, which leads to the intensification of surface currents in the drifting ice. Thus, a higher contamination risk from ice transport is implied, since water masses previously moving along the potential source regions of western industrialized countries are now expected to be reaching the Far North more rapidly as previously described due to the increased velocity of the inflow into the Arctic Ocean. Countering this argument, Karcher et al. (2010) suggested that with the reduction in ice cover, especially in summer, the importance of sea ice will decline as a transport medium for radionuclides from atmospheric fallout or in association with resuspended sediment. Overall, it is considered that the Arctic will tend to trap a greater proportion of its radionuclide inventory within the Arctic.

11.3.2.4. Contaminant change in marginal ice zones

The marginal ice zone (MIZ) comprises a circumpolar band of flaw leads north of the landfast ice. Here, stratification, supported by ice melting, and upwelling create the circumstances for primary production to occur from June to August. The organic




Figure 11.9. Distribution of pollutant concentrations in the surface layer of the Arctic Ocean 15 years after release from sources in the mouths (model assumption) of the major Arctic-flowing rivers: (a) Ob and Yenisey Rivers; (b) Lena River; (c) Kolyma River; and (d) Mackenzie River. The scale shows the percentage of pollutant in relation to its concentration at source. Arrows show the source location. Source: Pavlov (2007).

carbon so produced is presently considered to provide the basis for survival of almost all ice-associated organisms in the Arctic marine ecosystem (Rysgaard and Nielsen, 2006; Sundfjord et al., 2007; Hegseth and Sundfjord, 2008). The consequent lipid production in the lower pelagic ice-associated food web (Soreide et al., 2008; Falk-Petersen et al., 2009) provides a reservoir for lipophilic POPs (bioaccumulation), which then transfer into higher trophic levels (biomagnification). Bioaccumulation and biomagnification together put at risk Arctic top predators such as seabirds and marine mammals (Borgå et al., 2005; Sobek et al., 2006). Reliable productivity makes the MIZ an attractive location for foraging by predators such as seabirds, whales, and polar bears. A change in the location and timing of the MIZ due to climate change therefore has potentially large consequences for where, when, and how much lipid is produced, and whether that lipid supports epontic, pelagic, or benthic communities (e.g.,

Grebmeier et al., 2006). Furthermore, change in food production is often caused by – or invites – invasive species (Hegseth and Sundfjord, 2008; Vermeij and Roopnarine, 2008). Lipophilic contaminants will closely follow the changes in lipid production and transfer in the food web. Marine animals have adapted their reproduction to historic availability of high-quality energy. Trophic mismatch due to change in seasonality, or altered energy balance due to change in forage location or favored species leads to nutritional stress, which is compounded by contaminant release from stored fat.

Increases in surface water temperature and concentrations of particulate organic carbon associated with climate change are predicted to affect the bioaccumulation of hydrophobic organic contaminants in the Arctic marine food web (Borgå et al., 2010). A net reduction in bioaccumulation was predicted for two PCB compounds, driven in the main by their reduced bioavailability

associated with increases in particulate organic carbon in the water column.

It is important to note that change in ecosystems, and consequent change in contaminant pathways within organic systems, can be effected from the bottom up, as described for the MIZ, and from the top down (Macdonald et al., 2005). In the latter, the removal of ice as a habitat for polar bears or walrus would signal a change in food-web structure with consequences for biomagnifying contaminants.

11.3.2.5. Change in foraging behavior

The transport of contaminants within large individuals (whales) or large migratory populations (fish, birds), can represent a pathway of major importance to the biota themselves (Blais et al., 2007) or to their predators, including humans, while being of negligible importance in large-scale budgets or fluxes (Wania, 1998). Cryospheric change has great potential to alter migratory pathways, for example, through invasive species encouraged by climate change (Babaluk et al., 2000), which can import contaminants from outside the Arctic, or through change in feeding locations following altered prey distributions (Gaston et al., 2003), which then alters exposures within the Arctic (Michelutti et al., 2009).

Climate impact on foraging behavior is reported across all trophic levels in marine and terrestrial food webs (Couillard et al., 2008; Laidre et al., 2008; Loseto et al., 2008; Moore, 2008; Moore and Huntington, 2008; Thiemann et al., 2008; Cherry et al., 2009; Corcoran et al., 2009; Falk-Petersen et al., 2009; Sharma et al., 2009; Verreault et al., 2010). Indigenous peoples are potentially subject to some of the greatest changes in contaminant exposure because their diets shift between terrestrial and aquatic foods (Usher, 2002) in response to changes in the distribution of the food (e.g., through migration) or changes in terrain conditions that prevent travel to favored harvesting areas (Macdonald et al., 2005). McKinney et al. (2009) concluded that polar bears from the Canadian Hudson Bay area have a modified exposure to POPs owing to a change in diet over the period 1991 and 2007. The dietary change was directly attributed to an increase in the consumption of open water-associated seal species (relative to ice-associated seal species) during years of earlier sea-ice break-up. Likewise, in the Beaufort Sea, Gaden et al. (2009) found that Hg concentrations in ringed seals depend on ice cover, presumably through the intermediary effect of ice on prey availability. These newly emerging results confirm predictions by Macdonald et al. (2005) that changes in ice conditions cascade into food webs and foraging strategy and thence affect contaminant pathways.

11.3.2.6. Change in mercury methylation

The complexity of the Hg cycle, involving transformations between Hg(0), Hg(II) and alkylated forms of Hg (AMAP, 2011a), provides great potential for change either through physical components of the system (see Section 11.3.2.2) or chemical transformations. Methylmercury (MeHg, CH₃Hg) is the most important form of Hg in relation to toxicity and capacity to biomagnify (Macdonald and Loseto, 2010). The process of methylation is directly linked to the organic carbon cycle such that change in carbon pathways due to cryospheric change (e.g., organic carbon production, carbon flux in the ocean, remineralization) have consequences for MeHg production (Cossa et al., 2009; Sunderland et al., 2009). MeHg

is usually formed by natural methylation processes of Hg(II), as reviewed in several comprehensive studies (Hammerschmidt et al., 2006; Fitzgerald et al., 2007; AMAP, 2011a). Intensification of Hg methylation/demethylation induced by climate change is a crucial aspect of the Hg cycle in all environmental systems and, perhaps, especially the Arctic given the projected changes in hydrology (soil moisture), the cryosphere (ice cover, permafrost) and the organic carbon cycle (remineralization and sulfate reduction).

Recent studies show a wide variation in Hg exposure in predatory animals (fish, whales, seals) and conflicting temporal trends in Hg concentrations in tissue (AMAP, 2011a). These biological trends cannot simply be linked to recent atmospheric Hg trends, which are relatively stable, and must, therefore, result from processes within the biogeochemical cycle in the Arctic (Macdonald and Loseto, 2010). In the case of seals from the Beaufort Sea, Gaden et al. (2009) proposed that changes in ice cover contribute a non-linear trend in tissue Hg caused by shifts in foraging strategy. Likewise, increases in Hg and PCB observed in Mackenzie River burbot *Lota lota* collected near Fort Good Hope (Carrie et al., 2010) have been assigned to increases in primary production that are likely to have been supported by declines in ice cover and/or increases in temperature.

In models, Hg concentrations in fish often respond directly to atmospheric deposition of Hg (Knights et al., 2009), a finding supported by the results of adding isotope-labeled Hg to the drainage basin of an experimental lake (Harris et al., 2007). Newly deposited Hg took a shortcut route to the biota. Modeled response times for Hg in predatory fish varied across ecosystem types and were highly affected by sediment burial rates and active layer depths when the system was not dominated by inputs from the watershed. These results emphasize the importance of intermediary cryospheric processes – the ones presently undergoing rapid change – in controlling the exposure of aquatic biota to Hg deposition, past or present.

11.3.2.7. Change in weather patterns

The Northern Annular Mode (Wallace and Thompson, 2002) and related indices such as the North Atlantic Oscillation (NAO) and Arctic Oscillation (AO) have been used to understand decadal-scale variability in northern hemispheric wind speed/direction and precipitation (Becker et al., 2008, 2009). As reported in Chapter 2 (see Figure 2.5), during the past decade, the AO has been on average in a neutral phase, but with considerable variation shifting between positive and negative phase.

Air concentrations of HCH measured at the Zeppelin research station on Svalbard correspond well with variations in the AO over the past decade, showing stronger variations in concentration, but generally declining with time (Figure 11.10). This signal could not be found in data generated at the Alert Station on Ellesmere Island, north-eastern Canada. The Zeppelin station is obviously strongly influenced by the marine environment. Thus, this relationship, confined to the ocean-influenced site (Zeppelin), implies that ice cover together with atmospheric pressure patterns (winds) contribute substantially to atmospheric POPs variability. If Shindell et al. (1999) are correct in proposing that climate change may manifest itself in more frequent AO positive states, then such a change implies a shift in the relationship between atmosphere and ocean for some POPs.




Figure 11.10. Influence of the Arctic Oscillation on the atmospheric distribution of α -HCH in Zeppelin air data. The DHR model fit is represented by the R^2 value and uncertainty is to within 95% confidence limits. Dashed lines represent the expected differences between summer and winter concentrations assuming a constant decline. Source: Becker et al. (2008).

The differences in intra-annual distribution patterns indicate that much larger concentration variations between summer and winter months are occurring in years when the AO is negative (after 2000).

11.3.2.8. Invasive species and the Arctic food webs

A nearly ice-free summer is now considered likely for the Arctic Ocean by mid-century (see Chapter 9). This would have considerable consequences for the local marine ecosystems as it will allow the northward movement of more southerly species that will compete with indigenous species for habitats and food resources. The indigenous, more sensitive Arctic species (such as crustaceans and fish), will eventually be marginalized. Invasive species can alter risk from contaminants in several ways, including: alteration of lower food webs, thus changing carbon production and flow (Macdonald et al., 2005); alteration of availability of prey species, thus changing the net energy obtained through foraging (Gaston et al., 2003); and alteration of migratory pathways that supply contaminants through biovectors (Blais et al., 2007). Migration ranges of non-Arctic commercially exploited fish species (Atlantic cod, mackerel, capelin, etc.) that currently approach Arctic waters (Drinkwater, 2005; Feehan et al., 2009; Huse and Ellingsen, 2009; Opdal, 2010) will extend into the Arctic with warming, potentially displacing indigenous species (Macdonald et al., 2003). Other species may also enter the Arctic because thermal or ice barriers have been removed, or because they have been brought in through increased shipping (Occhipinti-Ambrogi, 2007). This alteration to foraging and feeding habits of top predators (e.g., Loseto et al., 2008; Lindstrom et al., 2009; Post et al., 2009) will alter the pathways and biomagnification of POPs and MeHg.

Terrestrial food webs can also be affected by invasive species and shifts in species migration patterns (Feehan et al., 2009; Prowse et al., 2009b; Sharma et al., 2009). Many non-Arctic bird species migrate into Arctic habitats (Henningsson and Alerstam, 2008). The Arctic presently appears poised for invasion (Vermeij and Roopnarine, 2008), which suggests that monitoring and ecosystem studies are urgently required (Fox et al., 2009; McKinney et al., 2009; Michelutti et al., 2009).

11.3.3. Impact of cryospheric change on local sources of contaminants in the Arctic

11.3.3.1. Thawing permafrost

In regions of permafrost in the Arctic, historical disposal of wastes has occurred in the form of sewage lagoons, dump sites at DEW (Distant Early Warning) line installations, solid waste dumps in small communities, and oil drilling sumps (Macdonald et al., 2005). The permafrost itself is a large component of the containment strategy at these sites. With permafrost degradation, however, contaminants contained in these sites can be washed into rivers or the ocean or leached into the local soil and groundwater, possibly contaminating drinking water. Sub-permafrost water resources and surface lake systems, often used as drinking water sources, may also be directly influenced by thawing permafrost (Kokelj et al., 2009; Haldorsen et al., 2010). This will also include remobilized anthropogenic and biogenic contamination (ACIA, 2005).

Disposal of PCBs in landfills and dumpsites has received significant attention at DEW line sites across Arctic Canada (e.g., Brown et al., 2009). Recently, polybrominated diphenylethers (PBDEs, flame retardants present in household items, electrical goods, etc.) have been found at high concentrations in soils around dumpsites in Cambridge Bay and Iqaluit in Arctic Canada (Danon-Schaffer et al., 2008). Permafrost thawing has the potential to release these contaminants into aquatic systems.

In Canada, since the mid-1990s climate change has been incorporated into the design of waste-containment structures that depend on the encapsulation of wastes in permafrost to contain mine tailings or similar waste (Chapter 5, Section 5.4); however, some of the older sumps, such as those used in the past to store process water and drilling fluid from oil and gas exploration activities in Arctic regions, have been found to be leaking (AMAP, 2010). There are around 300 to 400 of these sumps in northern Canada, while around 700 oil and gas production and exploration sites in Alaska have onsite drilling waste disposal pits (AMAP, 2010). There are

no current estimates of the use and number of oil pits in Russia. The use of pits in Alaska has largely been phased out and replaced by down-hole injection of wastes, while old pits containing oil-based drilling mud are being remediated.

Oil and gas pipelines in the Arctic are also vulnerable to permafrost degradation and thawing. Although studies of the permafrost-related performance of pipelines in Alaska and northern Canada have found the integrity of these pipelines to be robust to climate change, the situation in Russia is different (Chapter 5, Section 5.3.5.1.2). Above-ground pipelines in Russian permafrost areas have been affected by the thawing of ice-rich soils and uplift of pipeline foundations due to frost heave. In the 350 000-km long network of pipelines in Siberia, about 31 000 failures are registered each year, more than 20% of which are probably due to deformations and weakening of foundations induced by permafrost thaw. The world's largest terrestrial oil spill occurred in 1994 when multiple breaks occurred in a pipeline in the Komi Republic, contaminating a large area of land and two river waterways. Uneven ground settlement due to permafrost thaw and thermokarst is likely to have contributed to the breakage. Whether recent warming played a role might be difficult to establish, but projected increased thaw in the Arctic will only lead to greater risk in the future.

11.3.3.2. Exploitation and transportation activities in the Arctic

With decreased ice coverage of marginal sea areas of the Arctic for longer periods of the year, shipping routes between Europe, Asia, and North America will open up either via the Northern Sea Route (Russia) or the Canadian Archipelago. Shipping will introduce various contaminants, such as hydrocarbons and antifouling chemicals (e.g., diuron, tributyltin), exhaust fumes from the combustion of ships' fuel, and possibly also non-indigenous species on ships' hulls and in ballast water (Macdonald et al., 2005). There will also be increased risk of accidents that could result in oil spills from tankers. The environmental hazards associated with increased ship movements across the Arctic have been assessed in a review by Huntington (2009). The author stated that during the next several decades, Arctic marine mammals will face threats from six areas of human influence: climate change, environmental contaminants, offshore oil and gas activities, shipping, hunting, and commercial fisheries. Increased tourism (i.e., cruise ships and airborne transportation) is an additional threat for the Arctic environment. The potential contamination risks of increased offshore industrial activities in the Arctic were identified as much as a decade ago (Klungsøyr et al., 1995; Macdonald and Bewers, 1996). The decrease in marginal sea ice will open up the possibility for oil and gas exploration on the Arctic continental shelves of North America and Eurasia, resulting in a risk of oil spills from offshore platforms and the increased tanker traffic carrying oil to market. There are no effective means of cleaning up oil spills in broken ice and responding to such spills in winter would presently be impossible, given limited daylight and harsh weather (AMAP, 2007).

Karcher et al. (2010) highlighted the likely intensification of risks from artificial radionuclides released within the Arctic as a consequence of reduced ice cover. Russia has plans to develop

floating nuclear power systems for potential use within the Arctic; transport of such systems to and from the Arctic and the handling of waste products are of obvious concern. Likewise, the reduced cost of shipping via the Arctic applies equally to shipping nuclear materials and/or the number of ships with nuclear propulsion systems.

Although the ice may clear from substantial areas of the Arctic's marginal seas annually, ice cover will still accumulate in winter and winds will produce pressure ridges and keels. Large open areas where occasional patches of thick ice and icebergs are free to drift in summer might make the Arctic a more dangerous place to navigate.

11.3.4. Future research priorities

With respect to cryospheric change and potential impact on pollution patterns and distribution, the major future challenges are expected to encompass the following five research priorities:

1. The influence of change in ice distributions (areal and seasonal) on the introduction, distribution, accumulation and transformation of anthropogenic pollutants (sources and sinks). This includes sea ice, glacial ice, and permafrost.
2. The potential for new contaminants or re-introduced contaminants to be sequestered in the Arctic by changes in Arctic hydrology, ice cover and vegetation.
3. The potential for complex contaminant mixtures to exert an effect on humans or wildlife as a consequence of nutritional or other stresses brought on by cryospheric changes such as difficulty to access food or change in available food (invasive species, altered migrations).
4. Change in exposure pathways for contaminants owing to industrial development in the Arctic, expansion of Arctic communities and increased shipping through Arctic waters due to more suitable ice conditions for shipping.
5. Increased coordinated observing systems where contaminants are measured within the context of other physical changes (temperature, winds, ice conditions, seasonality, hydrology, etc.).

11.3.5. Future perspectives

The scenario descriptions in the concluding reports of the Arctic Climate Impact Assessment (ACIA, 2005) and the Intergovernmental Panel on Climate Change (IPCC, 2007) allow a first-approximation assessment of the future challenges associated with pollutant transport and distribution related to climate change in the Arctic (Macdonald et al., 2005). However, the scenarios now appear conservative compared to the real-world developments that have taken place in recent years and should, therefore, be updated before comprehensive studies of the effects of climate change on contaminant loads in the Arctic are performed. Technological developments within the field of analytical chemistry leading to new instrumentation that allows the quantitative detection of ultra-trace levels of hitherto unknown contaminants will inevitably lead to the identification and quantification of many new Arctic contaminants. An important perspective to maintain is that action to mitigate climate change might

also help to mitigate contaminants. An example would be the double threat of high atmospheric CO₂ levels and Hg emissions from the combustion of coal where reduction of CO₂ emissions will also lead to reduced Hg emissions. Future scenarios envisaged:

- Increased industrial activity, transport across the Arctic Ocean and offshore activities in the Arctic (due to continuous reductions in sea-ice extent in the central Arctic) will lead to significantly more potential local contaminant sources.
- The lack of sea-ice cover in the central Arctic Ocean will lead to increased summer evasion of some (semi)-volatile POPs (e.g., HCH) and increased deposition of others (e.g., PCBs, currently used pesticides).
- Change in the amount, composition and duration of snow will alter the deposition and transfer efficiency of contaminants.
- Ice-associated fauna will change and new marine species (fish, crustaceans, other invertebrates, etc.) will shift northward into the central Arctic basin, serving as contaminant carriers and altering the food-web structure with consequences for biomagnification of POPs and Hg into top predators. Change in ice and permafrost will alter foraging opportunities for wildlife and humans, thereby altering exposure to biomagnifying POPs and Hg.
- The human population of the Arctic will increase due to new working opportunities (e.g., offshore oil and gas activities, mineral exploitation) and with this will come additional domestic and industrial sources of contaminants. New chemicals will inevitably enter the Arctic environment.
- New analytical instruments will be developed that allow increasing numbers of chemicals to be detected at ever lower detection limits, permitting the development of longer and better time series in virtually all environmental compartments of the Arctic.

11.3.6. Conclusions

Within the Arctic, it is evident that the levels and distributions of contaminants are influenced by cryospheric change from the local to regional scale and that these changes are directly linked to the changing climatology of the Arctic region. With the loss of ice and frozen soil, former contaminant sinks have become sources for legacy contaminants such as POPs and Hg. Exchange between air and water is increasing, causing increased evasion of some contaminants (HCH, Hg(0)) and increased deposition of others (PCBs, endosulfan). Models of atmospheric POPs transport clearly show the influence of climatology (e.g., MacLeod et al., 2005). The expected increase in human activities in the Arctic, will promote the introduction of new chemicals and point sources within the Arctic. Increased human activity in ice-free areas over longer seasons, especially those activities concerned with offshore oil exploitation and shipping, increase the risk of oil spills. Increased thawing of permafrost and soil instability will require greater attention to ensuring the containment of contaminants in sewage lagoons, tailings ponds, and dumps, and the structural stability of pipelines traversing permafrost.

11.4. Impacts of changing snow, water, ice and permafrost on Arctic ecosystems

11.4.1. Introduction

The Arctic region contains a remarkable diversity of habitats and associated ecosystems, from mountain glaciers and ice caps to tundra, inland waters and icy seas. Many of the ecosystems are interdependent, and changes in climate are beginning to have not only direct effects on the ecology of these environments, but also indirect effects through the physical and biological coupling between them (Box 11.2). These impacts will have direct consequences for humans living in the North via changes in ecosystem services, and indirect consequences elsewhere, for example via changes in global biodiversity, biogeography and biogeochemical fluxes. The shifts in Arctic ecosystem structure and dynamics are also resulting in a variety of feedback effects that may accelerate their rate of change (see Section 11.1). This section summarizes information from the preceding chapters to provide a synthesis of how climate-dependent alterations in snow, water, ice and permafrost are affecting and will increasingly affect the ecology of the Arctic, including potential impacts via the linkages between ecosystems.


11.4.2. Snow

The extent, quality and duration of snow cover, exert a controlling effect on ecosystems throughout the Arctic (Chapter 4). There are large interannual fluctuations in each of these snow-related factors, and the observed responses to this natural variability, in addition to the results of controlled snow-manipulation experiments and longer term paleo-ecological records, are providing insights into how Arctic ecosystems may continue to respond to climate forcing. Over the past 40 to 50 years there has been an overall trend of increasing winter precipitation in the Arctic accompanying the warming air temperatures that have been observed, however there is large spatial variability in current and projected future trends, and thus the ecological responses can also be expected to vary among regions. Global climate models predict that there will continue to be large differences in precipitation trends among regions, with decreases in snow water equivalent (SWE) over Scandinavia and Alaska, no change in SWE over the boreal forest region, and increased SWE over northern Siberia (by 15–30%) and the Canadian Arctic Archipelago (Brown and Mote, 2009). There is a consistent projected trend, however, of decreased snow cover duration (SCD) throughout the Arctic, with the greatest changes predicted to be over the more southerly regions (Brown and Mote, 2009). The ecological effects of these pronounced changes may be compounded by a shift toward increasingly frequent episodes of winter melting that cause surface ice crusts over the snowpack, although basal ice layers that also impede animal foraging may become less frequent given the progressively shorter duration of snow cover.

In the terrestrial environment, changes in snow cover have wide-ranging ecological effects on soil, plant and animal communities, as well as downstream effects on lakes, rivers and wetlands (see Section 11.4.3). Snow is a habitat for diverse microbial communities including snow algae and associated

Box 11.2 From land to sea: ecosystem coupling between the Mackenzie River delta and the adjacent Arctic Ocean

Arctic ecosystems will continue to experience the impacts of climate change on snow, water, ice and permafrost, not only in their immediate environment but also via the adjacent ecosystems to which they are physically or biologically coupled. For example, decreasing occurrence of ice jams on the Mackenzie River (Canada) are resulting in less flooding of higher elevation lakes and wetland communities within the flood plain delta (Lesack and Marsh, 2007; see also Chapter 6, Figure 6.20). These ecosystems contribute to nutrient and organic carbon exchange processes that ultimately affect the biogeochemical characteristics of Mackenzie River water discharged to the coastal ocean (Emmerton et al., 2008). This reduced connectivity between lakes and the river may also limit habitat availability for fish populations migrating to and from the sea.



Water, particulates and dissolved materials exported from the terrestrial catchments of large Arctic rivers, including from permafrost soils, vegetation, and wetlands, are initially retained behind ice dams or stamukhi formed by ice convergence in the coastal environment (see also Chapter 6, Figure 6.21). These ephemeral lagoons such as the stamukhi-dammed waters of 'Lake Mackenzie' appear to have distinct microbial communities and are biogeochemical processing sites for terrigenous materials prior to their sedimentation to the marine benthos or discharge to the ocean (Galand et al., 2008). Changes in the duration and magnitude of these ice dams relative to shifts in the timing and magnitude of peak discharge of the river are likely to influence the export of material to coastal Arctic ecosystems. The land-fast ice and dams also form the landward edge of the band of open water that persists throughout the winter, creating the circum-Arctic flaw lead ecosystem.

Figure 11.11. MODIS satellite image taken in June 2004 of the Mackenzie Shelf region. The delta lakes have been flooded by the seasonal peak discharge of the Mackenzie River. The thick ice ridge parallel to the coast (stamukhi) has begun to break up, releasing turbid river water into the sea. Reproduced from Fortier et al. (2008).

bacteria and fungi (Jones et al., 2001; Harding et al., 2011). These organisms provide organic carbon and nutrients to the soil during snow melt. Snow also acts as an insulator for Arctic soils, and increased snow depth (predicted for the High Arctic) may result in warmer winter soil temperatures, increased biogeochemical processing of organic materials, and increased respiration. For example, in the Swedish sub-Arctic an extra 20 to 30 cm depth of snow (added to the 74 and 27 cm of snow over birch and heath vegetation, respectively, at the time of maximum snow accumulation) resulted in a 77–157% increase in ecosystem respiration rates (Larsen et al., 2007). Also, in High Arctic Canada an experimental increase in snow depth over birch hummock tundra from 30 cm (the natural snowpack depth) to 100 cm (achieved with snow fences) resulted in a 60% increase in carbon dioxide (CO₂) efflux rates (Nobrega and Grogan, 2007).

Many Arctic plants, especially lichens and bryophytes, become physiologically active even before the overlying snow completely melts. However, this competitive advantage may be lost with the earlier disappearance of snow, and the longer, warmer growing season may favor the invasion of plants from more southern latitudes. Extreme warming events during winter can result in the sudden loss of protective snow over vegetation and cause a range of damage including mortality of buds and shoots, delayed bud burst in spring, and reduced flowering (Bokhorst et al., 2008). Such effects may result in decreased rates of primary production and may partially offset the increases in productivity associated with shrub expansion across the Arctic (Bokhorst et al., 2009). These thaw events can result in the loss of winter dormancy, which renders the

plants and their roots vulnerable to damage during subsequent freezing of snow-free ground (Beier et al., 2008).

Snow cover has a strong effect on the ecology of Arctic animals, throughout winter for resident species and at the time of arrival for migratory species. For the latter, small changes in the duration of snow cover can translate into large changes in breeding success. For example, studies on pink-footed goose *Anser brachyrhynchus* show that a 10% decrease in snow cover duration can advance egg-laying by 5 to 6 days, resulting in a 20% increase in breeding success (Madsen et al., 2007). The end date of snow cover directly affects the duration of the growing season for plants and therefore the food resources available to Arctic herbivores. For example, reindeer *Rangifer tarandus* calf production in Finland has been shown to increase by almost 1 calf per 100 females for each extra day of the snow-free season (Turunen et al., 2009). Positive effects of longer growing seasons in recent years have also been observed for musk ox *Ovibos moschatus* populations in northeastern Greenland (Forchhammer et al., 2008). On Ellesmere Island, Canada, years of extensive snow cover in the past have resulted in reduced vegetation growth and reduced herbivore populations (musk ox and Arctic hare *Lepus arcticus*), which in turn resulted in reduced populations of Arctic wolves *Canis lupus arctos* that prey on the herbivores (Mech, 2004).

Snow quality also has an effect on animals. The formation of surface and basal ice-crusts can drastically reduce the availability of the underlying vegetation to herbivores (see Section 11.4.3 for examples). The overall hardness of the snowpack can affect the availability of subnivean space for rodents, and the resultant

changes in their populations can have indirect effects on other species used as alternate prey by their shared predators (Kausrud et al., 2008). The nutrient and organic carbon content, acidity, and contaminant load are also likely to influence the ecological effects of Arctic snow, particularly on soils and vegetation, and on downstream ecosystems such as lakes and wetlands, including thermokarst ponds that are extremely abundant throughout the circumpolar North. Growth of brown trout *Salmo trutta* in alpine lakes of western Norway was negatively correlated with spring snow depth (Borgstrom, 2001), presumably as a result of effects on water temperature, nutrient levels and lower-trophic level productivity. Thus, in addition to direct effects on runoff, snow accumulation in concert with lake ice shifts is also likely to alter ecological processes in Arctic lakes.

11.4.3. Water

The availability of liquid water is a fundamental requirement for life, and shifts in freshwater supply through climate change have direct and indirect effects on all Arctic ecosystem types and the ecological linkages between them. Water availability rather than temperature appears to be an increasingly limiting factor for the northward progression of the treeline, with previous trends of positive tree growth now appearing to be weaker, non-existent, or even reversed as a result of temperature-induced drought (Wilmking et al., 2005). These observations imply that the treeline will advance over the course of this century in a non-uniform way, colonizing only those parts of the landscape where there is sufficient moisture (Chapter 4). Many Arctic aquatic ecosystems have begun to show shifts in water balance, in some cases leading to the complete drainage or drying-up of lakes and wetlands. The degradation of permafrost soils in Siberia has resulted in collapse, drainage and complete disappearance of many water bodies (Smith et al., 2005), while elsewhere in the Arctic, permafrost thawing over the past 50 years has created new basins and increased development of shallow water ecosystems (Payette et al., 2004; Walter et al., 2006). These thaw lakes and ponds are important wildlife habitats, as well as biogeochemical ‘hot spots’ in the landscape where greenhouse gases are produced and ventilated at high rates to the atmosphere (Walter et al., 2006; Laurion et al., 2010). A shift in the precipitation-evaporation balance in parts of the High Arctic has resulted in the complete drying-up of shallow ponds in some rock basins, perhaps for the first time in millennia (Smol and Douglas, 2007a). Late-lying snow banks are an important source of water for wetlands (Woo and Young, 2003). Semi-aquatic ecosystems are therefore vulnerable to the ongoing trend of decreased snow cover duration, and desiccation of wetlands has been observed at a number of Arctic sites (e.g., Vincent et al., 2009).

Warmer Arctic temperatures will be accompanied increasingly often by a shift in precipitation from snow to rain, with many ecological consequences. For example, rain tends to favor broadleaf over conifer tree species, which in turn may decrease carbon storage, increase soil respiration, and reduce the timber potential of the forest (Chapter 4). Sudden rains during winter can result in a rapid loss of protective snow cover that makes the vegetation more vulnerable to freezing damage (see Section 11.4.2). Rainfall over snow cover can also result in the production of surface crusts of ice that prevent herbivores from accessing the underlying vegetation. For example, a rain-

on-snow event on Banks Island in the Canadian Arctic resulted in a thick layer of ground ice; these conditions are thought to have resulted in the death of 20 000 musk ox (Rennert et al., 2009). Major declines in Peary caribou *Rangifer tarandus pearyi* in the Canadian Arctic Archipelago have also been attributed to unfavorable snow or ice conditions (Miller and Barry, 2009). The negative effects of ice-crusts associated with rain on snow are well known to reindeer herders in Fennoscandia, and there are increasing frequencies of such events in some regions. The shift from snow to rain will also affect marine and freshwater ecosystems. Snow provides a highly reflective surface that greatly reduces the penetration of light for photosynthesis in the planktonic communities within and beneath ice (Vincent and Belzile, 2003) and rainwater saturation of snow will greatly increase under-ice irradiance, as well as hasten melting of the remaining snow and ice.

Arctic freshwaters provide important migratory routes for fish, and changes in climate may alter the connectivity among lakes and river channels, as well as the physical coupling to the coastal marine ecosystem. Glacier-fed rivers are showing sustained periods of higher discharge associated with the increased duration and intensity of melt under a warmer climate (Chapter 7), and this provides more favorable habitats for some invertebrate and fish species (see Section 11.4.4.2). Increasing discharge has also been observed in the large Siberian rivers, with record flows in 2007 (Shiklomanov and Lammers, 2009). The changing freshwater content of the Arctic Ocean is likely to have a variety of effects. Increasing flow from Arctic rivers may bring increased nutrients and allochthonous (external) organic matter that stimulate processes at the base of marine food webs. However this water, combined with the effects of melting sea ice, may reduce the salinity of the Arctic Ocean mixed layer, thereby intensifying stratification. Over recent years, freshening of the Arctic Ocean surface waters has been accompanied by a shift in phytoplankton toward small-celled species (picophytoplankton, especially a cold-water ecotype of *Micromonas*; Lovejoy et al., 2007) that are more competitive in stratified nutrient-poor conditions. This cellular carbon is much less efficiently transferred within marine food webs than that associated with diatoms and other large cells, and the resultant changes may therefore alter organic carbon export to fish communities and to benthic ecosystems (Li et al., 2009).

11.4.4. Ice

11.4.4.1. Greenland Ice Sheet

The Greenland Ice Sheet has long been recognized as a habitat for microbial ecosystems associated with sediment accumulation and ephemeral melt pools. These cryoconite (cold rock dust) communities are dominated by nitrogen-fixing cyanobacteria that are darkly pigmented with UV photoprotectants (Vincent, 2000 and references therein), and may become more widespread over the ice as the Arctic climate warms. Runoff from the melting ice cap provides substantial water, nutrients and probably organic carbon to coastal environments around Greenland, and increased fluxes may affect marine food webs. Changes in iceberg fluxes from the ends of ocean-terminating glaciers may influence benthic communities through ice scouring, and cause local changes in

the surrounding environment. The effect of increased melting of the Greenland Ice Sheet on the adjacent marine ecosystems remains little explored, and is an important priority for future research (Chapter 8).

11.4.4.2. Glaciers, ice caps and ice shelves

Arctic glaciers provide a habitat for cryoconite microbial communities, as well as water supplies for streams, rivers, wetlands and the coastal ocean. From the 1990s onward, there have been increasing rates of mass loss from glaciers in Alaska, the Canadian Arctic, and Iceland, and this trend is likely to continue over the next few decades (Chapter 7). In the medium-term, ongoing increases in discharge, especially winter flows, may stimulate benthic invertebrate diversity (e.g., Milner et al., 2008) and enhance salmonid populations (e.g., Fleming, 2005). In the longer-term, with glacial shrinkage and declining discharge, there will be change in fluvial habitats, including the opening up of new streams in the landscape caused by large-scale glacial recession (Milner et al., 2008). Higher temperatures are likely in the absence of glacial meltwater inputs, which are likely to favor declines among cold-water salmonids (e.g., Matulla et al., 2007), and the invasion of warm-water taxa from the south. Changes in runoff volume will also influence the coastal environment, with potential effects on currents, nutrient supply, marine productivity and fisheries, and the eventual retreat of tidewater glaciers will result in loss of the productive glacier-front habitat for marine birds and mammals (Chapter 7).

Unusual ice features in the Arctic and their associated microbial ecosystems are likely to become extinct through ongoing climate change (Vincent, 2010). The ancient ice shelves along the northern coastline of Ellesmere Island in High Arctic Canada harbor diverse communities of microbes and micro-invertebrates (Varin et al., 2010), and these shelves are currently experiencing rapid attrition. For example, in the warm summer of 2008, there was a 23% decrease in overall ice shelf habitat, including complete break-out and loss of the Markham Ice Shelf (Vincent et al., 2009). These ice shelves dam bays and fiords to create ‘epishelf lakes’, an ecosystem type that is well known in Antarctica. Fracturing and break-up of ice shelves can cause a draining of such lake ecosystems, and the loss of their unusual fresh and brackish water communities. Only one epishelf ecosystem is believed to remain in the High Arctic (Milne Fjord, northern Ellesmere Island, Canada), and it is vulnerable to ongoing warming (Veillette et al., 2008). The loss of ice shelf ecosystems will affect biogeochemical processing of material entering the sea from land-based ecosystems, and conversely, the newly opened coastal waters are likely to cause accelerated warming of the adjacent terrestrial environment.

11.4.4.3. Lake ice

Ice covers Arctic lakes for six to 12 months each year and therefore has a major influence on the physical, chemical and biological characteristics of these ecosystems (Chapter 6). There is evidence of earlier break-up and delayed freeze-up at many sites (e.g., Latifovic and Pouliot, 2007), and this trend is predicted to accelerate in the future (Prowse et al.,

2009a). Such changes may favor some fish and invertebrate species by providing more ice-free habitat, and by reducing the period of time that the lakes are sealed from oxygen exchange with the atmosphere. Paleolimnological studies suggest that the shorter duration of snow and ice cover results in higher primary production at sites throughout the Arctic (Melles et al., 2007; Smol and Douglas, 2007b; Antoniadou et al., 2009). Such changes have been attributed to improved light conditions for photosynthesis, which in some lakes may be compounded by increased wind-induced mixing and entrainment of nutrient-rich deeper waters into the photic zone, and increased nutrient inputs from their catchment areas in a warmer climate. The longer ice-free period will allow more exposure of the water column to direct solar heating, and in the High Arctic may drive lakes from cold monomictic (one period of mixing a year) situations to dimictic (two periods of mixing a year) conditions. The latter may favor higher productivity in a warm surface mixed-layer, and the development of cladoceran zooplankton communities (Sorvari et al., 2002), leading to increased contaminant transfer to high trophic levels (Chételat and Amyot, 2009). These warmer conditions may force cold-adapted specialists into more restricted habitats, for example Arctic char *Salvelinus alpinus* may be increasingly confined to deep lake habitats (Power et al., 2008). Alternatively more complex responses are possible for some fishes. In mid-latitude lakes (e.g., 60° N, northern boreal) lake trout *S. namaycush* tend to use epilimnetic waters which more closely approximate their thermal preferences thereby promoting growth. Projected effects of earlier ice loss and radiative heating suggest shallower and earlier thermocline development which will decrease the availability of this habitat (Mackenzie-Grieve and Post, 2006), thus stressing such populations. Finally, the increased evaporative losses associated with a longer period of open water may result in decreased lake levels, a loss of shallow water habitat, and in extreme cases complete loss of the aquatic ecosystems (e.g., Smol and Douglas, 2007a).

Changing lake ice will also alter the coupling between these ecosystems and other environments and biota. These climate-dependent changes may influence the through-flow of contaminants from catchments via lakes to the sea (e.g., Semkin et al., 2005). Coupling of lake-ice decline to increased contaminant exposure is supported by correlative links observed in mercury and polychlorinated biphenyl incorporation into burbot, a locally harvested freshwater fish species present throughout many Arctic freshwaters (Carrie et al., 2010). The increasing open water conditions may attract aquatic bird populations and thereby new trophic levels (e.g., Vincent et al., 2009), and may favor the competitive success of less cold-tolerant plant, fish and other organisms invading from the south, perhaps driving some northern species to extinction (e.g., Sharma et al., 2007).

11.4.4.4. River ice

Ice is a major structuring feature of Arctic rivers and their associated flood plain ecosystems, and changes in the duration and magnitude of ice accumulation will have many ecological impacts, not only on these waters but also on the coastal ocean ecosystems into which they discharge (Chapter 6). Ice reduces the winter survival of many river-dwelling organisms (e.g.,

Huusko et al., 2007) and release from this constraint will have a mixture of negative and positive effects on riverine communities. Reductions in ice cover may result in decreased habitat availability for some fish species (e.g., Linnansaari et al., 2009), and mid-winter break-up may be especially deleterious (Wrona et al., 2005). Conversely, with ongoing warming, many Arctic rivers that currently have bed-fast ice may open up as winter habitats for fish, and increasing zones of broken ice or open water during winter will aid the oxygenation of rivers. River ice, especially during break-up, causes substantial bank and channel erosion that not only controls the geomorphology of the fluvial environment and therefore the spatial distribution of habitat types (Prowse et al., 2006), but also affects the timing and magnitude of particulate and dissolved material exported from terrestrial catchments to the sea. Ice scour damage results in tiered bands of different types of riparian vegetation that correspond to break-up frequency and severity (Prowse and Culp, 2008), and reductions in river ice could result in reduced diversity and structure of such vegetation and its associated biota.

The larger Arctic rivers have lake-rich floodplains that are productive sites for aquatic and semi-aquatic plants and animals. These also act as biogeochemical processing regions for river water before its discharge to the sea (e.g., Emmerton et al., 2008), and changes in the flooding regime are likely to affect not only the ecology of the floodplain delta, but also biogeochemical characteristics, primary production and food web processes in the coastal marine ecosystem. Ice-jams result in high spring flood levels, and decreasing ice compounded with reduced spring runoff as a result of less winter snow pack will reduce ice-jam flooding (Beltaos et al., 2006). This could isolate some of the higher elevation floodplain lakes and their biota from the river (Box 11.2). Changes in coastal stamukhi ice will also affect how river water is biogeochemically modified before it is discharged into the marine environment (Box 11.2).

11.4.4.5. Sea ice

Sea ice is a key component of the Arctic Ocean ecosystem, which is currently undergoing rapid change (Chapter 9, Section 9.3). Observations and models indicate that the extent of multi-year ice has diminished greatly over the past few years, and that Arctic seas may be seasonally ice-free within a few decades. This has enormous ecological implications for the structure and functioning of all Arctic Ocean ecosystems. It will also impact strongly on coastal terrestrial ecosystems and the lifestyle of indigenous communities living on the coast.

Sea ice is a habitat for marine mammals, and for diverse communities of other biota that live within or in association with the ice. Changes have already been observed in Arctic marine ecosystems that have been attributed to recent decreases in sea-ice extent and duration. These include: a regime shift in the Bering Sea from an ice-dominated ecosystem, with bottom-feeding birds and mammals that depend on carbon input to the benthos from sea-ice algae, to an open water ecosystem more dominated by plankton and pelagic fish (Grebmeier et al., 2006); satellite evidence of increased phytoplankton biomass in response to more open water and a longer open-water season (Arrigo et al., 2008); and a decline in condition and reproductive

success of polar bears *Ursus maritimus* in western Hudson Bay associated with earlier ice break-up (Regehr et al., 2007). Such changes are likely to accelerate over the course of this century, but there are many uncertainties that make future predictions challenging. Reduced sea ice is also almost certain to lead to increased shipping, tourism and exploration for oil, gas and mineral resources, all of which are likely to have ecological impacts on land as well as in the sea. Also, changes in sea ice will affect hunting and traditional over-ice transport routes that will become increasingly dangerous, even in winter. Finally, the increased extent and duration of open water will affect the temperature and precipitation regimes of coastal ecosystems, including those based on land, as well as coastal erosion processes (Chapter 9, Section 9.4).

Changing sea-ice conditions (less multi-year ice, more seasonal ice, earlier melt, later freeze-up) may lead to increased light availability for photosynthesis and therefore increased biological productivity at all trophic levels (see Chapter 9, Section 9.3). However, these positive effects may be offset by increased freshwater runoff and ice melting that enhances stratification and inhibits the entrainment of nutrients from the deeper layers into the surface waters by mixing, thereby limiting phytoplankton production. Field measurements in Canada Basin have revealed high $p\text{CO}_2$ levels in its surface waters after extensive ice melt had occurred, leading to the prediction that the Arctic Ocean will not become a large photosynthetic sink for atmospheric CO_2 under ice-free conditions (Cai et al., 2010). Also, increased runoff of river water rich in dissolved and particulate organic matter may cause local reductions in underwater light, particularly to the deep population maxima of phytoplankton that can contribute a large fraction of total water-column photosynthesis (Retamal et al., 2008; Martin et al., 2010). The loss of snow-covered sea ice also results in water column biota experiencing much greater ultraviolet (UV) radiation exposure (Vincent and Belzile, 2003), and this high energy waveband may have negative effects on some phytoplankton and other biota. Satellite imagery suggests that there are large differences between different parts of the Arctic Ocean in the response of phytoplankton to decreased ice cover, however ongoing work is required to validate such observations for Arctic seas, where the surface chlorophyll concentrations may not be an accurate guide to total water-column algal biomass.

Sea ice is an important habitat for lipid-rich, Arctic-adapted zooplankton that feed on ice algae and ice edge phytoplankton blooms, and these in turn provide high quality food for seabirds, fish and whales. The algal populations in these habitats also provide an important food source to benthic communities. Ice-associated marine mammals will be especially impacted by changing sea ice. Already, ice-related declines have been reported in hooded seals *Cystophora cristata*, harp seals *Phoca groenlandica* and ringed seals *Phoca hispida* at some locations, and there is also evidence of impacts on the distribution and health status of Pacific walrus *Odobenus rosmarus* (Chapter 9, Section 9.3). Whale species may differ greatly in their sensitivity to ice change depending on their degree of specialization and flexibility in diet. Narwhal *Monodon monoceros* are likely to be strongly impacted by the loss of pack ice in their winter-time benthic feeding regions (Laidre et al., 2008), while the more generalist feeding habits of beluga *Delphinapterus leucas*, grey whales *Eschrichtius robustus* and bowhead whales *Balaena mysticetus* may allow them to adjust more readily to changes in the Arctic marine ecosystem

caused by loss of sea ice (Moore et al., 2010). Polar bears are especially prone to negative consequences of the changing sea-ice conditions, and drastic declines have been predicted (e.g., Durner et al., 2009), including complete extirpation from many areas where they are presently common (Regehr et al., 2010). The ecology of terrestrial species that use sea ice seasonally as foraging habitat (e.g., Arctic fox *Vulpes lagopus*, Gagnon and Berteaux, 2009; Tarroux et al., 2010) will also be strongly modified by sea-ice decline.

Ice-associated zooplankton are important for certain fish species, notably capelin *Mallotus villosus* and Arctic cod (*Boreogadus saida*), which in turn are resources for several commercially important species such as Atlantic cod *Gadus morhua*, as well as whales (e.g., beluga). Bird populations that depend on these zooplankton, such as some auklets, are likely to experience ongoing decline, although some bird species appear to be increasing in population size, possibly as a result of earlier ice break-up (Chapter 9, Section 9.3).

11.4.5. Permafrost

Permafrost, defined as soil, rock or sediment that remains at or below 0 °C for two or more consecutive years, covers vast areas of the Arctic. Unlike sea ice, it does not provide a unique habitat for a dependent biota (with the exception perhaps of extreme cold-adapted microbes in permafrost micro-niches; Gilichinsky et al., 2008), but it does strongly influence the hydrology, biogeochemistry and geomorphology of the landscape and thereby the biological productivity and biodiversity of northern regions (Chapter 5). Permafrost provides an impermeable barrier to drainage, and the resultant high water table favors wetlands, lakes and ponds, and their associated biota (Woo and Young, 1998). Uplift and erosion of permafrost soils cause variations in surface topography and drainage, and the resultant heterogeneity causes a patchy distribution of plants and other organisms across the landscape, allowing increased species diversity. The degradation of permafrost proceeds in a great variety of ways that depend not only on climate but also on geomorphology, soil texture, hydrology and ice characteristics. These diverse degradation pathways in turn affect the nature of the ecological responses, including creation of lakes and wetlands, conversion of forests to fens, and increased drainage with loss of lakes or little change in vegetation (Jorgenson and Osterkamp, 2005).

In many parts of the Arctic, the permafrost has begun to warm and the active layer has deepened. However, the extent of these changes is highly variable regionally, with a deepening of the active layer by several metres or more at some sites and yet no detectable change at others. In Russia, for example, thawing has been pronounced over the past three decades at many sites, especially in the discontinuous permafrost zone, while at some other sites such as the Urengoy area in western Siberia, the permafrost continues to be stable (Romanovsky et al., 2010). Slumping and drainage due to permafrost melting may damage some vegetation, such as the complete destruction of forest ecosystems (Jorgenson and Osterkamp, 2005), but the disturbance also allows new species to colonize and become established (e.g., Lantz et al., 2009), including invasive species from the south. In parts of the Arctic, thermokarst lakes and wetlands are expanding as a result of permafrost thawing and erosion, thereby producing more habitats for aquatic birds and

other animals. Such effects have been observed in northern Quebec (low Arctic Canada), for example, where the southern limit of discontinuous permafrost has moved 130 km northward over the past few decades (Thibault and Payette, 2009) and thaw lakes have become larger and more abundant (Payette et al., 2004). Elsewhere, however, the degradation of permafrost is causing a draining of the landscape and loss of aquatic and semi-aquatic ecosystems. Such changes may result in a more homogeneous northern landscape, with reduced habitat and species diversity. The sub-Arctic palusa mires (bogs containing permanently frozen peat hummocks) of Fennoscandia, for example, are predicted to disappear almost completely by 2050; this loss is likely to have detrimental effects on migrating birds such as waders that feed on the abundant insect life in these habitats (Luoto et al., 2004).

There are complex interactions between permafrost soils and vegetation that affect soil temperature, surface albedo and even a region's sensitivity to fire. By trapping snow and directly insulating the ground with its foliage, plant communities can reduce soil temperatures by several degrees, and permafrost patches may therefore continue to exist beneath undisturbed vegetation despite rising air temperatures. Trees and shrubs have a much lower albedo than snow on tundra, and the conversion of northern landscapes to shrub tundra and forest is likely to cause increased heating; after snowmelt, however, increased evapotranspiration from vegetation can also cause local cooling (Göttl et al., 2008). Finally, increased vegetation biomass combined with drier conditions is likely to increase the frequency of fires on the tundra, with additional impacts on permafrost stability and temperature.

Thawing permafrost may release organic matter, gases, inorganic solutes and microbiota into the surrounding environment, with implications not only for land-based ecosystems, but also for thaw ponds, northern rivers and the coastal ocean. The increasing incidence of fires and other extreme weather events (Post et al., 2009) may also exacerbate permafrost degradation and the transfer of soil materials into waterways. Terrigenous, organic-rich particles released into rivers are a substrate for bacteria and archaea (Garneau et al., 2008), and climate effects on these organisms combined with increased light limitation of phytoplankton may drive Arctic rivers and estuaries toward even greater heterotrophy and net CO₂ efflux in the future (Vallières et al., 2008). Viable microbial populations dating back three million years have been identified in Siberian permafrost (Gilichinsky et al., 2008), and the impacts of release of these ancient genotypes into the present-day biosphere are completely unknown. Globally significant quantities of organic carbon are stored in frozen northern soils (Tarnocai et al., 2009), and some of these compounds released into lakes, rivers and coastal seas may be converted into CO₂ and methane. Sub-Arctic thaw lakes have been found to be stratified throughout most of the year, with anoxic bottom waters despite their shallow depths; these conditions favor microbial processes that convert allochthonous tundra carbon to methane, which is ultimately released to the atmosphere (Laurion et al., 2010). Large quantities of methane are stored in the tundra and in the frozen sediments beneath Arctic seas as gas hydrates and free gas. The continuous efflux of this gas (e.g., into the ocean over the East Siberian Arctic Shelf; Shakhova et al., 2010) is likely to stimulate methanotrophic bacteria and perhaps chemotrophic food webs, but such effects

have been little explored to date, and there is much uncertainty about how much warming will be required to trigger globally significant releases from these vast greenhouse gas reservoirs.

11.4.6. Conclusions

The Arctic's changing climate has already had marked impacts on snow, water, ice and permafrost regimes of the region. Such changes will continue to accelerate over the course of this century and will have ongoing impacts on the ecosystem services that are vitally important to northern indigenous communities, such as safe drinking water supplies and fishing, hunting and other harvesting resources. Each of these changes is affecting different Arctic ecosystems in different ways. However, there are also some commonalities. In each ecosystem type, from permafrost to sea ice, there are large variations among Arctic sectors in the pace of change. This heterogeneity is likely to persist in the future, underscoring the urgent need for downscaling climate projections and impact assessments to specific Arctic sectors and localities.

Extreme climate events are likely to continue to have severe effects on many ecosystem types. Examples discussed above include rain on snow in winter giving rise to surface crusts of ice that impede animal feeding, a seasonal thawing of permafrost that breaks winter dormancy and cold-tolerance of plants, and winter break-up of river ice that disrupts fish habitats. Such extremes compounded with the general warming trend is hastening the demise of unique habitats, for example palsamires in Fennoscandia, ice shelves and epishelf lakes in northern Canada, and multiyear sea ice across Arctic Ocean.

As the Arctic region warms and loses its extreme habitats, it is becoming more homogenous and more suited to generalist species. Specialists such as psychrophilic microbes, polar desert plants, and obligate sea-ice biota including seals, walrus and polar bears will become increasingly limited in habitat range, while invasive generalists from the south are likely to become increasingly prevalent constituents of each type of Arctic ecosystem. The loss of perennial sea ice and increased access to resources in the Arctic will be accompanied by increased human activities, which will impact all ecosystems. Accelerated development of the North will create ongoing challenges for Arctic ecosystem management, and for the traditional lifestyles of Inuit and First Nation communities that have been based on these ecosystems.

Many of the ecosystems referred to here are interdependent, and the overall effects of changing snow, water, ice and permafrost on Arctic ecology cannot be evaluated without considering this connectivity. The melting of glaciers, ice caps and snow and the resultant transfer of water, nutrients and stored contaminants from land to the ocean mean that shifts in the terrestrial cryosphere have strong ecological effects downstream, for example, changes in organic carbon and nutrient export to coastal food webs, and in the freshwater content and stratification of the Arctic Ocean ecosystem. Conversely, changes in sea ice may affect the temperature and precipitation regime of coastal terrestrial ecosystems, and the migrations of fish and birds between marine and freshwater environments. The many forms of ice throughout the Arctic region give rise to diverse, spatially complex habitats for terrestrial and aquatic life (e.g., Box 11.2), and ongoing climate change has begun to alter these ice-dependent ecosystems and the connections among them.

11.5. Observational needs and knowledge gaps for the cryosphere

Summary

Cryospheric observations help us understand, assess, predict, mitigate, and adapt to climate variability and change; improve weather forecasting; help reduce the loss of life and property from disasters; provide a better understanding of environmental factors affecting health; and improve the management of resources. Closing gaps in snow and ice observation networks and in knowledge of cryospheric processes would allow the full potential of snow and ice information to be realized for the benefit of society. This assessment has made the following findings:

- Many Arctic surface-based observation networks for snow, lake and river ice, permafrost, and precipitation have diminished or been completely lost. Many important observations and monitoring efforts are research based and in need of sustained funding.
- There is no pan-Arctic dataset of *in situ* snow measurements. There are few measurements of snow depth on sea ice. Space-based capabilities for snow extent are robust, but methods of estimating snow water equivalent and snow depth are limited.
- Precipitation gauge networks are the most important source of information on high latitude snowfall but have large errors. Satellite methods are challenging but promising.
- While satellites have provided reliable observations of sea-ice extent, concentration, and motion for over 30 years, methods for estimating ice thickness from space are only now being developed. *In situ* measurements of ice thickness are sparse.
- There are numerous boreholes that provide temperatures for permafrost studies but many of the records are discontinuous and short. There is a wealth of historical data extending back 50 to 100 or more years; data rescue efforts are needed.
- Glacier inventories have basic data for less than half of the world's glaciers. Satellite-based inventories are discontinuous. Mass balance measurements over long periods are available for only a small subset of Arctic glaciers.
- Since the Arctic Climate Impact Assessment there has been considerable progress in the ability to estimate the mass balance of ice sheets. Gravity, laser altimetry, and radar data from satellites have become a major source of information. These new observational methods have broadened the range of estimates, revealing that uncertainties may be larger than previously thought.
- Traditional knowledge can provide important value-added content to data products and serves to make the data more relevant to northern users. Community-based observing programs provide a mechanism for two-way knowledge transfers.


- There are considerable uncertainties in modeling cryospheric processes. Permafrost models under-represent ice content and the insulating effect of the organic layer; climate models do not resolve the steep topography of the Greenland Ice Sheet margins; models of snow-vegetation interactions need to be improved; and models that link meteorology to glacier mass balance need to incorporate downscaling techniques and satellite data.

11.5.1. Introduction

Snow and ice observations play a crucial role in numerical weather prediction, climate monitoring, change detection, hazard forecasting, and water resource management. A comprehensive set of observations is required to assess the efficacy of mitigation and adaptive strategies and to prioritize needs for governance. Improved mapping and monitoring of drifting ice and icebergs, local sea-ice formation, annual variations in ice cover, and trends in storm surge characteristics are important to shipping, industrial developments, and local hunting. Forecasts of break-up

and freeze-up of the ice will help industry to determine the seasonal window for operations. Monitoring of snow cover, winter thaw, and rain will provide information relevant for hydropower, drought, snow load, avalanches, and floods. For many hunting activities, knowledge of changes in the timing and amount of snow and ice are important. For maintaining the integrity of infrastructure, monitoring of permafrost characteristics is important.

However, conditions in areas where the cryosphere exists are harsh, and *in situ* observations there are difficult and expensive. Satellite monitoring overcomes some of the logistical obstacles, but satellites are costly and do not yet fully address the range of geophysical variables needed to understand the cryosphere. Furthermore, satellite products will always require ground truth for validation. A comprehensive cryosphere observing system must therefore be a combination of ground-based instrumentation, satellite remote sensing, aircraft measurements, modeling, and data management (Figure 11.12). Surface and airborne observations provide data that cannot currently be measured from space, more



11.12. The various types of observation system (satellite, aircraft, and *in situ*) and scales of operation. Sources of photos from top down: ESA-AOES Medialab, NASA/Patrick Black, Martin Fortier/ArcticNet, Roland Kallenborn.

detailed information in critical areas, and observations with which to calibrate and validate satellite retrievals. Satellite instruments are essential for delivering sustained, consistent observations of the global Arctic cryosphere and are key to extending local *in situ* measurements. No single all-encompassing sensor exists; rather, the combination and synthesis of data from different yet complementary sensors is essential and underlines the critical importance of maintaining key synergetic elements of the system.

While the previous chapters use snow and ice data to assess changes in the Arctic cryosphere, this section assesses the state of the cryosphere observing system itself. It addresses observations more broadly, synthesizing the material presented earlier and focusing on observational gaps. Table

11.2 provides a summary of the observing systems for snow and ice. It lists the measurement approach for the major variables, describes the status of the networks (operational or research), provides a qualitative assessment of how well each is meeting the measurement requirements, and outlines any major issues. As robust as the satellite and *in situ* measurement networks are, there are many shortcomings in the cryosphere observing system that give rise to sometimes-large uncertainties in assessments such as SWIPA. These are discussed for each cryospheric element in the following sections. The societal impacts of changes in the cryosphere, and hence the importance of robust measurements of snow and ice properties, are described in Chapter 10.

Table 11.2. Observational readiness of snow and ice measurements for the observing system overall. Green satisfies the requirements ($\geq 85\%$); blue meets the requirements most of the time ($\geq 70\%$); yellow meets the requirements some of the time, or only for specific conditions; orange does not meet the requirements. O: operational, R: research, C: commercial, L: long-term (≥ 20 years) record.

	In situ	Satellite	Major gaps in observations
Ocean			
Ice extent	Coastal radar (R), Ship observations	Passive microwave (O, L)	<i>In situ</i> coverage is sparse and incomplete
Ice concentration	Ship observations	Passive microwave (O, L)	Potentially large uncertainties in satellite retrievals in summer
Ice thickness	Ice-profiling sonar on moorings (O), Mass balance buoys (C), Electromagnetic sleds (R)	Optical, Laser and Radar altimeter (R)	Satellite methods are still developing; snow depth on ice is an unknown
Ice motion	Drifting buoys (O, L), Coastal radar (R)	Passive and active microwave (O, L), Optical (R)	Important small-scale motions not captured by satellites; <i>in situ</i> measurements sparse
Snow depth on ice	Depth gauge (R)	Passive microwave (R)	Satellite method is limited to first-year ice with potentially large uncertainties; <i>in situ</i> data are sparse
Sea level	Tide gauges (O, L), Bottom pressure recorders (C)	Altimeters (R)	
Surface temperature	Drifting buoys (O, L)	Optical (O, L)	Uncertainty in satellite estimates due to cloud cover
Albedo	Radiometers (O, L)	Optical (O, L)	Sparse <i>in situ</i> coverage; significant uncertainty
Terrestrial			
Snow cover	Depth gauge (O, L)	Optical (O, L)	<i>In situ</i> network is declining
Snow depth	Depth gauge (O, L)	Optical (R)	Satellite method is limited to tall-grass prairie
Snow-water equivalent	Various methods (O)	Passive microwave (R)	<i>In situ</i> coverage is sparse
Freshwater ice	Visual observations (O, L)	Optical (R)	Declining observation network
Glacier, ice cap, ice sheet thickness	Seismology (R)	Radar (R), Gravity (R)	Sporadic coverage
Glacier length, area	Surveys (R, L)	Optical (R)	Incomplete coverage
Glacier, ice cap, ice sheet motion	GPS (R)	InSAR, Visible imager (R)	Sporadic coverage
Permafrost: ground temperature	Boreholes (O, L)	(none)	Large parts of the Arctic not covered
Permafrost active-layer thickness	Boreholes, Probes (O, L)	(none)	Large parts of the Arctic not covered
Surface temperature	Thermistors, Thermocouples (O, L)	Optical (O, L)	Satellite method is clear sky only
Albedo	Radiometers (O, L)	Optical (O, L)	Sporadic <i>in situ</i> coverage; significant uncertainty




Figure 11.13. Northerly position of the ice edge in August between Svalbard and Franz Josef Land for the period 1553 to 2004 given by its mean latitude in the sector 20–45° E (blue bars). Source: Falk-Petersen et al. (2008).

11.5.2. Sea ice

The first quantifiable observations of sea-ice properties came from ships sailing in and near ice-covered regions as early as the 1500s (Figure 11.13). National ice services began routinely producing ice charts for the Arctic in the 1950s using visual aerial reconnaissance missions and aerial photography. The thickness of ice fragments laid on edge due to the icebreaker movement has been determined using onboard digital video cameras on Russian icebreakers for many years. Submarine sonar observations of ice draft under the Arctic sea ice began in earnest in the 1950s, although the data are sparse and remained classified for decades. Moored upward-looking sonar (ULS) gives thickness and volume flux estimates from below. Electromagnetic (EM) sensors mounted on ships, surface vehicles, helicopters, or aircraft can estimate thickness. Surveys using new airborne and satellite lidar methods can now provide thickness estimates for large regions, although uncertainties, particularly in snow cover, limit accuracy. More recently, near-surface observations have been taken from autonomous underwater vehicles and from unmanned aerial vehicles, although their small size limits the type of sensor that can be carried. Manned Russian ‘North Pole drifting stations’ have operated on the Arctic sea ice from 1937 to 1991 and since 2003. Mass balance buoys are now being deployed to obtain ice and snow thickness and internal temperatures.

Satellite-borne visible and infrared sensors provide observations of surface albedo and temperature, snow cover, radiative fluxes, ice extent, concentration, motion, and melt, but coverage is limited due to frequent cloud cover, and for visible imagery, sunlight. Satellite passive microwave radiometers provide a 30-year plus record, with near-complete daily coverage, of the polar regions under all sky conditions for concentration and extent, motion, and melt. Unfortunately, the spatial resolution of these products (6 to 25 km) makes it impossible to obtain detailed information on the ice cover, such as deformation, melt-pond and lead formation, and ridging. Synthetic aperture radar (SAR) instruments provide high-resolution information on deformation, leads, ridging, and new ice production, which is important for marine transportation.

Scatterometry provides information at a similar spatial scale to passive microwave data, but can provide better information on perennial ice cover and complementary information on other properties (e.g., melt and snow). Spaceborne laser and radar altimeters can provide indirect estimates of ice thickness,

which is useful for navigation and for modeling ice-atmosphere fluxes. Accurate estimates of ice thickness from altimeters require good knowledge of snow depth and density. More *in situ* measurements of snow depth are needed for better estimates of ice thickness (Chapter 9, Section 9.1.5). The potential to derive snow depth on floating ice by passive microwave remote sensing has been demonstrated by Markus and Cavalieri (2000), but it is only applicable over first-year ice regimes and requires further research. Other satellite-based products for estimating ice thickness and age are currently being developed.

There is no single accepted passive microwave ice concentration product², leading to confusion among users. Rigorous evaluation and consolidation of products are needed, together with formal estimates of algorithm uncertainties and errors. This should include improved inter-sensor calibration with longer periods of overlap, rigorous evaluation and intercomparison of current algorithms, and the development of data fusion methods to obtain optimal combined products. Sea-ice observations are not well suited for model assimilation because their error structures are not well known at the grid cell or pixel level.

11.5.3. The Greenland Ice Sheet

The Greenland Ice Sheet has been studied extensively in an effort to quantify the surface mass balance and to estimate its contribution to global sea level. However, *in situ* observations are limited due to the large area and remoteness of the ice sheet. The notable exception is the record from the Greenland Climate Network (GC-Net) of automatic weather stations, operating since 1995 and distributed across the ice sheet. Scientists must therefore rely on remotely sensed observations and estimations from downscaled general circulation models (GCMs) or high-resolution regional climate models (RCMs) to investigate surface mass balance. However, systematic biases in the models relative to the *in situ* record illustrate that the climate of the ice sheet is more or less decoupled from the coastal regions where most of the direct observations that feed the models are made.

Satellites have triggered a quantum leap in observations of

² The term ‘product’ as used here does not imply an extensive level of validation nor the adherence to any particular standard. The products may be research or operational datasets, but all have undergone at least a basic level of validation.

the ice sheets (Chapter 8). Images acquired by reconnaissance satellites starting in 1962 provide a treasure of historical data for gauging subsequent changes in the positions of shear margins, grounding lines and glacier terminuses (Kim et al., 2001; Zhou and Jezek, 2002). Passive and active microwave observations are used to measure the onset, duration, and extent of ice sheet surface melt. Passive microwave data have also been used to estimate average annual accumulation (Zwally and Giovinetto, 1995). Satellite altimeters are invaluable for measuring ice sheet elevation and also provide information on subglacial water movement (Wingham et al., 2006; Fricker et al., 2007). SAR interferometry (InSAR) provides a powerful means to investigate glacier flow. Satellite gravity instruments provide measurements of ice sheet mass change (Chen et al., 2006; Velicogna, 2009).

In situ measurements are progressing, although at a slow pace due to resource-demanding fieldwork (Chapter 8). Snow pits are used to measure near-surface temperature, snow and firn density, crystalline structure, surface accumulation, and when coupled with GPS measurements, surface velocity. *In situ* seismological experiments are used to measure ice thickness, near-surface density, and the properties of the glacier bed. Surface and airborne radars are used to measure ice thickness, although spatial coverage is limited and there are still large gaps in the ice thickness maps. To efficiently fill these gaps, fixed-wing aircraft, unmanned aerial vehicles, and satellite implementations of ice sounding synthetic aperture radars should be explored. A combined effort in advancing process theory, field methods, coverage, and modeling efforts could facilitate major advances in understanding ice sheet mass balance and help create less uncertain future scenarios of ice mass loss and sea-level rise.

Ice sheet models are insensitive to ocean forcing, in contrast to recent observations of significant velocity variations in marine-based outlet glaciers, which were most likely triggered by ice-ocean interactions and thinning at the grounding line. Gaps in knowledge are mainly related to physical processes of fast-flowing outlet glaciers and ice streams, bed topography, and melting rates under floating glacier tongues. Melt rates on the submarine parts of terminal ice cliffs are also poorly known and often ignored.

Compared with processes that take place at the base of the ice sheet, those that influence the surface mass balance are relatively well understood and considerably easier to observe. Despite this, reconstructions of the individual components that make up the surface mass balance differ significantly. The differences can be as large as the inferred increase in mass loss due to changes in ice dynamics over the past decade. The uncertainties in the surface mass balance are largely a result of the paucity of spatially extensive *in situ* observations. Reducing uncertainties will require a concerted effort to collect more targeted *in situ* data, especially from the percolation and ablation zone. Improvements in process understanding and modeling of key processes such as refreezing, blowing snow, and subgrid-scale effects will also be needed. Meteorological measurements from automatic weather station networks are the key means of estimating near-surface fluxes. These measurements should be maintained and spatially extended to key regions on the Greenland Ice Sheet.

Instead of reducing uncertainty about changes in the mass

balance of the Greenland Ice Sheet, new observational methods from space have broadened the range of estimates, revealing that the uncertainties of methods may be larger than previously thought. They also point to the incomplete understanding of the fundamental dynamics of calving glaciers and land-terminating outlets of large ice sheets. Most changes appear in the marginal regions of the ice sheet where data are scarce. Many climate models do not resolve the steep topography of the Greenland Ice Sheet margins, limiting skill in simulating orographic precipitation and ice sheet ablation. New progress in snow physics theory and parameterizations needs to be incorporated into climate models (Chapter 8).

Climate models generally do not include ice sheets and glaciers, which limits their use for projecting sea-level rise. Particular challenges in modeling sea-level rise are the coupling of ice sheet and ice bed and of ice sheet, ice shelf, and ocean. Key uncertainties in predicting Greenland's contribution to sea-level rise are ice dynamics and surface mass balance. The response to warming remains a large uncertainty.

11.5.4. Terrestrial snow

Surface-based methods of measuring snow properties include graduated probes, acoustic depth sounders, coring devices, snow pillows (pressure transducers), and excavation of snow pits with detailed sampling. Worldwide, many surface-based snow-observation networks have diminished or have been completely lost. The number of Arctic stations reporting snow depth increased between 1960 and the 1990s, but decreased in many areas over the past decade. The most common observation is snow depth. Far fewer snow-water equivalent (SWE) observations are available, and observations of other snow parameters (e.g., layer snow temperature, layer boundaries, hardness, grain form, grain size, density, strength, and stability) are limited. A coordinated plan for surface-based snow observation networks must be developed, first at the national, then at the international level. Although there are regional snow cover products (Chapter 4, Appendix 4.1), at present there is no pan-Arctic dataset of *in situ* snow measurements, and there is no single archive that has all snow depth data. Data are particularly sparse for the mountain and tundra regions.

Observations of snow extent from visible, near-infrared, and microwave satellite sensors have been widely used since 1966. Space-based capabilities for observing snow depth and SWE are more limited. Microwave sensors appear ideal for this purpose, but current sensors lack optimal combinations of frequencies and spatial resolutions, particularly for mountainous terrain. Long-term SWE data have been derived from passive microwave sensors, although comparative analyses of basin-wide SWE and winter precipitation suggest uncertainties in the determination of snowfall amounts and SWE over large watersheds and regions with different physical characteristics (Yang et al., 2009). SAR observations overcome the resolution problem, but current sensors operate at frequencies too low to be useful for most snowpacks. Priority should be given to research and the development of algorithms and new sensors to measure SWE (high frequency SAR), under a wide range of vegetation conditions.

Energy and mass-balance snow models, now widely used for many applications, are highly nonlinear and include several

interacting variables. These models are under-constrained by mass-oriented observations of SWE or snow depth alone. Snow temperature observations are necessary to constrain the energy states of these models. Snow observation sites are often not representative of surrounding areas. This results in observation biases that can be easily propagated to large regions through modeling and data assimilation. Such biases are common and can be quite large.

Further work is needed to improve models of snow-vegetation interactions. There are dramatic differences in snow model response if vegetation is included. One of the problems is that parameterization of key processes such as snow unloading are either non-existent or based on site-specific data. Integrated multi-sensor data fusion and global analysis systems that blend snow observations from all sources must be improved. The ideal global snow observing system will use observations from all relevant sources in coherent, consistent high-resolution analyses of snow extent, depth, SWE, wetness, and albedo. No current system provides global coverage.

11.5.5. Permafrost and seasonally frozen ground

The Global Terrestrial Network for Permafrost (GTN-P) identifies permafrost thermal state (i.e., ground temperature) and the active layer thickness as key variables for monitoring (WMO, 1997). Many permafrost temperature records are of short duration and discontinuous, although some sites have 20- to 40-year time series. Currently about 400 boreholes are listed in the GTN-P database; around half of these are in Arctic countries (Figure 11.14). There are currently over 100 Arctic sites that report seasonal thaw, soil temperatures, moisture and frost heave, and subsidence.

No formal international network exists for seasonally frozen soil temperature or moisture observations, although several programs make some data available. The Arctic Coastal Dynamics (ACD) program began in 1999, where a network of 25 key sites was identified along the coastline of the entire Arctic Basin (Rachold et al., 2005). Some national networks are extensive. There were more than 800 stations in the former Soviet Union where soil temperature and soil freezing depth were measured on a daily basis (Chudinova et al., 2006), but the number of stations has declined significantly in the past two decades. Canada and the United States have many stations where soil temperature is measured, although not all are Arctic.

Many of the GTN-P sites are not maintained for long-term monitoring. There are significant thematic and regional gaps in the present networks, especially in eastern and central Canada, most ice-free areas in Greenland, and north-central and northeastern Russia. Many sites lack instrumentation for collecting the ancillary data required to analyze the linkages between permafrost and climate. Existing borehole and active layer networks must be expanded. Soil temperature and frost depth measurements should be standard parameters for all cold-region meteorological stations.

Properties of permafrost terrain are currently not directly detected from remote sensing platforms. Zhang et al. (2004) and Duguay et al. (2005) provided a comprehensive overview of satellite remote sensing of permafrost and seasonally frozen ground. Surface indicators of permafrost terrains that are discernable by remote sensing include pingos, thaw lakes and




Figure 11.14. Soil temperature stations and sites in the Northern Hemisphere. Blue and green symbols are sites for which data are available. Red symbols indicate sites for which data are not available. Source: adapted from IGOS (2007).

basins, thaw slumps, thermo-erosional valleys, thermokarst mounds, ice wedge polygons, beaded drainage, slope failures, and rock glaciers. SAR data have been used to map zones of wintertime heat loss that indirectly approximate the distribution of permafrost (Granberg, 1994). Scatterometer data have been used to monitor freeze and thaw cycles (Bartsch et al., 2007). Data from passive microwave sensors can be used to detect surface-soil freeze or thaw status (Zhang and Armstrong, 2001) as well as soil moisture. The application of multi-temporal, basin-scale gravity data for the detection of mass loss from ground ice melting in lowland permafrost regions should be evaluated.

There is a wealth of historical observations extending back in time for 50 to 100 or more years. For example, the former Soviet Union has some sites with daily observations extending back to the 19th century. However, many of the historical national databases lack adequate metadata. While data rescue is labor intensive and can be expensive, it would provide a valuable historical perspective, putting cryosphere-climate interactions into the current context of rapid change (Chapter 5).

There are considerable uncertainties in modeling future permafrost distribution and dynamics. These include an under-representation of the ice content and the organic layer and its importance in insulating permafrost during climatic warming. Permafrost models also fail to adequately represent the disequilibrium that has arisen because some current permafrost is related to past climates. This results in a lag period between a climatic change and a response of the permafrost.

11.5.6. Glaciers and ice caps

For glaciers and ice caps, key uncertainties are the incomplete knowledge of their total mass and the regional variations in mass balance. New datasets on ice thickness and glacier outlines are required to improve estimates of glacier melt. The World Glacier Monitoring Service (WGMS) combines *in situ* measurements of mass balance and length change with global information from remote sensing data (Haeberli, 2006). Systematic compilation of inventories at regional or national scales started in the 1940s based on aerial photography. Of around 160 000 glaciers, about 44% (71 000) are currently

stored in the World Glacier Inventory (WGI) (WGMS, 1989). Many regions are still not included in the WGI although data have been compiled.

High-resolution multispectral optical sensors are the most efficient means for glacier mapping. Repeat inventories are needed at five- to ten-year intervals for global change studies and assessing change of water resources. The Global Land Ice Measurements from Space (GLIMS) Project (Bishop et al., 2004; Kargel et al., 2005) will establish a digital baseline inventory of ice extent during the period 2000 to 2005 for comparison with inventories created at earlier and later times. This will in turn lead to improved information on the global extent of glacier retreats and advances. Enhanced resolution data from satellite scatterometers are used to generate products such as melt onset and freeze-up dates, melt duration, and inferred facies distributions for ice caps and large glaciers. InSAR can be used to map glacier surface topography and provide maps of surface motion. Speckle tracking with visible imagery is also important for motion estimation and is more widespread than InSAR approaches, as interpretation of interferometric velocities is not straightforward. The use of satellite gravity measurements for estimates of mass change for large glaciated regions should be expanded.

Continuous annual mass balance measurements made over relatively long periods from field measurements of accumulation and ablation are only available for about 50 glaciers worldwide (Dyurgerov and Meier, 1997). Many glacier regions have no mass balance observations, which biases the network of mass balance sites strongly toward those glaciers that are easily accessible, particularly smaller glaciers in Europe, Scandinavia, and North America. There are issues with measurement methods being used: such as whether data for winter and summer balances are available or only the annual balance, whether processes of internal accumulation are taken into account in the calculation of annual balance, and whether changes in glacier area over the period of record are taken into account in estimating the annual glacier-wide balance (Chapter 7).

For the most part, ice thickness measurements come from surface-based radars, as borehole studies of ice deformation properties and of subglacial till are rare. However, some of the ice masses of the Arctic are too large to survey with surface radars, so airborne surveys are important. Ice coring in the cold firn of glaciers and ice caps is needed to extend the climate archive obtained by coring on the ice sheets (Chapter 7).

The glacier topography database is fragmentary and of poor quality. Space-based data are needed to improve it. A dedicated InSAR mission for precise mapping of glacier topography is a high priority for determining the evolution of changes. A satellite mission providing information on accumulation should be implemented. Repeat laser altimetry surveying should ideally be extended to all major glaciated regions of the Arctic.

Models that link meteorology to glacier mass balance and dynamic response need to be improved. Downscaling techniques need to be developed for feeding such models with GCM data. Remote sensing data are needed to initialize and validate these models. Water management tools for glacier runoff will also benefit from these developments.

11.5.7. Freshwater ice

Freeze-up and break-up dates from lakes and rivers have traditionally been determined from surface observations. Unfortunately, surface-based lake and river ice observations have been steadily declining since the 1980s to a point where networks have almost disappeared in many countries (Figure 11.15). In Canada, freeze-up and break-up observations were reported for only 12 water bodies across the entire country during the 2000/01 season. Some lake and river ice observations from various countries have been compiled into the Global Lake and River Ice Phenology Database



Figure 11.15. Lake ice observations in 1970 (upper) and 1995 (lower). Courtesy of C. Duguay, University of Waterloo.

(GLRID). The database contains records for 748 sites, but the number of sites reporting ice observations has plummeted since the 1980s. Financial cutbacks and the automation of meteorological stations in the vicinity of lake and river ice observation sites are the two main reasons for the drastic decline in the surface-based networks. A set of target regions and lakes and rivers must be identified for future long-term ice monitoring. A major data rescue effort must be undertaken (Chapter 6).

The Canadian Ice Service (CIS) began operational, weekly monitoring of ice extent on large lakes in 1995 using visible/IR and SAR satellite data. The program started with 34 lakes in 1995 and now has 136 lakes, mostly in Canada with a few in the United States. It is possible to derive dates of complete freeze-over and when water is clear of ice with an accuracy of ± 1 week using this dataset. In 1997, NOAA began generating a daily snow and ice product with the Interactive Multisensor Snow and Ice Mapping System (IMS). The IMS incorporates a wide variety of satellite imagery as well as derived mapped products and surface observations. The coarse resolution of the 24-km product allowed for mapping of ice extent only on the largest lakes of the Northern Hemisphere, but a 4-km resolution product became available starting in 2004.

Lake-ice thickness measurements have primarily been through field observation programs. Like the freeze-up and break-up network, ice thickness networks are sparse, and the number of sites has been steadily declining since the 1980s (Lenormand et al., 2002). Ice thickness has been estimated with some success using numerical ice growth models (see Duguay et al., 2003) and through the synergistic use of optical and SAR data on shallow Arctic lakes (Duguay and Lafleur, 2003). Passive microwave data offer a promising means to obtain lake-ice thickness from very large lakes. It might also be possible to obtain the total thickness of snow and ice on medium to large lakes from snow surface elevation data acquired by spaceborne lasers (Jeffries et al., 2005).

Knowing which lakes and rivers freeze to their bottom (grounded ice) or not (floating ice), and when this occurs during the course of the winter period is critical for mapping and monitoring water availability and fish over-wintering

habitats and for planning winter ice roads. The potential of SAR imagery has been demonstrated for such purposes (Jeffries et al., 2005; Duguay and Lafleur, 2003). Surface measurements of parameters such as the dates of the first appearance of ice, complete freeze-over, beginning of thaw, and when the water body becomes completely free of ice (which are important for transportation) are not currently available.

11.5.8. Solid precipitation

Methods of observing solid precipitation include the precipitation gauge network, satellite remote sensing, and ground radar. Precipitation gauge networks and data are long term and fundamental; they make it possible to define global snowfall and climate regimes as well as changes. Manual and automatic precipitation gauges can measure the water equivalent of snowfall but not snow particle size. Manual gauges are standard at most national networks, although the use of automated systems is growing rapidly. Snow rulers are also used for snowfall observations in national or regional networks. They provide snow depth information only, not SWE. As important as gauge measurements are, quality control can be difficult (Figure 11.16).

Estimating solid precipitation amounts and rates from space is a challenge. The use of satellite data for solid precipitation measurements is limited and is an active area of research. Experimental products are available from passive microwave sounders (Kongoli et al., 2003) and cloud radar (Hiley et al., 2010). Various satellite data have been merged to improve the spatial and temporal coverage of precipitation products (Huffman et al., 1997). The future precipitation radar of the Global Precipitation Mission will observe solid precipitation, although its utility for high latitude snowfall is not clear. Of course, remote sensing of snow-cover extent and SWE data provide information on snowfall and have been widely used for large-scale climate and hydrology analyses.

Satellite retrievals have been blended with gauge data. For instance, the Global Precipitation Climatology Project has provided global coverage since 1987. Examination of hydrological budgets over several global river basins revealed



Figure 11.16. Conditions can make quality control challenging for solid precipitation measurement in the Arctic. Photos courtesy of B. Goodison, World Meteorological Organization.

unrealistically low precipitation in the merged products (Fekete et al., 2004). Over land, the magnitude of these combined products is primarily dominated by gauge observations. The under-estimation of land precipitation in the gauge-based analyses, and thus the merged analyses, is mostly due to the combined effect of a sparse gauge network biased toward low elevations, a lack of consideration of orographic effects, and gauge undercatch of precipitation, especially snowfall in cold and windy conditions.

Although ground-based radar provides information about precipitation at high spatial and temporal resolution, the coverage it provides is limited – much less extensive than the gauge networks. The radar network is particularly sparse and expensive to operate at high latitudes. In complex terrain, mountains often block the radar beam or the radar is located to scan over the top of mountains and not in the valleys. A new innovation is the deployment of a network of redundant low-cost, low-maintenance radars to scan the low levels of the atmosphere.

Problems in current precipitation gauge networks include the sparseness and decline of precipitation observation networks in cold regions, uneven distribution of sites and a resulting bias toward coastal and low-elevation areas, spatial and temporal discontinuities of precipitation measurements induced by changes in observation methods (such as

automation) and by different observation techniques used across national borders, biases in gauge measurements (such as wind-induced undercatch), underestimation of trace and low amounts of precipitation, and blowing snow in the gauges. There is no operational precipitation network over the oceans.

11.5.9. Summary

While there are numerous snow and ice surface measurement sites across the Arctic, operations at existing stations are, in general, not well coordinated. There is a need to improve the coordination of resources provided by national and international agencies responsible for cryospheric observations, and to facilitate the transition of research-based products into sustained monitoring systems. There is also a need to standardize the types and methods of measurements at surface stations, so that a robust and consistent set of snow and ice properties is available across the Arctic.

The satellite observing system for the cryosphere is robust, and missions planned for the next 10 to 20 years will provide even greater capabilities. Figure 11.17 shows the timeline of satellites that are used for monitoring the cryosphere. However, some potential gaps will be detrimental to long-term monitoring. In particular, the current gap in laser altimetry and the potential near-future gap in gravity measurements will impact ice sheet and glacier monitoring and change assessment.




Figure 11.17. Timeline of satellites used for measuring and monitoring the cryosphere as of 1 November 2011. Source: adapted from a figure by M. Drinkwater, European Space Agency.

Additionally, there are some critical parameters that are difficult to measure from space, notably sea-ice thickness, snow water equivalent, and accumulation on glaciers and ice sheets.

Traditional knowledge can provide important value-added content to data products and information and serves to make the data more useful and relevant to northern users (Chapter 10). Community-based observing programs provide a mechanism for two-way knowledge transfer, such as the Gwich'in First Nation International Polar Year (IPY) environmental monitoring project that includes snow cover monitoring along with a wide range of environmental, wildlife, and cultural variables. The ELOKA (Exchange for Local Observations and Knowledge of the Arctic) project will facilitate the collection, preservation, exchange, and use of local observations and knowledge of the Arctic and will foster collaboration between local and international researchers. Similarly, Sámi and scientists in Scandinavia are uniting traditional knowledge and scientific information on snow properties and monitoring (Chapter 4). Traditional knowledge can provide important supplementary information for the assessment of changes in the Arctic cryosphere.

While there are gaps and deficiencies in the cryosphere observing system, the data that do exist are underutilized. The use of cryospheric products in weather and climate models needs to be extended. Surface albedo is a good example, as many models use rudimentary and unrealistic albedo schemes for snow and ice. Data assimilation schemes for snow and ice variables are generally underdeveloped. Sea-ice extent and concentration data are assimilated at several real-time modeling centers, but ice thickness and motion data are not. Reprocessing of data products should be organized and promoted by national and international agencies and organizations.

Acknowledgments

Section 11.1: We thank Sebastian Gerland, Mats Granskog and two reviewers for comments on the manuscript. Terry Callaghan and Margareta Johansson gratefully acknowledge the support from the Swedish Research Councils FORMAS and the Environmental Protection Agency for supporting their involvement in the SWIPA process.

Section 11.5: Co-authors from other sections of this report provided valuable input, notably Lars-Otto Reiersen, Margareta Johansson, Terry Callaghan, Walter N. Meier, and James D. Reist. Some of the material in this chapter is based on the IGOS Cryosphere Theme Report. We thank the authors of that report.

References

- Ablain, M., A. Cazenave, G. Valladeau and S. Guinehut, 2009. A new assessment of the error budget of global mean sea level rate estimated by satellite altimetry over 1993–2008. *Ocean Science*, 5:193–201.
- ACIA, 2005. Arctic Climate Impact Assessment. 1042 pp. Cambridge University Press.
- Alekseev, G.V. and A.P. Nagurny, 2007. Role of sea ice in the formation of annual carbon dioxide cycle in the Arctic. *Doklady Earth Sciences*, 417:1398–1401.
- Allison, I., R.B. Alley, H.A. Fricker, R.H. Thomas and R.C. Warner, 2009. Ice sheet mass balance and sea level. *Antarctic Science*, 21:413–426.
- AMAP, 1998. AMAP Assessment Report: Arctic Pollution Issues. Arctic Monitoring and Assessment Programme (AMAP). 859 pp. Oslo, Norway.
- AMAP, 2007. Arctic Oil and Gas 2007. 57 pp. Arctic Monitoring and Assessment Programme. Oslo, Norway.
- AMAP, 2009. Arctic Pollution 2009. 97 pp. Arctic Monitoring and Assessment Programme. Oslo, Norway.
- AMAP, 2010. Assessment 2007. Oil and Gas Activities in the Arctic – Effects and Potential Effects. Volume 2. Arctic Monitoring and Assessment Programme. Oslo.
- AMAP, 2011a. AMAP Assessment 2011: Mercury in the Arctic. Arctic Monitoring and Assessment Programme. Oslo.
- AMAP, 2011b. The Impact of Black Carbon on Arctic Climate (2011). By: P.K. Quinn, A. Stohl, A. Arneth, T. Berntsen, J. F. Burkhardt, J. Christensen, M. Flanner, K. Kupiainen, H. Lihavainen, M. Shepherd, V. Shevchenko, H. Skov, and V. Vestreng. AMAP Technical Report No. 4 (2011). Arctic Monitoring and Assessment Programme (AMAP), Oslo. 72 pp.
- Anderson, L.G., E. Falck, E.P. Jones, S. Jutterström and J.H. Swift, 2004. Enhanced uptake of atmospheric CO₂ during freezing of seawater: A field study in Storfjorden, Svalbard. *Journal of Geophysical Research-Oceans*, 109:C06004.
- Andersson, M.E., J. Sommar, K. Gardfeldt and O. Lindqvist, 2008. Enhanced concentrations of dissolved gaseous mercury in the surface waters of the Arctic Ocean. *Marine Chemistry*, 110:190–194.
- Anisimov, O.A., D.G. Vaughan, T.V. Callaghan, C. Furgal, H. Marchant, T.D. Prowse, H. Vilhjálmsson and J.E. Walsh, 2007. Polar regions (Arctic and Antarctic). In: Parry, M.L., O.F. Canziani, J.P. Palutikof, C.E. Hanson and P.J. van der Linden (Eds.). *Climate Change 2007: Impacts, Adaptation and Vulnerability. Contribution of Working Group II to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change*. pp. 655–685. Cambridge University Press.
- Antoniades, D., J. Veillette, M.-J. Martineau, C. Belzile, J. Tomkins, R. Pienitz, S. Lamoureux and W.F. Vincent, 2009. Bacterial dominance of phototrophic communities in a High Arctic lake and its implications for paleoclimate analysis. *Polar Science*, 3:147–161.
- Arendt, A.A., K.A. Echelmeyer, W.D. Harrison, C.S. Lingle and V.B. Valentine, 2002. Rapid wastage of Alaska glaciers and their contribution to rising sea level. *Science*, 297:382–386.
- Arrigo, K.R., G. van Dijken and S. Pabi, 2008. Impact of a shrinking Arctic ice cover on marine primary production. *Geophysical Research Letters*, 35:L19603.
- Arzel, O., T. Fichefet, H. Goosse and J.L. Dufresne, 2008. Causes and impacts of changes in the Arctic freshwater budget during the twentieth and twenty-first centuries in an AOGCM. *Climate Dynamics*, 30:37–58.
- Babaluk, J.A., J.D. Reist, J.D. Johnson and L. Johnson, 2000. First records of sockeye (*Oncorhynchus nerka*) and pink salmon (*O. gorbuscha*) from Banks Island and other records of Pacific salmon in Northwest Territories, Canada. *Arctic*, 53:161–164.
- Bamber, J. and R. Riva, 2010. The sea level fingerprint of recent ice mass fluxes. *The Cryosphere*, 4:621–627.
- Bartsch, A., R.A. Kidd, W. Wagner and Z. Bartalis, 2007. Temporal and spatial variability of the beginning and end of daily spring freeze/thaw cycles derived from scatterometer data. *Remote Sensing of Environment*, 106:360–374.
- Becker, S., C.J. Halsall, W. Tych, R. Kallenborn, Y. Su and H. Hung, 2008. Long-term trends in α - and γ -HCH in the arctic atmosphere: the effect of legislation and climate fluctuations on atmospheric concentrations. *Atmospheric Environment*, 42:8225–8233.
- Becker, S., C.J. Halsall, W. Tych, R. Kallenborn, M. Schlabach and S. Manø, 2009. Changing sources and environmental factors reduce the rates of decline of organochlorine pesticides in the Arctic Atmosphere. *Atmospheric Chemistry and Physics Discussions*, 9:515–540.
- Beier, C.M., S.E. Sink, P.E. Hennon, D.V. D'Amore and G.P. Juday, 2008. Twentieth-century warming and the dendroclimatology of declining yellow-cedar forests in southeastern Alaska. *Canadian Journal of Forest Research*, 38:1319–1334.
- Beltaos, S., T. Prowse, B. Bonsal, R. MacKay, L. Romolo, A. Pietroniro and B. Toth, 2006. Climatic effects on ice-jam flooding of the Peace-Athabasca Delta. *Hydrological Processes*, 20:4031–4050.
- Berger, W.H., 2008. Sea level in the late Quaternary: patterns of variation and implications. *International Journal of Earth Sciences*, 97:1143–1150.
- Bidleman, T.F., H. Kylin, L.M. Jantunen, P.A. Helm and R.W. Macdonald, 2007. Hexachlorocyclohexanes in the Canadian Archipelago. 1. Spatial distribution and pathways of α -, β -, and γ -HCHs in surface water. *Environmental Science and Technology*, 41:2688–2695.
- Bindoff, N.L., J. Willebrand, V. Artale, A. Cazenave, J. Gregory, S. Gulev, K.

- Hanawa, C. Le Quéré, S. Levitus, Y. Nojiri, C.K. Shum, L.D. Talley and A. Unnikrishnan, 2007. Observations: Oceanic climate change and sea level. In: Solomon, S., D. Qin, M. Manning, Z. Chen, M. Marquis, K.B. Averyt, M. Tignor and H.L. Miller (Eds.). *Climate Change 2007: The Physical Science Basis*. Contribution of Working Group I to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change. Cambridge University Press.
- Bishop, M.P., J.A. Olsenholler, J.F. Shroder, R.G. Barry, B.H. Raup, A.B. G. Bush, L. Copland, J.L. Dwyer, A.G. Fountain, W. Haeberli, A. Käb, F. Paul, D.K. Hall, J.S. Kargel, B.F. Molnia, D.C. Trabant and R. Wessels, 2004. Global land ice measurements from space (GLIMS): Remote sensing and GIS investigations of the Earth's cryosphere. *Geocarto International*, 19:57–84.
- Bitz, C.M., 2008. Some aspects of uncertainty in predicting sea ice retreat, in Arctic sea ice decline: observations, projections, mechanisms, and implications. AGU Geophysical Monograph Series, vol. E. deWeaver, C. M. Bitz, B. Tremblay (Eds.). pp. 63–76, American Geophysical Union.
- Blais, J.M., D.W. Schindler, D.C.G. Muir, M. Sharp, D. Donald, M. Lafreniere, E. Braekevelt and W.M.J. Strachan, 2001. Melting glaciers: A major source of persistent organochlorines to subalpine Bow Lake in Banff National Park, Canada. *Ambio*, 30:410–415.
- Blais, J.M., R.W. Macdonald, D. Mackey, E. Webster, C. Harvey and J.P. Smol, 2007. Biologically mediated transport of contaminants to aquatic systems. *Environmental Science and Technology*, 41:1075–1084.
- Bogdal, C., P. Schmid, M. Zennegg, F.S. Anselmetti, M. Scheringer and K. Hungerbühler, 2009. Blast from the past: Melting glaciers as a relevant source for persistent organic pollutants. *Environmental Science and Technology*, 43:8173–8177.
- Bokhorst, S., J.W. Bjerke, F.W. Bowles, J. Melillo, T.V. Callaghan and G.K. Phoenix, 2008. Impacts of extreme winter warming in the sub-Arctic: growing season responses of dwarf shrub heathland. *Global Change Biology*, 14:2603–2612.
- Bokhorst, S., J.W. Bjerke, H. Tømmervik, C. T.V. and G.K. Phoenix, 2009. Winter warming events damage sub-Arctic vegetation: consistent evidence from an experimental manipulation and a natural event. *Journal of Ecology*, 97:1408–1415.
- Bolin, B., 2007. A History of the Science and Politics of Climate Change. The role of the Intergovernmental Panel on Climate Change. 292 pp. Cambridge University Press.
- Borgå, K., G.W. Gabrielsen, J.U. Skaare, L. Kleivane, R.J. Norstrom and A.T. Fisk, 2005. Why do organochlorine differences between arctic regions vary among trophic levels? *Environmental Science and Technology*, 39:4343–4352.
- Borgå, K., T.M. Saloranta and A. Ruus, 2010. Simulating climate change-induced alterations in bioaccumulation of organic contaminants in an Arctic marine food web. *Environmental Toxicology and Chemistry*, 29:1349–1357.
- Borgstrom, R., 2001. Relationship between spring snow depth and growth of brown trout, *Salmo trutta*, in an alpine lake: Predicting consequences of climate change. *Arctic Antarctic and Alpine Research*, 33:476–480.
- Brown, R.D. and P.W. Mote, 2009. The response of northern hemisphere snow cover to a changing climate. *Journal of Climate*, 22:2124–2145.
- Brown, T.M., T.A. Sheldon, N.M. Burgess and K.J. Reimer, 2009. Reduction of PCB contamination in an Arctic coastal environment: A first step in assessing ecosystem recovery after the removal of a point source. *Environmental Science and Technology*, 43:7635–7642.
- Bunn, A.G., S.J. Goetz, J.S. Kimball and K. Zhang, 2007. Northern high latitude ecosystems respond to recent climate change. *Eos Transactions, American Geophysical Union*, 88:333–338.
- Bustnes, J.O., G.W. Gabrielsen and J. Verreault, 2010. Climate variability and temporal trends of persistent organic pollutants in the Arctic: A study of glaucous gulls. *Environmental Science and Technology*, 44:3155–3161.
- Cai, W.J., L.Q. Chen, B.S. Chen, Z.Y. Gao, S.H. Lee, J.F. Chen, D. Pierrot, K. Sullivan, Y.C. Wang, X.P. Hu, W.J. Huang, Y.H. Zhang, S.Q. Xu, A. Murata, J.M. Grebmeier, E.P. Jones and H.S. Zhang, 2010. Decrease in the CO₂ uptake capacity in an ice-free Arctic Ocean basin. *Science*, 329:556–559.
- Callaghan, T., V., L.O. Björn, Y. Chernov, I.F.S. Chapin, T.R. Christensen, B. Huntley, R.A. Ims, D. Jolly, M. Johansson, S. Jonasson, N. Matveyeva, N. Panikov, W.C. Oechel, G.R. Shaver, J. Elster, I.S. Jonsdottir, K. Laine, K. Taulavuori, E. Taulavuori and C. Zöckler, 2004a. Climate change and UV-B impacts on Arctic tundra and polar desert ecosystems: Responses to projected changes in climate and UV-B at the species level. *Ambio*, 33:418–435.
- Callaghan, T., V., L.O. Björn, Y. Chernov, I.F.S. Chapin, T.R. Christensen, B. Huntley, R.A. Ims, D. Jolly, M. Johansson, S. Jonasson, N. Matveyeva, N. Panikov, W.C. Oechel, G.R. Shaver, S. Schaphoff and S. Sitch, 2004b. Climate change and UV-B impacts on Arctic tundra and polar desert ecosystems: Effects of changes in climate on landscape and regional processes, and feedbacks to the climate system. *Ambio*, 33:459–468.
- Carmack, E.C., 2000. The Arctic Ocean's freshwater budget: Sources, storage and export. In: Lewis, E.L., E.P. Jones, P. Lemke, T.D. Prowse and P. Wadhams (Eds.). *The Freshwater Budget of the Arctic Ocean*. pp. 91–126. Kluwer Academic Publishers.
- Carrie, J., F. Wang, H. Sanei, R.W. Macdonald, P.M. Outridge and G.A. Stern, 2010. Increasing contaminant burdens in an Arctic fish, burbot (*Lota lota*), in a warming climate. *Environmental Science and Technology*, 44:316–322.
- Cazenave, A. and W. Llovel, 2010. Contemporary sea level rise. *Annual Review of Marine Science*, 2:145–173.
- Cazenave, A., A. Lombard and W. Llovel, 2008. Present-day sea level rise: A synthesis. *Comptes Rendus Geoscience*, 340:761–770.
- Cazenave, A., K. Dominh, S. Guinehut, E. Berthier, W. Llovel, G. Ramillien, M. Ablain and G. Larnicol, 2009. Sea level budget over 2003–2008: A reevaluation from GRACE space gravimetry, satellite altimetry and Argo. *Global and Planetary Change*, 65:83–88.
- Chapin, F.S., M. Sturm, M.C. Serreze, J.P. McFadden, J.R. Key, A.H. Lloyd, A.D. McGuire, T.S. Rupp, A.H. Lynch, J.P. Schimel, J. Beringer, W.L. Chapman, H.E. Epstein, E.S. Euskirchen, L.D. Hinzman, G. Jia, C.L. Ping, K.D. Tape, C.D.C. Thompson, D.A. Walker and J.M. Welker, 2005. Role of land-surface changes in Arctic summer warming. *Science*, 310:657–660.
- Chen, J.L., C.R. Wilson and B.D. Tapley, 2006. Satellite gravity measurements confirm accelerated melting of Greenland ice sheet. *Science*, 313:1958–1960.
- Cherry, S.G., A.E. Derocher, I. Stirling and E.S. Richardson, 2009. Fasting physiology of polar bears in relation to environmental change and breeding behavior in the Beaufort Sea. *Polar Biology*, 32:383–391.
- Chételat, J. and M. Amyot, 2009. Elevated methylmercury in High Arctic *Daphnia* and the role of productivity in controlling their distribution. *Global Change Biology*, 15:706–718.
- Chizhova, Y.N., 2005. Chemical additions in snow cover and glacier ice of mountain regions of Elbrus, Polar Urals and Khibiny Mountains. *Moscow University Bulletin, Geography Series*. 56 pp.
- Christensen, T.R., T. Johansson, N. Malmer, J. Åkerman, T. Friberg, P. Crill, M. Mastepanov and S. B., 2004. Thawing sub-arctic permafrost: Effects on vegetation and methane emissions. *Geophysical Research Letters*, 31:L04501.
- Chudinova, S.M., O.W. Frauenfeld, R.G. Barry, T.J. Zhang and V.A. Sorokovikov, 2006. Relationship between air and soil temperature trends and periodicities in the permafrost regions of Russia. *Journal of Geophysical Research-Earth Surface*, 111:F02008.
- Church, J.A. and N.J. White, 2006. A 20th century acceleration in global sea-level rise. *Geophysical Research Letters*, 33:L01602.
- Church, J.A., J.M. Gregory, P. Huybrechts, M. Kuhn, K. Lambeck, M.T. Nhuan, D. Qin and P. Woodworth, 2001. Changes in sea level. In: Houghton, J.T., Y. Ding, D.J. Griggs, M. Noguer, P. van der Linder, X. Dai, K. Maskell and C.I. Johnson (Eds.). *Climate change 2001: The scientific basis*. Contribution of Working Group I to the Third Assessment Report of the Intergovernmental Panel on Climate Change. pp. 639–693. Cambridge University Press.
- Cogley, J.G., 2009. Geodetic and direct mass - balance measurements: comparison and joint analysis. *Annals of Glaciology*, 50:96–100.
- Cooper, L.W., J.W. McClelland, R.M. Holmes, P.A. Raymond, J.J. Gibson, C.K. Guay and B.J. Peterson, 2008. Flow-weighted values of runoff tracers (delta ¹⁸O, DOC, Ba, alkalinity) from the six largest Arctic rivers. *Geophysical Research Letters*, 35: L18606.
- Corcoran, R.M., J.R. Lovvorn and P.J. Heglund, 2009. Long-term change in limnology and invertebrates in Alaskan boreal wetlands. *Hydrobiologia*, 620:77–89.
- Cossa, D., B. Averyt and N. Pirrone, 2009. The origin of methylmercury in open Mediterranean waters. *Limnology and Oceanography*, 54:837–844.
- Couillard, C.M., R.W. Macdonald, S.C. Courtenay and V.P. Palace, 2008. Chemical-environment interactions affecting the risk of impacts on aquatic organisms: A review with a Canadian perspective - interactions

- affecting exposure. *Environmental Reviews*, 16:1–17.
- Curry, J.A., J.L. Schramm and E.E. Ebert, 1995. Sea ice-albedo climate feedback mechanism. *Journal of Climate*, 8:240–247.
- Daly, G.L. and F. Wania, 2004. Simulating the influence of snow on the fate of organic compounds. *Environmental Science and Technology*, 38:4176–4186.
- Danon-Schaffer, M.N., J.R. Grace and M.G. Ikononou, 2008. PBDEs in waste disposal sites from Northern Canada. *Organohalogen Compounds*, 70:365–368.
- Dethloff, K., A. Rinke, A. Benkel, M. Koltzow, E. Sokolova, S.K. Saha, D. Handorf, W. Dorn, B. Rockel, H. von Storch, J.E. Haugen, L.P. Roed, E. Roeckner, J.H. Christensen and M. Stendel, 2006. A dynamical link between the Arctic and the global climate system. *Geophysical Research Letters*, 33:L03703.
- Domine, F., A. Cincinelli, E. Bonnaud, T. Martellini and S. Picaud, 2007. Adsorption of phenanthrene on natural snow. *Environmental Science and Technology*, 41:6033–6038.
- Domingues, C.M., J.A. Church, N.J. White, P.J. Gleckler, S.E. Wijffels, P.M. Barker and J.R. Dunn, 2008. Improved estimates of upper-ocean warming and multi-decadal sea-level rise. *Nature*, 453:1090.
- Donald, D.B., J. Syrgiannis, R.W. Crosley, G. Holdsworth, D.C.G. Muir, B. Rosenberg, A. Sole and D. Schindler, 1999. Delayed deposition of organochlorine pesticides at a temperate glacier. *Environmental Science and Technology*, 33:1794–1798.
- Dorrepal, E., S. Toet, R.S.P. van Logtestijn, E. Swart, M.J. van de Weg, T.V. Callaghan and R. Aerts, 2009. Carbon respiration from subsurface peat accelerated by climate warming in the subarctic. *Nature*, 460:616–619.
- Drinkwater, K.F., 2005. The response of Atlantic cod (*Gadus morhua*) to future climate change. *ICES Journal of Marine Science*, 62:1327–1337.
- Duguay, C.R. and P.M. Lafleur, 2003. Determining depth and ice thickness of shallow sub-Arctic lakes using space-borne optical and SAR data. *International Journal of Remote Sensing*, 24:475–489.
- Duguay, C.R., G.M. Flato, M.O. Jeffries, P. Ménard, K. Morris and W.R. Rouse, 2003. Ice-cover variability on shallow lakes at high latitudes: model simulations and observations. *Hydrological Processes*, 17:3465–3483.
- Duguay, C.R., T. Zhang, D.W. Leverington and V.E. Romanovsky, 2005. Satellite remote sensing of permafrost and seasonally frozen ground. In: Duguay, C.R. and A. Pietroniro (Eds.). *Remote Sensing in Northern Hydrology: Measuring Environmental Change*. pp. 91–118. American Geophysical Union.
- Durner, G.M., D.C. Douglas, R.M. Nielson, S.C. Amstrup, T.L. McDonald, I. Stirling, M. Mauritzen, E.W. Born, Ø. Wiig, E. DeWeaver, M.C. Serreze, S.E. Belikov, M.M. Holland, J. Maslanik, J. Aars, D.A. Bailey and A.E. Derocher, 2009. Predicting 21st-century polar bear habitat distribution from global climate models. *Ecological Monographs*, 79:25–58.
- Dyke, L.D., 2001. Contaminant migration through the permafrost active layer, Mackenzie Delta area, Northwest Territories, Canada. *Polar Record*, 37:215–228.
- Dyrgerov, M.B. and C.L. Carter, 2004. Observational evidence of increases in freshwater inflow to the Arctic Ocean. *Arctic Antarctic and Alpine Research*, 36:117–122.
- Dyrgerov, M.B. and M.F. Meier, 1997. Mass balance of mountain and subpolar glaciers: A new global assessment for 1961–1990. *Arctic and Alpine Research*, 29:379–391.
- Dyrgerov, M., M.F. Meier and D.B. Bahr, 2009. A new index of glacier area change: a tool for glacier monitoring. *Journal of Glaciology*, 55:710–716.
- Eckhardt, S., K. Breivik, S. Manø and A. Stohl, 2007. Record high peaks in PCB concentrations in the Arctic atmosphere due to long-range transport of biomass burning emissions. *Atmospheric Chemistry and Physics*, 7:4527–4536.
- Elberling, B., H.H. Christiansen and B.U. Hansen, 2010. High nitrous oxide production from thawing permafrost. *Nature Geoscience*, 3:332–335.
- Emmerton, C.A., L.F.W. Lesack and W.F. Vincent, 2008. Mackenzie River nutrient delivery to the Arctic Ocean and effects of the Mackenzie Delta during open water conditions. *Global Biogeochemical Cycles*, 22:GB1024.
- Essery, R., J. Pomeroy, C. Ellis and T. Link, 2008. Modelling longwave radiation to snow beneath forest canopies using hemispherical photography or linear regression. *Hydrological Processes*, 22:2788–2800.
- Euskirchen, E.S., A.D. McGuire, D.W. Kicklighter, Q. Zhuang, J.S. Clein, R.J. Dargaville, D.G. Dye, J.S. Kimball, K.C. McDonald, J.M. Melillo, V.E. Romanovsky and N.V. Smith, 2006. Importance of recent shifts in soil thermal dynamics on growing season length, productivity, and carbon sequestration in terrestrial high-latitude ecosystems. *Global Change Biology*, 12:731–750.
- Euskirchen, E.S., A.D. McGuire and F.S. Chapin III, 2007. Energy feedbacks of northern high-latitude ecosystems to the climate system due to reduced snow cover during 20th century warming. *Global Change Biology*, 13:2425–2438.
- Euskirchen, E.S., A.D. McGuire, F.S. Chapin III, S. Yi and C.C. Thompson, 2009. Changes in vegetation in northern Alaska under scenarios of climate change, 2003–2100: implications for climate feedbacks. *Ecological Applications*, 19:1022–1043.
- Faïn, X., C.P. Ferrari, A. Dommergue, M.R. Albert, M. Battle, J. Severinghaus, L. Arnaud, J.M. Barnola, W. Cairns, C. Barbante and C. Boutron, 2009. Polar firn air reveals large-scale impact of anthropogenic mercury emissions during the 1970s. *Proceedings of the National Academy of Sciences of the United States of America*, 106:16114–16119.
- Falk-Petersen, S., E. Leu, J. Berge, S. Kwasniewski, H. Nygård, A. Røstad, E. Keskinen, J. Thormar, C. von Quillfeldt, A. Wold and B. Gulliksen, 2008. Vertical migration in high Arctic waters during autumn 2004. *Deep-Sea Research Part II-Topical Studies in Oceanography*, 55:2275–2284.
- Falk-Petersen, S., P. Mayzaud, G. Kattner and J. Sargent, 2009. Lipids and life strategy of Arctic *Calanus*. *Marine Biology Research*, 5:18–39.
- Feehan, J., M. Harley and J. van Minnen, 2009. Climate change in Europe. 1. Impact on terrestrial ecosystems and biodiversity. A review. *Agronomy for Sustainable Development*, 29:409–421.
- Fekete, B.M., C.J. Vörösmarty, J.O. Roads and C.J. Willmot, 2004. Uncertainties in precipitation and their impacts on runoff estimates. *Journal of Climate*, 17:294–304.
- Fernandes, R., H. Zhao, X. Wang, J. Key, X. Qu and A. Hall, 2009. Controls on Northern Hemisphere snow albedo feedback quantified using satellite Earth observations. *Geophysical Research Letters*, 36:L21702.
- Fitzgerald, W.F., C.H. Lamborg and C.R. Hammerschmidt, 2007. Marine biogeochemical cycling of mercury. *Chemical Reviews*, 107:641–662.
- Flanner, M.G., C.S. Zender, P.G. Hess, N.M. Mahowald, T.H. Painter, V. Ramanathan and P.J. Rasch, 2008. Springtime warming and reduced snow cover from carbonaceous particles. *Atmospheric Chemistry and Physics*, Discussions, 8:19819–19859.
- Fleming, S.W., 2005. Comparative analysis of glacial and nival streamflow regimes with implications for lotic habitat quantity and fish species richness. *River Research and Applications*, 21:363–379.
- Fletcher, C.G., P.J. Kushner, A. Hall and X. Qu, 2009. Circulation responses to snow albedo feedback in climate change. *Geophysical Research Letters*, 36:L09702.
- Forchhammer, M.C., N.M. Schmidt, T.T. Høye, T.B. Berg, D.K. Hendrichsen and E. Post, 2008. Population dynamical responses to climate change. *Advances in Ecological Research*, 40: 391–419.
- Forster, P., V. Ramaswamy, P. Artaxo, T. Bernsten, R. Betts, D.W. Fahey, J. Haywood, J. Lean, D.C. Lowe, G. Myhre, J. Nganga, R. Prinn, G. Raga, M. Schulz and M.R. van Dorland, 2007. Changes in atmospheric constituents and radiative forcing. In: Solomon, S. and M.M. D. Qin, Z. Chen, M. Marquis, K.B. Averyt, M. Tignor and H.L. Miller (Eds.). *Climate Change 2007: The Physical Science Basis. Contribution of Working Group I to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change*. Cambridge University Press.
- Fortier, L., D. Barber and J. Michaud (Eds.), 2008. *On Thin Ice: A Synthesis of the Canadian Arctic Shelf Exchange Study (CASES)*. 215 pp. Aboriginal Issue Press, University of Manitoba.
- Fox, C., R. Harris, S. Sundby, E. Achterberg, J.I. Allen, J. Allen, A. Baker, C.P.D. Brussaard, P. Buckley, E.J. Cook, S.R. Dye, M. Edwards, L. Fernand, P. Kershaw, J. Metcalfe, S. Osterhus, T. Potter, E. Sakshaug, D. Speirs, E. Stenevik, M.S. John, F. Thingstad and B. Wilson, 2009. Transregional linkages in the North Eastern Atlantic - An 'end-to-end' analysis of pelagic ecosystems. *Oceanography and Marine Biology: An Annual Review*, 47:1–75.
- Francis, J.A., D.M. White, J.J. Cassano, W.J. Gutowski, L.D. Hinzman, M.M. Holland, M.A. Steele and C.J. Vorosmarty, 2009. An arctic hydrologic system in transition: Feedbacks and impacts on terrestrial, marine, and human life. *Journal of Geophysical Research-Biogeosciences*, 114:G04019.

- Fricker, H.A., T. Scambos, R. Bindshadler and L. Padman, 2007. An active subglacial water system in West Antarctica mapped from space. *Science*, 315:1544–1548.
- Gaden, A., S.H. Ferguson, L. Harwood, H. Melling and G.A. Stern, 2009. Mercury trends in ringed seals (*Phoca hispida*) from the Western Canadian Arctic since 1973: Associations with length of ice-free season. *Environmental Science and Technology*, 43:3646–3651.
- Gagnon, C.A. and D. Berteaux, 2009. Integrating traditional ecological knowledge and ecological science: a question of scale. *Ecology and Society*, 14:19.
- Galand, P.E., C. Lovejoy, J. Pouliot, M.E. Garneau and W.F. Vincent, 2008. Microbial community diversity and heterotrophic production in a coastal Arctic ecosystem: A stamukhi lake and its source waters. *Limnology and Oceanography*, 53:813–823.
- Gantner, N., M. Power, D. Iqaluk, M. Meili, H. Borg, M. Sundbom, K. Solomon, G. Lawson and D.C. Muir, 2010. Mercury concentrations in landlocked Arctic char (*Salvelinus alpinus*) from the Canadian Arctic: Part I - insights from trophic relationships in 18 lakes. *Environmental Toxicology and Chemistry*, 29:621–632.
- Garneau, M.-E., W.F. Vincent, R. Terrado and C. Lovejoy, 2008. Importance of particle-associated bacterial heterotrophy in a coastal Arctic ecosystem. *Journal of Marine Systems*, 75:185–197.
- Garrett, T.J. and C.F. Zhao, 2006. Increased Arctic cloud longwave emissivity associated with pollution from mid-latitudes. *Nature*, 440:787–789.
- Gaston, A.J., K. Woo and J.M. Hipfner, 2003. Trends in forage fish populations in northern Hudson Bay since 1981, as determined from the diet of nestling thick-billed murres *Uria lomvia*. *Arctic*, 56:227–233.
- Gieisz, H.N., R.M. Dickhut, M.A. Chochran, W.R. Fraser and H.W. Ducklow, 2008. Melting glaciers: A probable source of DDT to the Antarctic marine ecosystem. *Environmental Science and Technology*, 42:3958–3962.
- Gilichinsky, D., T. Vishnivetskaya, M. Petrova, E. Spirina, V. Mamykin and E. Rivkina, 2008. Bacteria in permafrost. In: Margesin, R., F. Schinner, J.-C. Marx and C. Gerday (Eds.). *Psychrophiles: From Biodiversity to Biotechnology*. pp. 83–102. Springer.
- Gioia, R., R. Lohmann, J. Dachs, C. Temme, S. Lakaschus, D. Schulz-Bull, I. Hand and K.C. Jones, 2008. Polychlorinated biphenyls in air and water of the North Atlantic and Arctic Ocean. *Journal of Geophysical Research-Atmospheres*, 113:D19302.
- Goetz, S.J., M.C. Mack, K.R. Gurney, J.T. Randerson and R.A. Houghton, 2007. Ecosystem responses to recent climate change and fire disturbance at northern high latitudes: observations and model results contrasting northern Eurasia and North America. *Environmental Research Letters*, 2:045031.
- Göttel, H., J. Alexander, E. Keup-Thiel, D. Rechid, S. Hagemann, T. Blome, A. Wolf and D. Jacob, 2008. Influence of changed vegetations fields on regional climate simulations in the Barents Sea Region. *Climatic Change*, 87:35–50.
- Granberg, H.B., 1994. Mapping heat loss zones for permafrost prediction at the northern alpine limit of the Boreal forest using high-resolution C-Band SAR. *Remote Sensing of Environment*, 50:280–286.
- Graverson, R.G. and M. Wang, 2009. Polar amplification in a coupled climate model with locked albedo. *Climate Dynamics*, 33:629–643.
- Grebmeier, J.M., J.E. Overland, S.E. Moore, E.V. Farley, E.C. Carmack, L.W. Cooper, K.E. Frey, J.H. Helle, F.A. McLaughlin and S.L. McNutt, 2006. A major ecosystem shift in the northern Bering Sea. *Science*, 311:1461–1464.
- Grinsted, A., J.C. Moore and S. Jevrejeva, 2009. Reconstructing sea level from paleo and projected temperatures 200 to 2100 AD. *Climate Dynamics*, 34:461–472.
- Haerberli, W., 2006. Integrated perception of glacier changes: a challenge of historical dimensions. In: Knight, P.G. (Ed.). *Glacier Science and Environmental Change*. pp. 423–430. Blackwell.
- Hakkinen, S., A. Proshutinsky and I. Ashik, 2008. Sea ice drift in the Arctic since the 1950s. *Geophysical Research Letters*, 35:L19704.
- Haldorsen, S., M. Heim, B. Dale, J.Y. Landvik, M. van der Ploeg, A. Leijnse, O. Salvigsen, J.O. Hagen and D. Banks, 2010. Sensitivity to long-term climate change of sub-permafrost groundwater systems in Svalbard. *Quaternary Research*, 73:393–402.
- Halsall, C.J., 2004. Investigating the occurrence of persistent organic pollutants (POPs) in the arctic: their atmospheric behaviour and interaction with the seasonal snow pack. *Environmental Pollution*, 128:163–175.
- Hammerschmidt, C.R. and W.F. Fitzgerald, 2006. Photodecomposition of methylmercury in an arctic Alaskan lake. *Environmental Science and Technology*, 40:1212–1216.
- Hammerschmidt, C.R., W.F. Fitzgerald, C.H. Lamborg, P.H. Balcom and C.M. Tseng, 2006. Biogeochemical cycling of methylmercury in lakes and tundra watersheds of Arctic Alaska. *Environmental Science and Technology*, 40:1204–1211.
- Hansen, K.M., C.J. Halsall, J.H. Christensen, J. Brandt, L.M. Frohn, C. Geels and C.A. Skjøth, 2008. The role of the snowpack on the fate of alpha-HCH in an atmospheric chemistry-transport model. *Environmental Science and Technology*, 42:2943–2948.
- Harding, T., A.D. Jungblut, C. Lovejoy and W.F. Vincent, 2011. Microbes in High Arctic snow and implications for the cold biosphere. *Applied and Environmental Microbiology*, 77:3234–3243.
- Harris, R.C., J.W.M. Rudd, M. Amyot, C.L. Babiarz, K.G. Beaty, P.J. Blanchfield, R.A. Bodaly, B.A. Branfireun, C.C. Gilmour, J.A. Graydon, A. Heyes, H. Hintelmann, J.P. Hurley, C.A. Kelly, D.P. Krabbenhoft, S.E. Lindberg, R.P. Mason, M.J. Paterson, C.L. Podemski, A. Robinson, K.A. Sandilands, G.R. Southworth, V.L.S. Louis and M.T. Tate, 2007. Whole-ecosystem study shows rapid fish-mercury response to changes in mercury deposition. *Proceedings of the National Academy of Sciences of the United States of America*, 104:16586–16591.
- Hegseth, E.N. and A. Sundfjord, 2008. Intrusion and blooming of Atlantic phytoplankton species in the high Arctic. *Journal of Marine Systems*, 74:108–119.
- Henningsen, S. and T. Alerstam, 2008. The role of migration for spatial turnover of arctic bird species in a circumpolar perspective. *Oikos*, 117:1619–1628.
- Herbert, B.M.J., C.J. Halsall, K.C. Jones and R. Kallenborn, 2006a. Field investigation into the diffusion of semi-volatile organic compounds into fresh and aged snow. *Atmospheric Environment*, 40:1385–1393.
- Herbert, B.M.J., S. Villa and C. Halsall, 2006b. Chemical interactions with snow: Understanding the behavior and fate of semi-volatile organic compounds in snow. *Ecotoxicology and Environmental Safety*, 63:3–16.
- Hermanson, M.H., E.H. Isaksson, C. Teixeira, D.C.G. Muir, K.M. Compher, Y.F. Li, I. Igarashi and K. Kamiyama, 2005. Current-use and legacy pesticide history in the Austfonna ice cap, Svalbard, Norway. *Environmental Science and Technology*, 39:8163–8169.
- Hiley, M., M. Kulie and R. Bennartz, 2010. Uncertainty analysis for CloudSat snowfall retrievals. *Journal of Applied Meteorology and Climatology*, 50:399–418.
- Holgate, S.J. and P.L. Woodworth, 2004. Evidence for enhanced coastal sea level rise during the 1990s. *Geophysical Research Letters*, 31:L07305.
- Holland, M.M., J. Finnis, A.P. Barrett and M.C. Serreze, 2007. Projected changes in arctic ocean freshwater budgets. *Journal of Geophysical Research-Biogeosciences*, 112:G04S55.
- Huffman, G.J., R.F. Adler, P. Arkin, A. Chang, R. Ferraro, A. Gruber, J. Janowiak, A. McNab, B. Rudolf and U. Schneider, 1997. The Global Precipitation Climatology Project (GPCP) Combined Precipitation Dataset. *Bulletin of the American Meteorological Society*, 78:5–20.
- Hung, H., R. Kallenborn, K. Breivik, Y.S. Su, E. Brorstrom-Lunden, K. Olafsdottir, J.M. Thorlacius, S. Leppanen, R. Bossi, H. Skov, S. Manø, G.W. Patton, G. Stern, E. Sverko and P. Fellin, 2010. Atmospheric monitoring of organic pollutants in the Arctic under the Arctic Monitoring and Assessment Programme (AMAP): 1993–2006. *Science of the Total Environment*, 408:2854–2873.
- Huntington, H.P., 2009. A preliminary assessment of threats to arctic marine mammals and their conservation in the coming decades. *Marine Policy*, 33:77–82.
- Huse, G. and I. Ellingsen, 2008. Capelin migrations and climate change - a modelling analysis. *Climatic Change*, 87:177–197.
- Huusko, A., L. Greenberg, M. Stickler, T. Linnansaari, M. Nykänen, T. Vehanen, S. Koljonen, P. Louhi and K. Alfredsen, 2007. Life in the ice lane: The winter ecology of stream salmonids. *River Research and Applications*, 23:469–491.
- IGOS, 2007. Integrated Global Observing Strategy Cryosphere Theme Report - For the Monitoring of our Environment from Space and from Earth. World Meteorological Organization. Geneva. 114 pp.
- IPCC, 2007. Climate Change 2007: The Physical Science Basis. Contribution of Working Group I to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change. Solomon, S., D. Qin, M. Manning, Z. Chen, M. Marquis, K.B. Averyt, M. Tignor and

- H.L. Miller (Eds.) Cambridge University Press.
- Ishii, M. and M. Kimoto, 2009. Reevaluation of historical ocean heat content variations with varying XBT and MBT depth bias corrections. *Journal of Oceanography*, 65:287–99.
- Jantunen, L.M., P.A. Helm, H. Kylin and T.F. Bidleman, 2008. Hexachlorocyclohexanes (HCHs) in the Canadian archipelago. 2. Air–water gas exchange of α , and γ -HCH. *Environmental Science and Technology*, 42:465–470.
- Jeffries, M., K. Morris and N. Kozlenko, 2005. Ice characteristics and processes, and remote sensing of frozen rivers and lakes. *Remote Sensing in Northern Hydrology: Measuring Environmental Change*. pp. 63–90. American Geophysical Union.
- Jones, H.G., J.W. Pomeroy, D.A. Walker and R. Hoham (Eds.), 2001. *Snow Ecology*. 378 pp. Cambridge University Press.
- Jones, E.P., L.G. Anderson, S. Jutterström, L. Mintrop and J.H. Swift, 2008. Pacific freshwater, river water and sea ice meltwater across Arctic Ocean basins: Results from the 2005 Beringia Expedition. *Journal of Geophysical Research-Oceans*, 113:C08012.
- Jonsson, A., J. Karlsson and M. Jansson, 2003. Sources of carbon dioxide supersaturation in clearwater and humic lakes in northern Sweden. *Ecosystems*, 6:224–235.
- Jorgenson, M.T. and T.E. Osterkamp, 2005. Response of boreal ecosystems to varying modes of permafrost degradation. *Canadian Journal of Forest Research*, 35:2100–2111.
- Juday, G.P., V. Barber, P. Duffy, H. Linderholm, S. Rupp, S. Sparrow, E. Vaganov, Y. Yarie, E. Berg, R. D'Arrigo, O. Eggertsson, V.V. Fyryaev, E.H. Hogg, S. Huttunen, G. Jacoby, V.Y. Kaplunov, S. Kellomaki, A.V. Kirilyanov, C.E. Lewis, S. Linder, M.M. Naurzbaev, E.I. Pleshikov, U.T. Runesson, Y.V. Savva, O.V. Sidorova, V.D. Stakanov, N.M. Tchebakova, E.N. Valendik, E.F. Vedrova and M. Wilmking, 2005. Forests, land management, and agriculture. In: *Arctic Climate Impacts Assessment*. pp. 781–862. Cambridge University Press.
- Karcher, M., I. Harms, W.J.F. Standring, M. Dowall and P. Strand, 2010. On the potential for climate change impacts on marine anthropogenic radioactivity in the Arctic regions. *Marine Pollution Bulletin*, 60:1151–1159.
- Kargel, J.S., M.J. Abrams, M.P. Bishop, A. Bush, G. Hamilton, H. Jiskoot, A. Kaab, H.H. Kieffer, E.M. Lee, F. Paul, F. Rau, B. Raup, J.F. Shroder, D. Soltesz, D. Stainforth, L. Stearns and R. Wessels, 2005. Multispectral imaging contributions to global land ice measurements from space. *Remote Sensing of Environment*, 99:187–219.
- Kaser, G., J.G. Cogley, M.B. Dyurgerov, M.F. Meier and A. Ohmura, 2006. Mass balance of glaciers and ice caps: Consensus estimates for 1961–2004. *Geophysical Research Letters*, 33:L19501.
- Kattsov, V.M. and E. Källén, 2005. Future climate change: Modeling and scenarios for the Arctic. In: *Arctic Climate Impact Assessment*. pp. 99–150. Cambridge University Press.
- Kausrud, K.L., A. Mysterud, H. Steen, J.O. Vik, E. Østbye, B. Cazelles, E. Framstad, A.M. Eikeset, I. Mysterud, T. Solhøy and N.C. Stenseth, 2008. Linking climate change to lemming cycles. *Nature*, 456:93–97.
- Kay, J.E. and A. Gettelman, 2009. Cloud influence on and response to seasonal Arctic sea ice loss. *Journal of Geophysical Research-Atmospheres*, 114:D18204.
- Kim, K.T., K.C. Jezek and H.G. Sohn, 2001. Ice shelf advance and retreat rates along the coast of Queen Maud Land, Antarctica. *Journal of Geophysical Research-Oceans*, 106:7097–7106.
- King, J.C., J.W. Pomeroy, D.M. Gray, C. Fierz, P.M.B. Föhn, R.J. Harding, R.E. Jordan, E. Martin and C. Plüss, 2008. Snow-atmosphere energy and mass balance. In: *Armstrong, R.L. and E. Brun (Eds.). Snow and Climate*. pp. 70–124. Cambridge University Press.
- Klaminder, J., K. Yoo, J. Rydberg and R. Giesler, 2008. An explorative study of mercury export from a thawing *palsa mire*. *Journal of Geophysical Research-Biogeosciences*, 113:G04034.
- Klaminder, J., D. Hammarlund, U. Kokfelt, J.E. Vonk and C. Bigler, 2010. Lead contamination of subarctic lakes and its response to reduced atmospheric fallout: Can the recovery process be counteracted by the ongoing climate change? *Environmental Science and Technology*, 44:2335–2340.
- Klungsoyr, J., R. Sætre, L. Føyn and H. Loeng, 1995. Man's impact on the Barents Sea. *Arctic*, 48:279–296.
- Knightes, C.D., E.M. Sunderland, M.C. Barber, J.M. Johnston and R.B. Ambrose, 2009. Application of ecosystem scale fate and bioaccumulation models to predict fish mercury response times to changes in atmospheric deposition. *Environmental Toxicology and Chemistry*, 28:881–893.
- Koenigk, T., U. Mikolajewicz, H. Haak and J. Jungclaus, 2007. Arctic freshwater export in the 20th and 21st centuries. *Journal of Geophysical Research-Biogeosciences*, 112:G04S41.
- Kokelj, S.V., B. Zajdlik and M.S. Thompson, 2009. The impacts of thawing permafrost on the chemistry of lakes across the subarctic boreal-tundra transition, Mackenzie Delta region, Canada. *Permafrost and Periglacial Processes*, 20:185–199.
- Kongoli, C., P. Pellegrino, R.R. Ferraro, N.C. Grody and H. Meng, 2003. A new snowfall detection algorithm over land using measurements from the AMSU. *Geophysical Research Letters*, 30:1756–1759.
- Krenke, A.N., 1982. Mass exchange in glacier systems over the USSR territory. 288 pp. Hydrometeoizdat, Leningrad.
- Kwok, R., G.F. Cunningham, M. Wensnahan, I. Rigor, H.J. Zwally and D. Yi, 2009. Thinning and volume loss of the Arctic Ocean sea ice cover: 2003–2008. *Journal of Geophysical Research-Oceans*, 114:C07005.
- Laidre, K.L., I. Stirling, L.F. Lowry, O. Wiig, M.P. Heide-Jørgensen and S.H. Ferguson, 2008. Quantifying the sensitivity of arctic marine mammals to climate-induced habitat change. *Ecological Applications*, 18:S97–S125.
- Lantz, T.C., S.V. Kokelj, S.E. Gergel and G.H.R. Henryz, 2009. Relative impacts of disturbance and temperature: persistent changes in microenvironment and vegetation in retrogressive thaw slumps. *Global Change Biology*, 15:1664–1675.
- Larsen, K.S., P. Grogan, S. Jonasson and A. Michelsen, 2007. Respiration and microbial dynamics in two subarctic ecosystems during winter and spring thaw: Effects of increased snow depth. *Arctic Antarctic and Alpine Research*, 39:268–276.
- Latifovic, R. and D. Pouliot, 2007. Analysis of climate change impacts on lake ice phenology in Canada using the historical satellite data record. *Remote Sensing of Environment*, 106:492–507.
- Laurion, I., W.F. Vincent, S. MacIntyre, L. Retamal, C. Dupont, P. Francus and R. Pienitz, 2010. Variability in greenhouse gas emissions from permafrost thaw ponds. *Limnology and Oceanography*, 55:115–133.
- Lawrence, D.M., A.G. Slater, R.A. Tomas, M.M. Holland and C. Deser, 2008. Accelerated Arctic land warming and permafrost degradation during rapid sea ice loss. *Geophysical Research Letters*, 35:L11506.
- Lee, H., E.A.G. Schuur and J.G. Vogel, 2009. Soil CO₂ production in upland tundra where permafrost is thawing. *Journal of Geophysical Research – Biogeosciences*, 115:G01009.
- Lei, Y.D. and F. Wania, 2004. Is rain or snow a more efficient scavenger of organic chemicals? *Atmospheric Environment*, 38:3557–3571.
- Lenormand, F., C.R. Duguay and R. Gauthier, 2002. Development of a historical ice database for the study of climate change in Canada. *Hydrological Processes*, 16:3707–3722.
- Lesack, L.F.W. and P. Marsh, 2007. Lengthening plus shortening of river-to-lake connection times in the Mackenzie River Delta respectively via two global change mechanisms along the arctic coast. *Geophysical Research Letters*, 34:L23404.
- Leuliette, E. and L. Miller, 2009. Closing the sea level rise budget with altimetry, Argo and GRACE. *Geophysical Research Letters*, 36:L04608.
- Levitus, S., J.L. Antonov, T.P. Boyer, R.A. Locarnini, H.E. Garcia and A.V. Mishonov, 2009. Global ocean heat content 1955–2008 in light of recently revealed instrumentation. *Geophysical Research Letters*, 36:L07608.
- Li, Y.-F., R.W. Macdonald, J.M. Ma, H. Hung and S. Venkatesh, 2004. Historical alpha-HCH budget in the Arctic Ocean: The Arctic Mass Balance Box Model (AMBBM). *Science of the Total Environment*, 324:115–139.
- Li, W.K.W., F.A. McLaughlin, C. Lovejoy and E.C. Carmack, 2009. Smallest algae thrive as the Arctic Ocean freshens. *Science*, 326:539–539.
- Lindstrom, U., S. Smout, D. Howell and B. Bogstad, 2009. Modelling multi-species interactions in the Barents Sea ecosystem with special emphasis on minke whale and their interactions with cod, herring and capelin. *Deep-Sea Research, II - Topical Studies in Oceanography*, 56:2068–2079.
- Linnansaari, T., K. Alfreðsen, M. Stickler, J.V. Arnekleiv, A. Harby and R.A. Cunjak, 2009. Does ice matter? Site fidelity and movements by Atlantic salmon (*Salmo salar* L.) parr during winter in a substrate enhanced river reach. *River Research and Applications*, 25:773–787.
- Liu, Y.H., J.R. Key and X.J. Wang, 2009. Influence of changes in sea ice

- concentration and cloud cover on recent Arctic surface temperature trends. *Geophysical Research Letters*, 36:L20710.
- Lohmann, R., R. Gioia, K.C. Jones, L. Nizzetto, C. Temme, Z. Xie, D. Schulz-Bull, I. Hand, E. Morgan and L. Jantunen, 2009. Organochlorine pesticides and PAHs in the surface water and atmosphere of the North Atlantic and Arctic Ocean. *Environmental Science and Technology*, 43:5633–5639.
- Loseto, L.L., G.A. Stern, D. Deibel, T.L. Connelly, A. Prokopowicz, D.R.S. Lean, L. Fortier and S.H. Ferguson, 2008. Linking mercury exposure to habitat and feeding behaviour in Beaufort Sea beluga whales. *Journal of Marine Systems*, 74:1012–1024.
- Lovejoy, C., W.F. Vincent, S. Bonilla, S. Roy, M.-J. Martineau, R. Terrado, M. Potvin, R. Massana and C. Pedrós-Alió, 2007. Distribution, phylogeny and growth of cold-adapted picoplankton in Arctic seas. *Journal of Phycology*, 43:78–89.
- Lunt, D.J., N. de Noblet-Ducoudre and S. Charbit, 2004. Effects of a melted Greenland ice sheet on climate, vegetation, and the cryosphere. *Climate Dynamics*, 23:679–694.
- Luoto, M., R.K. Heikkinen and T.R. Carter, 2004. Loss of palaeo mires in Europe and biological consequences. *Environmental Conservation*, 31:30–37.
- Macdonald, R.W. and J.M. Bewers, 1996. Contaminants in the arctic marine environment: Priorities for protection. *ICES Journal of Marine Science*, 53:537–563.
- Macdonald, R.W. and L.L. Loseto, 2010. Are Arctic ocean ecosystems exceptionally vulnerable to global emissions of mercury? A call for emphasized research on methylation and the consequences of climate change. *Environmental Chemistry*, 7:133–138.
- Macdonald, R.W., L.A. Barrie, T.F. Bidleman, M.L. Diamond, D.J. Gregor, R.G. Semkin, W.M.J. Strachan, Y.F. Li, F. Wania, M. Alae, L.B. Alexeeva, S.M. Backus, R. Bailey, J.M. Bewers, C. Gobeil, C.J. Halsall, T. Harner, J.T. Hoff, L.M.M. Jantunen, W.L. Lockhart, D. Mackay, D.C.G. Muir, J. Pudykiewicz, K.J. Reimer, J.N. Smith, G.A. Stern, W.H. Schroeder, R. Wagemann and M.B. Yunker, 2000a. Contaminants in the Canadian Arctic: 5 years of progress in understanding sources, occurrence and pathways. *Science of the Total Environment*, 254:93–234.
- Macdonald, R.W., S.J. Eisenreich, T.F. Bidleman, J. Dachs, J. Pacyna, K. Jones, B. Bailey, D. Swackhamer and D.C.G. Muir, 2000b. Case studies on persistence and long range transport of persistent organic pollutants. In: Klecka, G. and D. Mackay (Eds.). *Evaluation of Persistence and Long-range Transport of Organic Chemicals in the Environment*. pp. 245–314. SETAC Press.
- Macdonald, R.W., D. Mackay and B. Hickie, 2002. A contaminant amplification in the environment. *Environmental Science and Technology*, 36:456A–462A.
- Macdonald, R.W., T. Harner, J. Fyfe, H. Loeng and T. Weingartner, 2003. The Influence of Global Change on Contaminant Pathways to, within and from the Arctic. 65 pp. Arctic Monitoring and Assessment Programme (AMAP). Oslo, Norway.
- Macdonald, R.W., T. Harner and J. Fyfe, 2005. Recent climate change in the Arctic and its impact on contaminant pathways and interpretation of temporal trend data. *Science of the Total Environment*, 342:5–86.
- Mackenzie-Grieve, J.L. and J.R. Post, 2006. Projected impacts of climate warming on production of lake trout (*Salvelinus namaycush*) in southern Yukon lakes. *Canadian Journal of Fisheries and Aquatic Sciences*, 63:788–797.
- MacLeod, M., W.J. Riley and T.E. McKone, 2005. Assessing the influence of climate variability on atmospheric concentrations of polychlorinated biphenyls using a global-scale mass balance model (BETR-global). *Environmental Science and Technology*, 39:6749–6756.
- Madsen, J., M. Tamstorf, M. Klaassen, N. Eide, C. Glahder, F. Rigét, H. Nygaard and F. Cottaar, 2007. Effects of snow cover on the timing and success of reproduction in high-Arctic pink-footed geese *Anser brachyrhynchus*. *Polar Biology*, 30:1363–1372.
- Maggi, V., S. Villa, A. Finizio, B. Delmonte, P. Casati and F. Marino, 2006. Variability of anthropogenic and natural compounds in high altitude-high accumulation alpine glaciers. *Hydrobiologia*, 562:43–56.
- Markus, T. and D.J. Cavalieri, 2000. An enhancement of the NASA Team sea ice algorithm. *IEEE Transactions on Geoscience and Remote Sensing*, 38:1387–1398.
- Martin, J., J.-E. Tremblay, J. Gagnon, G. Tremblay, A. Lapoussière, C. Jose, M. Poulin, M. Gosselin, Y. Gratton and C. Michel, 2010. Prevalence, structure and properties of subsurface chlorophyll maxima in Canadian Arctic waters. *Marine Ecology Progress Series*, 412:69–84.
- Mastepanov, M., C. Sigsgaard, E.J. Dlugokencky, S. Houweling, L. Strom, M.P. Tamstorf and T.R. Christensen, 2008. Large tundra methane burst during onset of freezing. *Nature*, 456:628–631.
- Matrai, P.A., L. Tranvik, C. Leck and J.C. Knulst, 2008. Are high Arctic surface microlayers a potential source of aerosol organic precursors? *Marine Chemistry*, 108:109–122.
- Matulla, C., S. Schmutz, A. Melcher, T. Gerersdorfer and P. Haas, 2007. Assessing the impact of a downscaled climate change simulation on the fish fauna in an Inner-Alpine River. *International Journal of Biometeorology*, 52:127–137.
- McGuire, A.D., L.G. Anderson, T.R. Christensen, S. Dallimore, L.D. Guo, D.J. Hayes, M. Heimann, T.D. Lorenson, R.W. Macdonald and N. Roulet, 2009. Sensitivity of the carbon cycle in the Arctic to climate change. *Ecological Monographs*, 79:523–555.
- McKinney, M.A., E. Peacock and R.J. Letcher, 2009. Sea ice-associated diet change increases the levels of chlorinated and brominated contaminants in polar bears. *Environmental Science and Technology*, 43:4334–4339.
- McKone, T.E., J.I. Daniels and M. Goldman, 1996. Uncertainties in the link between global climate change and predicted health risks from pollution: Hexachlorobenzene (HCB) case study using a fugacity model. *Risk Analysis*, 16:377–393.
- McLaughlin, F., E. Carmack, R. Macdonald, A.J. Weaver and J. Smith, 2002. The Canada Basin, 1989–1995: Upstream events and far-field effects of the Barents Sea. *Journal of Geophysical Research-Oceans*, 107:20.
- McPhee, M.G., A. Proshutinsky, J.H. Morison, M. Steele and M.B. Alkire, 2009. Rapid change in freshwater content of the Arctic Ocean. *Geophysical Research Letters*, 36:L10602.
- Mech, L.D., 2004. Is climate change affecting wolf populations in the High Arctic? *Climatic Change*, 67:87–93.
- Meehl, G.A., T.F. Stocker, W.D. Collins, P. Friedlingstein, A.T. Gaye, J.M. Gregory, A. Kitoh, R. Knutti, J.M. Murphy, A. Noda, S.C.B. Raper, I.G. Watterson, A.J. Weaver and Z.-C. Zhao, 2007. Global Climate Projections. In: *Climate Change 2007: The Physical Science Basis. Contribution of Working Group I to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change* [Solomon, S., D. Qin, M. Manning, Z. Chen, M. Marquis, K.B. Averyt, M. Tignor and H.L. Miller (eds.)]. Cambridge University Press.
- Meier, M.F., M.B. Dyurgerov, U.K. Rick, S. O’Neel, W.T. Pfeffer, R.S. Anderson, S.P. Anderson and A.F. Glazovsky, 2007. Glaciers dominate eustatic sea-level rise in the 21st century. *Science*, 317:1064–1067.
- Melles, M., J. Brigham-Grette, O.Y. Glushkova, P.S. Minyuk, N.R. Nowaczyk and H.W. Hubberten, 2007. Sedimentary geochemistry of core PG1351 from Lake El’gygytyn - a sensitive record of climate variability in the East Siberian Arctic during the past three glacial-interglacial cycles. *Journal of Paleolimnology*, 37:89–104.
- Meyer, T. and F. Wania, 2008. Organic contaminant amplification during snowmelt. *Water Research*, 42:1847–1865.
- Meyer, T., Y.D. Lei, I. Muradi and F. Wania, 2009a. Organic contaminant release from melting snow. 1. Influence of chemical partitioning. *Environmental Science and Technology*, 43:657–662.
- Meyer, T., Y.D. Lei, I. Muradi and F. Wania, 2009b. Organic contaminant release from melting snow. 2. Influence of snow pack and melt characteristics. *Environmental Science and Technology*, 43:663–668.
- Michelutti, N., B.E. Keatley, S. Brimble, J.M. Blais, H.J. Liu, M.S.V. Douglas, M.L. Mallory, R.W. Macdonald and J.P. Smol, 2009. Seabird-driven shifts in Arctic pond ecosystems. *Proceedings of the Royal Society B-Biological Sciences*, 276:591–596.
- Miller, F.L. and S.J. Barry, 2009. Long-term control of Peary caribou numbers by unpredictable, exceptionally severe snow or ice conditions in a non-equilibrium grazing system. *Arctic*, 62:175–189.
- Milne, G.A., W.R. Gehrels, C.W. Hughes and M.E. Tamisiea, 2009. Identifying the causes of sea-level change. *Nature Geoscience*, 2:471–478.
- Milner, A.M., A.L. Robertson, K.A. Monaghan, A.J. Veal and E.A. Flory, 2008. Colonization and development of an Alaskan stream community over 28 years. *Frontiers in Ecology and the Environment*, 6:413–419.
- Moore, S.E., 2008. Marine mammals as ecosystem sentinels. *Journal of Mammalogy*, 89:534–540.
- Moore, S.E. and H.P. Huntington, 2008. Arctic marine mammals and climate change: Impacts and resilience. *Ecological Applications*, 18:S157–S165.
- Moore, S.E., J.C. George, G. Sheffield, J. Bacon and C.J. Ashjian, 2010.

- Bowhead whale distribution and feeding near Barrow, Alaska, in late summer 2005–06. *Arctic*, 63:195–205.
- Murton, J.B., M.D. Bateman, S.R. Dallimore, J.T. Teller and Z.R. Yang, 2010. Identification of Younger Dryas outburst flood path from Lake Agassiz to the Arctic Ocean. *Nature*, 464:740–743.
- Myers-Smith, I.H., J.W. Harden, M. Wilmking, C.C. Fuller, A.D. McGuire and F.S. Chapin, III, 2008. Wetland succession in a permafrost collapse: interactions between fire and thermokarst. *Biogeosciences*, 5:1273–1286.
- National Research Council, 2011. *Climate Stabilization Targets: Emissions, Concentrations, and Impacts over Decades to Millennia*. Committee on Stabilization Targets for Atmospheric Greenhouse Gas Concentrations. 298 pp. Board on Atmospheric Sciences and Climate, Division on Earth and Life Studies. Washington D.C.
- Nicholls, R.J. and A. Cazenave, 2010. Sea-level rise and its impact on coastal zones. *Science*, 328:1517–1520.
- Nilsen, F., F. Cottier, R. Skogseth and S. Mattsson, 2008. Fjord-shelf exchanges controlled by ice and brine production: The interannual variation of Atlantic Water in Isfjorden, Svalbard. *Continental Shelf Research*, 28:1838–1853.
- Nobrega, S. and P. Grogan, 2007. Deeper snow enhances winter respiration from both plant-associated and bulk soil carbon pools in birch hummock tundra. *Ecosystems*, 10:419–431.
- Occhipinti-Ambrogi, A., 2007. Global change and marine communities: Alien species and climate change. *Marine Pollution Bulletin*, 55:342–352.
- Ogi, M., K. Yamazaki and J.M. Wallace, 2010. Influence of winter and summer surface wind anomalies on summer Arctic sea ice extent. *Geophysical Research Letters*, 37:L07701.
- Opdal, A.F., 2010. Fisheries change spawning ground distribution of northeast Arctic cod. *Biology Letters*, 6:261–264.
- Outridge, P.M., G.A. Stern, P.B. Hamilton, J.B. Percival, R. McNeely and W.L. Lockhart, 2005. Trace metal profiles in the varved sediment of an Arctic lake. *Geochimica et Cosmochimica Acta*, 69:4881–4894.
- Outridge, P.M., H. Sanei, G.A. Stern, P.B. Hamilton and F. Goodarzi, 2007. Evidence for control of mercury accumulation rates in Canadian High Arctic lake sediments by variations of aquatic primary productivity. *Environmental Science and Technology*, 41:5259–5265.
- Outridge, P.M., R.W. Macdonald, F. Wang, G.A. Stern and A.P. Dastoor, 2008. A mass balance inventory of mercury in the Arctic Ocean. *Environmental Chemistry*, 5:89–111.
- Overland, J.E. and M.Y. Wang, 2010. Large-scale atmospheric circulation changes are associated with the recent loss of Arctic sea ice. *Tellus Series A-Dynamic Meteorology and Oceanography*, 62:1–9.
- Overpeck, J.T., M. Sturmf, J.A. Francis, D.K. Perovich, M.C. Serreze, R. Benner, E.C. Carmack, F.S. Chapin III, S.C. Gerlach, L.C. Hamilton, L.D. Hinzman, M. Holland, H.P. Huntington, J.R. Key, A.H. Lloyd, G.M. Macdonald, J. McFadden, D. Noone, T.D. Prowse, P. Schlosser and C. Vörösmarty, 2005. Arctic system on trajectory to new, seasonally ice-free state. *Eos Transactions, American Geophysical Union*, 86:309–313.
- Overpeck, J.T., B.L. Otto-Bliesner, G.H. Miller, D.R. Muhs, R.B. Alley and J.T. Kiehl, 2006. Paleoclimatic evidence for future ice-sheet instability and rapid sea-level rise. *Science*, 311:1747–1750.
- Pavlov, V., 2007. Modeling of long-range transport of contaminants from potential sources in the Arctic Ocean by water and sea ice. In: Orbaek, J.B., T. Tombre, R. Kallenborn, E. Hegseth, S. Falk-Petersen and A.H. Hoel (Eds.). *Arctic Alpine Ecosystems and People in a Changing Environment*. pp. 329–350. Springer Verlag.
- Pavlov, V.K. and O.A. Pavlova, 2008. Sea ice drifts in the Arctic Ocean. Seasonal variability and long-term changes. In: Tewles, K.B. (Ed.). *Pacific and Arctic Oceans: New Oceanographic Research*. pp. 157–186. NOVA Science Publishers.
- Payette, S., A. Delwaide, M. Caccianiga and M. Beauchemin, 2004. Accelerated thawing of subarctic peatland permafrost over the last 50 years. *Geophysical Research Letters*, 31:L18208.
- Peings, Y. and H. Douville, 2010. Influence of the Eurasian snow cover on the Indian summer monsoon variability in observed climatologies and CMIP3 simulations. *Climate Dynamics*, 34:643–660.
- Peltier, W.R., 2007. Rapid climate change and Arctic Ocean freshening. *Geology*, 35:1147–1148.
- Perovich, D.K., J.A. Richter-Menge, K.F. Jones and B. Light, 2008. Sunlight, water, and ice: Extreme Arctic sea ice melt during the summer of 2007. *Geophysical Research Letters*, 35:L11501.
- Peterson, B.J., J. McClelland, R. Curry, R.M. Holmes, J.E. Walsh and K. Aagaard, 2006. Trajectory shifts in the Arctic and subarctic freshwater cycle. *Science*, 313:1061–1066.
- Pfeffer, W.T., J.T. Harper and S. O’Neel, 2008. Kinematic constraints on glacier contributions to 21st-century sea-level rise. *Science*, 321:1340–1343.
- Pomeroy, J.W., D.S. Bewley, R.L.H. Essery, N.R. Hedstrom, T. Link, R.J. Granger, J.E. Sicart, C.R. Ellis and J.R. Janowicz, 2006. Shrub tundra snowmelt. *Hydrological Processes*, 20:923–941.
- Post, E., M.C. Forchhammer, M.S. Bret-Harte, T.V. Callaghan, T.R. Christensen, B. Elberling, A.D. Fox, O. Gilg, D.S. Hik, T.T. Høye, R.A. Ims, E. Jeppesen, D.R. Klein, J. Madsen, A.D. McGuire, S. Rysgaard, D.E. Schindler, I. Stirling, M.P. Tamstorf, N.J.C. Tyler, R. van der Wal, J. Welker, P.A. Wookey, N.M. Schmidt and P. Aastrup, 2009. Ecological dynamics across the Arctic associated with recent climate change. *Science*, 325:1355–1358.
- Power, M., J.D. Reist and J.B. Dempson, 2008. Fish in high-latitude lakes. In: Vincent, W.F. and J. Laybourn-Parry (Eds.). *Polar Lakes and Rivers - Limnology of Arctic and Antarctic Aquatic Ecosystems*. pp. 249–269. Oxford University Press.
- Prowse, T.D., 2009. Introduction: hydrologic effects of a shrinking cryosphere. *Hydrological Processes*, 23:1–6.
- Prowse, T.D. and J.M. Culp, 2008. Ice breakup: a neglected factor in river ecology. In: Beltaos, S. (Ed.). *River Ice Breakup*. pp. 349–375. Water Resources Publications.
- Prowse, T.D. and P.O. Flegg, 2000. The magnitude of river flow to the Arctic Ocean: dependence on contributing area. *Hydrological Processes*, 14:3185–3188.
- Prowse, T.D., F.J. Wrona, J.D. Reist, J.J. Gibson, J.E. Hobbie, L.M.J. Lévesque and W.F. Vincent, 2006. Climate change effects on hydroecology of Arctic freshwater ecosystems. *Ambio*, 35:347–358.
- Prowse, T.D., C. Furgal, H. Melling and S.L. Smith, 2009a. Implications of climate change for northern Canada: The physical environment. *Ambio*, 38:266–271.
- Prowse, T.D., C. Furgal, F.J. Wrona and J.D. Reist, 2009b. Implications of climate change for northern Canada: freshwater, marine, and terrestrial ecosystems. *Ambio*, 38:282–289.
- Rachold, V., F.E. Are, D.E. Atkinson, G. Cherkashov and S.M. Solomon, 2005. Arctic coastal dynamics (ACD): an introduction. *Geo-Marine Letters*, 25:63–68.
- Radić, V. and R. Hock, 2010. Regional and global volumes of glaciers derived from statistical upscaling of glacier inventory data. *Journal of Geophysical Research*, 115:F01010.
- Radić, V. and R. Hock, 2011. Regionally differentiated contribution of mountain glaciers and ice caps to future sea-level rise. *Nature Geoscience*, 4:91–94.
- Rahmstorf, S., 2007. A semi-empirical approach to projecting future sea-level rise. *Science*, 315:368–370.
- Randall, D.A., R.A. Wood, S. Bony, R. Colman, T. Fichefet, J. Fyfe, V. Kattsov, A. Pitman, J. Shukla, J. Srinivasan, R.J. Stouffer, A. Sumi and K.E. Taylor, 2007. Climate models and their evaluation. In: Solomon, S., D. Quinn, M. Manning, Z. Chen, M. Marquis, K.B. Averyt, M. Tignor and H.L. Miller (Eds.). *Climate Change 2007: the Physical Science Basis. Contribution of Working Group I to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change*. pp. 589–662. Cambridge University Press.
- Regehr, E.V., N.J. Lunn, S.C. Amstrup and L. Stirling, 2007. Effects of earlier sea ice breakup on survival and population size of polar bears in western Hudson Bay. *Journal of Wildlife Management*, 71:2673–2683.
- Regehr, E.V., C.M. Hunter, H. Caswell, S.C. Amstrup and I. Stirling, 2010. Survival and breeding of polar bears in the southern Beaufort Sea in relation to sea ice. *Journal of Animal Ecology*, 79:117–127.
- Rennermalm, A.K., L.C. Smith, J.C. Stroeve and V.W. Chu, 2009. Does sea ice influence Greenland ice sheet surface-melt? *Environmental Research Letters*, 4:024011.
- Rennert, K.J., G. Roe, J. Putkonen and C.M. Bitz, 2009. Soil thermal and ecological impacts of rain on snow events in the circumpolar Arctic. *Journal of Climate*, 22:2302–2315.
- Repo, M.E., S. Susiluoto, S.E. Lind, S. Jokinen, V. Elsakov, C. Biasi, T. Virtanen and P.J. Martikainen, 2009. Large N₂O emissions found from cryoturbated peat soil in tundra. *Nature Geoscience*, 2:189–192.
- Retamal, L., S. Bonilla and W.F. Vincent, 2008. Optical gradients and phytoplankton production in the Mackenzie River and the coastal

- Beaufort Sea. *Polar Biology*, 31:363–379.
- Rignot, E., 2006. Changes in ice dynamics and mass balance of the Antarctic ice sheet. *Philosophical Transactions of the Royal Society A-Mathematical Physical and Engineering Sciences*, 364:1637–1655.
- Rignot, E. and R.H. Thomas, 2002. Mass balance of polar ice sheets. *Science*, 297:1502–1506.
- Riordan, B., D. Verbyla and A.D. McGuire, 2006. Shrinking ponds in subarctic Alaska based on 1950–2002 remotely sensed images. *Journal of Geophysical Research*, 111:G04002.
- Rohling, E.J., K. Grant, C. Hemleben, M. Siddall, B.A.A. Hoogakker, M. Bolshaw and M. Kucera, 2008. High rates of sea-level rise during the last interglacial period. *Nature Geoscience*, 1:38–42.
- Romanovsky, V.E., D.S. Drozdov, N.G. Oberman, G.V. Malkova, A.L. Kholodov, S.S. Marchenko, N.G. Moskalenko, D.O. Sergeev, N.G. Ukraintseva, A.A. Abramov, D.A. Gilichinsky and A.A. Vasiliev, 2010. Thermal state of permafrost in Russia. *Permafrost and Periglacial Processes*, 21:136–155.
- Rouse, W.R., M.S.V. Douglas, R.E. Hecky, A.E. Hershey, G.W. Kling, L. Lesack, P. Marsh, M. McDonald, B.J. Nicholson, N.T. Roulet and J.P. Smol, 1997. Effects of climate change on the freshwaters of arctic and subarctic North America. *Hydrological Processes*, 11:873–902.
- Rydberg, J., J. Klaminder, P. Rosen and R. Bindler, 2010. Climate driven release of carbon and mercury from permafrost mires increases mercury loading to sub-arctic lakes. *Science of the Total Environment*, 408:4778–4783.
- Rysgaard, S. and T.G. Nielsen, 2006. Carbon cycling in a high-arctic marine ecosystem - Young Sound, NE Greenland. *Progress in Oceanography*, 71:426–445.
- Rysgaard, S., J. Bendtsen, L.T. Pedersen, H. Ramløv and R.N. Glud, 2009. Increased CO₂ uptake due to sea ice growth and decay in the Nordic Seas. *Journal of Geophysical Research-Oceans*, 114:C09011.
- Schiedek, D., B. Sundelin, J.W. Readman and R.W. Macdonald, 2007. Interactions between climate change and contaminants. *Marine Pollution Bulletin*, 54:1845–1856.
- Schindler, D.W. and J.P. Smol, 2006. Cumulative effects of climate warming and other human activities on freshwaters of Arctic and subarctic North America. *Ambio*, 35:160–168.
- Schuur, E.A.G., J.G. Vogel, K.G. Crummer, H. Lee, J.O. Sickman and T.E. Osterkamp, 2009. The impact of permafrost thaw on old carbon release and net carbon exchange from tundra. *Nature*, 459:556–559.
- Schweiger, A.J., R.W. Lindsay, S. Vavrus and J.A. Francis, 2008. Relationships between Arctic sea ice and clouds during autumn. *Journal of Climate*, 21:4799–4810.
- Scinocca, J.F., M.C. Reader, D.A. Plummer, M. Sigmond, P.J. Kushner, T.G. Shepherd and A.R. Ravishankara, 2009. Impact of sudden Arctic sea-ice loss on stratospheric polar ozone recovery. *Geophysical Research Letters*, 36:L24701.
- Screen, J.A. and I. Simmonds, 2010. The central role of diminishing sea ice in recent Arctic temperature amplification. *Nature*, 464:1334–1337.
- Semkin, R.G., G. Mierle and R.J. Neureuther, 2005. Hydrochemistry and mercury cycling in a High Arctic watershed. *Science of the Total Environment*, 342:199–221.
- Serreze, M.C., A.P. Barrett, A.G. Slater, R.A. Woodgate, K. Aagaard, R.B. Lammers, M. Steele, R. Moritz, M. Meredith and C.M. Lee, 2006. The large-scale freshwater cycle of the Arctic. *Journal of Geophysical Research-Oceans*, 111:C11010.
- Serreze, M.C., M.M. Holland and J. Stroeve, 2007. Perspectives on the Arctic's shrinking sea-ice cover. *Science*, 315:1533–1536.
- Shakhova, N., I. Semiletov, A. Salyuk, N. Belcheva, D. Kosmach and V.I. Sergienko, 2008a. On the role of the East-Siberian Shelf in the modern methane cycle and global change. *Herald of the East-Siberian Branch of Russian Academy of Sciences*. No. 4.
- Shakhova, N.E., I.P. Semiletov, V.I. Sergienko, A.N. Salyuk, N.N. Belcheva and D.A. Kosmach, 2008b. On the role of the East Siberian Arctic Shelf in the modern marine methane cycle. In: *Change of Natural Environment and Climate: Natural and possible consequent human-induced catastrophes*. pp. 164–176. Russian Academy of Science, Moscow. [In Russian]
- Shakhova, N., I. Semiletov, A. Salyuk, V. Yusupov, D. Kosmach and O. Gustafsson, 2010. Extensive methane venting to the atmosphere from sediments of the East Siberian Arctic Shelf. *Science*, 327:1246–1250.
- Sharma, S., D.A. Jackson, C.K. Minns and B.J. Shuter, 2007. Will northern fish populations be in hot water because of climate change? *Global Change Biology*, 13:2052–2064.
- Sharma, S., S. Couturier and S.D. Cote, 2009. Impacts of climate change on the seasonal distribution of migratory caribou. *Global Change Biology*, 15:2549–2562.
- Shiklomanov, A.I. and R.B. Lammers, 2009. Record Russian river discharge in 2007 and the limits of analysis. *Environmental Research Letters*, 4:045015.
- Shimada, K., T. Kamoshida, M. Itoh, S. Nishino, E. Carmack, F. McLaughlin, S. Zimmermann and A. Proshutinsky, 2006. Pacific Ocean inflow: Influence on catastrophic reduction of sea ice cover in the Arctic Ocean. *Geophysical Research Letters*, 33:L08605.
- Shindell, D., 2007. Estimating the potential for twenty-first century sudden climate change. *Philosophical Transactions of the Royal Society A - Mathematical Physical and Engineering Sciences*, 365:2675–2694.
- Shindell, D.T., R.L. Miller, G.A. Schmidt and L. Pandolfo, 1999. Simulation of recent northern winter climate trends by greenhouse-gas forcing. *Nature*, 399:452–455.
- Shindell, D., G. Faluvegi, A. Lacis, J. Hansen, R. Ruedy and E. Aguilar, 2006. Role of tropospheric ozone increases in 20th century climate change. *Journal of Geophysical Research*, 111:D08302.
- Sitch, S., A.D. McGuire, J. Kimball, N. Gedney, J. Gamon, R. Emgstrom, A. Wolf, Q. Zhuang and J. Clein, 2007. Assessing the circumpolar carbon balance of arctic tundra with remote sensing and process-based modeling approaches. *Ecological Applications*, 17:213–234.
- Slubowska-Wodengen, M., T.L. Rasmussen, N. Koc, D. Klitgaard-Kristensen, F. Nilsen and A. Solheim, 2007. Advection of Atlantic Water to the western and northern Svalbard shelf since 17,500 cal yr BP. *Quaternary Science Reviews*, 26:463–478.
- Smith, L.C., Y. Sheng, G.M. MacDonald and L.D. Hinzman, 2005. Disappearing Arctic lakes. *Science*, 308:1429–1429.
- Smol, J.P. and M.S.V. Douglas, 2007a. Crossing the final ecological threshold in high Arctic ponds. *Proceedings of the National Academy of Sciences of the United States of America*, 104:12395–12397.
- Smol, J.P. and M.S.V. Douglas, 2007b. From controversy to consensus: making the case for recent climatic change in the Arctic using lake sediments. *Frontiers in Ecology and the Environment*, 5:466–474.
- Sobek, A., M. Reigstad and O. Gustafsson, 2006. Partitioning of polychlorinated biphenyls between arctic seawater and size-fractionated zooplankton. *Environmental Toxicology and Chemistry*, 25:1720–1728.
- Soreide, J.E., S. Falk-Petersen, E.N. Hegseth, H. Hop, M.L. Carroll, K.A. Hobson and K. Blachowiak-Samolyk, 2008. Seasonal feeding strategies of *Calanus* in the high-Arctic Svalbard region. *Deep-Sea Research Part II-Topical Studies in Oceanography*, 55:2225–2244.
- Sorvari, S., A. Korhola and R. Thompson, 2002. Lake diatom response to recent Arctic warming in Finnish Lapland. *Global Change Biology*, 8:171–181.
- Stanley, J.B., P.F. Schuster, M.M. Reddy, D.A. Roth, H.E. Taylor and G.R. Aiken, 2002. Mercury on the move during snowmelt in Vermont. *Eos, Transactions, American Geophysical Union*, 83:45, 47–48.
- Steffen, A., T. Douglas, M. Amyot, P. Ariya, K. Aspmo, T. Berg, J. Bottenheim, S. Brooks, F. Cobbe, A. Dastoor, A. Dommergue, R. Ebinghaus, C. Ferrari, K. Gardfeldt, M.E. Goodsite, D. Lean, A.J. Poulain, C. Scherz, H. Skov, J. Sommar and C. Temme, 2008. A synthesis of atmospheric mercury depletion event chemistry in the atmosphere and snow. *Atmospheric Chemistry and Physics*, 8:1445–1482.
- Stemmler, I. and G. Lammel, 2009. Cycling of DDT in the global environment 1950–2002: World ocean returns the pollutant. *Geophysical Research Letters*, 36:L24602.
- Stern, G.A., E. Braekelvel, P.A. Helm, T.F. Bidleman, P.M. Outridge, W.L. Lockhart, R. McNeeley, B. Rosenberg, M.G. Ikononou, P. Hamilton, G.T. Tomy and P. Wilkinson, 2005. Modern and historical fluxes of halogenated organic contaminants to a lake in the Canadian arctic, as determined from annually laminated sediment cores. *Science of the Total Environment*, 342:223–243.
- Stocker, T.F. and C.C. Raible, 2005. Climate change - Water cycle shifts gear. *Nature*, 434:830–833.
- Stroeve, J., M.M. Holland, W. Meier, T. Scambos and M. Serreze, 2007. Arctic sea ice decline: Faster than forecast. *Geophysical Research Letters*, 34:L09501.
- Stroeve, J., M. Serreze, S. Drobot, S. Gearheard, M. Holland, J. Maslanik, W. Meier and T. Scambos, 2008. Arctic sea ice extent plummets in 2007.

- Eos, Transactions, American Geophysical Union, 89:13–14.
- Ström, L. and T.R. Christensen, 2007. Below ground carbon turnover and greenhouse gas exchanges in a sub-arctic wetland. *Soil Biology and Biochemistry*, 39:1689–1698.
- Sturm, M., C. Racine and K. Tape, 2001. Climate change - Increasing shrub abundance in the Arctic. *Nature*, 411:546–547.
- Sunderland, E.M., D.P. Krabbenhoft, J.W. Moreau, S.A. Strode and W.M. Landing, 2009. Mercury sources, distribution, and bioavailability in the North Pacific Ocean: Insights from data and models. *Global Biogeochemical Cycles*, 23:GB2010.
- Sundfjord, A., I. Fer, Y. Kasajima and H. Svendsen, 2007. Observations of turbulent mixing and hydrography in the marginal ice zone of the Barents Sea. *Journal of Geophysical Research-Oceans*, 112:C05008.
- Taillandier, A.S., F. Domine, W.R. Simpson, M. Sturm, T.A. Douglas and K. Severin, 2006. Evolution of the snow area index of the subarctic snowpack in central Alaska over a whole season. Consequences for the air to snow transfer of pollutants. *Environmental Science and Technology*, 40:7521–7527.
- Tape, K., M. Sturm and C. Racine, 2006. The evidence for shrub expansion in Northern Alaska and the Pan-Arctic. *Global Change Biology*, 12:686–702.
- Tarnocai, C., J. Canadell, E.A.G. Schuur, P. Kuhry, G. Mazhitova and S. Zimov, 2009. Soil organic carbon stocks in the northern circumpolar permafrost region. *Global Biogeochemical Cycles*, 23:GB2023.
- Tarroux, A., D. Berteaux and J. Bêty, 2010. Northern nomads: ability for extensive movements in adult arctic foxes. *Polar Biology*, 33:1021–1026.
- Thibault, S. and S. Payette, 2009. Recent permafrost degradation in bogs of the James Bay area, Northern Quebec, Canada. *Permafrost and Periglacial Processes*, 20:383–389.
- Thiemann, G.W., S.J. Iverson and I. Stirling, 2008. Polar bear diets and Arctic marine food webs: Insights from fatty acid analysis. *Ecological Monographs*, 78:591–613.
- Thies, H., U. Nickus, V. Mair, R. Tessadri, D. Tait, B. Thaler and R. Psenner, 2007. Unexpected response of high alpine lake waters to climate warming. *Environmental Science and Technology*, 41:7424–7429.
- Turunen, M., P. Soppela, H. Kinnunen, M.L. Sutinen and F. Martz, 2009. Does climate change influence the availability and quality of reindeer forage plants? *Polar Biology*, 32:813–832.
- Ueda, H., M. Shinoda and H. Kamahori, 2003. Spring northward retreat of Eurasian snow cover relevant to seasonal and interannual variations of atmospheric circulation. *International Journal of Climatology*, 23:615–629.
- Usher, P.J., 2002. Inuvialuit use of the Beaufort Sea and its resources, 1960–2000. *Arctic*, 55:18–28.
- Vallières, C., L. Retamal, P. Ramlal, C.L. Osburn and W.F. Vincent, 2008. Bacterial production and microbial food web structure in a large arctic river and the coastal Arctic Ocean. *Journal of Marine Systems*, 74:756–773.
- van den Brink, N., M. Riddle, M. van den Heuvel-Greve, I. Allison, I. Snape and J.A. van Franeker, 2009. Correspondence on Geisz et al. *Melting Glaciers: A Probable Source of DDT to the Antarctic Marine Ecosystem*. *Environmental Science and Technology*, 43:3976–3977.
- Van Oostdam, J., A. Gilman, E. Dewailly, P. Usher, B. Wheatley, H. Kuhnlein, S. Neve, J. Walker, B. Tracy, M. Feeley, V. Jerome and B. Kwavnick, 1999. Human health implications of environmental contaminants in Arctic Canada: a review. *Science of the Total Environment*, 230:1–82.
- Varin, T., C. Lovejoy, A.D. Jungblut, W.F. Vincent and J. Corbeil, 2010. Metagenomic profiling of Arctic microbial mat communities as nutrient scavenging and recycling systems. *Limnology and Oceanography*, 55:1901–1911.
- Veillette, J., D.R. Mueller, D. Antoniadis and W.F. Vincent, 2008. Arctic epishelf lakes as sentinel ecosystems: Past, present and future. *Journal of Geophysical Research-Biogeosciences*, 113:G04014.
- Veillette, J., D.C.G. Muir, T.N. Loewen, J.A. Babaluk, J.D. Reist and W.F. Vincent, 2009. Perfluorinated acid contaminants in high Arctic meromictic lakes: Transport pathways and implications of climate change. Paper presented at Ecological and evolutionary implications of climate change. A national symposium. Centre for Northern Studies, Lakehead University, Canada, March 6–7, 2009.
- Vermeij, G.J. and P.D. Roopnarine, 2008. The coming Arctic invasion. *Science*, 321:780–781.
- Verreault, J., G.W. Gabrielsen and J.O. Bustnes, 2010. The Svalbard glaucous gull as bioindicator species in the European Arctic: Insight from 35 years of contaminants research. *Reviews of Environmental Contamination and Toxicology*, 205:77–116.
- Vincent, W.F., 2000. Cyanobacterial dominance in the polar regions. In: Whitton, B. and M. Potts (Eds.). *Ecology of the Cyanobacteria: their Diversity in Space and Time*. pp. 321–340. Kluwer Academic Press.
- Vincent, W.F., 2010. Microbial ecosystem responses to rapid climate change in the Arctic. *The ISME Journal*, 4:1087–1090.
- Vincent, W.F. and C. Belzile, 2003. Biological UV exposure in the polar oceans: Arctic-Antarctic comparisons. In: Huiskes, A.H.L., W.W.C. Gieskes, J. Rozema, R.M.L. Schorno, S.M. van der Vies and W.J. Wolff (Eds.). *Antarctic Biology in a Global Context*. pp. 176–181. Backhuys Publishers.
- Vincent, W.F., L.G. Whyte, C. Lovejoy, C.W. Greer, I. Laurion, C.A. Suttle, J. Corbeil and D.R. Mueller, 2009. Arctic microbial ecosystems and impacts of extreme warming during the International Polar Year. *Polar Science*, 3:171–180.
- Vogel, J.G., E.A.G. Schuur, C. Trucco and H. Lee, 2009. The carbon cycling response of tussock tundra to permafrost thaw and thermokarst development. *Journal of Geophysical Research – Biogeosciences*, 114:G04018.
- Voulgarakis, A., X. Yang and J.A. Pyle, 2009. How different would tropospheric oxidation be over an ice-free Arctic? *Geophysical Research Letters*, 36:L23807.
- Wallace, J.M. and D.W.J. Thompson, 2002. Annular modes and climate prediction. *Physics Today*, 55:28–33.
- Walter, K.M., S.A. Zimov, J.P. Chanton, D. Verbyla and F.S. Chapin, III, 2006. Methane bubbling from Siberian thaw lakes as a positive feedback to climate warming. *Nature*, 443:71–75.
- Walter, K.M., M. Edwards, S.A. Zimov, G. Grosse and F.S. Chapin III, 2007a. Thermokarst lakes as a source of atmospheric CH₄ during the last deglaciation. *Science*, 318:633–636.
- Walter, K.M., L.C. Smith and F.S. Chapin III, 2007b. Methane bubbling from northern lakes: present and future contributions to the methane budget. *Philosophical Transactions of the Royal Society, A*, 365:1657–1676.
- Wang, X.J. and J.R. Key, 2003. Recent trends in arctic surface, cloud, and radiation properties from space. *Science*, 299:1725–1728.
- Wang, X.P., P. Gong, Q.G. Zhang and T.D. Yao, 2010. Impact of climate fluctuations on deposition of DDT and hexachlorocyclohexane in mountain glaciers: Evidence from ice core records. *Environmental Pollution*, 158:375–380.
- Wania, F., 1998. The significance of long-range transport of persistent organic pollutants by migratory animals. *WECC Report 3/98*: 17 pp. Toronto, Ontario, Canada.
- Wania, F. and C. Halsall, 2003. Air/snow exchange of persistent organic pollutants, in *Canadian Arctic Contaminants Assessment Report II*. Sources, occurrence, trends and pathways in the physical environment. pp. 185–190, Indian and Northern Affairs Canada.
- Wania, F., R. Semkin, J.T. Hoff and D. Mackay, 1999. Modelling the fate of non-polar organic chemicals during the melting of an Arctic snowpack. *Hydrological Processes*, 13:2245–2256.
- Weber, J., C.J. Halsall, D.C.G. Muir, C. Teixeira, D.A. Burniston, W.M.J. Strachan, H. Hung, N. Mackay, D. Arnold and H. Kylin, 2006. Endosulfan and gamma-HCH in the Arctic: An assessment of surface seawater concentrations and air-sea exchange. *Environmental Science and Technology*, 40:7570–7576.
- Westbrook, G.K., K.E. Thatcher, E.J. Rohling, A.M. Piotrowski, H. Palike, A.H. Osborne, E.G. Nisbet, T.A. Minshall, M. Lanoiselle, R.H. James, V. Huhnerbach, D. Green, R.E. Fisher, A.J. Crocker, A. Chabert, C. Bolton, A. Beszczynska-Moller, C. Berndt and A. Aquilina, 2009. Escape of methane gas from the seabed along the West Spitsbergen continental margin. *Geophysical Research Letters*, 36:L15608.
- WGMS, 1989, World glacier inventory - Status 1988. Haeberli, W., H. Bösch, K. Scherler, G. Østrem and C.C. Wallén (Eds.), *IAHS (ICS1) / UNEP / UNESCO, World Glacier Monitoring Service*, Zurich, Switzerland. 458 pp.
- Willis, J.K., D.T. Chambers and R.S. Nerem, 2008. Assessing the globally averaged sea level budget on seasonal to interannual time scales. *Journal of Geophysical Research*, 113:C06015.
- Wilmking, M., R. D'Arrigo, G.C. Jacoby and G.P. Juday, 2005. Increased temperature sensitivity and divergent growth trends in circumpolar boreal forests. *Geophysical Research Letters*, 32:L15715.

- Wingham, D.J., M.L. Siegert, A. Shepherd and A.S. Muir, 2006. Rapid discharge connects Antarctic subglacial lakes. *Nature*, 440:1033-1036.
- Winton, M., 2006. Amplified Arctic climate change: What does surface albedo feedback have to do with it? *Geophysical Research Letters*, 33:L03701.
- Winton, M., 2008. Sea Ice - albedo feedback and nonlinear Arctic climate change in Arctic sea ice decline: observations, projections, mechanisms and implications. *Geophysical Monograph Series*, American Geophysical Union. 180:111-131.
- WMO, 1997. Global Climate Observing System: GCOS/GTOS Plan for terrestrial climate-related observations, Version 2.0, GCOS-32. World Meteorological Organization. Geneva. 130 pp.
- Woo, M.K. and K.L. Young, 1998. Characteristics of patchy wetlands in a polar desert environment, Arctic Canada. Paper presented at Seventh International Conference on Permafrost, pp. 1141-1146.
- Woo, M.K. and K.L. Young, 2003. Hydrogeomorphology of patchy wetlands in the High Arctic, polar desert environment. *Wetlands*, 23:291-309.
- Woodgate, R.A. and K. Aagaard, 2005. Revising the Bering Strait freshwater flux into the Arctic Ocean. *Geophysical Research Letters*, 32:L02602.
- Wrona, F.J., T.D. Prowse, J.D. Reist, R. Beamish, J.J. Gibson, J. Hobbie, E. Jeppesen, J. King, G. Koeck, A. Korhola, L. Levesque, R. Macdonald, M. Power, V. Skvortsov and W.F. Vincent, 2005. Freshwater ecosystems and fisheries. In: *Arctic Climate Impact Assessment*. pp. 353-452. Cambridge University Press.
- Yamamoto-Kawai, M., F.A. McLaughlin, E.C. Carmack, S. Nishino and K. Shimada, 2008. Freshwater budget of the Canada Basin, Arctic Ocean, from salinity, $\delta^{18}\text{O}$, and nutrients. *Journal of Geophysical Research-Oceans*, 113:C01007.
- Yamamoto-Kawai, M., F.A. McLaughlin, E.C. Carmack, S. Nishino, K. Shimada and N. Kurita, 2009. Surface freshening of the Canada Basin, 2003-2007: River runoff versus sea ice meltwater. *Journal of Geophysical Research-Oceans*, 114:C00A05.
- Yang, D.Q., Y.Y. Zhao, R. Armstrong and D. Robinson, 2009. Yukon River streamflow response to seasonal snow cover changes. *Hydrological Processes*, 23:109-121.
- Ye, H.C. and Z.H. Bao, 2001. Lagged teleconnections between snow depth in northern Eurasia, rainfall in Southeast Asia and sea-surface temperatures over the tropical Pacific Ocean. *International Journal of Climatology*, 21:1607-1621.
- Zepp, R., T.V. Callaghan and D.J. Erikson, 1995. Effects of increased solar ultraviolet radiation on biogeochemical cycles. *Ambio*, 24:181-187.
- Zhang, T. and R.L. Armstrong, 2001. Soil freeze/thaw cycles over snow-free land detected by passive microwave remote sensing. *Geophysical Research Letters*, 28:763-766.
- Zhang, T., R.G. Barry and R.L. Armstrong, 2004. Application of satellite remote sensing techniques to frozen ground studies. *Polar Geography*, 28:163-196.
- Zhou, G.Q. and K.C. Jezek, 2002. Satellite photograph mosaics of Greenland from the 1960s era. *International Journal of Remote Sensing*, 23:1143-1159.
- Zwally, H.J. and M.B. Giovinetto, 1995. Accumulation in Antarctica and Greenland derived from passive microwave data: A comparison with contoured compilations. *Annals of Glaciology*, 21:123-130.

12. SWIPA Synthesis: Implications of Findings

LEAD AUTHOR: JAMES D. REIST

CONTRIBUTING AUTHORS: TERRY V. CALLAGHAN, DORTHE DAHL-JENSEN, GRETE K. HOVELSRUD, MARGARETA JOHANSSON, ROLAND KALLENBORN, JEFFREY R. KEY, WALTER N. MEIER, MORTEN SKOVGAARD OLSEN, JAMES OVERLAND, TERRY PROWSE, LARS-OTTO REIERSEN, MARTIN SHARP, WARWICK F. VINCENT, JOHN WALSH

Contents

12.1. Introduction and scope of chapter	2
12.2. Ongoing and projected changes in the cryosphere ...	2
12.2.1. Changes in the cryosphere	2
12.2.2. Feedbacks	3
12.2.3. Effects of cryospheric changes on other aspects of the Arctic environment	5
12.3. Integrated consequences of cryospheric-driven changes on Arctic societies	7
12.3.1. Changes to access in the Arctic environment	7
12.3.2. Humans, biodiversity changes and land-use activities	8
12.3.3. Industrialization and development	9
12.3.4. Hazards	10
12.3.5. Ecosystem and biodiversity losses	11
12.3.6. Shift in lifestyles, culture and socio-economics	11
12.4. Integrated consequences of cryospheric changes for lower latitudes and the global system	12
12.4.1. Climate system changes	12
12.4.2. Global marine effects	12
12.4.3. Trade and economic development	13
12.5. Knowledge gaps and recommendations	13
12.5.1. Gaps in information and knowledge	13
12.5.2. Recommendations	14
12.6. Conclusion	15

12.1. Introduction and scope of chapter

Climate change is causing significant changes in the Arctic cryosphere, and these changes are expected to continue (Chapters 2 and 3). As reported in Chapters 4 to 9, these changes involve the timing and duration of snow and ice cover and seasonally frozen periods. They may also involve the loss or severe degradation of specific elements of the cryosphere. Observed and projected changes in the cryosphere cross the full spectrum of temporal scales (i.e., seasonal to century levels and beyond). The spatial scales involved similarly range from local to pan-Arctic and global. The changes are having, and will continue to have profound impacts on Arctic environments and human activities in the Arctic (Chapters 2, 10 and 11). Within this general context, four issues are especially important: the nature and magnitude of the changes, their timing relative to the seasonal/annual cycle, the spatial and temporal scales on which they occur, and their consequences for physical and biotic systems. This chapter provides a synthesis of the cryospheric changes documented in the preceding chapters and evaluates their combined impact on the Arctic environment and its inhabitants.

12.2. Ongoing and projected changes in the cryosphere

The increase in annual average temperature over the Arctic since 1980 is twice that over the rest of the world (with the exception of some regions of Antarctica), almost certainly due to polar amplification processes (see Chapter 1, Box 1.3). This has had considerable consequences for the cryosphere, most of which in the Northern Hemisphere is in the Arctic. It is now evident that feedbacks between the climate system and the cryosphere and between the different elements of the cryosphere are significant, and that the changes may be greater overall than projected by either the Arctic Climate Impact Assessment (ACIA) in 2005 or the Intergovernmental Panel on Climate Change (IPCC) in 2007. The current trends in cryospheric change are projected to continue within the Arctic (additional warming of 2 to 7 °C by 2100), with consequences of increasing significance expected for biological and human systems. The following sections address first-order changes (i.e., those in the cryospheric components themselves), feedbacks, and the second and higher-order changes induced by the cryospheric changes (i.e., changes in Arctic ecosystems and in the services these provide to humans).

12.2.1. Changes in the cryosphere

Substantial changes are expected throughout the Arctic cryosphere, driven by warming and in part by feedbacks among the cryospheric components and between the cryosphere and other systems.

Past/Present Climate (Chapter 2): ACIA projections of greater and more rapid warming in the Arctic than in other parts of the world are confirmed for the immediate past, particularly in autumn and spring. Sea-ice reduction is coupled with increased warming – this may represent a large shift in the Arctic climate system as evidenced by the greatest warming being over the Arctic Ocean (rather than on land as previously observed).

Model Projections (Chapter 3): General circulation model (GCM) projections based on scenarios of anthropogenic greenhouse gas (GHG) emissions indicate that the Arctic will continue to warm at a greater rate than other regions of the world over the next several decades. These projections may be regarded as ‘best estimates’ of future changes, but are subject to uncertainties arising from (i) natural variations in the climate system, (ii) the range of plausible trajectories of GHG concentrations, aerosols and other climate drivers over the next century, and (iii) systematic errors arising from model formulations, particularly the parameterizations of unresolved processes. The net effect of these various factors is a range of uncertainty that can be comparable to the projected change, although the use of ensembles of simulations from multiple models can help to extract the ‘signal’ of climate change. It must be kept in mind, however, that natural variability can result in occasional short-term trends of cooling during long-term trends of warming.

The overall average increase in surface air temperatures in the Arctic is projected to be 3 to 6 °C in autumn and winter by 2080 (6 to 7 °C in areas of sea-ice loss and 2 to 3 °C over land), relative to a 1957–2006 baseline. Precipitation is projected to increase throughout the Arctic with the greatest increases at the highest latitudes (a 5–40% increase by the end of the century for the IPCC B1 emissions scenario). The projected changes are greatest in winter (e.g., as snowfall) and autumn, and least in summer. Despite overall increased precipitation in the Arctic, some areas may experience drying of the landscapes due, in part, to increased evaporation associated with higher summer temperatures, a longer summer season, and perhaps altered drainage due to permafrost changes in some areas.

Snow (Chapter 4): Snow (structure, quantity, timing, extent, duration) is a fundamental attribute of northern environments. Snow-pack structure is changing, with winter thaws and rain-on-snow events increasing in frequency and with more ice crustings. Satellite imagery indicates that average snow cover extent decreased in summer (May–June) by 18% between 1966 and 2008. Annual snow-cover duration across the terrestrial Arctic (excluding Greenland) decreased by 3.9 days per decade, mostly due to the earlier disappearance of snow in spring (averaging 3.4 days per decade earlier for 1972 to 2009) with decreases projected to continue (by 10–20% over most of the Arctic by 2050). Some of this decline is likely to be due to albedo feedbacks (see Section 12.2.2). Projections suggest a slight increase in snow water equivalent (0–15%) over most of the Arctic by 2100 with high regional variation. In those areas with projected decreases in snow-cover duration and snow-water equivalent, the earliest and largest changes are projected to occur over coastal regions (as has been observed in the recent past).

Permafrost (Chapter 5): Permafrost temperatures have increased throughout the circumpolar area but there is high regional variation in the rates and magnitudes of warming. The thickness of the active layer (the surface layer above permafrost that thaws in summer) has progressively increased over much of Eurasia and central Alaska, but has remained relatively stable in northwestern Arctic Canada and the Alaskan North Slope. Over the past few decades, permafrost has disappeared from several lower latitude sites formerly characterized by discontinuous

permafrost. Projections indicate that by 2100 the area of near-surface permafrost will be reduced by 16–20% in Canada with an additional 9–22% projected to contain taliks (i.e., areas of unfrozen ground) embedded within the permafrost. There will be widespread permafrost degradation over up to 57% of Alaska (850 000 km²). Eastern areas of Siberia, which are particularly susceptible to climate warming, are showing similar widespread changes that are likely to continue. The consequences of these changes for landforms, ecosystems and infrastructure – such as melt water drainage, soil subsidence, slumping to lakes, and high silt loads in rivers – are likely to be profound (see Section 12.3).

River and Lake Ice (Chapter 6): The seasonal duration of river- and lake-ice cover is declining, primarily due to the earlier occurrence of spring break-ups. Some of the most profound changes have been observed on far-north lakes in recent decades. Models suggest that lake-ice duration on mid-sized lakes in the Northern Hemisphere could be 15 to 50 days shorter by around mid-century (2040–2079) compared to 1960–1999, mainly due to ice break-up occurring 10 to 30 days earlier. Maximum lake-ice thickness has also been modeled to decrease, by 10 to 50 cm. Changes in ice composition reflecting spatial patterns in ice-thickness reduction and snow-cover accumulation are also anticipated. Reduced temperature gradients along large northward-flowing rivers will favor a greater proportion of break-ups by thermal processes rather than mechanical (dynamic) processes, and thus reduced severity of ice-jam flooding. Mid-winter break-ups and associated flooding will become increasingly common in northerly areas. The nature of break-ups will also be affected by changes in the form (rain vs snow) and magnitude of precipitation.

Mountain Glaciers and Ice Caps (Chapter 7): General declines have been observed in mass (and volume) of mountain glaciers and ice caps over the past century, however, the rates of decline appear to have increased substantially since 1995. Mass losses from mountain glaciers and ice caps in the Arctic may have exceeded 150 Gt¹ per year over the past decade, similar to the mass loss from the Greenland Ice Sheet. Half of the observed loss is from glaciers in the Canadian Arctic and southern Alaska. Future projections indicate continuing losses due to warming, with the greatest losses projected for the Canadian Arctic and Alaska, followed by Svalbard and the Russian Arctic. Under the IPCC A1B emissions scenario, the total volume of Arctic glaciers is projected to decline by 13–36% by 2100, corresponding to a rise in sea level of 51–136 mm (but this estimate does not include losses by iceberg calving).

Greenland Ice Sheet (Chapter 8): Up until 1990, the total amount of ice added to and lost each year from the Greenland Ice Sheet was roughly in balance. Mass loss by both meltwater and ice discharge have increased since 1990 and the inputs and losses are no longer in balance. The estimated rate of net mass loss from the Greenland Ice Sheet over the recent past is four times that of earlier estimates (i.e., 205 ± 50 Gt per year for 2005–2006 compared to 50 ± 50 Gt per year for 1995–2000, of which roughly half is due to melting and half due to discharge).

Increased ice discharge is primarily due to accelerated flow in many of the fast-flowing glaciers that terminate on ocean water in the fjords. This speeding up of the ocean-terminating glaciers, a phenomenon that has spread northward along the west coast of Greenland over the past 10 to 15 years, appears to have been triggered by contact with warmer ocean water.

Sea ice (Chapter 9): The average extent of the summer (September) minimum sea-ice cover has declined by 25–30% since estimates based on satellite information began in 1979. The rate of decline increased over the past ten years and is now greater than reported by ACIA. Complete summer sea-ice loss is projected as likely to occur by mid-century. Variability in summer sea-ice extent is projected to increase initially, but then to decrease as ice-free summers are approached. Sea ice is generally thinning and older ice types (5+ years old) are being lost with increasing frequency; first-year ice is projected to dominate in the future. Shifts in the proportion and areal extent of multi-year ice versus first-year ice have immediate physical consequences including a larger area of open ocean during summer and autumn and greater heat absorption. Loss of summer sea ice and increased heat storage in the upper ocean are modifying regional wind patterns with increasing potential for impacts in mid-latitudes as sea ice retreats further in the coming decades. However, trends toward increased cloudiness have suppressed surface warming of the Arctic Ocean to some degree. Projections of annual maximum extent and duration of seasonal sea-ice cover are uncertain and regionally variable (and affected by local bathymetry and weather conditions), but maximum extent and duration are very likely to be less than at present (i.e., with a more northerly distribution, smaller area, shorter duration). Corroboration of local changes, especially for land-fast ice through traditional knowledge and local observations, support these findings (i.e., later freeze-up, earlier break-up, longer ice-free summer, shifted ice dynamics and types). The extent and location of summer/autumn polar pack (i.e., multi-year sea-ice remnants) will be uncertain in future years as the summer ice decline continues, but most models project that pack-ice remnants are very likely to occur along the northwestern margin of the Canadian Archipelago and the north coast of Greenland at least until complete loss.

12.2.2. Feedbacks

Arctic climate change results from complex interactions between the atmosphere, ocean, and individual components of the cryosphere. Many aspects of Arctic climate change are simple responses to a driving force, for example, higher (or lower) air temperatures will alter the ice balance in a particular area. Other changes may involve a feedback whereby a change in one component of the system drives a change in another, which ultimately induces additional change in the original component (see Chapter 11, Section 11.1). Such feedbacks can be positive (i.e., induced change reinforces and exacerbates the original change), whereas others can be negative (i.e., induced change dampens, cancels or reverses the original change)². Feedbacks are important because they may alter rates of change, magnitudes of change, or even directions of change. Owing to

¹ 1 Gt = 1 gigatonne = 1 billion tonnes, which is slightly greater than 1.1 cubic kilometres of water.

² Note – positive and negative here refer to the feedback itself and not the warming or cooling effects in the cryosphere context.

their unpredictable effects and their variable scales (spatial and temporal) of operation, feedbacks also add to the uncertainties of outcomes especially for higher-order consequences of climate and cryospheric change. Appropriate parameterization of processes and their interactions, and thus feedback processes, may be inadequately represented in climate models. This affects projections of future states of the climate system.

Two aspects of feedback are important in the present context: feedbacks between the cryosphere and other climate system components, and feedbacks between different cryospheric elements. Examples are discussed below. The list of major feedbacks is much longer than given here, however, and many remain poorly understood (see also Chapter 11, Section 11.1). A third level of feedback is that between the cryosphere and human systems. This feedback is extremely important but also highly uncertain – feedbacks at this level are discussed in Sections 12.3 to 12.5.

12.2.2.1. Feedbacks between cryospheric and other climate system components

Potential feedbacks between the cryosphere and climate include:

- Snow has an extremely high albedo (surface reflectivity). Albedo of snow and ice decreases as they melt and metamorphose, and/or as particulate matter (dust, soot, volcanic ash) is deposited onto them, and/or as particulate matter is exposed at the surface as it is released from snow and ice by melt. Increased heating of darker land and sea surfaces will occur as snow amounts decrease in time and space which, in turn, will exacerbate melting. This feedback is partly responsible for the accelerated rates of cryospheric change observed over the recent past, albeit with high uncertainty associated with them. The replacement of sea ice by open water over wide areas of the Arctic Ocean has substantially increased heat absorption by the upper ocean. This appears to have increased the rate of melting of the remaining sea ice, to have altered the Arctic climate system itself (heat storage and wind patterns), and to have accelerated changes in other cryospheric components. Moreover, higher ocean temperatures pre-set conditions for seasonally later sea-ice formation, ultimately resulting in a thinner and generally less consolidated sea-ice cover, and influencing the magnitude and timing of ice loss and seasonal melt the following year. This may be exacerbated by increased snowfall (which would insulate and slow seasonal ice formation); however, some effects may be modified by the increased freshening of the system, as less saline waters are more liable to freeze.
- From a total of 48 interactions (six cryospheric components and eight forcing mechanisms), present evaluation (Chapter 11, Section 11.1) shows that more feedbacks between the cryosphere and Arctic climate change have a warming effect (fourteen) than a cooling effect (eleven), and result in accelerated rates of climate change in the Arctic (i.e., ‘polar amplification’). Of the remainder, three are uncertain due to conflicting evidence and 20 represent gaps in knowledge.
- Feedbacks operate at different spatial and temporal scales and so understanding their consequences is difficult and associated with high uncertainty. Additional uncertainty

arises because effects from some feedbacks are expected to intensify over time, while others are expected to diminish.

- Spatial connections mean that the effects of cryospheric change within the Arctic will have implications for areas outside the Arctic and these effects may be large and possibly counter-intuitive. For example, sea-ice loss north of Eurasia may lead to colder weather in Europe and Siberia during late autumn and early winter (see Chapter 2, Box 2.1). Reduced summer sea ice, increases ocean heat absorption which is released back as the atmosphere cools in autumn. The lower atmosphere thickness is increased which thus increases pressure, resulting in de-stabilization of the Arctic boundary layer. Winter winds flowing out of the Arctic may therefore be more intense and affect lower latitudes to a greater degree than is typical, resulting in winters of greater severity in Europe and Siberia – a counter-intuitive effect of climate warming.
- The production and release of GHGs from Arctic stores or processes is likely to increase as the cryosphere degrades or changes. Changes in permafrost and lake ice, for example, can enhance the production of methane (which has great capacity to induce warming) and nitrous oxide and increase the seasonal window for their release. However, drying of the active soil layer can cause a methane sink in some cases. Overall, processes such as carbon dioxide fluxes are likely to have very small global effects. Others, such as those that may result in the release of subsea methane, could have large global effects, although in both cases the uncertainty is high.

12.2.2.2. Feedbacks among cryospheric components

Feedbacks among cryospheric components include:

- The occurrence of relatively warm open water near floating ice tongues from the Greenland Ice Sheet appears to have increased mass loss from the ice sheet through increased flow rates to the sea and thus increased calving of icebergs, particularly in western Greenland. Similarly, the degradation and complete loss of semi-permanent land-fast sea ice on the northern coast of Ellesmere Island in the Canadian Arctic appears to have contributed to the break-up of the 3000–6000 year old marginal ice shelves in the area, probably due to their exposure to a warmer and more open-water environment.
- Snow insulates underlying environments from atmospheric temperature extremes. As snow extent and duration decrease, and despite the likely increase in snowfall amounts, ice (lake, river, sea) and permafrost environments will probably both be exposed earlier in the season to generally warmer atmospheric conditions. If so, this will exacerbate spring thaws and increase active-layer depth in permafrost. Consequently, decreased integrity of ice and permafrost can be expected due to the insulating properties of snow.
- In the terrestrial environment, permafrost acts as a key element determining hydrology over great areas of the Arctic. As a result, changes in the permafrost will alter drainage and this could lead either to drying or to increased ponding over significant areas. Drying creates conditions

for wildfires in tundra and forested areas, which will be exacerbated by higher summer temperatures and increased evaporation. Fires may contribute to increased emissions of GHGs and other climate forcers.

- Decreased ice on land, rivers, lakes and the sea will result in greater evaporation of water. The likely effect will be an increase in clouds at mid-levels in the atmosphere. Clouds reflect incoming radiation, which means increased amounts of cloud may result in overall cooling of the atmosphere. Increased evaporation also affects precipitation regimes.

These feedbacks, as well as additional feedbacks noted in other chapters, generally exacerbate the effects of changes in the climate system and the cryosphere. Furthermore, as already noted, feedbacks also increase uncertainty in the timing, rates, nature, spatial scales and outcomes associated with climate change. The relevance of these feedbacks and their interactions with Arctic ecosystems are discussed in the following sections.

12.2.3. Effects of cryospheric changes on other aspects of the Arctic environment

Changes in the physical nature of the cryosphere have consequences for other components of the Arctic environment.

Snow: Changes in snow will have profound effects on terrestrial environments and their soil, plant and animal communities, as well as on aquatic environments influenced by terrestrial runoff (wetlands, rivers, lakes, coastal seas). Increased insulation resulting from greater snowfall may increase winter soil temperatures, thus increasing rates of biological processes, such as decomposition and nutrient release. In turn, where water is not limiting, there may be an overall increase in terrestrial productivity manifested by seasonally earlier, more intense and higher levels of production; as well as shifts in community types (e.g., greater shrubiness). These effects may be offset by earlier disappearance of snow, winter thaws, or rain-on-snow events. Winter-resident herbivores, such as rodents, rely on sub-nivean environments that, if affected by adverse events or if frozen, would lead to decreased population abundance. Follow-on responses by resident predators to declining food sources have effects throughout the entire food web. Similarly, consequences for large herbivores, such as musk-ox and caribou/reindeer that forage through the snow in winter, will reflect the combination of many local factors (e.g., winter mortalities due to limited access to forage, increased mortality due to moulds, possibly increased fecundity due to earlier forage availability in spring), but overall the net effect is likely be negative. Effects on peoples who hunt or herd could be substantive, with a significant decline in food security and traditional activities, particularly during winter. Conversely, increased nutrients and earlier production in terrestrial environments may result in greater local productivity with positive consequences for some animal species and people. Water from snow melt transports nutrients to aquatic systems, possibly enhancing local productivity, and if trapped on the landscape tending to counteract drying regimes.

Snow insulates ice and blocks light penetration, whether the ice is on lakes, rivers or the sea. By insulating the

underlying ice, increased snowfall will tend to result in the ice being thinner (although shorter snow durations may offset this to some degree, and increased snow loads on thin ice could promote snow-ice formation). Winter nutrient accumulation in the water column combined with light penetration during early polar spring ‘jump start’ the seasonal production in freshwater and marine ice-covered ecosystems. Greater snowfall, particularly during polar spring will reduce the light available for photosynthesis by phytoplankton below the ice, although this effect may be offset by longer open water conditions. This shading effect may also impede photosynthesis by sea-ice algal communities, which can represent a large fraction of the total annual primary production, and thereby alter marine food webs.

Permafrost: Permafrost affects the landscape drainage patterns, and is responsible for the vast range of tundra wetlands, ponds and small lakes present in the Arctic. Degradation of permafrost alters the nutrient processes in these systems and in many areas has resulted in the drainage and loss of lakes. Tundra water bodies are ecological and biogeochemical hotspots providing key habitats for biota. They are also significant sources of GHGs to the atmosphere, and permafrost degradation may alter GHG export from such areas. Permafrost degradation in terrestrial areas may also result in slope instabilities and subsequent failure; failures affect the receiving ecosystems (lakes, rivers) and also represent hazards to humans and built environments (roads, towns, industrial sites). High uncertainty surrounds effects of permafrost thaw on soil water content thus subsequent effects on ecosystems and on GHG emissions – projections are uncertain but models suggest that the tundra will continue to act as a weak carbon sink at least for the next 100 years (i.e., net balance throughout the Arctic will be slightly toward continued storage of carbon thus slightly ameliorating effects of GHG production). Up to 65% of the Arctic coastline is composed of unconsolidated materials with considerable ice-rich constituents and is therefore at risk due to permafrost degradation; this is particularly acute near the deltas of most major Arctic rivers. Alteration of coastlines due to slumping will be exacerbated by a decline in sea ice, longer open-water fetches, and increased effects of storms. Continental marine shelves and the nearby low-lying deltas of large northern rivers also hold large reserves of carbon, mostly in the form of methane capped by an impermeable layer of permafrost. Degradation of the permafrost may ultimately result in the abrupt release of large quantities of this potent GHG, representing an uncertain future threat.

River and Lake Ice: Second and higher-order effects of changes in freshwater ice (e.g., on gas exchanges, mixing regimes, contaminant capture, exposure to ultraviolet radiation, and overall biological productivity and diversity) will have numerous implications for the ecosystem health of aquatic systems. The effects of changes in river and lake ice are very likely to be closely coupled with nearby land-form changes due to permafrost thaw. Changes in ice-cover dynamics are likely to decrease the frequency and magnitude of spring ice-jam flooding in many areas of the Arctic, affecting the ecology of deltas, which is especially relevant to the overall production in the large Arctic rivers. Ice-jam flooding produced by mid-winter melt and ice break-up represents an increasing hazard

to nearby communities and infrastructure. Predictions of ice-induced flood conditions, however, are confounded by uncertainties about the intensity and magnitude of future snowmelt runoff that affect the dynamics of river-ice break-up processes.

Mountain Glaciers and Ice Caps, and the Greenland Ice Sheet:

The consequences of changes in these cryospheric components include exposure of new land and altered drainage patterns, initial increases in runoff followed by eventual declines as glacier area decreases, and water outbursts of several types if glacier lake dams fail. Increased iceberg formation and continued break-up of ice shelves (until they disappear completely from the Arctic) are also expected, and may create hazards in the marine environment. Also, release of materials stored in ice (contaminants, sediments, fine particulates) may affect downstream water quality (generally negatively). Increased water output during the summer melt period is also expected and may represent a positive benefit in some locations, at least in the near term.

Sea Ice: A progressive decline in the area of multi-year sea ice, its seasonal replacement by younger ice, lengthening of ice-free periods, and increased area of open water have profound implications for the Arctic. These physical changes will alter albedo and increase heating and gas exchange in marine waters. These effects will, in turn, have follow-on effects on the climate system, marine ecosystems and human activities. Some ice-associated ecosystems (such as multi-year sea ice and epishelf lakes) are at risk of complete loss; others will change significantly. Phytoplankton production rates in the marine ecosystem are likely to change, but to a variable extent among sites. In general, these rates are likely to increase as a result of sea ice loss and increased exposure to sunlight, although this effect may be offset to some degree by increased water column stability caused by freshwater inputs to the surface layer. In addition, ice-associated biota are likely to decline, while other biota will become more important. Both types of effect will alter structural and functional relationships within the ecosystems. Altered trophic relationships due to changes in pivotal components (ice algae, cryophilic zooplankton, Arctic cod) will induce effects in those species that prey upon them. As it is the higher-trophic level species (seabirds, marine mammals, predatory fishes) that are the most directly relevant to humans, changes in sea ice will ultimately affect human food and exploitation opportunities in the Arctic. Increased extent and duration of open water in the Arctic Ocean will also feed back to climate and affect coastal environments.

Induced Effects and Ecosystem Overview: Physical changes in the environment resulting from changes in cryospheric components induce follow-on effects, many of which ultimately cascade to ecosystems. The rest of this section reports wide-ranging and over-arching induced effects (for further details see Chapter 11, Sections 11.3 and 11.4).

- *Shifts in Terrestrial and Freshwater Ecosystems and Water Balances:* Greater precipitation overall (regardless of how delivered) primarily as snow, increased glacier and ice-mass shrinkage, shorter ice duration, and warmer winters, will all combine to result in an overall increase in the amount, temporal extent, and availability of liquid water in the Arctic

(at least in the short term). Processes that increase drying (evaporation, drainage) will counterbalance this to a varying degree. High spatial variation is also likely, thus local water balances will be highly variable. Effects that increase water in the landscape will occur in the near future and most will continue at least until mid-century, although some will ultimately decline (such as water flow from smaller glaciers). Assuming warming feedbacks continue, mass loss associated with large glaciers and ice sheets will continue for centuries. As previously noted, these effects will also be modified locally by changes in permafrost, effects from ice, and similar linkages among cryospheric elements, all of which will affect local and regional hydrology. Moreover, higher air temperatures in summer will alter evaporation by increasing drying regimes. A change in the water balance will have significant follow-on effects on terrestrial ecosystems by creating new habitats. Responses in the vegetation may include greater productivity, northward shifts in distribution, increased invasions of pest and disease organisms, local extirpations of some endemic Arctic flora, and increased local biotic diversity but with species composition differing from present-day. Changes in the vegetation and productivity will then enable similar shifts in animal diversity within the terrestrial landscapes. Nutrients and other constituents (silt, contaminants) carried by water will affect freshwater ecosystems with similar consequences. Infilling of habitats due to sedimentation, and slumping and de-watering over large areas of tundra will also affect biota (waterfowl, freshwater fishes) that rely on these biological ‘hotspots’. In some areas new aquatic and terrestrial habitats will be created as glaciers and ice sheets decay, and freshwater ice is lost particularly where it currently freezes to the bed or exists as perennial forms. Colonization of these new environments represents a microcosm of wider shifts that are likely to be forthcoming for many terrestrial and freshwater ecosystems in the Arctic.

- *Shifts in Marine Ecosystems:* Sea ice affects and controls element cycling in marine ecosystems (thus regulating primary production), water-mass mixing processes (including upwelling of deeper waters), and light penetration. Sea ice also acts as a physical habitat for some marine mammals and seabirds. As a result, shifts in the presence and types of sea ice present will have far-reaching consequences for marine ecosystems in the Arctic. These are likely to include: increased production in the central Arctic basin accompanied by a switch from light- to nutrient-limited conditions; a shift in primary production (and associated secondary production) from a high proportion of ice-based primary production to much greater plankton-based production, particularly over coastal shelves, with consequences for nearshore benthic production (possibly decreased) and unknown consequences for higher trophic levels such as fishes and marine mammals; and, northward shifts in marginal ice zones associated with highly productive sub-Arctic seas and general ocean warming, which are likely to be accompanied by changes in the distribution of marine biota of direct interest to humans (fishable species as well as new predators such as killer whales). Alternatively, the seasonal timing of sea-ice retreat will affect the availability

of ice-associated zooplankton and lipid-rich forage fish – critical resources for higher trophic levels. Negative follow-on consequences for Arctic-adapted biota may ensue. Mismatches in space and time between sea ice and Arctic ecology will have significant consequences for populations. For example, reproductive success in seabird populations is likely to decline in many locations as land-fast ice edges retreat or degrade earlier and as underlying fish quality changes as species distributions shift. Shifts in biodiversity may also result as sea-ice habitats change or are lost (see Section 12.3.5).

- **Contaminants:** Glacial ice and/or snowpacks, once considered semi-permanent sinks for contaminants will eventually become local sources as melting releases stores of long-lived contaminants to Arctic waterbodies, landscapes and the atmosphere (see Chapter 11, Section 11.3). This will increase the likelihood of these contaminants re-entering biological and human systems. Such contaminants include legacy persistent organic pollutants (POPs) and metals and possibly also radioactive elements. At least over the short term (to mid-century), degradation of multi-year sea ice is likely to alter contaminant dynamics. Shifts in snow characteristics are likely to alter the dynamics of volatile contaminants with greater transfer to the atmosphere and/or water possible. Altered landscape hydrology and drying of some landscapes may also release or expose contaminants stored in freshwater sediments. Increased exposure is likely to increase entrainment in seasonal flows and biota, thus encouraging contaminant re-entry into Arctic ecosystems. Accelerated remobilization of legacy POPs is very likely as the Arctic Ocean becomes more exposed and warmer; moreover, decreased ice is likely to increase this, whether or not winds change in the future. Uncertainties with respect to biotic degradation processes for POPs may alter rates; this is a significant gap in understanding. Altered ice dynamics will alter the mercury cycle in the Arctic Ocean. Enhanced entrainment and transport of contaminants is likely throughout the Arctic Ocean via greater amounts of seasonal first-year sea ice. Shifts in marginal ice zones, the sites of extensive biological production supporting most *in situ* trophic productivity in the Arctic marine system, will induce shifts in lipid pathways and transfers. As a result, contaminants preferentially stored and transferred in lipids are very likely to affect higher trophic levels (Arctic top predators such as seabirds, whales, and polar bears). Changes in foraging behaviors are also likely with altered trophic patterns and loss of key habitats such as sea ice. Follow-on health effects of contaminants on biota, as well as on humans relying on these organisms are possible but details are uncertain at this time. Colonizing and invasive species that are typically highly migratory will increase in the Arctic as thermal and ecological barriers decline; the proximate effect will be to alter contaminant pathways in unknown ways. In addition to the cryospheric linkages outlined above, human activities and the changing climate will also influence contaminants in uncertain ways, for example, increased human access and development may increase the potential for contaminant release.

12.3. Integrated consequences of cryospheric-driven changes on Arctic societies

The lifestyles and activities of humans in the Arctic are very closely associated with the environment; that is, the Arctic in general and the cryosphere in particular exert great and close control over when, what and how activities can occur (Chapter 9, Section 9.4 and Chapter 10). This is true irrespective of whether one lives on the land with a traditional lifestyle and a primarily subsistence-based livelihood, whether livelihood is primarily wage-based and thus life is oriented more toward urban centers, or whether one is a seasonal worker in the North. These forms of livelihood have different associations with the Arctic landscapes and seascapes, and cryospheric changes will affect each in different ways. Also, the nature and consequences of cryospheric change will differ depending on whether the area occupied is primarily inland or coastal. The various sectors from which livelihoods are derived will be exposed to different consequences of cryospheric change. The consequences include a combination of direct effects (access, hazards) and indirect effects (shifted or lost ecosystem services requiring adaptation or replacement), both of which sum to an overall effect. Finally, changes also have non-material consequences as they affect the overall experience, perception, cultural value and well-being of people living in close relation to the Arctic cryosphere.

12.3.1. Changes to access in the Arctic environment

Ice in its many forms represents the solid phase of water present throughout the Arctic cryosphere. Ice thus represents a barrier (or impediment) as well as a benefit to virtually all human activities in the Arctic. As a result, changes in ice alter aspects of human accessibility to local and regional land and aquatic areas, directly affecting how these are utilized. Altered accessibility has far-reaching social, cultural and economic consequences.

- River and lake ice, and permafrost in terrestrial landscapes offer relatively inexpensive seasonal transportation routes via ice roads between southern centers of supply and northern communities and industrial sites. Thus, changes in these cryospheric components (such as shorter seasons, altered routes, weaker or thinner ice) affect transportation options and result in increased costs for overland transport. Few viable adaptation options exist, especially for communities far from coasts or large river systems. Permanent all-weather roads or railways may ultimately be necessary at significant cost to regional and/or national economies. On the other hand, cryospheric changes may also result in increased opportunities for water-based transport (longer seasons, more water from increased precipitation), but these are mostly restricted to northward-flowing large rivers, large lakes, and coastal areas.
- Land-fast sea ice provides local transportation options when it is present, and negative effects result from its earlier seasonal degradation. Activities on land-fast sea ice include hunter travel to floe edges for wildlife harvesting, inter-community travel, and industrial activities. Land-fast sea ice also provides a stabilizing and protective feature for

coastlines and near-shore activities such as hydrocarbon development. Its degradation will require changes in how these areas are used and the duration of their use. Altered shorelines will also affect communities (see Section 12.3.4). Alternatively, the presence of land-fast sea ice inhibits summer marine transportation, often requires local ice-breaking activities, and affects the re-supply of communities and coastal shipping. Earlier seasonal disappearance is likely to benefit such activities. Shifts in seasonal sea ice will also permit earlier and later, and perhaps increased, overall ice-breaking to allow for longer operational shipping seasons. Ice-breaking activities affect sea-ice habitats and ecosystems and may also affect local human activities.

- Pack ice, especially when highly consolidated and at its greatest seasonal extent during late winter, acts as a barrier to Arctic marine transportation and so restricts access by humans to many areas over much of the year. Decreased duration and areal extent of pack ice will thus facilitate marine transportation. Open areas in pack ice (polynyas and flaw leads) are key habitats for ice-associated Arctic biota but also represent access points for ice-capable shipping, and thus potential conflicts arise between habitat use by biota and economic endeavors.
- At the level of the individual (in contrast to the previous points which address the community level), over large areas of the Arctic access involves travel both on land and over local infrastructure such as roads. Similar to the consequences outlined above, changes in terrestrial and freshwater cryospheric elements will affect local accessibility. Permafrost degradation, changes in lake and river ice, glacier or ice sheet retreat, and changes in snow regimes will all affect the integrity of local landscapes and thus their suitability for overland travel. Poorer travel conditions increase hazard and may require a change in lifestyles, areas and timing of use, and traditional practices for indigenous groups. Changes are also likely to be required in local land use practices associated with industrial activities (e.g., seismic exploration). Where built infrastructure is present (roads, bridges, airstrips) cryospheric changes will affect local usage patterns and may require increased maintenance schedules or re-construction.
- Sea-ice affects marine vessel traffic whether this is destination shipping to/from the Arctic, marine fishing, ship-based tourism, research cruises, military activities, coastal monitoring, or ultimately transpolar shipping. Altered sea-ice regimes for land-fast and pack ice will affect access associated with these activities. Although decreased sea ice can generally be expected to lengthen seasonal periods of access, ice regimes are expected to be highly variable in space and time. Moreover, larger areas of open water allow for increased consequences of wind and storms, and perhaps increased fog and icing events. Winds and storms also move large masses of unconsolidated ice, which represent a significant but highly dynamic local issue for shipping. Thus, while access may overall be longer or better, it may be offset by more rigorous operational conditions, greater probability for accidents, and associated requirements for safety and infrastructure. Also, feedbacks of human activities on the cryosphere from increased shipping

may occur with increased production and deposition of contaminants and perhaps also engine soot in sensitive northern ice environments. Issues associated with Arctic shipping consist of those within territorial jurisdictions as well as those associated with the offshore environment. Given the connectivity among Arctic marine areas due to currents and present-day ice movements, accidents (particularly hydrocarbon spills) have the potential to affect large areas for long periods of time. Thus, cooperative pan-Arctic solutions to these issues are required.

- Overall reductions in sea ice will also allow for access to areas that were previously accessible only with great difficulty. Increased access may stimulate industrial activities (mines, sea-bed activities, hydrocarbon development), thus increasing local economic output, shipping, and further alteration of local lifestyles. These areas are likely to be those that persist for the longest, and thus within the next few decades may become remnant refuges for Arctic endemic biota. Modeled projections indicate that remnant multi-year sea ice is most likely to become associated with the northwestern margin of the Canadian Arctic Archipelago and northern Greenland, although substantive mobility may also occur. Action will be required to ensure the sustainable uses of such areas.
- Although limited at present, future glacial retreat, especially in Greenland, will expose new land allowing greater access to non-renewable resources. Economic benefits derived from increased access may be offset by the longer travel times required for hunters to reach wildlife populations. Thus, the overall balance of these changes to human activities is a dynamic consequence of potential positive and negative effects that cross many scales.

Altered accessibility within, to and from the Arctic is an inevitable outcome of cryospheric change and will affect many aspects of human activities in this area, albeit with uncertain timings. Even more uncertain are the local consequences of effects, whether these will be beneficial or detrimental, and whether the overall balance of effects will be negative or positive at a particular level or to a particular group in Arctic society, as well as collectively across all levels. The ability of humans to adapt to the challenges and opportunities associated with cryospheric change in the Arctic depends to a large degree on non-cryospheric factors and drivers of change. It is entirely possible that the overall balance of effects at one level may be negative (e.g., personal travel on sea ice) while at another level the effects may be positive (e.g., community re-supply and costs of purchased goods). Moreover, there may be local differences in adaptive capacity and involvement that will determine whether a change will be largely positive or largely negative. It is the sum of the effects that affect local cultural, economic and societal viability, and thus detailed examinations are required to better understand adaptation options to changes in the cryosphere.

12.3.2. Humans, biodiversity changes and land-use activities

Humans in the Arctic rely on ecosystem services and utilization of terrestrial and aquatic ecosystems for security of their local food supply, health and well-being, integrity of cultures and

lifestyles, income, and economic development. Cryospheric changes generally affect all these aspects of life, however, the nature and potential effects of these changes, and whether they represent potential threats or benefits, depend upon the economic sub-sector to which the individual belongs. Examples of some possible consequences follow, but this list is by no means comprehensive.

- Changes in land-fast sea ice have affected travel to/from the floe edge to hunt, with subsequent effects on safety, food security and personal economies of indigenous peoples. Such effects are locally variable; for example, generally negative in Nunavut, Canada but positive in Greenland (where a switch to boats has increased local harvests of some marine mammals). These effects are likely to continue and become more acute, however, longer ice-free seasons may benefit new approaches to hunting, traveling and local fishing but this is likely to require financial and technological capacity building. Changes in traditional harvesting practices that are closely connected to indigenous cultures will also be required. Moreover, current knowledge (i.e., traditional knowledge) must be expanded to accommodate cryospheric change. Increased reliance on some forms of technology (e.g., personal GPS devices) may aid activities in changing environments, but these do have limitations.
- Terrestrial cryospheric changes also affect travel to hunting, fishing and harvesting sites. Moreover, these activities often rely on large land mammals, such as caribou, that also travel as migratory herds. Migration routes and timing may be altered due to cryospheric changes and a mismatch may occur in traditional timing or place, or in hunter or herder access to areas for these activities. Routes of migratory land animals which cross water bodies increase the likelihood of habitat contraction and catastrophic losses of large numbers as cryospheric changes occur. In the case of herding activities, adjustments in the timing of seasonal activities are likely to be required. These adjustments are also management issues and so require adaptation in governance and regulation.
- Changes in snowpack conditions will affect accessibility, and the forage base and its quality for reindeer and other land herbivores. Follow-on effects are likely to be negative overall for reindeer husbandry, herd survival and well-being, as well as for harvesting wild populations, and thus engender further effects on the cultural, economic and lifestyle significance of this activity.
- As sea ice retreats, shifts in commercial or locally harvested fish species may occur and fishing activities may require adjustment. These will be highly regional in nature and may be exacerbated by unrealistic expectations regarding the biomass and sustainability of Arctic fisheries. In freshwater ecosystems, shifts in productivity and colonization may increase overall fisheries production particularly in the more southerly areas of the Arctic, although this is likely to be at the expense of some Arctic-adapted species.
- Large shifts in biodiversity are expected as cryospheric changes continue (see also Section 12.3.5). These include the following changes (most of which have negative outcomes

relative to the present situation): loss/extirpation of some organisms; changes and re-structuring of communities; loss of some unique habitats and communities; and colonization by invasive or pest species. Alternatively, some shifts in biodiversity offer opportunities, including: changes in ranges; higher productivity within some existing ecosystems; and new colonizing species some of which may be harvestable. The outcomes of biodiversity shifts are all highly uncertain, but it is reasonable to conclude that most Arctic ecosystems and communities will change substantively, ultimately with significant effects on humans. Also, given the rate and scope of cryospheric changes in the Arctic, it may be decades before ecosystems are sufficiently re-equilibrated and resilient to permit large-scale commercial exploitation. In the interim, some aspects of local subsistence resource harvesting may be seriously challenged.

- Cryospheric changes will also affect aspects of land use other than travel. Local hydropower options will be affected by snow changes (increased snow and more runoff is likely to represent a benefit) but altered lake (reservoir) and river-ice regimes will require adjustment to operations. Similarly, altered glacial mass balances imply short-term flow increases for some glacial-fed rivers and hydropower planning, as is happening in Greenland. Glacier retreat and changes in land drainage patterns, and eventually the complete loss of some glaciers will require planning to ensure water supply remains steady over the lifetime of the facilities.
- Ground subsidence in ice-rich permafrost areas affects travel, infrastructure, and long-term integrity of buildings. In addition to local economic consequences of infrastructure maintenance, repair and replacement, loss or rupture of containment structures or pipelines may have profound environmental effects including release of hydrocarbons or toxic metals into sensitive environments. This is exacerbated by aging and/or poorly inspected infrastructure, and follow-on consequences of permafrost changes such as altered flow regimes possibly facilitating wider movement of spilled materials.

Perhaps the biggest challenge in the future will be to try to maintain environmental and ecosystem integrity in the face of more rapid, yet still uncertain, changes resulting from many causes: substantive cryospheric changes, additional environmental changes due to climate change, and shifts in human populations and the nature of their activities in the Arctic. Uncertainty of outcomes is extremely high, especially at the ecosystem level and is compounded by high variability in system drivers and potential responses. Feedbacks between human systems and the environment, both within and outside the Arctic, further increase the uncertainty of outcomes. These factors will combine to make planning and environmental stewardship extremely difficult.

12.3.3. Industrialization and development

Cryospheric changes can create opportunities for industrial development in the Arctic by increasing accessibility. These opportunities include those associated with non-renewable resources including hydrocarbon development on land and coastal shelves and slopes, new mining possibilities (primarily

on land but potentially also in the sea), and transportation needs and opportunities. Opportunities also exist for renewable resource sectors, including increased potential for forestry and agriculture further north than at present, fisheries and aquaculture potential, and tourism.

Challenges to development opportunities also exist. These include high uncertainty in future states of the Arctic system and thus limited ability for predicting future potential (especially for industries that rely on renewable resources such as water). The overall system is rapidly following a trajectory of high change; high variability exists in the system, and the effects of changes on industrial and other human developmental activities are uncertain. Also, human responses to change are uncertain and the capacities to adapt to such challenges are highly variable across the Arctic. Nevertheless, appropriate planning and regulation are required to ensure that exploitation of new opportunities does not exacerbate changes in the cryosphere.

Aspects and challenges specific to many of these industrial or economic activities have been discussed or touched upon in other sections and will not be re-examined here. However, several have not and these are outlined below.

- **Tourism:** Increased ship-based tourism will be fostered by increased access associated with sea-ice changes, and existing evidence suggests a recent increase in this activity. Expectations of service, safety and positive experiences will be high and many local communities may be challenged to meet the capacity (e.g., in terms of providing local cultural experiences to meet demands). Regional or national governments may also face challenges (e.g., search and rescue needs). As components of the cryosphere continue to degenerate or re-equilibrate, the ice-associated animal species are likely to be reduced or re-distributed into smaller more northerly areas. Thus, access may become more difficult and, as species become rarer, disturbance will be an increasing problem that is likely to require responses to ensure sustainability both of species and their dwindling habitats. At the same time, land-based tourism to observe Arctic wildlife, experience adventures, or see cryospheric structures is a growing industry. As cryospheric degradation continues, however, the potential for this may be altered.
- **Forestry and Agriculture:** Increased precipitation and the resulting increase in local productivity may facilitate growth of harvestable renewable resources. This may also be positively affected by increased warming. Thus, along the southern margins of the Arctic and in many northerly sub-Arctic areas, increased production in renewable resource sectors is likely. Such increases, however, are likely to be highly variable in space and time, and effective increases in productivity may not be realized for decades. Moreover, in some areas drying will increase moisture stress on forests and exacerbate fires. Stressed trees are also more susceptible to pests.
- **Hydrocarbons:** Stores of oil, natural gas, and gas hydrates in the Arctic are significant and many are readily accessible in terrestrial and marine shelf environments, albeit with major technological challenges. Moreover, as access changes additional areas may become exploitable. As a result,

hydrocarbon development, production, and transport to southern markets are very likely to increase substantially over the coming decades. Increased variability and uncertainty in cryospheric environments, the Arctic climate system itself, and long-term adverse consequences of accidental discharges of oil, drilling wastes, or contaminants in cold and ice-associated environments, all represent substantive issues to be addressed.

12.3.4. Hazards

Changes in the Arctic cryosphere either create new hazards or alter exposure to existing hazards. As with most consequences of climate and cryospheric changes, hazards cross a wide spectrum of relevance ranging from immediate physical and direct hazards to those that are less direct and perhaps secondarily derived. Increased potential or realized hazards will require increased personal vigilance and local risk assessments, mitigation where required, and direct responses to the hazards themselves. Moreover, some hazards are predictable or can be assessed through risk-based methods whereas others cannot. Preparedness to meet both types of challenge is required. In addition to the hazards previously discussed, examples across the spectrum of likely hazards include the following.

- Decline of summer sea ice will expose vulnerable shorelines to open water and storm events, thus contributing to significant erosion and flooding in some areas. Sea-ice declines will interact with other cryospheric changes (e.g., permafrost decline) and other climate-driven changes (e.g., increased runoff) to further affect coastlines. The result will be significant consequences for shore-based infrastructure, coastal communities, and some cultural sites. Reinforcement and stabilization of buffering systems on coasts and/or re-location of coastal communities may be required with significant costs incurred by individuals, local and regional governments, or local industries.
- Where increased ice calving occurs directly into the sea, iceberg transport into southern shipping lanes of the Northwest Atlantic represents a hazard, but uncertainties presently preclude projections into the future. This represents a knowledge gap.
- Glacial outburst floods and avalanches are all exacerbated by increased snowfalls, enhanced freeze/thaw cycles, and degradation of cryospheric components such as glaciers, ice and permafrost. Slope instabilities further increase the likelihood of such occurrences. Moreover, effects from such events can be locally widespread and reach distant locations downstream. As a result, infrastructure, towns, and habitation in such areas are at increased risk as the cryosphere continues to degenerate. Appropriate risk assessments and potential remedial actions are required.
- Ice- and permafrost-related travel is inherently risky and longer freeze-up or break-up seasons, perhaps thinner ice, and less stable conditions are likely to increase human strandings or mortalities. Increased loss of equipment, industrial loads, foodstuffs, and perhaps hazardous goods can also be expected. Reduced use of ice and permafrost, reduced loads, alternative transportation routes, enhanced

search and rescue responses, and increased monitoring are required as local shorter-term responses. Longer-term responses may involve developing alternative transportation routes over great stretches of difficult terrain.

- Cultural or archaeological sites on coastlines, and/or lake or river margins are likely to be lost as permafrost degrades. Also, loss or exposure of paleontological remains is likely to occur. In many cases these sites have neither been discovered nor explored, and so their loss represents a significant cultural loss of global relevance. Permafrost changes may also enhance industrial hazards such as containment failures, pipeline ruptures, and infrastructure failures ranging from personal housing to community services. Enhanced monitoring and risk assessment is required; replacement planning requires enhanced engineering protocols, implying greater costs.
- Spring ice break-ups, particularly on large northward-flowing rivers (the Arctic has five of the ten largest rivers in the world and a high number of smaller but still substantive rivers), are projected to become less dynamic (mechanical) in nature. Although decreases in break-up flooding will have negative effects on the ecology of productive deltas, overall the changes are expected to be beneficial to communities and infrastructure in vulnerable locations. If, however, break-up occurs much earlier, particularly during mid-winter, or if enhanced snowmelt runoff drives break-up, increased severity and impacts of ice-jam flooding will result. The potential interactions between these two cryospheric components, river ice and snow, remain to be fully resolved.
- Decreased sea ice and more open water could alter the probability of higher winds and the severity of storms over the Arctic Ocean. Such storms will also result in more energetic motion of remaining ice. These represent uncertain hazards to human endeavors in the Arctic and require better weather prediction for large areas of the Arctic.

12.3.5. Ecosystem and biodiversity losses

Some cryospheric components and their associated biota are unique and irreplaceable once lost or degraded. Ice shelves, most of which fringe the northern margins of the Canadian Arctic Archipelago have persisted for the past 3000 to 5500 years. Substantial areal loss has occurred over the past 100 years, including large changes since 2000 (e.g., 23% loss of total ice shelf area in the warm summer of 2008, relative to 2007). The epishelf lakes retained behind ice shelves are unique polar aquatic ecosystems, but are now almost completely lost from the Arctic, with only one remaining.

Changes in permafrost condition fundamentally change hydrological conditions on land, and unique elements in permafrost areas such as peat mounds with frozen cores and ice-cored hills have been observed to decline. Permafrost degradation in land areas is likely to increase slope instability, while permafrost thawing in coastal areas may increase coastal erosion. Permafrost degradation, both in land and coastal areas, is likely to cause significant ecosystem changes.

Permafrost contains viable life to at least 400 m depth, in some cases preserved for significant periods of geological time (millions of years in northern Siberia). Biological activity

(bacteria, viruses) is evident after thousands of years of existence in permafrost. In many cases in deeper horizons these constitute ‘prehistoric’ floras of potential significance (e.g., ‘new’ genes predating humans, possibly suitable for molecular applications; re-emergence of human diseases); permafrost degradation will variously destroy or liberate such organisms.

Multi-year sea ice represents a unique, albeit spatially and temporally highly dynamic habitat. Many Arctic biota are highly ‘ice-adapted’ (e.g., iconic species such as ringed seal, narwhal, polar bear, ivory gull, walrus; specialized primary producers such as sea-ice diatoms; and ice-associated amphipods and copepods) and thus depend to a large degree on the presence of relevant sea-ice amounts and types. Others are highly ‘ice-associated’ (e.g., Arctic cod and seabirds such as thick-billed murre). Sea-ice degradation will significantly reduce habitat availability with consequences for population abundance, distribution, and persistence of many of these species. Spatio-temporal mismatches among ecosystem components are also likely to occur, with uncertain consequences for the remainder of the ecosystems. Similarly, although less obvious, semi-unique small-scale ecosystems and biota (e.g., seasonal melt-water ponds on multi-year sea ice) will be adversely affected. The sheer number of these small ecosystems, their intimate connection to productivity pathways to higher biota, and limited understanding all argue for their significance. Colonization by sub-Arctic biota and/or shifts in balance among obligate Arctic cryophiles and Arctic habitat generalists will tend to offset these losses of biodiversity, but will engender wide changes in the ecosystems. Substantive ecosystem and biotic consequences of cryospheric change are likely to involve widespread re-equilibration of existing Arctic ecosystems, and possibly the formation of completely new ecosystems which may take decades to stabilize. Follow-on consequences to humans will result and include conservation issues for Arctic biota, habitats and vanishing ecosystems. Also, there may be degradation or loss of supplies of local foods, traditionally relied upon by indigenous peoples. Tourism represents a renewable resource development opportunity for many areas of the Arctic – loss of key habitats and biota may diminish some of the attractiveness of this activity.

In addition to the above changes, some of which represent globally significant potential reductions or losses, many species, particularly birds migrate to the Arctic seasonally and winter in non-Arctic areas. Cryospheric shifts, particularly drainage of large terrestrial areas and shoreline impacts are likely to have significant impacts on such species. Similarly, changes in hydrology and altered vegetation and productivity regimes affect migrant terrestrial avifauna. The ultimate consequences are uncertain but migratory populations may decline, particularly if habitats are lost. Mismatches in food and key life history events such as nesting success in the Arctic will exacerbate such issues. This adds to the overall conservation needs required in the Arctic and beyond.

12.3.6. Shift in lifestyles, culture and socio-economics

Sustainability of some Arctic ecosystems as used for traditional activities, in particular food harvesting, is uncertain due either to difficulties in access or a declining resource base. Food

gathering and traditional annual cycles provide a basis for the culture of Arctic indigenous peoples. Development, shifts to wage-based economies, human demographic changes, and associated embedded changes all affect traditional lifestyles and culture. Cryospheric changes are likely to exacerbate the magnitude and rate of such changes. Decreased applicability of traditional knowledge, and limits to adaptive capacity and potential responses are likely to be presently strained, and will become more so as further changes occur. Food security is at risk as are culture, health and well-being of peoples with lifestyles connected to the cryosphere. Temporal and spatial mismatches are/will be important in ecosystem contexts and also in human contexts. If prey do not occur where people traditionally hunt, or if they are of lower quality, then it may not be possible to harvest adequate amounts.

12.4. Integrated consequences of cryospheric changes for lower latitudes and the global system

The Arctic is part of the global climate system and is closely linked to key elements through heat exchange and carbon cycling. Thus, in addition to significant effects within the Arctic, change in the Arctic cryosphere will feed back in many ways to affect the entire globe. Such feedbacks have far-reaching implications on the global climate system, sea level, and humans outside Arctic. In addition, the Arctic is economically linked to the entire globe and increased access and activities will have effects locally and within the global context.

12.4.1. Climate system changes

The Arctic is closely linked with the global climate system primarily through heat exchange in the atmosphere and ocean, but also through carbon cycling (e.g., GHGs). Alteration of these processes within the Arctic cryosphere results in their alteration globally, with significant consequences to humans at this scale.

Albedo Effects: Reduced Arctic albedo, particularly for the Arctic Ocean, will increase surface heating within the Arctic but will also generally increase heat retention by the globe. This feeds back within the Arctic to effect more rapid and greater change in the cryosphere. Heating of the Arctic also reduces the temperature gradient between the Arctic and southern areas, and thus may affect the strength of atmospheric and oceanic transport mechanisms.

Patterns of Atmospheric Circulation: Shifts in Arctic sea ice and increased heating will warm the lower atmosphere in the Arctic. This change will affect weather at lower latitudes of the Northern Hemisphere, particularly in winter. However, incomplete understanding of the nature and the closeness of the coupling between sea-ice extent, Arctic lower atmospheric heating, stability of Arctic boundary fronts, and circulation responses at lower latitudes complicate the development of adequate models with which to project future trends. Rapidly changing, perhaps increasing extremes, and highly variable weather responses at lower latitudes may result. Recent ‘outbreaks’ of cold Arctic air masses (e.g., 2005, 2008, 2009, 2010) over lower latitudes particularly in Eurasia appear to have resulted from weakening of the ‘polar vortex’ which typically

traps cold Arctic air near the pole. This variability may reflect an early shift toward altered Arctic, and perhaps northern hemispheric, climatic patterns.

Greenhouse Gas Releases: The Arctic is an effective moderator of the global carbon cycle with respect to storage capacity and local processes cycling GHGs. Over the recent geological past the GHG balance has been toward the storage of carbon (the Arctic has been a long-term sink). However, recent changes suggest the storage capacity is declining. Thus, GHGs are not as readily sequestered there and may contribute to global warming. Moreover, in some areas cryospheric changes are resulting in releases of stored GHGs and/or increased processing of GHGs. Permafrost degradation in some areas exacerbates this and its loss may potentially release large stores of trapped GHGs over decadal to centennial time frames. The significance of this feedback to the global system could be to further and very rapidly accelerate global climate change.

Contaminants: In parallel with the lessening of the temperature gradient between the Arctic and more southerly latitudes, the capacity for northward transport of contaminants is reduced, and thus accumulation in southerly areas is likely to increase. Also, it is very likely that the stores of legacy contaminants within the Arctic are being mobilized by cryospheric degradation. Their release from ice, snow, permafrost, glaciers and ice caps and subsequent re-entry into ecosystems appears to be occurring.

12.4.2. Global marine effects

Sea-Level Change: The issue of sea-level change, at local and global scales, is one of the more serious consequences of climate change, primarily due to the scale of potential effects. Sea-level change is a complex phenomenon resulting from many factors. Climate change affects sea level primarily through water mass changes and through density changes due to changes in temperature and salinity. Global sea levels are also affected by mass losses from non-Arctic glaciers and the Antarctic ice masses.

Present (2003–2008) mass losses from Arctic glaciers and the Greenland Ice Sheet contribute a total increase of 1.3 mm per year to the rise in global mean sea level. Increasing contributions from the Greenland Ice Sheet and other Arctic glaciers have occurred since 1995. Contributions from other sources (Antarctic Ice Sheet, non-Arctic glaciers) are added to these. Total projected sea-level rise resulting from all sources by 2100 cannot be estimated with high confidence at present. Lower and upper limits have a range of 0.79 to 2.01 m. A range of 0.9 to 1.6 m is considered the more plausible current estimate by the authors of the SWIPA assessment. Nevertheless, significant effects of the rising sea level will become increasingly evident by mid-century. High regional variation in sea-level rise will result from concurrent changes in other factors that include gravity fields, ocean temperatures, freshening, tidal effects and local isostatic rebound or subsidence of land. Rates will also differ, thus impacts may be highly regionalized and realized over varying time scales.

Mean sea-level rise increases possibilities of coastal flooding, erosion, infrastructure damage, environmental impacts on ecosystems, and saltwater intrusions into groundwater. Such effects may be accompanied or exacerbated by local additional

effects. Ultimate global effects realized at the century scale and beyond include significant inundation of low-lying coasts and possibly complete submergence of small islands in some areas of the globe, although growth of coral atolls may offset this to some degree.

Atlantic Meridional Overturning Circulation (AMOC): Ocean circulation (thermohaline circulation) is a global phenomenon by which heat and water are transported between the polar and equatorial regions. This circulation is powered in part by density differences among water masses due to differences in temperature and salinity. Inflows to the Arctic resulting from this phenomenon consist of surface (lower salinity, warmer) waters entering from the Pacific via the Bering Strait, and surface (warmer) waters entering from the North Atlantic. These inflows are counterbalanced by the outflow of Arctic waters primarily through the Canadian Archipelago and along eastern Greenland, mostly as lower salinity, cold and freshened surface flows. Additional deeper outflows of Arctic Ocean water (high salinity, cold) occur in the northeastern area of the Atlantic. The North Atlantic thus has several mixing zones where warm surface currents from the south interact with cold surface and sub-surface currents originating from the north. Areas of deepwater renewal (Northeast Atlantic – Barents Sea / Fram Strait; Northwest Atlantic – northern Labrador Sea / Southern Greenland) are essential to return water to the south and to the present strength of North Atlantic surface currents (the so-called ‘Gulf Stream’) which transport heat to northern Europe.

Several changes in the Arctic cryosphere are anticipated to increase freshwater inputs to the Arctic Ocean, thus reducing its salinity (at least in surface waters). These include: increased direct precipitation, possibly increased inputs of low salinity Pacific waters, increased runoff from large Arctic rivers, reduction of ice stores on land, and degradation of perennial sea ice. The increased input of freshwater will have local effects within the Arctic primarily on coastal shelves, many of which are largely associated with increased stratification. Concern has also been raised that increased freshwater outflow from the Arctic (possibly as deeper water masses) will alter the dynamics of ocean circulation and mixing in the North Atlantic. That is, the AMOC may be weakened. The SWIPA assessment found no conclusive evidence to support significant effects of cryospheric change on overturn circulation or deepwater formation. Total increased outputs of freshwater are likely to be at least one order of magnitude less than present flows of the major currents; accordingly, impacts of cryospheric change are likely to have little influence on major ocean current patterns at least for the foreseeable future. This is particularly so in comparison to the direct atmospheric effects of climate change on the strength and patterns of this circulation.

Freshwater Outflow: Most effects of cryospheric change will result in increased presence of freshwater in Arctic environments, much of which will eventually enter the Arctic Ocean. Considerable entrainment of freshwater occurs on marginal shelves and deeper in the Canada Basin, with accompanying shifts in salinity. Recent estimates suggest increased storage of freshwater has occurred in the Canada Basin, while export of freshwater stores from the Eurasian Basin appears to have increased. Large-scale export of freshwater

from the Arctic over geological time has been linked with large-scale cooling of the Northern Hemisphere. Factors that drive such export are poorly understood, although regional climatology is implicated. Thus, if storage turns to export, there may be significant surprises in store for the northern hemisphere climate.

Freshwater entry to coastal shelves and fjords decreases overall salinity and results in a mixed-layer of freshened seawater. Runoff, particularly from ice mass changes in Greenland, together with atmospheric forcing controls the depth of the mixed layer. As modeled freshwater outputs increased, mixed-layer decreased. This is likely to have profound consequences for nearshore productivity, although little research exists regarding likely changes on fjord and shelf ecosystems, or with respect to the shift of those effects to higher trophic levels of direct interest to humans. Also, as larger amounts of freshened water are expected to exit the Arctic seasonally (primarily as surface outflows in Baffin Bay / Davis Strait and along eastern Greenland), downstream effects on productive sub-Arctic seas are uncertain but may be profound. Better understanding of physical and biotic linkages is required for Arctic and sub-Arctic ecosystems, as well as cross-regional physical linkages to ‘downstream’ ecosystems.

12.4.3. Trade and economic development

Altered access (particularly that associated with changes in sea ice) increases possibilities for transpolar shipping and extraction of renewable and non-renewable resources. Changes in the cryosphere appear to be stimulating increased interest in exploration, development, and perhaps also migration from southern regions to the Arctic. Substantive follow-on effects will ensue if this occurs. Overall, reduction in polar sea ice can theoretically reduce intercontinental shipping distances by up to 40%, thus stimulating trade; realization of this potential is likely within the foreseeable future but benefits may take several decades to occur. Similarly, declines or shifts in some cryospheric components enhance development opportunities (albeit with many challenges remaining), many of which will benefit non-Arctic as well as Arctic residents. Coastal and some inland Arctic communities may realize benefits from increased trade (and in some cases these may offset effects of degraded land-based transportation). Overall, increased transport presents significant issues for resolution, such as development and implementation of a polar shipping code, establishing routes, mapping and development of appropriate services, and accident prevention and response.

12.5. Knowledge gaps and recommendations

12.5.1. Gaps in information and knowledge

Shortfalls in understanding and thus ability to project future states result from insufficient data (such as observational data) and the shortcomings of climate models. Each of the preceding chapters of this report noted discipline-specific gaps and issues, the resolution of which is required to ensure more accurate understanding in the future. In addition, an integrative section (Chapter 11, Section 11.5) focuses on many over-arching issues.

Some gaps are also explicitly or implicitly (through inferred conclusions) noted above. The following deficiencies are noted in the knowledge base.

- Although satellite observations of the cryosphere have expanded in type and quantity over the past decade, observational networks are still limited throughout the Arctic for many components, their key drivers and induced effects, and their linkages to human systems. This is particularly true for direct observations. Many important observations and monitoring efforts are research-based and in need of sustained funding. Coordination and common data linkages among observational networks are presently limited.
- There are considerable uncertainties in modeling some cryospheric processes. Permafrost models under-represent ice content and the insulating effect of the organic layer; climate models do not resolve the steep topography of the Greenland Ice Sheet margins; models of snow-vegetation interactions need to be improved; and models that link meteorology to glacier mass balance need to incorporate down-scaling techniques and satellite data.
- The effects of clouds on altering the nature and rates of change in the climate system, and particularly in the Arctic cryosphere, are very poorly known, and at present cannot be effectively modeled by many GCMs. Increased open water in a cold environment is likely to increase local cloudiness; how this may link to local cryospheric changes and thence to the global climate system is uncertain.
- Increased atmospheric carbon dioxide concentrations along with other GHGs fuel climate warming. They also have additional effects, for example carbon dioxide is sequestered within aquatic systems where acidification processes occur. Gas exchange between the atmosphere and waterbodies will increase as concentrations and temperatures rise and as duration and extent of ice covers decline. There is a need to better understand effects and model future situations, particularly for the Arctic Ocean.
- Cryospheric degradation will result in cascading effects on Arctic environments and peoples, their livelihoods, living conditions and quality of life, and the regional climate systems. It will also result in global consequences. The precise ways in which people and communities will be affected needs further study, particularly with regard to adaptation, changes in behavior, health, and resource development.
- Effective observations and monitoring across geographic and temporal scales, sectors and disciplines are all required in a linked inter-disciplinary fashion to provide measurement of change, assess efficacy of mitigative and adaptive strategies, and to prioritize needs for governance and other appropriate responses.
- Climate-driven cryospheric change is only one of many facets of overall Arctic change. Consequences of all drivers of Arctic change, including those in the cryosphere, need to be integrated into an overall understanding of the nature, rates and potential costs/benefits. This integration needs to include cumulative effects of multiple drivers, stressors or forcings on the Arctic system, and needs to cross the

physical, ecological and human systems present in the Arctic, and within the latter to cross the various sectors of human society.

12.5.2. Recommendations

The focus for the SWIPA assessment report has been to summarize the evidence for recent cryospheric change in the Arctic, and the effects and consequences of this change for the entire Arctic system. The objective of the SWIPA program was not to focus on the ultimate cause of the cryospheric change (see Chapter 1). Instead, the syntheses embodied in the preceding chapters of this Science Report highlight the present state of knowledge within the various disciplines, and the follow-on effects of present and ongoing change on Arctic ecosystems and humans. The following recommendations aim to increase that knowledge base and facilitate its use.

Near-term needs

- Increase the nature, spatial and temporal resolution, and availability of data from all observational platforms, all continuing into the future – including data for physical, ecological and human elements of the overall system and with a specific focus on feedback linkages within the system (e.g., enhanced methane releases due to cryospheric change) and other gaps.
- Modeling approaches provide insight into future possibilities, but efforts are required to reduce uncertainties in projections and enhance their spatial resolution, to parameterize and incorporate important feedbacks; and to downscale model results to appropriate regional levels.
- Enhance existing efforts to understand causal linkages across all aspects of the Arctic system, both among cryospheric components and between the cryosphere and other components of the Arctic system.
- Integrate and foster seamless availability of data products associated with the cryosphere, the consequences of change, and additional potential drivers.
- Identify and resolve impediments to inter-disciplinary linkages within and among cryospheric components, thereby fostering cross-disciplinary and integrated studies of changes in this system and their consequences for the Arctic.
- Link existing or develop new quantitative models to provide an integrated perspective of climate and cryospheric changes for the Arctic.
- Assess risks, or develop approaches to do so, of cryospheric changes for ecological and human systems in the Arctic across all relevant scales to allow effective planning and remediation. Identify shortfalls in design or approaches presently in place to address future changes in the cryosphere.
- Assess the consequences of cryospheric change for other physical and ecological systems (e.g., enhanced gas exchange driving acidification of Arctic aquatic systems).
- Evaluate roles and cumulative effects of potential drivers of continued cryospheric change across spatial scales to better understand causation and interactions, thus informing mitigation efforts.

Medium-term needs

- Identify and resolve impediments to linking all drivers and consequences of Arctic change into an overall understanding ranging from the physical to human levels of the system.
- Link or develop quantitative and qualitative approaches to enable cross-disciplinary analyses of change, causation and consequences.
- Initiate regional assessments focused on inter-disciplinary integration of recent changes, drivers of change and consequences; and develop projections of future possible outcomes to better inform planning and preparedness.

Long-term needs

- Develop and implement an overall strategy to assess Arctic change from all causes on a regular basis within which major proximate drivers such as cryospheric changes can be assessed.
- Integrate regional and sectoral assessments into regular Arctic-wide assessments.

12.6. Conclusion

The findings summarized in the SWIPA Science Report provide insights into the scope and nature of cryospheric changes in the Arctic. These, in turn, in combination with widespread climate variability, over large spatial and temporal scales, and with human adaptive capacity will ultimately determine whether particular changes in the cryosphere are viewed as opportunities or challenges. The overwhelming consequence appears to be a highly variable and uncertain future for the Arctic. This is perhaps the main challenge resulting from cryospheric change in the Arctic. Strategies and approaches that incorporate such uncertainty as a basic consideration underpin effective solutions. Thus, past trends, expectations of smooth transitions, expectations of slow rates of change, and expectations of low frequencies of extreme events appear to be becoming less trustworthy predictors of future situations and risks. As a consequence, planning for surprises or unanticipated events is increasingly important.

Acronyms and abbreviations

AAR	Accumulation area ratio	MeHg	Methylmercury
ACIA	Arctic Climate Impact Assessment	MIZ	Marginal ice zone
ALT	Active-layer thickness	MSL	Mean sea level
AMAP	Arctic Monitoring and Assessment Programme	MYI	Multi-year ice
AMOC	Atlantic Meridional Overturning Circulation	N ₂ O	Nitrous oxide
AO	Arctic Oscillation	NAM	Northern Annular Mode
AOGCM	Atmosphere-Ocean General Circulation Model	NAO	North Atlantic Oscillation
ATM	Airborne Topographic Mapper	NASA	National Aeronautics and Space Administration
BC	Black carbon ('soot')	NCAR	National Center for Atmospheric Research
BP	Before present	NCEP	National Centers for Environmental Prediction
BVOC	Biogenic volatile organic compounds	NMVOC	Non-methane volatile organic compound
C	Carbon	NO ₂	Nitrogen dioxide
CAD	Canadian dollar	NOAA	National Oceanic and Atmospheric Administration
CALM	Circumpolar Active Layer Monitoring	NO _x	Nitrogen oxides
CH ₄	Methane	NSIDC	National Snow and Ice Data Center
CMIP3	Coupled Model Intercomparison Project phase 3	pbb	Parts per billion
CO ₂	Carbon dioxide	PCB	Polychlorinated biphenyl
DIC	Dissolved inorganic carbon	PDD	Positive degree day
DMI	Danish Meteorological Institute	PDO	Pacific Decadal Oscillation
DO	Dissolved oxygen	PNA	Pacific North America
DOC	Dissolved organic carbon	POC	Particulate organic carbon
ECMWF	European Centre for Medium-Range Weather Forecasts	POP	Persistent organic pollutant
EEZ	Exclusive economic zone	ppt	Parts per thousand
ELA	Equilibrium-line altitude	RCM	Regional climate model
ENSO	El Niño / Southern Oscillation	SAR	Synthetic aperture radar
ERA-40	ECMWF Re-Analysis covering the ~40 year period 1957-2002	SAT	Surface air temperature
ESA	European Space Agency	SCD	Snow-cover duration
FYI	First-year ice	SLE	Sea-level equivalent
GCM	General circulation model	SLiCA	Survey of Living Conditions in the Arctic
GDP	Gross domestic product	SLP	Sea-level pressure
GHG	Greenhouse gas	SLR	Sea-level rise
GLRIP	Global Lake and River Ice Phenology dataset	SMB	Surface mass balance
GPR	Ground-penetrating radar	SO ₄	Sulfate
GPS	Global Positioning System	SRALT	Satellite radar altimetry
GRACE	Gravity Recovery and Climate Experiment	SST	Sea-surface temperature
GRP	Gross regional product	Sv	Sverdrup (1 Sv = 10 ⁶ m ³)
Gt	Gigatonne	SWE	Snow-water equivalent
HCB	Hexachlorobenzene	SWEmax	Maximum monthly SWE
HCH	Hexachlorocyclohexane	SWIPA	Snow, Water, Ice and Permafrost in the Arctic
Hg	Mercury	TEK	Traditional ecological knowledge
IPCC	Intergovernmental Panel on Climate Change	ULS	Upward-looking sonar
IPCC AR4	IPCC fourth assessment	UNCLOS	United Nations Convention on the Law of the Sea
IPY	International Polar Year	USD	US dollar
ky	Thousand years	w.e.	Water equivalent
MAGT	Mean annual ground temperature	WMO	World Meteorological Organization

AMAP Secretariat


Gaustadalléen 21
N-0349 Oslo, Norway

T +47 22 95 83 40

F +47 22 60 44 27

www.amap.no

ISBN – 978-82-7971-071-4



ARCTIC COUNCIL

AMAP
Arctic Monitoring and
Assessment Programme

AMAP – IASC – IASSA – WCRP-CLiC

